

SECTION I – MONITORING FREQUENCY

- At a minimum, sludge or biosolids shall be tested for volume and percent total solids on a frequency that will accurately represent sludge quantities produced and disposed. Please see the table below.

TABLE 5

Design Sludge Production (dry tons per year)	Monitoring Frequency (See Notes 1, 2, and 3)			
	Metals, Pathogens and Vectors	Nitrogen TKN ¹	Nitrogen PAN ²	Priority Pollutants and TCLP ³
0 to 100	1 per year	1 per year	1 per month	1 per year
101 to 200	biannual	biannual	1 per month	1 per year
201 to 1,000	quarterly	quarterly	1 per month	1 per year
1,001 to 10,000	1 per month	1 per month	1 per week	-- ⁴
10,001 +	1 per week	1 per week	1 per day	-- ⁴

- Test total Kjeldahl nitrogen, if biosolids application is 2 dry tons per acre per year or less.
- Calculate plant available nitrogen (PAN) when either of the following occurs: 1) when biosolids are greater than 50,000 mg/kg TN; or 2) when biosolids are land applied at an application rate greater than two dry tons per acre per year.
- Priority pollutants (40 CFR 122.21, Appendix D, Tables II and III) and toxicity characteristic leaching procedure (40 CFR 261.24) is required only for permit holders that must have a pre-treatment program.
- One sample for each 1,000 dry tons of sludge.

Note 1: Total solids: A grab sample of sludge shall be tested one per day during land application periods for percent total solids. This data shall be used to calculate the dry tons of sludge applied per acre.
Note 2: Total Phosphorus: Total phosphorus and total potassium shall be tested at the same monitoring frequency as metals.
Note 3: Table 5 is not applicable for incineration and permit holders that landfill their sludge.

- If you own a wastewater treatment lagoon or sludge lagoon that is cleaned out once a year or less, you may choose to sample only when the sludge is removed or the lagoon is closed. Test one composite sample for each 100 dry tons of sludge or biosolids removed from the lagoon during the year within the lagoon at closing. Composite sample must represent various areas at one-foot depth.
- Additional testing may be required in the special conditions or other sections of the permit. Permittees receiving industrial wastewater may be required to conduct additional testing upon request from the Department.
- At this time, the Department recommends monitoring requirements shall be performed in accordance with, "POTW Sludge Sampling and Analysis Guidance Document," United States Environmental Protection Agency, August 1989, and the subsequent revisions.

SECTION J – RECORD KEEPING AND REPORTING REQUIREMENTS

- The permittee shall maintain records on file at the facility for at least five years for the items listed in these standard conditions and any additional items in the Special Conditions section of this permit. This shall include dates when the sludge facility is checked for proper operation, records of maintenance and repairs and other relevant information.
- Reporting period
 - By January 28th of each year, an annual report shall be submitted for the previous calendar year period for all mechanical wastewater treatment facilities, sludge lagoons, and sludge or biosolids disposal facilities.
 - Permittees with wastewater treatment lagoons shall submit the above annual report only when sludge or biosolids are removed from the lagoon during the report period or when the lagoon is closed.
- Report Forms. The annual report shall be submitted on report forms provided by the Department or equivalent forms approved by the Department.
- Reports shall be submitted as follows:

Major facilities (those serving 10,000 persons or 1 million gallons per day) shall report to both the Department and EPA. Other facilities need to report only to the Department. Reports shall be submitted to the addresses listed as follows:

DNR regional office listed in your permit
(see cover letter of permit)
ATTN: Sludge Coordinator

EPA Region VII
Water Compliance Branch (WACM)
Sludge Coordinator
11201 Renner Blvd.
Lenexa, KS 66219

5. Annual report contents. The annual report shall include the following:
- a. Sludge and biosolids testing performed. Include a copy or summary of all test results, even if not required by the permit.
 - b. Sludge or biosolids quantity shall be reported as dry tons for quantity generated by the wastewater treatment facility, the quantity stored on site at the end of the year, and the quantity used or disposed.
 - c. Gallons and % solids data used to calculate the dry ton amounts.
 - d. Description of any unusual operating conditions.
 - e. Final disposal method, dates, and location, and person responsible for hauling and disposal.
 - i. This must include the name, address for the hauler and sludge facility. If hauled to a municipal wastewater treatment facility, sanitary landfill, or other approved treatment facility, give the name of that facility.
 - ii. Include a description of the type of hauling equipment used and the capacity in tons, gallons, or cubic feet.
 - f. Contract Hauler Activities:
If contract hauler, provide a copy of a signed contract from the contractor. Permittee shall require the contractor to supply information required under this permit for which the contractor is responsible. The permittee shall submit a signed statement from the contractor that he has complied with the standards contained in this permit, unless the contract hauler has a separate sludge or biosolids use permit.
 - g. Land Application Sites:
 - i. Report the location of each application site, the annual and cumulative dry tons/acre for each site, and the landowners name and address. The location for each spreading site shall be given as a legal description for nearest ¼, ¼, Section, Township, Range, and county, or UTM coordinates. The facility shall report PAN when either of the following occurs: 1) When biosolids are greater than 50,000 mg/kg TN; or 2) when biosolids are land applied at an application rate greater than two dry tons per acre per year.
 - ii. If the "Low Metals" criteria are exceeded, report the annual and cumulative pollutant loading rates in pounds per acre for each applicable pollutant, and report the percent of cumulative pollutant loading which has been reached at each site.
 - iii. Report the method used for compliance with pathogen and vector attraction requirements.
 - iv. Report soil test results for pH, CEC, and phosphorus. If none was tested during the year, report the last date when tested and results.

RECEIVED

JUN 16 2015

AD 2-48-1



MISSOURI DEPARTMENT OF NATURAL RESOURCES
 WATER PROTECTION PROGRAM
**FORM B: APPLICATION FOR OPERATING PERMIT FOR FACILITIES THAT RECEIVE
 PRIMARILY DOMESTIC WASTE AND HAVE A DESIGN FLOW LESS THAN OR
 EQUAL TO 100,000 GALLONS PER DAY**

FOR AGENCY USE ONLY	
CHECK NUMBER	
DATE RECEIVED	FEE SUBMITTED
6-20-15	0-

OS

READ THE ACCOMPANYING INSTRUCTIONS BEFORE COMPLETING THIS FORM

1. THIS APPLICATION IS FOR:

An operating permit for a new or unpermitted facility. Construction Permit # _____
 (Include completed antidegradation review or request for antidegradation review, see instructions)

A site-specific operating permit renewal: Permit #MO- 0135305 Expiration Date 3/10/2016

A site-specific operating permit modification: Permit #MO- _____ Reason: _____

General permit (MOGD – Non POTWs discharging < 50,000 GPD or MOG823 – Land Application of Domestic Wastewater):
 Permit #MO- _____ Expiration Date _____

1.1 Is the appropriate fee included with the application (see instructions for appropriate fee)? YES NO

2. FACILITY

NAME BCRSD Brown Station WWTF		TELEPHONE NUMBER WITH AREA CODE (573) 443-2774	
ADDRESS (PHYSICAL) O'Rear Road and North Brown Station Road	CITY Columbia	STATE MO	ZIP CODE 65204
2.1 Legal description: $\frac{1}{4}$ NW $\frac{1}{4}$ NW $\frac{1}{4}$ Sec. 10, T 49n, R 12w	County Boone		
2.2 UTM Coordinates Easting (X): 563938 Northing (Y): 4322492 <i>For Universal Transverse Mercator (UTM), Zone 15 North referenced to North American Datum 1983 (NAD83)</i>			
2.3 Name of receiving stream: Clays Fork			
2.4 Number of outfalls: one Wastewater outfalls: one Stormwater outfalls: 0 Instream monitoring sites: 0			

3. OWNER

NAME Boone County Regional Sewer District		EMAIL ADDRESS dcooksey@bcrsd.com	TELEPHONE NUMBER WITH AREA CODE (573) 441-0098
ADDRESS 1314 North 7th street	CITY Columbia	STATE Mo	ZIP CODE 65201
3.1 Request review of draft permit prior to public notice? <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO			
3.2 Are you a publicly owned treatment works? If yes, is the Financial Questionnaire attached? <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO			
3.3 Are you a privately owned treatment works? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO			
3.4 Are you a privately owned treatment facility regulated by the Public Service Commission? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO			

4. CONTINUING AUTHORITY: Permanent organization that will serve as the continuing authority for the operation, maintenance and modernization of the facility.

NAME Boone County Regional Sewer District		EMAIL ADDRESS dcooksey@bcrsd.com	TELEPHONE NUMBER WITH AREA CODE (573) 441-0098
ADDRESS 1314 North Seventh Street	CITY Columbia	STATE Mo	ZIP CODE 65201
If the continuing authority is different than the owner, include a copy of the contract agreement between the two parties and a description of the responsibilities of both parties within the agreement.			

5. OPERATOR

NAME Dwayne Cooksey	TITLE Operations Manager	CERTIFICATE NUMBER 1249
EMAIL ADDRESS dcooksey@bcrsd.com		TELEPHONE NUMBER WITH AREA CODE (573) 441-0098

6. FACILITY CONTACT

NAME Dwayne Cooksey		TITLE Operations Manager	
EMAIL ADDRESS dcooksey@bcrsd.com		TELEPHONE NUMBER WITH AREA CODE (573) 441-0098	
ADDRESS 1314 North Seventh Street	CITY Columbia	STATE Mo.	ZIP CODE 65257

MO 780-1512 (12-14)

NE Boone

7. DESCRIPTION OF FACILITY

7.1 Process Flow Diagram or Schematic: Provide a diagram showing the processes of the treatment plant. Show all of the treatment units, including disinfection (e.g. – chlorination and dechlorination), influents, and outfalls. Specify where samples are taken. Indicate any treatment process changes in the routing of wastewater during dry weather and peak wet weather. Include a brief narrative description of the diagram.
Attach sheets as necessary.

STEP System/Recirculating sand filter. Sludge disposal is handled by BCRSD. Design population equivalent is 19. Design flow is 1,850 gallon per day. Design sludge production is 0.37 dry tons/year.


7.2 Attach an aerial photograph or USGS topographic map showing the location of the facility and outfall.

MO 780-1512 (12-14)


8. ADDITIONAL FACILITY INFORMATION	
8.1	Facility SIC code: _____ Discharge SIC code: <u>4952</u>
8.2	Number of people presently connected or population equivalent (P.E.) <u>18.5</u> Design P.E. <u>18.5</u>
8.3	Connections to the facility: Number of units presently connected: Homes <u>5</u> Trailers _____ Apartments _____ Other (including industrial) _____ Number of commercial establishments: _____
8.4	Design flow: <u>1,850</u> gpd Actual flow: <u>< 1,000</u> gallon per day
8.5	Will discharge be continuous through the year? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Discharge will occur during the following months: How many days of the week will discharge occur? <u>7</u>
8.6	Is industrial wastewater discharged to the facility? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If yes, attach a list of the industries that discharge to your facility
8.7	Does the facility accept or process leachate from landfills? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
8.8	Is wastewater land applied? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If yes, is Form I attached? <input type="checkbox"/> Yes <input type="checkbox"/> No
8.9	Does the facility discharge to a losing stream or sinkhole? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
8.10	Has a wasteload allocation study been completed for this facility? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
9. LABORATORY CONTROL INFORMATION	
LABORATORY WORK CONDUCTED BY PLANT PERSONNEL <u>In House</u>	
Lab work conducted outside of plant.	<input type="checkbox"/> Yes <input type="checkbox"/> No
Push-button or visual methods for simple test such as pH, settleable solids.	<input type="checkbox"/> Yes <input type="checkbox"/> No
Additional procedures such as dissolved oxygen, chemical oxygen demand, biological oxygen demand, titrations, solids, volatile content.	<input type="checkbox"/> Yes <input type="checkbox"/> No
More advanced determinations such as BOD seeding procedures, fecal coliform, nutrients, total oils, phenols, etc.	<input type="checkbox"/> Yes <input type="checkbox"/> No
Highly sophisticated instrumentation, such as atomic absorption and gas chromatograph.	<input type="checkbox"/> Yes <input type="checkbox"/> No
10. COLLECTION SYSTEM	
10.1	Length of pipe in the sewer collection system? <u>1.383</u> Feet, or _____ Miles (either unit is appropriate)
10.2	Does significant infiltration occur in the collection system? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If yes, briefly explain any steps underway or planned to minimize inflow and infiltration:
11. BYPASSING	
Does any bypassing occur in the collection system or at the treatment facility? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If yes, explain:	

MO 780-1512 (12-14)

12. SLUDGE HANDLING, USE AND DISPOSAL			
12.1	Is the sludge a hazardous waste as defined by 10 CSR 25?	<input type="checkbox"/> Yes	<input checked="" type="checkbox"/> No
12.2	Sludge production, including sludge received from others:	<u>0.37</u> Design dry tons/year	<u>0.37</u> Actual dry tons/year
12.3	Capacity of sludge holding structures: Sludge storage provided: <u>507</u> cubic feet; <u>1825</u> days of storage; <u>15</u> average percent solids of sludge; <input checked="" type="checkbox"/> No sludge storage is provided. <input type="checkbox"/> Sludge is stored in lagoon.		
12.4	Type of Storage:	<input type="checkbox"/> Holding tank <input type="checkbox"/> Basin <input type="checkbox"/> Concrete Pad	<input type="checkbox"/> Building <input type="checkbox"/> Lagoon <input checked="" type="checkbox"/> Other (Describe) <u>residential septic tanks and WWTF</u>
12.5	Sludge Treatment:	<input type="checkbox"/> Anaerobic Digester <input checked="" type="checkbox"/> Storage Tank <input type="checkbox"/> Lime Stabilization	<input type="checkbox"/> Lagoon <input type="checkbox"/> Aerobic Digester <input type="checkbox"/> Air or Heat Drying <input type="checkbox"/> Composting <input type="checkbox"/> Other (Attach description)
12.6	Sludge Use or Disposal:	<input type="checkbox"/> Land Application <input type="checkbox"/> Contract Hauler <input type="checkbox"/> Incineration <input type="checkbox"/> Solid waste landfill	<input type="checkbox"/> Surface Disposal (Sludge Disposal Lagoon, Sludge held for more than two years) <input checked="" type="checkbox"/> Hauled to Another treatment facility <input type="checkbox"/> Sludge Retained in Wastewater treatment lagoon
12.7	Person responsible for hauling sludge to disposal facility: <input checked="" type="checkbox"/> By applicant <input type="checkbox"/> By others (complete below)		
NAME		EMAIL ADDRESS	
ADDRESS		CITY	STATE ZIP CODE
CONTACT PERSON		TELEPHONE NUMBER WITH AREA CODE	PERMIT NO. MO-
12.8	Sludge use or disposal facility <input type="checkbox"/> By applicant <input checked="" type="checkbox"/> By others (Complete below.)		
NAME		EMAIL ADDRESS	
City of Columbia			
ADDRESS POB N		CITY Columbia	STATE ZIP CODE MO 65202
CONTACT PERSON Davie Sorrel		TELEPHONE NUMBER WITH AREA CODE (573) 874-6286	PERMIT NO. MO- 0097837
12.9	Does the sludge or biosolids disposal comply with federal sludge regulations under 40 CFR 503? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No (Explain)		

13. CERTIFICATION		
I certify that I am familiar with the information contained in the application, that to the best of my knowledge and belief such information is true, complete and accurate, and if granted this permit, I agree to abide by the Missouri Clean Water Law and all rules, regulations, orders and decisions, subject to any legitimate appeal available to applicant under the Missouri Clean Water Law.		
NAME (TYPE OR PRINT)	OFFICIAL TITLE	TELEPHONE NUMBER WITH AREA CODE
Dwayne Cooksey	Operations Manager	(573) 441-0098
SIGNATURE	DATE SIGNED	
	6/24/2015	


MO 780-1512 (12-14)



Fitter

APPENDIX B

EXHIBIT 1: PROPOSED IMPROVEMENTS



Legend

- Wastewater Facilities
- Force Main Alignment



Case No. SA-2021-0017

Schedule TR-1, Part 3, Page 124 of 160



Cedar Gate, Richardson Acres and Brown Station Wastewater Improvements

EXHIBIT 1

APPENDIX C

DAILY MONITORING REPORTS

CEDAR GATE DRM DATA

Date	Description	Influent/Effluent	Unit	Monthly Average	Daily Max
12/31/2019	Ammonia (as N) + unionized ammonia	End of Pipe	mg/L	13.2	
09/30/2019	Ammonia (as N) + unionized ammonia	End of Pipe	mg/L	14.3	
06/30/2019	Ammonia (as N) + unionized ammonia	End of Pipe	mg/L	17.1	
03/31/2019	Ammonia (as N) + unionized ammonia	End of Pipe	mg/L	17.4	
12/31/2018	Ammonia (as N) + unionized ammonia	End of Pipe	mg/L	11.5	
09/30/2018	Ammonia (as N) + unionized ammonia	End of Pipe	mg/L	8.1	
06/30/2018	Ammonia (as N) + unionized ammonia	End of Pipe	mg/L	25.2	
03/31/2018	Ammonia (as N) + unionized ammonia	End of Pipe	mg/L	35.4	
12/31/2017	Ammonia (as N) + unionized ammonia	End of Pipe	mg/L	22.7	
09/30/2017	Ammonia (as N) + unionized ammonia	End of Pipe	mg/L	8.1	
06/30/2017	Ammonia (as N) + unionized ammonia	End of Pipe	mg/L	11.2	
03/31/2017	Ammonia (as N) + unionized ammonia	End of Pipe	mg/L	33.9	
12/31/2016	Ammonia (as N) + unionized ammonia	End of Pipe	mg/L	18.5	
09/30/2016	Ammonia (as N) + unionized ammonia	End of Pipe	mg/L	11.8	
06/30/2016	Ammonia (as N) + unionized ammonia	End of Pipe	mg/L	22.1	
03/31/2016	Ammonia (as N) + unionized ammonia	End of Pipe	mg/L	2.2	
12/31/2015	Ammonia (as N) + unionized ammonia	End of Pipe	mg/L	9.5	
09/30/2015	Ammonia (as N) + unionized ammonia	End of Pipe	mg/L	13.4	
06/30/2015	Ammonia (as N) + unionized ammonia	End of Pipe	mg/L	12.3	
03/31/2015	Ammonia (as N) + unionized ammonia	End of Pipe	mg/L	40.3	
12/31/2019	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	9	
09/30/2019	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	17	
06/30/2019	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	16	
03/31/2019	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	19	
12/31/2018	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	10	
09/30/2018	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	25	
06/30/2018	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	14	
03/31/2018	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	43	
12/31/2017	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	14	
09/30/2017	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	7	
06/30/2017	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	13	
03/31/2017	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	41	
12/31/2016	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	10	
09/30/2016	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	11	
06/30/2016	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	43	
03/31/2016	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	26	
12/31/2015	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	11	
09/30/2015	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	13	
06/30/2015	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	34	
03/31/2015	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	116	
12/31/2019	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.00295	0.003
11/30/2019	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0028	0.0028
10/31/2019	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0025	0.0029
09/30/2019	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0029	0.003
08/31/2019	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0021	0.0028
07/31/2019	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.00305	0.0032
06/30/2019	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.00295	0.003
05/31/2019	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.00295	0.003
04/30/2019	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.00295	0.003
03/31/2019	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.00255	0.003
02/28/2019	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0032	0.0036
01/31/2019	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0033	0.0036
12/31/2018	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.00255	0.003
11/30/2018	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.00215	0.0029
10/31/2018	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.00265	0.0034
09/30/2018	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.00175	0.0021
08/31/2018	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.00175	0.0021
07/31/2018	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0025	0.0029
06/30/2018	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0021	0.0028
05/31/2018	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0029	0.003
04/30/2018	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.00201	0.00216
03/31/2018	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0026	0.0048
02/28/2018	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0021	0.0028
01/31/2018	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0014	0.0014
12/31/2017	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.00155	0.0017
11/30/2017	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0012	0.00144
10/31/2017	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.00155	0.0017
09/30/2017	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.00127	0.0014
08/31/2017	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0021	0.0028
07/31/2017	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.001	0.001
06/30/2017	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.001	0.001

05/31/2017	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.001	0.001
04/30/2017	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.00122	0.00144
03/31/2017	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.00122	0.00144
02/28/2017	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.00122	0.00144
01/31/2017	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0014	0.0014
12/31/2016	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.00122	0.00144
11/30/2016	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.00144	0.00144
10/31/2016	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.00144	0.0014
09/30/2016	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0012	0.00144
08/31/2016	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.00122	0.00144
07/31/2016	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.012	0.014
06/30/2016	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0021	0.0028
05/31/2016	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0012	0.0014
04/30/2016	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.00144	0.00144
03/31/2016	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.001	0.001
02/29/2016	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0012	0.0014
01/31/2016	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.00122	0.00144
12/31/2015	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.00122	0.00144
11/30/2015	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.00194	0.00288
10/31/2015	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.001	0.001
09/30/2015	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0012	0.0014
08/31/2015	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.001	0.001
07/31/2015	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0012	0.0014
06/30/2015	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0019	0.0029
05/31/2015	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0021	0.0029
04/30/2015	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.00216	0.00288
03/31/2015	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.00097	0.00144
02/28/2015	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d		
01/31/2015	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0027933	0.00428
12/31/2019	Total Suspended Solids (TSS)	End of Pipe	mg/L	6	
09/30/2019	Total Suspended Solids (TSS)	End of Pipe	mg/L	15	
06/30/2019	Total Suspended Solids (TSS)	End of Pipe	mg/L	10	
03/31/2019	Total Suspended Solids (TSS)	End of Pipe	mg/L	25	
12/31/2018	Total Suspended Solids (TSS)	End of Pipe	mg/L	12	
09/30/2018	Total Suspended Solids (TSS)	End of Pipe	mg/L	10	
06/30/2018	Total Suspended Solids (TSS)	End of Pipe	mg/L	13	
03/31/2018	Total Suspended Solids (TSS)	End of Pipe	mg/L	56	
12/31/2017	Total Suspended Solids (TSS)	End of Pipe	mg/L	14	
09/30/2017	Total Suspended Solids (TSS)	End of Pipe	mg/L	14	
06/30/2017	Total Suspended Solids (TSS)	End of Pipe	mg/L	13	
03/31/2017	Total Suspended Solids (TSS)	End of Pipe	mg/L	33	
12/31/2016	Total Suspended Solids (TSS)	End of Pipe	mg/L	6	
09/30/2016	Total Suspended Solids (TSS)	End of Pipe	mg/L	12	
06/30/2016	Total Suspended Solids (TSS)	End of Pipe	mg/L	33	
03/31/2016	Total Suspended Solids (TSS)	End of Pipe	mg/L	23	
12/31/2015	Total Suspended Solids (TSS)	End of Pipe	mg/L	24	
09/30/2015	Total Suspended Solids (TSS)	End of Pipe	mg/L	13	
06/30/2015	Total Suspended Solids (TSS)	End of Pipe	mg/L	72	
03/31/2015	Total Suspended Solids (TSS)	End of Pipe	mg/L	37	
12/31/2019	BOD, 5-day, 20 deg. C	Influent	mg/L	279	
12/31/2018	BOD, 5-day, 20 deg. C	Influent	mg/L	426	
12/31/2017	BOD, 5-day, 20 deg. C	Influent	mg/L	348	
12/31/2016	BOD, 5-day, 20 deg. C	Influent	mg/L	284	
12/31/2015	BOD, 5-day, 20 deg. C	Influent	mg/L	310	
12/31/2019	Total Suspended Solids (TSS)	Influent	mg/L	190	
12/31/2018	Total Suspended Solids (TSS)	Influent	mg/L	322	
12/31/2017	Total Suspended Solids (TSS)	Influent	mg/L	316	
12/31/2016	Total Suspended Solids (TSS)	Influent	mg/L	420	
12/31/2015	Total Suspended Solids (TSS)	Influent	mg/L	298	

RICHARDSON ACRES DMR DATA


Date	Description	Influent/Effluent	Unit	Monthly Average	Daily Max
12/31/2019	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	9	
09/30/2019	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	14	
06/30/2019	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	37	
03/31/2019	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	14	
12/31/2018	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	8	
09/30/2018	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	18	
06/30/2018	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	12	
03/31/2018	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	15	
12/31/2017	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	13	
09/30/2017	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	6	
06/30/2017	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	10	
03/31/2017	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	9	
12/31/2016	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	8	
09/30/2016	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	17	
06/30/2016	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	34	
03/31/2016	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	10	
12/31/2015	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	16	
09/30/2015	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	19	
06/30/2015	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	27	
03/31/2015	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	14	
12/31/2019	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0038	0.0041
09/30/2019	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.00436	0.0054
06/30/2019	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0042	0.0047
03/31/2019	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.00445	0.0057
12/31/2018	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0037	0.0041
09/30/2018	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0032	0.0036
06/30/2018	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.00288	0.00288
03/31/2018	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0038	0.0047
12/31/2017	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0036	0.0041
09/30/2017	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.00344	0.0041
06/30/2017	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0031	0.0043
03/31/2017	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0034833	0.003927
12/31/2016	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0041713	0.0048
09/30/2016	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0039713	0.0042
06/30/2016	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.003638	0.004114
03/31/2016	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0036683	0.00432
12/31/2015	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0040205	0.004114
09/30/2015	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.004155667	0.004547
06/30/2015	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0035635	0.003927
03/31/2015	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.00288	0.00288
12/31/2019	Nitrogen, ammonia total (as N)	End of Pipe	mg/L	2	
09/30/2019	Nitrogen, ammonia total (as N)	End of Pipe	mg/L	0.8	
06/30/2019	Nitrogen, ammonia total (as N)	End of Pipe	mg/L	0.3	
03/31/2019	Nitrogen, ammonia total (as N)	End of Pipe	mg/L	5.6	
12/31/2018	Nitrogen, ammonia total (as N)	End of Pipe	mg/L	0.6	
09/30/2018	Nitrogen, ammonia total (as N)	End of Pipe	mg/L	2.7	
06/30/2018	Nitrogen, ammonia total (as N)	End of Pipe	mg/L	1.1	
03/31/2018	Nitrogen, ammonia total (as N)	End of Pipe	mg/L	11.5	
12/31/2017	Nitrogen, ammonia total (as N)	End of Pipe	mg/L	4.2	
09/30/2017	Nitrogen, ammonia total (as N)	End of Pipe	mg/L	1.1	
06/30/2017	Nitrogen, ammonia total (as N)	End of Pipe	mg/L	3.6	
03/31/2017	Nitrogen, ammonia total (as N)	End of Pipe	mg/L	9.2	
03/31/2015	Nitrogen, ammonia total (as N)	End of Pipe	mg/L	8.4	
12/31/2019	Total Suspended Solids (TSS)	End of Pipe	mg/L	8	
09/30/2019	Total Suspended Solids (TSS)	End of Pipe	mg/L	9	
06/30/2019	Total Suspended Solids (TSS)	End of Pipe	mg/L	49	
03/31/2019	Total Suspended Solids (TSS)	End of Pipe	mg/L	15	
12/31/2018	Total Suspended Solids (TSS)	End of Pipe	mg/L	4	
09/30/2018	Total Suspended Solids (TSS)	End of Pipe	mg/L	42	
06/30/2018	Total Suspended Solids (TSS)	End of Pipe	mg/L	16	
03/31/2018	Total Suspended Solids (TSS)	End of Pipe	mg/L	13	
12/31/2017	Total Suspended Solids (TSS)	End of Pipe	mg/L	15	
09/30/2017	Total Suspended Solids (TSS)	End of Pipe	mg/L	17	
06/30/2017	Total Suspended Solids (TSS)	End of Pipe	mg/L	14	
03/31/2017	Total Suspended Solids (TSS)	End of Pipe	mg/L	9	
12/31/2016	Total Suspended Solids (TSS)	End of Pipe	mg/L	12	
09/30/2016	Total Suspended Solids (TSS)	End of Pipe	mg/L	32	
06/30/2016	Total Suspended Solids (TSS)	End of Pipe	mg/L	41.5	
03/31/2016	Total Suspended Solids (TSS)	End of Pipe	mg/L	27	
12/31/2015	Total Suspended Solids (TSS)	End of Pipe	mg/L	26	
09/30/2015	Total Suspended Solids (TSS)	End of Pipe	mg/L	38	
06/30/2015	Total Suspended Solids (TSS)	End of Pipe	mg/L	33	
03/31/2015	Total Suspended Solids (TSS)	End of Pipe	mg/L	33	
09/30/2018	BOD, 5-day, 20 deg. C	Influent	mg/L	79	
06/30/2018	BOD, 5-day, 20 deg. C	Influent	mg/L	105	
03/31/2018	BOD, 5-day, 20 deg. C	Influent	mg/L	190	
12/31/2017	BOD, 5-day, 20 deg. C	Influent	mg/L	55	
09/30/2017	BOD, 5-day, 20 deg. C	Influent	mg/L	83	
06/30/2017	BOD, 5-day, 20 deg. C	Influent	mg/L	102	
03/31/2017	BOD, 5-day, 20 deg. C	Influent	mg/L	177	
09/30/2018	Total Suspended Solids (TSS)	Influent	mg/L	42	
06/30/2018	Total Suspended Solids (TSS)	Influent	mg/L	64	
03/31/2018	Total Suspended Solids (TSS)	Influent	mg/L	72	
12/31/2017	Total Suspended Solids (TSS)	Influent	mg/L	25	
09/30/2017	Total Suspended Solids (TSS)	Influent	mg/L	32	
06/30/2017	Total Suspended Solids (TSS)	Influent	mg/L	53	
03/31/2017	Total Suspended Solids (TSS)	Influent	mg/L	28	

BROWN STATION DMR DATA

Date	Description	Influent/Effluent	Unit	Monthly Average	Daily Max
3/31/2015	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	3	
6/30/2015	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	3	
9/30/2015	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	3	
12/31/2015	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	3	
3/31/2016	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	3	
6/30/2016	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	4	
9/30/2016	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	3	
12/31/2016	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	3	
3/31/2017	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	5	
6/30/2017	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	4	
9/30/2017	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	3	
12/31/2017	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	3	
3/31/2018	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	6	
6/30/2018	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	5	
9/30/2018	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	3	
12/31/2018	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	4	
3/31/2019	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	3	
6/30/2019	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	3	
9/30/2019	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	3	
12/31/2019	BOD, 5-day, 20 deg. C	End of Pipe	mg/L	5	
3/31/2015	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	1000	1000
6/30/2015	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.0065667	0.00144
9/30/2015	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.001	0.001
12/31/2015	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.001352	0.00288
3/31/2016	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.001	0.001
6/30/2016	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.001	0.001
9/30/2016	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.001	0.001
12/31/2016	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.001	0.001
3/31/2017	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.001	0.001
6/30/2017	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.001	0.001
9/30/2017	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.001	0.001
12/31/2017	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.001	0.001
3/31/2018	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.001	0.00178
6/30/2018	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.001	0.001
9/30/2018	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.001	0.001
12/31/2018	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.001	0.001
3/31/2019	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.001	0.001
6/30/2019	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.001	0.001
9/30/2019	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.001	0.001
12/31/2019	Flow, in conduit or thru treatment plant	End of Pipe	Mgal/d	0.001	0.001
3/31/2015	Nitrogen, ammonia total (as N)	End of Pipe	mg/L	0.8	
6/30/2015	Nitrogen, ammonia total (as N)	End of Pipe	mg/L	0.8	
9/30/2015	Nitrogen, ammonia total (as N)	End of Pipe	mg/L	0.3	
12/31/2015	Nitrogen, ammonia total (as N)	End of Pipe	mg/L	0.3	
3/31/2016	Nitrogen, ammonia total (as N)	End of Pipe	mg/L	0.6	
6/30/2016	Nitrogen, ammonia total (as N)	End of Pipe	mg/L	0.3	
9/30/2016	Nitrogen, ammonia total (as N)	End of Pipe	mg/L	0.3	
12/31/2016	Nitrogen, ammonia total (as N)	End of Pipe	mg/L	1.4	
3/31/2017	Nitrogen, ammonia total (as N)	End of Pipe	mg/L	0.6	
6/30/2017	Nitrogen, ammonia total (as N)	End of Pipe	mg/L	0.3	
9/30/2017	Nitrogen, ammonia total (as N)	End of Pipe	mg/L	0.3	
12/31/2017	Nitrogen, ammonia total (as N)	End of Pipe	mg/L	0.3	
3/31/2018	Nitrogen, ammonia total (as N)	End of Pipe	mg/L	1.1	
6/30/2018	Nitrogen, ammonia total (as N)	End of Pipe	mg/L	0.6	
9/30/2018	Nitrogen, ammonia total (as N)	End of Pipe	mg/L	0.3	
12/31/2018	Nitrogen, ammonia total (as N)	End of Pipe	mg/L	1.4	
3/31/2019	Nitrogen, ammonia total (as N)	End of Pipe	mg/L	5.3	
6/30/2019	Nitrogen, ammonia total (as N)	End of Pipe	mg/L	0.3	
9/30/2019	Nitrogen, ammonia total (as N)	End of Pipe	mg/L	0.3	
12/31/2019	Nitrogen, ammonia total (as N)	End of Pipe	mg/L	0.3	
3/31/2015	Total Suspended Solids (TSS)	End of Pipe	mg/L	2	
6/30/2015	Total Suspended Solids (TSS)	End of Pipe	mg/L	3.5	
9/30/2015	Total Suspended Solids (TSS)	End of Pipe	mg/L	2	
12/31/2015	Total Suspended Solids (TSS)	End of Pipe	mg/L	3	
3/31/2016	Total Suspended Solids (TSS)	End of Pipe	mg/L	3	
6/30/2016	Total Suspended Solids (TSS)	End of Pipe	mg/L	7	
9/30/2016	Total Suspended Solids (TSS)	End of Pipe	mg/L	2	
12/31/2016	Total Suspended Solids (TSS)	End of Pipe	mg/L	3	
3/31/2017	Total Suspended Solids (TSS)	End of Pipe	mg/L	3	
6/30/2017	Total Suspended Solids (TSS)	End of Pipe	mg/L	3	
9/30/2017	Total Suspended Solids (TSS)	End of Pipe	mg/L	7	
12/31/2017	Total Suspended Solids (TSS)	End of Pipe	mg/L	6	
3/31/2018	Total Suspended Solids (TSS)	End of Pipe	mg/L	3	
6/30/2018	Total Suspended Solids (TSS)	End of Pipe	mg/L	8	
9/30/2018	Total Suspended Solids (TSS)	End of Pipe	mg/L	3	
12/31/2018	Total Suspended Solids (TSS)	End of Pipe	mg/L	3	
3/31/2019	Total Suspended Solids (TSS)	End of Pipe	mg/L	3	
6/30/2019	Total Suspended Solids (TSS)	End of Pipe	mg/L	3	
9/30/2019	Total Suspended Solids (TSS)	End of Pipe	mg/L	3	
12/31/2019	Total Suspended Solids (TSS)	End of Pipe	mg/L	3	

APPENDIX D

CONVEYANCE SYSTEM PROCESS SCHEMATIC



C:\pwworking\central\01\00973820\EXHIBIT 3.dwg, Plot, 12/14/2020 2:50:56 PM, TGRAHAM

EXHIBIT 3.dwg
 12/14/2020 2:50 PM
 Graham, Tyler



Process Schematic
Cedar Gate, Richardson Acres and Brown Station Wastewater Improvements

EXHIBIT
3
 Case No. SA-2021-0017
 Schedule TR-1, Part 3, Page 131 of 160

APPENDIX E

PUMP/FORCE MAIN DESIGN CALCULATIONS

**Boone County Regional Sewer District
Cedar Gate
Pump Station & Force Main Design Calculations
8-Oct-20**

PVC 2241

Static Lift

Gravity Invert Elevation Into the PS (ft)	900.00
Assumed Depth Below Gravity Invert (ft)	6.00
Pump Center Line Elevation (ft)	894.00
High Point Elevation	935.00
Pump Static Lift Required (ft)	41.00

Length Of Pipe

PS Station (ft)	0
Discharge Point Station (ft)	15300
Total Pipe Length (ft)	15300

Pipe Diameter

Nominal (in)	3
Pipe Type PVC D2241 SDR 21 Inside Diameter (in)	3
Pipe Area (sf)	0.05
Flow at 5 ft/sec (cfs)	0.25
Flow at 5 ft/sec (gpm)	110.2
Flow at 2 ft/sec (cfs)	0.10
Flow at 2 ft/sec (gpm)	44.1

System Flow - From Facility Plan

Number of Future Residences	0
Number of Existing Residences	0
Total Residences in 20 Years	0
Future Flow at 3.7 capita/home and 100 gpd	0
Existing Flow at 3.7 capita/home and 100 gpd	0
Total Flow gpd	12200
Average Day Flow (gpm)	8.5
Peak Hour Flow (PF = 4 x Avg Day) gpm	33.9

Pump Head

Hazen Williams Friction Coefficient New	150
Hazen Williams Friction Coefficient (20 Yrs)	130
Friction Head Calculation (C=150)	48.6
Friction Head Calculation (C=130)	63.4
Friction Head + Static Lift (C=150)	89.6
Friction Head + Static Lift (C=130)	104.4

Wetwell Size

Diameter (ft)	6
Area (sf)	28.27
Water Depth (ft)	5
Volume (cf)	141.4
Volume (gallons)	1057.5

Detention Time Calculations

Existing Avg Flow (gal/day)	12200
Volume of Forcemain (cf)	751
Volume of Forcemain (gal)	5618
Number of Changes/ day	2.17
Retention Time (hours)	11.05

More than 6 hours - Odor Control Required.

Pump Operation - Future Conditions

Average Day Flow Future (gpm)	8.5
Time to Fill Manhole (min)	124.81
Pump Design Flow (gpm)	33.9
Time to Drain Manhole (min)	34.0

Recommended Pump Design

Flow = 34 gpm

Head = 147 feet (104 + 43)

Estimated Pump Horsepower at 50% Efficient(hp)	1.9
--	-----

**Boone County Regional Sewer District
Richardson Acres
Pump Station & Force Main Design Calculations
8-Oct-20**

	PVC 2241
<u>Static Lift</u>	
Gravity Invert Elevation into the PS (ft)	925.00
Assumed Depth Below Gravity Invert (ft)	6.00
Pump Center Line Elevation (ft)	919.00
High Point Elevation	930.00
Pump Static Lift Required (ft)	11.00

<u>Length Of Pipe</u>	
PS Station (ft)	0
Discharge Point Station (ft)	1000
Total Pipe Length (ft)	1000

<u>Pipe Diameter</u>	
Nominal (in)	2
Pipe Type PVC D2241 SDR 21 Inside Diameter (in)	2
Pipe Area (sf)	0.02
Flow at 5 ft/sec (cfs)	0.11
Flow at 5 ft/sec (gpm)	49.0
Flow at 2 ft/sec (cfs)	0.04
Flow at 2 ft/sec (gpm)	19.6

<u>System Flow - From Facility Plan</u>	
Number of Future Residences	0
Number of Existing Residences	0
Total Residences in 20 Years	0
Future Flow at 3.7 capita/home and 100 gpd	0
Existing Flow at 3.7 capita/home and 100 gpd	0
Total Flow gpd	8500
Average Day Flow (gpm)	5.9
Peak Hour Flow (PF = 4 x Avg Day) gpm	23.6

<u>Pump Head</u>	
Hazen Williams Friction Coefficient New	150
Hazen Williams Friction Coefficient (20 Yrs)	130
Friction Head Calculation (C=150)	11.7
Friction Head Calculation (C=130)	15.3
Friction Head + Static Lift (C=150)	22.7
Friction Head + Static Lift (C=130)	26.3

<u>Manhole Size</u>	
Diameter (ft)	6
Area (sf)	28.27
Water Depth (ft)	5
Volume (cf)	141.4
Volume (gallons)	1057.5

<u>Detention Time Calculations</u>	
Existing Avg Flow (gal/day)	8500
Volume of Forcemain (cf)	22
Volume of Forcemain (gal)	163
Number of Changes/ day	52.09
Retention Time (hours)	0.46

Less than 6 hours - Odor Control Not Required.


<u>Pump Operation - Future Conditions</u>	
Average Day Flow Future (gpm)	5.9
Time to Fill Manhole (min)	179.15
Pump Design Flow (gpm)	23.6
Time to Drain Manhole (min)	47.5

Recommended Pump Design	
Flow = 24 gpm	
Head = 69 feet (26 + 43)	
Estimated Pump Horsepower at 50% Efficient(hp)	0.6



**Boone County Regional Sewer District
Brown Station Booster Pump Station
Pump Station & Force Main Design Calculations
8-Oct-20**


	PVC 2241
<u>Static Lift</u>	
Gravity Invert Elevation Into the PS (ft)	920.00
Assumed Depth Below Gravity Invert (ft)	6.00
Pump Center Line Elevation (ft)	914.00
High Point Elevation	925.00
Pump Static Lift Required (ft)	11.00
 <u>Length Of Pipe</u>	
PS Station (ft)	0
Discharge Point Station (ft)	23200
Total Pipe Length (ft)	23200
 <u>Pipe Diameter</u>	
Nominal (in)	6
Pipe Type PVC D2241 SDR 21 Inside Diameter (in)	6
Pipe Area (sf)	0.20
Flow at 5 ft/sec (cfs)	0.98
Flow at 5 ft/sec (gpm)	440.6
Flow at 2 ft/sec (cfs)	0.39
Flow at 2 ft/sec (gpm)	176.2
 <u>System Flow - From Facility Plan</u>	
Number of Future Residences	0
Number of Existing Residences	0
Total Residences in 20 Years	0
Future Flow at 3.7 capita/home and 100 gpd	0
Existing Flow at 3.7 capita/home and 100 gpd	0
Total Flow gpd	91500
Average Day Flow (gpm)	63.5
Peak Hour Flow (PF = 4 x Avg Day) gpm	254.2
 <u>Pump Head</u>	
Hazen Williams Friction Coefficient New	150
Hazen Williams Friction Coefficient (20 Yrs)	130
Friction Head Calculation (C=150)	105.1
Friction Head Calculation (C=130)	137.0
Friction Head + Static Lift (C=150)	116.1
Friction Head + Static Lift (C=130)	148.0
 <u>Manhole Size</u>	
Diameter (ft)	6
Area (sf)	28.27
Water Depth (ft)	5
Volume (cf)	141.4
Volume (gallons)	1057.5
 <u>Detention Time Calculations</u>	
Existing Avg Flow (gal/day)	91500
Volume of Forcemain (cf)	4555
Volume of Forcemain (gal)	34074
Number of Changes/ day	2.69
Retention Time (hours)	8.94
More than 6 hours - Odor Control Required.	
 <u>Pump Operation - Future Conditions</u>	
Average Day Flow Future (gpm)	63.5
Time to Fill Manhole (min)	16.64
Pump Design Flow (gpm)	254.2
Time to Drain Manhole (min)	6.9
 Recommended Pump Design	
Flow = 254 gpm	
Head = 148 feet	
Estimated Pump Horsepower at 50% Efficient(hp)	14.3

APPENDIX F
TYPICAL PUMP STATION SITE PLAN
TYPICAL PUMP STATION PLAN AND SECTION




C:\pwworking\central\01\cd0973820\EXHIBIT 4.dwg, Plot: 8/10/2020 9:22:46 AM, TGRAHAM
 EXHIBIT 4.dwg
 8/10/2020 9:22 AM
 Graham, Tyler


 BCRSD <small>Barron County Regional Sewer District</small>		<h3 style="margin: 0;">Typical Pump Station Site Plan</h3> <h2 style="margin: 0;">Cedar Gate, Richardson Acres and Brown Station Wastewater Improvements</h2>	EXHIBIT <h1 style="margin: 0;">4</h1>
		Case No. SA-2021-0017 Schedule 1R-1, Part 3, Page 137 of 160	



TYPICAL PUMP STATION - UPPER PLAN



SECTION



TYPICAL PUMP STATION - LOWER PLAN

C:\pwworking\central\01\0973820\EXHIBIT 6.dwg, Plot, 8/10/2020 9:26:24 AM, TGRAHAM

EXHIBIT 6.dwg
 8/10/2020 9:26 AM
 Graham, Tyler



**Typical Pump Station
 Plan and Sections**

**Cedar Gate, Richardson Acres and Brown
 Station Wastewater Improvements**

EXHIBIT

6

APPENDIX G
PROJECT COST ESTIMATE
OPERATIONS AND MAINTENANCE COST ESTIMATE

ALTERNATIVE NO. 2

Base Year for cost Estimate: 2020
 First Year of Service: 2022
 Mid-Point of Construction: 2021

Item	Base Year Cost	Mid-Point of Construction	First Year of Service	2022	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037	2038	2039	2040	2041	
Total Project Costs		\$916,000																						
NPV of Capital Costs at Base Year ⁽¹⁾		\$916,000																						
Total NPV of Capital Costs ⁽¹⁾		\$916,000																						
RRR	\$7,823		\$7,823	\$7,823	\$7,823	\$7,823	\$7,823	\$7,823	\$7,823	\$7,823	\$7,823	\$7,823	\$7,823	\$7,823	\$7,823	\$7,823	\$7,823	\$7,823	\$7,823	\$7,823	\$7,823	\$7,823	\$7,823	
Labour	\$10,400		\$11,033	\$11,364	\$11,705	\$12,047	\$12,389	\$12,731	\$13,073	\$13,415	\$13,757	\$14,100	\$14,442	\$14,784	\$15,126	\$15,468	\$15,810	\$16,152	\$16,494	\$16,836	\$17,178	\$17,520	\$17,862	
Electricity	\$2,991		\$3,173	\$3,355	\$3,537	\$3,719	\$3,901	\$4,083	\$4,265	\$4,447	\$4,629	\$4,811	\$4,993	\$5,175	\$5,357	\$5,539	\$5,721	\$5,903	\$6,085	\$6,267	\$6,449	\$6,631	\$6,813	
Total O&M Costs	\$21,214		\$22,029	\$22,456	\$22,883	\$23,310	\$23,737	\$24,164	\$24,591	\$25,018	\$25,445	\$25,872	\$26,299	\$26,726	\$27,153	\$27,580	\$28,007	\$28,434	\$28,861	\$29,288	\$29,715	\$30,142	\$30,569	
NPV of O&M Costs at Base Year		\$21,214		\$22,029	\$22,456	\$22,883	\$23,310	\$23,737	\$24,164	\$24,591	\$25,018	\$25,445	\$25,872	\$26,299	\$26,726	\$27,153	\$27,580	\$28,007	\$28,434	\$28,861	\$29,288	\$29,715	\$30,142	
Total NPV of O&M Costs		\$21,214		\$22,029	\$22,456	\$22,883	\$23,310	\$23,737	\$24,164	\$24,591	\$25,018	\$25,445	\$25,872	\$26,299	\$26,726	\$27,153	\$27,580	\$28,007	\$28,434	\$28,861	\$29,288	\$29,715	\$30,142	
NPV Summary																								
Capital Cost		\$916,000																						
O&M		\$21,214		\$22,029	\$22,456	\$22,883	\$23,310	\$23,737	\$24,164	\$24,591	\$25,018	\$25,445	\$25,872	\$26,299	\$26,726	\$27,153	\$27,580	\$28,007	\$28,434	\$28,861	\$29,288	\$29,715	\$30,142	
Total NPV		\$937,214		\$938,029	\$938,483	\$938,937	\$939,391	\$939,845	\$940,299	\$940,753	\$941,207	\$941,661	\$942,115	\$942,569	\$943,023	\$943,477	\$943,931	\$944,385	\$944,839	\$945,293	\$945,747	\$946,201	\$946,655	\$947,109

NPV Summary
 Capital Cost: \$916,000
 O&M: \$21,214
Total NPV: \$937,214

Economic Assumptions
 Capital Escalation (Inflation) Rate: 3.00%
 O&M Escalation (Inflation) Rate: 3.00%
 Annual Interest (Discount) Rate: 4.00%

Notes:

Project # 162809/240022

Base Year for cost Estimate 2020
 First Year of Service 2022
 Mid-Point of Construction 2021

Item	2020	2021	2022	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037	2038	2039	2040	2041	
Base Year Cost																							
2020	\$1,327,000																						
Mid-Point of Construction																							
2021		\$1,327,000																					
First Year of Service																							
2022			\$7,387	\$7,387	\$7,387	\$7,387	\$7,387	\$7,387	\$7,387	\$7,387	\$7,387	\$7,387	\$7,387	\$7,387	\$7,387	\$7,387	\$7,387	\$7,387	\$7,387	\$7,387	\$7,387	\$7,387	\$7,387
Total Project Costs			\$7,387	\$7,387	\$7,387	\$7,387	\$7,387	\$7,387	\$7,387	\$7,387	\$7,387	\$7,387	\$7,387	\$7,387	\$7,387	\$7,387	\$7,387	\$7,387	\$7,387	\$7,387	\$7,387	\$7,387	\$7,387
NPV of Capital Costs at Base Year⁽¹⁾			\$11,033	\$11,033	\$11,033	\$11,033	\$11,033	\$11,033	\$11,033	\$11,033	\$11,033	\$11,033	\$11,033	\$11,033	\$11,033	\$11,033	\$11,033	\$11,033	\$11,033	\$11,033	\$11,033	\$11,033	\$11,033
NPV of O&M Costs at Base Year			\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687
NPV of O&M Costs			\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687
Total NPV of O&M Costs			\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687	\$4,687
Total NPV of Capital Costs			\$11,033	\$11,033	\$11,033	\$11,033	\$11,033	\$11,033	\$11,033	\$11,033	\$11,033	\$11,033	\$11,033	\$11,033	\$11,033	\$11,033	\$11,033	\$11,033	\$11,033	\$11,033	\$11,033	\$11,033	\$11,033
Total NPV			\$15,720	\$15,720	\$15,720	\$15,720	\$15,720	\$15,720	\$15,720	\$15,720	\$15,720	\$15,720	\$15,720	\$15,720	\$15,720	\$15,720	\$15,720	\$15,720	\$15,720	\$15,720	\$15,720	\$15,720	\$15,720

NPV Summary
 Capital Cost \$1,327,000
 O&M \$556,000
Total NPV \$1,693,000

Economic Assumptions
 Capital Escalation (Inflation) Rate 3.00%
 O&M Escalation (Inflation) Rate 3.00%
 Annual Interest (Discount) Rate 7.00%

Notes:

Project # 155249200212

2020
Base Year for cost Estimate
2021
Mid-Point of Construction

Item	2020	2021	2022	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037	2038	2039	2040	2041		
Year Project Costs																								
DCV of Capital Costs at Base Year ⁽¹⁾	\$677,000	\$677,000																						
Year NPV of Capital Costs	\$646,000	\$646,000																						
RRR	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	
Labour	\$10,400	\$10,400	\$10,400	\$10,400	\$10,400	\$10,400	\$10,400	\$10,400	\$10,400	\$10,400	\$10,400	\$10,400	\$10,400	\$10,400	\$10,400	\$10,400	\$10,400	\$10,400	\$10,400	\$10,400	\$10,400	\$10,400	\$10,400	
EMPS/OS	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	\$4,008	
OS/OSM	\$5,034	\$5,034	\$5,034	\$5,034	\$5,034	\$5,034	\$5,034	\$5,034	\$5,034	\$5,034	\$5,034	\$5,034	\$5,034	\$5,034	\$5,034	\$5,034	\$5,034	\$5,034	\$5,034	\$5,034	\$5,034	\$5,034	\$5,034	
OSM	\$19,015	\$19,015	\$19,015	\$19,015	\$19,015	\$19,015	\$19,015	\$19,015	\$19,015	\$19,015	\$19,015	\$19,015	\$19,015	\$19,015	\$19,015	\$19,015	\$19,015	\$19,015	\$19,015	\$19,015	\$19,015	\$19,015	\$19,015	
Year NPV of O&M Costs	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	
NPV Summary																								
Capital Cost	\$646,000	\$646,000																						
O&M	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	\$321,000	
Total NPV	\$967,000	\$967,000	\$967,000	\$967,000	\$967,000	\$967,000	\$967,000	\$967,000	\$967,000	\$967,000	\$967,000	\$967,000	\$967,000	\$967,000	\$967,000	\$967,000	\$967,000	\$967,000	\$967,000	\$967,000	\$967,000	\$967,000	\$967,000	

NPV Summary
Capital Cost
O&M

Total NPV

Economic Assumptions
Capital Expenditure (Million) Rate
Operating Expenditure (Million) Rate
Annual Interest (Discount) Rate

Notes:

**BOONE COUNTY REGIONAL SEWER DISTRICT
ALTERNATIVE #2 - CEDAR GATE WWTF IMPROVEMENTS
ENGINEER'S OPINION OF PROJECT COSTS
10/8/2020**

Item Description	Est. Qty.	Unit	Unit Price	Extension
Intermediate Pump Station				
Excavation/Backfill	148	CY	\$25	\$3,698
Granular Bedding	1	CY	\$50	\$52
Package Pump Station	1	LS	\$49,500	\$49,500
Pump Controls	1	LS	\$10,000	\$10,000
Installation / Start-Up	50%			\$31,625
Tertiary Nitrification				
Excavation/Backfill	86	CY	\$25	\$2,139
Granular Bedding	6	CY	\$50	\$286
Concrete Basins	51	CY	\$1,500	\$75,825
NitrOx System	1	LS	\$117,500	\$117,500
Installation / Start-Up	35%			\$68,513
UV Disinfection				
Excavation/Backfill	3	CY	\$25	\$78
Granular Bedding	2	CY	\$50	\$89
Base Slab	2	CY	\$1,000	\$1,778
UV System	1	LS	\$41,250	\$41,250
Installation / Start-Up	35%			\$15,118
SUBTOTAL				\$417,500
Site Piping and Site Civil	15%			\$62,625
Electrical and I&C	10%			\$42,000
SUBTOTAL				\$522,100
Contractor Items				
Mobilization	2%			\$11,000
Bonding and Insurance	3%			\$16,000
General Conditions, OH&P	10%			\$55,000
SUBTOTAL				\$604,100
Contingency	25%			\$152,000
SUBTOTAL				\$756,100
SRF Closing Costs	2%			\$16,000
Engineering, Legal, and Administration	20%			\$152,000
Temporary Easement (3)	1	AC	\$1,000.00	\$1,000
TOTAL PROJECT				\$925,100
Notes:				
1. Assumes no rock excavation				
2. Assumes portable generator cost included in Richardson Acres cost.				
3. Assume temporary easement required for site staging and construction.				

**BOONE COUNTY REGIONAL SEWER DISTRICT
ALTERNATIVE #2 - RICHARDSON ACRES WWTF IMPROVEMENTS
ENGINEER'S OPINION OF PROJECT COSTS
10/8/2020**

Item Description	Est. Qty.	Unit	Unit Price	Extension
Intermediate Pump Station				
Excavation/Backfill	150	CY	\$25	\$3,750
Granular Bedding	2	CY	\$50	\$100
Package Pump Station	1	LS	\$48,000	\$48,000
Pump Controls	1	LS	\$10,000	\$10,000
Installation / Start-Up	50%			\$30,925
Tertiary Nitrification				
Excavation/Backfill	2,500	CY	\$30	\$75,000
SAGR (Nitrification Equipment, Including Blowers)	1	LS	\$150,000	\$150,000
Uniform Graded Clean Rock	960	CY	\$35	\$33,600
Insulating Woodchips	80	CY	\$10	\$800
Non-Woven Geotextile (8oz)	11,800	SF	\$0.15	\$1,800
HDPE Liner (60 mil)	7,840	SF	\$1.50	\$11,800
Wall Framing and Sheating	470	LF	\$13	\$6,200
Influent Flow Splitter Structure	1	EA	\$5,000	\$5,000
Piping, Fittings, Valves from Splitter to SAGR	1	LS	\$10,000	\$10,000
Effluent Level Control Manhole	2	EA	\$5,000	\$10,000
Installation / Start-Up ⁽³⁾	40%			\$121,680
UV Disinfection				
Excavation/Backfill	4	CY	\$25	\$100
Granular Bedding	2	CY	\$50	\$100
Base Slab	2	CY	\$1,000	\$2,000
UV System	1	LS	\$40,500	\$40,500
Installation / Start-Up	35%			\$14,945
SUBTOTAL				\$576,300
Site Piping and Site Civil	15%			\$86,445
Portable Generator	1	EA	\$36,000	\$36,000
Electrical and I&C	10%			\$57,630
SUBTOTAL				\$756,400
Contractor Items				
Mobilization	2%			\$16,000
Bonding and Insurance	3%			\$24,000
General Conditions, OH&P	10%			\$80,000

Case No. SA-2021-0017

Item Description	Est. Qty.	Unit	Unit Price	Extension
SUBTOTAL				\$876,400
Contingency	25%			\$219,100
SUBTOTAL				\$1,095,500
SRF Closing Costs	2%			\$22,000
Engineering, Legal, and Administration	20%			\$220,000
Temporary Easement ⁽²⁾	1	AC	\$2,500	\$2,500
TOTAL PROJECT				\$1,340,000
Notes:				
1. Assumes no rock excavation.				
2. Assume temporary easement required for site staging and construction.				
3. Utilizd 40% SAGR installation due to high anticipated labor requirement.				

**BOONE COUNTY REGIONAL SEWER DISTRICT
ALTERNATIVE #2 - BROWN STATION WWTF IMPROVEMENTS
ENGINEER'S OPINION OF PROJECT COSTS
10/8/2020**

Item Description	Est. Qty.	Unit	Unit Price	Extension
Intermediate Pump Station				
Excavation/Backfill	150	CY	\$25	\$3,750
Granular Bedding	2	EA	\$50	\$100
Package Pump Station	1	LS	\$46,500	\$46,500
Pump Controls	1	LS	\$10,000	\$10,000
Installation / Start-Up	50%	LS		\$30,175
Tertiary Nitrification				
Excavation/Backfill	710	CY	\$30	\$21,300
SAGR (Nitrification Equipment, Including Blowers)	1	LS	\$42,200	\$42,200
Uniform Graded Clean Rock	270	CY	\$35	\$9,500
Insulating Woodchips	30	CY	\$10	\$300
Non-Woven Geotextile (8oz)	3,320	SF	\$0.15	\$500
HDPE Liner (60 mil)	2,210	SF	\$1.50	\$3,400
Wall Framing and Sheeting	140	LF	\$13	\$1,900
Influent Flow Splitter Structure	1	EA	\$5,000	\$5,000
Piping, Fittings, Valves from Splitter to SAGR	1	LS	\$10,000	\$10,000
Effluent Level Control Manhole	2	EA	\$5,000	\$10,000
Installation / Start-Up ⁽³⁾	40%			\$41,640
UV Disinfection				
Excavation/Backfill	4	CY	\$25	\$100
Granular Bedding	2	CY	\$50	\$100
Base Slab	2	CY	\$1,000	\$2,000
UV System	1	LS	\$39,750	\$39,750
Installation / Start-Up	35%			\$14,683
SUBTOTAL				\$292,900
Site Piping and Site Civil	15%			\$43,935
Electrical and I&C	10%			\$29,290
SUBTOTAL				\$366,200

Item Description	Est. Qty.	Unit	Unit Price	Extension
Contractor Items				
Mobilization	2%			\$8,000
Bonding and Insurance	3%			\$12,000
General Conditions, OH&P	10%			\$39,000
SUBTOTAL				\$425,200
Contingency	25%			\$106,300
SUBTOTAL				\$531,500
SRF Closing Costs	2%			\$11,000
Engineering, Legal, and Administration	20%			\$107,000
Temporary Easement ⁽²⁾	1	AC	\$2,500	\$2,500
TOTAL PROJECT				\$652,000
Notes:				
1. Assumes no rock excavation.				
2. Assume temporary easement required for site staging and construction.				
3. Utilizd 40% SAGR installation due to high anticipated labor requirement.				
4. Assumes portable generator cost included in Richardson Acres cost.				

**BOONE COUNTY REGIONAL SEWER DISTRICT
CEDAR GATE WWTF IMPROVEMENTS
OPERATIONS AND MAINTENANCE COST ESTIMATE - ALT 2 WWTF**

Replacement Costs

Inflation Rate	3%	Assumed
Interest Rate	4%	Assumed

Today's Replacement Costs

Item	5 YR - 10%	10 YR - 50%	15 YR - 10%	20 YR - 75%	Original Cost
Intermediate Pumps	\$2,063	\$10,313	\$2,063	\$15,469	\$20,625
NitrOx System	\$5,850	\$29,250	\$5,850	\$43,875	\$58,500
UV Equipment	\$2,000	\$2,000	\$2,000	\$2,000	
Total	\$9,913	\$41,563	\$9,913	\$61,344	

Future Replacement Costs

(Adjusted w/ Inflation)

	Present Value	5 YR	10 YR	15 YR	20 YR
		1.16	1.34	1.56	1.81
5 Year Equipment Cycle	\$9,913	\$11,491			
10 Year Equipment Cycle	\$41,563		\$55,857		
15 Year Equipment Cycle	\$9,913			\$15,443	
20 Year Equipment Cycle	\$61,344				\$110,794
Total	\$122,731	\$11,491	\$55,857	\$15,443	\$110,794

Replacement Acnt. Deposit

(Includes Interest)

Required

	Annual Factor	Annual Deposit	5 YR	10 YR	15 YR	20 YR
			\$11,491	\$55,857	\$15,443	\$110,794
			Future Replacement Funds			
SFF - 5 yrs	0.1846	\$2,122	\$11,491	\$11,491	\$11,491	\$11,491
SFF - 10 yrs	0.0833	\$3,695		\$44,365	\$20,015	\$20,015
SFF - 15 yrs	0.0499	(\$802)			(\$16,062)	(\$4,345)
SFF - 20 yrs	0.0336	\$2,809				\$83,633
Total			\$11,491	\$55,857	\$15,443	\$110,794

Estimated Annual Replacement Costs

Deposit \$7,823

Labor Costs

Component	Days Per Week	Hours Per Day	Personnel	Rate	Overhead / Fringe	Cost
Daily Operator Attention	5	1.0	1	\$25.00	\$15.00	\$10,400

Estimated Annual Labor Costs

\$10,400

Electricity Usage Costs (Design Year)

Component	HP	Quantity	Total HP	Watts	Hours/day	kW-hrs/year
Intermediate Pumps	2.0	1	2	1,491	8	4,355
Nitrox System						
Nitrox Aeration Blowers	2.0	1	2	1,491	16	8,710
Nitrox Heating (Based on 1°C for 2 months and 3°C for 2 months Infl.)	-	-	-	-	-	17,611
UV Equipment	-	2	-	250	24	2,190
					kW-hrs/year =	32,866
					\$/kW-hrs =	\$0.09

Estimated Additional Annual Electricity Usage Costs (Design Year, Not Adjusted For Inflation)

\$2,991

TOTAL

\$21,214

**BOONE COUNTY REGIONAL SEWER DISTRICT
RICHARDSON ACRES WWTF IMPROVEMENTS
OPERATIONS AND MAINTENANCE COST ESTIMATE - ALT 2 WWTF**

Replacement Costs

Inflation Rate	<u>3%</u>	Assumed
Interest Rate	<u>4%</u>	Assumed

Today's Replacement Costs

Item	5 YR - 10%	10 YR - 50%	15 YR - 10%	20 YR - 75%	Original Cost
Intermediate Pumps	\$2,000	\$10,000	\$2,000	\$15,000	\$20,000
SAGR - Aeration	\$6,500	\$6,500	\$6,500	\$6,500	
SAGR - Media	\$0	\$0	\$0	\$0	
Sand Filter Equipment					
UV Equipment	\$2,000	\$2,000	\$2,000	\$2,000	
Portable Standby Generator	\$3,600	\$18,000	\$3,600	\$27,000	\$36,000
Total	\$14,100	\$36,500	\$14,100	\$50,500	

Future Replacement Costs

(Adjusted w/ Inflation)	Present Value	5 YR	10 YR	15 YR	20 YR
		<u>1.16</u>	<u>1.34</u>	<u>1.56</u>	<u>1.81</u>
5 Year Equipment Cycle	\$14,100	\$16,346			
10 Year Equipment Cycle	\$36,500		\$49,053		
15 Year Equipment Cycle	\$14,100			\$21,967	
20 Year Equipment Cycle	\$50,500				\$91,209
Total	\$115,200	\$16,346	\$49,053	\$21,967	\$91,209

Replacement Acnt. Deposit

(Includes Interest)

	<u>Required</u>		5 YR	10 YR	15 YR	20 YR
	Annual Factor	Annual Deposit	\$16,346	\$49,053	\$21,967	\$91,209
SFF - 5 yrs	0.1846	\$3,018	\$16,346	\$16,346	\$16,346	\$16,346
SFF - 10 yrs	0.0833	\$2,724		\$32,707	\$14,755	\$14,755
SFF - 15 yrs	0.0499	(\$456)			(\$9,134)	(\$2,471)
SFF - 20 yrs	0.0336	\$2,101				\$62,578
Total			\$16,346	\$49,053	\$21,967	\$91,209

Estimated Annual Replacement Costs

Deposit \$7,387

Labor Costs

Component	Days Per Week	Hours Per Day	Personnel	Rate	Overhead / Fringe	Cost
Daily Operator Attention	5	1.0	1	\$25.00	\$15.00	\$10,400

Estimated Annual Labor Costs

\$10,400

Electricity Usage Costs (Design Year)

Component	HP	Quantity	Total HP	Watts	Hours/day	kW-hrs/year
Intermediate Pumps	2.0	2	4	2,983	8	8,710
SAGR Aeration Blowers	7.5	1	7.5	5,593	24	48,992
UV Equipment		1		250	24	2,190
					kW-hrs/year =	51,182
					\$/kW-hrs =	\$0.09

Estimated Additional Annual Electricity Usage Costs (Design Year, Not Adjusted For Inflation)

\$4,606

TOTAL

Case No. SA-2021-0017 \$22,394

**BOONE COUNTY REGIONAL SEWER DISTRICT
BROWN STATION WWTF IMPROVEMENTS
OPERATIONS AND MAINTENANCE COST ESTIMATE - ALT 2 WWTF**

Replacement Costs

Inflation Rate	3%	Assumed
Interest Rate	4%	Assumed

Today's Replacement Costs

Item	5 YR - 10%	10 YR - 50%	15 YR - 10%	20 YR - 75%	Original Cost
Intermediate Pumps	\$1,938	\$9,688	\$1,938	\$14,531	\$19,375
SAGR - Aeration	\$6,500	\$6,500	\$6,500	\$6,500	
SAGR - Media	\$0	\$0	\$0	\$0	
Sand Filter Equipment					
UV Equipment	\$2,000	\$2,000	\$2,000	\$2,000	
Total	\$10,438	\$18,188	\$10,438	\$23,031	

Future Replacement Costs

(Adjusted w/ Inflation)	Present Value	5 YR	10 YR	15 YR	20 YR
		1.16	1.34	1.56	1.81
5 Year Equipment Cycle	\$10,438	\$12,100			
10 Year Equipment Cycle	\$18,188		\$24,442		
15 Year Equipment Cycle	\$10,438			\$16,261	
20 Year Equipment Cycle	\$23,031				\$41,597
Total	\$62,094	\$12,100	\$24,442	\$16,261	\$41,597

**Replacement Acct. Deposit
(Includes Interest)**

	Required					
	Annual Factor	Annual Deposit	5 YR	10 YR	15 YR	20 YR
			\$12,100	\$24,442	\$16,261	\$41,597
SFF - 5 yrs	0.1846	\$2,234	\$12,100	\$12,100	\$12,100	\$12,100
SFF - 10 yrs	0.0833	\$1,028		\$12,343	\$5,568	\$5,568
SFF - 15 yrs	0.0499	(\$70)			(\$1,407)	(\$381)
SFF - 20 yrs	0.0336	\$816				\$24,309
Total			\$12,100	\$24,442	\$16,261	\$41,597

Estimated Annual Replacement Costs

Deposit \$4,008

Labor Costs

Component	Days Per Week	Hours Per Day	Personnel	Rate	Overhead / Fringe	Cost
Daily Operator Attention	5	1.0	1	\$25.00	\$15.00	\$10,400

Estimated Annual Labor Costs

\$10,400

Electricity Usage Costs (Design Year)

Component	HP	Quantity	Total HP	Watts	Hours/day	kW-hrs/year
Intermediate Pumps	2.0	2	4	2,983	8	8,710
SAGR Aeration	7.5	1	7.5	5,593	24	48,992
UV Equipment		1		250	24	2,190
					kW-hrs/year =	51,182
					\$/kW-hrs =	\$0.09

Estimated Additional Annual Electricity Usage Costs (Design Year, Not Adjusted For Inflation)

\$4,606

TOTAL

\$19,015

ALTERNATIVE NO. 3

Project # 16266/24042

Base Year for cost estimate
 2020
 Year of Service
 2022
 Mid-Point of Construction
 2021

Item	Base Year Cost	Mid-Point of Construction	First Year of Service	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037	2038	2039	2040	2041
Total Project Costs	\$3,501,000	\$3,501,000																				
NPV of Capital Costs at Base Year ⁽¹⁾		\$3,501,000																				
NPV of O&M Costs																						
R&R	\$13,680	\$13,680	\$13,680	\$13,680	\$13,680	\$13,680	\$13,680	\$13,680	\$13,680	\$13,680	\$13,680	\$13,680	\$13,680	\$13,680	\$13,680	\$13,680	\$13,680	\$13,680	\$13,680	\$13,680	\$13,680	\$13,680
Labor	\$17,450	\$17,450	\$17,450	\$17,450	\$17,450	\$17,450	\$17,450	\$17,450	\$17,450	\$17,450	\$17,450	\$17,450	\$17,450	\$17,450	\$17,450	\$17,450	\$17,450	\$17,450	\$17,450	\$17,450	\$17,450	\$17,450
Chemical	\$3,400	\$3,400	\$3,400	\$3,400	\$3,400	\$3,400	\$3,400	\$3,400	\$3,400	\$3,400	\$3,400	\$3,400	\$3,400	\$3,400	\$3,400	\$3,400	\$3,400	\$3,400	\$3,400	\$3,400	\$3,400	\$3,400
Electricity	\$5,720	\$5,720	\$5,720	\$5,720	\$5,720	\$5,720	\$5,720	\$5,720	\$5,720	\$5,720	\$5,720	\$5,720	\$5,720	\$5,720	\$5,720	\$5,720	\$5,720	\$5,720	\$5,720	\$5,720	\$5,720	\$5,720
Other O&M Costs	\$2,850	\$2,850	\$2,850	\$2,850	\$2,850	\$2,850	\$2,850	\$2,850	\$2,850	\$2,850	\$2,850	\$2,850	\$2,850	\$2,850	\$2,850	\$2,850	\$2,850	\$2,850	\$2,850	\$2,850	\$2,850	\$2,850
NPV of O&M Costs at Base Year	\$17,440	\$17,440	\$17,440	\$17,440	\$17,440	\$17,440	\$17,440	\$17,440	\$17,440	\$17,440	\$17,440	\$17,440	\$17,440	\$17,440	\$17,440	\$17,440	\$17,440	\$17,440	\$17,440	\$17,440	\$17,440	\$17,440
Total NPV of O&M Costs	\$605,000	\$605,000	\$605,000	\$605,000	\$605,000	\$605,000	\$605,000	\$605,000	\$605,000	\$605,000	\$605,000	\$605,000	\$605,000	\$605,000	\$605,000	\$605,000	\$605,000	\$605,000	\$605,000	\$605,000	\$605,000	\$605,000
NPV Summary																						
Project Cost		\$3,501,000																				
O&M		\$605,000																				
Total NPV		\$4,106,000																				

Economic Assumptions
 Capital Escalation (inflation) Rate
 O&M Escalation (inflation) Rate
 Annual Interest (Discount) Rate

Notes:

AMENDMENT 1 - RICHARDSON ACRES AND BROWN STATION WASTEWATER IMPROVEMENTS
BOONE COUNTY REGIONAL SEWER DISTRICT
ESTIMATE OF COST
OCTOBER 8, 2020

Item No.	Item Description	Est. Qty.	Unit	Estimate of Cost	
				Unit Price	Extension
1	Mobilization	1	LS	\$80,000.00	\$80,000.00
2	2 IN Force Main	1000	LF	\$11.00	\$11,000.00
3	3 IN Force Main	15300	LF	\$14.00	\$214,200.00
4	4 IN Force Main	29300	LF	\$8.00	\$234,400.00
5	6 IN Force Main	22200	LF	\$21.00	\$466,200.00
6	2 IN Combination Air Release/Vacuum Valve	22	EA	\$4,800.00	\$105,600.00
7	12 IN Horizontal Directional Drilling	300	LF	\$170.00	\$51,000.00
CEDAR GATE PUMP STATION					
8	Submersable Non-Clog Pumps	0	LS	\$40,000.00	\$0.00
9	Submersable Grinder Pumps	1	LS	\$25,000.00	\$25,000.00
10	Odor Control Facility	0	LS	\$90,000.00	\$0.00
11	Pump Station (Excluding Submersible Pumps)	1	LS	\$180,000.00	\$180,000.00
12	Lagoon Fill Material	100	CY	\$25.00	\$2,500.00
13	Sludge Removal	1	LS	\$50,000.00	\$50,000.00
14	Wastewater Treatment Facility Closure	1	LS	\$10,000.00	\$10,000.00
RICHARDSON ACRES PUMP STATION					
15	Submersable Non-Clog Pumps	0	LS	\$40,000.00	\$0.00
16	Submersable Grinder Pumps	1	LS	\$25,000.00	\$25,000.00
17	Odor Control Facility	0	LS	\$90,000.00	\$0.00
18	Pump Station (Excluding Submersible Pumps)	1	LS	\$180,000.00	\$180,000.00
19	Lagoon Fill Material	200	CY	\$25.00	\$5,000.00
20	Sludge Removal	1	LS	\$50,000.00	\$50,000.00
21	Wastewater Treatment Facility Closure	1	LS	\$10,000.00	\$10,000.00
BOOSTER PUMP STATION AT BROWN STATION					
22	Submersable Non-Clog Pumps	1	LS	\$40,000.00	\$40,000.00
23	Submersable Grinder Pumps	0	LS	\$25,000.00	\$0.00
24	Odor Control Facility	1	LS	\$90,000.00	\$90,000.00
25	Pump Station (Excluding Submersible Pumps)	1	LS	\$180,000.00	\$180,000.00
26	Underground Pipe Storage	100	LF	\$300.00	\$30,000.00
27	Lagoon Fill Material	0	CY	\$25.00	\$0.00
28	Sludge Removal	0	LS	\$50,000.00	\$0.00
29	Wastewater Treatment Facility Closure	1	LS	\$15,000.00	\$15,000.00
30	Erosion Control Fence	45000	LF	\$2.20	\$99,000.00
31	Seeding	45000	LF	\$2.00	\$90,000.00
CONSTRUCTION SUBTOTAL					\$2,243,900.00
Contingency (25%)			LS		\$560,975.00
CONSTRUCTION TOTAL					\$2,804,875.00
Easements			LS		\$113,000.00
SRF Closing Costs (2%)			LS		\$56,097.50
Engineering, Legal, Administration (20%)			LS		\$560,975.00
PROJECT TOTAL					\$3,534,947.50

**BOONE COUNTY REGIONAL SEWER DISTRICT
CEDAR GATE PUMP STATION
OPERATIONS AND MAINTENANCE COST ESTIMATE
10/06/20**

Replacement Costs

Inflation Rate	3%	Assumed
Interest Rate	4%	Assumed

Today's Replacement Costs

Item	5 YR - 10%	10 YR - 25%	15 YR - 10%	20 YR - 50%	Original Cost
Pumps	\$6,000	\$7,500	\$6,000	\$15,000	\$30,000
Liquid Odor Control	\$8,000	\$0	\$8,000	\$0	\$0
Portable Standby Generator	\$7,200	\$0	\$7,200	\$0	\$0
Total	\$21,200	\$7,500	\$21,200	\$15,000	

Future Replacement Costs

(Adjusted w/ Inflation)	Present Value	5 YR	10 YR	15 YR	20 YR
		1.16	1.34	1.56	1.81
5 Year Equipment Cycle	\$21,200	\$24,577			
10 Year Equipment Cycle	\$7,500		\$10,079		
15 Year Equipment Cycle	\$21,200			\$33,029	
20 Year Equipment Cycle	\$15,000				\$27,092
Total	\$64,900	\$24,577	\$10,079	\$33,029	\$27,092

Replacement Acct. Deposit

(Includes Interest)	Required	5 YR	10 YR	15 YR	20 YR
		\$24,577	\$10,079	\$33,029	\$27,092
	Annual Factor	Annual Deposit	Future Replacement Funds		
SFF - 5 yrs	0.1846	\$4,538	\$24,577	\$24,577	\$24,577
SFF - 10 yrs	0.0833	(\$1,207)		(\$14,497)	(\$6,540)
SFF - 15 yrs	0.0499	\$749		\$14,992	\$4,055
SFF - 20 yrs	0.0336	\$168			\$5,000
Total			\$24,577	\$10,079	\$33,029

Estimated Annual Replacement Costs

Deposit \$4,247

Chemical Costs

Component	Gallons Per Day	Gallons Per Year	Cost Per Gallon	Cost
Bioxide (Future)	0	0	\$3.00	\$0

Estimated Annual Chemical Costs

\$0

Labor Costs

Component	Days Per Week	Hours Per Day	Personnel	Rate	Overhead / Fringe	Cost
Lift Stations Week Day Staff (Operator)	2	1	1	\$25.00	\$15.00	\$4,160

Estimated Annual Labor Costs

\$4,160

Electricity Usage Costs (Design Year)

Component	HP	Quantity	Total HP	Watts	Hours/day	kW-hrs/year
Pumps	4.0	1	4	2,983	8	8,710
Liquid Odor Control	0	0	0	0	12	0
					kW-hrs/year =	8,710
					\$/kW-hrs =	\$0.09

Estimated Additional Annual Electricity Usage Costs (Design Year, Not Adjusted For Inflation)

\$784

TOTAL

\$9,191

**BOONE COUNTY REGIONAL SEWER DISTRICT
RICHARDSON ACRES PUMP STATION
OPERATIONS AND MAINTENANCE COST ESTIMATE
10/06/20**

Replacement Costs

Inflation Rate	3%	Assumed
Interest Rate	4%	Assumed

Today's Replacement Costs

Item	5 YR - 10%	10 YR - 25%	15 YR - 10%	20 YR - 50%	Original Cost
Pumps	\$6,000	\$7,500	\$6,000	\$15,000	\$30,000
Liquid Odor Control	\$8,000	\$0	\$8,000	\$0	\$0
Portable Standby Generator	\$7,200	\$0	\$7,200	\$0	\$0
Total	\$21,200	\$7,500	\$21,200	\$15,000	

Future Replacement Costs

(Adjusted w/ Inflation)	Present Value	5 YR	10 YR	15 YR	20 YR
5 Year Equipment Cycle	\$21,200	\$24,577			
10 Year Equipment Cycle	\$7,500		\$10,079		
15 Year Equipment Cycle	\$21,200			\$33,029	
20 Year Equipment Cycle	\$15,000				\$27,092
Total	\$64,900	\$24,577	\$10,079	\$33,029	\$27,092

Replacement Acct. Deposit

(Includes Interest)	Required	5 YR	10 YR	15 YR	20 YR
Annual Factor	Annual Deposit	\$24,577	\$10,079	\$33,029	\$27,092
SFF - 5 yrs	0.1846	\$4,538	\$24,577	\$24,577	\$24,577
SFF - 10 yrs	0.0833	(\$1,207)		(\$14,497)	(\$6,540)
SFF - 15 yrs	0.0499	\$749		\$14,992	\$4,055
SFF - 20 yrs	0.0336	\$168			\$5,000
Total			\$24,577	\$10,079	\$33,029

Estimated Annual Replacement Costs

Deposit \$4,247

Chemical Costs

Component	Gallons Per Day	Gallons Per Year	Cost Per Gallon	Cost
Bioxide (Future)	0	0	\$3.00	\$0

Estimated Annual Chemical Costs

\$0

Labor Costs

Component	Days Per Week	Hours Per Day	Personnel	Rate	Overhead / Fringe	Cost
Lift Stations Week Day Staff (Operator)	2	1	1	\$25.00	\$15.00	\$4,160

Estimated Annual Labor Costs

\$4,160

Electricity Usage Costs (Design Year)

Component	HP	Quantity	Total HP	Watts	Hours/day	kW-hrs/year
Pumps	2.0	1	2	1,491	8	4,355
Liquid Odor Control	0	0	0	0	12	0
					kW-hrs/year =	4,355
					\$/kW-hrs =	\$0.09

Estimated Additional Annual Electricity Usage Costs (Design Year, Not Adjusted For Inflation)

\$392

TOTAL

\$8,799

**BOONE COUNTY REGIONAL SEWER DISTRICT
BROWN STATION BOOSTER PUMP STATION
OPERATIONS AND MAINTENANCE COST ESTIMATE
10/06/20**

Replacement Costs

Inflation Rate	3%	Assumed
Interest Rate	4%	Assumed

Today's Replacement Costs

Item	5 YR - 10%	10 YR - 25%	15 YR - 10%	20 YR - 50%	Original Cost
Pumps	\$6,000	\$10,000	\$6,000	\$20,000	\$40,000
Liquid Odor Control	\$8,000	\$2,500	\$8,000	\$5,000	\$10,000
Portable Standby Generator	\$7,200	\$0	\$7,200	\$0	\$0
Total	\$21,200	\$12,500	\$21,200	\$25,000	

Future Replacement Costs

(Adjusted w/ Inflation)	Present Value	5 YR	10 YR	15 YR	20 YR
5 Year Equipment Cycle	\$21,200	\$24,577			
10 Year Equipment Cycle	\$12,500		\$16,799		
15 Year Equipment Cycle	\$21,200			\$33,029	
20 Year Equipment Cycle	\$25,000				\$45,153
Total	\$79,900	\$24,577	\$16,799	\$33,029	\$45,153

Replacement Acct. Deposit

(Includes Interest)	Required	5 YR	10 YR	15 YR	20 YR
Annual Factor	Annual Deposit	\$24,577	\$16,799	\$33,029	\$45,153
SFF - 5 yrs	0.1846	\$4,538	\$24,577	\$24,577	\$24,577
SFF - 10 yrs	0.0833	(\$648)		(\$7,778)	(\$3,509)
SFF - 15 yrs	0.0499	\$597		\$11,961	\$3,235
SFF - 20 yrs	0.0336	\$700			\$20,849
Total			\$24,577	\$16,799	\$33,029

Estimated Annual Replacement Costs

Deposit \$5,187

Chemical Costs

Component	Gallons Per Day	Gallons Per Year	Cost Per Gallon	Cost
Bioxide (Future)	5	1,800	\$3.00	\$5,400

Estimated Annual Chemical Costs

\$5,400

Labor Costs

Component	Days Per Week	Hours Per Day	Personnel	Rate	Overhead / Fringe	Cost
Lift Stations Week Day Staff (Operator)	2	1	1	\$25.00	\$15.00	\$4,160

Estimated Annual Labor Costs

\$4,160

Electricity Usage Costs (Design Year)

Component	HP	Quantity	Total HP	Watts	Hours/day	kW-hrs/year
Pumps	15.0	1	15	11,185	12	48,992
Liquid Odor Control	1	1	1	746	12	3,266
					kW-hrs/year =	52,259
					\$/kW-hrs =	\$0.09

Estimated Additional Annual Electricity Usage Costs (Design Year, Not Adjusted For Inflation)

\$4,703

TOTAL

\$19,450

APPENDIX H
2019 USER RATE STUDY
SANITARY SEWER USE REGULATIONS

2019 USER RATE STUDY

**BOONE COUNTY REGIONAL SEWER DISTRICT
BOONE COUNTY, MO
ASSUMPTIONS FOR RATE STUDY**

**Prepared by Stephen M. Connelly, CPA, PC
July 31, 2019**

1 CUSTOMERS

We assume an annual growth rate of customers at 0.5%, plus any additional customer acquisitions. Our customer base is billed customers from the billing report.

2 USAGE

We used a calculated 5 year average monthly usage from the billing reports as our base. This generally reflects less average usage as more conservation is realized and usage is trending downward over time.

3 RATES

Rates are derived based on the necessary levels to meet the state mandated 1.10 debt service coverage ratio, cash requirements and other various assumptions regarding expenses.

4 DEBT

Debt is a function of the Capital Improvement Plan funding list for projects related to the recent MDNR Cost Analysis for Compliance. Additional capital purchases are factored into the fixed asset schedule as required. Debt is also fully recognized on the financial statements in the year of draw down.

Successful bond issue election of \$31mm is assumed in 2021.
If the bond issues were to fail, projects would be paid for from current cash which would dramatically increase rates.

5 INCOME STATEMENT ITEMS

Items on the income statement are evaluated on an individual basis, based on known data. Absent specific additional information, expenses are assumed to increase at the historical inflation rate from 1914-2018 of 3.23%.

We assume a 4% annual increase in wholesale treatment expense which is nearly 1/3 of the annual operating budget. However, this line-item is highly variable and dependent on the City of Columbia, (City) their costs, and the resultant rates they charge. The City is currently negotiating an integrated management plan with MDNR which could result in higher annual increases than 4 per cent. Higher cost increases would necessarily result in higher rates charged by the District.

In 2019 and going forward, personnel expense assumes various retirements, replacements, etc. An additional full time administrative support position is added in 2021. The timing of these changes are reflected in the income statements.