



- Protect the environment and reduce greenhouse gases 3
- I like using new technologies 4
- It was free 5
- Other, specify 6
- Don't know 98 [SINGLE

SELECTION]

- 3. When you received the display, did you expect to save money on your electric bill?
 - Yes 1 [CONTINUE TO Q4]
 - No 2 [SKIP TO Q5]
 - (DO NOT READ) Don't know 98 [SKIP TO Q5]
 - (DO NOT READ) Refused 99 [SKIP TO Q5]

[IF Q3=1, CONTINUE. OTHERWISE, SKIP TO Q5]

- 4. On average, how much money did you expect to save on your electricity bill each month? (USE 98 FOR DON'T KNOW AND 99 FOR REFUSED.)

_____ [ENTER WHOLE DOLLAR AMOUNTS]

- 5. Have you noticed a decrease in your electric bill since you began using the display?
 - Yes 1 [CONTINUE TO Q6]
 - No 2 [SKIP TO Q7]
 - Too soon to tell 3 [SKIP TO Q7]
 - (DO NOT READ) Don't Know 98 [SKIP TO Q7]
 - (DO NOT READ) Refused 99 [SKIP TO Q7]

[IF Q5=2,3, 98 or 99, SKIP TO Q7. OTHERWISE, CONTINUE.]

- 6. How much has your monthly bill decreased? (USE 98 FOR DON'T KNOW AND 99 FOR REFUSED. CLARIFY IF NEEDED, DECREASE IS AVERAGE DECREASE IN A MONTH)

_____ [ENTER WHOLE DOLLAR AMOUNTS]

- 7. Since you began using your display, do you feel you have more, less, or the same amount of control over your energy use?

- More control 1
- Less control 2



The same amount of control 3
 (DO NOT READ) Don't Know 98

8. How comfortable are you in using your display to see all the information that is available on it? Do you ... (READ LIST)?
- Feel very comfortable 1
 - Feel somewhat comfortable 2
 - Don't feel comfortable 3
 - (DO NOT READ) Don't know 98

Now I would like you to rate the usefulness of some MySmart Display features. For each feature, please tell me if you find the feature Very Useful, Somewhat Useful, or Not Very Useful.

[RANDOMIZE LIST]

How would you rate the usefulness of the [INSERT FEATURE] feature? Would you say it is ... (READ LIST)

	Very Useful	Somewhat Useful	Not Very Useful	(DO NOT READ) Don't Know
9) Daily cost	3	2	1	98
10) Daily consumption	3	2	1	98
11) Alerts	3	2	1	98
12) Billing detail	3	2	1	98
13) Estimated bill	3	2	1	98

14. How would you rate the accuracy of the display's estimated bill amount? Would you say it is ... (READ LIST)?
- Very accurate 4
 - Somewhat accurate 3
 - Somewhat inaccurate 2
 - Very inaccurate 1
 - (DO NOT READ) Don't know 98
 - (DO NOT READ) Refused 99
15. How much do you think you know about being energy efficient in your home? Would you say you... (READ LIST. ACCEPT ONE)?
- don't know much about being energy efficient in your home 1



know a little bit about being energy efficient in your home 2
 know quite a lot about being energy efficient in your home 3
 know everything you need to know about being energy
 efficient in your home 4
 (DO NOT READ) Don't know 98

16. Since you began using the MySmart display, what **additional** steps have you taken to reduce your electricity use? (DO NOT READ LIST. ACCEPT MULTIPLE RESPONSES.)

Turn air conditioning down 1
 Turn air conditioning down when I leave home 2
 Turn air conditioning off 3
 Turn lights off 4
 Turn TV(s) off 5
 Turn computer off 6
 Turn printer off 7
 Unplug chargers for phones and other devices 8
 Shut down or "sleep" option for electronics when not in use 9
 Don't run electric dryer 10
 Don't wash clothes 11
 Line dry washed clothing 12
 Lower water heater temperature 13
 Use only warm (or cold) water for washing clothes 14
 Don't cook on electric stove/oven 15
 Had my home weatherized 16
 Other, specify 17
 Don't know 98[SINGLE
SELECTION]
 None 18[SINGLE
SELECTION]

17. When you first signed up to receive the display, did you have any concerns about your participation in the program? (DO NOT READ LIST. ACCEPT MULTIPLE RESPONSES.)

I don't/didn't have any concerns 1 [SINGLE
SELECTION]
 It will/would be hard to understand 2
 It will/would requires too much time to operate 3
 It will/would be difficult to use 4
 My utility bill will/would go up 5
 I will/would not realize any benefits from participating 6
 The utility will/would have too much information about my
 personal information or habits 7



- The utility will/could share information about my personal information or habits..... 8
- Other, specify..... 9
- Don't know 98 [SINGLE]

SELECTION]

[FOR Q17=10, RECODE TO Q17=1]

18. Based on your original expectations, how satisfied are you with the display so far? Are you... (READ LIST. SELECT ONE)?
- Completely satisfied..... 5
 - Somewhat satisfied..... 4
 - Neither satisfied nor dissatisfied..... 3
 - Somewhat dissatisfied..... 2
 - Completely dissatisfied..... 1
 - (DO NOT READ) Refused..... 99
 - (DO NOT READ) Don't know..... 98

[IF Q18 = 1 or 2, CONTINUE TO 18B, OTHERWISE SKIP TO Q19]

18B. Why are you dissatisfied with the display? **[RECORD VERBATIM]**

19. Based on your experience with the MySmart Display so far, would you say your satisfaction with KCP&L has... (READ LIST)?
- Increased..... 1
 - Stayed the same..... 2
 - Decreased..... 3
 - (DO NOT READ) Don't know..... 98
 - (DO NOT READ) Refused..... 99

TOU (TIME OF USE) QUESTIONS

20. Are you on KCP&L's Time of Use rate plan? (INTERVIEWER: IF RESPONDENT ASKS WHAT THE TIME OF USE RATE PLAN IS, USE THIS PAT RESPONSE: "THE TIME OF USE RATE PLAN OFFERS LOWER COST ENERGY RATES DURING OFF-PEAK HOURS DURING THE MONTHS OF MAY TO SEPTEMBER.")
- Yes..... 1
 - No..... 2 [SKIP TO Q26]
 - Don't know..... 98 [SKIP TO Q26]
 - Refused..... 99 [SKIP TO Q26]

[IF Q20=1, CONTINUE. OTHERWISE, SKIP TO Q26]



TIME INTRO. Now I would like you to think about changes in your electric usage since joining the Time of Use rate plan. For each time period I read, please tell me if you are using less electricity during this period, there is no change, or you are using more electricity during this period.

From the hours of [INSERT TIME PERIOD], would you say ...?

	You are using LESS electricity during this time period	There is NO CHANGE in your electric usage during this time period	You are using MORE electricity during this time period	(DO NOT READ) Don't Know
21) 7am to 11am	3	2	1	98
22) 11am to 3pm	3	2	1	98
23) 3pm to 7pm	3	2	1	98
24) 7pm to 11pm	3	2	1	98

25. Based on your original expectations, how satisfied are you with the Time of Use rate plan so far? Are you... (READ LIST. SELECT ONE)?
- Completely satisfied 5
 - Somewhat satisfied 4
 - Neither satisfied nor dissatisfied 3
 - Somewhat dissatisfied 2
 - Completely dissatisfied 1
 - (DO NOT READ) Refused 99
 - (DO NOT READ) Don't know 98

PORTAL QUESTIONS

26. Do you have an ID and password that allows you to view your electric usage through KCP&L's MySmart Portal? (INTERVIEWER: IF RESPONDENT ASKS WHAT THE MY SMART PORTAL IS, USE THIS PAT RESPONSE: "MYSMART PORTAL IS AN ONLINE FEATURE ACCESSED FROM THE KCP&L PAYMENT WEBSITE. WITH MYSMART PORTAL, YOU CAN VIEW YOUR ESTIMATED MONTHLY BILL, SET ENERGY SAVINGS GOALS, GET ENERGY SAVING TIPS, AND COMPARE YOUR ENERGY USAGE COMPARED TO OTHER HOMES IN YOUR COMMUNITY.")
- Yes 1
 - No 2 [SKIP TO Q37]
 - Don't know 98 [SKIP TO Q37]
 - Refused 99 [SKIP TO Q37]



27. How often have you looked at the MySmart Portal in the last month? (DO NOT READ LIST. ACCEPT SINGLE RESPONSE.)

- Just once 1
- Two to five times..... 2
- Six to 15 times..... 3
- 16 times or more..... 4
- Zero/None 5
- Don't know 98 [SKIP TO Q37]
- Refused 99 [SKIP TO Q37]

[IF Q27=5, CONTINUE. IF Q27=1-4, SKIP TO Q28. IF Q27=98 OR 99, SKIP TO Q37]

27a. Have you ever used the MySmart Portal?

- Yes 1
- No..... 2 [SKIP TO Q37]

28. What actions do you typically take when you use the portal?

[RECORD VERBATIM]

FEATURE INTRO. Now I would like you to rate the usefulness of some MySmart Portal features. For each feature, please tell me if you think it is Very Useful, Somewhat Useful, or Not Very Useful.

[RANDOMIZE LIST]

For the feature [INSERT FEATURE], would you say it is very useful, somewhat useful, or not very useful?

	Very Useful	Somewhat Useful	Not Very Useful	(DO NOT READ) Don't Know
29) Energy-Saving Tips	3	2	1	98
30) Energy Expert	3	2	1	98
31) Set an energy savings goal	3	2	1	98
32) Bill estimate	3	2	1	98
33) Amount of bill to date	3	2	1	98
34) Hourly energy usage charts	3	2	1	98



35) MySmart Portal in general	3	2	1	98
-------------------------------	---	---	---	----

36. Based on your original expectations, how satisfied are you with the MySmart Portal so far? Are you... (READ LIST. SELECT ONE)?

- Completely satisfied 5
- Somewhat satisfied 4
- Neither satisfied nor dissatisfied 3
- Somewhat dissatisfied 2
- Completely dissatisfied 1
- (DO NOT READ) Refused 99
- (DO NOT READ) Don't know 98

[IF Q36 = 1 or 2, CONTINUE, OTHERWISE SKIP TO Q37]

36B. Why are you dissatisfied with the MySmart Portal?
[RECORD VERBATIM]

SMARTGRID PROJECT

In addition to introducing new technologies to the SmartGrid demonstration area, KCP&L has partnered with local businesses and organizations to help with economic development. In doing so, KCP&L has been able to hire project leads and installers that live and work within the local community. KCP&L also opened a dedicated SmartGrid office at 4600 Paseo that allows customers to pick-up SmartGrid products and get additional information from a live person. This is all part of KCP&L's commitment to the SmartGrid demonstration project and its customers in this area.

37. How aware were you of KCP&L's involvement in the SmartGrid project that I just described? Were you... (READ LIST. SELECT ONE)?

- Completely aware 5
- Somewhat aware 4
- Neither aware nor unaware 3
- Somewhat unaware 2
- Completely unaware 1
- (DO NOT READ) Refused 99
- (DO NOT READ) Don't know 98

38. How important is it to you that KCP&L provides these additional benefits to the customers in the SmartGrid demonstration area? Is it... (READ LIST. SELECT ONE)?

- Extremely important 5
- Somewhat important 4
- Neither important nor unimportant 3
- Somewhat unimportant 2
- Extremely unimportant 1
- (DO NOT READ) Refused 99



(DO NOT READ) Don't know 98

39. Based on your participation in KCP&L's SmartGrid program so far, how satisfied are you with KCP&L? Are you... (READ LIST. SELECT ONE)?

- Completely satisfied 5
- Somewhat satisfied 4
- Neither satisfied nor dissatisfied 3
- Somewhat dissatisfied 2
- Completely dissatisfied 1
- (DO NOT READ) Refused 99
- (DO NOT READ) Don't know 98

40. Do you have any suggestions on ways that KCP&L could improve the program?
[RECORD VERBATIM]
[PROGRAMMER: ALLOW A NO COMMENT CHECK BOX.]

41. Do you have any other comments on the program as you've experienced it so far?
[RECORD VERBATIM]
[PROGRAMMER: ALLOW A NO COMMENT CHECK BOX.]

42. What is the highest level of education completed by any head of household in the home? (DO NOT READ LIST. SELECT ONE)

- Elementary (grades 1-8) 6
- Some high school (grades 9-12) 5
- High school graduate 4
- Some college/trade/vocational school 3
- College graduate 2
- Postgraduate college 1
- (DO NOT READ) Don't know 98
- (DO NOT READ) Refused 99

43. Please stop me when I read your age range. Are you...(READ LIST)?

- Under 21 years old 1
- 21 - 29 2
- 30 - 39 3
- 40 - 49 4
- 50 - 64 5
- 65 years old or older 6
- Don't Know (DO NOT READ) 98
- Refused (DO NOT READ) 99

44. (RECORD GENDER. VERIFY, IF NECESSARY.)

- Male 1



Female 2
 Refused 3

45. What kind of home do you live in? [READ LIST. ACCEPT SINGLE RESPONSE]

Single-family home 1
 Single family attached, such as a townhouse 2
 Multi-family home, such as a duplex, apartment, or condo 3
 Mobile home 4
 Other (Specify) 5
 Don't Know (DO NOT READ)..... 98
 Refused (DO NOT READ)..... 99

46. Do you own or rent your residence?

Own 1
 Rent 2
 Other (Specify) 3
 Don't Know 98
 Refused 99

CLOSING: These are all of the questions I have for you today. Thank you very much for your time.

This page intentionally blank.

Appendix S Build Metrics

S.1	Baseline 2010	S-2
S.2	Baseline 2011	S-13
S.3	Baseline 2012	S-24
S.4	Baseline 2013	S-35
S.5	Baseline 2014	S-46
S.6	2011 Q3	S-57
S.7	2011 Q4	S-69
S.8	2012 Q1	S-81
S.9	2012 Q2	S-93
S.10	2012 Q3	S-105
S.11	2012 Q4	S-117
S.12	2013 Q1	S-129
S.13	2013 Q2	S-141
S.14	2013 Q3	S-153
S.15	2013 Q4	S-165
S.16	2014 Q1	S-177
S.17	2014 Q2	S-189
S.18	2014 Q3	S-201
S.19	2014 Q4	S-213

S.1 Baseline 2010



Project	DE-OE000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2010	
Period	Start: Jan 1, 2010	End: Dec 31, 2010	Submission Due Date: October 31, 2011

AMI Assets - Build Metrics Baseline

All data should be cumulative. All data reported should be at the project level i.e. it should not include assets that were installed prior to the SGDP project, it should only include assets that would have been installed had the SGDP award not been granted.

AMI End Points Installed	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
End Points (meters) forecasted to be installed and operational	#	0	0	0	0
Portion of customers with AMI residential	#	0	0	0	0
Portion of customers with AMI commercial	#	0	0	0	0
Portion of customers with AMI industrial	#	0	0	0	0

Implemented Meter Features	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Reading interval for residential meters	minutes	0	0	0	0
Reading interval for commercial meters	minutes	0	0	0	0
Reading interval for industrial meters	minutes	0	0	0	0
Remote Connect/Disconnect: is feature implemented? (estimated time frame when feature is operational)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Remote Connect/Disconnect: forecasted number of meters with feature	#	0	0	0	0
Outage Reporting: is feature implemented? (estimated time frame when feature is operational)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Outage Reporting: forecasted number of meters with feature implemented	#	0	0	0	0
Power Quality Measurement: is feature implemented? (estimated time frame when feature is operational)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Power Quality Measurement: forecasted number of meters with feature	#	0	0	0	0
Tamper Detection: is feature implemented? (estimated time frame when feature is operational)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Tamper Detection: forecasted number of meters with feature implemented	#	0	0	0	0
Other feature implemented: <input style="width: 100px;" type="text"/>	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other feature: forecasted number of meters with feature implemented	#	0	0	0	0
Other feature implemented: <input style="width: 100px;" type="text"/>	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other feature: forecasted number of meters with feature implemented	#	0	0	0	0

Page 1 of 21 Custom Created: October 4, 2011

Master Updated: April 8, 2011
Schema Version: 1.3



Project	DE-OE000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2010	
Period	Start: Jan 1, 2010	End: Dec 31, 2010	Submission Due Date: October 31, 2011

Implemented Meter Features	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Other feature implemented: <input style="width: 100px;" type="text"/>	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other feature: forecasted number of meters with feature implemented	#	0	0	0	0

Implemented Enterprise Integration	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Billing System: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Customer Information System: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Outage Management System: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Distribution Management System: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other Enterprise Systems: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

AMI System Descriptions

Please enter the information only once for project and specify the year and quarter that the metric is first planned to be installed and operational. Please report the Quarter this equipment is first planned to become operational.

Backhaul Network	
Meter Communication	
Headend System	

Page 2 of 21 Custom Created: October 4, 2011

Master Updated: April 8, 2011
Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2010	
Period	Start: Jan 1, 2010	End: Dec 31, 2010	Submission Due Date: October 31, 2011

AMI System Descriptions

Meter Data Management System	
Meter Data Analysis	
Other Meter Feature	
Other Meter Feature	
Other Meter Feature	

Page 3 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2010	
Period	Start: Jan 1, 2010	End: Dec 31, 2010	Submission Due Date: October 31, 2011

AMI Enterprise Integration Descriptions

Please enter the information only once for project and specify the year and quarter that the metric is first planned to be installed and operational. Please report the Quarter this equipment is first planned to become operational.

Billing System	
Customer Information System	
Outage Management System	
Distribution Management System	
Other Enterprise System	
Additional Project Descriptions	

Page 4 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2010	
Period	Start: Jan 1, 2010	End: Dec 31, 2010	Submission Due Date: October 31, 2011

Customer Systems Assets - Build Metrics Baseline

All data should be cumulative. All data reported should be at the project level (i.e. it should not include assets that were installed prior to the SGDP project, it should only include assets that would have been installed had the SGDP award not been granted).

Implemented Customer Systems	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
In-Home display: forecasted devices installed	#	0	0	0	0
Direct load control devices: forecasted devices installed	#	0.0	0.0	0.0	0.0
Programmable communicating thermostats: forecasted devices installed	#	0	0	0	0
Smart appliances: forecasted devices installed	#	0	0	0	0
Energy management devices/systems: forecasted devices installed	#	0.0	0.0	0.0	0.0
Other devices installed	#				
Other devices installed	#				
Other devices installed	#				

Web Portal	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Web portal: Is portal in production?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Forecasted number of customers with access	#				
Forecasted number of customers with active accounts	#				

Customer Device Descriptions

Please enter the information only once for project and specify the year and quarter that the metric is first planned to be installed and operational. Please report the Quarter this equipment is first planned to become operational.

In-Home Displays

Page 5 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2010	
Period	Start: Jan 1, 2010	End: Dec 31, 2010	Submission Due Date: October 31, 2011

Customer Device Descriptions

Direct Load Control Devices	
Programmable Communicating Thermostats	
Smart Appliances	
Energy Mgmt Systems	
Web Portal	
Home Area Network	

Page 6 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2010	
Period	Start: Jan 1, 2010	End: Dec 31, 2010	Submission Due Date: October 31, 2011

Customer Device Descriptions

Other Device	
Other Device	
Other Device	
Additional Project Descriptions	

Page 7 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2010	
Period	Start: Jan 1, 2010	End: Dec 31, 2010	Submission Due Date: October 31, 2011

Pricing Programs - Build Metrics Baseline

All data should be cumulative. All data reported should be at the project level i.e. it should not include assets that were installed prior to the SGDP project, it should only include assets that would have been installed had the SGDP award not been granted.

Implemented Rate Plans	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Flat Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate: forecasted number of customers with access	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Flat Rate: forecasted number of customers enrolled	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Flat Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Critical Peak Pricing: forecasted number of customers with access	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Flat Rate with Critical Peak Pricing: forecasted number of customers enrolled	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Flat Rate with Peak-Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Peak-Time Rebate: forecasted number of customers with access	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Flat Rate with Peak-Time Rebate: forecasted number of customers enrolled	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Tiered Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate: forecasted number of customers with access	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Tiered Rate: forecasted number of customers enrolled	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Tiered Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Critical Peak Pricing: forecasted number of customers with access	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Tiered Rate with Critical Peak Pricing: forecasted number of customers enrolled	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Tiered Rate with Peak-Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Peak-Time Rebate: forecasted number of customers with access	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Tiered Rate with Peak-Time Rebate: forecasted number of customers enrolled	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Time of Use Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Page 8 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2010	
Period	Start: Jan 1, 2010	End: Dec 31, 2010	Submission Due Date: October 31, 2011

Implemented Rate Plans	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Time of Use Rate: forecasted number of customers with access	#				
Time of Use Rate: forecasted number of customers enrolled	#				
Time of Use Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Time of Use Rate with Critical Peak Pricing: forecasted number of customers with access	#				
Time of Use Rate with Critical Peak Pricing: forecasted number of customers enrolled	#				
Time of Use Rate with Peak-Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Time of Use Rate with Peak-Time Rebate: forecasted number of customers with access	#				
Time of Use Rate with Peak-Time Rebate: forecasted number of customers enrolled	#				
Real-time Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Real-time Pricing: forecasted number of customers with access	#				
Real-time Pricing: forecasted number of customers enrolled	#				
Real-time Pricing with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Real-time Pricing with Critical Peak Pricing: forecasted number of customers with access	#				
Real-time Pricing with Critical Peak Pricing: forecasted number of customers enrolled	#				
Real-time Pricing with Peak-Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Real-time Pricing with Peak-Time Rebate: forecasted number of customers with access	#				
Real-time Pricing with Peak-Time Rebate: forecasted number of customers enrolled	#				
Variable Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Variable Peak Pricing: forecasted number of customers with access	#				
Variable Peak Pricing: forecasted number of customers enrolled	#				
Pre-pay Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Pre-pay Pricing: forecasted number of customers with access	#				
Pre-pay Pricing: forecasted number of customers enrolled	#				

Page 9 of 21 Custom Created: October 4, 2011

Master Updated: April 8, 2011
Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2010	
Period	Start: Jan 1, 2010	End: Dec 31, 2010	Submission Due Date: October 31, 2011

Implemented Rate Plans	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Net Metering: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Net Metering: forecasted number of customers with access	#				
Net Metering: forecasted number of customers enrolled	#				
Other program available: <input style="width: 150px;" type="text"/>	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: forecasted number of customers with access	#				
Other programs: forecasted number of customers enrolled	#				
Other program available: <input style="width: 150px;" type="text"/>	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: forecasted number of customers with access	#				
Other programs: forecasted number of customers enrolled	#				
Other program available: <input style="width: 150px;" type="text"/>	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: forecasted number of customers with access	#				
Other programs: forecasted number of customers enrolled	#				
Rate Decoupling: is implemented?	yes/ no	<input type="checkbox"/>			

Rate Plan Descriptions
 Please enter the information only once for project and specify the year and quarter that the metric is first planned to be installed and operational. Please report the Quarter this equipment is first planned to become operational.

Flat Rate	
-----------	--

Page 10 of 21 Custom Created: October 4, 2011

Master Updated: April 8, 2011
Schema Version: 1.3

		Project DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)
Filing	build_baseline	Baseline Build Metrics Report 2010
Period	Start: Jan 1, 2010	End: Dec 31, 2010 Submission Due Date: October 31, 2011

Rate Plan Descriptions	
Flat Rate with Critical Peak Pricing	
Flat Rate with Peak Time Rebate	
Tiered Rate	
Tiered Rate with Critical Peak Pricing	
Tiered Rate with Peak Time Rebate	
Time of Use Rate	

Page 11 of 21 Custom Created: October 4, 2011

Master Updated: April 8, 2011 Schema Version: 1.3

		Project DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)
Filing	build_baseline	Baseline Build Metrics Report 2010
Period	Start: Jan 1, 2010	End: Dec 31, 2010 Submission Due Date: October 31, 2011

Rate Plan Descriptions	
Time of Use Rate with Critical Peak Pricing	
Time of Use Rate with Peak Time Rebate	
Real-Time Rate	
Real-time Rate with Critical Peak Pricing	
Real-time Rate with Peak Time Rebate	
Variable Peak Pricing	

Page 12 of 21 Custom Created: October 4, 2011

Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2010	
Period	Start: Jan 1, 2010	End: Dec 31, 2010	Submission Due Date: October 31, 2011

Rate Plan Descriptions

Pre-paid Rate	
Net Metering Rate	
Other program	
Other program	
Other program	
Additional Program Descriptions:	

Page 13 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2010	
Period	Start: Jan 1, 2010	End: Dec 31, 2010	Submission Due Date: October 31, 2011

Distributed Energy Resources - Build Metrics Baseline

All data should be cumulative. All data reported should be at the project level i.e. it should not include assets that were installed prior to the SGDP project, it should only include assets that would have been installed had the SGDP award not been granted.

Implemented Distributed Energy and Renewable Devices	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Distributed generation: forecasted number of units	#	0	0	0	0
Distributed generation: estimated installed capacity	KW	0.0	0.0	0.0	0.0
Distributed generation: estimated total energy delivered	* kWh	0	0	0	0
Energy storage: forecasted number of units	#	0	0	0	0
Energy storage: estimated installed capacity	KW	0.0	0.0	0.0	0.0
Energy storage: estimated total energy delivered	* kWh	0.0	0.0	0.0	0.0
Plug-in electric vehicles charging points: forecasted number of units	#	0	0	0	0
Plug-in electric vehicles charging points: installed capacity	KW	0.0	0.0	0.0	0.0
Plug-in electric vehicles charging points: estimated total energy delivered	* kWh	0.0	0.0	0.0	0.0
DER/DG interconnection equipment: forecasted number of units	#				

* Energy delivered should be reported just for the quarter being reported, not cumulative for the project to-date.

Project

Distributed Generation Interface Description	
Additional Program Descriptions:	

Page 14 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2010	
Period	Start: Jan 1, 2010	End: Dec 31, 2010	Submission Due Date: October 31, 2011

Electric Distribution System Assets - Build Metrics Baseline

All data should be cumulative. All data reported should be at the project level (i.e. it should not include assets that were installed prior to the SGDP project, it should only include assets that would have been installed had the SGDP award not been granted).

Implemented Distribution Devices		Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Portion of system with SCADA	%		0	0	0	0
Portion of system with Distribution Automation (DA)	%		0	0	0	0
Automated Feeder Switches: forecasted number of devices installed	#		0	0	0	0
Automated Capacitors: forecasted number of devices installed	#		0.0	0.0	0.0	0.0
Automated Regulators: forecasted number of devices installed	#		0	0	0	0
Feeder Monitors: forecasted number of devices installed	#		0	0	0	0
Remote Fault Indicators: forecasted number of devices installed	#		0.0	0.0	0.0	0.0
Transformer Monitors (line): forecasted number of devices installed	#		0	0	0	0
Smart Relays: forecasted number of devices installed	#		0	0	0	0
Fault Current Limiter: forecasted number of devices installed	#		0	0	0	0
Other devices installed:	#					
Other devices installed:	#					
Other devices installed:	#					

DA Applications in Operation		Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Fault Location, Isolation, and Service Restoration (FLISR): is this application in operation?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Voltage Optimization: is this application in operation?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Feeder Peak Load Management: is this application in operation?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Microgrids: is this application in operation?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other DA Application: is this application in operation?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Page 15 of 21 Custom Created: October 4, 2011


Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2010	
Period	Start: Jan 1, 2010	End: Dec 31, 2010	Submission Due Date: October 31, 2011

Implemented Distribution Management Integration

		Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
AMI: is integration complete? (estimated time frame when integration is complete)	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Outage Management System: is integration complete? (estimated time frame when integration is complete)	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Transmission Management System: is integration complete? (estimated time frame when integration is complete)	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Distributed Energy Resources: is integration complete? (estimated time frame when integration is complete)	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other Systems: is integration complete? (estimated time frame when integration is complete)	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Distribution Device Descriptions

Please enter the information only once for project and specify the year and quarter that the metric is first planned to be installed and operational. Please report the Quarter this equipment is first planned to become operational.

SCADA	KCP&L has a transmission level EMS that monitors and controls all urban substations, including the project area which is fed by the Midtown substation. At the Midtown substation, the EMS reaches down to the heads of each circuit.
Portion of system with SCADA	100% of the project area has SCADA.
Portion of system with DA	

Page 16 of 21 Custom Created: October 4, 2011


Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2010	
Period	Start: Jan 1, 2010	End: Dec 31, 2010	Submission Due Date: October 31, 2011

Distribution Device Descriptions

DA devices	
DA communications network	
Other device	
Other device	
Other device	

Page 17 of 21 Custom Created: October 4, 2011

Master Updated: April 8, 2011
Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2010	
Period	Start: Jan 1, 2010	End: Dec 31, 2010	Submission Due Date: October 31, 2011

Distribution Application Descriptions

Please enter the information only once for project and specify the year and quarter that the metric is first planned to be installed and operational. Please report the Quarter this equipment is first planned to become operational.

FLSR	
Voltage Optimization	
Feeder Peak Load Management	
Microgrids	
Other DA Applications	

Page 18 of 21 Custom Created: October 4, 2011

Master Updated: April 8, 2011
Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2010	
Period	Start: Jan 1, 2010	End: Dec 31, 2010	Submission Due Date: October 31, 2011

Distribution Management Integration Descriptions

Please enter the information only once for project and specify the year and quarter that the metric is first planned to be installed and operational. Please report the Quarter this equipment is first planned to become operational.

AMI	
Outage Management	
Transmission Management	
DER Systems	
Distribution Management System	
Other Systems	

Page 19 of 21 Custom Created: October 4, 2011

Master Updated: April 8, 2011
Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2010	
Period	Start: Jan 1, 2010	End: Dec 31, 2010	Submission Due Date: October 31, 2011

Additional Program Descriptions

Page 20 of 21 Custom Created: October 4, 2011

Master Updated: April 8, 2011
Schema Version: 1.3



Project	DE-DE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2010	
Period	Start: Jan 1, 2010	End: Dec 31, 2010	Submission Due Date: October 31, 2011

Page 21 of 21 Custom Created October 4, 2011



Missouri Department of ENERGY Master Updated: April 8, 2011 Schema Version: 1.3

S.2 Baseline 2011



Project	DE-OE000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2011	
Period	Start: Jan 1, 2011	End: Dec 31, 2011	Submission Due Date: October 31, 2011

AMI Assets - Build Metrics Baseline

All data should be cumulative. All data reported should be at the project level i.e. it should not include assets that were installed prior to the SGDP project, it should only include assets that would have been installed had the SGDP award not been granted.

AMI End Points Installed	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
End Points (meters) forecasted to be installed and operational	#	0	0	0	0
Portion of customers with AMI residential	#	0	0	0	0
Portion of customers with AMI commercial	#	0	0	0	0
Portion of customers with AMI industrial	#	0	0	0	0

Implemented Meter Features	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Reading interval for residential meters	minutes	0	0	0	0
Reading interval for commercial meters	minutes	0	0	0	0
Reading interval for industrial meters	minutes	0	0	0	0
Remote Connect/Disconnect: is feature implemented? (estimated time frame when feature is operational)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Remote Connect/Disconnect: forecasted number of meters with feature	#				
Outage Reporting: is feature implemented? (estimated time frame when feature is operational)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Outage Reporting: forecasted number of meters with feature implemented	#				
Power Quality Measurement: is feature implemented? (estimated time frame when feature is operational)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Power Quality Measurement: forecasted number of meters with feature	#				
Tamper Detection: is feature implemented? (estimated time frame when feature is operational)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Tamper Detection: forecasted number of meters with feature implemented	#				
Other feature implemented: <input style="width: 150px;" type="text"/>	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other feature: forecasted number of meters with feature implemented	#				
Other feature implemented: <input style="width: 150px;" type="text"/>	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other feature: forecasted number of meters with feature implemented	#				

Page 1 of 21 Custom Created: October 4, 2011


Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2011	
Period	Start: Jan 1, 2011	End: Dec 31, 2011	Submission Due Date: October 31, 2011

Implemented Meter Features	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Other feature implemented: <input style="width: 150px;" type="text"/>	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other feature: forecasted number of meters with feature implemented	#				

Implemented Enterprise Integration	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Billing System: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Customer Information System: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Outage Management System: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Distribution Management System: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other Enterprise Systems: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

AMI System Descriptions

Please enter the information only once for project and specify the year and quarter that the metric is first planned to be installed and operational. Please report the Quarter this equipment is first planned to become operational.

Backhaul Network	
Meter Communication	
Headend System	

Page 2 of 21 Custom Created: October 4, 2011


Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2011	
Period	Start: Jan 1, 2011	End: Dec 31, 2011	Submission Due Date: October 31, 2011

AMI System Descriptions

Meter Data Management System	
Meter Data Analysis	
Other Meter Feature	
Other Meter Feature	
Other Meter Feature	

Page 3 of 21 Custom Created: October 4, 2011

Master Updated: April 8, 2011
Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2011	
Period	Start: Jan 1, 2011	End: Dec 31, 2011	Submission Due Date: October 31, 2011

AMI Enterprise Integration Descriptions

Please enter the information only once for project and specify the year and quarter that the metric is first planned to be installed and operational. Please report the Quarter this equipment is first planned to become operational.

Billing System	
Customer Information System	
Outage Management System	
Distribution Management System	
Other Enterprise System	
Additional Project Descriptions	

Page 4 of 21 Custom Created: October 4, 2011

Master Updated: April 8, 2011
Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2011	
Period	Start: Jan 1, 2011	End: Dec 31, 2011	Submission Due Date: October 31, 2011

Customer Systems Assets - Build Metrics Baseline

All data should be cumulative. All data reported should be at the project level (i.e. it should not include assets that were installed prior to the SGDP project, it should only include assets that would have been installed had the SGDP award not been granted).

Implemented Customer Systems	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
In-Home display: forecasted devices installed	#	0	0	0	0
Direct load control devices: forecasted devices installed	#	0.0	0.0	0.0	0.0
Programmable communicating thermostats: forecasted devices installed	#	0	0	0	0
Smart appliances: forecasted devices installed	#	0	0	0	0
Energy management devices/systems: forecasted devices installed	#	0.0	0.0	0.0	0.0
Other devices installed	#				
Other devices installed	#				
Other devices installed	#				

Web Portal	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Web portal: Is portal in production?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Forecasted number of customers with access	#				
Forecasted number of customers with active accounts	#				

Customer Device Descriptions

Please enter the information only once for project and specify the year and quarter that the metric is first planned to be installed and operational. Please report the Quarter this equipment is first planned to become operational.

In-Home Displays

Page 5 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2011	
Period	Start: Jan 1, 2011	End: Dec 31, 2011	Submission Due Date: October 31, 2011

Customer Device Descriptions

Direct Load Control Devices	
Programmable Communicating Thermostats	
Smart Appliances	
Energy Mgmt Systems	
Web Portal	
Home Area Network	

Page 6 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE000021 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2011	
Period	Start: Jan 1, 2011	End: Dec 31, 2011	Submission Due Date: October 31, 2011

Customer Device Descriptions

Other Device	
Other Device	
Other Device	
Additional Project Descriptions	

Page 7 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE000021 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2011	
Period	Start: Jan 1, 2011	End: Dec 31, 2011	Submission Due Date: October 31, 2011

Pricing Programs - Build Metrics Baseline

All data should be cumulative. All data reported should be at the project level i.e. it should not include assets that were installed prior to the SGDP project, it should only include assets that would have been installed had the SGDP award not been granted.

Implemented Rate Plans	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Flat Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate: forecasted number of customers with access	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Flat Rate: forecasted number of customers enrolled	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Flat Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Critical Peak Pricing: forecasted number of customers with access	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Flat Rate with Critical Peak Pricing: forecasted number of customers enrolled	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Flat Rate with Peak-Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Peak-Time Rebate: forecasted number of customers with access	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Flat Rate with Peak-Time Rebate: forecasted number of customers enrolled	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Tiered Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate: forecasted number of customers with access	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Tiered Rate: forecasted number of customers enrolled	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Tiered Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Critical Peak Pricing: forecasted number of customers with access	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Tiered Rate with Critical Peak Pricing: forecasted number of customers enrolled	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Tiered Rate with Peak-Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Peak-Time Rebate: forecasted number of customers with access	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Tiered Rate with Peak-Time Rebate: forecasted number of customers enrolled	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Time of Use Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Page 8 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE000021 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2011	
Period	Start: Jan 1, 2011	End: Dec 31, 2011	Submission Due Date: October 31, 2011

Implemented Rate Plans	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Time of Use Rate: forecasted number of customers with access	#				
Time of Use Rate: forecasted number of customers enrolled	#				
Time of Use Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Time of Use Rate with Critical Peak Pricing: forecasted number of customers with access	#				
Time of Use Rate with Critical Peak Pricing: forecasted number of customers enrolled	#				
Time of Use Rate with Peak-Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Time of Use Rate with Peak-Time Rebate: forecasted number of customers with access	#				
Time of Use Rate with Peak-Time Rebate: forecasted number of customers enrolled	#				
Real-time Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Real-time Pricing: forecasted number of customers with access	#				
Real-time Pricing: forecasted number of customers enrolled	#				
Real-time Pricing with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Real-time Pricing with Critical Peak Pricing: forecasted number of customers with access	#				
Real-time Pricing with Critical Peak Pricing: forecasted number of customers enrolled	#				
Real-time Pricing with Peak-Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Real-time Pricing with Peak-Time Rebate: forecasted number of customers with access	#				
Real-time Pricing with Peak-Time Rebate: forecasted number of customers enrolled	#				
Variable Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Variable Peak Pricing: forecasted number of customers with access	#				
Variable Peak Pricing: forecasted number of customers enrolled	#				
Pre-pay Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Pre-pay Pricing: forecasted number of customers with access	#				
Pre-pay Pricing: forecasted number of customers enrolled	#				

Page 9 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE000021 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2011	
Period	Start: Jan 1, 2011	End: Dec 31, 2011	Submission Due Date: October 31, 2011

Implemented Rate Plans	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Net Metering: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Net Metering: forecasted number of customers with access	#				
Net Metering: forecasted number of customers enrolled	#				
Other program available: <input style="width: 150px;" type="text"/>	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: forecasted number of customers with access	#				
Other programs: forecasted number of customers enrolled	#				
Other program available: <input style="width: 150px;" type="text"/>	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: forecasted number of customers with access	#				
Other programs: forecasted number of customers enrolled	#				
Other program available: <input style="width: 150px;" type="text"/>	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: forecasted number of customers with access	#				
Other programs: forecasted number of customers enrolled	#				
Rate Decoupling: is implemented?	yes/ no	<input type="checkbox"/>			

Rate Plan Descriptions

Please enter the information only once for project and specify the year and quarter that the metric is first planned to be installed and operational. Please report the Quarter this equipment is first planned to become operational.

Flat Rate

Page 10 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2011	
Period	Start: Jan 1, 2011	End: Dec 31, 2011	Submission Due Date: October 31, 2011

Rate Plan Descriptions

Flat Rate with Critical Peak Pricing	
Flat Rate with Peak Time Rebate	
Tiered Rate	
Tiered Rate with Critical Peak Pricing	
Tiered Rate with Peak Time Rebate	
Time of Use Rate	

Page 11 of 21 Custom Created: October 4, 2011


Master Updated: April 8, 2011

Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2011	
Period	Start: Jan 1, 2011	End: Dec 31, 2011	Submission Due Date: October 31, 2011

Rate Plan Descriptions

Time of Use Rate with Critical Peak Pricing	
Time of Use Rate with Peak Time Rebate	
Real-Time Rate	
Real-time Rate with Critical Peak Pricing	
Real-time Rate with Peak Time Rebate	
Variable Peak Pricing	

Page 12 of 21 Custom Created: October 4, 2011


Master Updated: April 8, 2011

Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2011	
Period	Start: Jan 1, 2011	End: Dec 31, 2011	Submission Due Date: October 31, 2011

Rate Plan Descriptions

Pre-paid Rate	
Net Metering Rate	
Other program	
Other program	
Other program	
Additional Program Descriptions:	

Page 13 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2011	
Period	Start: Jan 1, 2011	End: Dec 31, 2011	Submission Due Date: October 31, 2011

Distributed Energy Resources - Build Metrics Baseline

All data should be cumulative. All data reported should be at the project level i.e. it should not include assets that were installed prior to the SGDP project, it should only include assets that would have been installed had the SGDP award not been granted.

Implemented Distributed Energy and Renewable Devices	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Distributed generation: forecasted number of units	#	0	0	0	0
Distributed generation: estimated installed capacity	KW	0.0	0.0	0.0	0.0
Distributed generation: estimated total energy delivered	* kWh	0	0	0	0
Energy storage: forecasted number of units	#	0	0	0	0
Energy storage: estimated installed capacity	KW	0.0	0.0	0.0	0.0
Energy storage: estimated total energy delivered	* kWh	0.0	0.0	0.0	0.0
Plug-in electric vehicles charging points: forecasted number of units	#	0	0	0	0
Plug-in electric vehicles charging points: installed capacity	KW	0.0	0.0	0.0	0.0
Plug-in electric vehicles charging points: estimated total energy delivered	* kWh	0.0	0.0	0.0	0.0
DER/DG interconnection equipment: forecasted number of units	#				

* Energy delivered should be reported just for the quarter being reported, not cumulative for the project to-date.

Project

Distributed Generation Interface Description	
Additional Program Descriptions:	

Page 14 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2011	
Period	Start: Jan 1, 2011	End: Dec 31, 2011	Submission Due Date: October 31, 2011

Electric Distribution System Assets - Build Metrics Baseline

All data should be cumulative. All data reported should be at the project level (i.e. it should not include assets that were installed prior to the SGDP project, it should only include assets that would have been installed had the SGDP award not been granted).

Implemented Distribution Devices		Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Portion of system with SCADA	%	0	0	0	0	
Portion of system with Distribution Automation (DA)	%	0	0	0	0	
Automated Feeder Switches: forecasted number of devices installed	#	0	0	0	0	
Automated Capacitors: forecasted number of devices installed	#	0.0	0.0	0.0	0.0	
Automated Regulators: forecasted number of devices installed	#	0	0	0	0	
Feeder Monitors: forecasted number of devices installed	#	0	0	0	0	
Remote Fault Indicators: forecasted number of devices installed	#	0.0	0.0	0.0	0.0	
Transformer Monitors (line): forecasted number of devices installed	#	0	0	0	0	
Smart Relays: forecasted number of devices installed	#	0	0	0	0	
Fault Current Limiter: forecasted number of devices installed	#	0	0	0	0	
Other devices installed:	#					
Other devices installed:	#					
Other devices installed:	#					

DA Applications in Operation		Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Fault Location, Isolation, and Service Restoration (FLISR): is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Voltage Optimization: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Feeder Peak Load Management: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Microgrids: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Other DA Application: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

Page 15 of 21 Custom Created: October 4, 2011


Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2011	
Period	Start: Jan 1, 2011	End: Dec 31, 2011	Submission Due Date: October 31, 2011

Implemented Distribution Management Integration

		Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
AMI: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Outage Management System: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Transmission Management System: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Distributed Energy Resources: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Other Systems: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

Distribution Device Descriptions

Please enter the information only once for project and specify the year and quarter that the metric is first planned to be installed and operational. Please report the Quarter this equipment is first planned to become operational.

SCADA	
Portion of system with SCADA	
Portion of system with DA	

Page 16 of 21 Custom Created: October 4, 2011


Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2011	
Period	Start: Jan 1, 2011	End: Dec 31, 2011	Submission Due Date: October 31, 2011

Distribution Device Descriptions

DA devices	
DA communications network	
Other device	
Other device	
Other device	

Page 17 of 21 Custom Created: October 4, 2011

Master Updated: April 8, 2011
Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2011	
Period	Start: Jan 1, 2011	End: Dec 31, 2011	Submission Due Date: October 31, 2011

Distribution Application Descriptions

Please enter the information only once for project and specify the year and quarter that the metric is first planned to be installed and operational. Please report the Quarter this equipment is first planned to become operational.

FLSR	
Voltage Optimization	
Feeder Peak Load Management	
Microgrids	
Other DA Applications	

Page 18 of 21 Custom Created: October 4, 2011

Master Updated: April 8, 2011
Schema Version: 1.3

 **Project** DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)
Filing build_baseline **Baseline Build Metrics Report 2011**
Period Start: Jan 1, 2011 End: Dec 31, 2011 Submission Due Date: October 31, 2011

Distribution Management Integration Descriptions
Please enter the information only once for project and specify the year and quarter that the metric is first planned to be installed and operational. Please report the Quarter this equipment is first planned to become operational.

AMI	
Outage Management	
Transmission Management	
DER Systems	
Distribution Management System	
Other Systems	

Page 19 of 21 Custom Created: October 4, 2011  Master Updated: April 8, 2011 Schema Version: 1.3

 **Project** DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)
Filing build_baseline **Baseline Build Metrics Report 2011**
Period Start: Jan 1, 2011 End: Dec 31, 2011 Submission Due Date: October 31, 2011

Additional Program Descriptions

--	--

Page 20 of 21 Custom Created: October 4, 2011  Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-DE000021 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2011	
Period	Start: Jan 1, 2011	End: Dec 31, 2011	Submission Due Date: October 31, 2011

Page 21 of 21 Custom Created October 4, 2011

 ENERGY Master Updated: April 8, 2011 Schema Version: 1.3

S.3 Baseline 2012



Project	DE-OE000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2012	
Period	Start: Jan 1, 2012	End: Dec 31, 2012	Submission Due Date: October 31, 2011

AMI Assets - Build Metrics Baseline

All data should be cumulative. All data reported should be at the project level i.e. it should not include assets that were installed prior to the SGDP project, it should only include assets that would have been installed had the SGDP award not been granted.

AMI End Points Installed	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
End Points (meters) forecasted to be installed and operational	#	0	0	0	0
Portion of customers with AMI residential	#	0	0	0	0
Portion of customers with AMI commercial	#	0	0	0	0
Portion of customers with AMI industrial	#	0	0	0	0

Implemented Meter Features	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Reading interval for residential meters	minutes	0	0	0	0
Reading interval for commercial meters	minutes	0	0	0	0
Reading interval for industrial meters	minutes	0	0	0	0
Remote Connect/Disconnect: is feature implemented? (estimated time frame when feature is operational)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Remote Connect/Disconnect: forecasted number of meters with feature	#				
Outage Reporting: is feature implemented? (estimated time frame when feature is operational)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Outage Reporting: forecasted number of meters with feature implemented	#				
Power Quality Measurement: is feature implemented? (estimated time frame when feature is operational)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Power Quality Measurement: forecasted number of meters with feature	#				
Tamper Detection: is feature implemented? (estimated time frame when feature is operational)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Tamper Detection: forecasted number of meters with feature implemented	#				
Other feature implemented: <input style="width: 150px;" type="text"/>	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other feature: forecasted number of meters with feature implemented	#				
Other feature implemented: <input style="width: 150px;" type="text"/>	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other feature: forecasted number of meters with feature implemented	#				

Page 1 of 21 Custom Created: October 4, 2011


Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2012	
Period	Start: Jan 1, 2012	End: Dec 31, 2012	Submission Due Date: October 31, 2011

Implemented Meter Features	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Other feature implemented: <input style="width: 150px;" type="text"/>	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other feature: forecasted number of meters with feature implemented	#				

Implemented Enterprise Integration	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Billing System: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Customer Information System: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Outage Management System: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Distribution Management System: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other Enterprise Systems: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

AMI System Descriptions

Please enter the information only once for project and specify the year and quarter that the metric is first planned to be installed and operational. Please report the Quarter this equipment is first planned to become operational.

Backhaul Network	
Meter Communication	
Headend System	

Page 2 of 21 Custom Created: October 4, 2011


Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2012	
Period	Start: Jan 1, 2012	End: Dec 31, 2012	Submission Due Date: October 31, 2011

AMI System Descriptions

Meter Data Management System	
Meter Data Analysis	
Other Meter Feature	
Other Meter Feature	
Other Meter Feature	

Page 3 of 21 Custom Created: October 4, 2011

Master Updated: April 8, 2011
Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2012	
Period	Start: Jan 1, 2012	End: Dec 31, 2012	Submission Due Date: October 31, 2011

AMI Enterprise Integration Descriptions

Please enter the information only once for project and specify the year and quarter that the metric is first planned to be installed and operational. Please report the Quarter this equipment is first planned to become operational.

Billing System	
Customer Information System	
Outage Management System	
Distribution Management System	
Other Enterprise System	
Additional Project Descriptions	

Page 4 of 21 Custom Created: October 4, 2011

Master Updated: April 8, 2011
Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2012	
Period	Start: Jan 1, 2012	End: Dec 31, 2012	Submission Due Date: October 31, 2011

Customer Systems Assets - Build Metrics Baseline

All data should be cumulative. All data reported should be at the project level (i.e. it should not include assets that were installed prior to the SGDP project, it should only include assets that would have been installed had the SGDP award not been granted).

Implemented Customer Systems	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
In-Home display: forecasted devices installed	#	0	0	0	0
Direct load control devices: forecasted devices installed	#	0.0	0.0	0.0	0.0
Programmable communicating thermostats: forecasted devices installed	#	0	0	0	0
Smart appliances: forecasted devices installed	#	0	0	0	0
Energy management devices/systems: forecasted devices installed	#	0.0	0.0	0.0	0.0
Other devices installed	#				
Other devices installed	#				
Other devices installed	#				

Web Portal	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Web portal: Is portal in production?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Forecasted number of customers with access	#				
Forecasted number of customers with active accounts	#				

Customer Device Descriptions

Please enter the information only once for project and specify the year and quarter that the metric is first planned to be installed and operational. Please report the Quarter this equipment is first planned to become operational.

In-Home Displays

Page 5 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2012	
Period	Start: Jan 1, 2012	End: Dec 31, 2012	Submission Due Date: October 31, 2011

Customer Device Descriptions

Direct Load Control Devices	
Programmable Communicating Thermostats	
Smart Appliances	
Energy Mgmt Systems	
Web Portal	
Home Area Network	

Page 6 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2012	
Period	Start: Jan 1, 2012	End: Dec 31, 2012	Submission Due Date: October 31, 2011

Customer Device Descriptions

Other Device	
Other Device	
Other Device	
Additional Project Descriptions	

Page 7 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2012	
Period	Start: Jan 1, 2012	End: Dec 31, 2012	Submission Due Date: October 31, 2011

Pricing Programs - Build Metrics Baseline

All data should be cumulative. All data reported should be at the project level i.e. it should not include assets that were installed prior to the SGDP project, it should only include assets that would have been installed had the SGDP award not been granted.

Implemented Rate Plans	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Flat Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate: forecasted number of customers with access	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Flat Rate: forecasted number of customers enrolled	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Flat Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Critical Peak Pricing: forecasted number of customers with access	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Flat Rate with Critical Peak Pricing: forecasted number of customers enrolled	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Flat Rate with Peak-Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Peak-Time Rebate: forecasted number of customers with access	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Flat Rate with Peak-Time Rebate: forecasted number of customers enrolled	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Tiered Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate: forecasted number of customers with access	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Tiered Rate: forecasted number of customers enrolled	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Tiered Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Critical Peak Pricing: forecasted number of customers with access	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Tiered Rate with Critical Peak Pricing: forecasted number of customers enrolled	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Tiered Rate with Peak-Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Peak-Time Rebate: forecasted number of customers with access	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Tiered Rate with Peak-Time Rebate: forecasted number of customers enrolled	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Time of Use Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Page 8 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2012	
Period	Start: Jan 1, 2012	End: Dec 31, 2012	Submission Due Date: October 31, 2011

Implemented Rate Plans	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Time of Use Rate: forecasted number of customers with access	#				
Time of Use Rate: forecasted number of customers enrolled	#				
Time of Use Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Time of Use Rate with Critical Peak Pricing: forecasted number of customers with access	#				
Time of Use Rate with Critical Peak Pricing: forecasted number of customers enrolled	#				
Time of Use Rate with Peak-Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Time of Use Rate with Peak-Time Rebate: forecasted number of customers with access	#				
Time of Use Rate with Peak-Time Rebate: forecasted number of customers enrolled	#				
Real-time Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Real-time Pricing: forecasted number of customers with access	#				
Real-time Pricing: forecasted number of customers enrolled	#				
Real-time Pricing with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Real-time Pricing with Critical Peak Pricing: forecasted number of customers with access	#				
Real-time Pricing with Critical Peak Pricing: forecasted number of customers enrolled	#				
Real-time Pricing with Peak-Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Real-time Pricing with Peak-Time Rebate: forecasted number of customers with access	#				
Real-time Pricing with Peak-Time Rebate: forecasted number of customers enrolled	#				
Variable Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Variable Peak Pricing: forecasted number of customers with access	#				
Variable Peak Pricing: forecasted number of customers enrolled	#				
Pre-pay Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Pre-pay Pricing: forecasted number of customers with access	#				
Pre-pay Pricing: forecasted number of customers enrolled	#				

Page 9 of 21 Custom Created: October 4, 2011

Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2012	
Period	Start: Jan 1, 2012	End: Dec 31, 2012	Submission Due Date: October 31, 2011

Implemented Rate Plans	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Net Metering: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Net Metering: forecasted number of customers with access	#				
Net Metering: forecasted number of customers enrolled	#				
Other program available: <input style="width: 150px;" type="text"/>	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: forecasted number of customers with access	#				
Other programs: forecasted number of customers enrolled	#				
Other program available: <input style="width: 150px;" type="text"/>	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: forecasted number of customers with access	#				
Other programs: forecasted number of customers enrolled	#				
Other program available: <input style="width: 150px;" type="text"/>	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: forecasted number of customers with access	#				
Other programs: forecasted number of customers enrolled	#				
Rate Decoupling: is implemented?	yes/ no	<input type="checkbox"/>			

Rate Plan Descriptions

Please enter the information only once for project and specify the year and quarter that the metric is first planned to be installed and operational. Please report the Quarter this equipment is first planned to become operational.

Flat Rate	
-----------	--

Page 10 of 21 Custom Created: October 4, 2011

Master Updated: April 8, 2011 Schema Version: 1.3

		Project DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)
Filing	build_baseline	Baseline Build Metrics Report 2012
Period	Start: Jan 1, 2012	End: Dec 31, 2012 Submission Due Date: October 31, 2011

Rate Plan Descriptions	
Flat Rate with Critical Peak Pricing	
Flat Rate with Peak Time Rebate	
Tiered Rate	
Tiered Rate with Critical Peak Pricing	
Tiered Rate with Peak Time Rebate	
Time of Use Rate	

Page 11 of 21 Custom Created: October 4, 2011

Master Updated: April 8, 2011 Schema Version: 1.3

		Project DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)
Filing	build_baseline	Baseline Build Metrics Report 2012
Period	Start: Jan 1, 2012	End: Dec 31, 2012 Submission Due Date: October 31, 2011

Rate Plan Descriptions	
Time of Use Rate with Critical Peak Pricing	
Time of Use Rate with Peak Time Rebate	
Real-Time Rate	
Real-time Rate with Critical Peak Pricing	
Real-time Rate with Peak Time Rebate	
Variable Peak Pricing	

Page 12 of 21 Custom Created: October 4, 2011

Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2012	
Period	Start: Jan 1, 2012	End: Dec 31, 2012	Submission Due Date: October 31, 2011

Rate Plan Descriptions

Pre-paid Rate	
Net Metering Rate	
Other program	
Other program	
Other program	
Additional Program Descriptions:	

Page 13 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2012	
Period	Start: Jan 1, 2012	End: Dec 31, 2012	Submission Due Date: October 31, 2011

Distributed Energy Resources - Build Metrics Baseline

All data should be cumulative. All data reported should be at the project level i.e. it should not include assets that were installed prior to the SGDP project, it should only include assets that would have been installed had the SGDP award not been granted.

Implemented Distributed Energy and Renewable Devices	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Distributed generation: forecasted number of units	#	0	0	0	0
Distributed generation: estimated installed capacity	KW	0.0	0.0	0.0	0.0
Distributed generation: estimated total energy delivered	* kWh	0	0	0	0
Energy storage: forecasted number of units	#	0	0	0	0
Energy storage: estimated installed capacity	KW	0.0	0.0	0.0	0.0
Energy storage: estimated total energy delivered	* kWh	0.0	0.0	0.0	0.0
Plug-in electric vehicles charging points: forecasted number of units	#	0	0	0	0
Plug-in electric vehicles charging points: installed capacity	KW	0.0	0.0	0.0	0.0
Plug-in electric vehicles charging points: estimated total energy delivered	* kWh	0.0	0.0	0.0	0.0
DER/DG interconnection equipment: forecasted number of units	#				

* Energy delivered should be reported just for the quarter being reported, not cumulative for the project to-date.

Project

Distributed Generation Interface Description	
Additional Program Descriptions:	

Page 14 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2012	
Period	Start: Jan 1, 2012	End: Dec 31, 2012	Submission Due Date: October 31, 2011

Electric Distribution System Assets - Build Metrics Baseline

All data should be cumulative. All data reported should be at the project level (i.e. it should not include assets that were installed prior to the SGDP project, it should only include assets that would have been installed had the SGDP award not been granted).

Implemented Distribution Devices	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Portion of system with SCADA	%	0	0	0	0
Portion of system with Distribution Automation (DA)	%	0	0	0	0
Automated Feeder Switches: forecasted number of devices installed	#	0	0	0	0
Automated Capacitors: forecasted number of devices installed	#	0.0	0.0	0.0	0.0
Automated Regulators: forecasted number of devices installed	#	0	0	0	0
Feeder Monitors: forecasted number of devices installed	#	0	0	0	0
Remote Fault Indicators: forecasted number of devices installed	#	0.0	0.0	0.0	0.0
Transformer Monitors (line): forecasted number of devices installed	#	0	0	0	0
Smart Relays: forecasted number of devices installed	#	0	0	0	0
Fault Current Limiter: forecasted number of devices installed	#	0	0	0	0
Other devices installed:	#				
Other devices installed:	#				
Other devices installed:	#				

DA Applications in Operation	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Fault Location, Isolation, and Service Restoration (FLISR): is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Voltage Optimization: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Feeder Peak Load Management: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Microgrids: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other DA Application: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Page 15 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2012	
Period	Start: Jan 1, 2012	End: Dec 31, 2012	Submission Due Date: October 31, 2011

Implemented Distribution Management Integration

Implemented Distribution Management Integration	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
AMI: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Outage Management System: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Transmission Management System: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Distributed Energy Resources: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other Systems: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Distribution Device Descriptions

Please enter the information only once for project and specify the year and quarter that the metric is first planned to be installed and operational. Please report the Quarter this equipment is first planned to become operational.

SCADA	
Portion of system with SCADA	
Portion of system with DA	

Page 16 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2012	
Period	Start: Jan 1, 2012	End: Dec 31, 2012	Submission Due Date: October 31, 2011

Distribution Device Descriptions

DA devices	
DA communications network	
Other device	
Other device	
Other device	

Page 17 of 21 Custom Created: October 4, 2011

Master Updated: April 8, 2011
Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2012	
Period	Start: Jan 1, 2012	End: Dec 31, 2012	Submission Due Date: October 31, 2011

Distribution Application Descriptions

Please enter the information only once for project and specify the year and quarter that the metric is first planned to be installed and operational. Please report the Quarter this equipment is first planned to become operational.

FLSR	
Voltage Optimization	
Feeder Peak Load Management	
Microgrids	
Other DA Applications	

Page 18 of 21 Custom Created: October 4, 2011

Master Updated: April 8, 2011
Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2012	
Period	Start: Jan 1, 2012	End: Dec 31, 2012	Submission Due Date: October 31, 2011

Distribution Management Integration Descriptions

Please enter the information only once for project and specify the year and quarter that the metric is first planned to be installed and operational. Please report the Quarter this equipment is first planned to become operational.

AMI	
Outage Management	
Transmission Management	
DER Systems	
Distribution Management System	
Other Systems	

Page 19 of 21 Custom Created: October 4, 2011

Master Updated: April 8, 2011
Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2012	
Period	Start: Jan 1, 2012	End: Dec 31, 2012	Submission Due Date: October 31, 2011

Additional Program Descriptions

Page 20 of 21 Custom Created: October 4, 2011

Master Updated: April 8, 2011
Schema Version: 1.3



Project	DE-DE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2012	
Period	Start: Jan 1, 2012	End: Dec 31, 2012	Submission Due Date: October 31, 2011

Page 21 of 21 Custom Created October 4, 2011

 ENERGY Master Updated: April 8, 2011 Schema Version: 1.3

S.4 Baseline 2013



Project	DE-OE000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2013	
Period	Start: Jan 1, 2013	End: Dec 31, 2013	Submission Due Date: October 31, 2011

AMI Assets - Build Metrics Baseline

All data should be cumulative. All data reported should be at the project level i.e. it should not include assets that were installed prior to the SGDP project, it should only include assets that would have been installed had the SGDP award not been granted.

AMI End Points Installed	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
End Points (meters) forecasted to be installed and operational	#	0	0	0	0
Portion of customers with AMI residential	#	0	0	0	0
Portion of customers with AMI commercial	#	0	0	0	0
Portion of customers with AMI industrial	#	0	0	0	0

Implemented Meter Features	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Reading interval for residential meters	minutes	0	0	0	0
Reading interval for commercial meters	minutes	0	0	0	0
Reading interval for industrial meters	minutes	0	0	0	0
Remote Connect/Disconnect: is feature implemented? (estimated time frame when feature is operational)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Remote Connect/Disconnect: forecasted number of meters with feature	#	0	0	0	0
Outage Reporting: is feature implemented? (estimated time frame when feature is operational)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Outage Reporting: forecasted number of meters with feature implemented	#	0	0	0	0
Power Quality Measurement: is feature implemented? (estimated time frame when feature is operational)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Power Quality Measurement: forecasted number of meters with feature	#	0	0	0	0
Tamper Detection: is feature implemented? (estimated time frame when feature is operational)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Tamper Detection: forecasted number of meters with feature implemented	#	0	0	0	0
Other feature implemented: <input style="width: 150px;" type="text"/>	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other feature: forecasted number of meters with feature implemented	#	0	0	0	0
Other feature implemented: <input style="width: 150px;" type="text"/>	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other feature: forecasted number of meters with feature implemented	#	0	0	0	0

Page 1 of 21 Custom Created: October 4, 2011


Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2013	
Period	Start: Jan 1, 2013	End: Dec 31, 2013	Submission Due Date: October 31, 2011

Implemented Meter Features	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Other feature implemented: <input style="width: 150px;" type="text"/>	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other feature: forecasted number of meters with feature implemented	#	0	0	0	0

Implemented Enterprise Integration	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Billing System: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Customer Information System: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Outage Management System: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Distribution Management System: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other Enterprise Systems: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

AMI System Descriptions

Please enter the information only once for project and specify the year and quarter that the metric is first planned to be installed and operational. Please report the Quarter this equipment is first planned to become operational.

Backhaul Network	
Meter Communication	
Headend System	

Page 2 of 21 Custom Created: October 4, 2011


Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2013	
Period	Start: Jan 1, 2013	End: Dec 31, 2013	Submission Due Date: October 31, 2011

AMI System Descriptions

Meter Data Management System	
Meter Data Analysis	
Other Meter Feature	
Other Meter Feature	
Other Meter Feature	

Page 3 of 21 Custom Created: October 4, 2011

Master Updated: April 8, 2011
Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2013	
Period	Start: Jan 1, 2013	End: Dec 31, 2013	Submission Due Date: October 31, 2011

AMI Enterprise Integration Descriptions

Please enter the information only once for project and specify the year and quarter that the metric is first planned to be installed and operational. Please report the Quarter this equipment is first planned to become operational.

Billing System	
Customer Information System	
Outage Management System	
Distribution Management System	
Other Enterprise System	
Additional Project Descriptions	

Page 4 of 21 Custom Created: October 4, 2011

Master Updated: April 8, 2011
Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2013	
Period	Start: Jan 1, 2013	End: Dec 31, 2013	Submission Due Date: October 31, 2011

Customer Systems Assets - Build Metrics Baseline

All data should be cumulative. All data reported should be at the project level (i.e. it should not include assets that were installed prior to the SGDP project, it should only include assets that would have been installed had the SGDP award not been granted).

Implemented Customer Systems	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
In-Home display: forecasted devices installed	#	0	0	0	0
Direct load control devices: forecasted devices installed	#	0.0	0.0	0.0	0.0
Programmable communicating thermostats: forecasted devices installed	#	0	0	0	0
Smart appliances: forecasted devices installed	#	0	0	0	0
Energy management devices/systems: forecasted devices installed	#	0.0	0.0	0.0	0.0
Other devices installed	#				
Other devices installed	#				
Other devices installed	#				

Web Portal	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Web portal: Is portal in production?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Forecasted number of customers with access	#				
Forecasted number of customers with active accounts	#				

Customer Device Descriptions

Please enter the information only once for project and specify the year and quarter that the metric is first planned to be installed and operational. Please report the Quarter this equipment is first planned to become operational.

In-Home Displays

Page 5 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2013	
Period	Start: Jan 1, 2013	End: Dec 31, 2013	Submission Due Date: October 31, 2011

Customer Device Descriptions

Direct Load Control Devices	
Programmable Communicating Thermostats	
Smart Appliances	
Energy Mgmt Systems	
Web Portal	
Home Area Network	

Page 6 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2013	
Period	Start: Jan 1, 2013	End: Dec 31, 2013	Submission Due Date: October 31, 2011

Customer Device Descriptions

Other Device	
Other Device	
Other Device	
Additional Project Descriptions	

Page 7 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2013	
Period	Start: Jan 1, 2013	End: Dec 31, 2013	Submission Due Date: October 31, 2011

Pricing Programs - Build Metrics Baseline

All data should be cumulative. All data reported should be at the project level i.e. it should not include assets that were installed prior to the SGDP project, it should only include assets that would have been installed had the SGDP award not been granted.

Implemented Rate Plans	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Flat Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate: forecasted number of customers with access	#				
Flat Rate: forecasted number of customers enrolled	#				
Flat Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Critical Peak Pricing: forecasted number of customers with access	#				
Flat Rate with Critical Peak Pricing: forecasted number of customers enrolled	#				
Flat Rate with Peak-Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Peak-Time Rebate: forecasted number of customers with access	#				
Flat Rate with Peak-Time Rebate: forecasted number of customers enrolled	#				
Tiered Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate: forecasted number of customers with access	#				
Tiered Rate: forecasted number of customers enrolled	#				
Tiered Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Critical Peak Pricing: forecasted number of customers with access	#				
Tiered Rate with Critical Peak Pricing: forecasted number of customers enrolled	#				
Tiered Rate with Peak-Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Peak-Time Rebate: forecasted number of customers with access	#				
Tiered Rate with Peak-Time Rebate: forecasted number of customers enrolled	#				
Time of Use Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Page 8 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE000021 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2013	
Period	Start: Jan 1, 2013	End: Dec 31, 2013	Submission Due Date: October 31, 2011

Implemented Rate Plans	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Time of Use Rate: forecasted number of customers with access	#				
Time of Use Rate: forecasted number of customers enrolled	#				
Time of Use Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Time of Use Rate with Critical Peak Pricing: forecasted number of customers with access	#				
Time of Use Rate with Critical Peak Pricing: forecasted number of customers enrolled	#				
Time of Use Rate with Peak-Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Time of Use Rate with Peak-Time Rebate: forecasted number of customers with access	#				
Time of Use Rate with Peak-Time Rebate: forecasted number of customers enrolled	#				
Real-time Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Real-time Pricing: forecasted number of customers with access	#				
Real-time Pricing: forecasted number of customers enrolled	#				
Real-time Pricing with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Real-time Pricing with Critical Peak Pricing: forecasted number of customers with access	#				
Real-time Pricing with Critical Peak Pricing: forecasted number of customers enrolled	#				
Real-time Pricing with Peak-Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Real-time Pricing with Peak-Time Rebate: forecasted number of customers with access	#				
Real-time Pricing with Peak-Time Rebate: forecasted number of customers enrolled	#				
Variable Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Variable Peak Pricing: forecasted number of customers with access	#				
Variable Peak Pricing: forecasted number of customers enrolled	#				
Pre-pay Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Pre-pay Pricing: forecasted number of customers with access	#				
Pre-pay Pricing: forecasted number of customers enrolled	#				

Page 9 of 21 Custom Created: October 4, 2011


Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE000021 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2013	
Period	Start: Jan 1, 2013	End: Dec 31, 2013	Submission Due Date: October 31, 2011

Implemented Rate Plans	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Net Metering: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Net Metering: forecasted number of customers with access	#				
Net Metering: forecasted number of customers enrolled	#				
Other program available: <input style="width: 150px;" type="text"/>	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: forecasted number of customers with access	#				
Other programs: forecasted number of customers enrolled	#				
Other program available: <input style="width: 150px;" type="text"/>	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: forecasted number of customers with access	#				
Other programs: forecasted number of customers enrolled	#				
Other program available: <input style="width: 150px;" type="text"/>	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: forecasted number of customers with access	#				
Other programs: forecasted number of customers enrolled	#				
Rate Decoupling: is implemented?	yes/ no	<input type="checkbox"/>			

Rate Plan Descriptions

Please enter the information only once for project and specify the year and quarter that the metric is first planned to be installed and operational. Please report the Quarter this equipment is first planned to become operational.

Flat Rate

Page 10 of 21 Custom Created: October 4, 2011


Master Updated: April 8, 2011 Schema Version: 1.3

		Project DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)	
		Filing build_baseline	Baseline Build Metrics Report 2013
		Period Start: Jan 1, 2013	End: Dec 31, 2013 Submission Due Date: October 31, 2011
Rate Plan Descriptions			
Flat Rate with Critical Peak Pricing			
Flat Rate with Peak Time Rebate			
Tiered Rate			
Tiered Rate with Critical Peak Pricing			
Tiered Rate with Peak Time Rebate			
Time of Use Rate			
Page 11 of 21 Custom Created: October 4, 2011		Master Updated: April 8, 2011 Schema Version: 1.3	

		Project DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)	
		Filing build_baseline	Baseline Build Metrics Report 2013
		Period Start: Jan 1, 2013	End: Dec 31, 2013 Submission Due Date: October 31, 2011
Rate Plan Descriptions			
Time of Use Rate with Critical Peak Pricing			
Time of Use Rate with Peak Time Rebate			
Real-Time Rate			
Real-time Rate with Critical Peak Pricing			
Real-time Rate with Peak Time Rebate			
Variable Peak Pricing			
Page 12 of 21 Custom Created: October 4, 2011		Master Updated: April 8, 2011 Schema Version: 1.3	



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2013	
Period	Start: Jan 1, 2013	End: Dec 31, 2013	Submission Due Date: October 31, 2011

Rate Plan Descriptions

Pre-paid Rate	
Net Metering Rate	
Other program	
Other program	
Other program	
Additional Program Descriptions:	

Page 13 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2013	
Period	Start: Jan 1, 2013	End: Dec 31, 2013	Submission Due Date: October 31, 2011

Distributed Energy Resources - Build Metrics Baseline

All data should be cumulative. All data reported should be at the project level i.e. it should not include assets that were installed prior to the SGDP project, it should only include assets that would have been installed had the SGDP award not been granted.

Implemented Distributed Energy and Renewable Devices	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Distributed generation: forecasted number of units	#	0	0	0	0
Distributed generation: estimated installed capacity	KW	0.0	0.0	0.0	0.0
Distributed generation: estimated total energy delivered	* kWh	0	0	0	0
Energy storage: forecasted number of units	#	0	0	0	0
Energy storage: estimated installed capacity	KW	0.0	0.0	0.0	0.0
Energy storage: estimated total energy delivered	* kWh	0.0	0.0	0.0	0.0
Plug-in electric vehicles charging points: forecasted number of units	#	0	0	0	0
Plug-in electric vehicles charging points: installed capacity	KW	0.0	0.0	0.0	0.0
Plug-in electric vehicles charging points: estimated total energy delivered	* kWh	0.0	0.0	0.0	0.0
DER/DG interconnection equipment: forecasted number of units	#				

* Energy delivered should be reported just for the quarter being reported, not cumulative for the project to-date.

Project

Distributed Generation Interface Description	
Additional Program Descriptions:	

Page 14 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2013	
Period	Start: Jan 1, 2013	End: Dec 31, 2013	Submission Due Date: October 31, 2011

Electric Distribution System Assets - Build Metrics Baseline

All data should be cumulative. All data reported should be at the project level (i.e. it should not include assets that were installed prior to the SGDP project, it should only include assets that would have been installed had the SGDP award not been granted).

Implemented Distribution Devices		Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Portion of system with SCADA	%		0	0	0	0
Portion of system with Distribution Automation (DA)	%		0	0	0	0
Automated Feeder Switches: forecasted number of devices installed	#		0	0	0	0
Automated Capacitors: forecasted number of devices installed	#		0.0	0.0	0.0	0.0
Automated Regulators: forecasted number of devices installed	#		0	0	0	0
Feeder Monitors: forecasted number of devices installed	#		0	0	0	0
Remote Fault Indicators: forecasted number of devices installed	#		0.0	0.0	0.0	0.0
Transformer Monitors (line): forecasted number of devices installed	#		0	0	0	0
Smart Relays: forecasted number of devices installed	#		0	0	0	0
Fault Current Limiter: forecasted number of devices installed	#		0	0	0	0
Other devices installed:	#					
Other devices installed:	#					
Other devices installed:	#					

DA Applications in Operation		Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Fault Location, Isolation, and Service Restoration (FLISR): is this application in operation?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Voltage Optimization: is this application in operation?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Feeder Peak Load Management: is this application in operation?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Microgrids: is this application in operation?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other DA Application: is this application in operation?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Page 15 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2013	
Period	Start: Jan 1, 2013	End: Dec 31, 2013	Submission Due Date: October 31, 2011

Implemented Distribution Management Integration

Implemented Distribution Management Integration		Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
AMI: is integration complete? (estimated time frame when integration is complete)	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Outage Management System: is integration complete? (estimated time frame when integration is complete)	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Transmission Management System: is integration complete? (estimated time frame when integration is complete)	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Distributed Energy Resources: is integration complete? (estimated time frame when integration is complete)	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other Systems: is integration complete? (estimated time frame when integration is complete)	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Distribution Device Descriptions

Please enter the information only once for project and specify the year and quarter that the metric is first planned to be installed and operational. Please report the Quarter this equipment is first planned to become operational.

SCADA	
Portion of system with SCADA	
Portion of system with DA	

Page 16 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2013	
Period	Start: Jan 1, 2013	End: Dec 31, 2013	Submission Due Date: October 31, 2011

Distribution Device Descriptions

DA devices	
DA communications network	
Other device	
Other device	
Other device	

Page 17 of 21 Custom Created: October 4, 2011


Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2013	
Period	Start: Jan 1, 2013	End: Dec 31, 2013	Submission Due Date: October 31, 2011

Distribution Application Descriptions

Please enter the information only once for project and specify the year and quarter that the metric is first planned to be installed and operational. Please report the Quarter this equipment is first planned to become operational.

FLSR	
Voltage Optimization	
Feeder Peak Load Management	
Microgrids	
Other DA Applications	

Page 18 of 21 Custom Created: October 4, 2011


Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2013	
Period	Start: Jan 1, 2013	End: Dec 31, 2013	Submission Due Date: October 31, 2011

Distribution Management Integration Descriptions

Please enter the information only once for project and specify the year and quarter that the metric is first planned to be installed and operational. Please report the Quarter this equipment is first planned to become operational.

AMI	
Outage Management	
Transmission Management	
DER Systems	
Distribution Management System	
Other Systems	

Page 19 of 21 Custom Created: October 4, 2011

Master Updated: April 8, 2011
Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2013	
Period	Start: Jan 1, 2013	End: Dec 31, 2013	Submission Due Date: October 31, 2011

Additional Program Descriptions

Page 20 of 21 Custom Created: October 4, 2011

Master Updated: April 8, 2011
Schema Version: 1.3



Project	DE-DE000021 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2014	
Period	Start: Jan 1, 2014	End: Dec 31, 2014	Submission Due Date: October 31, 2011

Page 21 of 21 Custom Created October 4, 2011

 ENERGY Master Updated: April 8, 2011 Schema Version: 1.3

S.5 Baseline 2014



Project	DE-OE000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2014	
Period	Start: Jan 1, 2014	End: Dec 31, 2014	Submission Due Date: October 31, 2011

AMI Assets - Build Metrics Baseline

All data should be cumulative. All data reported should be at the project level i.e. it should not include assets that were installed prior to the SGDP project, it should only include assets that would have been installed had the SGDP award not been granted.

AMI End Points Installed	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
End Points (meters) forecasted to be installed and operational	#	0	0	0	0
Portion of customers with AMI residential	#	0	0	0	0
Portion of customers with AMI commercial	#	0	0	0	0
Portion of customers with AMI industrial	#	0	0	0	0

Implemented Meter Features	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Reading interval for residential meters	minutes	0	0	0	0
Reading interval for commercial meters	minutes	0	0	0	0
Reading interval for industrial meters	minutes	0	0	0	0
Remote Connect/Disconnect: is feature implemented? (estimated time frame when feature is operational)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Remote Connect/Disconnect: forecasted number of meters with feature	#				
Outage Reporting: is feature implemented? (estimated time frame when feature is operational)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Outage Reporting: forecasted number of meters with feature implemented	#				
Power Quality Measurement: is feature implemented? (estimated time frame when feature is operational)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Power Quality Measurement: forecasted number of meters with feature	#				
Tamper Detection: is feature implemented? (estimated time frame when feature is operational)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Tamper Detection: forecasted number of meters with feature implemented	#				
Other feature implemented: <input style="width: 100px;" type="text"/>	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other feature: forecasted number of meters with feature implemented	#				
Other feature implemented: <input style="width: 100px;" type="text"/>	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other feature: forecasted number of meters with feature implemented	#				

Page 1 of 21 Custom Created: October 4, 2011

Master Updated: April 8, 2011
Schematics Version: 1.3



Project	DE-OE000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2014	
Period	Start: Jan 1, 2014	End: Dec 31, 2014	Submission Due Date: October 31, 2011

Implemented Meter Features:

Implemented Meter Features	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Other feature implemented: <input style="width: 100px;" type="text"/>	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other feature: forecasted number of meters with feature implemented	#				

Implemented Enterprise Integration

Implemented Enterprise Integration	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Billing System: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Customer Information System: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Outage Management System: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Distribution Management System: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other Enterprise Systems: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

AMI System Descriptions

Please enter the information only once for project and specify the year and quarter that the metric is first planned to be installed and operational. Please report the Quarter this equipment is first planned to become operational.

Backhaul Network	
Meter Communication	
Headend System	

Page 2 of 21 Custom Created: October 4, 2011

Master Updated: April 8, 2011
Schematics Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2014	
Period	Start: Jan 1, 2014	End: Dec 31, 2014	Submission Due Date: October 31, 2011

AMI System Descriptions

Meter Data Management System	
Meter Data Analysis	
Other Meter Feature	
Other Meter Feature	
Other Meter Feature	

Page 3 of 21 Custom Created: October 4, 2011

Master Updated: April 8, 2011
Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2014	
Period	Start: Jan 1, 2014	End: Dec 31, 2014	Submission Due Date: October 31, 2011

AMI Enterprise Integration Descriptions

Please enter the information only once for project and specify the year and quarter that the metric is first planned to be installed and operational. Please report the Quarter this equipment is first planned to become operational.

Billing System	
Customer Information System	
Outage Management System	
Distribution Management System	
Other Enterprise System	
Additional Project Descriptions	

Page 4 of 21 Custom Created: October 4, 2011

Master Updated: April 8, 2011
Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2014	
Period	Start: Jan 1, 2014	End: Dec 31, 2014	Submission Due Date: October 31, 2011

Customer Systems Assets - Build Metrics Baseline

All data should be cumulative. All data reported should be at the project level (i.e. it should not include assets that were installed prior to the SGDP project, it should only include assets that would have been installed had the SGDP award not been granted).

Implemented Customer Systems	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
In-Home display: forecasted devices installed	#	0	0	0	0
Direct load control devices: forecasted devices installed	#	0.0	0.0	0.0	0.0
Programmable communicating thermostats: forecasted devices installed	#	0	0	0	0
Smart appliances: forecasted devices installed	#	0	0	0	0
Energy management devices/systems: forecasted devices installed	#	0.0	0.0	0.0	0.0
Other devices installed	#				
Other devices installed	#				
Other devices installed	#				

Web Portal	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Web portal: Is portal in production?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Forecasted number of customers with access	#				
Forecasted number of customers with active accounts	#				

Customer Device Descriptions

Please enter the information only once for project and specify the year and quarter that the metric is first planned to be installed and operational. Please report the Quarter this equipment is first planned to become operational.

In-Home Displays

Page 5 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2014	
Period	Start: Jan 1, 2014	End: Dec 31, 2014	Submission Due Date: October 31, 2011

Customer Device Descriptions

Direct Load Control Devices	
Programmable Communicating Thermostats	
Smart Appliances	
Energy Mgmt Systems	
Web Portal	
Home Area Network	

Page 6 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE000021 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2014	
Period	Start: Jan 1, 2014	End: Dec 31, 2014	Submission Due Date: October 31, 2011

Customer Device Descriptions

Other Device	
Other Device	
Other Device	
Additional Project Descriptions	

Page 7 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE000021 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2014	
Period	Start: Jan 1, 2014	End: Dec 31, 2014	Submission Due Date: October 31, 2011

Pricing Programs - Build Metrics Baseline

All data should be cumulative. All data reported should be at the project level i.e. it should not include assets that were installed prior to the SGDP project, it should only include assets that would have been installed had the SGDP award not been granted.

Implemented Rate Plans	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Flat Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate: forecasted number of customers with access	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Flat Rate: forecasted number of customers enrolled	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Flat Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Critical Peak Pricing: forecasted number of customers with access	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Flat Rate with Critical Peak Pricing: forecasted number of customers enrolled	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Flat Rate with Peak-Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Peak-Time Rebate: forecasted number of customers with access	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Flat Rate with Peak-Time Rebate: forecasted number of customers enrolled	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Tiered Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate: forecasted number of customers with access	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Tiered Rate: forecasted number of customers enrolled	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Tiered Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Critical Peak Pricing: forecasted number of customers with access	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Tiered Rate with Critical Peak Pricing: forecasted number of customers enrolled	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Tiered Rate with Peak-Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Peak-Time Rebate: forecasted number of customers with access	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Tiered Rate with Peak-Time Rebate: forecasted number of customers enrolled	#	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Time of Use Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Page 8 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2014	
Period	Start: Jan 1, 2014	End: Dec 31, 2014	Submission Due Date: October 31, 2011

Implemented Rate Plans	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Time of Use Rate: forecasted number of customers with access	#				
Time of Use Rate: forecasted number of customers enrolled	#				
Time of Use Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Time of Use Rate with Critical Peak Pricing: forecasted number of customers with access	#				
Time of Use Rate with Critical Peak Pricing: forecasted number of customers enrolled	#				
Time of Use Rate with Peak-Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Time of Use Rate with Peak-Time Rebate: forecasted number of customers with access	#				
Time of Use Rate with Peak-Time Rebate: forecasted number of customers enrolled	#				
Real-time Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Real-time Pricing: forecasted number of customers with access	#				
Real-time Pricing: forecasted number of customers enrolled	#				
Real-time Pricing with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Real-time Pricing with Critical Peak Pricing: forecasted number of customers with access	#				
Real-time Pricing with Critical Peak Pricing: forecasted number of customers enrolled	#				
Real-time Pricing with Peak-Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Real-time Pricing with Peak-Time Rebate: forecasted number of customers with access	#				
Real-time Pricing with Peak-Time Rebate: forecasted number of customers enrolled	#				
Variable Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Variable Peak Pricing: forecasted number of customers with access	#				
Variable Peak Pricing: forecasted number of customers enrolled	#				
Pre-pay Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Pre-pay Pricing: forecasted number of customers with access	#				
Pre-pay Pricing: forecasted number of customers enrolled	#				

Page 9 of 21 Custom Created: October 4, 2011


Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2014	
Period	Start: Jan 1, 2014	End: Dec 31, 2014	Submission Due Date: October 31, 2011

Implemented Rate Plans	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Net Metering: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Net Metering: forecasted number of customers with access	#				
Net Metering: forecasted number of customers enrolled	#				
Other program available: <input style="width: 150px;" type="text"/>	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: forecasted number of customers with access	#				
Other programs: forecasted number of customers enrolled	#				
Other program available: <input style="width: 150px;" type="text"/>	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: forecasted number of customers with access	#				
Other programs: forecasted number of customers enrolled	#				
Other program available: <input style="width: 150px;" type="text"/>	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: forecasted number of customers with access	#				
Other programs: forecasted number of customers enrolled	#				
Rate Decoupling: is implemented?	yes/ no	<input type="checkbox"/>			

Rate Plan Descriptions
Please enter the information only once for project and specify the year and quarter that the metric is first planned to be installed and operational. Please report the Quarter this equipment is first planned to become operational.

Flat Rate:

Page 10 of 21 Custom Created: October 4, 2011


Master Updated: April 8, 2011 Schema Version: 1.3

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_baseline Baseline Build Metrics Report 2014		
		Period	Start: Jan 1, 2014	End: Dec 31, 2014	Submission Due Date: October 31, 2011
Rate Plan Descriptions					
Flat Rate with Critical Peak Pricing					
Flat Rate with Peak Time Rebate					
Tiered Rate					
Tiered Rate with Critical Peak Pricing					
Tiered Rate with Peak Time Rebate					
Time of Use Rate					

Page 11 of 21 Custom Created: October 4, 2011

U.S. DEPARTMENT OF ENERGY **ENERGY** Master Updated: April 8, 2011 Schema Version: 1.3

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_baseline Baseline Build Metrics Report 2014		
		Period	Start: Jan 1, 2014	End: Dec 31, 2014	Submission Due Date: October 31, 2011
Rate Plan Descriptions					
Time of Use Rate with Critical Peak Pricing					
Time of Use Rate with Peak Time Rebate					
Real-Time Rate					
Real-time Rate with Critical Peak Pricing					
Real-time Rate with Peak Time Rebate					
Variable Peak Pricing					

Page 12 of 21 Custom Created: October 4, 2011

U.S. DEPARTMENT OF ENERGY **ENERGY** Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2014	
Period	Start: Jan 1, 2014	End: Dec 31, 2014	Submission Due Date: October 31, 2011

Rate Plan Descriptions

Pre-paid Rate	
Net Metering Rate	
Other program	
Other program	
Other program	
Additional Program Descriptions:	

Page 13 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2014	
Period	Start: Jan 1, 2014	End: Dec 31, 2014	Submission Due Date: October 31, 2011

Distributed Energy Resources - Build Metrics Baseline

All data should be cumulative. All data reported should be at the project level i.e. it should not include assets that were installed prior to the SGDP project, it should only include assets that would have been installed had the SGDP award not been granted.

Implemented Distributed Energy and Renewable Devices	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Distributed generation: forecasted number of units	#	0	0	0	0
Distributed generation: estimated installed capacity	KW	0.0	0.0	0.0	0.0
Distributed generation: estimated total energy delivered	* kWh	0	0	0	0
Energy storage: forecasted number of units	#	0	0	0	0
Energy storage: estimated installed capacity	KW	0.0	0.0	0.0	0.0
Energy storage: estimated total energy delivered	* kWh	0.0	0.0	0.0	0.0
Plug-in electric vehicles charging points: forecasted number of units	#	0	0	0	0
Plug-in electric vehicles charging points: installed capacity	KW	0.0	0.0	0.0	0.0
Plug-in electric vehicles charging points: estimated total energy delivered	* kWh	0.0	0.0	0.0	0.0
DER/DG interconnection equipment: forecasted number of units	#				

* Energy delivered should be reported just for the quarter being reported, not cumulative for the project to-date.

Project

Distributed Generation Interface Description	
Additional Program Descriptions:	

Page 14 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2014	
Period	Start: Jan 1, 2014	End: Dec 31, 2014	Submission Due Date: October 31, 2011

Electric Distribution System Assets - Build Metrics Baseline

All data should be cumulative. All data reported should be at the project level (i.e. it should not include assets that were installed prior to the SGDP project, it should only include assets that would have been installed had the SGDP award not been granted).

Implemented Distribution Devices	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Portion of system with SCADA	%	0	0	0	0
Portion of system with Distribution Automation (DA)	%	0	0	0	0
Automated Feeder Switches: forecasted number of devices installed	#	0	0	0	0
Automated Capacitors: forecasted number of devices installed	#	0.0	0.0	0.0	0.0
Automated Regulators: forecasted number of devices installed	#	0	0	0	0
Feeder Monitors: forecasted number of devices installed	#	0	0	0	0
Remote Fault Indicators: forecasted number of devices installed	#	0.0	0.0	0.0	0.0
Transformer Monitors (line): forecasted number of devices installed	#	0	0	0	0
Smart Relays: forecasted number of devices installed	#	0	0	0	0
Fault Current Limiter: forecasted number of devices installed	#	0	0	0	0
Other devices installed:	#				
Other devices installed:	#				
Other devices installed:	#				

DA Applications in Operation	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
Fault Location, Isolation, and Service Restoration (FLISR): is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Voltage Optimization: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Feeder Peak Load Management: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Microgrids: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other DA Application: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Page 15 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2014	
Period	Start: Jan 1, 2014	End: Dec 31, 2014	Submission Due Date: October 31, 2011

Implemented Distribution Management Integration

Implemented Distribution Management Integration	Units	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec
AMI: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Outage Management System: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Transmission Management System: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Distributed Energy Resources: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other Systems: is integration complete? (estimated time frame when integration is complete)	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Distribution Device Descriptions

Please enter the information only once for project and specify the year and quarter that the metric is first planned to be installed and operational. Please report the Quarter this equipment is first planned to become operational.

SCADA	
Portion of system with SCADA	
Portion of system with DA	

Page 16 of 21 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2014	
Period	Start: Jan 1, 2014	End: Dec 31, 2014	Submission Due Date: October 31, 2011

Distribution Device Descriptions

DA devices	
DA communications network	
Other device	
Other device	
Other device	

Page 17 of 21 Custom Created: October 4, 2011

Metric Updated: April 8, 2011
Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2014	
Period	Start: Jan 1, 2014	End: Dec 31, 2014	Submission Due Date: October 31, 2011

Distribution Application Descriptions

Please enter the information only once for project and specify the year and quarter that the metric is first planned to be installed and operational. Please report the Quarter this equipment is first planned to become operational.

FLSR	
Voltage Optimization	
Feeder Peak Load Management	
Microgrids	
Other DA Applications	

Page 18 of 21 Custom Created: October 4, 2011

Metric Updated: April 8, 2011
Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2014	
Period	Start: Jan 1, 2014	End: Dec 31, 2014	Submission Due Date: October 31, 2011

Distribution Management Integration Descriptions

Please enter the information only once for project and specify the year and quarter that the metric is first planned to be installed and operational. Please report the Quarter this equipment is first planned to become operational.

AMI	
Outage Management	
Transmission Management	
DER Systems	
Distribution Management System	
Other Systems	

Page 19 of 21 Custom Created: October 4, 2011

 Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2014	
Period	Start: Jan 1, 2014	End: Dec 31, 2014	Submission Due Date: October 31, 2011

Additional Program Descriptions

--	--

Page 20 of 21 Custom Created: October 4, 2011

 Master Updated: April 8, 2011 Schema Version: 1.3



Project	DE-DE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_baseline	Baseline Build Metrics Report 2014	
Period	Start: Jan 1, 2014	End: Dec 31, 2014	Submission Due Date: October 31, 2011

Page 21 of 21 Custom Created October 4, 2011

 ENERGY Master Updated: April 8, 2011 Schema Version: 1.3

S.6 2011 Q3

SMARTGRID.GOV		Project	DE-OE000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2011		
		Period	Start: Jul 1, 2011	End: Sep 30, 2011	Submission Due Date: October 31, 2011
AMI Assets - Build Metrics					
<i>All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.</i>					
AMI End Points Installed		Units	Project	System	
End Points (meters) installed and operational	#		12,113	12,113	
Portion of customers with AMI residential	#		10,950	10,950	
Portion of customers with AMI commercial	#		1,163	1,163	
Portion of customers with AMI industrial	#		0	0	
Implemented Meter Features		Units	Project	System	
Reading interval for residential meters	minutes		15	15	
Reading interval for commercial meters	minutes		15	15	
Reading interval for industrial meters	minutes		0	0	
Remote Connect/Disconnect: is feature implemented?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Remote Connect/Disconnect: number of meters with feature implemented	#				
Outage Reporting: is feature implemented?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Outage Reporting: number of meters with feature implemented	#		12,113	12,113	
Power Quality Measurement: is feature implemented?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Power Quality Measurement: number of meters with feature implemented	#				
Tamper Detection: is feature implemented?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Tamper Detection: number of meters with feature implemented	#		12,113	12,113	
Other feature implemented	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other feature: number of meters with feature implemented	#				
Other feature implemented	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other feature: number of meters with feature implemented	#				
Other feature implemented	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other feature: number of meters with feature implemented	#				

Page 1 of 24 Custom Created: October 8, 2011 Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2011		
		Period	Start: Jul 1, 2011	End: Sep 30, 2011	Submission Due Date: October 31, 2011
Implemented Meter Features		Units	Project	System	
Other feature: number of meters with feature implemented	#				
Implemented Enterprise Integration		Units	Project	System	
Billing System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Customer Information System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Outage Management System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Distribution Management System: is integration complete?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other Enterprise Systems: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
AMI System Descriptions					
	Project	System			
Backend Network	Fiber and Wireless Raven radio with network carrier	Fiber and Wireless Raven radio with network carrier			
Meter Communication Network	Gridstream RF 900MHz - Collectors and Routers	Gridstream RF 900MHz - Collectors and Routers			
Headend System	Lands+Gyr Command Center	Lands+Gyr Command Center			
Meter Data Management System	eMeter	eMeter			

Page 2 of 24 Custom Created: October 8, 2011 Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2011	
		Period	Start: Jul 1, 2011	End: Sep 30, 2011 Submission Due Date: October 31, 2011
AMI System Descriptions				
	Project	System		
Meter Data Analysis	The project AMI was incorporated into the existing ARM – MDA interfaces. AMI->MDA provides daily midnight read and interval meter readings (DataRaker).	The project AMI was incorporated into the existing ARM – MDA interfaces. AMI->MDA provides daily midnight read and interval meter readings (DataRaker).		
Other Meter Feature	N/A	N/A		
Other Meter Feature	N/A	N/A		
Other Meter Feature	N/A	N/A		
AMI Enterprise Integration Descriptions				
	Project	System		
Billing System	AMI is integrated with enterprise Oracle CIS.	AMI is integrated with enterprise Oracle CIS.		

Page 3 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2011	
		Period	Start: Jul 1, 2011	End: Sep 30, 2011 Submission Due Date: October 31, 2011
AMI Enterprise Integration Descriptions				
	Project	System		
Customer Information System	AMI is integrated with enterprise Oracle CIS. The project AMI was incorporated into the existing AMR – CIS interfaces. CIS->AMI daily account/meter synchronization. AMI->CIS daily meter readings. CIS->AMI daily to-date use calculation and of monthly bill.	AMI is integrated with enterprise Oracle CIS. The project AMI was incorporated into the existing AMR – CIS interfaces. CIS->AMI daily account/meter synchronization. AMI->CIS daily meter readings. CIS->AMI daily to-date use calculation and of monthly bill.		
Outage Management System	AMI is integrated with enterprise OMS. An additional project OMS (redundant) will also be implemented in conjunction with a DMS. The project AMI was incorporated into the existing AMR – OMS interfaces. AMI->OMS meter outage alerts and OMS->AMI meter "ping" functions to verify power restoration.	AMI is integrated with enterprise OMS. An additional project OMS (redundant) will also be implemented in conjunction with a DMS. The project AMI was incorporated into the existing AMR – OMS interfaces. AMI->OMS meter outage alerts and OMS->AMI meter "ping" functions to verify power restoration.		
Distribution Management System	Not yet integrated	Not yet integrated		
Other Enterprise Systems	Data Mining and Analysis Tool (DataRaker)	Data Mining and Analysis Tool (DataRaker)		
Additional Project Descriptions	N/A			
AMI Installed Costs		Units	Project Funded	Cost Share
Back Office Systems	\$	343,373	343,373	
Communications Equipment	\$	99,251	99,251	
AMI Smart Meters	\$	2,010,845	2,010,845	

Page 4 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2011	
Period	Start: Jul 1, 2011	End: Sep 30, 2011	Submission Due Date: October 31, 2011

AMI Installed Costs	Units	Project Funded	Cost Share
Other Costs	\$	0	0
Other Costs Description	N/A		

Page 5 of 24 Custom Created: October 4, 2011



Metric Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2011	
Period	Start: Jul 1, 2011	End: Sep 30, 2011	Submission Due Date: October 31, 2011

Customer Systems Assets - Build Metrics			
All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.			
Implemented Customer Systems	Units	Project	System
In-Home display: devices installed	#	828	828
Direct Load Control Devices: devices installed	#	0.0	0.0
Programmable Communicating Thermostats: devices installed	#	0	51,875
Smart Appliances: devices installed	#	0	0
Energy Management Devices/Systems: devices installed	#	0.0	0.0
Other Devices installed	#	0	0
Other Devices installed	#	0	0
Other Devices installed	#	0	0
Web Portal	Units	Project	System
Web portal is portal in production?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Customers with access	#	11,760	11,760
Customers with active accounts	#	780	780
Customer System Descriptions			
	Project	System	
In-Home Displays	Tendril InSight	Tendril InSight	

Page 6 of 24 Custom Created: October 4, 2011



Metric Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2011		
		Period	Start: Jul 1, 2011	End: Sep 30, 2011	Submission Due Date: October 31, 2011
Customer System Descriptions					
	Project	System			
Direct Load Control Devices	Not yet installed	Not yet installed			
Programmable Communicating Thermostats	Not yet installed	Honeywell PC-Ts with one-way paging communications			
Smart Appliances	N/A	N/A			
Energy Mgmt. Systems	N/A	N/A			
Web Portal	Tendril Energy Management Portal	Tendril Energy Management Portal			
Home Area Network	Zigbee SEP 1.0	Zigbee SEP 1.0			

Page 7 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2011		
		Period	Start: Jul 1, 2011	End: Sep 30, 2011	Submission Due Date: October 31, 2011
Customer System Descriptions					
	Project	System			
Other Device	N/A	N/A			
Other Device	N/A	N/A			
Other Device	N/A	N/A			
Additional Project Descriptions	N/A				

Customer System Installed Costs	Units	Project Funded	Cost Share
Back Office Systems	\$	220,542	220,542
Web Portals	\$	279,500	279,500
In-Home Displays	\$	110,863	110,863
Direct Load Control Devices	\$	0	0
Smart Appliances	\$	0	0
Programmable Communicating Thermostats	\$	0	0
Cost of other devices installed	\$	0	0

Page 8 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2011	
Period	Start: Jul 1, 2011	End: Sep 30, 2011	Submission Due Date: October 31, 2011

Customer System Installed Costs	Units	Project Funded	Cost Share
Cost of other devices installed	\$	0	0
Cost of other devices installed	\$	0	0
Other Costs	\$	35,993	35,993
Other Cost Description	Program delivery costs including KCP&L labor for program administration, analysis, and customer engagement		

Page 9 of 24 Custom Created: October 4, 2011

Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2011	
Period	Start: Jul 1, 2011	End: Sep 30, 2011	Submission Due Date: October 31, 2011

Pricing Programs - Build Metrics

All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.

Implemented Rate Plans	Units	Project	System
Flat Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Flat Rate: number of customers with access	#		540,841
Flat Rate: number of customers enrolled	#		540,798
Flat Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Critical Peak Pricing: number of customers with access	#		
Flat Rate with Critical Peak Pricing: number of customers enrolled	#		
Flat Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Peak Time Rebate: number of customers with access	#		
Flat Rate with Peak Time Rebate: number of customers enrolled	#		
Tiered Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Tiered Rate: number of customers with access	#		300,073
Tiered Rate: number of customers enrolled	#		300,026
Tiered Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Critical Peak Pricing: number of customers with access	#		
Tiered Rate with Critical Peak Pricing: number of customers enrolled	#		
Tiered Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Peak Time Rebate: number of customers with access	#		
Tiered Rate with Peak Time Rebate: number of customers enrolled	#		
Time of Use Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Time of Use Rate: number of customers with access	#		841,416

Page 10 of 24 Custom Created: October 4, 2011

Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2011	
Period	Start: Jul 1, 2011	End: Sep 30, 2011	Submission Due Date: October 31, 2011

Implemented Rate Plans	Units	Project	System
Time of Use Rate: number of customers enrolled	#	<input type="text"/>	429
Time of Use Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Time of Use Rate with Critical Peak Pricing: number of customers with access	#	<input type="text"/>	<input type="text"/>
Time of Use Rate with Critical Peak Pricing: number of customers enrolled	#	<input type="text"/>	<input type="text"/>
Time of Use Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Time of Use Rate with Peak Time Rebate: number of customers with access	#	<input type="text"/>	<input type="text"/>
Time of Use Rate with Peak Time Rebate: number of customers enrolled	#	<input type="text"/>	<input type="text"/>
Real-time Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Real-time Pricing: number of customers with access	#	<input type="text"/>	2,453
Real-time Pricing: number of customers enrolled	#	<input type="text"/>	9
Real-time Pricing with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Real-time Pricing with Critical Peak Pricing: number of customers with access	#	<input type="text"/>	<input type="text"/>
Real-time Pricing with Critical Peak Pricing: number of customers enrolled	#	<input type="text"/>	<input type="text"/>
Real-time Pricing with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Real-time Pricing with Peak Time Rebate: number of customers with access	#	<input type="text"/>	<input type="text"/>
Real-time Pricing with Peak Time Rebate: number of customers enrolled	#	<input type="text"/>	<input type="text"/>
Variable Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Variable Peak Pricing: number of customers with access	#	<input type="text"/>	<input type="text"/>
Variable Peak Pricing: number of customers enrolled	#	<input type="text"/>	<input type="text"/>
Pre-pay Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Pre-pay Pricing: number of customers with access	#	<input type="text"/>	<input type="text"/>
Pre-pay Pricing: number of customers enrolled	#	<input type="text"/>	<input type="text"/>
Net Metering: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>

Page 11 of 24 Custom Created: October 4, 2011


Meter Updated: April 9, 2011

Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2011	
Period	Start: Jul 1, 2011	End: Sep 30, 2011	Submission Due Date: October 31, 2011

Implemented Rate Plans	Units	Project	System
Net Metering: number of customers with access	#	<input type="text"/>	154
Net Metering: number of customers enrolled	#	<input type="text"/>	154
Other program available	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: number of customers with access	#	<input type="text"/>	<input type="text"/>
Other programs: number of customers enrolled	#	<input type="text"/>	<input type="text"/>
Other program available	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: number of customers with access	#	<input type="text"/>	<input type="text"/>
Other programs: number of customers enrolled	#	<input type="text"/>	<input type="text"/>
Other program available	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: number of customers with access	#	<input type="text"/>	<input type="text"/>
Other programs: number of customers enrolled	#	<input type="text"/>	<input type="text"/>
Rate Decoupling: is implemented?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>

Rate Plan Descriptions	Project	System
Flat Rate	N/A	KCP&L has multiple Flat rates that occur during both summer and winter.
Flat Rate with Critical Peak Pricing	N/A	N/A

Page 12 of 24 Custom Created: October 4, 2011


Meter Updated: April 9, 2011

Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2011	
		Period	Start: Jul 1, 2011	End: Sep 30, 2011 Submission Due Date: October 31, 2011
Rate Plan Descriptions				
	Project	System		
Flat Rate with Peak Time Rebate	N/A	N/A		
Tiered Rate	N/A	KCPL has multiple existing Tiered Rates. A majority of those are declining block rates.		
Tiered Rate with Critical Peak Pricing	N/A	N/A		
Tiered Rate with Peak Time Rebate	N/A	N/A		
Time of Use Rate	A new TOU rate will be piloted as part of this project to augment the evaluation of customer systems and devices.	KCPL has multiple existing TOU rates		
Time of Use Rate with Critical Peak Pricing	N/A	N/A		

Page 13 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2011	
		Period	Start: Jul 1, 2011	End: Sep 30, 2011 Submission Due Date: October 31, 2011
Rate Plan Descriptions				
	Project	System		
Time of Use Rate with Peak Time Rebate	N/A	N/A		
Real-Time Rate	N/A	KCPL has multiple existing RTP rates		
Real-time Rate with Critical Peak Pricing	N/A	N/A		
Real-time Rate with Peak Time Rebate	N/A	N/A		
Variable Peak Pricing	N/A	N/A		
Pre-paid Rate	N/A	N/A		

Page 14 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2011		
		Period	Start: Jul 1, 2011	End: Sep 30, 2011	Submission Due Date: October 31, 2011
Rate Plan Descriptions					
	Project	System			
Net Metering Rate	N/A	KCPL has multiple existing Net Metering rates			
Other program	N/A	N/A			
Other program	N/A	N/A			
Other program	N/A	N/A			
Additional Project Descriptions	N/A				

Page 15 of 24 Custom Created: October 4, 2011

U.S. DEPARTMENT OF ENERGY Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2011		
		Period	Start: Jul 1, 2011	End: Sep 30, 2011	Submission Due Date: October 31, 2011
Distributed Energy Resources - Build Metrics					
<i>All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.</i>					
Distributed Energy Resources		Units	Project	System	
Distributed generation: number of units	#		1	1	
Distributed generation: installed capacity	KW		3	3	
Distributed generation: total energy delivered	* kWh		0	0	
Energy storage: number of units	#		0	0	
Energy storage: installed capacity	KW		0.0	0.0	
Energy storage: total energy delivered	* kWh		0.0	0.0	
Plug-in electric vehicles charging points: number of units	#		1	11	
Plug-in electric vehicles charging points: installed capacity	KW		3	73	
Plug-in electric vehicles charging points: total energy delivered	* kWh		0.0	425	
DER/DG interconnection equipment: number of units	#				
* Energy delivered should be reported just for the quarter being reported, not cumulative for the project to-date.					
Distributed Energy Resource Descriptions					
	Project	System			
Distributed Generation Interface Description	Non-dispatchable utility-owned DG and EV Chargers. All EV chargers are installed behind customer meters.	Non-dispatchable utility-owned DG and EV Chargers. All EV chargers are installed behind customer meters.			

Page 16 of 24 Custom Created: October 4, 2011

U.S. DEPARTMENT OF ENERGY Meter Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE000021 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2011	
Period	Start: Jul 1, 2011	End: Sep 30, 2011	Submission Due Date: October 31, 2011

Additional Project Descriptions: kWh on the residential PV system and EV charger (120V) installed has not been measured directly up to this point but future systems will include direct usage measurement.

Distributed Energy Resources' Installed Costs	Units	Project Funded	Cost Share
DER Interface Control Systems	\$	0	0
Communications Equipment	\$	0	0
DER/DG Interconnection Equipment	\$	0	0
Renewable DER	\$	0	0
Distributed Generation Equipment	\$	18,366	18,366
Stationary Electric Storage Equipment	\$	0	0
PEVs and Charging Stations	\$	3,846	3,846
Other Costs	\$	0	0
Other Cost Description	N/A		

Page 17 of 24 Custom Created: October 4, 2011



Metric Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE000021 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2011	
Period	Start: Jul 1, 2011	End: Sep 30, 2011	Submission Due Date: October 31, 2011

Electric Distribution System Assets - Build Metrics

All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.

Implemented Distribution Devices	Units	Project	System
Portion of system with SCADA	%	0	10.5
Portion of system with Distribution Automation (DA)	%	0	75
Automated Feeder Switches: number of devices installed	#	0	94
Automated Capacitors: number of devices installed	#	0.0	1,822
Automated Regulators: number of devices installed	#	0	3
Feeder Monitors: number of devices installed	#	0	0
Remote Fault Indicators: number of devices installed	#	0.0	222
Transformer Monitors (line): number of devices installed	#	0	0
Smart Relays: number of devices installed	#	35	2,250
Fault Current Limiter: number of devices installed	#	0	0
Other devices installed	#	0	0
Other devices installed	#	0	0
Other devices installed	#	0	0

DA Applications in Operation	Units	Project	System
Fault Location, Isolation, and Service Restoration (FLISR): is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Voltage Optimization: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Feeder Peak Load Management: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Microgrids: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other DA Application: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>

Page 18 of 24 Custom Created: October 4, 2011



Metric Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2011	
Period	Start: Jul 1, 2011	End: Sep 30, 2011	Submission Due Date: October 31, 2011

Distribution Management System Integration

	Units	Project	System
AMIs: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Outage Management System: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Transmission Management System: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Distributed Energy Resources: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other Systems: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>

Distribution Device Description

	Project	System
SCADA	Distribution SCADA will be installed in the project area	ABB Network Manager (EMS)
Portion of system with SCADA	Distribution SCADA will be installed in the project area	The ABB Network Manager (EMS) communicates to 70% of distribution feeders but only 15% are capable of supporting Smart Grid functionality.
Portion of system with DA	DA has not been implemented yet	KCP&L has locally automated devices such as capacitors, voltage monitors, faulted circuit indicators, and reclosers across the distribution system. 75% represents an estimate of coverage based on number of circuits with one or more of these devices.
DA devices	DA devices have not yet been installed and/or integrated.	There is a mix of locally automated capacitors, voltage monitors, faulted circuit indicators, and reclosers across distribution system.

Page 19 of 24 Custom Created: October 4, 2011



Metric Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2011	
Period	Start: Jul 1, 2011	End: Sep 30, 2011	Submission Due Date: October 31, 2011

Distribution Device Description

	Project	System
DA communications network	DA network has not been installed yet	L+G AMR system and Telemetric/Sensus cellular-based system.
Other device	N/A	N/A
Other device	N/A	N/A
Other device	N/A	N/A

Distribution Application Descriptions

	Project	System
FLISR	FLISR has not yet been implemented	FLISR has not yet been implemented

Page 20 of 24 Custom Created: October 4, 2011



Metric Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2011		
		Period	Start: Jul 1, 2011	End: Sep 30, 2011	Submission Due Date: October 31, 2011
Voltage Optimization	Voltage Optimization has not been implemented yet	A Dynamic Voltage Control (DVC) system exists on 203 buses within metropolitan Kansas City. This system is able to dynamically reduce voltage through load tap changers to achieve voltage changes in coordination with locally controlled cap banks.			
Feeder Peak Load Management	Feeder Peak Load Mgmt has not been implemented yet	System peak loads are curtailed through utilization of the DVC system and existing PCT program operated by Honeywell.			
Microgrids	N/A	N/A			
Other DA Applications	N/A	N/A			
Distribution Management Integration Descriptions					
	Project	System			
AMI	Not integrated yet	Not integrated yet			
Outage Management	Not integrated yet	Not integrated yet			

Page 21 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2011		
		Period	Start: Jul 1, 2011	End: Sep 30, 2011	Submission Due Date: October 31, 2011
Distribution Management Integration Descriptions					
	Project	System			
Transmission Management	Not integrated yet	Not integrated yet			
DER Systems	Not integrated yet	Not integrated yet			
Distribution Management System	Not integrated yet	Not integrated yet			
Other Systems	Not integrated yet	Not integrated yet			
Additional Project Descriptions:	N/A				
Distribution Systems Installed Costs		Units	Project Funded	Cost Share	
Back Office Systems	\$		12,220	12,220	
Distribution Management System	\$		0	0	
Communications Equipment and SCADA	\$		0	0	

Page 22 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2011	
Period	Start: Jul 1, 2011	End: Sep 30, 2011	Submission Due Date: October 31, 2011

Distribution Systems Installed Costs	Units	Project Funded	Cost Share
Feeder Monitor/Indicator	\$	0	0
Substation Monitors	\$	317,657	317,657
Automated Feeder Switches	\$	0	0
Capacitor Automation Equipment	\$	0	0
Regulator Automation Equipment	\$	0	0
Fault Current Limiter Equipment	\$	0	0
Cost of other devices installed	\$	0	0
Cost of other devices installed	\$	0	0
Cost of other devices installed	\$	0	0
Other Costs	\$	0	0
Other Cost Description	N/A		

Page 23 of 24 Custom Created: October 4, 2011



Meter Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power & Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2011	
Period	Start: Jul 1, 2011	End: Sep 30, 2011	Submission Due Date: October 31, 2011

Submit
Print Form

Page 24 of 24 Custom Created: October 4, 2011



Meter Updated: April 8, 2011 Schema Version: 1.2

S.7 2011 Q4



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2011	
Period	Start: Oct 1, 2011	End: Dec 31, 2011	Submission Due Date: January 31, 2012

AMI Assets - Build Metrics

All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.

AMI End Points Installed	Units	Project	System
End Points (meters) installed and operational	#	12,252	12,252
Portion of customers with AMI residential	#	11,092	11,092
Portion of customers with AMI commercial	#	1,160	1,160
Portion of customers with AMI industrial	#	0	0

Implemented Meter Features	Units	Project	System
Reading interval for residential meters	minutes	15	15
Reading interval for commercial meters	minutes	15	15
Reading interval for industrial meters	minutes	0	0
Remote Connect/Disconnect: is feature implemented?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Remote Connect/Disconnect: number of meters with feature implemented	#		
Outage Reporting: is feature implemented?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Outage Reporting: number of meters with feature implemented	#	12,252	12,252
Power Quality Measurement: is feature implemented?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Power Quality Measurement: number of meters with feature implemented	#		
Tamper Detection: is feature implemented?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Tamper Detection: number of meters with feature implemented	#	12,252	12,252
Other feature implemented	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other feature: number of meters with feature implemented	#		
Other feature implemented	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other feature: number of meters with feature implemented	#		
Other feature implemented	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>

Page 1 of 24 Custom Created: October 4, 2011


Meter Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2011	
Period	Start: Oct 1, 2011	End: Dec 31, 2011	Submission Due Date: January 31, 2012

Implemented Meter Features	Units	Project	System
Other feature: number of meters with feature implemented	#		

Implemented Enterprise Integration	Units	Project	System
Billing System: is integration complete?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Customer Information System: is integration complete?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Outage Management System: is integration complete?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Distribution Management System: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other Enterprise Systems: is integration complete?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>

AMI System Descriptions	Project	System
Backend Network	Fiber and Wireless Raven radio with network carrier	Fiber and Wireless Raven radio with network carrier
Meter Communication Network	Lands+Gyr Gridstream RF 900MHz - Collectors and Routers	Lands+Gyr Gridstream RF 900MHz - Collectors and Routers
Headend System	Lands+Gyr Command Center	Lands+Gyr Command Center
Meter Data Management System	eMeter	eMeter

Page 2 of 24 Custom Created: October 4, 2011


Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 4, 2011	
		Period	Start: Oct 1, 2011	End: Dec 31, 2011 Submission Due Date: January 31, 2012
AMI System Descriptions				
	Project	System		
Meter Data Analysis	The project AMI was incorporated into the existing AMR – MDA interfaces. AMI daily register reads and 15-min interval reads are loaded into MDA (DataRaker) on a daily basis.	The project AMI was incorporated into the existing AMR – MDA interfaces. AMI daily register reads and 15-min interval reads are loaded into MDA (DataRaker) on a daily basis.		
Other Meter Feature	N/A	N/A		
Other Meter Feature	N/A	N/A		
Other Meter Feature	N/A	N/A		
AMI Enterprise Integration Descriptions				
	Project	System		
Billing System	AMI is integrated with enterprise Oracle CIS.	AMI is integrated with enterprise Oracle CIS.		

Page 3 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 4, 2011		
		Period	Start: Oct 1, 2011	End: Dec 31, 2011 Submission Due Date: January 31, 2012	
AMI Enterprise Integration Descriptions					
	Project	System			
Customer Information System	AMI is integrated with KCPL enterprise Oracle CIS. The project AMI was incorporated into the existing AMR – CIS interfaces. CIS daily account/meter synchronization. AMI provides CIS daily register meter reads for direct billing. CIS daily billing cycle-to-date usage info and bill prediction pushed to IHDs via AMI Network.	AMI is integrated with KCPL enterprise Oracle CIS. The project AMI was incorporated into the existing AMR – CIS interfaces. CIS daily account/meter synchronization. AMI provides CIS daily register meter reads for direct billing. CIS daily billing cycle-to-date usage info and bill prediction pushed to IHDs via AMI Network.			
Outage Management System	AMI is integrated with enterprise OMS. An additional project OMS (redundant) will also be implemented in conjunction with a DMS. The project AMI was incorporated into the existing AMR to enterprise OMS interfaces including, meter outage alerts and meter "ping" functionality to verify power restoration.	AMI is integrated with enterprise OMS. An additional project OMS (redundant) will also be implemented in conjunction with a DMS. The project AMI was incorporated into the existing AMR to enterprise OMS interfaces including, meter outage alerts and meter "ping" functionality to verify power restoration.			
Distribution Management System	Not yet integrated	Not yet integrated			
Other Enterprise Systems	Data Mining and Analysis Tool (DataRaker) covered by the MDA	Data Mining and Analysis Tool (DataRaker) covered by the MDA			
Additional Project Descriptions	N/A				
AMI Installed Costs			Units	Project Funded	Cost Share
Back Office Systems		\$	402,273	402,273	
Communications Equipment		\$	103,669	103,669	
AMI Smart Meters		\$	2,021,042	2,021,042	

Page 4 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2011	
Period	Start: Oct 1, 2011	End: Dec 31, 2011	Submission Due Date: January 31, 2012

AMI Installed Costs	Units	Project Funded	Cost Share
Other Costs	\$	0	0
Other Costs Description	N/A		

Page 5 of 24 Custom Created: October 4, 2011



Metric Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2011	
Period	Start: Oct 1, 2011	End: Dec 31, 2011	Submission Due Date: January 31, 2012

Customer Systems Assets - Build Metrics				
All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.				
Implemented Customer Systems		Units	Project	System
In-Home display: devices installed		#	626	626
Direct Load Control Devices: devices installed		#	2	2
Programmable Communicating Thermostats: devices installed		#	1	52,633
Smart Appliances: devices installed		#	0	0
Energy Management Devices/Systems: devices installed		#	0.0	0.0
Other Devices installed	HAN Gateway	#	1	1
Other Devices installed		#	0	0
Other Devices installed		#	0	0
Web Portal		Units	Project	System
Web portal is portal in production?		yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Customers with access		#	11,892	11,892
Customers with active accounts		#	984	984
Customer System Descriptions				
	Project	System		
In-Home Displays	Tendril In-Sight	Tendril In-Sight		

Page 6 of 24 Custom Created: October 4, 2011



Metric Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 4, 2011		
		Period	Start: Oct 1, 2011	End: Dec 31, 2011	Submission Due Date: January 31, 2012
Customer System Descriptions					
	Project	System			
Direct Load Control Devices	Tendril Volt	Tendril Volt			
Programmable Communicating Thermostats	Tendril Setpoint	Tendril Setpoint and Honeywell PCTs			
Smart Appliances	N/A	N/A			
Energy Mgmt. Systems	N/A	N/A			
Web Portal	Tendril Energize Web Portal	Tendril Energize Web Portal			
Home Area Network	Zigbee SEP 1.0	Zigbee SEP 1.0			

Page 7 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 4, 2011		
		Period	Start: Oct 1, 2011	End: Dec 31, 2011	Submission Due Date: January 31, 2012
Customer System Descriptions					
	Project	System			
Other Device	Tendril Transport Gateway	Tendril Transport Gateway			
HAN Gateway					
Other Device	N/A	N/A			
Other Device	N/A	N/A			
Additional Project Descriptions	N/A				

Customer System Installed Costs	Units	Project Funded	Cost Share
Back Office Systems	\$	273,933	273,933
Web Portals	\$	514,622	514,622
In-Home Displays	\$	119,329	119,329
Direct Load Control Devices	\$	79,622	79,622
Smart Appliances	\$	0	0
Programmable Communicating Thermostats	\$	33,750	33,750
Cost of other devices installed: HAN Gateway	\$	13,961	13,961

Page 8 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2011	
Period	Start: Oct 1, 2011	End: Dec 31, 2011	Submission Due Date: January 31, 2012

Customer System Installed Costs	Units	Project Funded	Cost Share
Cost of other devices installed	\$	0	0
Cost of other devices installed	\$	0	0
Other Costs	\$	46,093	46,093
Other Cost Description	Program delivery costs including KCP&L labor for program administration, analysis, and customer engagement		

Page 9 of 24 Custom Created: October 4, 2011

Master Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2011	
Period	Start: Oct 1, 2011	End: Dec 31, 2011	Submission Due Date: January 31, 2012

Pricing Programs - Build Metrics

All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.

Implemented Rate Plans	Units	Project	System
Flat Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Flat Rate: number of customers with access	#	0	
Flat Rate: number of customers enrolled	#	0	156,855
Flat Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Critical Peak Pricing: number of customers with access	#	0	0
Flat Rate with Critical Peak Pricing: number of customers enrolled	#	0	0
Flat Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Peak Time Rebate: number of customers with access	#	0	0
Flat Rate with Peak Time Rebate: number of customers enrolled	#	0	0
Tiered Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Tiered Rate: number of customers with access	#	0	
Tiered Rate: number of customers enrolled	#	0	687,611
Tiered Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Critical Peak Pricing: number of customers with access	#	0	0
Tiered Rate with Critical Peak Pricing: number of customers enrolled	#	0	0
Tiered Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Peak Time Rebate: number of customers with access	#	0	0
Tiered Rate with Peak Time Rebate: number of customers enrolled	#	0	0
Time of Use Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Time of Use Rate: number of customers with access	#	0	

Page 10 of 24 Custom Created: October 4, 2011

Master Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)			
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 4, 2011			
		Period	Start: Oct 1, 2011	End: Dec 31, 2011	Submission Due Date: January 31, 2012	
Implemented Rate Plans						
Time of Use Rate: number of customers enrolled	Units	#	Project	0	System	333
Time of Use Rate with Critical Peak Pricing: is the pricing program available?	yes/ no		<input type="checkbox"/>		<input type="checkbox"/>	
Time of Use Rate with Critical Peak Pricing: number of customers with access	#		0		0	
Time of Use Rate with Critical Peak Pricing: number of customers enrolled	#		0		0	
Time of Use Rate with Peak Time Rebate: is the pricing program available?	yes/ no		<input type="checkbox"/>		<input type="checkbox"/>	
Time of Use Rate with Peak Time Rebate: number of customers with access	#		0		0	
Time of Use Rate with Peak Time Rebate: number of customers enrolled	#		0		0	
Real-time Pricing: is the pricing program available?	yes/ no		<input type="checkbox"/>		<input checked="" type="checkbox"/>	
Real-time Pricing: number of customers with access	#		0			
Real-time Pricing: number of customers enrolled	#		0		0	
Real-time Pricing with Critical Peak Pricing: is the pricing program available?	yes/ no		<input type="checkbox"/>		<input type="checkbox"/>	
Real-time Pricing with Critical Peak Pricing: number of customers with access	#		0		0	
Real-time Pricing with Critical Peak Pricing: number of customers enrolled	#		0		0	
Real-time Pricing with Peak Time Rebate: is the pricing program available?	yes/ no		<input type="checkbox"/>		<input type="checkbox"/>	
Real-time Pricing with Peak Time Rebate: number of customers with access	#		0		0	
Real-time Pricing with Peak Time Rebate: number of customers enrolled	#		0		0	
Variable Peak Pricing: is the pricing program available?	yes/ no		<input type="checkbox"/>		<input type="checkbox"/>	
Variable Peak Pricing: number of customers with access	#		0		0	
Variable Peak Pricing: number of customers enrolled	#		0		0	
Pre-pay Pricing: is the pricing program available?	yes/ no		<input type="checkbox"/>		<input type="checkbox"/>	
Pre-pay Pricing: number of customers with access	#		0		0	
Pre-pay Pricing: number of customers enrolled	#		0		0	
Net Metering: is the pricing program available?	yes/ no		<input type="checkbox"/>		<input checked="" type="checkbox"/>	

Page 11 of 24 Custom Created: October 4, 2011

U.S. DEPARTMENT OF ENERGY Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)			
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 4, 2011			
		Period	Start: Oct 1, 2011	End: Dec 31, 2011	Submission Due Date: January 31, 2012	
Implemented Rate Plans						
Net Metering: number of customers with access	Units	#	Project	0	System	
Net Metering: number of customers enrolled	#		0		188	
Other program available	yes/ no		<input type="checkbox"/>		<input type="checkbox"/>	
Other programs: number of customers with access	#		0		0	
Other programs: number of customers enrolled	#		0		0	
Other program available	yes/ no		<input type="checkbox"/>		<input type="checkbox"/>	
Other programs: number of customers with access	#		0		0	
Other programs: number of customers enrolled	#		0		0	
Other program available	yes/ no		<input type="checkbox"/>		<input type="checkbox"/>	
Other programs: number of customers with access	#		0		0	
Other programs: number of customers enrolled	#		0		0	
Rate Decoupling: is implemented?	yes/ no		<input type="checkbox"/>			
Rate Plan Descriptions						
	Project	System				
Flat Rate	N/A	KCP&L has multiple residential and C&I Flat Rates that occur during both summer and winter. We are not able to calculate an accurate number for how many customers have access.				
Flat Rate with Critical Peak Pricing	N/A	N/A				

Page 12 of 24 Custom Created: October 4, 2011

U.S. DEPARTMENT OF ENERGY Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 4, 2011	
		Period	Start: Oct 1, 2011	End: Dec 31, 2011 Submission Due Date: January 31, 2012
Rate Plan Descriptions				
	Project	System		
Flat Rate with Peak Time Rebate	N/A	N/A		
Tiered Rate	N/A	KCPL has multiple existing residential and C&I Tiered Rates. A majority of those are declining block rates. We are not able to calculate an accurate number for how many customers have access.		
Tiered Rate with Critical Peak Pricing	N/A	N/A		
Tiered Rate with Peak Time Rebate	N/A	N/A		
Time of Use Rate	A new residential TOU rate will be piloted as part of this project to augment the evaluation of customer systems and devices.	KCPL has multiple existing residential and C&I TOU Rates. We are not able to calculate an accurate number for how many customers have access.		
Time of Use Rate with Critical Peak Pricing	N/A	N/A		

Page 13 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 4, 2011	
		Period	Start: Oct 1, 2011	End: Dec 31, 2011 Submission Due Date: January 31, 2012
Rate Plan Descriptions				
	Project	System		
Time of Use Rate with Peak Time Rebate	N/A	N/A		
Real-Time Rate	N/A	KCPL has multiple existing RTP rates for commercial and industrial customers. We are not able to calculate an accurate number for how many customers have access.		
Real-time Rate with Critical Peak Pricing	N/A	N/A		
Real-time Rate with Peak Time Rebate	N/A	N/A		
Variable Peak Pricing	N/A	N/A		
Pre-paid Rate	N/A	N/A		

Page 14 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2

		Project DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration) Filing build_quarterly Build Metrics Quarterly Report Quarter 4, 2011 Period Start: Oct 1, 2011 End: Dec 31, 2011 Submission Due Date: January 31, 2012
Rate Plan Descriptions		
	Project	System
Net Metering Rate	N/A	KCP&L has multiple existing residential and C&I Net Metering Rates. We are not able to calculate an accurate number for how many customers have access.
Other program	N/A	N/A
Other program	N/A	N/A
Other program	N/A	N/A
Additional Project Descriptions	N/A	

Page 15 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2

		Project DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration) Filing build_quarterly Build Metrics Quarterly Report Quarter 4, 2011 Period Start: Oct 1, 2011 End: Dec 31, 2011 Submission Due Date: January 31, 2012
Distributed Energy Resources - Build Metrics		
<i>All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.</i>		
Distributed Energy Resources	Units	Project System
Distributed generation: number of units	#	2 87
Distributed generation: installed capacity	KW	102.4 883.4
Distributed generation: total energy delivered	* kWh	3,646 37,441
Energy storage: number of units	#	0 0
Energy storage: installed capacity	KW	0.0 0.0
Energy storage: total energy delivered	* kWh	0.0 0.0
Plug-in electric vehicles charging points: number of units	#	1 11
Plug-in electric vehicles charging points: installed capacity	KW	4 74
Plug-in electric vehicles charging points: total energy delivered	* kWh	556
DER/DG interconnection equipment: number of units	#	

* Energy delivered should be reported just for the quarter being reported, not cumulative for the project to-date.

Distributed Energy Resource Descriptions		
	Project	System
Distributed Generation Interface Description	All DG installed is non-dispatchable utility-owned PV that is being metered separately. All project EV chargers are installed behind customer meters. Interfaces currently limited to measuring data.	Non-dispatchable utility-owned DG and EV Chargers. All EV chargers are installed behind customer meters. Interfaces currently limited to measuring data.

Page 16 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2011	
Period	Start: Oct 1, 2011	End: Dec 31, 2011	Submission Due Date: January 31, 2012

Additional Project Descriptions: kWh for Demo Home PV is not yet accessible and kWh for Demo Home EVSE (110V) not currently measured independently. Grid-connected battery system (1MW) not yet interconnected.

Distributed Energy Resources' Installed Costs	Units	Project Funded	Cost Share
DER Interface Control Systems	\$	0	0
Communications Equipment	\$	0	0
DER/DG Interconnection Equipment	\$	0	0
Renewable DER	\$	347,868	347,868
Distributed Generation Equipment	\$	0	0
Stationary Electric Storage Equipment	\$	0	0
PEVs and Charging Stations	\$	3,846	3,846
Other Costs	\$	0	0
Other Cost Description	N/A		

Page 17 of 24 Custom Created: October 4, 2011



Metric Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2011	
Period	Start: Oct 1, 2011	End: Dec 31, 2011	Submission Due Date: January 31, 2012

Electric Distribution System Assets - Build Metrics

All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.

Implemented Distribution Devices	Units	Project	System
Portion of system with SCADA	%	0	10.5
Portion of system with Distribution Automation (DA)	%	0	75
Automated Feeder Switches: number of devices installed	#	0	94
Automated Capacitors: number of devices installed	#	0.0	1,972
Automated Regulators: number of devices installed	#	0	3
Feeder Monitors: number of devices installed	#	0	0
Remote Fault Indicators: number of devices installed	#	0.0	222
Transformer Monitors (line): number of devices installed	#	0	0
Smart Relays: number of devices installed	#	35	2,250
Fault Current Limiter: number of devices installed	#	0	0
Other devices installed	#	0	0
Other devices installed	#	0	0
Other devices installed	#	0	0

DA Applications in Operation	Units	Project	System
Fault Location, Isolation, and Service Restoration (FLISR): is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Voltage Optimization: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Feeder Peak Load Management: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Microgrids: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other DA Application: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>

Page 18 of 24 Custom Created: October 4, 2011



Metric Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2011	
Period	Start: Oct 1, 2011	End: Dec 31, 2011	Submission Due Date: January 31, 2012

Distribution Management System Integration

	Units	Project	System
AMIS: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Outage Management System: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Transmission Management System: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Distributed Energy Resources: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other Systems: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>

Distribution Device Description

	Project	System
SCADA	Distribution SCADA will be installed in the project area	ABB Network Manager (EMS)
Portion of system with SCADA	Distribution SCADA will be installed in the project area	The ABB Network Manager (EMS) communicates with 70% of feeder breakers, but only 15% of those have communications capable of supporting Smart Grid functionality.
Portion of system with DA	DA has not been implemented yet	KCP&L has locally automated devices such as capacitors, voltage monitors, faulted circuit indicators, and reclosers across the distribution system. 75% represents an estimate of coverage based on number of circuits with one or more of these devices.
DA devices	DA devices have not yet been installed and/or integrated.	There is a mix of locally automated capacitors, voltage monitors, faulted circuit indicators, and reclosers across distribution system.

Page 19 of 24 Custom Created: October 4, 2011



Metric Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2011	
Period	Start: Oct 1, 2011	End: Dec 31, 2011	Submission Due Date: January 31, 2012

Distribution Device Description

	Project	System
DA communications network	DA network has not been installed yet	Lands+Gyr AMR system and Telemetric/Sensus cellular-based system.
Other device	N/A	N/A
N/A		
Other device	N/A	N/A
N/A		
Other device	N/A	N/A
N/A		

Distribution Application Descriptions

	Project	System
FLISR	FLISR has not yet been implemented	FLISR has not yet been implemented

Page 20 of 24 Custom Created: October 4, 2011



Metric Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 4, 2011	
		Period	Start: Oct 1, 2011	End: Dec 31, 2011 Submission Due Date: January 31, 2012
Voltage Optimization	Voltage Optimization has not been implemented yet	A Dynamic Voltage Control (DVC) system exists on 203 buses within metropolitan Kansas City. This system is able to dynamically reduce voltage through load tap changers to achieve voltage changes in coordination with locally controlled cap banks.		
Feeder Peak Load Management	Feeder Peak Load Mgmt has not been implemented yet	System peak loads are curtailed through utilization of the DVC system and existing PCT program operated by Honeywell.		
Microgrids	N/A	N/A		
Other DA Applications	N/A	N/A		
Distribution Management Integration Descriptions				
	Project	System		
AMI	Not integrated yet	Not integrated yet		
Outage Management	Not integrated yet	Not integrated yet		

Page 21 of 24 Custom Created: October 4, 2011

U.S. DEPARTMENT OF ENERGY Master Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 4, 2011	
		Period	Start: Oct 1, 2011	End: Dec 31, 2011 Submission Due Date: January 31, 2012
Distribution Management Integration Descriptions				
	Project	System		
Transmission Management	Not integrated yet	Not integrated yet		
DER Systems	Not integrated yet	Not integrated yet		
Distribution Management System	Not integrated yet	Not integrated yet		
Other Systems	Not integrated yet	Not integrated yet		
Additional Project Descriptions:	N/A			
Distribution Systems Installed Costs				
	Units	Project Funded	Cost Share	
Back Office Systems	\$	18,772	18,772	
Distribution Management System	\$	393,104	393,104	
Communications Equipment and SCADA	\$	22,172	22,172	

Page 22 of 24 Custom Created: October 4, 2011

U.S. DEPARTMENT OF ENERGY Master Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2011	
Period	Start: Oct 1, 2011	End: Dec 31, 2011	Submission Due Date: January 31, 2012

Distribution Systems Installed Costs	Units	Project Funded	Cost Share
Feeder Monitor/Indicator	\$	0	0
Substation Monitors	\$	577,849	577,849
Automated Feeder Switches	\$	58,971	58,971
Capacitor Automation Equipment	\$	0	0
Regulator Automation Equipment	\$	0	0
Fault Current Limiter Equipment	\$	0	0
Cost of other devices installed N/A	\$	0	0
Cost of other devices installed N/A	\$	0	0
Cost of other devices installed N/A	\$	0	0
Other Costs	\$	0	0
Other Cost Description	N/A		

Page 23 of 24 Custom Created: October 4, 2011



Meter Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2011	
Period	Start: Oct 1, 2011	End: Dec 31, 2011	Submission Due Date: January 31, 2012

Submit
Print Form

Page 24 of 24 Custom Created: October 4, 2011



Meter Updated: April 8, 2011 Schema Version: 1.2

S.8 2012 Q1

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 1, 2012		
		Period	Start: Jan 1, 2012	End: Mar 31, 2012	Submission Due Date: April 30, 2012
AMI Assets - Build Metrics					
<i>All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.</i>					
AMI End Points Installed		Units	Project	System	
End Points (meters) installed and operational	#		13,034	13,034	
Portion of customers with AMI residential	#		11,888	11,888	
Portion of customers with AMI commercial	#		1,168	1,168	
Portion of customers with AMI industrial	#		0	0	
Implemented Meter Features		Units	Project	System	
Reading interval for residential meters	minutes		15	15	
Reading interval for commercial meters	minutes		15	15	
Reading interval for industrial meters	minutes				
Remote Connect/Disconnect: is feature implemented?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Remote Connect/Disconnect: number of meters with feature implemented	#				
Outage Reporting: is feature implemented?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Outage Reporting: number of meters with feature implemented	#		13,034	13,034	
Power Quality Measurement: is feature implemented?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Power Quality Measurement: number of meters with feature implemented	#				
Tamper Detection: is feature implemented?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Tamper Detection: number of meters with feature implemented	#		13,034	13,034	
Other feature implemented	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other feature: number of meters with feature implemented	#				
Other feature implemented	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other feature: number of meters with feature implemented	#				
Other feature implemented	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other feature: number of meters with feature implemented	#				

Page 1 of 24 Custom Created: October 4, 2011 Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 1, 2012		
		Period	Start: Jan 1, 2012	End: Mar 31, 2012	Submission Due Date: April 30, 2012
Implemented Meter Features		Units	Project	System	
Other feature: number of meters with feature implemented	#				
Implemented Enterprise Integration		Units	Project	System	
Billing System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Customer Information System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Outage Management System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Distribution Management System: is integration complete?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other Enterprise Systems: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
AMI System Descriptions					
	Project	System			
Backhaul Network	Hybrid of Fiber and Wireless Raven radio with network carrier	Hybrid of Fiber and Wireless Raven radio with network carrier			
Meter Communication Network	Lands+Gyr Gridstream RF 900MHz - Collectors and Routers	Lands+Gyr Gridstream RF 900MHz - Collectors and Routers			
Headend System	Lands+Gyr Command Center	Lands+Gyr Command Center			
Meter Data Management System	eMeter/Siemens	eMeter/Siemens			

Page 2 of 24 Custom Created: October 4, 2011 Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 1, 2012		
		Period	Start: Jan 1, 2012	End: Mar 31, 2012	Submission Due Date: April 30, 2012
AMI System Descriptions					
	Project	System			
Meter Data Analysis	The project AMI was incorporated into the existing AMR – MDA interfaces. AMI daily register reads and 15-min interval reads are loaded into MDA (DataRaker) on a daily basis.	The project AMI was incorporated into the existing AMR – MDA interfaces. AMI daily register reads and 15-min interval reads are loaded into MDA (DataRaker) on a daily basis.			
Other Meter Feature	N/A	N/A			
Other Meter Feature	N/A	N/A			
Other Meter Feature	N/A	N/A			
AMI Enterprise Integration Descriptions					
	Project	System			
Billing System	AMI is integrated with enterprise Oracle CIS.	AMI is integrated with enterprise Oracle CIS.			

Page 3 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 1, 2012		
		Period	Start: Jan 1, 2012	End: Mar 31, 2012	Submission Due Date: April 30, 2012
AMI Enterprise Integration Descriptions					
	Project	System			
Customer Information System	AMI is integrated with KCPL enterprise Oracle CIS. The project AMI was incorporated into the existing AMR – CIS interfaces. CIS daily account/meter synchronization. AMI provides CIS daily register meter reads for direct billing. CIS daily billing cycle-to-date usage info and bill prediction pushed to IHDs via AMI Network.	AMI is integrated with KCPL enterprise Oracle CIS. The project AMI was incorporated into the existing AMR – CIS interfaces. CIS daily account/meter synchronization. AMI provides CIS daily register meter reads for direct billing. CIS daily billing cycle-to-date usage info and bill prediction pushed to IHDs via AMI Network.			
Outage Management System	AMI is integrated with enterprise OMS. An additional project OMS (redundant) will also be implemented in conjunction with a DMS. The project AMI was incorporated into the existing AMR to enterprise OMS interfaces including meter outage alerts and meter "ping" functionality to verify power restoration.	AMI is integrated with enterprise OMS. An additional project OMS (redundant) will also be implemented in conjunction with a DMS. The project AMI was incorporated into the existing AMR to enterprise OMS interfaces including meter outage alerts and meter "ping" functionality to verify power restoration.			
Distribution Management System	Not yet integrated	Not yet integrated			
Other Enterprise Systems	Data Mining and Analysis Tool (DataRaker) covered by the MDA	Data Mining and Analysis Tool (DataRaker) covered by the MDA			
Additional Project Descriptions	N/A				
AMI Installed Costs			Units	Project Funded	Cost Share
Back Office Systems		\$	819,589	819,589	
Communications Equipment		\$	104,373	104,373	
AMI Smart Meters		\$	2,027,246	2,027,246	

Page 4 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 1, 2012	
Period	Start: Jan 1, 2012	End: Mar 31, 2012	Submission Due Date: April 30, 2012

AMI Installed Costs	Units	Project Funded	Cost Share
Other Costs	\$	0	0
Other Costs Description	N/A		

Page 5 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 1, 2012	
Period	Start: Jan 1, 2012	End: Mar 31, 2012	Submission Due Date: April 30, 2012

Customer Systems Assets - Build Metrics				
All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.				
Implemented Customer Systems		Units	Project	System
In-Home display: devices installed		#	642	642
Direct Load Control Devices: devices installed		#	15	15
Programmable Communicating Thermostats: devices installed		#	7	52,861
Smart Appliances: devices installed		#	0	0
Energy Management Devices/Systems: devices installed		#	0.0	0.0
Other Devices installed	HAN Gateway device	#	7	7
Other Devices installed		#		
Other Devices installed		#		
Web Portal		Units	Project	System
Web portal is portal in production?		yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Customers with access		#	11,896	11,896
Customers with active accounts		#	1,106	1,106
Customer System Descriptions				
	Project		System	
In-Home Displays	Tendril In-Sight		Tendril In-Sight	

Page 6 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 1, 2012		
		Period	Start: Jan 1, 2012	End: Mar 31, 2012	Submission Due Date: April 30, 2012

Customer System Descriptions		
	Project	System
Direct Load Control Devices	Tendril Volt	Tendril Volt
Programmable Communicating Thermostats	Tendril Setpoint	Tendril Setpoint and Honeywell PCTs
Smart Appliances	N/A	N/A
Energy Mgmt. Systems	N/A	N/A
Web Portal	Tendril Energize Web Portal	Tendril Energize Web Portal
Home Area Network	Zigbee SEP 1.0	Zigbee SEP 1.0

Page 7 of 24 Custom Created: October 4, 2011 Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 1, 2012		
		Period	Start: Jan 1, 2012	End: Mar 31, 2012	Submission Due Date: April 30, 2012

Customer System Descriptions		
	Project	System
Other Device	Tendril Transport Gateway	Tendril Transport Gateway
HAN Gateway device		
Other Device	N/A	N/A
Other Device	N/A	N/A
Additional Project Descriptions	N/A	

Customer System Installed Costs	Units	Project Funded	Cost Share
Back Office Systems	\$	282,880	282,880
Web Portals	\$	514,622	514,622
In-Home Displays	\$	122,048	122,048
Direct Load Control Devices	\$	79,622	79,622
Smart Appliances	\$	0	0
Programmable Communicating Thermostats	\$	155,802	155,802
Cost of other devices installed: HAN Gateway device	\$	34,001	34,001

Page 8 of 24 Custom Created: October 4, 2011 Meter Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 1, 2012	
Period	Start: Jan 1, 2012	End: Mar 31, 2012	Submission Due Date: April 30, 2012

Customer System Installed Costs	Units	Project Funded	Cost Share
Cost of other devices installed	\$		
Cost of other devices installed	\$		
Other Costs	\$	79,683	79,683
Other Cost Description	Program delivery costs including KCP&L labor for program administration, analysis, and customer engagement as well as vendor travel expenses.		

Page 9 of 24 Custom Created: October 4, 2011

Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 1, 2012	
Period	Start: Jan 1, 2012	End: Mar 31, 2012	Submission Due Date: April 30, 2012

Pricing Programs - Build Metrics

All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.

Implemented Rate Plans	Units	Project	System
Flat Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Flat Rate: number of customers with access	#		
Flat Rate: number of customers enrolled	#		156,780
Flat Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Critical Peak Pricing: number of customers with access	#		
Flat Rate with Critical Peak Pricing: number of customers enrolled	#		
Flat Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Peak Time Rebate: number of customers with access	#		
Flat Rate with Peak Time Rebate: number of customers enrolled	#		
Tiered Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Tiered Rate: number of customers with access	#		
Tiered Rate: number of customers enrolled	#		687,611
Tiered Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Critical Peak Pricing: number of customers with access	#		
Tiered Rate with Critical Peak Pricing: number of customers enrolled	#		
Tiered Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Peak Time Rebate: number of customers with access	#		
Tiered Rate with Peak Time Rebate: number of customers enrolled	#		
Time of Use Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Time of Use Rate: number of customers with access	#		

Page 10 of 24 Custom Created: October 4, 2011

Metric Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 1, 2012		
		Period	Start: Jan 1, 2012	End: Mar 31, 2012	Submission Due Date: April 30, 2012
Implemented Rate Plans		Units	Project	System	
Time of Use Rate: number of customers enrolled	#			335	
Time of Use Rate with Critical Peak Pricing: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Time of Use Rate with Critical Peak Pricing: number of customers with access	#				
Time of Use Rate with Critical Peak Pricing: number of customers enrolled	#				
Time of Use Rate with Peak-Time Rebate: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Time of Use Rate with Peak-Time Rebate: number of customers with access	#				
Time of Use Rate with Peak-Time Rebate: number of customers enrolled	#				
Real-time Pricing: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Real-time Pricing: number of customers with access	#				
Real-time Pricing: number of customers enrolled	#			0	
Real-time Pricing with Critical Peak Pricing: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Real-time Pricing with Critical Peak Pricing: number of customers with access	#				
Real-time Pricing with Critical Peak Pricing: number of customers enrolled	#				
Real-time Pricing with Peak-Time Rebate: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Real-time Pricing with Peak-Time Rebate: number of customers with access	#				
Real-time Pricing with Peak-Time Rebate: number of customers enrolled	#				
Variable Peak Pricing: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Variable Peak Pricing: number of customers with access	#				
Variable Peak Pricing: number of customers enrolled	#				
Pre-pay Pricing: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Pre-pay Pricing: number of customers with access	#				
Pre-pay Pricing: number of customers enrolled	#				
Net Metering: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input checked="" type="checkbox"/>	

Page 11 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 1, 2012		
		Period	Start: Jan 1, 2012	End: Mar 31, 2012	Submission Due Date: April 30, 2012
Implemented Rate Plans		Units	Project	System	
Net Metering: number of customers with access	#				
Net Metering: number of customers enrolled	#			226	
Other program available	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other programs: number of customers with access	#				
Other programs: number of customers enrolled	#				
Other program available	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other programs: number of customers with access	#				
Other programs: number of customers enrolled	#				
Other program available	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other programs: number of customers with access	#				
Other programs: number of customers enrolled	#				
Rate Decoupling: is implemented?	yes/ no		<input type="checkbox"/>		
Rate Plan Descriptions					
	Project	System			
Flat Rate	N/A	KCP&L has multiple residential and C&I Flat Rates that occur during both summer and winter. We are not able to calculate an accurate number for how many customers have access.			
Flat Rate with Critical Peak Pricing	N/A	N/A			

Page 12 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 1, 2012		
		Period	Start: Jan 1, 2012	End: Mar 31, 2012	Submission Due Date: April 30, 2012
Rate Plan Descriptions					
	Project	System			
Flat Rate with Peak Time Rebate	N/A	N/A			
Tiered Rate	N/A	KCPL has multiple existing residential and C&I Tiered Rates. A majority of those are declining block rates. We are not able to calculate an accurate number for how many customers have access.			
Tiered Rate with Critical Peak Pricing	N/A	N/A			
Tiered Rate with Peak Time Rebate	N/A	N/A			
Time of Use Rate	A new residential TOU rate will be piloted as part of this project to augment the evaluation of customer systems and devices.	KCPL has multiple existing residential and C&I TOU Rates. We are not able to calculate an accurate number for how many customers have access.			
Time of Use Rate with Critical Peak Pricing	N/A	N/A			

Page 13 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 1, 2012		
		Period	Start: Jan 1, 2012	End: Mar 31, 2012	Submission Due Date: April 30, 2012
Rate Plan Descriptions					
	Project	System			
Time of Use Rate with Peak Time Rebate	N/A	N/A			
Real-Time Rate	N/A	KCPL has multiple existing RTP rates for commercial and industrial customers. We are not able to calculate an accurate number for how many customers have access.			
Real-time Rate with Critical Peak Pricing	N/A	N/A			
Real-time Rate with Peak Time Rebate	N/A	N/A			
Variable Peak Pricing	N/A	N/A			
Pre-paid Rate	N/A	N/A			

Page 14 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

		Project DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)			
		Filing build_quarterly		Build Metrics Quarterly Report Quarter 1, 2012	
		Period Start: Jan 1, 2012		End: Mar 31, 2012 Submission Due Date: April 30, 2012	
Rate Plan Descriptions					
	Project		System		
Net Metering Rate	N/A		KCP&L has multiple existing residential and C&I Net Metering Rates. We are not able to calculate an accurate number for how many customers have access.		
Other program	N/A		N/A		
Other program	N/A		N/A		
Other program	N/A		N/A		
Additional Project Descriptions	N/A				
Page 15 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2					

		Project DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)			
		Filing build_quarterly		Build Metrics Quarterly Report Quarter 1, 2012	
		Period Start: Jan 1, 2012		End: Mar 31, 2012 Submission Due Date: April 30, 2012	
Distributed Energy Resources - Build Metrics					
<i>All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.</i>					
Distributed Energy Resources		Units	Project	System	
Distributed generation: number of units		#	2	105	
Distributed generation: installed capacity		KW	102.4	1,298.4	
Distributed generation: total energy delivered		* kWh	24,155	89,358	
Energy storage: number of units		#	0	0	
Energy storage: installed capacity		KW	0.0	0.0	
Energy storage: total energy delivered		* kWh	0.0	0.0	
Plug-in electric vehicles charging points: number of units		#	1	11	
Plug-in electric vehicles charging points: installed capacity		KW	4	74	
Plug-in electric vehicles charging points: total energy delivered		* kWh	13	1,808	
DER/DG interconnection equipment: number of units		#			
* Energy delivered should be reported just for the quarter being reported, not cumulative for the project to-date.					
Distributed Energy Resource Descriptions					
	Project		System		
Distributed Generation Interface Description	All DG installed is non-dispatchable utility-owned PV that is being metered separately. All project EV chargers are installed behind customer meters. Interfaces currently limited to measuring data.		Non-dispatchable utility-owned DG and EV Chargers. All EV chargers are installed behind customer meters. Interfaces currently limited to measuring data.		
Page 16 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2					



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 1, 2012	
Period	Start: Jan 1, 2012	End: Mar 31, 2012	Submission Due Date: April 30, 2012

Additional Project Descriptions:

Distributed Energy Resources' Installed Costs	Units	Project Funded	Cost Share
DER Interface Control Systems	\$	0	0
Communications Equipment	\$	0	0
DER/DG Interconnection Equipment	\$	0	0
Renewable DER	\$	0	0
Distributed Generation Equipment	\$	347,865	347,865
Stationary Electric Storage Equipment	\$	0	0
PEVs and Charging Stations	\$	3,846	3,846
Other Costs	\$	0	0
Other Cost Description	N/A		

Page 17 of 24 Custom Created: October 4, 2011



Master Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 1, 2012	
Period	Start: Jan 1, 2012	End: Mar 31, 2012	Submission Due Date: April 30, 2012

Electric Distribution System Assets - Build Metrics

All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.

Implemented Distribution Devices	Units	Project	System
Portion of system with SCADA	%	0	10.5
Portion of system with Distribution Automation (DA)	%	0	75
Automated Feeder Switches: number of devices installed	#	0	94
Automated Capacitors: number of devices installed	#	0.0	1,972
Automated Regulators: number of devices installed	#	0	3
Feeder Monitors: number of devices installed	#	0	0
Remote Fault Indicators: number of devices installed	#	0.0	222
Transformer Monitors (line): number of devices installed	#	0	0
Smart Relays: number of devices installed	#	58	2,250
Fault Current Limiter: number of devices installed	#	0	0
Other devices installed	#		
Other devices installed	#		
Other devices installed	#		

DA Applications in Operation	Units	Project	System
Fault Location, Isolation, and Service Restoration (FLISR): is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Voltage Optimization: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Feeder Peak Load Management: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Microgrids: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other DA Application: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>

Page 16 of 24 Custom Created: October 4, 2011



Master Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 1, 2012	
Period	Start: Jan 1, 2012	End: Mar 31, 2012	Submission Due Date: April 30, 2012

Distribution Management System Integration

	Units	Project	System
AMR: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Outage Management System: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Transmission Management System: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Distributed Energy Resources: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other Systems: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>

Distribution Device Description

	Project	System
SCADA	Distribution SCADA will be installed in the project area.	ABB Network Manager (EMS)
Portion of system with SCADA	Distribution SCADA will be installed in the project area.	The ABB Network Manager (EMS) communicates with 70% of feeder breakers, but only 15% of those have communications capable of supporting Smart Grid functionality.
Portion of system with DA	DA has not been implemented yet.	KCP&L has locally automated devices such as capacitors, voltage monitors, faulted circuit indicators, and reclosers across the distribution system. 75% represents an estimate of coverage based on number of circuits with one or more of these devices.
DA devices	DA devices have not yet been installed and/or integrated.	There is a mix of locally automated capacitors, voltage monitors, faulted circuit indicators, and reclosers across distribution system.

Page 19 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 1, 2012	
Period	Start: Jan 1, 2012	End: Mar 31, 2012	Submission Due Date: April 30, 2012

Distribution Device Description

	Project	System
DA communications network	DA network has not been installed yet.	Lands+Gyr AMR system and Telemetric/Sensus cellular-based system.
Other device	N/A	N/A
N/A		
Other device	N/A	N/A
N/A		
Other device	N/A	N/A
N/A		

Distribution Application Descriptions

	Project	System
FLISR	FLISR has not yet been implemented	FLISR has not yet been implemented

Page 20 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 1, 2012		
		Period	Start: Jan 1, 2012	End: Mar 31, 2012	Submission Due Date: April 30, 2012
Voltage Optimization	Voltage Optimization has not been implemented yet.	A Dynamic Voltage Control (DVC) system exists on 203 buses within metropolitan Kansas City. This system is able to dynamically reduce voltage through load tap changers to achieve voltage changes in coordination with locally controlled cap banks.			
Feeder Peak Load Management	Feeder Peak Load Management has not been implemented yet.	System peak loads are curtailed through utilization of the DVC system and existing PCT program operated by Honeywell.			
Microgrids	N/A	N/A			
Other DA Applications	N/A	N/A			
Distribution Management Integration Descriptions					
	Project	System			
AMI	Not integrated yet	Not integrated yet			
Outage Management	Not integrated yet	Not integrated yet			

Page 21 of 24 Custom Created: October 4, 2011  Master Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 1, 2012		
		Period	Start: Jan 1, 2012	End: Mar 31, 2012	Submission Due Date: April 30, 2012
Distribution Management Integration Descriptions					
	Project	System			
Transmission Management	N/A	N/A			
DER Systems	Not integrated yet	Not integrated yet			
Distribution Management System	Not integrated yet	Not integrated yet			
Other Systems	N/A	N/A			
Additional Project Descriptions:	N/A				
Distribution Systems Installed Costs					
	Units	Project Funded	Cost Share		
Back Office Systems	\$	207,371	207,371		
Distribution Management System	\$	0	0		
Communications Equipment and SCADA	\$	0	0		

Page 22 of 24 Custom Created: October 4, 2011  Master Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 1, 2012	
Period	Start: Jan 1, 2012	End: Mar 31, 2012	Submission Due Date: April 30, 2012

Distribution Systems Installed Costs	Units	Project Funded	Cost Share
Feeder Monitor/Indicator	\$	0	0
Substation Monitors	\$	817,956	817,956
Automated Feeder Switches	\$	0	0
Capacitor Automation Equipment	\$	0	0
Regulator Automation Equipment	\$	0	0
Fault Current Limiter Equipment	\$	0	0
Cost of other devices installed N/A	\$		
Cost of other devices installed N/A	\$		
Cost of other devices installed N/A	\$		
Other Costs	\$		
Other Cost Description	N/A		

Page 23 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 1, 2012	
Period	Start: Jan 1, 2012	End: Mar 31, 2012	Submission Due Date: April 30, 2012

Submit
Print Form

Page 24 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2

S.9 2012 Q2

		Project: DE-OE000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
Filing: build_quarterly		Build Metrics Quarterly Report Quarter 2, 2012	
Period: Start: Apr 1, 2012		End: Jun 30, 2012 Submission Due Date: July 31, 2012	

AMI Assets - Build Metrics

All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.

AMI End Points Installed	Units	Project	System
End Points (meters) installed and operational	#	13,269	13,269
Portion of customers with AMI residential	#	12,068	12,068
Portion of customers with AMI commercial	#	1,203	1,203
Portion of customers with AMI industrial	#	0	0

Implemented Meter Features	Units	Project	System
Reading interval for residential meters	minutes	15	15
Reading interval for commercial meters	minutes	15	15
Reading interval for industrial meters	minutes		
Remote Connect/Disconnect: is feature implemented?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Remote Connect/Disconnect: number of meters with feature implemented	#		
Outage Reporting: is feature implemented?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Outage Reporting: number of meters with feature implemented	#	13,269	13,269
Power Quality Measurement: is feature implemented?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Power Quality Measurement: number of meters with feature implemented	#		
Tamper Detection: is feature implemented?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Tamper Detection: number of meters with feature implemented	#	13,269	13,269
Other feature implemented	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other feature: number of meters with feature implemented	#		
Other feature implemented	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other feature: number of meters with feature implemented	#		
Other feature implemented	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>

Page 1 of 24 Custom Created: October 4, 2011 Meter Updated: April 9, 2011 Schema Version: 1.2

		Project: DE-OE000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
Filing: build_quarterly		Build Metrics Quarterly Report Quarter 2, 2012	
Period: Start: Apr 1, 2012		End: Jun 30, 2012 Submission Due Date: July 31, 2012	

Implemented Meter Features	Units	Project	System
Other feature: number of meters with feature implemented	#		

Implemented Enterprise Integration	Units	Project	System
Billing System: is integration complete?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Customer Information System: is integration complete?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Outage Management System: is integration complete?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Distribution Management System: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other Enterprise Systems: is integration complete?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>

AMI System Descriptions	Project	System
Backhaul Network	Hybrid of Fiber and Wireless Raven radio with network carrier	Hybrid of Fiber and Wireless Raven radio with network carrier
Meter Communication Network	Lands+Gyr Gridstream RF 900MHz - Collectors and Routers	Lands+Gyr Gridstream RF 900MHz - Collectors and Routers
Headend System	Lands+Gyr Command Center	Lands+Gyr Command Center
Meter Data Management System	eMeter/Siemens	eMeter/Siemens

Page 2 of 24 Custom Created: October 4, 2011 Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 2, 2012	
		Period	Start: Apr 1, 2012	End: Jun 30, 2012 Submission Due Date: July 31, 2012
AMI System Descriptions				
	Project	System		
Meter Data Analysis	The project AMI was incorporated into the existing AMR – MDA interfaces. AMI daily register reads and 15-min interval reads are loaded into MDA (DataRaker) on a daily basis.	The project AMI was incorporated into the existing AMR – MDA interfaces. AMI daily register reads and 15-min interval reads are loaded into MDA (DataRaker) on a daily basis.		
Other Meter Feature	N/A	N/A		
Other Meter Feature	N/A	N/A		
Other Meter Feature	N/A	N/A		
AMI Enterprise Integration Descriptions				
	Project	System		
Billing System	AMI is integrated with enterprise Oracle CIS.	AMI is integrated with enterprise Oracle CIS.		

Page 3 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 2, 2012	
		Period	Start: Apr 1, 2012	End: Jun 30, 2012 Submission Due Date: July 31, 2012
AMI Enterprise Integration Descriptions				
	Project	System		
Customer Information System	AMI is integrated with KCPL enterprise Oracle CIS. The project AMI was incorporated into the existing AMR – CIS interfaces. CIS daily account/meter synchronization. AMI provides CIS daily register meter reads for direct billing. CIS daily billing cycle-to-date usage info and bill prediction pushed to IHDs via AMI Network.	AMI is integrated with KCPL enterprise Oracle CIS. The project AMI was incorporated into the existing AMR – CIS interfaces. CIS daily account/meter synchronization. AMI provides CIS daily register meter reads for direct billing. CIS daily billing cycle-to-date usage info and bill prediction pushed to IHDs via AMI Network.		
Outage Management System	AMI is integrated with enterprise OMS. An additional project OMS (redundant) will also be implemented in conjunction with a DMS. The project AMI was incorporated into the existing AMR to enterprise OMS interfaces including meter outage alerts and meter "ping" functionality to verify power restoration.	AMI is integrated with enterprise OMS. An additional project OMS (redundant) will also be implemented in conjunction with a DMS. The project AMI was incorporated into the existing AMR to enterprise OMS interfaces including meter outage alerts and meter "ping" functionality to verify power restoration.		
Distribution Management System	Not yet integrated	Not yet integrated		
Other Enterprise Systems	Data Mining and Analysis Tool (DataRaker) covered by the MDA	Data Mining and Analysis Tool (DataRaker) covered by the MDA		
Additional Project Descriptions	N/A			
AMI Installed Costs		Units	Project Funded	Cost Share
Back Office Systems	\$	1,325,012	1,325,012	
Communications Equipment	\$	107,117	107,117	
AMI Smart Meters	\$	2,063,148	2,063,148	

Page 4 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 2, 2012	
Period	Start: Apr 1, 2012	End: Jun 30, 2012	Submission Due Date: July 31, 2012

AMI Installed Costs	Units	Project Funded	Cost Share
Other Costs	\$	0	0
Other Costs Description	N/A		

Page 5 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 2, 2012	
Period	Start: Apr 1, 2012	End: Jun 30, 2012	Submission Due Date: July 31, 2012

Customer Systems Assets - Build Metrics				
All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.				
Implemented Customer Systems		Units	Project	System
In-Home display: devices installed		#	666	666
Direct Load Control Devices: devices installed		#	24	24
Programmable Communicating Thermostats: devices installed		#	30	51,655
Smart Appliances: devices installed		#	0	0
Energy Management Devices/Systems: devices installed		#	0.0	0.0
Other Devices installed	HAN Gateway	#	11	11
Other Devices installed		#		
Other Devices installed		#		
Web Portal		Units	Project	System
Web portal is portal in production?		yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Customers with access		#	11,675	11,675
Customers with active accounts		#	1,322	1,322
Customer System Descriptions				
	Project		System	
In-Home Displays	Tendril In-Sight		Tendril In-Sight	

Page 6 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 2, 2012	
		Period	Start: Apr 1, 2012	End: Jun 30, 2012 Submission Due Date: July 31, 2012

Customer System Descriptions		
	Project	System
Direct Load Control Devices	Tendril Volt	Tendril Volt
Programmable Communicating Thermostats	Tendril Setpoint	Tendril Setpoint and Honeywell PCTs
Smart Appliances	N/A	N/A
Energy Mgmt. Systems	N/A	N/A
Web Portal	Tendril Energize Web Portal	Tendril Energize Web Portal
Home Area Network	Zigbee SEP 1.0	Zigbee SEP 1.0

Page 7 of 24 Custom Created: October 4, 2011 Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 2, 2012	
		Period	Start: Apr 1, 2012	End: Jun 30, 2012 Submission Due Date: July 31, 2012

Customer System Descriptions		
	Project	System
Other Device	Tendril Transport Gateway	Tendril Transport Gateway
HAN Gateway		
Other Device	N/A	N/A
Other Device	N/A	N/A
Additional Project Descriptions	N/A	

Customer System Installed Costs			
	Units	Project Funded	Cost Share
Back Office Systems	\$	289,084	289,084
Web Portals	\$	580,762	580,762
In-Home Displays	\$	122,183	122,183
Direct Load Control Devices	\$	79,622	79,622
Smart Appliances	\$	0	0
Programmable Communicating Thermostats	\$	217,721	217,721
Cost of other devices installed: HAN Gateway	\$	76,447	76,447

Page 8 of 24 Custom Created: October 4, 2011 Meter Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 2, 2012	
Period	Start: Apr 1, 2012	End: Jun 30, 2012	Submission Due Date: July 31, 2012

Customer System Installed Costs	Units	Project Funded	Cost Share
Cost of other devices installed	\$	<input type="text"/>	<input type="text"/>
Cost of other devices installed	\$	<input type="text"/>	<input type="text"/>
Other Costs	\$	188,867	188,867
Other Cost Description	Program delivery costs including KCPL labor for program administration, analysis, and customer engagement as well as vendor travel expenses.		

Page 9 of 24 Custom Created: October 4, 2011

Master Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 2, 2012	
Period	Start: Apr 1, 2012	End: Jun 30, 2012	Submission Due Date: July 31, 2012

Pricing Programs - Build Metrics

All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.

Implemented Rate Plans	Units	Project	System
Flat Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Flat Rate: number of customers with access	#	<input type="text"/>	<input type="text"/>
Flat Rate: number of customers enrolled	#	<input type="text"/>	542,079
Flat Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Critical Peak Pricing: number of customers with access	#	<input type="text"/>	<input type="text"/>
Flat Rate with Critical Peak Pricing: number of customers enrolled	#	<input type="text"/>	<input type="text"/>
Flat Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Peak Time Rebate: number of customers with access	#	<input type="text"/>	<input type="text"/>
Flat Rate with Peak Time Rebate: number of customers enrolled	#	<input type="text"/>	<input type="text"/>
Tiered Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Tiered Rate: number of customers with access	#	<input type="text"/>	<input type="text"/>
Tiered Rate: number of customers enrolled	#	<input type="text"/>	300,783
Tiered Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Critical Peak Pricing: number of customers with access	#	<input type="text"/>	<input type="text"/>
Tiered Rate with Critical Peak Pricing: number of customers enrolled	#	<input type="text"/>	<input type="text"/>
Tiered Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Peak Time Rebate: number of customers with access	#	<input type="text"/>	<input type="text"/>
Tiered Rate with Peak Time Rebate: number of customers enrolled	#	<input type="text"/>	<input type="text"/>
Time of Use Rate: is the pricing program available?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Time of Use Rate: number of customers with access	#	12,066	<input type="text"/>

Page 10 of 24 Custom Created: October 4, 2011

Master Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 2, 2012		
		Period	Start: Apr 1, 2012	End: Jun 30, 2012	Submission Due Date: July 31, 2012
Implemented Rate Plans		Units	Project	System	
Time of Use Rate: number of customers enrolled	#		25	486	
Time of Use Rate with Critical Peak Pricing: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Time of Use Rate with Critical Peak Pricing: number of customers with access	#				
Time of Use Rate with Critical Peak Pricing: number of customers enrolled	#				
Time of Use Rate with Peak Time Rebate: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Time of Use Rate with Peak Time Rebate: number of customers with access	#				
Time of Use Rate with Peak Time Rebate: number of customers enrolled	#				
Real-time Pricing: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Real-time Pricing: number of customers with access	#				
Real-time Pricing: number of customers enrolled	#			8	
Real-time Pricing with Critical Peak Pricing: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Real-time Pricing with Critical Peak Pricing: number of customers with access	#				
Real-time Pricing with Critical Peak Pricing: number of customers enrolled	#				
Real-time Pricing with Peak Time Rebate: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Real-time Pricing with Peak Time Rebate: number of customers with access	#				
Real-time Pricing with Peak Time Rebate: number of customers enrolled	#				
Variable Peak Pricing: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Variable Peak Pricing: number of customers with access	#				
Variable Peak Pricing: number of customers enrolled	#				
Pre-pay Pricing: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Pre-pay Pricing: number of customers with access	#				
Pre-pay Pricing: number of customers enrolled	#				
Net Metering: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input checked="" type="checkbox"/>	

Page 11 of 24 Custom Created: October 4, 2011 Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 2, 2012		
		Period	Start: Apr 1, 2012	End: Jun 30, 2012	Submission Due Date: July 31, 2012
Implemented Rate Plans		Units	Project	System	
Net Metering: number of customers with access	#				
Net Metering: number of customers enrolled	#			286	
Other program available	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other programs: number of customers with access	#				
Other programs: number of customers enrolled	#				
Other program available	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other programs: number of customers with access	#				
Other programs: number of customers enrolled	#				
Other program available	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other programs: number of customers with access	#				
Other programs: number of customers enrolled	#				
Rate Decoupling: is implemented?	yes/ no		<input type="checkbox"/>		
Rate Plan Descriptions					
	Project	System			
Flat Rate	N/A	KCP&L has multiple residential and C&I Flat Rates that occur during both summer and winter. We are not able to calculate an accurate number for how many customers have access.			
Flat Rate with Critical Peak Pricing	N/A	N/A			

Page 12 of 24 Custom Created: October 4, 2011 Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 2, 2012		
		Period	Start: Apr 1, 2012	End: Jun 30, 2012	Submission Due Date: July 31, 2012
Rate Plan Descriptions					
	Project	System			
Flat Rate with Peak Time Rebate	N/A	N/A			
Tiered Rate	N/A	KCPL has multiple existing residential and C&I Tiered Rates. A majority of those are declining block rates. We are not able to calculate an accurate number for how many customers have access.			
Tiered Rate with Critical Peak Pricing	N/A	N/A			
Tiered Rate with Peak Time Rebate	N/A	N/A			
Time of Use Rate	A new residential TOU rate will be piloted as part of this project to augment the evaluation of customer systems and devices.	KCPL has multiple existing residential and C&I TOU Rates. We are not able to calculate an accurate number for how many customers have access.			
Time of Use Rate with Critical Peak Pricing	N/A	N/A			

Page 13 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 2, 2012		
		Period	Start: Apr 1, 2012	End: Jun 30, 2012	Submission Due Date: July 31, 2012
Rate Plan Descriptions					
	Project	System			
Time of Use Rate with Peak Time Rebate	N/A	N/A			
Real-Time Rate	N/A	KCPL has multiple existing RTP rates for commercial and industrial customers. We are not able to calculate an accurate number for how many customers have access.			
Real-time Rate with Critical Peak Pricing	N/A	N/A			
Real-time Rate with Peak Time Rebate	N/A	N/A			
Variable Peak Pricing	N/A	N/A			
Pre-paid Rate	N/A	N/A			

Page 14 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

		Project DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
Filing build_quarterly		Build Metrics Quarterly Report Quarter 2, 2012	
Period Start: Apr 1, 2012		End: Jun 30, 2012 Submission Due Date: July 31, 2012	

Rate Plan Descriptions		
	Project	System
Net Metering Rate	N/A	KCP&L has multiple existing residential and C&I Net Metering Rates. We are not able to calculate an accurate number for how many customers have access.
Other program	N/A	N/A
Other program	N/A	N/A
Other program	N/A	N/A
Additional Project Descriptions	N/A	

Page 15 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

		Project DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
Filing build_quarterly		Build Metrics Quarterly Report Quarter 2, 2012	
Period Start: Apr 1, 2012		End: Jun 30, 2012 Submission Due Date: July 31, 2012	

Distributed Energy Resources - Build Metrics			
<i>All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.</i>			
Distributed Energy Resources	Units	Project	System
Distributed generation: number of units	#	2	276
Distributed generation: installed capacity	KW	102.4	4,305.7
Distributed generation: total energy delivered	* kWh	46,025	
Energy storage: number of units	#	0	0
Energy storage: installed capacity	KW	0.0	0.0
Energy storage: total energy delivered	* kWh	0.0	0.0
Plug-in electric vehicles charging points: number of units	#	1	11
Plug-in electric vehicles charging points: installed capacity	KW	4	74
Plug-in electric vehicles charging points: total energy delivered	* kWh	0.0	1,710
DER/DG interconnection equipment: number of units	#		

* Energy delivered should be reported just for the quarter being reported, not cumulative for the project to-date.

Distributed Energy Resource Descriptions		
	Project	System
Distributed Generation Interface Description	All DG installed is non-dispatchable utility-owned PV that is being metered separately. All project EV chargers are installed behind customer meters. Interfaces currently limited to measuring data.	Non-dispatchable utility-owned DG and EV Chargers. All EV chargers are installed behind customer meters. Interfaces currently limited to measuring data. We cannot determine the total energy delivered since we only have net kWh numbers, not total generation behind customer meters.

Page 16 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 2, 2012	
Period	Start: Apr 1, 2012	End: Jun 30, 2012	Submission Due Date: July 31, 2012

Additional Project Descriptions

Distributed Energy Resources' Installed Costs	Units	Project Funded	Cost Share
DER Interface Control Systems	\$	0	0
Communications Equipment	\$	0	0
DER/DG Interconnection Equipment	\$	0	0
Renewable DER	\$	0	0
Distributed Generation Equipment	\$	348,137	348,137
Stationary Electric Storage Equipment	\$	0	0
PEVs and Charging Stations	\$	3,846	3,846
Other Costs	\$		
Other Cost Description	N/A		

Page 17 of 24 Custom Created: October 4, 2011



Master Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 2, 2012	
Period	Start: Apr 1, 2012	End: Jun 30, 2012	Submission Due Date: July 31, 2012

Electric Distribution System Assets - Build Metrics

All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.

Implemented Distribution Devices	Units	Project	System
Portion of system with SCADA	%	0	10.5
Portion of system with Distribution Automation (DA)	%	0	75
Automated Feeder Switches: number of devices installed	#	0	96
Automated Capacitors: number of devices installed	#	0.0	2,072
Automated Regulators: number of devices installed	#	0	3
Feeder Monitors: number of devices installed	#	0	0
Remote Fault Indicators: number of devices installed	#	0.0	222
Transformer Monitors (line): number of devices installed	#	0	0
Smart Relays: number of devices installed	#	62	2,273
Fault Current Limiter: number of devices installed	#	0	0
Other devices installed	#		
Other devices installed	#		
Other devices installed	#		

DA Applications in Operation	Units	Project	System
Fault Location, Isolation, and Service Restoration (FLISR): is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Voltage Optimization: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Feeder Peak Load Management: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Microgrids: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other DA Application: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>

Page 16 of 24 Custom Created: October 4, 2011



Master Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 2, 2012	
Period	Start: Apr 1, 2012	End: Jun 30, 2012	Submission Due Date: July 31, 2012

Distribution Management System Integration

	Units	Project	System
AMIS: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Outage Management System: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Transmission Management System: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Distributed Energy Resources: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other Systems: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>

Distribution Device Description

	Project	System
SCADA	Distribution SCADA will be installed in the project area.	ABB Network Manager (EMS)
Portion of system with SCADA	Distribution SCADA will be installed in the project area.	The ABB Network Manager (EMS) communicates with 70% of feeder breakers, but only 15% of those have communications capable of supporting Smart Grid functionality.
Portion of system with DA	DA has not been implemented yet.	KCP&L has locally automated devices such as capacitors, voltage monitors, faulted circuit indicators, and reclosers across the distribution system. 75% represents an estimate of coverage based on number of circuits with one or more of these devices.
DA devices	DA devices have not yet been installed and/or integrated.	There is a mix of locally automated capacitors, voltage monitors, faulted circuit indicators, and reclosers across distribution system.

Page 19 of 24 Custom Created: October 4, 2011



Master Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 2, 2012	
Period	Start: Apr 1, 2012	End: Jun 30, 2012	Submission Due Date: July 31, 2012

Distribution Device Description

	Project	System
DA communications network	DA network has not been installed yet.	Lands+Gyr AMR system and Telemetric/Sensus cellular-based system.
Other device	N/A	N/A
N/A		
Other device	N/A	N/A
N/A		
Other device	N/A	N/A
N/A		

Distribution Application Descriptions

	Project	System
FLISR	FLISR has not yet been implemented	FLISR has not yet been implemented

Page 20 of 24 Custom Created: October 4, 2011



Master Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 2, 2012	
		Period	Start: Apr 1, 2012	End: Jun 30, 2012 Submission Due Date: July 31, 2012
Voltage Optimization	Voltage Optimization has not been implemented yet.	A Dynamic Voltage Control (DVC) system exists on 203 buses within metropolitan Kansas City. This system is able to dynamically reduce voltage through load tap changers to achieve voltage changes in coordination with locally controlled cap banks.		
Feeder Peak Load Management	Feeder Peak Load Management has not been implemented yet.	System peak loads are curtailed through utilization of the DVC system and existing PCT program operated by Honeywell.		
Microgrids	N/A	N/A		
Other DA Applications	N/A	N/A		
Distribution Management Integration Descriptions				
	Project	System		
AMI	Not integrated yet	Not integrated yet		
Outage Management	Not integrated yet	Not integrated yet		

Page 21 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 2, 2012	
		Period	Start: Apr 1, 2012	End: Jun 30, 2012 Submission Due Date: July 31, 2012
Distribution Management Integration Descriptions				
	Project	System		
Transmission Management	N/A	N/A		
DER Systems	Not integrated yet	Not integrated yet		
Distribution Management System	Not integrated yet	Not integrated yet		
Other Systems	N/A	N/A		
Additional Project Descriptions:	N/A			
Distribution Systems Installed Costs				
Back Office Systems	\$	228,002	228,002	
Distribution Management System	\$	0	0	
Communications Equipment and SCADA	\$	0	0	

Page 22 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 2, 2012	
Period	Start: Apr 1, 2012	End: Jun 30, 2012	Submission Due Date: July 31, 2012

Distribution Systems Installed Costs	Units	Project Funded	Cost Share
Feeder Monitor/Indicator	\$	0	0
Substation Monitors	\$	854,503	854,503
Automated Feeder Switches	\$	0	0
Capacitor Automation Equipment	\$	0	0
Regulator Automation Equipment	\$	0	0
Fault Current Limiter Equipment	\$	0	0
Cost of other devices installed N/A	\$		
Cost of other devices installed N/A	\$		
Cost of other devices installed N/A	\$		
Other Costs	\$		
Other Cost Description	N/A		

Page 23 of 24 Custom Created: October 4, 2011



Master Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 2, 2012	
Period	Start: Apr 1, 2012	End: Jun 30, 2012	Submission Due Date: July 31, 2012

Submit
Print Form

Page 24 of 24 Custom Created: October 4, 2011



Master Updated: April 9, 2011 Schema Version: 1.2

S.10 2012 Q3

SMARTGRID.GOV		Project	DE-OE000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2012		
		Period	Start: Jul 1, 2012	End: Sep 30, 2012	Submission Due Date: October 31, 2012
AMI Assets - Build Metrics					
<i>All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.</i>					
AMI End Points Installed		Units	Project	System	
End Points (meters) installed and operational	#		13,217	13,217	
Portion of customers with AMI residential	#		12,018	12,018	
Portion of customers with AMI commercial	#		1,201	1,201	
Portion of customers with AMI industrial	#		0	0	
Implemented Meter Features		Units	Project	System	
Reading interval for residential meters	minutes		15	15	
Reading interval for commercial meters	minutes		15	15	
Reading interval for industrial meters	minutes				
Remote Connect/Disconnect: is feature implemented?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Remote Connect/Disconnect: number of meters with feature implemented	#				
Outage Reporting: is feature implemented?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Outage Reporting: number of meters with feature implemented	#		13,217	13,217	
Power Quality Measurement: is feature implemented?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Power Quality Measurement: number of meters with feature implemented	#				
Tamper Detection: is feature implemented?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Tamper Detection: number of meters with feature implemented	#		13,217	13,217	
Other feature implemented	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other feature: number of meters with feature implemented	#				
Other feature implemented	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other feature: number of meters with feature implemented	#				
Other feature implemented	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other feature: number of meters with feature implemented	#				

Page 1 of 24 Custom Created: October 4, 2011 Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2012		
		Period	Start: Jul 1, 2012	End: Sep 30, 2012	Submission Due Date: October 31, 2012
Implemented Meter Features		Units	Project	System	
Other feature: number of meters with feature implemented	#				
Implemented Enterprise Integration		Units	Project	System	
Billing System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Customer Information System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Outage Management System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Distribution Management System: is integration complete?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other Enterprise Systems: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
AMI System Descriptions					
	Project	System			
Backhaul Network	Hybrid of Fiber and Wireless Raven radio with network carrier	Hybrid of Fiber and Wireless Raven radio with network carrier			
Meter Communication Network	Lands+Gyr Gridstream RF 900MHz - Collectors and Routers	Lands+Gyr Gridstream RF 900MHz - Collectors and Routers			
Headend System	Lands+Gyr Command Center	Lands+Gyr Command Center			
Meter Data Management System	eMeter/Siemens	eMeter/Siemens			

Page 2 of 24 Custom Created: October 4, 2011 Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2012		
		Period	Start: Jul 1, 2012	End: Sep 30, 2012	Submission Due Date: October 31, 2012
AMI System Descriptions					
	Project	System			
Meter Data Analysis	The project AMI was incorporated into the existing AMR – MDA interfaces. AMI daily register reads and 15-min interval reads are loaded into MDA (DataRaker) on a daily basis.	The project AMI was incorporated into the existing AMR – MDA interfaces. AMI daily register reads and 15-min interval reads are loaded into MDA (DataRaker) on a daily basis.			
Other Meter Feature	N/A	N/A			
Other Meter Feature	N/A	N/A			
Other Meter Feature	N/A	N/A			
AMI Enterprise Integration Descriptions					
	Project	System			
Billing System	AMI is integrated with enterprise Oracle CIS.	AMI is integrated with enterprise Oracle CIS.			

Page 3 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2012		
		Period	Start: Jul 1, 2012	End: Sep 30, 2012	Submission Due Date: October 31, 2012
AMI Enterprise Integration Descriptions					
	Project	System			
Customer Information System	AMI is integrated with KCPL enterprise Oracle CIS. The project AMI was incorporated into the existing AMR – CIS interfaces. CIS daily account/meter synchronization. AMI provides CIS daily register meter reads for direct billing. CIS daily billing cycle-to-date usage info and bill prediction pushed to IHDs via AMI Network.	AMI is integrated with KCPL enterprise Oracle CIS. The project AMI was incorporated into the existing AMR – CIS interfaces. CIS daily account/meter synchronization. AMI provides CIS daily register meter reads for direct billing. CIS daily billing cycle-to-date usage info and bill prediction pushed to IHDs via AMI Network.			
Outage Management System	AMI is integrated with enterprise OMS. An additional project OMS (redundant) will also be implemented in conjunction with a DMS. The project AMI was incorporated into the existing AMR to enterprise OMS interfaces including meter outage alerts and meter "ping" functionality to verify power restoration.	AMI is integrated with enterprise OMS. An additional project OMS (redundant) will also be implemented in conjunction with a DMS. The project AMI was incorporated into the existing AMR to enterprise OMS interfaces including meter outage alerts and meter "ping" functionality to verify power restoration.			
Distribution Management System	Not yet integrated	Not yet integrated			
Other Enterprise Systems	Data Mining and Analysis Tool (DataRaker) covered by the MDA	Data Mining and Analysis Tool (DataRaker) covered by the MDA			
Additional Project Descriptions	N/A				
AMI Installed Costs					
	Units	Project Funded	Cost Share		
Back Office Systems	\$	1,723,180	1,723,180		
Communications Equipment	\$	113,606	113,606		
AMI Smart Meters	\$	2,112,603	2,112,603		

Page 4 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2012	
Period	Start: Jul 1, 2012	End: Sep 30, 2012	Submission Due Date: October 31, 2012

AMI Installed Costs	Units	Project Funded	Cost Share
Other Costs	5		
Other Costs Description	N/A		

Page 5 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2012	
Period	Start: Jul 1, 2012	End: Sep 30, 2012	Submission Due Date: October 31, 2012

Customer Systems Assets - Build Metrics

All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.

Implemented Customer Systems	Units	Project	System
In-Home display: devices installed	#	656	656
Direct Load Control Devices: devices installed	#	63	63
Programmable Communicating Thermostats: devices installed	#	81	53,373
Smart Appliances: devices installed	#	0	0
Energy Management Devices/Systems: devices installed	#	0.0	0.0
Other Devices installed	#	30	30
Other Devices installed	#		
Other Devices installed	#		

Web Portal	Units	Project	System
Web portal is portal in production?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Customers with access	#	11,681	11,681
Customers with active accounts	#	1,807	1,807

Customer System Descriptions	Project	System
In-Home Displays	Tendril InSight	Tendril InSight

Page 6 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2012		
		Period	Start: Jul 1, 2012	End: Sep 30, 2012	Submission Due Date: October 31, 2012
Customer System Descriptions					
	Project	System			
Direct Load Control Devices	Tendril Volt	Tendril Volt			
Programmable Communicating Thermostats	Tendril Setpoint	Tendril Setpoint and Honeywell PCTs			
Smart Appliances	N/A	N/A			
Energy Mgmt. Systems	N/A	N/A			
Web Portal	Tendril Energize Web Portal	Tendril Energize Web Portal			
Home Area Network	Zigbee SEP 1.0	Zigbee SEP 1.0			

Page 7 of 24 Custom Created: October 4, 2011 Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2012		
		Period	Start: Jul 1, 2012	End: Sep 30, 2012	Submission Due Date: October 31, 2012
Customer System Descriptions					
	Project	System			
Other Device	Tendril Transport Gateway	Tendril Transport Gateway			
HAN Gateway					
Other Device	N/A	N/A			
Other Device	N/A	N/A			
Additional Project Descriptions	N/A				

Customer System Installed Costs	Units	Project Funded	Cost Share
Back Office Systems	\$	304,096	304,096
Web Portals	\$	485,105	485,105
In-Home Displays	\$	144,633	144,633
Direct Load Control Devices	\$	86,669	86,669
Smart Appliances	\$	0	0
Programmable Communicating Thermostats	\$	228,833	228,833
Cost of other devices installed: HAN Gateway	\$	167,362	167,362

Page 8 of 24 Custom Created: October 4, 2011 Meter Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2012	
Period	Start: Jul 1, 2012	End: Sep 30, 2012	Submission Due Date: October 31, 2012

Customer System Installed Costs	Units	Project Funded	Cost Share
Cost of other devices installed	\$		
Cost of other devices installed	\$		
Other Costs	\$	264,353	264,353
Other Cost Description	Program delivery costs including KCP&L labor for program administration, analysis, and customer engagement as well as vendor travel expenses.		

Page 9 of 24 Custom Created: October 4, 2011

Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2012	
Period	Start: Jul 1, 2012	End: Sep 30, 2012	Submission Due Date: October 31, 2012

Pricing Programs - Build Metrics

All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.

Implemented Rate Plans	Units	Project	System
Flat Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Flat Rate: number of customers with access	#		
Flat Rate: number of customers enrolled	#		542,210
Flat Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Critical Peak Pricing: number of customers with access	#		
Flat Rate with Critical Peak Pricing: number of customers enrolled	#		
Flat Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Peak Time Rebate: number of customers with access	#		
Flat Rate with Peak Time Rebate: number of customers enrolled	#		
Tiered Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Tiered Rate: number of customers with access	#		
Tiered Rate: number of customers enrolled	#		300,522
Tiered Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Critical Peak Pricing: number of customers with access	#		
Tiered Rate with Critical Peak Pricing: number of customers enrolled	#		
Tiered Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Peak Time Rebate: number of customers with access	#		
Tiered Rate with Peak Time Rebate: number of customers enrolled	#		
Time of Use Rate: is the pricing program available?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Time of Use Rate: number of customers with access	#	12,016	

Page 10 of 24 Custom Created: October 4, 2011

Metric Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2012		
		Period	Start: Jul 1, 2012	End: Sep 30, 2012	Submission Due Date: October 31, 2012
Implemented Rate Plans		Units	Project	System	
Time of Use Rate: number of customers enrolled	#		68	494	
Time of Use Rate with Critical Peak Pricing: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Time of Use Rate with Critical Peak Pricing: number of customers with access	#				
Time of Use Rate with Critical Peak Pricing: number of customers enrolled	#				
Time of Use Rate with Peak-Time Rebate: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Time of Use Rate with Peak-Time Rebate: number of customers with access	#				
Time of Use Rate with Peak-Time Rebate: number of customers enrolled	#				
Real-time Pricing: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Real-time Pricing: number of customers with access	#				
Real-time Pricing: number of customers enrolled	#			8	
Real-time Pricing with Critical Peak Pricing: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Real-time Pricing with Critical Peak Pricing: number of customers with access	#				
Real-time Pricing with Critical Peak Pricing: number of customers enrolled	#				
Real-time Pricing with Peak-Time Rebate: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Real-time Pricing with Peak-Time Rebate: number of customers with access	#				
Real-time Pricing with Peak-Time Rebate: number of customers enrolled	#				
Variable Peak Pricing: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Variable Peak Pricing: number of customers with access	#				
Variable Peak Pricing: number of customers enrolled	#				
Pre-pay Pricing: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Pre-pay Pricing: number of customers with access	#				
Pre-pay Pricing: number of customers enrolled	#				
Net Metering: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input checked="" type="checkbox"/>	

Page 11 of 24 Custom Created: October 4, 2011

U.S. DEPARTMENT OF ENERGY Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2012		
		Period	Start: Jul 1, 2012	End: Sep 30, 2012	Submission Due Date: October 31, 2012
Implemented Rate Plans		Units	Project	System	
Net Metering: number of customers with access	#				
Net Metering: number of customers enrolled	#			351	
Other program available	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other programs: number of customers with access	#				
Other programs: number of customers enrolled	#				
Other program available	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other programs: number of customers with access	#				
Other programs: number of customers enrolled	#				
Other program available	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other programs: number of customers with access	#				
Other programs: number of customers enrolled	#				
Rate Decoupling: is implemented?	yes/ no		<input type="checkbox"/>		
Rate Plan Descriptions					
	Project	System			
Flat Rate	N/A	KCP&L has multiple residential and C&I Flat Rates that occur during both summer and winter. We are not able to calculate an accurate number for how many customers have access.			
Flat Rate with Critical Peak Pricing	N/A	N/A			

Page 12 of 24 Custom Created: October 4, 2011

U.S. DEPARTMENT OF ENERGY Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2012	
		Period	Start: Jul 1, 2012	End: Sep 30, 2012 Submission Due Date: October 31, 2012
Rate Plan Descriptions				
	Project	System		
Flat Rate with Peak Time Rebate	N/A	N/A		
Tiered Rate	N/A	KCPL has multiple existing residential and C&I Tiered Rates. A majority of those are declining block rates. We are not able to calculate an accurate number for how many customers have access.		
Tiered Rate with Critical Peak Pricing	N/A	N/A		
Tiered Rate with Peak Time Rebate	N/A	N/A		
Time of Use Rate	A new residential TOU rate is being piloted as part of this project to augment the evaluation of customer systems and devices.	KCPL has multiple existing residential and C&I TOU Rates. We are not able to calculate an accurate number for how many customers have access.		
Time of Use Rate with Critical Peak Pricing	N/A	N/A		

Page 13 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2012	
		Period	Start: Jul 1, 2012	End: Sep 30, 2012 Submission Due Date: October 31, 2012
Rate Plan Descriptions				
	Project	System		
Time of Use Rate with Peak Time Rebate	N/A	N/A		
Real-Time Rate	N/A	KCPL has multiple existing RTP rates for commercial and industrial customers. We are not able to calculate an accurate number for how many customers have access.		
Real-time Rate with Critical Peak Pricing	N/A	N/A		
Real-time Rate with Peak Time Rebate	N/A	N/A		
Variable Peak Pricing	N/A	N/A		
Pre-paid Rate	N/A	N/A		

Page 14 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

		Project DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration) Filing build_quarterly Build Metrics Quarterly Report Quarter 3, 2012 Period Start: Jul 1, 2012 End: Sep 30, 2012 Submission Due Date: October 31, 2012
Rate Plan Descriptions		
	Project	System
Net Metering Rate	N/A	KCP&L has multiple existing residential and C&I Net Metering Rates. We are not able to calculate an accurate number for how many customers have access.
Other program	N/A	N/A
Other program	N/A	N/A
Other program	N/A	N/A
Additional Project Descriptions	N/A	

Page 15 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

		Project DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration) Filing build_quarterly Build Metrics Quarterly Report Quarter 3, 2012 Period Start: Jul 1, 2012 End: Sep 30, 2012 Submission Due Date: October 31, 2012
Distributed Energy Resources - Build Metrics		
<i>All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.</i>		
Distributed Energy Resources	Units	Project System
Distributed generation: number of units	#	2 338
Distributed generation: installed capacity	KW	102.4 5,528.7
Distributed generation: total energy delivered	* kWh	41,661
Energy storage: number of units	#	1 1
Energy storage: installed capacity	KW	1,000 1,000
Energy storage: total energy delivered	* kWh	0.0 0.0
Plug-in electric vehicles charging points: number of units	#	1 11
Plug-in electric vehicles charging points: installed capacity	KW	4 74
Plug-in electric vehicles charging points: total energy delivered	* kWh	0.0 1,634
DER/DG interconnection equipment: number of units	#	

* Energy delivered should be reported just for the quarter being reported, not cumulative for the project to-date.

Distributed Energy Resource Descriptions		
	Project	System
Distributed Generation Interface Description	All DG installed is non-dispatchable utility-owned PV that is being metered separately. All project EV chargers are installed behind customer meters. Interfaces currently limited to measuring data.	Non-dispatchable utility-owned DG and EV Chargers. All EV chargers are installed behind customer meters. Interfaces currently limited to measuring data.

Page 16 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2012	
Period	Start: Jul 1, 2012	End: Sep 30, 2012	Submission Due Date: October 31, 2012

Additional Project Descriptions:

Distributed Energy Resources' Installed Costs	Units	Project Funded	Cost Share
DER Interface Control Systems	\$		
Communications Equipment	\$		
DER/DG Interconnection Equipment	\$		
Renewable DER	\$	380,743	380,743
Distributed Generation Equipment	\$		
Stationary Electric Storage Equipment	\$	3,757,159	3,757,159
PEVs and Charging Stations	\$	3,846	3,846
Other Costs	\$		
Other Cost Description	N/A		

Page 17 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2012	
Period	Start: Jul 1, 2012	End: Sep 30, 2012	Submission Due Date: October 31, 2012

Electric Distribution System Assets - Build Metrics

All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.

Implemented Distribution Devices	Units	Project	System
Portion of system with SCADA	%	0	10.5
Portion of system with Distribution Automation (DA)	%	0	80
Automated Feeder Switches: number of devices installed	#	0	96
Automated Capacitors: number of devices installed	#	29	2,122
Automated Regulators: number of devices installed	#	0	3
Feeder Monitors: number of devices installed	#	0	0
Remote Fault Indicators: number of devices installed	#	0.0	229
Transformer Monitors (line): number of devices installed	#	0	0
Smart Relays: number of devices installed	#	63	2,277
Fault Current Limiter: number of devices installed	#	0	0
Other devices installed	#		
Other devices installed	#		
Other devices installed	#		

DA Applications in Operation	Units	Project	System
Fault Location, Isolation, and Service Restoration (FLISR): is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Voltage Optimization: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Feeder Peak Load Management: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Microgrids: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other DA Application: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>

Page 16 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2012	
Period	Start: Jul 1, 2012	End: Sep 30, 2012	Submission Due Date: October 31, 2012

Distribution Management System Integration

	Units	Project	System
AMI: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Outage Management System: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Transmission Management System: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Distributed Energy Resources: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other Systems: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>

Distribution Device Description

	Project	System
SCADA	Distribution SCADA will be installed in the project area.	ABB Network Manager (EMS)
Portion of system with SCADA	Distribution SCADA will be installed in the project area.	The ABB Network Manager (EMS) communicates with 70% of feeder breakers, but only 15% of those have communications capable of supporting Smart Grid functionality.
Portion of system with DA	DA has not been implemented yet.	KCP&L has locally automated devices such as capacitors, voltage monitors, faulted circuit indicators, and reclosers across the distribution system. 80% represents an estimate of coverage based on number of circuits with one or more of these devices.
DA devices	DA devices have not yet been installed and/or integrated.	There is a mix of locally automated capacitors, voltage monitors, faulted circuit indicators, and reclosers across distribution system.

Page 19 of 24 Custom Created: October 4, 2011



Master Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2012	
Period	Start: Jul 1, 2012	End: Sep 30, 2012	Submission Due Date: October 31, 2012

Distribution Device Description

	Project	System
DA communications network	DA network has not been installed yet.	Lands+Gyr AMR system and Telemetric/Sensus cellular-based system.
Other device	N/A	N/A
N/A		
Other device	N/A	N/A
N/A		
Other device	N/A	N/A
N/A		

Distribution Application Descriptions

	Project	System
FLISR	FLISR has not yet been implemented	FLISR has not yet been implemented

Page 20 of 24 Custom Created: October 4, 2011



Master Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2012	
		Period	Start: Jul 1, 2012	End: Sep 30, 2012 Submission Due Date: October 31, 2012
Voltage Optimization	Voltage Optimization has not been implemented yet.	A Dynamic Voltage Control (DVC) system exists on 203 buses within metropolitan Kansas City. This system is able to dynamically reduce voltage through load tap changers to achieve voltage changes in coordination with locally controlled cap banks.		
Feeder Peak Load Management	Feeder Peak Load Management has not been implemented yet.	System peak loads are curtailed through utilization of the DVC system and existing PCT program operated by Honeywell.		
Microgrids	N/A	N/A		
Other DA Applications	N/A	N/A		
Distribution Management Integration Descriptions				
	Project	System		
AMI	Not integrated yet	Not integrated yet		
Outage Management	Not integrated yet	Not integrated yet		

Page 21 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2012	
		Period	Start: Jul 1, 2012	End: Sep 30, 2012 Submission Due Date: October 31, 2012
Distribution Management Integration Descriptions				
	Project	System		
Transmission Management	N/A	N/A		
DER Systems	Not integrated yet	Not integrated yet		
Distribution Management System	Not integrated yet	Not integrated yet		
Other Systems	N/A	N/A		
Additional Project Descriptions:	N/A			
Distribution Systems Installed Costs				
	Units	Project Funded	Cost Share	
Back Office Systems	\$	283,294	283,294	
Distribution Management System	\$			
Communications Equipment and SCADA	\$			

Page 22 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2012	
Period	Start: Jul 1, 2012	End: Sep 30, 2012	Submission Due Date: October 31, 2012

Distribution Systems Installed Costs	Units	Project Funded	Cost Share
Feeder Monitor/Indicator	\$		
Substation Monitors	\$	1,108,824	1,108,824
Automated Feeder Switches	\$		
Capacitor Automation Equipment	\$	133,858	133,858
Regulator Automation Equipment	\$		
Fault Current Limiter Equipment	\$		
Cost of other devices installed N/A	\$		
Cost of other devices installed N/A	\$		
Cost of other devices installed N/A	\$		
Other Costs	\$		
Other Cost Description	N/A		

Page 23 of 24 Custom Created: October 4, 2011



Master Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2012	
Period	Start: Jul 1, 2012	End: Sep 30, 2012	Submission Due Date: October 31, 2012

Submit
Print Form

Page 24 of 24 Custom Created: October 4, 2011



Master Updated: April 9, 2011 Schema Version: 1.2

S.11 2012 Q4

SMARTGRID.GOV		Project	DE-OE000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metric Quarterly Report Quarter 4, 2012	
		Period	Start: Oct 1, 2012	End: Dec 31, 2012 Submission Due Date: January 31, 2013

AMI Assets - Build Metrics			
<i>All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.</i>			
AMI End Points Installed	Units	Project	System
End Points (meters) installed and operational	#	13,415	13,415
Portion of customers with AMI residential	#	12,182	12,182
Portion of customers with AMI commercial	#	1,233	1,233
Portion of customers with AMI industrial	#	0	0
Implemented Meter Features	Units	Project	System
Reading interval for residential meters	minutes	15	15
Reading interval for commercial meters	minutes	15	15
Reading interval for industrial meters	minutes		
Remote Connect/Disconnect: is feature implemented?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Remote Connect/Disconnect: number of meters with feature implemented	#		
Outage Reporting: is feature implemented?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Outage Reporting: number of meters with feature implemented	#	13,415	13,415
Power Quality Measurement: is feature implemented?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Power Quality Measurement: number of meters with feature implemented	#		
Tamper Detection: is feature implemented?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Tamper Detection: number of meters with feature implemented	#	13,415	13,415
Other feature implemented	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other feature: number of meters with feature implemented	#		
Other feature implemented	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other feature: number of meters with feature implemented	#		
Other feature implemented	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>

Page 1 of 24 Custom Created: October 8, 2011 Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metric Quarterly Report Quarter 4, 2012	
		Period	Start: Oct 1, 2012	End: Dec 31, 2012 Submission Due Date: January 31, 2013

Implemented Meter Features	Units	Project	System
Other feature: number of meters with feature implemented	#		
Implemented Enterprise Integration	Units	Project	System
Billing System: is integration complete?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Customer Information System: is integration complete?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Outage Management System: is integration complete?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Distribution Management System: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other Enterprise Systems: is integration complete?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
AMI System Descriptions	Project	System	
Backhaul Network	Hybrid of Fiber and Wireless Raven radio with network carrier	Hybrid of Fiber and Wireless Raven radio with network carrier	
Meter Communication Network	Lands+Gyr Gridstream RF 900MHz - Collectors and Routers	Lands+Gyr Gridstream RF 900MHz - Collectors and Routers	
Headend System	Lands+Gyr Command Center	Lands+Gyr Command Center	
Meter Data Management System	eMeter/Siemens	eMeter/Siemens	

Page 2 of 24 Custom Created: October 8, 2011 Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metric Quarterly Report Quarter 4, 2012	
		Period	Start: Oct 1, 2012	End: Dec 31, 2012 Submission Due Date: January 31, 2013
AMI System Descriptions				
	Project	System		
Meter Data Analysis	The project AMI was incorporated into the existing AMR – MDA interfaces. AMI daily register reads and 15-min interval reads are loaded into MDA (DataRaker) on a daily basis.	The project AMI was incorporated into the existing AMR – MDA interfaces. AMI daily register reads and 15-min interval reads are loaded into MDA (DataRaker) on a daily basis.		
Other Meter Feature	N/A	N/A		
Other Meter Feature	N/A	N/A		
Other Meter Feature	N/A	N/A		
AMI Enterprise Integration Descriptions				
	Project	System		
Billing System	AMI is integrated with enterprise Oracle CIS.	AMI is integrated with enterprise Oracle CIS.		

Page 3 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metric Quarterly Report Quarter 4, 2012	
		Period	Start: Oct 1, 2012	End: Dec 31, 2012 Submission Due Date: January 31, 2013
AMI Enterprise Integration Descriptions				
	Project	System		
Customer Information System	AMI is integrated with KCPL enterprise Oracle CIS. The project AMI was incorporated into the existing AMR – CIS interfaces. CIS daily account/meter synchronization. AMI provides CIS daily register meter reads for direct billing. CIS daily billing cycle-to-date usage info and bill prediction pushed to IHDs via AMI Network.	AMI is integrated with KCPL enterprise Oracle CIS. The project AMI was incorporated into the existing AMR – CIS interfaces. CIS daily account/meter synchronization. AMI provides CIS daily register meter reads for direct billing. CIS daily billing cycle-to-date usage info and bill prediction pushed to IHDs via AMI Network.		
Outage Management System	AMI is integrated with enterprise OMS. An additional project OMS (redundant) will also be implemented in conjunction with a DMS. The project AMI was incorporated into the existing AMR to enterprise OMS interfaces including meter outage alerts and meter "ping" functionality to verify power restoration.	AMI is integrated with enterprise OMS. An additional project OMS (redundant) will also be implemented in conjunction with a DMS. The project AMI was incorporated into the existing AMR to enterprise OMS interfaces including meter outage alerts and meter "ping" functionality to verify power restoration.		
Distribution Management System	Not yet integrated	Not yet integrated		
Other Enterprise Systems	Data Mining and Analysis Tool (DataRaker) covered by the MDA	Data Mining and Analysis Tool (DataRaker) covered by the MDA		
Additional Project Descriptions	N/A			
AMI Installed Costs				
	Units	Project Funded	Cost Share	
Back Office Systems	\$	1,813,054	1,813,054	
Communications Equipment	\$	113,746	113,746	
AMI Smart Meters	\$	2,112,395	2,112,395	

Page 4 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metric Quarterly Report Quarter 4, 2012	
Period	Start: Oct 1, 2012	End: Dec 31, 2012	Submission Due Date: January 31, 2013

AMI Installed Costs	Units	Project Funded	Cost Share
Other Costs	5		
Other Costs Description	N/A		

Page 5 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metric Quarterly Report Quarter 4, 2012	
Period	Start: Oct 1, 2012	End: Dec 31, 2012	Submission Due Date: January 31, 2013

Customer Systems Assets - Build Metrics

All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.

Implemented Customer Systems	Units	Project	System
In-Home display: devices installed	#	639	639
Direct Load Control Devices: devices installed	#	116	116
Programmable Communicating Thermostats: devices installed	#	98	53,515
Smart Appliances: devices installed	#	0	0
Energy Management Devices/Systems: devices installed	#	0.0	0.0
Other Devices installed	#	51	51
Other Devices installed	#		
Other Devices installed	#		

Web Portal	Units	Project	System
Web portal is portal in production?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Customers with access	#	11,914	11,914
Customers with active accounts	#	1,893	1,893

Customer System Descriptions	Project	System
In-Home Displays	Tendril InSight	Tendril InSight

Page 6 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metric Quarterly Report Quarter 4, 2012		
		Period	Start: Oct 1, 2012	End: Dec 31, 2012	Submission Due Date: January 31, 2013
Customer System Descriptions					
	Project	System			
Direct Load Control Devices	Tendril Volt	Tendril Volt			
Programmable Communicating Thermostats	Tendril Setpoint	Tendril Setpoint and Honeywell PCTs			
Smart Appliances	N/A	N/A			
Energy Mgmt. Systems	N/A	N/A			
Web Portal	Tendril Energize Web Portal	Tendril Energize Web Portal			
Home Area Network	Zigbee SEP 1.0	Zigbee SEP 1.0			

Page 7 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metric Quarterly Report Quarter 4, 2012		
		Period	Start: Oct 1, 2012	End: Dec 31, 2012	Submission Due Date: January 31, 2013
Customer System Descriptions					
	Project	System			
Other Device	Tendril Transport Gateway	Tendril Transport Gateway			
HAN Gateway					
Other Device	N/A	N/A			
Other Device	N/A	N/A			
Additional Project Descriptions	N/A				

Customer System Installed Costs	Units	Project Funded	Cost Share
Back Office Systems	\$	311,120	311,120
Web Portals	\$	495,739	495,739
In-Home Displays	\$	145,667	145,667
Direct Load Control Devices	\$	86,669	86,669
Smart Appliances	\$	0	0
Programmable Communicating Thermostats	\$	249,507	249,507
Cost of other devices installed: HAN Gateway	\$	187,269	187,269

Page 8 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metric Quarterly Report Quarter 4, 2012	
Period	Start: Oct 1, 2012	End: Dec 31, 2012	Submission Due Date: January 31, 2013

Customer System Installed Costs	Units	Project Funded	Cost Share
Cost of other devices installed	\$		
Cost of other devices installed	\$		
Other Costs	\$	271,965	271,965
Other Cost Description	Program delivery costs including KCP&L labor for program administration, analysis, and customer engagement as well as vendor travel expenses.		

Page 9 of 24 Custom Created: October 4, 2011

Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metric Quarterly Report Quarter 4, 2012	
Period	Start: Oct 1, 2012	End: Dec 31, 2012	Submission Due Date: January 31, 2013

Pricing Programs - Build Metrics

All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.

Implemented Rate Plans	Units	Project	System
Flat Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Flat Rate: number of customers with access	#		
Flat Rate: number of customers enrolled	#		157,082
Flat Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Critical Peak Pricing: number of customers with access	#		
Flat Rate with Critical Peak Pricing: number of customers enrolled	#		
Flat Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Peak Time Rebate: number of customers with access	#		
Flat Rate with Peak Time Rebate: number of customers enrolled	#		
Tiered Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Tiered Rate: number of customers with access	#		
Tiered Rate: number of customers enrolled	#		687,464
Tiered Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Critical Peak Pricing: number of customers with access	#		
Tiered Rate with Critical Peak Pricing: number of customers enrolled	#		
Tiered Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Peak Time Rebate: number of customers with access	#		
Tiered Rate with Peak Time Rebate: number of customers enrolled	#		
Time of Use Rate: is the pricing program available?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Time of Use Rate: number of customers with access	#	12,182	

Page 10 of 24 Custom Created: October 4, 2011

Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metric Quarterly Report Quarter 4, 2012	
Period	Start: Oct 1, 2012	End: Dec 31, 2012	Submission Due Date: January 31, 2013

Implemented Rate Plans	Units	Project	System
Time of Use Rate: number of customers enrolled	#	68	330
Time of Use Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Time of Use Rate with Critical Peak Pricing: number of customers with access	#		
Time of Use Rate with Critical Peak Pricing: number of customers enrolled	#		
Time of Use Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Time of Use Rate with Peak Time Rebate: number of customers with access	#		
Time of Use Rate with Peak Time Rebate: number of customers enrolled	#		
Real-time Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Real-time Pricing: number of customers with access	#		
Real-time Pricing: number of customers enrolled	#		8
Real-time Pricing with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Real-time Pricing with Critical Peak Pricing: number of customers with access	#		
Real-time Pricing with Critical Peak Pricing: number of customers enrolled	#		
Real-time Pricing with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Real-time Pricing with Peak Time Rebate: number of customers with access	#		
Real-time Pricing with Peak Time Rebate: number of customers enrolled	#		
Variable Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Variable Peak Pricing: number of customers with access	#		
Variable Peak Pricing: number of customers enrolled	#		
Pre-pay Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Pre-pay Pricing: number of customers with access	#		
Pre-pay Pricing: number of customers enrolled	#		
Net Metering: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>

Page 11 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metric Quarterly Report Quarter 4, 2012	
Period	Start: Oct 1, 2012	End: Dec 31, 2012	Submission Due Date: January 31, 2013

Implemented Rate Plans	Units	Project	System
Net Metering: number of customers with access	#		
Net Metering: number of customers enrolled	#		452
Other program available	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: number of customers with access	#		
Other programs: number of customers enrolled	#		
Other program available	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: number of customers with access	#		
Other programs: number of customers enrolled	#		
Other program available	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: number of customers with access	#		
Other programs: number of customers enrolled	#		
Rate Decoupling: is implemented?	yes/ no	<input type="checkbox"/>	

Rate Plan Descriptions	Project	System
Flat Rate	N/A	KCP&L has multiple residential and C&I Flat Rates that occur during both summer and winter. We are not able to calculate an accurate number for how many customers have access.
Flat Rate with Critical Peak Pricing	N/A	N/A

Page 12 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		
Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
Filing	build_quarterly	Build Metric Quarterly Report Quarter 4, 2012
Period	Start: Oct 1, 2012	End: Dec 31, 2012 Submission Due Date: January 31, 2013
Rate Plan Descriptions		
	Project	System
Flat Rate with Peak Time Rebate	N/A	N/A
Tiered Rate	N/A	KCP&L has multiple existing residential and C&I Tiered Rates. A majority of those are declining block rates. We are not able to calculate an accurate number for how many customers have access.
Tiered Rate with Critical Peak Pricing	N/A	N/A
Tiered Rate with Peak Time Rebate	N/A	N/A
Time of Use Rate	A new residential TOU rate will be piloted as part of this project to augment the evaluation of customer systems and devices.	KCP&L has multiple existing residential and C&I TOU Rates. We are not able to calculate an accurate number for how many customers have access.
Time of Use Rate with Critical Peak Pricing	N/A	N/A

Page 13 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		
Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
Filing	build_quarterly	Build Metric Quarterly Report Quarter 4, 2012
Period	Start: Oct 1, 2012	End: Dec 31, 2012 Submission Due Date: January 31, 2013
Rate Plan Descriptions		
	Project	System
Time of Use Rate with Peak Time Rebate	N/A	N/A
Real-Time Rate	N/A	KCP&L has multiple existing RTP rates for commercial and industrial customers. We are not able to calculate an accurate number for how many customers have access.
Real-time Rate with Critical Peak Pricing	N/A	N/A
Real-time Rate with Peak Time Rebate	N/A	N/A
Variable Peak Pricing	N/A	N/A
Pre-paid Rate	N/A	N/A

Page 14 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metric Quarterly Report Quarter 4, 2012		
		Period	Start: Oct 1, 2012	End: Dec 31, 2012	Submission Due Date: January 31, 2013
Rate Plan Descriptions					
	Project	System			
Net Metering Rate	N/A	KCPL has multiple existing residential and C&I Net Metering Rates. We are not able to calculate an accurate number for how many customers have access.			
Other program	N/A	N/A			
Other program	N/A	N/A			
Other program	N/A	N/A			
Additional Project Descriptions	N/A				

Page 15 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metric Quarterly Report Quarter 4, 2012		
		Period	Start: Oct 1, 2012	End: Dec 31, 2012	Submission Due Date: January 31, 2013
Distributed Energy Resources - Build Metrics					
<i>All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.</i>					
Distributed Energy Resources		Units	Project	System	
Distributed generation: number of units		#	3	436	
Distributed generation: installed capacity		KW	107.4	7,307.8	
Distributed generation: total energy delivered		* kWh	19,275		
Energy storage: number of units		#	1	1	
Energy storage: installed capacity		KW	1,000	1,000	
Energy storage: total energy delivered		* kWh	0.0	0.0	
Plug-in electric vehicles charging points: number of units		#	4	14	
Plug-in electric vehicles charging points: installed capacity		KW	47	155	
Plug-in electric vehicles charging points: total energy delivered		* kWh	102	1,866	
DER/DG interconnection equipment: number of units		#			
* Energy delivered should be reported just for the quarter being reported, not cumulative for the project to-date.					
Distributed Energy Resource Descriptions					
	Project	System			
Distributed Generation Interface Description	All DG installed is non-dispatchable utility-owned PV that is being metered separately. All project EV chargers are installed behind customer meters. Interfaces currently limited to measuring data.	Non-dispatchable utility-owned DG and EV Chargers. All EV chargers are installed behind customer meters. Interfaces currently limited to measuring data.			

Page 16 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metric Quarterly Report Quarter 4, 2012	
Period	Start: Oct 1, 2012	End: Dec 31, 2012	Submission Due Date: January 31, 2013

Additional Project Descriptions:

Distributed Energy Resources' Installed Costs	Units	Project Funded	Cost Share
DER Interface Control Systems	\$		
Communications Equipment	\$		
DER/DG Interconnection Equipment	\$		
Renewable DER	\$	377,938	377,938
Distributed Generation Equipment	\$		
Stationary Electric Storage Equipment	\$	3,776,477	3,776,477
PEVs and Charging Stations	\$	3,846	3,846
Other Costs	\$		
Other Cost Description	N/A		

Page 17 of 24 Custom Created: October 4, 2011



Master Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metric Quarterly Report Quarter 4, 2012	
Period	Start: Oct 1, 2012	End: Dec 31, 2012	Submission Due Date: January 31, 2013

Electric Distribution System Assets - Build Metrics

All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.

Implemented Distribution Devices	Units	Project	System
Portion of system with SCADA	%	0	10.5
Portion of system with Distribution Automation (DA)	%	50	85
Automated Feeder Switches: number of devices installed	#	0	97
Automated Capacitors: number of devices installed	#	29	2,302
Automated Regulators: number of devices installed	#	0	3
Feeder Monitors: number of devices installed	#	0	0
Remote Fault Indicators: number of devices installed	#	7	236
Transformer Monitors (line): number of devices installed	#	0	0
Smart Relays: number of devices installed	#	63	2,277
Fault Current Limiter: number of devices installed	#	0	0
Other devices installed	#		
Other devices installed	#		
Other devices installed	#		

DA Applications in Operation	Units	Project	System
Fault Location, Isolation, and Service Restoration (FLISR): is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Voltage Optimization: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Feeder Peak Load Management: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Microgrids: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other DA Application: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>

Page 16 of 24 Custom Created: October 4, 2011



Master Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metric Quarterly Report Quarter 4, 2012	
Period	Start: Oct 1, 2012	End: Dec 31, 2012	Submission Due Date: January 31, 2013

Distribution Management System Integration

	Units	Project	System
AMI: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Outage Management System: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Transmission Management System: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Distributed Energy Resources: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other Systems: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>

Distribution Device Description

	Project	System
SCADA	Distribution SCADA will be installed in the project area.	ABB Network Manager (EMS)
Portion of system with SCADA	Distribution SCADA will be installed in the project area.	The ABB Network Manager (EMS) communicates with 70% of feeder breakers, but only 15% of those have communications capable of supporting Smart Grid functionality.
Portion of system with DA	DA has not been implemented yet.	KCP&L has locally automated devices such as capacitors, voltage monitors, faulted circuit indicators, and reclosers across the distribution system. 75% represents an estimate of coverage based on number of circuits with one or more of these devices.
DA devices	DA devices have not yet been installed and/or integrated.	There is a mix of locally automated capacitors, voltage monitors, faulted circuit indicators, and reclosers across distribution system.

Page 19 of 24 Custom Created: October 4, 2011



Master Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metric Quarterly Report Quarter 4, 2012	
Period	Start: Oct 1, 2012	End: Dec 31, 2012	Submission Due Date: January 31, 2013

Distribution Device Description

	Project	System
DA communications network	DA network has not been installed yet.	Lands+Gyr AMR system and Telemetric/Sensus cellular-based system.
Other device	N/A	N/A
N/A		
Other device	N/A	N/A
N/A		
Other device	N/A	N/A
N/A		

Distribution Application Descriptions

	Project	System
FLISR	FLISR has not yet been implemented	FLISR has not yet been implemented

Page 20 of 24 Custom Created: October 4, 2011



Master Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metric Quarterly Report Quarter 4, 2012	
		Period	Start: Oct 1, 2012	End: Dec 31, 2012 Submission Due Date: January 31, 2013
Voltage Optimization	Voltage Optimization has not been implemented yet.	A Dynamic Voltage Control (DVC) system exists on 203 buses within metropolitan Kansas City. This system is able to dynamically reduce voltage through load tap changers to achieve voltage changes in coordination with locally controlled cap banks.		
Feeder Peak Load Management	Feeder Peak Load Management has not been implemented yet.	System peak loads are curtailed through utilization of the DVC system and existing PCT program operated by Honeywell.		
Microgrids	N/A	N/A		
Other DA Applications	N/A	N/A		
Distribution Management Integration Descriptions				
	Project	System		
AMI	Not integrated yet	Not integrated yet		
Outage Management	Not integrated yet	Not integrated yet		

Page 21 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metric Quarterly Report Quarter 4, 2012	
		Period	Start: Oct 1, 2012	End: Dec 31, 2012 Submission Due Date: January 31, 2013
Distribution Management Integration Descriptions				
	Project	System		
Transmission Management	N/A	N/A		
DER Systems	Not integrated yet	Not integrated yet		
Distribution Management System	Not integrated yet	Not integrated yet		
Other Systems	N/A	N/A		
Additional Project Descriptions:	N/A			
Distribution Systems Installed Costs				
	Units	Project Funded	Cost Share	
Back Office Systems	\$	288,844	288,844	
Distribution Management System	\$	0	0	
Communications Equipment and SCADA	\$	0	0	

Page 22 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metric Quarterly Report Quarter 4, 2012	
Period	Start: Oct 1, 2012	End: Dec 31, 2012	Submission Due Date: January 31, 2013

Distribution Systems Installed Costs	Units	Project Funded	Cost Share
Feeder Monitor/Indicator	\$	0	0
Substation Monitors	\$	1,163,518	1,163,518
Automated Feeder Switches	\$	0	0
Capacitor Automation Equipment	\$	82,973	82,973
Regulator Automation Equipment	\$	0	0
Fault Current Limiter Equipment	\$	0	0
Cost of other devices installed N/A	\$		
Cost of other devices installed N/A	\$		
Cost of other devices installed N/A	\$		
Other Costs	\$		
Other Cost Description	N/A		

Page 23 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metric Quarterly Report Quarter 4, 2012	
Period	Start: Oct 1, 2012	End: Dec 31, 2012	Submission Due Date: January 31, 2013

Submit
Print Form

Page 24 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2

S.12 2013 Q1

SMARTGRID.GOV		Project	DE-OE000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metric Quarterly Report Quarter 1, 2013		
		Period	Start: Jan 1, 2013	End: Mar 31, 2013	Submission Due Date: April 30, 2013
AMI Assets - Build Metrics					
<i>All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.</i>					
AMI End Points Installed		Units	Project	System	
End Points (meters) installed and operational	#		13,463	13,463	
Portion of customers with AMI residential	#		12,222	12,222	
Portion of customers with AMI commercial	#		1,241	1,241	
Portion of customers with AMI industrial	#				
Implemented Meter Features		Units	Project	System	
Reading interval for residential meters	minutes		15	15	
Reading interval for commercial meters	minutes		15	15	
Reading interval for industrial meters	minutes				
Remote Connect/Disconnect: is feature implemented?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Remote Connect/Disconnect: number of meters with feature implemented	#		13,463	13,463	
Outage Reporting: is feature implemented?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Outage Reporting: number of meters with feature implemented	#		13,463	13,463	
Power Quality Measurement: is feature implemented?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Power Quality Measurement: number of meters with feature implemented	#				
Tamper Detection: is feature implemented?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Tamper Detection: number of meters with feature implemented	#		13,463	13,463	
Other feature implemented	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other feature: number of meters with feature implemented	#				
Other feature implemented	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other feature: number of meters with feature implemented	#				
Other feature implemented	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other feature: number of meters with feature implemented	#				

Page 1 of 24 Custom Created: October 8, 2011 Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metric Quarterly Report Quarter 1, 2013		
		Period	Start: Jan 1, 2013	End: Mar 31, 2013	Submission Due Date: April 30, 2013
Implemented Meter Features		Units	Project	System	
Other feature: number of meters with feature implemented	#				
Implemented Enterprise Integration		Units	Project	System	
Billing System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Customer Information System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Outage Management System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Distribution Management System: is integration complete?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other Enterprise Systems: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
AMI System Descriptions					
	Project	System			
Backhaul Network	Hybrid of Fiber and Wireless Raven radio with network carrier	Hybrid of Fiber and Wireless Raven radio with network carrier			
Meter Communication Network	Lands+Gyr Gridstream RF 900MHz - Collectors and Routers	Lands+Gyr Gridstream RF 900MHz - Collectors and Routers			
Headend System	Lands+Gyr Command Center	Lands+Gyr Command Center			
Meter Data Management System	eMeter/Siemens	eMeter/Siemens			

Page 2 of 24 Custom Created: October 8, 2011 Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metric Quarterly Report Quarter 1, 2013		
		Period	Start: Jan 1, 2013	End: Mar 31, 2013	Submission Due Date: April 30, 2013
AMI System Descriptions					
	Project	System			
Meter Data Analysis	The project AMI was incorporated into the existing AMR – MDA interfaces. AMI daily register reads and 15-min interval reads are loaded into MDA (DataRaker) on a daily basis.	The project AMI was incorporated into the existing AMR – MDA interfaces. AMI daily register reads and 15-min interval reads are loaded into MDA (DataRaker) on a daily basis.			
Other Meter Feature	N/A	N/A			
Other Meter Feature	N/A	N/A			
Other Meter Feature	N/A	N/A			
AMI Enterprise Integration Descriptions					
	Project	System			
Billing System	AMI is integrated with enterprise Oracle CIS.	AMI is integrated with enterprise Oracle CIS.			

Page 3 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metric Quarterly Report Quarter 1, 2013		
		Period	Start: Jan 1, 2013	End: Mar 31, 2013	Submission Due Date: April 30, 2013
AMI Enterprise Integration Descriptions					
	Project	System			
Customer Information System	AMI is integrated with KCPL enterprise Oracle CIS. The project AMI was incorporated into the existing AMR – CIS interfaces. CIS daily account/meter synchronization. AMI provides CIS daily register meter reads for direct billing. CIS daily billing cycle-to-date usage info and bill prediction pushed to IHDs via AMI Network.	AMI is integrated with KCPL enterprise Oracle CIS. The project AMI was incorporated into the existing AMR – CIS interfaces. CIS daily account/meter synchronization. AMI provides CIS daily register meter reads for direct billing. CIS daily billing cycle-to-date usage info and bill prediction pushed to IHDs via AMI Network.			
Outage Management System	AMI is integrated with enterprise OMS. An additional project OMS (redundant) will also be implemented in conjunction with a DMS. The project AMI was incorporated into the existing AMR to enterprise OMS interfaces including meter outage alerts and meter "ping" functionality to verify power restoration.	AMI is integrated with enterprise OMS. An additional project OMS (redundant) will also be implemented in conjunction with a DMS. The project AMI was incorporated into the existing AMR to enterprise OMS interfaces including meter outage alerts and meter "ping" functionality to verify power restoration.			
Distribution Management System	Not yet integrated	Not yet integrated			
Other Enterprise Systems	Data Mining and Analysis Tool (DataRaker) covered by the MDA	Data Mining and Analysis Tool (DataRaker) covered by the MDA			
Additional Project Descriptions	N/A				
AMI Installed Costs			Units	Project Funded	Cost Share
Back Office Systems		\$	1,987,252	1,987,252	
Communications Equipment		\$	114,205	114,205	
AMI Smart Meters		\$	2,154,131	2,154,131	

Page 4 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metric Quarterly Report Quarter 1, 2013	
Period	Start: Jan 1, 2013	End: Mar 31, 2013	Submission Due Date: April 30, 2013

AMI Installed Costs	Units	Project Funded	Cost Share
Other Costs	5	<input type="text"/>	<input type="text"/>
Other Costs Description	N/A		

Page 5 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metric Quarterly Report Quarter 1, 2013	
Period	Start: Jan 1, 2013	End: Mar 31, 2013	Submission Due Date: April 30, 2013

Customer Systems Assets - Build Metrics				
All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.				
Implemented Customer Systems		Units	Project	System
In-Home display: devices installed		#	628	628
Direct Load Control Devices: devices installed		#	117	117
Programmable Communicating Thermostats: devices installed		#	107	53,787
Smart Appliances: devices installed		#	0	0
Energy Management Devices/Systems: devices installed		#	0.0	0.0
Other Devices installed	HAN Gateway	#	52	52
Other Devices installed	<input type="text"/>	#		
Other Devices installed	<input type="text"/>	#		
Web Portal		Units	Project	System
Web portal is portal in production?		yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Customers with access		#	12,012	12,012
Customers with active accounts		#	1,871	1,871
Customer System Descriptions				
	Project	System		
In-Home Displays	Tendril In-Sight	Tendril In-Sight		

Page 6 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metric Quarterly Report Quarter 1, 2013		
		Period	Start: Jan 1, 2013	End: Mar 31, 2013	Submission Due Date: April 30, 2013

Customer System Descriptions		
	Project	System
Direct Load Control Devices	Tendril Volt	Tendril Volt
Programmable Communicating Thermostats	Tendril Setpoint	Tendril Setpoint and Honeywell PCTs
Smart Appliances	N/A	N/A
Energy Mgmt. Systems	N/A	N/A
Web Portal	Tendril Energize Web Portal	Tendril Energize Web Portal
Home Area Network	Zigbee SEP 1.0	Zigbee SEP 1.0

Page 7 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metric Quarterly Report Quarter 1, 2013		
		Period	Start: Jan 1, 2013	End: Mar 31, 2013	Submission Due Date: April 30, 2013

Customer System Descriptions		
	Project	System
Other Device	Tendril Transport Gateway	Tendril Transport Gateway
HAN Gateway		
Other Device	N/A	N/A
Other Device	N/A	N/A
Additional Project Descriptions	N/A	

Customer System Installed Costs			
	Units	Project Funded	Cost Share
Back Office Systems	\$	384,288	384,288
Web Portals	\$	701,593	701,593
In-Home Displays	\$	148,860	148,860
Direct Load Control Devices	\$	88,869	88,869
Smart Appliances	\$	0	0
Programmable Communicating Thermostats	\$	313,292	313,292
Cost of other devices installed: HAN Gateway	\$	202,578	202,578

Page 8 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metric Quarterly Report Quarter 1, 2013	
Period	Start: Jan 1, 2013	End: Mar 31, 2013	Submission Due Date: April 30, 2013

Customer System Installed Costs	Units	Project Funded	Cost Share
Cost of other devices installed	\$		
Cost of other devices installed	\$		
Other Costs	\$	295,172	295,172
Other Cost Description	Program delivery costs including KCP&L labor for program administration, analysis, and customer engagement as well as vendor travel expenses.		

Page 9 of 24 Custom Created: October 4, 2011

Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metric Quarterly Report Quarter 1, 2013	
Period	Start: Jan 1, 2013	End: Mar 31, 2013	Submission Due Date: April 30, 2013

Pricing Programs - Build Metrics

All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.

Implemented Rate Plans	Units	Project	System
Flat Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Flat Rate: number of customers with access	#		
Flat Rate: number of customers enrolled	#		160,945
Flat Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Critical Peak Pricing: number of customers with access	#		
Flat Rate with Critical Peak Pricing: number of customers enrolled	#		
Flat Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Peak Time Rebate: number of customers with access	#		
Flat Rate with Peak Time Rebate: number of customers enrolled	#		
Tiered Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Tiered Rate: number of customers with access	#		
Tiered Rate: number of customers enrolled	#		686,732
Tiered Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Critical Peak Pricing: number of customers with access	#		
Tiered Rate with Critical Peak Pricing: number of customers enrolled	#		
Tiered Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Peak Time Rebate: number of customers with access	#		
Tiered Rate with Peak Time Rebate: number of customers enrolled	#		
Time of Use Rate: is the pricing program available?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Time of Use Rate: number of customers with access	#	12,222	

Page 10 of 24 Custom Created: October 4, 2011

Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metric Quarterly Report Quarter 1, 2013	
Period	Start: Jan 1, 2013	End: Mar 31, 2013	Submission Due Date: April 30, 2013

Implemented Rate Plans	Units	Project	System
Time of Use Rate: number of customers enrolled	#	61	330
Time of Use Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Time of Use Rate with Critical Peak Pricing: number of customers with access	#		
Time of Use Rate with Critical Peak Pricing: number of customers enrolled	#		
Time of Use Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Time of Use Rate with Peak Time Rebate: number of customers with access	#		
Time of Use Rate with Peak Time Rebate: number of customers enrolled	#		
Real-time Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Real-time Pricing: number of customers with access	#		
Real-time Pricing: number of customers enrolled	#		9
Real-time Pricing with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Real-time Pricing with Critical Peak Pricing: number of customers with access	#		
Real-time Pricing with Critical Peak Pricing: number of customers enrolled	#		
Real-time Pricing with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Real-time Pricing with Peak Time Rebate: number of customers with access	#		
Real-time Pricing with Peak Time Rebate: number of customers enrolled	#		
Variable Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Variable Peak Pricing: number of customers with access	#		
Variable Peak Pricing: number of customers enrolled	#		
Pre-pay Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Pre-pay Pricing: number of customers with access	#		
Pre-pay Pricing: number of customers enrolled	#		
Net Metering: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>

Page 11 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metric Quarterly Report Quarter 1, 2013	
Period	Start: Jan 1, 2013	End: Mar 31, 2013	Submission Due Date: April 30, 2013

Implemented Rate Plans	Units	Project	System
Net Metering: number of customers with access	#		
Net Metering: number of customers enrolled	#		579
Other program available	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: number of customers with access	#		
Other programs: number of customers enrolled	#		
Other program available	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: number of customers with access	#		
Other programs: number of customers enrolled	#		
Other program available	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: number of customers with access	#		
Other programs: number of customers enrolled	#		
Rate Decoupling: is implemented?	yes/ no	<input type="checkbox"/>	

Rate Plan Descriptions	Project	System
Flat Rate	N/A	KCP&L has multiple residential and C&I Flat Rates that occur during both summer and winter. We are not able to calculate an accurate number for how many customers have access.
Flat Rate with Critical Peak Pricing	N/A	N/A

Page 12 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		
Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
Filing	build_quarterly	Build Metric Quarterly Report Quarter 1, 2013
Period	Start: Jan 1, 2013	End: Mar 31, 2013 Submission Due Date: April 30, 2013
Rate Plan Descriptions		
	Project	System
Flat Rate with Peak Time Rebate	N/A	N/A
Tiered Rate	N/A	KCP&L has multiple existing residential and C&I Tiered Rates. A majority of those are declining block rates. We are not able to calculate an accurate number for how many customers have access.
Tiered Rate with Critical Peak Pricing	N/A	N/A
Tiered Rate with Peak Time Rebate	N/A	N/A
Time of Use Rate	A new residential TOU rate is being piloted as part of this project to augment the evaluation of customer systems and devices.	KCP&L has multiple existing residential and C&I TOU Rates. We are not able to calculate an accurate number for how many customers have access.
Time of Use Rate with Critical Peak Pricing	N/A	N/A

Page 13 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		
Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
Filing	build_quarterly	Build Metric Quarterly Report Quarter 1, 2013
Period	Start: Jan 1, 2013	End: Mar 31, 2013 Submission Due Date: April 30, 2013
Rate Plan Descriptions		
	Project	System
Time of Use Rate with Peak Time Rebate	N/A	N/A
Real-Time Rate	N/A	KCP&L has multiple existing RTP rates for commercial and industrial customers. We are not able to calculate an accurate number for how many customers have access.
Real-time Rate with Critical Peak Pricing	N/A	N/A
Real-time Rate with Peak Time Rebate	N/A	N/A
Variable Peak Pricing	N/A	N/A
Pre-paid Rate	N/A	N/A

Page 14 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metric Quarterly Report Quarter 1, 2013		
		Period	Start: Jan 1, 2013	End: Mar 31, 2013	Submission Due Date: April 30, 2013
Rate Plan Descriptions					
	Project	System			
Net Metering Rate	N/A	KCPL has multiple existing residential and C&I Net Metering Rates. We are not able to calculate an accurate number for how many customers have access.			
Other program	N/A	N/A			
Other program	N/A	N/A			
Other program	N/A	N/A			
Additional Project Descriptions	N/A				

Page 15 of 24 Custom Created: October 4, 2011 Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metric Quarterly Report Quarter 1, 2013		
		Period	Start: Jan 1, 2013	End: Mar 31, 2013	Submission Due Date: April 30, 2013
Distributed Energy Resources - Build Metrics					
<i>All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.</i>					
Distributed Energy Resources		Units	Project	System	
Distributed generation: number of units	#		3	571	
Distributed generation: installed capacity	KW		107.4	10,303.8	
Distributed generation: total energy delivered	* kWh		17,616		
Energy storage: number of units	#		1	1	
Energy storage: installed capacity	KW		1,000	1,000	
Energy storage: total energy delivered	* kWh		0.0	0.0	
Plug-in electric vehicles charging points: number of units	#		6	16	
Plug-in electric vehicles charging points: installed capacity	KW		76	184	
Plug-in electric vehicles charging points: total energy delivered	* kWh		397	2,362	
DER/DG interconnection equipment: number of units	#				
* Energy delivered should be reported just for the quarter being reported, not cumulative for the project to-date.					
Distributed Energy Resource Descriptions					
	Project	System			
Distributed Generation Interface Description	All DG installed is non-dispatchable utility-owned PV that is being metered separately. All project EV chargers are installed behind customer meters. Interfaces currently limited to measuring data.	Non-dispatchable utility-owned DG and EV Chargers. All EV chargers are installed behind customer meters. Interfaces currently limited to measuring data.			

Page 16 of 24 Custom Created: October 4, 2011 Meter Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metric Quarterly Report Quarter 1, 2013	
Period	Start: Jan 1, 2013	End: Mar 31, 2013	Submission Due Date: April 30, 2013

Additional Project Descriptions:

Distributed Energy Resources' Installed Costs	Units	Project Funded	Cost Share
DER Interface Control Systems	\$		
Communications Equipment	\$		
DER/DG Interconnection Equipment	\$		
Renewable DER	\$	471,706	471,706
Distributed Generation Equipment	\$		
Stationary Electric Storage Equipment	\$	3,782,304	3,782,304
PEVs and Charging Stations	\$	51,479	51,479
Other Costs	\$		
Other Cost Description	N/A		

Page 17 of 24 Custom Created: October 4, 2011



Master Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metric Quarterly Report Quarter 1, 2013	
Period	Start: Jan 1, 2013	End: Mar 31, 2013	Submission Due Date: April 30, 2013

Electric Distribution System Assets - Build Metrics

All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.

Implemented Distribution Devices	Units	Project	System
Portion of system with SCADA	%	0	10.5
Portion of system with Distribution Automation (DA)	%	60	85
Automated Feeder Switches: number of devices installed	#	0	97
Automated Capacitors: number of devices installed	#	29	2,322
Automated Regulators: number of devices installed	#	0	3
Feeder Monitors: number of devices installed	#	0	0
Remote Fault Indicators: number of devices installed	#	25	254
Transformer Monitors (line): number of devices installed	#	0	0
Smart Relays: number of devices installed	#	63	2,277
Fault Current Limiter: number of devices installed	#	0	0
Other devices installed: 	#		
Other devices installed: 	#		
Other devices installed: 	#		

DA Applications in Operation	Units	Project	System
Fault Location, Isolation, and Service Restoration (FLISR): is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Voltage Optimization: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Feeder Peak Load Management: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Microgrids: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other DA Application: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>

Page 16 of 24 Custom Created: October 4, 2011



Master Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metric Quarterly Report Quarter 1, 2013	
Period	Start: Jan 1, 2013	End: Mar 31, 2013	Submission Due Date: April 30, 2013

Distribution Management System Integration

	Units	Project	System
AMI: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Outage Management System: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Transmission Management System: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Distributed Energy Resources: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other Systems: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>

Distribution Device Description

	Project	System
SCADA	Distribution SCADA will be installed in the project area.	ABB Network Manager (EMS)
Portion of system with SCADA	Distribution SCADA will be installed in the project area.	The ABB Network Manager (EMS) communicates with 70% of feeder breakers, but only 15% of those have communications capable of supporting Smart Grid functionality.
Portion of system with DA	DA has not been implemented yet.	KCP&L has locally automated devices such as capacitors, voltage monitors, faulted circuit indicators, and reclosers across the distribution system. 85% represents an estimate of coverage based on number of circuits with one or more of these devices.
DA devices	DA devices have not yet been installed and/or integrated.	There is a mix of locally automated capacitors, voltage monitors, faulted circuit indicators, and reclosers across the distribution system.

Page 19 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metric Quarterly Report Quarter 1, 2013	
Period	Start: Jan 1, 2013	End: Mar 31, 2013	Submission Due Date: April 30, 2013

Distribution Device Description

	Project	System
DA communications network	DA network has not been installed yet.	Lands+Gyr AMR system and Telemetric/Sensus cellular-based system.
Other device	N/A	N/A
Other device	N/A	N/A
Other device	N/A	N/A

Distribution Application Descriptions

	Project	System
FLISR	FLISR has not yet been implemented	FLISR has not yet been implemented

Page 20 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metric Quarterly Report Quarter 1, 2013		
		Period	Start: Jan 1, 2013	End: Mar 31, 2013	Submission Due Date: April 30, 2013
Voltage Optimization	Voltage Optimization has not been implemented yet.	A Dynamic Voltage Control (DVC) system exists on 203 buses within metropolitan Kansas City. This system is able to dynamically reduce voltage through load tap changers to achieve voltage changes in coordination with locally controlled cap banks.			
Feeder Peak Load Management	Feeder Peak Load Management has not been implemented yet.	System peak loads are curtailed through utilization of the DVC system and existing PCT program operated by Honeywell.			
Microgrids	N/A	N/A			
Other DA Applications	N/A	N/A			
Distribution Management Integration Descriptions					
	Project	System			
AMI	Not integrated yet	Not integrated yet			
Outage Management	Not integrated yet	Not integrated yet			

Page 21 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metric Quarterly Report Quarter 1, 2013		
		Period	Start: Jan 1, 2013	End: Mar 31, 2013	Submission Due Date: April 30, 2013
Distribution Management Integration Descriptions					
	Project	System			
Transmission Management	N/A	N/A			
DER Systems	Not integrated yet	Not integrated yet			
Distribution Management System	Not integrated yet	Not integrated yet			
Other Systems	N/A	N/A			
Additional Project Descriptions:	N/A				
Distribution Systems Installed Costs					
	Units	Project Funded	Cost Share		
Back Office Systems	\$	303,123	303,123		
Distribution Management System	\$	0	0		
Communications Equipment and SCADA	\$	0	0		

Page 22 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metric Quarterly Report Quarter 1, 2013	
Period	Start: Jan 1, 2013	End: Mar 31, 2013	Submission Due Date: April 30, 2013

Distribution Systems Installed Costs	Units	Project Funded	Cost Share
Feeder Monitor/Indicator	\$	0	0
Substation Monitors	\$	1,178,896	1,178,896
Automated Feeder Switches	\$	0	0
Capacitor Automation Equipment	\$	92,360	92,360
Regulator Automation Equipment	\$		
Fault Current Limiter Equipment	\$		
Cost of other devices installed	\$		
Cost of other devices installed	\$		
Cost of other devices installed	\$		
Other Costs	\$		
Other Cost Description	N/A		

Page 23 of 24 Custom Created October 4, 2011



Metric Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metric Quarterly Report Quarter 1, 2013	
Period	Start: Jan 1, 2013	End: Mar 31, 2013	Submission Due Date: April 30, 2013

Submit
Print Form

Page 24 of 24 Custom Created October 4, 2011



Metric Updated: April 8, 2011 Schema Version: 1.2

S.13 2013 Q2

SMARTGRID.GOV		Project	DE-OE000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 2, 2013		
		Period	Start: Apr 1, 2013	End: Jun 30, 2013	Submission Due Date: July 31, 2013
AMI Assets - Build Metrics					
<i>All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.</i>					
AMI End Points Installed		Units	Project	System	
End Points (meters) installed and operational	#		13,448	13,448	
Portion of customers with AMI residential	#		12,202	12,202	
Portion of customers with AMI commercial	#		1,246	1,246	
Portion of customers with AMI industrial	#				
Implemented Meter Features		Units	Project	System	
Reading interval for residential meters	minutes		15	15	
Reading interval for commercial meters	minutes		15	15	
Reading interval for industrial meters	minutes				
Remote Connect/Disconnect: is feature implemented?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Remote Connect/Disconnect: number of meters with feature implemented	#		13,448	13,448	
Outage Reporting: is feature implemented?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Outage Reporting: number of meters with feature implemented	#		13,448	13,448	
Power Quality Measurement: is feature implemented?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Power Quality Measurement: number of meters with feature implemented	#				
Tamper Detection: is feature implemented?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Tamper Detection: number of meters with feature implemented	#		13,448	13,448	
Other feature implemented	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other feature: number of meters with feature implemented	#				
Other feature implemented	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other feature: number of meters with feature implemented	#				
Other feature implemented	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other feature: number of meters with feature implemented	#				

Page 1 of 24 Custom Created: October 8, 2011 Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 2, 2013		
		Period	Start: Apr 1, 2013	End: Jun 30, 2013	Submission Due Date: July 31, 2013
Implemented Meter Features		Units	Project	System	
Other feature: number of meters with feature implemented	#				
Implemented Enterprise Integration		Units	Project	System	
Billing System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Customer Information System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Outage Management System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Distribution Management System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Other Enterprise Systems: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
AMI System Descriptions					
	Project	System			
Backhaul Network	Hybrid of Fiber and Wireless Raven radio with network carrier	Hybrid of Fiber and Wireless Raven radio with network carrier			
Meter Communication Network	Lands+Gyr Gridstream RF 900MHz - Collectors and Routers	Lands+Gyr Gridstream RF 900MHz - Collectors and Routers			
Headend System	Lands+Gyr Command Center	Lands+Gyr Command Center			
Meter Data Management System	eMeter/Siemens	eMeter/Siemens			

Page 2 of 24 Custom Created: October 8, 2011 Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 2, 2013		
		Period	Start: Apr 1, 2013	End: Jun 30, 2013	Submission Due Date: July 31, 2013
AMI System Descriptions					
	Project	System			
Meter Data Analysis	The project AMI was incorporated into the existing AMR – MDA interfaces. AMI daily register reads and 15-min interval reads are loaded into MDA (DataRaker) on a daily basis.	The project AMI was incorporated into the existing AMR – MDA interfaces. AMI daily register reads and 15-min interval reads are loaded into MDA (DataRaker) on a daily basis.			
Other Meter Feature	N/A	N/A			
Other Meter Feature	N/A	N/A			
Other Meter Feature	N/A	N/A			
AMI Enterprise Integration Descriptions					
	Project	System			
Billing System	AMI is integrated with enterprise Oracle CIS.	AMI is integrated with enterprise Oracle CIS.			

Page 3 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 2, 2013		
		Period	Start: Apr 1, 2013	End: Jun 30, 2013	Submission Due Date: July 31, 2013
AMI Enterprise Integration Descriptions					
	Project	System			
Customer Information System	AMI is integrated with KCP&L enterprise Oracle CIS. The project AMI was incorporated into the existing AMR – CIS interfaces. CIS daily account/meter synchronization. AMI provides CIS daily register meter reads for direct billing. CIS daily billing cycle-to-date usage info and bill prediction pushed to IHDs via AMI Network.	AMI is integrated with KCP&L enterprise Oracle CIS. The project AMI was incorporated into the existing AMR – CIS interfaces. CIS daily account/meter synchronization. AMI provides CIS daily register meter reads for direct billing. CIS daily billing cycle-to-date usage info and bill prediction pushed to IHDs via AMI Network.			
Outage Management System	AMI is integrated with enterprise OMS. An additional project OMS (redundant) will also be implemented in conjunction with a DMS. The project AMI was incorporated into the existing AMR to enterprise OMS interfaces including meter outage alerts and meter "ping" functionality to verify power restoration.	AMI is integrated with enterprise OMS. An additional project OMS (redundant) will also be implemented in conjunction with a DMS. The project AMI was incorporated into the existing AMR to enterprise OMS interfaces including meter outage alerts and meter "ping" functionality to verify power restoration.			
Distribution Management System	DMS is integrated with multiple project and legacy systems including AMI, DERM, OMS, and energy storage.	DMS is integrated with multiple project and legacy systems including AMI, DERM, OMS, and energy storage.			
Other Enterprise Systems	Data Mining and Analysis Tool (DataRaker) covered by the MDA	Data Mining and Analysis Tool (DataRaker) covered by the MDA			
Additional Project Descriptions	N/A				
AMI Installed Costs		Units	Project Funded	Cost Share	
Back Office Systems		\$	2,520,579	2,328,686	
Communications Equipment		\$	188,317	173,831	
AMI Smart Meters		\$	2,254,965	2,081,506	

Page 4 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 2, 2013	
Period	Start: Apr 1, 2013	End: Jun 30, 2013	Submission Due Date: July 31, 2013

AMI Installed Costs	Units	Project Funded	Cost Share
Other Costs	5		
Other Costs Description	N/A		

Page 5 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 2, 2013	
Period	Start: Apr 1, 2013	End: Jun 30, 2013	Submission Due Date: July 31, 2013

Customer Systems Assets - Build Metrics

All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.

Implemented Customer Systems	Units	Project	System
In-Home display: devices installed	#	625	625
Direct Load Control Devices: devices installed	#	122	122
Programmable Communicating Thermostats: devices installed	#	103	53,884
Smart Appliances: devices installed	#	0	0
Energy Management Devices/Systems: devices installed	#	0.0	0.0
Other Devices installed	#	57	57
Other Devices installed	#		
Other Devices installed	#		

Web Portal	Units	Project	System
Web portal is portal in production?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Customers with access	#	11,805	11,805
Customers with active accounts	#	1,927	1,927

Customer System Descriptions	Project	System
In-Home Displays	Tendril InSight	Tendril InSight

Page 6 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 2, 2013	
		Period	Start: Apr 1, 2013	End: Jun 30, 2013 Submission Due Date: July 31, 2013

Customer System Descriptions		
	Project	System
Direct Load Control Devices	Tendril Volt	Tendril Volt
Programmable Communicating Thermostats	Tendril Setpoint	Tendril Setpoint and Honeywell PCTs
Smart Appliances	N/A	N/A
Energy Mgmt. Systems	N/A	N/A
Web Portal	Tendril Energize Web Portal	Tendril Energize Web Portal
Home Area Network	Zigbee SEP 1.0	Zigbee SEP 1.0

Page 7 of 24 Custom Created: October 4, 2011 Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 2, 2013	
		Period	Start: Apr 1, 2013	End: Jun 30, 2013 Submission Due Date: July 31, 2013

Customer System Descriptions		
	Project	System
Other Device	Tendril Transport Gateway	Tendril Transport Gateway
HAN Gateway		
Other Device	N/A	N/A
Other Device	N/A	N/A
Additional Project Descriptions	N/A	

Customer System Installed Costs	Units	Project Funded	Cost Share
Back Office Systems	\$	435,247	401,767
Web Portals	\$	720,006	673,767
In-Home Displays	\$	155,634	143,662
Direct Load Control Devices	\$	90,344	83,395
Smart Appliances	\$	0	0
Programmable Communicating Thermostats	\$	353,258	326,085
Cost of other devices installed: HAN Gateway	\$	213,720	197,260

Page 8 of 24 Custom Created: October 4, 2011 Meter Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 2, 2013	
Period	Start: Apr 1, 2013	End: Jun 30, 2013	Submission Due Date: July 31, 2013

Customer System Installed Costs	Units	Project Funded	Cost Share
Cost of other devices installed	\$	[]	[]
Cost of other devices installed	\$	[]	[]
Other Costs	\$	338,659	312,608
Other Cost Description	Program delivery costs including KCP&L labor for program administration, analysis, and customer engagement as well as vendor travel expenses.		

Page 9 of 24 Custom Created: October 4, 2011

Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 2, 2013	
Period	Start: Apr 1, 2013	End: Jun 30, 2013	Submission Due Date: July 31, 2013

Pricing Programs - Build Metrics

All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.

Implemented Rate Plans	Units	Project	System
Flat Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Flat Rate: number of customers with access	#	[]	[]
Flat Rate: number of customers enrolled	#	[]	543,606
Flat Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Critical Peak Pricing: number of customers with access	#	[]	[]
Flat Rate with Critical Peak Pricing: number of customers enrolled	#	[]	[]
Flat Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Peak Time Rebate: number of customers with access	#	[]	[]
Flat Rate with Peak Time Rebate: number of customers enrolled	#	[]	[]
Tiered Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Tiered Rate: number of customers with access	#	[]	[]
Tiered Rate: number of customers enrolled	#	[]	301,573
Tiered Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Critical Peak Pricing: number of customers with access	#	[]	[]
Tiered Rate with Critical Peak Pricing: number of customers enrolled	#	[]	[]
Tiered Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Peak Time Rebate: number of customers with access	#	[]	[]
Tiered Rate with Peak Time Rebate: number of customers enrolled	#	[]	[]
Time of Use Rate: is the pricing program available?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Time of Use Rate: number of customers with access	#	12,202	[]

Page 10 of 24 Custom Created: October 4, 2011

Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 2, 2013	
Period	Start: Apr 1, 2013	End: Jun 30, 2013	Submission Due Date: July 31, 2013

Implemented Rate Plans	Units	Project	System
Time of Use Rate: number of customers enrolled	#	131	559
Time of Use Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Time of Use Rate with Critical Peak Pricing: number of customers with access	#		
Time of Use Rate with Critical Peak Pricing: number of customers enrolled	#		
Time of Use Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Time of Use Rate with Peak Time Rebate: number of customers with access	#		
Time of Use Rate with Peak Time Rebate: number of customers enrolled	#		
Real-time Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Real-time Pricing: number of customers with access	#		
Real-time Pricing: number of customers enrolled	#		9
Real-time Pricing with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Real-time Pricing with Critical Peak Pricing: number of customers with access	#		
Real-time Pricing with Critical Peak Pricing: number of customers enrolled	#		
Real-time Pricing with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Real-time Pricing with Peak Time Rebate: number of customers with access	#		
Real-time Pricing with Peak Time Rebate: number of customers enrolled	#		
Variable Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Variable Peak Pricing: number of customers with access	#		
Variable Peak Pricing: number of customers enrolled	#		
Pre-pay Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Pre-pay Pricing: number of customers with access	#		
Pre-pay Pricing: number of customers enrolled	#		
Net Metering: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>

Page 11 of 24 Custom Created: October 4, 2011

Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 2, 2013	
Period	Start: Apr 1, 2013	End: Jun 30, 2013	Submission Due Date: July 31, 2013

Implemented Rate Plans	Units	Project	System
Net Metering: number of customers with access	#		
Net Metering: number of customers enrolled	#		742
Other program available	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: number of customers with access	#		
Other programs: number of customers enrolled	#		
Other program available	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: number of customers with access	#		
Other programs: number of customers enrolled	#		
Other program available	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: number of customers with access	#		
Other programs: number of customers enrolled	#		
Rate Decoupling: is implemented?	yes/ no	<input type="checkbox"/>	

Rate Plan Descriptions	Project	System
Flat Rate	N/A	KCP&L has multiple residential and C&I Flat Rates that occur during both summer and winter. We are not able to calculate an accurate number for how many customers have access.
Flat Rate with Critical Peak Pricing	N/A	N/A

Page 12 of 24 Custom Created: October 4, 2011

Metric Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 2, 2013		
		Period	Start: Apr 1, 2013	End: Jun 30, 2013	Submission Due Date: July 31, 2013
Rate Plan Descriptions					
	Project	System			
Flat Rate with Peak Time Rebate	N/A	N/A			
Tiered Rate	N/A	KCP&L has multiple existing residential and C&I Tiered Rates. A majority of those are declining block rates. We are not able to calculate an accurate number for how many customers have access.			
Tiered Rate with Critical Peak Pricing	N/A	N/A			
Tiered Rate with Peak Time Rebate	N/A	N/A			
Time of Use Rate	A new residential TOU rate is being piloted as part of this project to augment the evaluation of customer information systems and control devices.	KCP&L has multiple existing residential and C&I TOU Rates. We are not able to calculate an accurate number for how many customers have access.			
Time of Use Rate with Critical Peak Pricing	N/A	N/A			

Page 13 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 2, 2013		
		Period	Start: Apr 1, 2013	End: Jun 30, 2013	Submission Due Date: July 31, 2013
Rate Plan Descriptions					
	Project	System			
Time of Use Rate with Peak Time Rebate	N/A	N/A			
Real-Time Rate	N/A	KCP&L has multiple existing RTP rates for commercial and industrial customers. We are not able to calculate an accurate number for how many customers have access.			
Real-time Rate with Critical Peak Pricing	N/A	N/A			
Real-time Rate with Peak Time Rebate	N/A	N/A			
Variable Peak Pricing	N/A	N/A			
Pre-paid Rate	N/A	N/A			

Page 14 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 2, 2013		
		Period	Start: Apr 1, 2013	End: Jun 30, 2013	Submission Due Date: July 31, 2013
Rate Plan Descriptions					
	Project	System			
Net Metering Rate	N/A	KCP&L has multiple existing residential and CSI Net Metering Rates. We are not able to calculate an accurate number for how many customers have access.			
Other program	N/A	N/A			
Other program	N/A	N/A			
Other program	N/A	N/A			
Additional Project Descriptions	N/A				

Page 15 of 24 Custom Created: October 4, 2011 Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 2, 2013		
		Period	Start: Apr 1, 2013	End: Jun 30, 2013	Submission Due Date: July 31, 2013
Distributed Energy Resources - Build Metrics					
<i>All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.</i>					
Distributed Energy Resources		Units	Project	System	
Distributed generation: number of units		#	4	722	
Distributed generation: installed capacity		KW	117.89	13,401.15	
Distributed generation: total energy delivered		* kWh	40,783		
Energy storage: number of units		#	1	1	
Energy storage: installed capacity		KW	1,000	1,000	
Energy storage: total energy delivered		* kWh	3,848	3,848	
Plug-in electric vehicles charging points: number of units		#	8	19	
Plug-in electric vehicles charging points: installed capacity		KW	104	220	
Plug-in electric vehicles charging points: total energy delivered		* kWh	558	3,288	
DER/DG interconnection equipment: number of units		#			
* Energy delivered should be reported just for the quarter being reported, not cumulative for the project to-date.					
Distributed Energy Resource Descriptions					
	Project	System			
Distributed Generation Interface Description	All DG installed is non-dispatchable utility-owned PV that is being metered separately. All project EV chargers are installed behind customer meters. Most interfaces currently limited to measuring data. EV chargers may be remotely deactivated to curtail load.	Non-dispatchable utility-owned DG and EV Chargers. All EV chargers are installed behind customer meters. Most interfaces currently limited to measuring data. EV chargers may be remotely deactivated to curtail load.			

Page 16 of 24 Custom Created: October 4, 2011 Meter Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 2, 2013	
Period	Start: Apr 1, 2013	End: Jun 30, 2013	Submission Due Date: July 31, 2013

Additional Project Descriptions:

Distributed Energy Resources' Installed Costs	Units	Project Funded	Cost Share
DER Interface Control Systems	\$	2,354,388	2,173,281
Communications Equipment	\$		
DER/DG Interconnection Equipment	\$		
Renewable DER	\$	585,354	541,250
Distributed Generation Equipment	\$		
Stationary Electric Storage Equipment	\$	3,975,805	3,689,973
PEVs and Charging Stations	\$	56,851	52,293
Other Costs	\$		
Other Cost Description	N/A		

Page 17 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 2, 2013	
Period	Start: Apr 1, 2013	End: Jun 30, 2013	Submission Due Date: July 31, 2013

Electric Distribution System Assets - Build Metrics

All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.

Implemented Distribution Devices	Units	Project	System
Portion of system with SCADA	%	100	10.5
Portion of system with Distribution Automation (DA)	%	60	85
Automated Feeder Switches: number of devices installed	#	5	102
Automated Capacitors: number of devices installed	#	29	2,332
Automated Regulators: number of devices installed	#	0	3
Feeder Monitors: number of devices installed	#	0	0
Remote Fault Indicators: number of devices installed	#	25	254
Transformer Monitors (line): number of devices installed	#	0	0
Smart Relays: number of devices installed	#	63	2,277
Fault Current Limiter: number of devices installed	#	0	0
Other devices installed:	#		
Other devices installed:	#		
Other devices installed:	#		

DA Applications in Operation	Units	Project	System
Fault Location, Isolation, and Service Restoration (FLISR): is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Voltage Optimization: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Feeder Peak Load Management: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Microgrids: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other DA Application: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>

Page 18 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 2, 2013	
Period	Start: Apr 1, 2013	End: Jun 30, 2013	Submission Due Date: July 31, 2013

Distribution Management System Integration

	Units	Project	System
AMI: is integration complete?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Outage Management System: is integration complete?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Transmission Management System: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Distributed Energy Resources: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other Systems: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>

Distribution Device Description

	Project	System
SCADA	Distribution SCADA in conjunction with project DMS/CMS, includes a Tropos wireless network to reach devices outside the substation.	ABB Network Manager (EMS) across system plus project Distribution SCADA.
Portion of system with SCADA	Distribution SCADA has been deployed to all field devices in the project area.	The ABB Network Manager (EMS) communicates with 70% of feeder breakers, but only 15% of those have communications capable of supporting Smart Grid functionality.
Portion of system with DA	DA capabilities are installed on all project circuits.	KCP&L has locally automated devices such as capacitors, voltage monitors, faulted circuit indicators, and reclosers across the distribution system. 80% represents an estimate of coverage based on number of circuits with one or more of these devices.
DA devices	There is a mix of communicating and automated capacitors, faulted circuit indicators, and reclosers across the project area.	There is a mix of locally automated capacitors, voltage monitors, faulted circuit indicators, and reclosers across distribution system.

Page 19 of 24 Custom Created: October 4, 2011



Master Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 2, 2013	
Period	Start: Apr 1, 2013	End: Jun 30, 2013	Submission Due Date: July 31, 2013

Distribution Device Description

	Project	System
DA communications network	Tropos GridCom wireless IP mesh network	Lands+Gyr AMR system and Telemetric/Sensus cellular-based system.
Other device	N/A	N/A
Other device	N/A	N/A
Other device	N/A	N/A

Distribution Application Descriptions

	Project	System
FLISR	As part of the project, the DMS enables FLISR across project circuits. This will reduce outages and outage response time, and improve overall system performance.	As part of the project, the DMS enables FLISR across project circuits. This will reduce outages and outage response time, and improve overall system performance.

Page 20 of 24 Custom Created: October 4, 2011



Master Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 2, 2013		
		Period	Start: Apr 1, 2013	End: Jun 30, 2013	Submission Due Date: July 31, 2013
Voltage Optimization	As part of the project, the DMS enables voltage optimization across project circuits. This will improve power factor as well as enable voltage conservation.	A Dynamic Voltage Control (DVC) system exists on 203 buses within metropolitan Kansas City. This system is able to dynamically reduce voltage through load tap changers to achieve voltage changes in coordination with locally controlled cap banks.			
Feeder Peak Load Management	As part of the project, the DMS enables dynamic feeder load transfer across project circuits. This will reduce outages on project feeders, reduce stress on critical assets, and improve maintenance.	System peak loads are curtailed through utilization of the DVC system and existing PCT program operated by Honeywell.			
Microgrids	N/A	N/A			
Other DA Applications	N/A	N/A			
Distribution Management Integration Descriptions					
	Project	System			
AMI	DMS is integrated with project AMI.	DMS is integrated with project AMI.			
Outage Management	DMS is integrated with project OMS.	DMS is integrated with project OMS.			

Page 21 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 2, 2013		
		Period	Start: Apr 1, 2013	End: Jun 30, 2013	Submission Due Date: July 31, 2013
Distribution Management Integration Descriptions					
	Project	System			
Transmission Management	N/A	N/A			
DER Systems	DMS is integrated with project DERM.	DMS is integrated with project DERM.			
Distribution Management System	DMS consisting of D-SCADA and DNA provided by Siemens and OMS and user interface provided by Intergraph.	DMS consisting of D-SCADA and DNA provided by Siemens and OMS and user interface provided by Intergraph.			
Other Systems	N/A	N/A			
Additional Project Descriptions	N/A				
Distribution Systems Installed Costs					
	Units	Project Funded	Cost Share		
Back Office Systems	\$	380,929	351,827		
Distribution Management System	\$	2,733,807	2,523,514		
Communications Equipment and SCADA	\$	647,675	597,854		

Page 22 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 2, 2013	
Period	Start: Apr 1, 2013	End: Jun 30, 2013	Submission Due Date: July 31, 2013

Distribution Systems Installed Costs	Units	Project Funded	Cost Share
Feeder Monitor/Indicator	\$		
Substation Monitors	\$	1,246,048	1,150,198
Automated Feeder Switches	\$	548,732	506,522
Capacitor Automation Equipment	\$	121,612	112,258
Regulator Automation Equipment	\$		
Fault Current Limiter Equipment	\$		
Cost of other devices installed	\$		
Cost of other devices installed	\$		
Cost of other devices installed	\$		
Other Costs	\$		
Other Cost Description	N/A		

Page 23 of 24 Custom Created: October 4, 2011



Meter Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 2, 2013	
Period	Start: Apr 1, 2013	End: Jun 30, 2013	Submission Due Date: July 31, 2013

Submit
Print Form

Page 24 of 24 Custom Created: October 4, 2011



Meter Updated: April 9, 2011 Schema Version: 1.2

S.14 2013 Q3

SMARTGRID.GOV		Project	DE-OE000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2013	
		Period	Start: Jul 1, 2013	End: Sep 30, 2013 Submission Due Date: October 31, 2013
AMI Assets - Build Metrics				
<i>All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.</i>				
AMI End Points Installed		Units	Project	System
End Points (meters) installed and operational	#		13,433	13,433
Portion of customers with AMI residential	#		12,188	12,188
Portion of customers with AMI commercial	#		1,245	1,245
Portion of customers with AMI industrial	#		0	0
Implemented Meter Features		Units	Project	System
Reading interval for residential meters	minutes		15	15
Reading interval for commercial meters	minutes		15	15
Reading interval for industrial meters	minutes			
Remote Connect/Disconnect: is feature implemented?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Remote Connect/Disconnect: number of meters with feature implemented	#		13,433	13,433
Outage Reporting: is feature implemented?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Outage Reporting: number of meters with feature implemented	#		13,433	13,433
Power Quality Measurement: is feature implemented?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>
Power Quality Measurement: number of meters with feature implemented	#			
Tamper Detection: is feature implemented?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Tamper Detection: number of meters with feature implemented	#		13,433	13,433
Other feature implemented	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>
Other feature: number of meters with feature implemented	#			
Other feature implemented	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>
Other feature: number of meters with feature implemented	#			
Other feature implemented	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>

SMARTGRID.GOV		Project	DE-OE000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2013	
		Period	Start: Jul 1, 2013	End: Sep 30, 2013 Submission Due Date: October 31, 2013
Implemented Meter Features		Units	Project	System
Other feature: number of meters with feature implemented	#			
Implemented Enterprise Integration		Units	Project	System
Billing System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Customer Information System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Outage Management System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Distribution Management System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Other Enterprise Systems: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
AMI System Descriptions				
	Project	System		
Backhaul Network	Hybrid of Fiber and Wireless Raven radio with network carrier	Hybrid of Fiber and Wireless Raven radio with network carrier		
Meter Communication Network	Lands+Gyr Gridstream RF 900MHz - Collectors and Routers	Lands+Gyr Gridstream RF 900MHz - Collectors and Routers		
Headend System	Lands+Gyr Command Center	Lands+Gyr Command Center		
Meter Data Management System	eMeter/Siemens	eMeter/Siemens		

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2013		
		Period	Start: Jul 1, 2013	End: Sep 30, 2013	Submission Due Date: October 31, 2013
AMI System Descriptions					
	Project	System			
Meter Data Analysis	The project AMI was incorporated into the existing AMR – MDA interfaces. AMI daily register reads and 15-min interval reads are loaded into MDA (DataRaker) on a daily basis.	The project AMI was incorporated into the existing AMR – MDA interfaces. AMI daily register reads and 15-min interval reads are loaded into MDA (DataRaker) on a daily basis.			
Other Meter Feature	N/A	N/A			
Other Meter Feature	N/A	N/A			
Other Meter Feature	N/A	N/A			
AMI Enterprise Integration Descriptions					
	Project	System			
Billing System	AMI is integrated with enterprise Oracle CIS.	AMI is integrated with enterprise Oracle CIS.			

Page 3 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2013		
		Period	Start: Jul 1, 2013	End: Sep 30, 2013	Submission Due Date: October 31, 2013
AMI Enterprise Integration Descriptions					
	Project	System			
Customer Information System	AMI is integrated with KCPL enterprise Oracle CIS. The project AMI was incorporated into the existing AMR – CIS interfaces. CIS daily account/meter synchronization. AMI provides CIS daily register meter reads for direct billing. CIS daily billing cycle-to-date usage info and bill prediction pushed to IHDs via AMI Network.	AMI is integrated with KCPL enterprise Oracle CIS. The project AMI was incorporated into the existing AMR – CIS interfaces. CIS daily account/meter synchronization. AMI provides CIS daily register meter reads for direct billing. CIS daily billing cycle-to-date usage info and bill prediction pushed to IHDs via AMI Network.			
Outage Management System	AMI is integrated with enterprise OMS. An additional project OMS (redundant) will also be implemented in conjunction with a DMS. The project AMI was incorporated into the existing AMR to enterprise OMS interfaces including meter outage alerts and meter "ping" functionality to verify power restoration.	AMI is integrated with enterprise OMS. An additional project OMS (redundant) will also be implemented in conjunction with a DMS. The project AMI was incorporated into the existing AMR to enterprise OMS interfaces including meter outage alerts and meter "ping" functionality to verify power restoration.			
Distribution Management System	DMS is integrated with multiple project and legacy systems including AMI, DERM, OMS, energy storage.	DMS is integrated with multiple project and legacy systems including AMI, DERM, OMS, energy storage.			
Other Enterprise Systems	Data Mining and Analysis Tool (DataRaker) covered by the MDA	Data Mining and Analysis Tool (DataRaker) covered by the MDA			
Additional Project Descriptions	N/A				
AMI Installed Costs					
	Units	Project Funded	Cost Share		
Back Office Systems	\$	2,294,074	2,117,607		
Communications Equipment	\$	119,308	110,130		
AMI Smart Meters	\$	2,249,422	2,076,390		

Page 4 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2013	
Period	Start: Jul 1, 2013	End: Sep 30, 2013	Submission Due Date: October 31, 2013

AMI Installed Costs	Units	Project Funded	Cost Share
Other Costs	5		
Other Costs Description	N/A		

Page 5 of 24 Custom Created: October 4, 2011



Metric Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2013	
Period	Start: Jul 1, 2013	End: Sep 30, 2013	Submission Due Date: October 31, 2013

Customer Systems Assets - Build Metrics			
All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.			
Implemented Customer Systems	Units	Project	System
In-Home display: devices installed	#	625	625
Direct Load Control Devices: devices installed	#	129	129
Programmable Communicating Thermostats: devices installed	#	109	53,192
Smart Appliances: devices installed	#	0	0
Energy Management Devices/Systems: devices installed	#	0.0	0.0
Other Devices installed	#	59	59
Other Devices installed	#		
Other Devices installed	#		
Web Portal	Units	Project	System
Web portal is portal in production?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Customers with access	#	11,869	11,869
Customers with active accounts	#	2,040	2,040
Customer System Descriptions			
	Project	System	
In-Home Displays	Tendril In-Sight	Tendril In-Sight	

Page 6 of 24 Custom Created: October 4, 2011



Metric Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2013	
		Period	Start: Jul 1, 2013	End: Sep 30, 2013 Submission Due Date: October 31, 2013
Customer System Descriptions				
	Project	System		
Direct Load Control Devices	Tendril Volt	Tendril Volt		
Programmable Communicating Thermostats	Tendril Setpoint	Tendril Setpoint and Honeywell PCTs		
Smart Appliances	N/A	N/A		
Energy Mgmt. Systems	N/A	N/A		
Web Portal	Tendril Energize Web Portal	Tendril Energize Web Portal		
Home Area Network	Zigbee SEP 1.0	Zigbee SEP 1.0		

Page 7 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2013	
		Period	Start: Jul 1, 2013	End: Sep 30, 2013 Submission Due Date: October 31, 2013
Customer System Descriptions				
	Project	System		
Other Device	Tendril Transport Gateway	Tendril Transport Gateway		
HAN Gateway				
Other Device	N/A	N/A		
Other Device	N/A	N/A		
Additional Project Descriptions	N/A			

Customer System Installed Costs	Units	Project Funded	Cost Share
Back Office Systems	\$	437,920	404,234
Web Portals	\$	730,051	673,893
In-Home Displays	\$	155,669	143,694
Direct Load Control Devices	\$	90,344	83,395
Smart Appliances	\$	0	0
Programmable Communicating Thermostats	\$	354,650	327,369
Cost of other devices installed: HAN Gateway	\$	214,544	198,041

Page 8 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2013	
Period	Start: Jul 1, 2013	End: Sep 30, 2013	Submission Due Date: October 31, 2013

Customer System Installed Costs	Units	Project Funded	Cost Share
Cost of other devices installed	\$	[]	[]
Cost of other devices installed	\$	[]	[]
Other Costs	\$	344,807	318,284
Other Cost Description	Program delivery costs including KCP&L labor for program administration, analysis, and customer engagement as well as vendor travel expenses.		

Page 9 of 24 Custom Created: October 4, 2011

Master Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2013	
Period	Start: Jul 1, 2013	End: Sep 30, 2013	Submission Due Date: October 31, 2013

Pricing Programs - Build Metrics

All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.

Implemented Rate Plans	Units	Project	System
Flat Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Flat Rate: number of customers with access	#	[]	[]
Flat Rate: number of customers enrolled	#	[]	544,218
Flat Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Critical Peak Pricing: number of customers with access	#	[]	[]
Flat Rate with Critical Peak Pricing: number of customers enrolled	#	[]	[]
Flat Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Peak Time Rebate: number of customers with access	#	[]	[]
Flat Rate with Peak Time Rebate: number of customers enrolled	#	[]	[]
Tiered Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Tiered Rate: number of customers with access	#	[]	[]
Tiered Rate: number of customers enrolled	#	[]	302,264
Tiered Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Critical Peak Pricing: number of customers with access	#	[]	[]
Tiered Rate with Critical Peak Pricing: number of customers enrolled	#	[]	[]
Tiered Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Peak Time Rebate: number of customers with access	#	[]	[]
Tiered Rate with Peak Time Rebate: number of customers enrolled	#	[]	[]
Time of Use Rate: is the pricing program available?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Time of Use Rate: number of customers with access	#	12,188	[]

Page 10 of 24 Custom Created: October 4, 2011

Master Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2013	
Period	Start: Jul 1, 2013	End: Sep 30, 2013	Submission Due Date: October 31, 2013

Implemented Rate Plans	Units	Project	System
Time of Use Rate: number of customers enrolled	#	131	554
Time of Use Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Time of Use Rate with Critical Peak Pricing: number of customers with access	#		
Time of Use Rate with Critical Peak Pricing: number of customers enrolled	#		
Time of Use Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Time of Use Rate with Peak Time Rebate: number of customers with access	#		
Time of Use Rate with Peak Time Rebate: number of customers enrolled	#		
Real-time Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Real-time Pricing: number of customers with access	#		
Real-time Pricing: number of customers enrolled	#		9
Real-time Pricing with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Real-time Pricing with Critical Peak Pricing: number of customers with access	#		
Real-time Pricing with Critical Peak Pricing: number of customers enrolled	#		
Real-time Pricing with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Real-time Pricing with Peak Time Rebate: number of customers with access	#		
Real-time Pricing with Peak Time Rebate: number of customers enrolled	#		
Variable Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Variable Peak Pricing: number of customers with access	#		
Variable Peak Pricing: number of customers enrolled	#		
Pre-pay Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Pre-pay Pricing: number of customers with access	#		
Pre-pay Pricing: number of customers enrolled	#		
Net Metering: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>

Page 11 of 24 Custom Created: October 4, 2011


Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2013	
Period	Start: Jul 1, 2013	End: Sep 30, 2013	Submission Due Date: October 31, 2013

Implemented Rate Plans	Units	Project	System
Net Metering: number of customers with access	#		
Net Metering: number of customers enrolled	#		955
Other program available	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: number of customers with access	#		
Other programs: number of customers enrolled	#		
Other program available	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: number of customers with access	#		
Other programs: number of customers enrolled	#		
Other program available	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: number of customers with access	#		
Other programs: number of customers enrolled	#		
Rate Decoupling: is implemented?	yes/ no	<input type="checkbox"/>	

Rate Plan Descriptions	Project	System
Flat Rate	N/A	KCP&L has multiple residential and C&I Flat Rates that occur during both summer and winter. We are not able to calculate an accurate number for how many customers have access.
Flat Rate with Critical Peak Pricing	N/A	N/A

Page 12 of 24 Custom Created: October 4, 2011


Metric Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		
Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2013
Period	Start: Jul 1, 2013	End: Sep 30, 2013 Submission Due Date: October 31, 2013
Rate Plan Descriptions		
	Project	System
Flat Rate with Peak Time Rebate	N/A	N/A
Tiered Rate	N/A	KCP&L has multiple existing residential and C&I Tiered Rates. A majority of those are declining block rates. We are not able to calculate an accurate number for how many customers have access.
Tiered Rate with Critical Peak Pricing	N/A	N/A
Tiered Rate with Peak Time Rebate	N/A	N/A
Time of Use Rate	A new residential TOU rate is being piloted as part of this project to augment the evaluation of customer systems and devices.	KCP&L has multiple existing residential and C&I TOU Rates. We are not able to calculate an accurate number for how many customers have access.
Time of Use Rate with Critical Peak Pricing	N/A	N/A

Page 13 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		
Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2013
Period	Start: Jul 1, 2013	End: Sep 30, 2013 Submission Due Date: October 31, 2013
Rate Plan Descriptions		
	Project	System
Time of Use Rate with Peak Time Rebate	N/A	N/A
Real-Time Rate	N/A	KCP&L has multiple existing RTP rates for commercial and industrial customers. We are not able to calculate an accurate number for how many customers have access.
Real-time Rate with Critical Peak Pricing	N/A	N/A
Real-time Rate with Peak Time Rebate	N/A	N/A
Variable Peak Pricing	N/A	N/A
Pre-paid Rate	N/A	N/A

Page 14 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2013		
		Period	Start: Jul 1, 2013	End: Sep 30, 2013	Submission Due Date: October 31, 2013

Rate Plan Descriptions		
	Project	System
Net Metering Rate	N/A	KCP&L has multiple existing residential and C&I Net Metering Rates. We are not able to calculate an accurate number for how many customers have access.
Other program	N/A	N/A
Other program	N/A	N/A
Other program	N/A	N/A
Additional Project Descriptions	N/A	

Page 15 of 24 Custom Created: October 4, 2011 Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2013		
		Period	Start: Jul 1, 2013	End: Sep 30, 2013	Submission Due Date: October 31, 2013

Distributed Energy Resources - Build Metrics			
<i>All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.</i>			
Distributed Energy Resources	Units	Project	System
Distributed generation: number of units	#	7	936
Distributed generation: installed capacity	KW	137.57	17,808.54
Distributed generation: total energy delivered	* kWh	45,625	
Energy storage: number of units	#	1	1
Energy storage: installed capacity	KW	1,000	1,000
Energy storage: total energy delivered	* kWh	8,912	8,912
Plug-in electric vehicles charging points: number of units	#	9	20
Plug-in electric vehicles charging points: installed capacity	KW	119	234
Plug-in electric vehicles charging points: total energy delivered	* kWh	1,033	4,156
DER/DG interconnection equipment: number of units	#		

* Energy delivered should be reported just for the quarter being reported, not cumulative for the project to-date.

Distributed Energy Resource Descriptions		
	Project	System
Distributed Generation Interface Description	All DG installed is non-dispatchable utility-owned PV that is being metered separately. All project EV chargers are installed behind customer meters. Most interfaces currently limited to measuring data. EV chargers may be remotely deactivated to curtail load.	Non-dispatchable utility-owned DG and EV Chargers. All EV chargers are installed behind customer meters. Most interfaces currently limited to measuring data. EV chargers may be remotely deactivated to curtail load.

Page 16 of 24 Custom Created: October 4, 2011 Meter Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2013	
Period	Start: Jul 1, 2013	End: Sep 30, 2013	Submission Due Date: October 31, 2013

Additional Project Descriptions:

Distributed Energy Resources' Installed Costs	Units	Project Funded	Cost Share
DER Interface Control Systems	\$	2,364,927	2,183,009
Communications Equipment	\$	0	
DER/DG Interconnection Equipment	\$	0	
Renewable DER	\$	595,519	541,403
Distributed Generation Equipment	\$	0	0
Stationary Electric Storage Equipment	\$	4,012,656	3,703,991
PEVs and Charging Stations	\$	56,711	52,349
Other Costs	\$		
Other Cost Description	N/A		

Page 17 of 24 Custom Created: October 4, 2011



Master Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2013	
Period	Start: Jul 1, 2013	End: Sep 30, 2013	Submission Due Date: October 31, 2013

Electric Distribution System Assets - Build Metrics

All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.

Implemented Distribution Devices	Units	Project	System
Portion of system with SCADA	%	100	10.5
Portion of system with Distribution Automation (DA)	%	60	85
Automated Feeder Switches: number of devices installed	#	5	102
Automated Capacitors: number of devices installed	#	29	2,332
Automated Regulators: number of devices installed	#	0	3
Feeder Monitors: number of devices installed	#	0	0
Remote Fault Indicators: number of devices installed	#	25	254
Transformer Monitors (line): number of devices installed	#	0	0
Smart Relays: number of devices installed	#	63	2,277
Fault Current Limiter: number of devices installed	#	0	0
Other devices installed:	#		
Other devices installed:	#		
Other devices installed:	#		

DA Applications in Operation	Units	Project	System
Fault Location, Isolation, and Service Restoration (FLISR): is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Voltage Optimization: is this application in operation?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Feeder Peak Load Management: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Microgrids: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other DA Application: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>

Page 16 of 24 Custom Created: October 4, 2011



Master Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2013	
Period	Start: Jul 1, 2013	End: Sep 30, 2013	Submission Due Date: October 31, 2013

Distribution Management System Integration

	Units	Project	System
AMI: is integration complete?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Outage Management System: is integration complete?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Transmission Management System: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Distributed Energy Resources: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other Systems: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>

Distribution Device Description

	Project	System
SCADA	Distribution SCADA in conjunction with project DMS/CMS, includes a Tropos wireless network to reach devices outside the substation.	ABB Network Manager (EMS) across system plus project Distribution SCADA.
Portion of system with SCADA	Distribution SCADA has been deployed to all field devices in the project area.	The ABB Network Manager (EMS) communicates with 70% of feeder breakers, but only 15% of those have communications capable of supporting Smart Grid functionality.
Portion of system with DA	DA capabilities are installed on all project circuits.	KCP&L has locally automated devices such as capacitors, voltage monitors, faulted circuit indicators, and reclosers across the distribution system. 80% represents an estimate of coverage based on number of circuits with one or more of these devices.
DA devices	There is a mix of communicating and automated capacitors, faulted circuit indicators, and reclosers across the project area.	There is a mix of locally automated capacitors, voltage monitors, faulted circuit indicators, and reclosers across distribution system.

Page 19 of 24 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2013	
Period	Start: Jul 1, 2013	End: Sep 30, 2013	Submission Due Date: October 31, 2013

Distribution Device Description

	Project	System
DA communications network	Tropos GridCom wireless IP mesh network	Lands+Gyr AMR system and Telemetric/Sensus cellular-based system.
Other device	N/A	N/A
Other device	N/A	N/A
Other device	N/A	N/A

Distribution Application Descriptions

	Project	System
FLISR	As part of the project, the DMS enables FLISR across project circuits. This will reduce outages and outage response time, and improve overall system performance.	As part of the project, the DMS enables FLISR across project circuits. This will reduce outages and outage response time, and improve overall system performance.

Page 20 of 24 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2013	
		Period	Start: Jul 1, 2013	End: Sep 30, 2013 Submission Due Date: October 31, 2013
Voltage Optimization	As part of the project, the DMS enables voltage optimization across project circuits. This will improve power factor as well as enable voltage conservation.		A Dynamic Voltage Control (DVC) system exists on 203 buses within metropolitan Kansas City. This system is able to dynamically reduce voltage through load tap changers to achieve voltage changes in coordination with locally controlled cap banks.	
Feeder Peak Load Management	As part of the project, the DMS enables dynamic feeder load transfer across project circuits. This will reduce outages on project feeders, reduce stress on critical assets, and improve maintenance.		System peak loads are curtailed through utilization of the DVC system and existing PCT program operated by Honeywell.	
Microgrids	N/A		N/A	
Other DA Applications	N/A		N/A	
Distribution Management Integration Descriptions				
	Project	System		
AMI	DMS is integrated with project AMI.	DMS is integrated with project AMI.		
Outage Management	DMS is integrated with project OMS.	DMS is integrated with project OMS.		

Page 21 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2013	
		Period	Start: Jul 1, 2013	End: Sep 30, 2013 Submission Due Date: October 31, 2013
Distribution Management Integration Descriptions				
	Project	System		
Transmission Management	N/A	N/A		
DER Systems	DMS is integrated with project DERM.	DMS is integrated with project DERM.		
Distribution Management System	DMS consisting of D-SCADA and DNA provided by Siemens and OMS and user interface provided by Intergraph.	DMS consisting of D-SCADA and DNA provided by Siemens and OMS and user interface provided by Intergraph.		
Other Systems	N/A	N/A		
Additional Project Descriptions	N/A			
Distribution Systems Installed Costs				
Back Office Systems	\$	380,410	332,888	
Distribution Management System	\$	2,905,740	2,682,222	
Communications Equipment and SCADA	\$	885,575	817,454	

Page 22 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2013	
Period	Start: Jul 1, 2013	End: Sep 30, 2013	Submission Due Date: October 31, 2013

Distribution Systems Installed Costs	Units	Project Funded	Cost Share
Feeder Monitor/Indicator	\$	31,408	28,992
Substation Monitors	\$	1,231,064	1,138,367
Automated Feeder Switches	\$	782,638	722,435
Capacitor Automation Equipment	\$	87,795	81,041
Regulator Automation Equipment	\$		
Fault Current Limiter Equipment	\$		
Cost of other devices installed	\$		
Cost of other devices installed	\$		
Cost of other devices installed	\$		
Other Costs	\$	355,476	328,132
Other Cost Description	KCP&L Labor costs for various components		

Page 23 of 24 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2013	
Period	Start: Jul 1, 2013	End: Sep 30, 2013	Submission Due Date: October 31, 2013

Submit
Print Form

Page 24 of 24 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.2

S.15 2013 Q4

SMARTGRID.GOV		Project	DE-OE000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 4, 2013	
		Period	Start: Oct 1, 2013	End: Dec 31, 2013 Submission Due Date: January 31, 2014
AMI Assets - Build Metrics				
<i>All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.</i>				
AMI End Points Installed		Units	Project	System
End Points (meters) installed and operational	#		13,417	13,417
Portion of customers with AMI residential	#		12,192	12,192
Portion of customers with AMI commercial	#		1,225	1,225
Portion of customers with AMI industrial	#		0	0
Implemented Meter Features		Units	Project	System
Reading interval for residential meters	minutes		15	15
Reading interval for commercial meters	minutes		15	15
Reading interval for industrial meters	minutes		0	0
Remote Connect/Disconnect: is feature implemented?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Remote Connect/Disconnect: number of meters with feature implemented	#		13,417	13,417
Outage Reporting: is feature implemented?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Outage Reporting: number of meters with feature implemented	#		13,417	13,417
Power Quality Measurement: is feature implemented?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>
Power Quality Measurement: number of meters with feature implemented	#			
Tamper Detection: is feature implemented?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Tamper Detection: number of meters with feature implemented	#		13,417	13,417
Other feature implemented	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>
Other feature: number of meters with feature implemented	#			
Other feature implemented	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>
Other feature: number of meters with feature implemented	#			
Other feature implemented	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>
Other feature: number of meters with feature implemented	#			

Page 1 of 24 Custom Created: October 8, 2011 Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 4, 2013	
		Period	Start: Oct 1, 2013	End: Dec 31, 2013 Submission Due Date: January 31, 2014
Implemented Meter Features		Units	Project	System
Other feature: number of meters with feature implemented	#			
Implemented Enterprise Integration		Units	Project	System
Billing System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Customer Information System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Outage Management System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Distribution Management System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Other Enterprise Systems: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
AMI System Descriptions				
	Project	System		
Backhaul Network	Hybrid of Fiber and Wireless Raven radio with network carrier	Hybrid of Fiber and Wireless Raven radio with network carrier		
Meter Communication Network	Lands+Gyr Gridstream RF 900MHz - Collectors and Routers	Lands+Gyr Gridstream RF 900MHz - Collectors and Routers		
Headend System	Lands+Gyr Command Center	Lands+Gyr Command Center		
Meter Data Management System	eMeter/Siemens	eMeter/Siemens		

Page 2 of 24 Custom Created: October 8, 2011 Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 4, 2013		
		Period	Start: Oct 1, 2013	End: Dec 31, 2013	Submission Due Date: January 31, 2014
AMI System Descriptions					
	Project	System			
Meter Data Analysis	The project AMI was incorporated into the existing AMR – MDA interfaces. AMI daily register reads and 15-min interval reads are loaded into MDA (DataRaker) on a daily basis.	The project AMI was incorporated into the existing AMR – MDA interfaces. AMI daily register reads and 15-min interval reads are loaded into MDA (DataRaker) on a daily basis.			
Other Meter Feature	N/A	N/A			
Other Meter Feature	N/A	N/A			
Other Meter Feature	N/A	N/A			
AMI Enterprise Integration Descriptions					
	Project	System			
Billing System	AMI is integrated with enterprise Oracle CIS.	AMI is integrated with enterprise Oracle CIS.			

Page 3 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 4, 2013		
		Period	Start: Oct 1, 2013	End: Dec 31, 2013	Submission Due Date: January 31, 2014
AMI Enterprise Integration Descriptions					
	Project	System			
Customer Information System	AMI is integrated with KCP&L enterprise Oracle CIS. The project AMI was incorporated into the existing AMR – CIS interfaces. CIS daily account/meter synchronization. AMI provides CIS daily register meter reads for direct billing. CIS daily billing cycle-to-date usage info and bill prediction pushed to IHDs via AMI Network.	AMI is integrated with KCP&L enterprise Oracle CIS. The project AMI was incorporated into the existing AMR – CIS interfaces. CIS daily account/meter synchronization. AMI provides CIS daily register meter reads for direct billing. CIS daily billing cycle-to-date usage info and bill prediction pushed to IHDs via AMI Network.			
Outage Management System	AMI is integrated with enterprise OMS. An additional project OMS (redundant) will also be implemented in conjunction with a DMS. The project AMI was incorporated into the existing AMR to enterprise OMS interfaces including meter outage alerts and meter "ping" functionality to verify power restoration.	AMI is integrated with enterprise OMS. An additional project OMS (redundant) will also be implemented in conjunction with a DMS. The project AMI was incorporated into the existing AMR to enterprise OMS interfaces including meter outage alerts and meter "ping" functionality to verify power restoration.			
Distribution Management System	DMS is integrated with multiple project and legacy systems including AMI, DERM, OMS, and energy storage.	DMS is integrated with multiple project and legacy systems including AMI, DERM, OMS, and energy storage.			
Other Enterprise Systems	Data Mining and Analysis Tool (DataRaker) covered by the MDA	Data Mining and Analysis Tool (DataRaker) covered by the MDA			
Additional Project Descriptions	N/A				
AMI Installed Costs		Units	Project Funded	Cost Share	
Back Office Systems		\$	2,337,739	2,157,913	
Communications Equipment		\$	119,308	110,130	
AMI Smart Meters		\$	2,249,422	2,076,390	

Page 4 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2013	
Period	Start: Oct 1, 2013	End: Dec 31, 2013	Submission Due Date: January 31, 2014

AMI Installed Costs	Units	Project Funded	Cost Share
Other Costs	5		
Other Costs Description	N/A		

Page 5 of 24 Custom Created: October 4, 2011



Metric Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2013	
Period	Start: Oct 1, 2013	End: Dec 31, 2013	Submission Due Date: January 31, 2014

Customer Systems Assets - Build Metrics			
All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.			
Implemented Customer Systems	Units	Project	System
In-Home display: devices installed	#	620	620
Direct Load Control Devices: devices installed	#	132	132
Programmable Communicating Thermostats: devices installed	#	115	53,824
Smart Appliances: devices installed	#	0	0
Energy Management Devices/Systems: devices installed	#	0.0	0.0
Other Devices installed	#	61	61
Other Devices installed	#		
Other Devices installed	#		
Web Portal	Units	Project	System
Web portal is portal in production?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Customers with access	#	12,036	12,036
Customers with active accounts	#	2,109	2,109
Customer System Descriptions			
	Project	System	
In-Home Displays	Tendril In-Sight	Tendril In-Sight	

Page 6 of 24 Custom Created: October 4, 2011



Metric Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 4, 2013		
		Period	Start: Oct 1, 2013	End: Dec 31, 2013	Submission Due Date: January 31, 2014
Customer System Descriptions					
	Project	System			
Direct Load Control Devices	Tendril Volt	Tendril Volt			
Programmable Communicating Thermostats	Tendril Setpoint	Tendril Setpoint and Honeywell PCTs			
Smart Appliances	N/A	N/A			
Energy Mgmt. Systems	N/A	N/A			
Web Portal	Tendril Energize Web Portal	Tendril Energize Web Portal			
Home Area Network	Zigbee SEP 1.0	Zigbee SEP 1.0			

Page 7 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 4, 2013		
		Period	Start: Oct 1, 2013	End: Dec 31, 2013	Submission Due Date: January 31, 2014
Customer System Descriptions					
	Project	System			
Other Device	Tendril Transport Gateway	Tendril Transport Gateway			
HAN Gateway					
Other Device	N/A	N/A			
Other Device	N/A	N/A			
Additional Project Descriptions	N/A				

Customer System Installed Costs	Units	Project Funded	Cost Share
Back Office Systems	\$	440,110	406,255
Web Portals	\$	940,651	868,293
In-Home Displays	\$	155,669	143,694
Direct Load Control Devices	\$	90,344	83,395
Smart Appliances	\$	0	0
Programmable Communicating Thermostats	\$	362,999	335,076
Cost of other devices installed: HAN Gateway	\$	221,524	204,464

Page 8 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2013	
Period	Start: Oct 1, 2013	End: Dec 31, 2013	Submission Due Date: January 31, 2014

Customer System Installed Costs	Units	Project Funded	Cost Share
Cost of other devices installed	\$		
Cost of other devices installed	\$		
Other Costs	\$	387,262	357,473
Other Cost Description	Program delivery costs including KCP&L labor for program administration, analysis, and customer engagement as well as vendor travel expenses.		

Page 9 of 24 Custom Created: October 4, 2011

Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2013	
Period	Start: Oct 1, 2013	End: Dec 31, 2013	Submission Due Date: January 31, 2014

Pricing Programs - Build Metrics

All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.

Implemented Rate Plans	Units	Project	System
Flat Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Flat Rate: number of customers with access	#		
Flat Rate: number of customers enrolled	#		161,899
Flat Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Critical Peak Pricing: number of customers with access	#		
Flat Rate with Critical Peak Pricing: number of customers enrolled	#		
Flat Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Peak Time Rebate: number of customers with access	#		
Flat Rate with Peak Time Rebate: number of customers enrolled	#		
Tiered Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Tiered Rate: number of customers with access	#		
Tiered Rate: number of customers enrolled	#		687,854
Tiered Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Critical Peak Pricing: number of customers with access	#		
Tiered Rate with Critical Peak Pricing: number of customers enrolled	#		
Tiered Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Peak Time Rebate: number of customers with access	#		
Tiered Rate with Peak Time Rebate: number of customers enrolled	#		
Time of Use Rate: is the pricing program available?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Time of Use Rate: number of customers with access	#	12,192	

Page 10 of 24 Custom Created: October 4, 2011

Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2013	
Period	Start: Oct 1, 2013	End: Dec 31, 2013	Submission Due Date: January 31, 2014

Implemented Rate Plans	Units	Project	System
Time of Use Rate: number of customers enrolled	#	127	332
Time of Use Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Time of Use Rate with Critical Peak Pricing: number of customers with access	#		
Time of Use Rate with Critical Peak Pricing: number of customers enrolled	#		
Time of Use Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Time of Use Rate with Peak Time Rebate: number of customers with access	#		
Time of Use Rate with Peak Time Rebate: number of customers enrolled	#		
Real-time Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Real-time Pricing: number of customers with access	#		
Real-time Pricing: number of customers enrolled	#		9
Real-time Pricing with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Real-time Pricing with Critical Peak Pricing: number of customers with access	#		
Real-time Pricing with Critical Peak Pricing: number of customers enrolled	#		
Real-time Pricing with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Real-time Pricing with Peak Time Rebate: number of customers with access	#		
Real-time Pricing with Peak Time Rebate: number of customers enrolled	#		
Variable Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Variable Peak Pricing: number of customers with access	#		
Variable Peak Pricing: number of customers enrolled	#		
Pre-pay Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Pre-pay Pricing: number of customers with access	#		
Pre-pay Pricing: number of customers enrolled	#		
Net Metering: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>

Page 11 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2013	
Period	Start: Oct 1, 2013	End: Dec 31, 2013	Submission Due Date: January 31, 2014

Implemented Rate Plans	Units	Project	System
Net Metering: number of customers with access	#		
Net Metering: number of customers enrolled	#		1,180
Other program available	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: number of customers with access	#		
Other programs: number of customers enrolled	#		
Other program available	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: number of customers with access	#		
Other programs: number of customers enrolled	#		
Other program available	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: number of customers with access	#		
Other programs: number of customers enrolled	#		
Rate Decoupling: is implemented?	yes/ no	<input type="checkbox"/>	

Rate Plan Descriptions	Project	System
Flat Rate	N/A	KCP&L has multiple residential and C&I Flat Rates that occur during both summer and winter. We are not able to calculate an accurate number for how many customers have access.
Flat Rate with Critical Peak Pricing	N/A	N/A

Page 12 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		
Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2013
Period	Start: Oct 1, 2013	End: Dec 31, 2013 Submission Due Date: January 31, 2014
Rate Plan Descriptions		
	Project	System
Flat Rate with Peak Time Rebate	N/A	N/A
Tiered Rate	N/A	KCP&L has multiple existing residential and C&I Tiered Rates. A majority of those are declining block rates. We are not able to calculate an accurate number for how many customers have access.
Tiered Rate with Critical Peak Pricing	N/A	N/A
Tiered Rate with Peak Time Rebate	N/A	N/A
Time of Use Rate	A new residential TOU rate is being piloted as part of this project to augment the evaluation of customer information systems and control devices.	KCP&L has multiple existing residential and C&I TOU Rates. We are not able to calculate an accurate number for how many customers have access.
Time of Use Rate with Critical Peak Pricing	N/A	N/A

Page 13 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		
Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2013
Period	Start: Oct 1, 2013	End: Dec 31, 2013 Submission Due Date: January 31, 2014
Rate Plan Descriptions		
	Project	System
Time of Use Rate with Peak Time Rebate	N/A	N/A
Real-Time Rate	N/A	KCP&L has multiple existing RTP rates for commercial and industrial customers. We are not able to calculate an accurate number for how many customers have access.
Real-time Rate with Critical Peak Pricing	N/A	N/A
Real-time Rate with Peak Time Rebate	N/A	N/A
Variable Peak Pricing	N/A	N/A
Pre-paid Rate	N/A	N/A

Page 14 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 4, 2013		
		Period	Start: Oct 1, 2013	End: Dec 31, 2013	Submission Due Date: January 31, 2014

Rate Plan Descriptions		
	Project	System
Net Metering Rate	N/A	KCP&L has multiple existing residential and C&I Net Metering Rates. We are not able to calculate an accurate number for how many customers have access.
Other program	N/A	N/A
Other program	N/A	N/A
Other program	N/A	N/A
Additional Project Descriptions	N/A	

Page 15 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 4, 2013		
		Period	Start: Oct 1, 2013	End: Dec 31, 2013	Submission Due Date: January 31, 2014

Distributed Energy Resources - Build Metrics			
<i>All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.</i>			
Distributed Energy Resources	Units	Project	System
Distributed generation: number of units	#	7	1,161
Distributed generation: installed capacity	KW	137.57	22,329.517
Distributed generation: total energy delivered	* kWh	23,853	
Energy storage: number of units	#	1	1
Energy storage: installed capacity	KW	1,000	1,000
Energy storage: total energy delivered	* kWh	8,292	8,292
Plug-in electric vehicles charging points: number of units	#	10	22
Plug-in electric vehicles charging points: installed capacity	KW	133	263
Plug-in electric vehicles charging points: total energy delivered	* kWh	1,692	6,362
DER/DG interconnection equipment: number of units	#		

* Energy delivered should be reported just for the quarter being reported, not cumulative for the project to-date.

Distributed Energy Resource Descriptions		
	Project	System
Distributed Generation Interface Description	All DG installed is non-dispatchable utility-owned PV that is being metered separately. All project EV chargers are installed behind customer meters. Most interfaces currently limited to measuring data. EV chargers may be remotely deactivated to curtail load.	Non-dispatchable utility-owned DG and EV Chargers. All EV chargers are installed behind customer meters. Most interfaces currently limited to measuring data. EV chargers may be remotely deactivated to curtail load.

Page 16 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2013	
Period	Start: Oct 1, 2013	End: Dec 31, 2013	Submission Due Date: January 31, 2014

Additional Project Descriptions:

Distributed Energy Resources' Installed Costs	Units	Project Funded	Cost Share
DER Interface Control Systems	\$	2,364,927	2,183,009
Communications Equipment	\$	0	0
DER/DG Interconnection Equipment	\$	0	0
Renewable DER	\$	595,519	541,403
Distributed Generation Equipment	\$	0	0
Stationary Electric Storage Equipment	\$	4,017,121	3,708,112
PEVs and Charging Stations	\$	85,224	80,207
Other Costs	\$		
Other Cost Description	N/A		

Page 17 of 24 Custom Created: October 4, 2011



Master Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2013	
Period	Start: Oct 1, 2013	End: Dec 31, 2013	Submission Due Date: January 31, 2014

Electric Distribution System Assets - Build Metrics

All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.

Implemented Distribution Devices	Units	Project	System
Portion of system with SCADA	%	100	10.5
Portion of system with Distribution Automation (DA)	%	100	85
Automated Feeder Switches: number of devices installed	#	20	117
Automated Capacitors: number of devices installed	#	29	2,342
Automated Regulators: number of devices installed	#	0	3
Feeder Monitors: number of devices installed	#	0	0
Remote Fault Indicators: number of devices installed	#	96	325
Transformer Monitors (line): number of devices installed	#	0	0
Smart Relays: number of devices installed	#	83	2,277
Fault Current Limiter: number of devices installed	#	0	0
Other devices installed:	#		
Other devices installed:	#		
Other devices installed:	#		

DA Applications in Operation	Units	Project	System
Fault Location, Isolation, and Service Restoration (FLISR): is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Voltage Optimization: is this application in operation?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Feeder Peak Load Management: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Microgrids: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other DA Application: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>

Page 18 of 24 Custom Created: October 4, 2011



Master Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2013	
Period	Start: Oct 1, 2013	End: Dec 31, 2013	Submission Due Date: January 31, 2014

Distribution Management System Integration

	Units	Project	System
AMI: is integration complete?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Outage Management System: is integration complete?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Transmission Management System: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Distributed Energy Resources: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other Systems: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>

Distribution Device Description

	Project	System
SCADA	Distribution SCADA in conjunction with project DMS/CMS, includes a Tropos wireless network to reach devices outside the substation.	ABB Network Manager (EMS) across system plus project Distribution SCADA.
Portion of system with SCADA	Distribution SCADA has been deployed to all field devices in the project area.	The ABB Network Manager (EMS) communicates with 70% of feeder breakers, but only 15% of those have communications capable of supporting Smart Grid functionality.
Portion of system with DA	DA capabilities are installed on all project circuits.	KCP&L has locally automated devices such as capacitors, voltage monitors, faulted circuit indicators, and reclosers across the distribution system. 80% represents an estimate of coverage based on number of circuits with one or more of these devices.
DA devices	There is a mix of communicating and automated capacitors, faulted circuit indicators, and reclosers across the project area.	There is a mix of locally automated capacitors, voltage monitors, faulted circuit indicators, and reclosers across distribution system.

Page 19 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2013	
Period	Start: Oct 1, 2013	End: Dec 31, 2013	Submission Due Date: January 31, 2014

Distribution Device Description

	Project	System
DA communications network	Tropos GridCom wireless IP mesh network	Lands+Gyr AMR system and Telemetric/Sensus cellular-based system.
Other device	N/A	N/A
Other device	N/A	N/A
Other device	N/A	N/A

Distribution Application Descriptions

	Project	System
FLISR	As part of the project, the DMS enables FLISR across project circuits. This will reduce outages and outage response time, and improve overall system performance.	As part of the project, the DMS enables FLISR across project circuits. This will reduce outages and outage response time, and improve overall system performance.

Page 20 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 4, 2013	
		Period	Start: Oct 1, 2013	End: Dec 31, 2013 Submission Due Date: January 31, 2014
Voltage Optimization	As part of the project, the DMS enables voltage optimization across project circuits. This will improve power factor as well as enable voltage conservation.		A Dynamic Voltage Control (DVC) system exists on 203 buses within metropolitan Kansas City. This system is able to dynamically reduce voltage through load tap changers to achieve voltage changes in coordination with locally controlled cap banks.	
Feeder Peak Load Management	As part of the project, the DMS enables dynamic feeder load transfer across project circuits. This will reduce outages on project feeders, reduce stress on critical assets, and improve maintenance.		System peak loads are curtailed through utilization of the DVC system and existing PCT program operated by Honeywell.	
Microgrids	N/A		N/A	
Other DA Applications	N/A		N/A	
Distribution Management Integration Descriptions				
	Project		System	
AMI	DMS is integrated with project AMI.		DMS is integrated with project AMI.	
Outage Management	DMS is integrated with project OMS.		DMS is integrated with project OMS.	

Page 21 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 4, 2013	
		Period	Start: Oct 1, 2013	End: Dec 31, 2013 Submission Due Date: January 31, 2014
Distribution Management Integration Descriptions				
	Project		System	
Transmission Management	N/A		N/A	
DER Systems	DMS is integrated with project DERM.		DMS is integrated with project DERM.	
Distribution Management System	DMS consisting of D-SCADA and DNA provided by Siemens and OMS and user interface provided by Intergraph.		DMS consisting of D-SCADA and DNA provided by Siemens and OMS and user interface provided by Intergraph.	
Other Systems	N/A		N/A	
Additional Project Descriptions	N/A			
Distribution Systems Installed Costs				
	Units	Project Funded	Cost Share	
Back Office Systems	\$	371,896	343,106	
Distribution Management System	\$	3,723,298	3,436,891	
Communications Equipment and SCADA	\$	959,422	885,621	

Page 22 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2013	
Period	Start: Oct 1, 2013	End: Dec 31, 2013	Submission Due Date: January 31, 2014

Distribution Systems Installed Costs	Units	Project Funded	Cost Share
Feeder Monitor/Indicator	\$	25,896	23,876
Substation Monitors	\$	1,238,783	1,141,846
Automated Feeder Switches	\$	684,943	632,255
Capacitor Automation Equipment	\$	72,302	66,740
Regulator Automation Equipment	\$	0	0
Fault Current Limiter Equipment	\$	0	0
Cost of other devices installed	\$		
Cost of other devices installed	\$		
Cost of other devices installed	\$		
Other Costs	\$	368,136	339,818

Other Cost Description: KCP&L labor charges across various device types.

Page 23 of 24 Custom Created: October 8, 2011



Metric Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2013	
Period	Start: Oct 1, 2013	End: Dec 31, 2013	Submission Due Date: January 31, 2014

Submit
Print Form

Page 24 of 24 Custom Created: October 8, 2011



Metric Updated: April 8, 2011 Schema Version: 1.2

S.16 2014 Q1

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 1, 2014		
		Period	Start: Jan 1, 2014	End: Mar 31, 2014	Submission Due Date: April 30, 2014
AMI Assets - Build Metrics					
<i>All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.</i>					
AMI End Points Installed		Units	Project	System	
End Points (meters) installed and operational	#		13,498	35,974	
Portion of customers with AMI residential	#		12,268	32,220	
Portion of customers with AMI commercial	#		1,232	3,754	
Portion of customers with AMI industrial	#				
Implemented Meter Features		Units	Project	System	
Reading interval for residential meters	minutes		15	15	
Reading interval for commercial meters	minutes		15	15	
Reading interval for industrial meters	minutes				
Remote Connect/Disconnect: is feature implemented?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Remote Connect/Disconnect: number of meters with feature implemented	#		13,049	15,641	
Outage Reporting: is feature implemented?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Outage Reporting: number of meters with feature implemented	#		13,498	35,974	
Power Quality Measurement: is feature implemented?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Power Quality Measurement: number of meters with feature implemented	#				
Tamper Detection: is feature implemented?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Tamper Detection: number of meters with feature implemented	#		13,498	35,974	
Other feature implemented	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other feature: number of meters with feature implemented	#				
Other feature implemented	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other feature: number of meters with feature implemented	#				
Other feature implemented	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other feature: number of meters with feature implemented	#				

Page 1 of 24 Custom Created: October 8, 2011 Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 1, 2014		
		Period	Start: Jan 1, 2014	End: Mar 31, 2014	Submission Due Date: April 30, 2014
Implemented Meter Features		Units	Project	System	
Other feature: number of meters with feature implemented	#				
Implemented Enterprise Integration		Units	Project	System	
Billing System: is integration complete?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Customer Information System: is integration complete?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Outage Management System: is integration complete?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Distribution Management System: is integration complete?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other Enterprise Systems: is integration complete?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
AMI System Descriptions					
	Project	System			
Backhaul Network	Hybrid of Fiber and Wireless Raven radio with network carrier	Hybrid of Fiber and Wireless Raven radio with network carrier			
Meter Communication Network	Lands+Gyr Gridstream RF 900MHz - Collectors and Routers	Lands+Gyr Gridstream RF 900MHz - Collectors and Routers			
Headend System	Lands+Gyr Command Center	Lands+Gyr Command Center			
Meter Data Management System	eMeter/Siemens	eMeter/Siemens			

Page 2 of 24 Custom Created: October 8, 2011 Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 1, 2014		
		Period	Start: Jan 1, 2014	End: Mar 31, 2014	Submission Due Date: April 30, 2014
AMI System Descriptions					
	Project	System			
Meter Data Analysis	The project AMI was incorporated into the existing AMR – MDA interfaces. AMI daily register reads and 15-min interval reads are loaded into MDA (DataRaker) on a daily basis.	The project AMI was incorporated into the existing AMR – MDA interfaces. AMI daily register reads and 15-min interval reads are loaded into MDA (DataRaker) on a daily basis.			
Other Meter Feature	N/A	N/A			
Other Meter Feature	N/A	N/A			
Other Meter Feature	N/A	N/A			
AMI Enterprise Integration Descriptions					
	Project	System			
Billing System	AMI is integrated with enterprise Oracle CIS.	AMI is integrated with enterprise Oracle CIS.			

Page 3 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 1, 2014		
		Period	Start: Jan 1, 2014	End: Mar 31, 2014	Submission Due Date: April 30, 2014
AMI Enterprise Integration Descriptions					
	Project	System			
Customer Information System	AMI is integrated with KCP&L enterprise Oracle CIS. The project AMI was incorporated into the existing AMR – CIS interfaces. CIS daily account/meter synchronization. AMI provides CIS daily register meter reads for direct billing. CIS daily billing cycle-to-date usage info and bill prediction pushed to IHDs via AMI Network.	AMI is integrated with KCP&L enterprise Oracle CIS. The project AMI was incorporated into the existing AMR – CIS interfaces. CIS daily account/meter synchronization. AMI provides CIS daily register meter reads for direct billing. CIS daily billing cycle-to-date usage info and bill prediction pushed to IHDs via AMI Network.			
Outage Management System	AMI is integrated with enterprise OMS. An additional project OMS (redundant) will also be implemented in conjunction with a DMS. The project AMI was incorporated into the existing AMR to enterprise OMS interfaces including meter outage alerts and meter "ping" functionality to verify power restoration.	AMI is integrated with enterprise OMS. An additional project OMS (redundant) will also be implemented in conjunction with a DMS. The project AMI was incorporated into the existing AMR to enterprise OMS interfaces including meter outage alerts and meter "ping" functionality to verify power restoration.			
Distribution Management System	DMS is integrated with multiple project and legacy systems including AMI, DERM, OMS, and energy storage.	DMS is integrated with multiple project and legacy systems including AMI, DERM, OMS, and energy storage.			
Other Enterprise Systems	Data Mining and Analysis Tool (DataRaker) covered by the MDA	Data Mining and Analysis Tool (DataRaker) covered by the MDA			
Additional Project Descriptions	N/A				
AMI Installed Costs		Units	Project Funded	Cost Share	
Back Office Systems	\$	2,337,739	2,157,913		
Communications Equipment	\$	119,308	110,130		
AMI Smart Meters	\$	2,249,422	2,076,390		

Page 4 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 1, 2014	
Period	Start: Jan 1, 2014	End: Mar 31, 2014	Submission Due Date: April 30, 2014

AMI Installed Costs	Units	Project Funded	Cost Share
Other Costs	5		
Other Costs Description	N/A		

Page 5 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 1, 2014	
Period	Start: Jan 1, 2014	End: Mar 31, 2014	Submission Due Date: April 30, 2014

Customer Systems Assets - Build Metrics			
All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.			
Implemented Customer Systems	Units	Project	System
In-Home display: devices installed	#	620	620
Direct Load Control Devices: devices installed	#	132	132
Programmable Communicating Thermostats: devices installed	#	115	53,824
Smart Appliances: devices installed	#		
Energy Management Devices/Systems: devices installed	#		
Other Devices installed	#	61	61
Other Devices installed	#		
Other Devices installed	#		
Web Portal	Units	Project	System
Web portal is portal in production?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Customers with access	#	12,036	12,036
Customers with active accounts	#	2,109	2,109
Customer System Descriptions			
	Project	System	
In-Home Displays	Tendril In-Sight	Tendril In-Sight	

Page 6 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 1, 2014		
		Period	Start: Jan 1, 2014	End: Mar 31, 2014	Submission Due Date: April 30, 2014
Customer System Descriptions					
	Project	System			
Direct Load Control Devices	Tendril Volt	Tendril Volt			
Programmable Communicating Thermostats	Tendril Setpoint	Tendril Setpoint and Honeywell PCTs			
Smart Appliances	N/A	N/A			
Energy Mgmt. Systems	N/A	N/A			
Web Portal	Tendril Energize Web Portal	Tendril Energize Web Portal			
Home Area Network	Zigbee SEP 1.0	Zigbee SEP 1.0			

Page 7 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 1, 2014		
		Period	Start: Jan 1, 2014	End: Mar 31, 2014	Submission Due Date: April 30, 2014
Customer System Descriptions					
	Project	System			
Other Device	Tendril Transport Gateway	Tendril Transport Gateway			
HAN Gateway					
Other Device	N/A	N/A			
Other Device	N/A	N/A			
Additional Project Descriptions	N/A				

Customer System Installed Costs	Units	Project Funded	Cost Share
Back Office Systems	\$	440,885	408,255
Web Portals	\$	940,730	868,293
In-Home Displays	\$	155,668	143,694
Direct Load Control Devices	\$	90,344	83,385
Smart Appliances	\$		
Programmable Communicating Thermostats	\$	378,220	335,076
Cost of other devices installed: HAN Gateway	\$	228,218	204,484

Page 8 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 1, 2014	
Period	Start: Jan 1, 2014	End: Mar 31, 2014	Submission Due Date: April 30, 2014

Customer System Installed Costs	Units	Project Funded	Cost Share
Cost of other devices installed	\$		
Cost of other devices installed	\$		
Other Costs	\$	389,053	357,473
Other Cost Description	Program delivery costs including KCP&L labor for program administration, analysis, and customer engagement as well as vendor travel expenses.		

Page 9 of 24 Custom Created: October 4, 2011

Master Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 1, 2014	
Period	Start: Jan 1, 2014	End: Mar 31, 2014	Submission Due Date: April 30, 2014

Pricing Programs - Build Metrics

All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.

Implemented Rate Plans	Units	Project	System
Flat Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Flat Rate: number of customers with access	#		
Flat Rate: number of customers enrolled	#		162,021
Flat Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Critical Peak Pricing: number of customers with access	#		
Flat Rate with Critical Peak Pricing: number of customers enrolled	#		
Flat Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Peak Time Rebate: number of customers with access	#		
Flat Rate with Peak Time Rebate: number of customers enrolled	#		
Tiered Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Tiered Rate: number of customers with access	#		
Tiered Rate: number of customers enrolled	#		689,583
Tiered Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Critical Peak Pricing: number of customers with access	#		
Tiered Rate with Critical Peak Pricing: number of customers enrolled	#		
Tiered Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Peak Time Rebate: number of customers with access	#		
Tiered Rate with Peak Time Rebate: number of customers enrolled	#		
Time of Use Rate: is the pricing program available?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Time of Use Rate: number of customers with access	#	12,266	

Page 10 of 24 Custom Created: October 4, 2011

Master Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 1, 2014	
Period	Start: Jan 1, 2014	End: Mar 31, 2014	Submission Due Date: April 30, 2014

Implemented Rate Plans	Units	Project	System
Time of Use Rate: number of customers enrolled	#	118	332
Time of Use Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Time of Use Rate with Critical Peak Pricing: number of customers with access	#		
Time of Use Rate with Critical Peak Pricing: number of customers enrolled	#		
Time of Use Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Time of Use Rate with Peak Time Rebate: number of customers with access	#		
Time of Use Rate with Peak Time Rebate: number of customers enrolled	#		
Real-time Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Real-time Pricing: number of customers with access	#		
Real-time Pricing: number of customers enrolled	#		8
Real-time Pricing with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Real-time Pricing with Critical Peak Pricing: number of customers with access	#		
Real-time Pricing with Critical Peak Pricing: number of customers enrolled	#		
Real-time Pricing with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Real-time Pricing with Peak Time Rebate: number of customers with access	#		
Real-time Pricing with Peak Time Rebate: number of customers enrolled	#		
Variable Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Variable Peak Pricing: number of customers with access	#		
Variable Peak Pricing: number of customers enrolled	#		
Pre-pay Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Pre-pay Pricing: number of customers with access	#		
Pre-pay Pricing: number of customers enrolled	#		
Net Metering: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>

Page 11 of 24 Custom Created: October 4, 2011

Metric Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 1, 2014	
Period	Start: Jan 1, 2014	End: Mar 31, 2014	Submission Due Date: April 30, 2014

Implemented Rate Plans	Units	Project	System
Net Metering: number of customers with access	#		
Net Metering: number of customers enrolled	#		1,554
Other program available	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: number of customers with access	#		
Other programs: number of customers enrolled	#		
Other program available	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: number of customers with access	#		
Other programs: number of customers enrolled	#		
Other program available	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: number of customers with access	#		
Other programs: number of customers enrolled	#		
Rate Decoupling: is implemented?	yes/ no	<input type="checkbox"/>	

Rate Plan Descriptions	Project	System
Flat Rate	N/A	KCP&L has multiple residential and C&I Flat Rates that occur during both summer and winter. We are not able to calculate an accurate number for how many customers have access.
Flat Rate with Critical Peak Pricing	N/A	N/A

Page 12 of 24 Custom Created: October 4, 2011

Metric Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 1, 2014		
		Period	Start: Jan 1, 2014	End: Mar 31, 2014	Submission Due Date: April 30, 2014
Rate Plan Descriptions					
	Project	System			
Flat Rate with Peak Time Rebate	N/A	N/A			
Tiered Rate	N/A	KCP&L has multiple existing residential and CSI Tiered Rates. A majority of those are declining block rates. We are not able to calculate an accurate number for how many customers have access.			
Tiered Rate with Critical Peak Pricing	N/A	N/A			
Tiered Rate with Peak Time Rebate	N/A	N/A			
Time of Use Rate	A new residential TOU rate is being piloted as part of this project to augment the evaluation of customer information systems and control devices.	KCP&L has multiple existing residential and CSI TOU Rates. We are not able to calculate an accurate number for how many customers have access.			
Time of Use Rate with Critical Peak Pricing	N/A	N/A			

Page 13 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 1, 2014		
		Period	Start: Jan 1, 2014	End: Mar 31, 2014	Submission Due Date: April 30, 2014
Rate Plan Descriptions					
	Project	System			
Time of Use Rate with Peak Time Rebate	N/A	N/A			
Real-Time Rate	N/A	KCP&L has multiple existing RTP rates for commercial and industrial customers. We are not able to calculate an accurate number for how many customers have access.			
Real-time Rate with Critical Peak Pricing	N/A	N/A			
Real-time Rate with Peak Time Rebate	N/A	N/A			
Variable Peak Pricing	N/A	N/A			
Pre-paid Rate	N/A	N/A			

Page 14 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 1, 2014		
		Period	Start: Jan 1, 2014	End: Mar 31, 2014	Submission Due Date: April 30, 2014

Rate Plan Descriptions		
	Project	System
Net Metering Rate	N/A	KCP&L has multiple existing residential and C&I Net Metering Rates. We are not able to calculate an accurate number for how many customers have access.
Other program	N/A	N/A
Other program	N/A	N/A
Other program	N/A	N/A
Additional Project Descriptions	N/A	

Page 15 of 24 Custom Created: October 4, 2011 Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 1, 2014		
		Period	Start: Jan 1, 2014	End: Mar 31, 2014	Submission Due Date: April 30, 2014

Distributed Energy Resources - Build Metrics			
<i>All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.</i>			
Distributed Energy Resources	Units	Project	System
Distributed generation: number of units	#	9	1,464
Distributed generation: installed capacity	KW	176.44	26,257.32
Distributed generation: total energy delivered	* kWh	29,486	
Energy storage: number of units	#	1	1
Energy storage: installed capacity	KW	1,000	1,000
Energy storage: total energy delivered	* kWh	39,394	39,394
Plug-in electric vehicles charging points: number of units	#	19	47
Plug-in electric vehicles charging points: installed capacity	KW	133	299
Plug-in electric vehicles charging points: total energy delivered	* kWh	1,943	7,073
DER/DG interconnection equipment: number of units	#		

* Energy delivered should be reported just for the quarter being reported, not cumulative for the project to-date.

Distributed Energy Resource Descriptions		
	Project	System
Distributed Generation Interface Description	All DG installed is non-dispatchable utility-owned PV that is being metered separately. All project EV chargers are installed behind customer meters. Most interfaces currently limited to measuring data. EV chargers may be remotely deactivated to curtail load.	Non-dispatchable utility-owned DG and EV Chargers. All EV chargers are installed behind customer meters. Most interfaces currently limited to measuring data. EV chargers may be remotely deactivated to curtail load.

Page 16 of 24 Custom Created: October 4, 2011 Meter Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 1, 2014	
Period	Start: Jan 1, 2014	End: Mar 31, 2014	Submission Due Date: April 30, 2014

Additional Project Descriptions:

Distributed Energy Resources' Installed Costs	Units	Project Funded	Cost Share
DER Interface Control Systems	\$	2,584,927	2,183,009
Communications Equipment	\$		
DER/DG Interconnection Equipment	\$		
Renewable DER	\$	653,967	541,403
Distributed Generation Equipment	\$		
Stationary Electric Storage Equipment	\$	4,017,121	3,708,112
PEVs and Charging Stations	\$	71,089	60,207
Other Costs	\$		
Other Cost Description	N/A		

Page 17 of 24 Custom Created: October 4, 2011



Master Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 1, 2014	
Period	Start: Jan 1, 2014	End: Mar 31, 2014	Submission Due Date: April 30, 2014

Electric Distribution System Assets - Build Metrics

All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.

Implemented Distribution Devices	Units	Project	System
Portion of system with SCADA	%	100	10.5
Portion of system with Distribution Automation (DA)	%	100	85
Automated Feeder Switches: number of devices installed	#	20	117
Automated Capacitors: number of devices installed	#	29	2,342
Automated Regulators: number of devices installed	#		
Feeder Monitors: number of devices installed	#		
Remote Fault Indicators: number of devices installed	#	96	325
Transformer Monitors (line): number of devices installed	#		
Smart Relays: number of devices installed	#	63	2,277
Fault Current Limiter: number of devices installed	#		
Other devices installed	#		
Other devices installed	#		
Other devices installed	#		

DA Applications in Operation	Units	Project	System
Fault Location, Isolation, and Service Restoration (FLISR): is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Voltage Optimization: is this application in operation?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Feeder Peak Load Management: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Microgrids: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other DA Application: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>

Page 16 of 24 Custom Created: October 4, 2011



Master Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 1, 2014	
Period	Start: Jan 1, 2014	End: Mar 31, 2014	Submission Due Date: April 30, 2014

Distribution Management System Integration

	Units	Project	System
AMI: is integration complete?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Outage Management System: is integration complete?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Transmission Management System: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Distributed Energy Resources: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other Systems: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>

Distribution Device Description

	Project	System
SCADA	Distribution SCADA in conjunction with project DMS/CMS, includes a Tropos wireless network to reach devices outside the substation.	ABB Network Manager (EMS) across system plus project Distribution SCADA.
Portion of system with SCADA	Distribution SCADA has been deployed to all field devices in the project area.	The ABB Network Manager (EMS) communicates with 70% of feeder breakers, but only 15% of those have communications capable of supporting Smart Grid functionality.
Portion of system with DA	DA capabilities are installed on all project circuits.	KCP&L has locally automated devices such as capacitors, voltage monitors, faulted circuit indicators, and reclosers across the distribution system. 80% represents an estimate of coverage based on number of circuits with one or more of these devices.
DA devices	There is a mix of communicating and automated capacitors, faulted circuit indicators, and reclosers across the project area.	There is a mix of locally automated capacitors, voltage monitors, faulted circuit indicators, and reclosers across distribution system.

Page 19 of 24 Custom Created: October 4, 2011



Master Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 1, 2014	
Period	Start: Jan 1, 2014	End: Mar 31, 2014	Submission Due Date: April 30, 2014

Distribution Device Description

	Project	System
DA communications network	Tropos GridCom wireless IP mesh network	Lands+Gyr AMR system and Telemetric/Sensus cellular-based system.
Other device	N/A	N/A
Other device	N/A	N/A
Other device	N/A	N/A

Distribution Application Descriptions

	Project	System
FLISR	As part of the project, the DMS enables FLISR across project circuits. This will reduce outages and outage response time, and improve overall system performance.	As part of the project, the DMS enables FLISR across project circuits. This will reduce outages and outage response time, and improve overall system performance.

Page 20 of 24 Custom Created: October 4, 2011



Master Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 1, 2014		
		Period	Start: Jan 1, 2014	End: Mar 31, 2014	Submission Due Date: April 30, 2014
Voltage Optimization	As part of the project, the DMS enables voltage optimization across project circuits. This will improve power factor as well as enable voltage conservation.		A Dynamic Voltage Control (DVC) system exists on 203 buses within metropolitan Kansas City. This system is able to dynamically reduce voltage through load tap changers to achieve voltage changes in coordination with locally controlled cap banks.		
Feeder Peak Load Management	As part of the project, the DMS enables dynamic feeder load transfer across project circuits. This will reduce outages on project feeders, reduce stress on critical assets, and improve maintenance.		System peak loads are curtailed through utilization of the DVC system and existing PCT program operated by Honeywell.		
Microgrids	N/A		N/A		
Other DA Applications	N/A		N/A		
Distribution Management Integration Descriptions					
	Project		System		
AMI	DMS is integrated with project AMI.		DMS is integrated with project AMI.		
Outage Management	DMS is integrated with project OMS.		DMS is integrated with project OMS.		

Page 21 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 1, 2014		
		Period	Start: Jan 1, 2014	End: Mar 31, 2014	Submission Due Date: April 30, 2014
Distribution Management Integration Descriptions					
	Project		System		
Transmission Management	N/A		N/A		
DER Systems	DMS is integrated with project DERM.		DMS is integrated with project DERM.		
Distribution Management System	DMS consisting of D-SCADA and DNA provided by Siemens and OMS and user interface provided by Intergraph.		DMS consisting of D-SCADA and DNA provided by Siemens and OMS and user interface provided by Intergraph.		
Other Systems	N/A		N/A		
Additional Project Descriptions	N/A				
Distribution Systems Installed Costs			Units	Project Funded	Cost Share
Back Office Systems		\$	371,604	343,106	
Distribution Management System		\$	4,338,858	3,436,891	
Communications Equipment and SCADA		\$	959,422	885,621	

Page 22 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 1, 2014	
Period	Start: Jan 1, 2014	End: Mar 31, 2014	Submission Due Date: April 30, 2014

Distribution Systems Installed Costs	Units	Project Funded	Cost Share
Feeder Monitor/Indicator	\$	25,917	23,876
Substation Monitors	\$	1,239,319	1,141,848
Automated Feeder Switches	\$	688,212	632,255
Capacitor Automation Equipment	\$	72,436	66,740
Regulator Automation Equipment	\$		
Fault Current Limiter Equipment	\$		
Cost of other devices installed	\$		
Cost of other devices installed	\$		
Cost of other devices installed	\$		
Other Costs	\$	372,099	339,816
Other Cost Description	KCP&L labor charges across various device types.		

Page 23 of 24 Custom Created: October 4, 2011



Metric Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 1, 2014	
Period	Start: Jan 1, 2014	End: Mar 31, 2014	Submission Due Date: April 30, 2014

Submit
Print Form

Page 24 of 24 Custom Created: October 4, 2011



Metric Updated: April 8, 2011 Schema Version: 1.2

S.17 2014 Q2

SMARTGRID.GOV		Project	DE-OE000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 2, 2014		
		Period	Start: Apr 1, 2014	End: Jun 30, 2014	Submission Due Date: July 31, 2014
AMI Assets - Build Metrics					
<i>All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.</i>					
AMI End Points Installed		Units	Project	System	
End Points (meters) installed and operational	#		13,358	82,442	
Portion of customers with AMI residential	#		12,119	73,372	
Portion of customers with AMI commercial	#		1,239	8,870	
Portion of customers with AMI industrial	#		0	200	
Implemented Meter Features		Units	Project	System	
Reading interval for residential meters	minutes		15	15	
Reading interval for commercial meters	minutes		15	15	
Reading interval for industrial meters	minutes			15	
Remote Connect/Disconnect: is feature implemented?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Remote Connect/Disconnect: number of meters with feature implemented	#		12,551	17,336	
Outage Reporting: is feature implemented?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Outage Reporting: number of meters with feature implemented	#		13,358	82,442	
Power Quality Measurement: is feature implemented?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Power Quality Measurement: number of meters with feature implemented	#				
Tamper Detection: is feature implemented?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Tamper Detection: number of meters with feature implemented	#		13,358	82,442	
Other feature implemented	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other feature: number of meters with feature implemented	#				
Other feature implemented	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other feature: number of meters with feature implemented	#				
Other feature implemented	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other feature: number of meters with feature implemented	#				

Page 1 of 24 Custom Created: October 8, 2011 Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 2, 2014		
		Period	Start: Apr 1, 2014	End: Jun 30, 2014	Submission Due Date: July 31, 2014
Implemented Meter Features		Units	Project	System	
Other feature: number of meters with feature implemented	#				
Implemented Enterprise Integration		Units	Project	System	
Billing System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Customer Information System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Outage Management System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Distribution Management System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Other Enterprise Systems: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
AMI System Descriptions					
	Project	System			
Backhaul Network	Hybrid of Fiber and Wireless Raven radio with network carrier	Hybrid of Fiber and Wireless Raven radio with network carrier			
Meter Communication Network	Lands+Gyr Gridstream RF 900MHz - Collectors and Routers	Lands+Gyr Gridstream RF 900MHz - Collectors and Routers			
Headend System	Lands+Gyr Command Center	Lands+Gyr Command Center			
Meter Data Management System	eMeter/Siemens	eMeter/Siemens			

Page 2 of 24 Custom Created: October 8, 2011 Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 2, 2014	
		Period	Start: Apr 1, 2014	End: Jun 30, 2014 Submission Due Date: July 31, 2014
AMI System Descriptions				
	Project	System		
Meter Data Analysis	The project AMI was incorporated into the existing AMR – MDA interfaces. AMI daily register reads and 15-min interval reads are loaded into MDA (DataRaker) on a daily basis.	The project AMI was incorporated into the existing AMR – MDA interfaces. AMI daily register reads and 15-min interval reads are loaded into MDA (DataRaker) on a daily basis.		
Other Meter Feature	N/A	N/A		
Other Meter Feature	N/A	N/A		
Other Meter Feature	N/A	N/A		
AMI Enterprise Integration Descriptions				
	Project	System		
Billing System	AMI is integrated with enterprise Oracle CIS.	AMI is integrated with enterprise Oracle CIS.		

Page 3 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 2, 2014		
		Period	Start: Apr 1, 2014	End: Jun 30, 2014 Submission Due Date: July 31, 2014	
AMI Enterprise Integration Descriptions					
	Project	System			
Customer Information System	AMI is integrated with KCP&L enterprise Oracle CIS. The project AMI was incorporated into the existing AMR – CIS interfaces. CIS daily account/meter synchronization. AMI provides CIS daily register meter reads for direct billing. CIS daily billing cycle-to-date usage info and bill prediction pushed to IHDs via AMI Network.	AMI is integrated with KCP&L enterprise Oracle CIS. The project AMI was incorporated into the existing AMR – CIS interfaces. CIS daily account/meter synchronization. AMI provides CIS daily register meter reads for direct billing. CIS daily billing cycle-to-date usage info and bill prediction pushed to IHDs via AMI Network.			
Outage Management System	AMI is integrated with enterprise OMS. An additional project OMS (redundant) will also be implemented in conjunction with a DMS. The project AMI was incorporated into the existing AMR to enterprise OMS interfaces including meter outage alerts and meter "ping" functionality to verify power restoration.	AMI is integrated with enterprise OMS. An additional project OMS (redundant) will also be implemented in conjunction with a DMS. The project AMI was incorporated into the existing AMR to enterprise OMS interfaces including meter outage alerts and meter "ping" functionality to verify power restoration.			
Distribution Management System	DMS is integrated with multiple project and legacy systems including AMI, DERM, OMS, and energy storage.	DMS is integrated with multiple project and legacy systems including AMI, DERM, OMS, and energy storage.			
Other Enterprise Systems	Data Mining and Analysis Tool (DataRaker) covered by the MDA	Data Mining and Analysis Tool (DataRaker) covered by the MDA			
Additional Project Descriptions	N/A				
AMI Installed Costs			Units	Project Funded	Cost Share
Back Office Systems		\$	2,337,739	2,157,913	
Communications Equipment		\$	119,308	110,130	
AMI Smart Meters		\$	2,249,422	2,076,390	

Page 4 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 2, 2014	
Period	Start: Apr 1, 2014	End: Jun 30, 2014	Submission Due Date: July 31, 2014

AMI Installed Costs	Units	Project Funded	Cost Share
Other Costs	5		
Other Costs Description	N/A		

Page 5 of 24 Custom Created: October 4, 2011



Metric Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 2, 2014	
Period	Start: Apr 1, 2014	End: Jun 30, 2014	Submission Due Date: July 31, 2014

Customer Systems Assets - Build Metrics

All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.

Implemented Customer Systems	Units	Project	System
In-Home display: devices installed	#	618	618
Direct Load Control Devices: devices installed	#	132	132
Programmable Communicating Thermostats: devices installed	#	112	53,824
Smart Appliances: devices installed	#		
Energy Management Devices/Systems: devices installed	#		
Other Devices installed	#	61	61
Other Devices installed	#		
Other Devices installed	#		

Web Portal	Units	Project	System
Web portal is portal in production?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Customers with access	#	12,036	12,036
Customers with active accounts	#	2,109	2,109

Customer System Descriptions	Project	System
In-Home Displays	Tendril InSight	Tendril InSight

Page 6 of 24 Custom Created: October 4, 2011



Metric Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 2, 2014		
		Period	Start: Apr 1, 2014	End: Jun 30, 2014	Submission Due Date: July 31, 2014
Customer System Descriptions					
	Project	System			
Direct Load Control Devices	Tendril Volt	Tendril Volt			
Programmable Communicating Thermostats	Tendril Setpoint	Tendril Setpoint and Honeywell PCTs			
Smart Appliances	N/A	N/A			
Energy Mgmt. Systems	N/A	N/A			
Web Portal	Tendril Energize Web Portal	Tendril Energize Web Portal			
Home Area Network	Zigbee SEP 1.0	Zigbee SEP 1.0			

Page 7 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 2, 2014		
		Period	Start: Apr 1, 2014	End: Jun 30, 2014	Submission Due Date: July 31, 2014
Customer System Descriptions					
	Project	System			
Other Device	Tendril Transport Gateway	Tendril Transport Gateway			
HAN Gateway					
Other Device	N/A	N/A			
Other Device	N/A	N/A			
Additional Project Descriptions	N/A				

Customer System Installed Costs	Units	Project Funded	Cost Share
Back Office Systems	\$	441,207	406,255
Web Portals	\$	940,730	868,293
In-Home Displays	\$	155,669	143,694
Direct Load Control Devices	\$	90,344	83,395
Smart Appliances	\$	0	0
Programmable Communicating Thermostats	\$	378,220	335,076
Cost of other devices installed: HAN Gateway	\$	228,218	204,454

Page 8 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 2, 2014	
Period	Start: Apr 1, 2014	End: Jun 30, 2014	Submission Due Date: July 31, 2014

Customer System Installed Costs	Units	Project Funded	Cost Share
Cost of other devices installed	\$		
Cost of other devices installed	\$		
Other Costs	\$	389,796	357,473
Other Cost Description	Program delivery costs including KCP&L labor for program administration, analysis, and customer engagement as well as vendor travel expenses.		

Page 9 of 24 Custom Created: October 4, 2011

Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 2, 2014	
Period	Start: Apr 1, 2014	End: Jun 30, 2014	Submission Due Date: July 31, 2014

Pricing Programs - Build Metrics

All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.

Implemented Rate Plans	Units	Project	System
Flat Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Flat Rate: number of customers with access	#		
Flat Rate: number of customers enrolled	#		546,795
Flat Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Critical Peak Pricing: number of customers with access	#		
Flat Rate with Critical Peak Pricing: number of customers enrolled	#		
Flat Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Peak Time Rebate: number of customers with access	#		
Flat Rate with Peak Time Rebate: number of customers enrolled	#		
Tiered Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Tiered Rate: number of customers with access	#		
Tiered Rate: number of customers enrolled	#		303,048
Tiered Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Critical Peak Pricing: number of customers with access	#		
Tiered Rate with Critical Peak Pricing: number of customers enrolled	#		
Tiered Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Peak Time Rebate: number of customers with access	#		
Tiered Rate with Peak Time Rebate: number of customers enrolled	#		
Time of Use Rate: is the pricing program available?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Time of Use Rate: number of customers with access	#	12,119	

Page 10 of 24 Custom Created: October 4, 2011

Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 2, 2014	
Period	Start: Apr 1, 2014	End: Jun 30, 2014	Submission Due Date: July 31, 2014

Implemented Rate Plans	Units	Project	System
Time of Use Rate: number of customers enrolled	#	113	548
Time of Use Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Time of Use Rate with Critical Peak Pricing: number of customers with access	#		
Time of Use Rate with Critical Peak Pricing: number of customers enrolled	#		
Time of Use Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Time of Use Rate with Peak Time Rebate: number of customers with access	#		
Time of Use Rate with Peak Time Rebate: number of customers enrolled	#		
Real-time Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Real-time Pricing: number of customers with access	#		
Real-time Pricing: number of customers enrolled	#		9
Real-time Pricing with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Real-time Pricing with Critical Peak Pricing: number of customers with access	#		
Real-time Pricing with Critical Peak Pricing: number of customers enrolled	#		
Real-time Pricing with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Real-time Pricing with Peak Time Rebate: number of customers with access	#		
Real-time Pricing with Peak Time Rebate: number of customers enrolled	#		
Variable Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Variable Peak Pricing: number of customers with access	#		
Variable Peak Pricing: number of customers enrolled	#		
Pre-pay Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Pre-pay Pricing: number of customers with access	#		
Pre-pay Pricing: number of customers enrolled	#		
Net Metering: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>

Page 11 of 24 Custom Created: October 4, 2011

Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 2, 2014	
Period	Start: Apr 1, 2014	End: Jun 30, 2014	Submission Due Date: July 31, 2014

Implemented Rate Plans	Units	Project	System
Net Metering: number of customers with access	#		
Net Metering: number of customers enrolled	#		1,913
Other program available	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: number of customers with access	#		
Other programs: number of customers enrolled	#		
Other program available	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: number of customers with access	#		
Other programs: number of customers enrolled	#		
Other program available	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other programs: number of customers with access	#		
Other programs: number of customers enrolled	#		
Rate Decoupling: is implemented?	yes/ no	<input type="checkbox"/>	

Rate Plan Descriptions	Project	System
Flat Rate	N/A	KCP&L has multiple residential and C&I Flat Rates that occur during both summer and winter. We are not able to calculate an accurate number for how many customers have access.
Flat Rate with Critical Peak Pricing	N/A	N/A

Page 12 of 24 Custom Created: October 4, 2011

Metric Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 2, 2014		
		Period	Start: Apr 1, 2014	End: Jun 30, 2014	Submission Due Date: July 31, 2014
Rate Plan Descriptions					
	Project	System			
Flat Rate with Peak Time Rebate	N/A	N/A			
Tiered Rate	N/A	KCP&L has multiple existing residential and C&I Tiered Rates. A majority of those are declining block rates. We are not able to calculate an accurate number for how many customers have access.			
Tiered Rate with Critical Peak Pricing	N/A	N/A			
Tiered Rate with Peak Time Rebate	N/A	N/A			
Time of Use Rate	A new residential TOU rate is being piloted as part of this project to augment the evaluation of customer information systems and control devices.	KCP&L has multiple existing residential and C&I TOU Rates. We are not able to calculate an accurate number for how many customers have access.			
Time of Use Rate with Critical Peak Pricing	N/A	N/A			

Page 13 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 2, 2014		
		Period	Start: Apr 1, 2014	End: Jun 30, 2014	Submission Due Date: July 31, 2014
Rate Plan Descriptions					
	Project	System			
Time of Use Rate with Peak Time Rebate	N/A	N/A			
Real-Time Rate	N/A	KCP&L has multiple existing RTP rates for commercial and industrial customers. We are not able to calculate an accurate number for how many customers have access.			
Real-time Rate with Critical Peak Pricing	N/A	N/A			
Real-time Rate with Peak Time Rebate	N/A	N/A			
Variable Peak Pricing	N/A	N/A			
Pre-paid Rate	N/A	N/A			

Page 14 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 2, 2014		
		Period	Start: Apr 1, 2014	End: Jun 30, 2014	Submission Due Date: July 31, 2014

Rate Plan Descriptions		
	Project	System
Net Metering Rate	N/A	KCP&L has multiple existing residential and C&I Net Metering Rates. We are not able to calculate an accurate number for how many customers have access.
Other program	N/A	N/A
Other program	N/A	N/A
Other program	N/A	N/A
Additional Project Descriptions	N/A	

Page 15 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 2, 2014		
		Period	Start: Apr 1, 2014	End: Jun 30, 2014	Submission Due Date: July 31, 2014

Distributed Energy Resources - Build Metrics			
<i>All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.</i>			
Distributed Energy Resources	Units	Project	System
Distributed generation: number of units	#	9	1,862
Distributed generation: installed capacity	KW	176.44	37,154
Distributed generation: total energy delivered	* kWh	41,405	
Energy storage: number of units	#	1	1
Energy storage: installed capacity	KW	1,000	1,000
Energy storage: total energy delivered	* kWh	49,754	49,754
Plug-in electric vehicles charging points: number of units	#	19	47
Plug-in electric vehicles charging points: installed capacity	KW	133	299
Plug-in electric vehicles charging points: total energy delivered	* kWh	1,848	7,454
DER/DG interconnection equipment: number of units	#		

* Energy delivered should be reported just for the quarter being reported, not cumulative for the project to-date.

Distributed Energy Resource Descriptions		
	Project	System
Distributed Generation Interface Description	All DG installed is non-dispatchable utility-owned PV that is being metered separately. All project EV chargers are installed behind customer meters. Most interfaces currently limited to measuring data. EV chargers may be remotely deactivated to curtail load.	Non-dispatchable utility-owned DG and EV Chargers. All EV chargers are installed behind customer meters. Most interfaces currently limited to measuring data. EV chargers may be remotely deactivated to curtail load.

Page 16 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 2, 2014	
Period	Start: Apr 1, 2014	End: Jun 30, 2014	Submission Due Date: July 31, 2014

Additional Project Descriptions

Distributed Energy Resources' Installed Costs	Units	Project Funded	Cost Share
DER Interface Control Systems	\$	2,585,382	2,183,009
Communications Equipment	\$	0	0
DER/DG Interconnection Equipment	\$	0	0
Renewable DER	\$	654,039	541,403
Distributed Generation Equipment	\$	0	0
Stationary Electric Storage Equipment	\$	4,017,121	3,708,112
PEVs and Charging Stations	\$	71,089	60,207
Other Costs	\$		

Other Cost Description

N/A

Page 17 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 2, 2014	
Period	Start: Apr 1, 2014	End: Jun 30, 2014	Submission Due Date: July 31, 2014

Electric Distribution System Assets - Build Metrics

All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.

Implemented Distribution Devices	Units	Project	System
Portion of system with SCADA	%	100	10.5
Portion of system with Distribution Automation (DA)	%	100	85
Automated Feeder Switches: number of devices installed	#	20	117
Automated Capacitors: number of devices installed	#	29	2,342
Automated Regulators: number of devices installed	#	0	3
Feeder Monitors: number of devices installed	#	0	0
Remote Fault Indicators: number of devices installed	#	96	325
Transformer Monitors (line): number of devices installed	#	0	0
Smart Relays: number of devices installed	#	63	2,277
Fault Current Limiter: number of devices installed	#	0	0
Other devices installed	#		
Other devices installed	#		
Other devices installed	#		

DA Applications in Operation	Units	Project	System
Fault Location, Isolation, and Service Restoration (FLISR): is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Voltage Optimization: is this application in operation?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Feeder Peak Load Management: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Microgrids: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other DA Application: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>

Page 16 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 2, 2014	
Period	Start: Apr 1, 2014	End: Jun 30, 2014	Submission Due Date: July 31, 2014

Distribution Management System Integration

	Units	Project	System
AMI: is integration complete?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Outage Management System: is integration complete?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Transmission Management System: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Distributed Energy Resources: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other Systems: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>

Distribution Device Description

	Project	System
SCADA	Distribution SCADA in conjunction with project DMS/CMS, includes a Tropos wireless network to reach devices outside the substation.	ABB Network Manager (EMS) across system plus project Distribution SCADA.
Portion of system with SCADA	Distribution SCADA has been deployed to all field devices in the project area.	The ABB Network Manager (EMS) communicates with 70% of feeder breakers, but only 15% of those have communications capable of supporting Smart Grid functionality.
Portion of system with DA	DA capabilities are installed on all project circuits.	KCP&L has locally automated devices such as capacitors, voltage monitors, faulted circuit indicators, and reclosers across the distribution system. 80% represents an estimate of coverage based on number of circuits with one or more of these devices.
DA devices	There is a mix of communicating and automated capacitors, faulted circuit indicators, and reclosers across the project area.	There is a mix of locally automated capacitors, voltage monitors, faulted circuit indicators, and reclosers across distribution system.

Page 19 of 24 Custom Created: October 4, 2011



Master Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 2, 2014	
Period	Start: Apr 1, 2014	End: Jun 30, 2014	Submission Due Date: July 31, 2014

Distribution Device Description

	Project	System
DA communications network	Tropos GridCom wireless IP mesh network	Lands+Gyr AMR system and Telemetric/Sensus cellular-based system.
Other device	N/A	N/A
Other device	N/A	N/A
Other device	N/A	N/A

Distribution Application Descriptions

	Project	System
FLISR	As part of the project, the DMS enables FLISR across project circuits. This will reduce outages and outage response time, and improve overall system performance.	As part of the project, the DMS enables FLISR across project circuits. This will reduce outages and outage response time, and improve overall system performance.

Page 20 of 24 Custom Created: October 4, 2011



Master Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 2, 2014		
		Period	Start: Apr 1, 2014	End: Jun 30, 2014	Submission Due Date: July 31, 2014
Voltage Optimization	As part of the project, the DMS enables voltage optimization across project circuits. This will improve power factor as well as enable voltage conservation.		A Dynamic Voltage Control (DVC) system exists on 203 buses within metropolitan Kansas City. This system is able to dynamically reduce voltage through load tap changers to achieve voltage changes in coordination with locally controlled cap banks.		
Feeder Peak Load Management	As part of the project, the DMS enables dynamic feeder load transfer across project circuits. This will reduce outages on project feeders, reduce stress on critical assets, and improve maintenance.		System peak loads are curtailed through utilization of the DVC system and existing PCT program operated by Honeywell.		
Microgrids	N/A		N/A		
Other DA Applications	N/A		N/A		
Distribution Management Integration Descriptions					
	Project	System			
AMI	DMS is integrated with project AMI.	DMS is integrated with project AMI.			
Outage Management	DMS is integrated with project OMS.	DMS is integrated with project OMS.			

Page 21 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 2, 2014		
		Period	Start: Apr 1, 2014	End: Jun 30, 2014	Submission Due Date: July 31, 2014
Distribution Management Integration Descriptions					
	Project	System			
Transmission Management	N/A	N/A			
DER Systems	DMS is integrated with project DERM.	DMS is integrated with project DERM.			
Distribution Management System	DMS consisting of D-SCADA and DNA provided by Siemens and OMS and user interface provided by Intergraph.	DMS consisting of D-SCADA and DNA provided by Siemens and OMS and user interface provided by Intergraph.			
Other Systems	N/A	N/A			
Additional Project Descriptions	N/A				
Distribution Systems Installed Costs			Units	Project Funded	Cost Share
Back Office Systems			\$	372,159	343,106
Distribution Management System			\$	4,338,858	3,436,891
Communications Equipment and SCADA			\$	959,422	885,621

Page 22 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 2, 2014	
Period	Start: Apr 1, 2014	End: Jun 30, 2014	Submission Due Date: July 31, 2014

Distribution Systems Installed Costs	Units	Project Funded	Cost Share
Feeder Monitor/Indicator	\$	25,930	23,876
Substation Monitors	\$	1,244,368	1,141,648
Automated Feeder Switches	\$	688,646	632,255
Capacitor Automation Equipment	\$	72,481	66,740
Regulator Automation Equipment	\$	0	0
Fault Current Limiter Equipment	\$	0	0
Cost of other devices installed	\$		
Cost of other devices installed	\$		
Cost of other devices installed	\$		
Other Costs	\$	375,251	339,616

Other Cost Description: KCP&L labor charges across various device types.

Page 23 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 2, 2014	
Period	Start: Apr 1, 2014	End: Jun 30, 2014	Submission Due Date: July 31, 2014

Submit
Print Form

Page 24 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2

S.18 2014 Q3

SMARTGRID.GOV		Project	DE-OE000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2014	
		Period	Start: Jul 1, 2014	End: Sep 30, 2014 Submission Due Date: October 31, 2014
AMI Assets - Build Metrics				
<i>All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.</i>				
AMI End Points Installed		Units	Project	System
End Points (meters) installed and operational	#		13,427	150,073
Portion of customers with AMI residential	#		12,204	132,584
Portion of customers with AMI commercial	#		1,223	17,113
Portion of customers with AMI industrial	#		0	376
Implemented Meter Features		Units	Project	System
Reading interval for residential meters	minutes		15	15
Reading interval for commercial meters	minutes		15	15
Reading interval for industrial meters	minutes			15
Remote Connect/Disconnect: is feature implemented?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Remote Connect/Disconnect: number of meters with feature implemented	#		13,014	23,052
Outage Reporting: is feature implemented?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Outage Reporting: number of meters with feature implemented	#		13,427	150,073
Power Quality Measurement: is feature implemented?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>
Power Quality Measurement: number of meters with feature implemented	#			
Tamper Detection: is feature implemented?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Tamper Detection: number of meters with feature implemented	#		13,427	150,073
Other feature implemented	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>
Other feature: number of meters with feature implemented	#			
Other feature implemented	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>
Other feature: number of meters with feature implemented	#			
Other feature implemented	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>

Page 1 of 24 Custom Created: October 8, 2011 Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2014	
		Period	Start: Jul 1, 2014	End: Sep 30, 2014 Submission Due Date: October 31, 2014
Implemented Meter Features		Units	Project	System
Other feature: number of meters with feature implemented	#			
Implemented Enterprise Integration		Units	Project	System
Billing System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Customer Information System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Outage Management System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Distribution Management System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Other Enterprise Systems: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
AMI System Descriptions				
	Project	System		
Backhaul Network	Hybrid of Fiber and Wireless Raven radio with network carrier	Hybrid of Fiber and Wireless Raven radio with network carrier		
Meter Communication Network	Lands+Gyr Gridstream RF 900MHz - Collectors and Routers	Lands+Gyr Gridstream RF 900MHz - Collectors and Routers		
Headend System	Lands+Gyr Command Center	Lands+Gyr Command Center		
Meter Data Management System	eMeter/Siemens	eMeter/Siemens		

Page 2 of 24 Custom Created: October 8, 2011 Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2014		
		Period	Start: Jul 1, 2014	End: Sep 30, 2014	Submission Due Date: October 31, 2014
AMI System Descriptions					
	Project	System			
Meter Data Analysis	The project AMI was incorporated into the existing AMR – MDA interfaces. AMI daily register reads and 15-min interval reads are loaded into MDA (DataRaker) on a daily basis.	The project AMI was incorporated into the existing AMR – MDA interfaces. AMI daily register reads and 15-min interval reads are loaded into MDA (DataRaker) on a daily basis.			
Other Meter Feature	N/A	N/A			
Other Meter Feature	N/A	N/A			
Other Meter Feature	N/A	N/A			
AMI Enterprise Integration Descriptions					
	Project	System			
Billing System	AMI is integrated with enterprise Oracle CIS.	AMI is integrated with enterprise Oracle CIS.			

Page 3 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2014		
		Period	Start: Jul 1, 2014	End: Sep 30, 2014	Submission Due Date: October 31, 2014
AMI Enterprise Integration Descriptions					
	Project	System			
Customer Information System	AMI is integrated with KCP&L enterprise Oracle CIS. The project AMI was incorporated into the existing AMR – CIS interfaces. CIS daily account/meter synchronization. AMI provides CIS daily register meter reads for direct billing. CIS daily billing cycle-to-date usage info and bill prediction pushed to IHDs via AMI Network.	AMI is integrated with KCP&L enterprise Oracle CIS. The project AMI was incorporated into the existing AMR – CIS interfaces. CIS daily account/meter synchronization. AMI provides CIS daily register meter reads for direct billing. CIS daily billing cycle-to-date usage info and bill prediction pushed to IHDs via AMI Network.			
Outage Management System	AMI is integrated with enterprise OMS. An additional project OMS (redundant) will also be implemented in conjunction with a DMS. The project AMI was incorporated into the existing AMR to enterprise OMS interfaces including meter outage alerts and meter "ping" functionality to verify power restoration.	AMI is integrated with enterprise OMS. An additional project OMS (redundant) will also be implemented in conjunction with a DMS. The project AMI was incorporated into the existing AMR to enterprise OMS interfaces including meter outage alerts and meter "ping" functionality to verify power restoration.			
Distribution Management System	DMS is integrated with multiple project and legacy systems including AMI, DERM, OMS, and energy storage.	DMS is integrated with multiple project and legacy systems including AMI, DERM, OMS, and energy storage.			
Other Enterprise Systems	Data Mining and Analysis Tool (DataRaker) covered by the MDA	Data Mining and Analysis Tool (DataRaker) covered by the MDA			
Additional Project Descriptions	N/A				
AMI Installed Costs					
	Units	Project Funded	Cost Share		
Back Office Systems	\$	2,337,739	2,157,913		
Communications Equipment	\$	119,308	110,130		
AMI Smart Meters	\$	2,252,704	2,076,390		

Page 4 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2014	
Period	Start: Jul 1, 2014	End: Sep 30, 2014	Submission Due Date: October 31, 2014

AMI Installed Costs	Units	Project Funded	Cost Share
Other Costs	5		
Other Costs Description	N/A		

Page 5 of 24 Custom Created: October 4, 2011



Metric Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2014	
Period	Start: Jul 1, 2014	End: Sep 30, 2014	Submission Due Date: October 31, 2014

Customer Systems Assets - Build Metrics			
All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.			
Implemented Customer Systems	Units	Project	System
In-Home display: devices installed	#	616	616
Direct Load Control Devices: devices installed	#	131	131
Programmable Communicating Thermostats: devices installed	#	112	53,824
Smart Appliances: devices installed	#		
Energy Management Devices/Systems: devices installed	#		
Other Devices installed	#	61	61
Other Devices installed	#		
Other Devices installed	#		
Web Portal	Units	Project	System
Web portal is portal in production?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Customers with access	#	12,036	12,036
Customers with active accounts	#	2,109	2,109
Customer System Descriptions			
	Project	System	
In-Home Displays	Tendril InSight	Tendril InSight	

Page 6 of 24 Custom Created: October 4, 2011



Metric Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2014	
		Period	Start: Jul 1, 2014	End: Sep 30, 2014 Submission Due Date: October 31, 2014

Customer System Descriptions		
	Project	System
Direct Load Control Devices	Tendril Volt	Tendril Volt
Programmable Communicating Thermostats	Tendril Setpoint	Tendril Setpoint and Honeywell PCTs
Smart Appliances	N/A	N/A
Energy Mgmt. Systems	N/A	N/A
Web Portal	Tendril Energize Web Portal	Tendril Energize Web Portal
Home Area Network	Zigbee SEP 1.0	Zigbee SEP 1.0

Page 7 of 24 Custom Created: October 4, 2011 Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2014	
		Period	Start: Jul 1, 2014	End: Sep 30, 2014 Submission Due Date: October 31, 2014

Customer System Descriptions		
	Project	System
Other Device	Tendril Transport Gateway	Tendril Transport Gateway
HAN Gateway		
Other Device	N/A	N/A
Other Device	N/A	N/A
Additional Project Descriptions	N/A	

Customer System Installed Costs			
	Units	Project Funded	Cost Share
Back Office Systems	\$	441,625	406,255
Web Portals	\$	940,730	868,293
In-Home Displays	\$	155,669	143,694
Direct Load Control Devices	\$	90,344	83,395
Smart Appliances	\$	0	0
Programmable Communicating Thermostats	\$	378,345	335,076
Cost of other devices installed: HAN Gateway	\$	228,510	204,454

Page 8 of 24 Custom Created: October 4, 2011 Meter Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2014	
Period	Start: Jul 1, 2014	End: Sep 30, 2014	Submission Due Date: October 31, 2014

Customer System Installed Costs	Units	Project Funded	Cost Share
Cost of other devices installed	\$		
Cost of other devices installed	\$		
Other Costs	\$	390,761	357,473
Other Cost Description	Program delivery costs including KCP&L labor for program administration, analysis, and customer engagement as well as vendor travel expenses.		

Page 9 of 24 Custom Created: October 4, 2011

Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2014	
Period	Start: Jul 1, 2014	End: Sep 30, 2014	Submission Due Date: October 31, 2014

Pricing Programs - Build Metrics

All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.

Implemented Rate Plans	Units	Project	System
Flat Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Flat Rate: number of customers with access	#		
Flat Rate: number of customers enrolled	#		548,284
Flat Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Critical Peak Pricing: number of customers with access	#		
Flat Rate with Critical Peak Pricing: number of customers enrolled	#		
Flat Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Peak Time Rebate: number of customers with access	#		
Flat Rate with Peak Time Rebate: number of customers enrolled	#		
Tiered Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Tiered Rate: number of customers with access	#		
Tiered Rate: number of customers enrolled	#		303,257
Tiered Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Critical Peak Pricing: number of customers with access	#		
Tiered Rate with Critical Peak Pricing: number of customers enrolled	#		
Tiered Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Peak Time Rebate: number of customers with access	#		
Tiered Rate with Peak Time Rebate: number of customers enrolled	#		
Time of Use Rate: is the pricing program available?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Time of Use Rate: number of customers with access	#	12,204	

Page 10 of 24 Custom Created: October 4, 2011

Metric Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2014		
		Period	Start: Jul 1, 2014	End: Sep 30, 2014	Submission Due Date: October 31, 2014
Implemented Rate Plans		Units	Project	System	
Time of Use Rate: number of customers enrolled	#		102	536	
Time of Use Rate with Critical Peak Pricing: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Time of Use Rate with Critical Peak Pricing: number of customers with access	#				
Time of Use Rate with Critical Peak Pricing: number of customers enrolled	#				
Time of Use Rate with Peak Time Rebate: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Time of Use Rate with Peak Time Rebate: number of customers with access	#				
Time of Use Rate with Peak Time Rebate: number of customers enrolled	#				
Real-time Pricing: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Real-time Pricing: number of customers with access	#				
Real-time Pricing: number of customers enrolled	#			0	
Real-time Pricing with Critical Peak Pricing: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Real-time Pricing with Critical Peak Pricing: number of customers with access	#				
Real-time Pricing with Critical Peak Pricing: number of customers enrolled	#				
Real-time Pricing with Peak Time Rebate: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Real-time Pricing with Peak Time Rebate: number of customers with access	#				
Real-time Pricing with Peak Time Rebate: number of customers enrolled	#				
Variable Peak Pricing: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Variable Peak Pricing: number of customers with access	#				
Variable Peak Pricing: number of customers enrolled	#				
Pre-pay Pricing: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Pre-pay Pricing: number of customers with access	#				
Pre-pay Pricing: number of customers enrolled	#				
Net Metering: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input checked="" type="checkbox"/>	

Page 11 of 24 Custom Created: October 4, 2011 Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2014		
		Period	Start: Jul 1, 2014	End: Sep 30, 2014	Submission Due Date: October 31, 2014
Implemented Rate Plans		Units	Project	System	
Net Metering: number of customers with access	#				
Net Metering: number of customers enrolled	#			2,269	
Other program available	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other programs: number of customers with access	#				
Other programs: number of customers enrolled	#				
Other program available	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other programs: number of customers with access	#				
Other programs: number of customers enrolled	#				
Other program available	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other programs: number of customers with access	#				
Other programs: number of customers enrolled	#				
Rate Decoupling: is implemented?	yes/ no		<input type="checkbox"/>		
Rate Plan Descriptions					
	Project	System			
Flat Rate	N/A	KCP&L has multiple residential and C&I Flat Rates that occur during both summer and winter. We are not able to calculate an accurate number for how many customers have access.			
Flat Rate with Critical Peak Pricing	N/A	N/A			

Page 12 of 24 Custom Created: October 4, 2011 Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2014	
		Period	Start: Jul 1, 2014	End: Sep 30, 2014 Submission Due Date: October 31, 2014
Rate Plan Descriptions				
	Project	System		
Flat Rate with Peak Time Rebate	N/A	N/A		
Tiered Rate	N/A	KCP&L has multiple existing residential and CSI Tiered Rates. A majority of those are declining block rates. We are not able to calculate an accurate number for how many customers have access.		
Tiered Rate with Critical Peak Pricing	N/A	N/A		
Tiered Rate with Peak Time Rebate	N/A	N/A		
Time of Use Rate	A new residential TOU rate is being piloted as part of this project to augment the evaluation of customer information systems and control devices.	KCP&L has multiple existing residential and CSI TOU Rates. We are not able to calculate an accurate number for how many customers have access.		
Time of Use Rate with Critical Peak Pricing	N/A	N/A		

Page 13 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2014	
		Period	Start: Jul 1, 2014	End: Sep 30, 2014 Submission Due Date: October 31, 2014
Rate Plan Descriptions				
	Project	System		
Time of Use Rate with Peak Time Rebate	N/A	N/A		
Real-Time Rate	N/A	KCP&L has multiple existing RTP rates for commercial and industrial customers. We are not able to calculate an accurate number for how many customers have access.		
Real-time Rate with Critical Peak Pricing	N/A	N/A		
Real-time Rate with Peak Time Rebate	N/A	N/A		
Variable Peak Pricing	N/A	N/A		
Pre-paid Rate	N/A	N/A		

Page 14 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2014		
		Period	Start: Jul 1, 2014	End: Sep 30, 2014	Submission Due Date: October 31, 2014

Rate Plan Descriptions		
	Project	System
Net Metering Rate	N/A	KCP&L has multiple existing residential and C&I Net Metering Rates. We are not able to calculate an accurate number for how many customers have access.
Other program	N/A	N/A
Other program	N/A	N/A
Other program	N/A	N/A
Additional Project Descriptions	N/A	

Page 15 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2014		
		Period	Start: Jul 1, 2014	End: Sep 30, 2014	Submission Due Date: October 31, 2014

Distributed Energy Resources - Build Metrics			
<i>All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.</i>			
Distributed Energy Resources	Units	Project	System
Distributed generation: number of units	#	9	2,295
Distributed generation: installed capacity	KW	176.11	45,234.431
Distributed generation: total energy delivered	* kWh	57,919	
Energy storage: number of units	#	1	1
Energy storage: installed capacity	KW	1,000	1,000
Energy storage: total energy delivered	* kWh	46,110	46,110
Plug-in electric vehicles charging points: number of units	#	19	57
Plug-in electric vehicles charging points: installed capacity	KW	133	371
Plug-in electric vehicles charging points: total energy delivered	* kWh	2,261	7,705
DER/DG interconnection equipment: number of units	#		

* Energy delivered should be reported just for the quarter being reported, not cumulative for the project to-date.

Distributed Energy Resource Descriptions		
	Project	System
Distributed Generation Interface Description	All DG installed is non-dispatchable utility-owned PV that is being metered separately. All project EV chargers are installed behind customer meters. Most interfaces currently limited to measuring data. EV chargers may be remotely deactivated to curtail load.	Non-dispatchable utility-owned DG and EV Chargers. All EV chargers are installed behind customer meters. Most interfaces currently limited to measuring data. EV chargers may be remotely deactivated to curtail load.

Page 16 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2014	
Period	Start: Jul 1, 2014	End: Sep 30, 2014	Submission Due Date: October 31, 2014

Additional Project Descriptions:

Distributed Energy Resources' Installed Costs	Units	Project Funded	Cost Share
DER Interface Control Systems	\$	2,585,382	2,183,009
Communications Equipment	\$	0	0
DER/DG Interconnection Equipment	\$	0	0
Renewable DER	\$	688,165	541,403
Distributed Generation Equipment	\$	0	0
Stationary Electric Storage Equipment	\$	4,017,121	3,708,112
PEVs and Charging Stations	\$	71,089	60,207
Other Costs	\$		

Other Cost Description: N/A

Page 17 of 24 Custom Created: October 4, 2011

Metric Updated: April 8, 2011
Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2014	
Period	Start: Jul 1, 2014	End: Sep 30, 2014	Submission Due Date: October 31, 2014

Electric Distribution System Assets - Build Metrics

All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.

Implemented Distribution Devices	Units	Project	System
Portion of system with SCADA	%	100	10.5
Portion of system with Distribution Automation (DA)	%	100	85
Automated Feeder Switches: number of devices installed	#	20	117
Automated Capacitors: number of devices installed	#	29	2,342
Automated Regulators: number of devices installed	#	0	3
Feeder Monitors: number of devices installed	#	0	0
Remote Fault Indicators: number of devices installed	#	96	325
Transformer Monitors (line): number of devices installed	#	0	
Smart Relays: number of devices installed	#	63	2,277
Fault Current Limiter: number of devices installed	#	0	0
Other devices installed:	#		
Other devices installed:	#		
Other devices installed:	#		

DA Applications in Operation	Units	Project	System
Fault Location, Isolation, and Service Restoration (FLISR): is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Voltage Optimization: is this application in operation?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Feeder Peak Load Management: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Microgrids: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other DA Application: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>

Page 16 of 24 Custom Created: October 4, 2011

Metric Updated: April 8, 2011
Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2014	
Period	Start: Jul 1, 2014	End: Sep 30, 2014	Submission Due Date: October 31, 2014

Distribution Management System Integration

	Units	Project	System
AMI: is integration complete?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Outage Management System: is integration complete?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Transmission Management System: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Distributed Energy Resources: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other Systems: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>

Distribution Device Description

	Project	System
SCADA	Distribution SCADA in conjunction with project DMS/CMS, includes a Tropos wireless network to reach devices outside the substation.	ABB Network Manager (EMS) across system plus project Distribution SCADA.
Portion of system with SCADA	Distribution SCADA has been deployed to all field devices in the project area.	The ABB Network Manager (EMS) communicates with 70% of feeder breakers, but only 15% of those have communications capable of supporting Smart Grid functionality.
Portion of system with DA	DA capabilities are installed on all project circuits.	KCP&L has locally automated devices such as capacitors, voltage monitors, faulted circuit indicators, and reclosers across the distribution system. 80% represents an estimate of coverage based on number of circuits with one or more of these devices.
DA devices	There is a mix of communicating and automated capacitors, faulted circuit indicators, and reclosers across the project area.	There is a mix of locally automated capacitors, voltage monitors, faulted circuit indicators, and reclosers across distribution system.

Page 19 of 24 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2014	
Period	Start: Jul 1, 2014	End: Sep 30, 2014	Submission Due Date: October 31, 2014

Distribution Device Description

	Project	System
DA communications network	Tropos GridCom wireless IP mesh network	Lands+Gyr AMR system and Telemetric/Sensus cellular-based system.
Other device	N/A	N/A
Other device	N/A	N/A
Other device	N/A	N/A

Distribution Application Descriptions

	Project	System
FLISR	As part of the project, the DMS enables FLISR across project circuits. This will reduce outages and outage response time, and improve overall system performance.	As part of the project, the DMS enables FLISR across project circuits. This will reduce outages and outage response time, and improve overall system performance.

Page 20 of 24 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2014	
		Period	Start: Jul 1, 2014	End: Sep 30, 2014 Submission Due Date: October 31, 2014
Voltage Optimization	As part of the project, the DMS enables voltage optimization across project circuits. This will improve power factor as well as enable voltage conservation.		A Dynamic Voltage Control (DVC) system exists on 203 buses within metropolitan Kansas City. This system is able to dynamically reduce voltage through load tap changers to achieve voltage changes in coordination with locally controlled cap banks.	
Feeder Peak Load Management	As part of the project, the DMS enables dynamic feeder load transfer across project circuits. This will reduce outages on project feeders, reduce stress on critical assets, and improve maintenance.		System peak loads are curtailed through utilization of the DVC system and existing PCT program operated by Honeywell.	
Microgrids	N/A		N/A	
Other DA Applications	N/A		N/A	
Distribution Management Integration Descriptions				
	Project		System	
AMI	DMS is integrated with project AMI.		DMS is integrated with project AMI.	
Outage Management	DMS is integrated with project OMS.		DMS is integrated with project OMS.	

Page 21 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 3, 2014	
		Period	Start: Jul 1, 2014	End: Sep 30, 2014 Submission Due Date: October 31, 2014
Distribution Management Integration Descriptions				
	Project		System	
Transmission Management	N/A		N/A	
DER Systems	DMS is integrated with project DERM.		DMS is integrated with project DERM.	
Distribution Management System	DMS consisting of D-SCADA and DNA provided by Siemens and OMS and user interface provided by Intergraph.		DMS consisting of D-SCADA and DNA provided by Siemens and OMS and user interface provided by Intergraph.	
Other Systems	N/A		N/A	
Additional Project Descriptions	N/A			
Distribution Systems Installed Costs				
	Units	Project Funded	Cost Share	
Back Office Systems	\$	372,159	343,106	
Distribution Management System	\$	4,338,858	3,436,891	
Communications Equipment and SCADA	\$	959,422	885,621	

Page 22 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2014	
Period	Start: Jul 1, 2014	End: Sep 30, 2014	Submission Due Date: October 31, 2014

Distribution Systems Installed Costs	Units	Project Funded	Cost Share
Feeder Monitor/Indicator	\$	26,079	23,876
Substation Monitors	\$	1,244,366	1,141,646
Automated Feeder Switches	\$	690,574	632,255
Capacitor Automation Equipment	\$	72,896	66,740
Regulator Automation Equipment	\$		
Fault Current Limiter Equipment	\$		
Cost of other devices installed	\$		
Cost of other devices installed	\$		
Cost of other devices installed	\$		
Other Costs	\$	377,579	339,616
Other Cost Description	KCP&L labor charges across various device types.		

Page 23 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 3, 2014	
Period	Start: Jul 1, 2014	End: Sep 30, 2014	Submission Due Date: October 31, 2014

Submit
Print Form

Page 24 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2

S.19 2014 Q4

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 4, 2014		
		Period	Start: Oct 1, 2014	End: Dec 31, 2014	Submission Due Date: January 31, 2015
AMI Assets - Build Metrics					
<i>All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.</i>					
AMI End Points Installed		Units	Project	System	
End Points (meters) installed and operational	#		13,483	231,571	
Portion of customers with AMI residential	#		12,259	207,674	
Portion of customers with AMI commercial	#		1,224	23,389	
Portion of customers with AMI industrial	#		0	498	
Implemented Meter Features		Units	Project	System	
Reading interval for residential meters	minutes		15	15	
Reading interval for commercial meters	minutes		15	15	
Reading interval for industrial meters	minutes			15	
Remote Connect/Disconnect: is feature implemented?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Remote Connect/Disconnect: number of meters with feature implemented	#		13,003	26,904	
Outage Reporting: is feature implemented?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Outage Reporting: number of meters with feature implemented	#		13,483	231,571	
Power Quality Measurement: is feature implemented?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Power Quality Measurement: number of meters with feature implemented	#				
Tamper Detection: is feature implemented?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Tamper Detection: number of meters with feature implemented	#		13,483	231,571	
Other feature implemented	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other feature: number of meters with feature implemented	#				
Other feature implemented	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other feature: number of meters with feature implemented	#				
Other feature implemented	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other feature: number of meters with feature implemented	#				

Page 1 of 24 Custom Created: October 8, 2011 Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 4, 2014		
		Period	Start: Oct 1, 2014	End: Dec 31, 2014	Submission Due Date: January 31, 2015
Implemented Meter Features		Units	Project	System	
Other feature: number of meters with feature implemented	#				
Implemented Enterprise Integration		Units	Project	System	
Billing System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Customer Information System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Outage Management System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Distribution Management System: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Other Enterprise Systems: is integration complete?	yes/ no		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
AMI System Descriptions					
	Project	System			
Backhaul Network	Hybrid of Fiber and Wireless Raven radio with network carrier	Hybrid of Fiber and Wireless Raven radio with network carrier			
Meter Communication Network	Lands+Gyr Gridstream RF 900MHz - Collectors and Routers	Lands+Gyr Gridstream RF 900MHz - Collectors and Routers			
Headend System	Lands+Gyr Command Center	Lands+Gyr Command Center			
Meter Data Management System	eMeter/Siemens	eMeter/Siemens			

Page 2 of 24 Custom Created: October 8, 2011 Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 4, 2014		
		Period	Start: Oct 1, 2014	End: Dec 31, 2014	Submission Due Date: January 31, 2015
AMI System Descriptions					
	Project	System			
Meter Data Analysis	The project AMI was incorporated into the existing AMR – MDA interfaces. AMI daily register reads and 15-min interval reads are loaded into MDA (DataRaker) on a daily basis.	The project AMI was incorporated into the existing AMR – MDA interfaces. AMI daily register reads and 15-min interval reads are loaded into MDA (DataRaker) on a daily basis.			
Other Meter Feature	N/A	N/A			
Other Meter Feature	N/A	N/A			
Other Meter Feature	N/A	N/A			
AMI Enterprise Integration Descriptions					
	Project	System			
Billing System	AMI is integrated with enterprise Oracle CIS.	AMI is integrated with enterprise Oracle CIS.			

Page 3 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 4, 2014		
		Period	Start: Oct 1, 2014	End: Dec 31, 2014	Submission Due Date: January 31, 2015
AMI Enterprise Integration Descriptions					
	Project	System			
Customer Information System	AMI is integrated with KCP&L enterprise Oracle CIS. The project AMI was incorporated into the existing AMR – CIS interfaces. CIS daily account/meter synchronization. AMI provides CIS daily register meter reads for direct billing. CIS daily billing cycle-to-date usage info and bill prediction pushed to IHDs via AMI Network.	AMI is integrated with KCP&L enterprise Oracle CIS. The project AMI was incorporated into the existing AMR – CIS interfaces. CIS daily account/meter synchronization. AMI provides CIS daily register meter reads for direct billing. CIS daily billing cycle-to-date usage info and bill prediction pushed to IHDs via AMI Network.			
Outage Management System	AMI is integrated with enterprise OMS. An additional project OMS (redundant) will also be implemented in conjunction with a DMS. The project AMI was incorporated into the existing AMR to enterprise OMS interfaces including meter outage alerts and meter "ping" functionality to verify power restoration.	AMI is integrated with enterprise OMS. An additional project OMS (redundant) will also be implemented in conjunction with a DMS. The project AMI was incorporated into the existing AMR to enterprise OMS interfaces including meter outage alerts and meter "ping" functionality to verify power restoration.			
Distribution Management System	DMS is integrated with multiple project and legacy systems including AMI, DERM, OMS, and energy storage.	DMS is integrated with multiple project and legacy systems including AMI, DERM, OMS, and energy storage.			
Other Enterprise Systems	Data Mining and Analysis Tool (DataRaker) covered by the MDA	Data Mining and Analysis Tool (DataRaker) covered by the MDA			
Additional Project Descriptions	N/A				
AMI Installed Costs		Units	Project Funded	Cost Share	
Back Office Systems	\$	2,337,739	2,157,913		
Communications Equipment	\$	119,308	110,130		
AMI Smart Meters	\$	2,252,704	2,076,390		

Page 4 of 24 Custom Created: October 4, 2011  Meter Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2014	
Period	Start: Oct 1, 2014	End: Dec 31, 2014	Submission Due Date: January 31, 2015

AMI Installed Costs	Units	Project Funded	Cost Share
Other Costs	5		
Other Costs Description	N/A		

Page 5 of 24 Custom Created: October 4, 2011



Metric Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2014	
Period	Start: Oct 1, 2014	End: Dec 31, 2014	Submission Due Date: January 31, 2015

Customer Systems Assets - Build Metrics

All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.

Implemented Customer Systems	Units	Project	System
In-Home display: devices installed	#	616	616
Direct Load Control Devices: devices installed	#	131	131
Programmable Communicating Thermostats: devices installed	#	112	53,824
Smart Appliances: devices installed	#	0	0
Energy Management Devices/Systems: devices installed	#	0.0	0.0
Other Devices installed	#	61	61
Other Devices installed	#		
Other Devices installed	#		

Web Portal	Units	Project	System
Web portal is portal in production?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Customers with access	#	12,036	12,036
Customers with active accounts	#	2,109	2,109

Customer System Descriptions	Project	System
In-Home Displays	Tendril In-Sight	Tendril In-Sight

Page 6 of 24 Custom Created: October 4, 2011



Metric Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 4, 2014		
		Period	Start: Oct 1, 2014	End: Dec 31, 2014	Submission Due Date: January 31, 2015
Customer System Descriptions					
	Project	System			
Direct Load Control Devices	Tendril Volt	Tendril Volt			
Programmable Communicating Thermostats	Tendril Setpoint	Tendril Setpoint and Honeywell PCTs			
Smart Appliances	N/A	N/A			
Energy Mgmt. Systems	N/A	N/A			
Web Portal	Tendril Energize Web Portal	Tendril Energize Web Portal			
Home Area Network	Zigbee SEP 1.0	Zigbee SEP 1.0			

Page 7 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 4, 2014		
		Period	Start: Oct 1, 2014	End: Dec 31, 2014	Submission Due Date: January 31, 2015
Customer System Descriptions					
	Project	System			
Other Device	Tendril Transport Gateway	Tendril Transport Gateway			
HAN Gateway					
Other Device	N/A	N/A			
Other Device	N/A	N/A			
Additional Project Descriptions	N/A				

Customer System Installed Costs	Units	Project Funded	Cost Share
Back Office Systems	\$	441,625	406,255
Web Portals	\$	940,730	868,293
In-Home Displays	\$	155,669	143,694
Direct Load Control Devices	\$	90,344	83,395
Smart Appliances	\$	0	0
Programmable Communicating Thermostats	\$	378,345	335,076
Cost of other devices installed: HAN Gateway	\$	228,510	204,464

Page 8 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2014	
Period	Start: Oct 1, 2014	End: Dec 31, 2014	Submission Due Date: January 31, 2015

Customer System Installed Costs	Units	Project Funded	Cost Share
Cost of other devices installed	\$	[]	[]
Cost of other devices installed	\$	[]	[]
Other Costs	\$	390,761	357,473
Other Cost Description	Program delivery costs including KCP&L labor for program administration, analysis, and customer engagement as well as vendor travel expenses.		

Page 9 of 24 Custom Created: October 4, 2011

Metric Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2014	
Period	Start: Oct 1, 2014	End: Dec 31, 2014	Submission Due Date: January 31, 2015

Pricing Programs - Build Metrics

All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.

Implemented Rate Plans	Units	Project	System
Flat Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Flat Rate: number of customers with access	#	[]	[]
Flat Rate: number of customers enrolled	#	[]	162,409
Flat Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Critical Peak Pricing: number of customers with access	#	[]	[]
Flat Rate with Critical Peak Pricing: number of customers enrolled	#	[]	[]
Flat Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Flat Rate with Peak Time Rebate: number of customers with access	#	[]	[]
Flat Rate with Peak Time Rebate: number of customers enrolled	#	[]	[]
Tiered Rate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Tiered Rate: number of customers with access	#	[]	[]
Tiered Rate: number of customers enrolled	#	[]	694,691
Tiered Rate with Critical Peak Pricing: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Critical Peak Pricing: number of customers with access	#	[]	[]
Tiered Rate with Critical Peak Pricing: number of customers enrolled	#	[]	[]
Tiered Rate with Peak Time Rebate: is the pricing program available?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Tiered Rate with Peak Time Rebate: number of customers with access	#	[]	[]
Tiered Rate with Peak Time Rebate: number of customers enrolled	#	[]	[]
Time of Use Rate: is the pricing program available?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Time of Use Rate: number of customers with access	#	12,259	[]

Page 10 of 24 Custom Created: October 4, 2011

Metric Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 4, 2014		
		Period	Start: Oct 1, 2014	End: Dec 31, 2014	Submission Due Date: January 31, 2015
Implemented Rate Plans		Units	Project	System	
Time of Use Rate: number of customers enrolled	#		102	341	
Time of Use Rate with Critical Peak Pricing: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Time of Use Rate with Critical Peak Pricing: number of customers with access	#				
Time of Use Rate with Critical Peak Pricing: number of customers enrolled	#				
Time of Use Rate with Peak Time Rebate: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Time of Use Rate with Peak Time Rebate: number of customers with access	#				
Time of Use Rate with Peak Time Rebate: number of customers enrolled	#				
Real-time Pricing: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Real-time Pricing: number of customers with access	#				
Real-time Pricing: number of customers enrolled	#			0	
Real-time Pricing with Critical Peak Pricing: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Real-time Pricing with Critical Peak Pricing: number of customers with access	#				
Real-time Pricing with Critical Peak Pricing: number of customers enrolled	#				
Real-time Pricing with Peak Time Rebate: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Real-time Pricing with Peak Time Rebate: number of customers with access	#				
Real-time Pricing with Peak Time Rebate: number of customers enrolled	#				
Variable Peak Pricing: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Variable Peak Pricing: number of customers with access	#				
Variable Peak Pricing: number of customers enrolled	#				
Pre-pay Pricing: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Pre-pay Pricing: number of customers with access	#				
Pre-pay Pricing: number of customers enrolled	#				
Net Metering: is the pricing program available?	yes/ no		<input type="checkbox"/>	<input checked="" type="checkbox"/>	

Page 11 of 24 Custom Created: October 4, 2011 Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 4, 2014		
		Period	Start: Oct 1, 2014	End: Dec 31, 2014	Submission Due Date: January 31, 2015
Implemented Rate Plans		Units	Project	System	
Net Metering: number of customers with access	#				
Net Metering: number of customers enrolled	#			2,336	
Other program available	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other programs: number of customers with access	#				
Other programs: number of customers enrolled	#				
Other program available	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other programs: number of customers with access	#				
Other programs: number of customers enrolled	#				
Other program available	yes/ no		<input type="checkbox"/>	<input type="checkbox"/>	
Other programs: number of customers with access	#				
Other programs: number of customers enrolled	#				
Rate Decoupling: is implemented?	yes/ no		<input type="checkbox"/>		
Rate Plan Descriptions					
	Project	System			
Flat Rate	N/A	KCP&L has multiple residential and C&I Flat Rates that occur during both summer and winter. We are not able to calculate an accurate number for how many customers have access.			
Flat Rate with Critical Peak Pricing	N/A	N/A			

Page 12 of 24 Custom Created: October 4, 2011 Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 4, 2014	
		Period	Start: Oct 1, 2014	End: Dec 31, 2014 Submission Due Date: January 31, 2015
Rate Plan Descriptions				
	Project	System		
Flat Rate with Peak Time Rebate	N/A	N/A		
Tiered Rate	N/A	KCP&L has multiple existing residential and C&I Tiered Rates. A majority of those are declining block rates. We are not able to calculate an accurate number for how many customers have access.		
Tiered Rate with Critical Peak Pricing	N/A	N/A		
Tiered Rate with Peak Time Rebate	N/A	N/A		
Time of Use Rate	A new residential TOU rate is being piloted as part of this project to augment the evaluation of customer information systems and control devices.	KCP&L has multiple existing residential and C&I TOU Rates. We are not able to calculate an accurate number for how many customers have access.		
Time of Use Rate with Critical Peak Pricing	N/A	N/A		

Page 13 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)	
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 4, 2014	
		Period	Start: Oct 1, 2014	End: Dec 31, 2014 Submission Due Date: January 31, 2015
Rate Plan Descriptions				
	Project	System		
Time of Use Rate with Peak Time Rebate	N/A	N/A		
Real-Time Rate	N/A	KCP&L has multiple existing RTP rates for commercial and industrial customers. We are not able to calculate an accurate number for how many customers have access.		
Real-time Rate with Critical Peak Pricing	N/A	N/A		
Real-time Rate with Peak Time Rebate	N/A	N/A		
Variable Peak Pricing	N/A	N/A		
Pre-paid Rate	N/A	N/A		

Page 14 of 24 Custom Created: October 4, 2011  Meter Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 4, 2014		
		Period	Start: Oct 1, 2014	End: Dec 31, 2014	Submission Due Date: January 31, 2015

Rate Plan Descriptions		
	Project	System
Net Metering Rate	N/A	KCP&L has multiple existing residential and C&I Net Metering Rates. We are not able to calculate an accurate number for how many customers have access.
Other program	N/A	N/A
Other program	N/A	N/A
Other program	N/A	N/A
Additional Project Descriptions	N/A	

Page 15 of 24 Custom Created: October 4, 2011 Meter Updated: April 9, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 4, 2014		
		Period	Start: Oct 1, 2014	End: Dec 31, 2014	Submission Due Date: January 31, 2015

Distributed Energy Resources - Build Metrics			
<i>All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.</i>			
Distributed Energy Resources	Units	Project	System
Distributed generation: number of units	#	9	2,361
Distributed generation: installed capacity	KW	176.11	46,055.126
Distributed generation: total energy delivered	* kWh	28,311	
Energy storage: number of units	#	1	1
Energy storage: installed capacity	KW	1,000	1,000
Energy storage: total energy delivered	* kWh	45,645	45,645
Plug-in electric vehicles charging points: number of units	#	19	57
Plug-in electric vehicles charging points: installed capacity	KW	133	371
Plug-in electric vehicles charging points: total energy delivered	* kWh	3,736	10,049
DER/DG interconnection equipment: number of units	#		

* Energy delivered should be reported just for the quarter being reported, not cumulative for the project to-date.

Distributed Energy Resource Descriptions		
	Project	System
Distributed Generation Interface Description	All DG installed is non-dispatchable utility-owned PV that is being metered separately. All project EV chargers are installed behind customer meters. Most interfaces currently limited to measuring data. EV chargers may be remotely deactivated to curtail load.	Non-dispatchable utility-owned DG and EV Chargers. All EV chargers are installed behind customer meters. Most interfaces currently limited to measuring data. EV chargers may be remotely deactivated to curtail load.

Page 16 of 24 Custom Created: October 4, 2011 Meter Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2014	
Period	Start: Oct 1, 2014	End: Dec 31, 2014	Submission Due Date: January 31, 2015

Additional Project Descriptions

Distributed Energy Resources' Installed Costs	Units	Project Funded	Cost Share
DER Interface Control Systems	\$	2,585,472	2,183,009
Communications Equipment	\$	0	0
DER/DG Interconnection Equipment	\$	0	0
Renewable DER	\$	688,165	541,403
Distributed Generation Equipment	\$	0	0
Stationary Electric Storage Equipment	\$	4,017,795	3,708,112
PEVs and Charging Stations	\$	71,089	60,207
Other Costs	\$		

Other Cost Description

N/A

Page 17 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2014	
Period	Start: Oct 1, 2014	End: Dec 31, 2014	Submission Due Date: January 31, 2015

Electric Distribution System Assets - Build Metrics

All data should be cumulative. Project data pertains to the assets or programs that are funded by the ARRA and Recipient Cost Share. System data should include both project data and any like assets or programs that are deployed in the entire service territory. The system value should be equal to or greater than the project value.

Implemented Distribution Devices	Units	Project	System
Portion of system with SCADA	%	100	10.5
Portion of system with Distribution Automation (DA)	%	100	85
Automated Feeder Switches: number of devices installed	#	20	117
Automated Capacitors: number of devices installed	#	29	2,342
Automated Regulators: number of devices installed	#	0	3
Feeder Monitors: number of devices installed	#	0	0
Remote Fault Indicators: number of devices installed	#	96	325
Transformer Monitors (line): number of devices installed	#	0	0
Smart Relays: number of devices installed	#	63	2,277
Fault Current Limiter: number of devices installed	#	0	0
Other devices installed	#		
Other devices installed	#		
Other devices installed	#		

DA Applications in Operation	Units	Project	System
Fault Location, Isolation, and Service Restoration (FLISR): is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Voltage Optimization: is this application in operation?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Feeder Peak Load Management: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Microgrids: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other DA Application: is this application in operation?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>

Page 16 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2014	
Period	Start: Oct 1, 2014	End: Dec 31, 2014	Submission Due Date: January 31, 2015

Distribution Management System Integration

	Units	Project	System
AMI: is integration complete?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Outage Management System: is integration complete?	yes/ no	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Transmission Management System: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Distributed Energy Resources: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>
Other Systems: is integration complete?	yes/ no	<input type="checkbox"/>	<input type="checkbox"/>

Distribution Device Description

	Project	System
SCADA	Distribution SCADA in conjunction with project DMS/CMS, includes a Tropos wireless network to reach devices outside the substation.	ABB Network Manager (EMS) across system plus project Distribution SCADA.
Portion of system with SCADA	Distribution SCADA has been deployed to all field devices in the project area.	The ABB Network Manager (EMS) communicates with 70% of feeder breakers, but only 15% of those have communications capable of supporting Smart Grid functionality.
Portion of system with DA	DA capabilities are installed on all project circuits.	KCP&L has locally automated devices such as capacitors, voltage monitors, faulted circuit indicators, and reclosers across the distribution system. 85% represents an estimate of coverage based on number of circuits with one or more of these devices.
DA devices	There is a mix of communicating and automated capacitors, faulted circuit indicators, and reclosers across the project area.	There is a mix of locally automated capacitors, voltage monitors, faulted circuit indicators, and reclosers across distribution system.

Page 19 of 24 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2014	
Period	Start: Oct 1, 2014	End: Dec 31, 2014	Submission Due Date: January 31, 2015

Distribution Device Description

	Project	System
DA communications network	Tropos GridCom wireless IP mesh network	Lands+Gyr AMR system and Telemetric/Sensus cellular-based system.
Other device	N/A	N/A
Other device	N/A	N/A
Other device	N/A	N/A

Distribution Application Descriptions

	Project	System
FLISR	As part of the project, the DMS enables FLISR across project circuits. This will reduce outages and outage response time, and improve overall system performance.	As part of the project, the DMS enables FLISR across project circuits. This will reduce outages and outage response time, and improve overall system performance.

Page 20 of 24 Custom Created: October 4, 2011



Master Updated: April 8, 2011 Schema Version: 1.2

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 4, 2014		
		Period	Start: Oct 1, 2014	End: Dec 31, 2014	Submission Due Date: January 31, 2015
Voltage Optimization	As part of the project, the DMS enables voltage optimization across project circuits. This will improve power factor as well as enable voltage conservation.		A Dynamic Voltage Control (DVC) system exists on 203 buses within metropolitan Kansas City. This system is able to dynamically reduce voltage through load tap changers to achieve voltage changes in coordination with locally controlled cap banks.		
Feeder Peak Load Management	As part of the project, the DMS enables dynamic feeder load transfer across project circuits. This will reduce outages on project feeders, reduce stress on critical assets, and improve maintenance.		System peak loads are curtailed through utilization of the DVC system and existing PCT program operated by Honeywell.		
Microgrids	N/A		N/A		
Other DA Applications	N/A		N/A		
Distribution Management Integration Descriptions					
	Project		System		
AMI	DMS is integrated with project AMI.		DMS is integrated with project AMI.		
Outage Management	DMS is integrated with project OMS.		DMS is integrated with project OMS.		

SMARTGRID.GOV		Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
		Filing	build_quarterly Build Metrics Quarterly Report Quarter 4, 2014		
		Period	Start: Oct 1, 2014	End: Dec 31, 2014	Submission Due Date: January 31, 2015
Distribution Management Integration Descriptions					
	Project		System		
Transmission Management	N/A		N/A		
DER Systems	DMS is integrated with project DERM.		DMS is integrated with project DERM.		
Distribution Management System	DMS consisting of D-SCADA and DNA provided by Siemens and OMS and user interface provided by Intergraph.		DMS consisting of D-SCADA and DNA provided by Siemens and OMS and user interface provided by Intergraph.		
Other Systems	N/A		N/A		
Additional Project Descriptions	N/A				
Distribution Systems Installed Costs			Units	Project Funded	Cost Share
Back Office Systems			\$	372,159	343,106
Distribution Management System			\$	4,338,858	3,436,891
Communications Equipment and SCADA			\$	959,422	885,621



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2014	
Period	Start: Oct 1, 2014	End: Dec 31, 2014	Submission Due Date: January 31, 2015

Distribution Systems Installed Costs	Units	Project Funded	Cost Share
Feeder Monitor/Indicator	\$	26,079	23,876
Substation Monitors	\$	1,244,366	1,141,646
Automated Feeder Switches	\$	690,574	632,255
Capacitor Automation Equipment	\$	72,896	66,740
Regulator Automation Equipment	\$	0	0
Fault Current Limiter Equipment	\$	0	0
Cost of other devices installed	\$		
Cost of other devices installed	\$		
Cost of other devices installed	\$		
Other Costs	\$	377,579	339,616

Other Cost Description: KCP&L labor charges across various device types.

Page 23 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2



Project	DE-OE0000221 Kansas City Power and Light (Green Impact Zone SmartGrid Demonstration)		
Filing	build_quarterly	Build Metrics Quarterly Report Quarter 4, 2014	
Period	Start: Oct 1, 2014	End: Dec 31, 2014	Submission Due Date: January 31, 2015

Submit
Print Form

Page 24 of 24 Custom Created: October 4, 2011



Metric Updated: April 9, 2011 Schema Version: 1.2

Appendix T Impact Metrics

T.1	WINTER 2011 (2011 Q4 – 2012 Q1)	T-3
T.2	SUMMER 2012 (2012 Q2 – 2012 Q3)	T-6
T.3	WINTER 2012 (2012 Q4 – 2013 Q1)	T-9
T.4	SUMMER 2013 (2013 Q2 – 2013 Q3)	T-17
T.5	WINTER 2013 (2013 Q4 – 2014 Q1)	T-25
T.6	SUMMER 2014 (2014 Q2 – 2014 Q3)	T-33

This page intentionally blank

T.1 Winter 2011 (2011 Q4 – 2012 Q1)

Project Name KCP&L Green Impact Zone Smart Grid Demonstration Project ID DE-OE0000221 Reporting Period SUMMER 2011		PLEASE DO NOT UNPROTECT THE SHEET FOR ANY REASON. IF THERE IS AN ISSUE WITH THE TEM			
Metric	Metric Qualifier	Unit	Project Value	System Value	Comments
Vehicle Type AMI	What type of vehicle is dispatched (or would have been dispatched) on the majority of the miles (or avoided miles) reported?	Drop Down	N/A		
EPA eGRID Region	What geographic subregion is your project located in (see the Geographic Subregion Map for reference)?	Drop Down	N/A		
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Residential Usage	8760 data	This will be reported using a separate sheet	This will be reported using a separate sheet	
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Residential Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Commercial Usage	8760 data	This will be reported using a separate sheet	This will be reported using a separate sheet	
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Commercial Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Industrial Usage	8760 data	This will be reported using a separate sheet	This will be reported using a separate sheet	
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Industrial Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Residential Usage	kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Residential Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Commercial Usage	kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Commercial Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Industrial Usage	kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Industrial Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Peak Load and Mix	Peak Load - Total Amount (AMI)	MW	37.7781450		
Peak Load and Mix	Peak Load - Customer Class A (AMI) (Optional)	MW	20.7070172		
Peak Load and Mix	Peak Load - Customer Class A Description (AMI) (Optional)	Text	AMI Meters- Residential		
Peak Load and Mix	Peak Load - Customer Class B (AMI) (Optional)	MW	17.0711287		
Peak Load and Mix	Peak Load - Customer Class B Description (AMI) (Optional)	Text	AMI Meters- Commercial		
Peak Load and Mix	Peak Load - Customer Class C (AMI) (Optional)	MW	N/A		
Peak Load and Mix	Peak Load - Customer Class C Description (AMI) (Optional)	Text	N/A		
Peak Load and Mix	Peak Load - Customer Class D (AMI) (Optional)	MW	N/A		
Peak Load and Mix	Peak Load - Customer Class D Description (AMI) (Optional)	Text	N/A		

Peak Load and Mix	Peak Load - Date and Time (AMI)	Date/Time	January 12, 2012 / 18:00:00		
Peak Load and Mix	Peak Load Mix - Direct Load Control Available (AMI)	MW	0		
Peak Load and Mix	Peak Load Mix - Direct Load Control Dispatched at Peak (Optional) (AMI)	MW	0		
Number of Meter Tamper Detections	Number of Meter Tamper Detections: # Identified	#	0	0	
Number of Meter Tamper Detections	Number of Meter Tamper Detections: # Confirmed (Optional)	#	0		
Meter Operations Cost	Meter Operations Cost	\$	Monthly: (\$19,357.76)		
Truck Rolls	Truck Rolls Avoided (mirror)	#	0		
Meter Operations Vehicle Miles	Meter Operations Vehicle Miles Avoided (mirror)	miles	0		
SAIFI	SAIFI	Index	0.876860519		
SAIDI	SAIDI	Index	62.15812107		
CAIDI	CAIDI	Index	70.88712486		
SAIDI and SAIFI	Total number of customers served used in SAIDI and SAIFI calculation	#	13,034		
CO2 Emissions	CO2 Emissions: AMI, Vehicle	tons		0	
CO2 Emissions	CO2 Emissions: AMI, Generation or Supply	tons		0	
CO2 Emissions	Avoided CO2 Emissions: AMI, Vehicle (mirror)	tons	0		
Pollutant Emissions (SOx, NOx, PM-2.5)	Avoided SOx Emissions: AMI, Vehicle (mirror)	tons	0		
Pollutant Emissions (SOx, NOx, PM-2.5)	Avoided NOx Emissions: AMI, Vehicle (mirror)	tons	0		
Meter Data Completeness	Meter Data Completeness	%	97.46%		
Meters Reporting Daily	Meters Reporting Daily (% of necessary data points reported)	%	97.71%		
Custom Metrics					
Metric Name		Units	Project Value	System Value	Comments
END	END	END			

Project Name		KCP&L Green Impact Zone Smart Grid Demonstration		PLEASE DO NOT UNPROTECT THE SHEET FOR ANY REASON. IF THERE IS AN ISSUE WITH THE TEMPLATE PLEASE CONTACT THE DDC.									
Project ID		DE-080000221											
Metric	Metric Qualifier	Units	2011 SUMMER	2011 WINTER	2012 SUMMER	2012 WINTER	2013 SUMMER	2013 WINTER	2014 SUMMER	2014 WINTER	2015 SUMMER		
Number of Meter Tamper Detections	Number of Meter Tamper Detections: # Identified	#	N/A	0									
Meter Operations Cost	Meter Operations Cost	-\$	N/A	0									
Truck Rolls	Truck Rolls Avoided (Estimated)	#	N/A	0									
CO2 Emissions	CO2 Emissions: AMI, Vehicle	tons	N/A	0									
CO2 Emissions	CO2 Emissions: AMI, Generation or Supply	tons	N/A	0									
Custom Metrics													
Metric Name		Units	2011 SUMMER	2011 WINTER	2012 SUMMER	2012 WINTER	2013 SUMMER	2013 WINTER	2014 SUMMER	2014 WINTER	2015 SUMMER		
END		END											

T.2 Summer 2012 (2012 Q2 – 2012 Q3)

Project Name KCP&L Green Impact Zone Smart Grid Demonstration Project ID DE-OE0000221 Reporting Period SUMMER 2011		PLEASE DO NOT UNPROTECT THE SHEET FOR ANY REASON. IF THERE IS AN ISSUE WITH THE TEM			
Metric	Metric Qualifier	Unit	Project Value	System Value	Comments
Vehicle Type AMI	What type of vehicle is dispatched (or would have been dispatched) on the majority of the miles (or avoided miles) reported?	Drop Down	N/A		
EPA eGRID Region	What geographic subregion is your project located in (see the Geographic Subregion Map for reference)?	Drop Down	N/A		
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Residential Usage	8760 data	This will be reported using a separate sheet	This will be reported using a separate sheet	
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Residential Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Commercial Usage	8760 data	This will be reported using a separate sheet	This will be reported using a separate sheet	
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Commercial Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Industrial Usage	8760 data	This will be reported using a separate sheet	This will be reported using a separate sheet	
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Industrial Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Residential Usage	kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Residential Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Commercial Usage	kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Commercial Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Industrial Usage	kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Industrial Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Peak Load and Mix	Peak Load - Total Amount (AMI)	MW	52.5041705		
Peak Load and Mix	Peak Load - Customer Class A (AMI) (Optional)	MW	28.6925985		
Peak Load and Mix	Peak Load - Customer Class A Description (AMI) (Optional)	Text	AMI Meters- Residential		
Peak Load and Mix	Peak Load - Customer Class B (AMI) (Optional)	MW	23.811572		
Peak Load and Mix	Peak Load - Customer Class B Description (AMI) (Optional)	Text	AMI Meters- Commercial		
Peak Load and Mix	Peak Load - Customer Class C (AMI) (Optional)	MW	N/A		
Peak Load and Mix	Peak Load - Customer Class C Description (AMI) (Optional)	Text	N/A		
Peak Load and Mix	Peak Load - Customer Class D (AMI) (Optional)	MW	N/A		
Peak Load and Mix	Peak Load - Customer Class D Description (AMI) (Optional)	Text	N/A		

Peak Load and Mix	Peak Load - Date and Time (AMI)	Date/Time	N/A		
Peak Load and Mix	Peak Load Mix - Direct Load Control Available (AMI)	MW	N/A		
Peak Load and Mix	Peak Load Mix - Direct Load Control Dispatched at Peak (Optional) (AMI)	MW	N/A		
Number of Meter Tamper Detections	Number of Meter Tamper Detections: # Identified	#	N/A		
Number of Meter Tamper Detections	Number of Meter Tamper Detections: # Confirmed (Optional)	#	N/A		
Meter Operations Cost	Meter Operations Cost	\$	Monthly: \$19,357.76		
Truck Rolls	Truck Rolls Avoided (mirror)	#	0		
Meter Operations Vehicle Miles	Meter Operations Vehicle Miles Avoided (mirror)	miles	0		
SAIFI	SAIFI	Index	1.537186956		
SAIDI	SAIDI	Index	202.409547		
CAIDI	CAIDI	Index	131.6752957		
SAIDI and SAIFI	Total number of customers served used in SAIDI and SAIFI calculation	#	13,217		
CO2 Emissions	CO2 Emissions: AMI, Vehicle	tons		Optional	
CO2 Emissions	CO2 Emissions: AMI, Generation or Supply	tons		Optional	
CO2 Emissions	Avoided CO2 Emissions: AMI, Vehicle (mirror)	tons	Optional		
Pollutant Emissions (SOx, NOx, PM-2.5)	Avoided SOx Emissions: AMI, Vehicle (mirror)	tons	Optional		
Pollutant Emissions (SOx, NOx, PM-2.5)	Avoided NOx Emissions: AMI, Vehicle (mirror)	tons	Optional		
Meter Data Completeness	Meter Data Completeness	%	98.28%		
Meters Reporting Daily	Meters Reporting Daily (% of necessary data points reported)	%	98.44%		
Custom Metrics					
Metric Name		Units	Project Value	System Value	Comments
END	END	END			

Project Name		KCP&L Green Impact Zone Smart Grid Demonstration		PLEASE DO NOT UNPROTECT THE SHEET FOR ANY REASON. IF THERE IS AN ISSUE WITH THE TEMPLATE PLEASE CONT						
Project ID		DE-0E0000221								
Metric	Metric Qualifier	Unit	2011 SUMMER	2011 WINTER	2012 SUMMER	2012 WINTER	2013 SUMMER	2013 WINTER	2014 SUMMER	
Number of Meter Tamper Detections	Number of Meter Tamper Detections: # Identified	#			N/a					
Meter Operations Cost	Meter Operations Cost	\$			N/a					
Truck Rolls	Truck Rolls Avoided (minor)	#				0				
CO2 Emissions	CO2 Emissions: AMI, Vehicle	tons				0				
CO2 Emissions	CO2 Emissions: AMI, Generation or Supply	tons				0				
Custom Metrics										
Metric Name		Units	2011 SUMMER	2011 WINTER	2012 SUMMER	2012 WINTER	2013 SUMMER	2013 WINTER	2014 SUMMER	
END	END	END								

T.3 Winter 2012 (2012 Q4 – 2013 Q1)

Project Name KCP&L Green Impact Zone Smart Grid Demonstration Project ID DE-DE0000221 Reporting Period SUMMER 2011		PLEASE DO NOT UNPROTECT THE SHEET FOR ANY REASON. IF THERE IS AN ISSUE WITH THE TEM			
Metric	Metric Qualifier	Unit	Project Value	System Value	Comments
Vehicle Type AMI	What type of vehicle is dispatched (or would have been dispatched) on the majority of the miles (or avoided miles) reported?	Drop Down	Small field truck		
EPA eGRID Region	What geographic subregion is your project located in (see the Geographic Subregion Map for reference)?	Drop Down	SPNO - SPP North		
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Residential Usage	8760 data	This will be reported using a separate sheet	This will be reported using a separate sheet	
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Residential Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Commercial Usage	8760 data	This will be reported using a separate sheet	This will be reported using a separate sheet	
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Commercial Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Industrial Usage	8760 data	This will be reported using a separate sheet	This will be reported using a separate sheet	
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Industrial Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Residential Usage	kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Residential Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Commercial Usage	kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Commercial Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Industrial Usage	kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Industrial Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Peak Load and Mix	Peak Load - Total Amount (AMI)	MW	40.1995082		
Peak Load and Mix	Peak Load - Customer Class A (AMI) (Optional)	MW	21.9240876		
Peak Load and Mix	Peak Load - Customer Class A Description (AMI) (Optional)	Text	AMI Meters- Residential		
Peak Load and Mix	Peak Load - Customer Class B (AMI) (Optional)	MW	18.2745206		
Peak Load and Mix	Peak Load - Customer Class B Description (AMI) (Optional)	Text	AMI Meters- Commercial		
Peak Load and Mix	Peak Load - Customer Class C (AMI) (Optional)	MW	N/A		
Peak Load and Mix	Peak Load - Customer Class C Description (AMI) (Optional)	Text	N/A		
Peak Load and Mix	Peak Load - Customer Class D (AMI) (Optional)	MW	N/A		
Peak Load and Mix	Peak Load - Customer Class D Description (AMI) (Optional)	Text	N/A		

Peak Load and Mix	Peak Load - Date and Time (AMI)	Date/Time	1/31/2013 19:00		
Peak Load and Mix	Peak Load Mix - Direct Load Control Available (AMI)	MW	N/A		
Peak Load and Mix	Peak Load Mix - Direct Load Control Dispatched at Peak (Optional) (AMI)	MW	N/A		
Number of Meter Tamper Detections	Number of Meter Tamper Detections: # Identified	#	N/A		
Number of Meter Tamper Detections	Number of Meter Tamper Detections: # Confirmed (Optional)	#	N/A		
Meter Operations Cost	Meter Operations Cost	\$	167090.1		Last period, we mistakenly reported monthly cost increase. This is 6-month aggregate service cost to read meters. Not a very useful metric as this is a consistent recurring cost for a service from a vendor. We do not have actual expense numbers that can be tracked accurately for our small pilot area.
Truck Rolls	Truck Rolls Avoided (mirror)	#	2,851		
Meter Operations Vehicle Miles	Meter Operations Vehicle Miles Avoided (mirror)	miles	45,616		Assuming 16 miles round trip per truck roll based on distance from Dotson service center.
SAIFI	SAIFI	Index	0.95038253		
SAIDI	SAIDI	Index	155.8434388		
CAIDI	CAIDI	Index	163.9796965		
SAIDI and SAIFI	Total number of customers served used in SAIDI and SAIFI calculation	#	13,463		
CO2 Emissions	Avoided CO2 Emissions: AMI, Vehicle (mirror)	tons	27.12631467		8.92 x 10 ⁻³ metric tons CO2/gallon of gasoline (http://www.epa.gov/cleanenergy/energy-resources/refs.html) Assuming 15 miles/gallon
Pollutant Emissions (SOx, NOx, PM-2.5)	Avoided SOx Emissions: AMI, Vehicle (mirror)	tons	Optional		
Pollutant Emissions (SOx, NOx, PM-2.5)	Avoided NOx Emissions: AMI, Vehicle (mirror)	tons	Optional		
Meter Data Completeness	Meter Data Completeness	%	98.53%		
Meters Reporting Daily	Meters Reporting Daily (% of necessary data points reported)	%	98.33%		
Custom Metrics					
Metric Name		Units	Project Value	System Value	Comments
END	END	END			

Project Name		KCP&L Green Impact Zone Smart Grid Demonstration		PLEASE DO NOT UNPROTECT THE SHEET FOR ANY REASON. IF THERE IS AN ISSUE WITH THE TEMPLATE PLEASE CONT						
Project ID		DE-GE0000221								
Metric	Metric Qualifier	Unit	2011 SUMMER	2011 WINTER	2012 SUMMER	2012 WINTER	2013 SUMMER	2013 WINTER	2014 SUMMER	
Meter Operations Cost	Meter Operations Cost	\$				50943.54				
Truck Rolls	Truck Rolls Avoided (mirror)	#				0				
Custom Metrics										
Metric Name	Units	2011 SUMMER	2011 WINTER	2012 SUMMER	2012 WINTER	2013 SUMMER	2013 WINTER	2014 SUMMER		
END	END	END								

Project Name	KCPL Green Impact Zone Smart Grid Demonstration
Project ID	DE-OE000221
Reporting Period	SUMMER 2011

PLEASE DO NOT UNPROTECT THE SHEET FOR ANY REASON, IF THERE IS AN ISSUE WITH THE TEM

Metric	Metric Qualifier	Unit	Project Value	System Value	Comments
Vehicle Type Distribution	What type of vehicle is dispatched (or would have been dispatched) on the majority of the miles (or avoided miles) reported?	Drop Down	Bucket Truck		
EPA eGRID Region	What geographic subregion is your project located in (see the Geographic Subregion Map for reference)?	Drop Down	SPND - SPP North		
Distribution feeder or equipment overload incidents	Feeder Line: Number of Incidents	#	0		
Distribution feeder or equipment overload incidents	Substation Transformer: Number of Incidents	#	0		
Distribution feeder or equipment overload incidents	Feeder Line: Average duration of incident	minutes	0		
Distribution feeder or equipment overload incidents	Substation Transformer: Average duration of incident	minutes	0		
Distribution feeder load	Aggregated Average Real Load	MW	Optional		
Distribution feeder load	Aggregated Average Reactive Load	MVAR	Optional		
Distribution feeder load	Hourly Load Curves (Real Load)	MW	This will be reported using a separate sheet	This will be reported using a separate sheet	
Distribution feeder load	Hourly Load Curves (Reactive Load)	MVAR	This will be reported using a separate sheet	This will be reported using a separate sheet	
Deferred Distribution Capacity Investment	Total Capital Cost	\$	0		
Deferred Distribution Capacity Investment	Total Capital Cost Instance 2	\$	0		
Deferred Distribution Capacity Investment	Total Capital Cost Instance 3	\$	0		
Deferred Distribution Capacity Investment	Total Capital Cost Instance 4	\$	0		
Deferred Distribution Capacity Investment	Total Capital Cost Instance 5	\$	0		
Deferred Distribution Capacity Investment	Amount of Time Deferred	years	0		
Deferred Distribution Capacity Investment	Amount of Time Deferred Instance 2	years	0		
Deferred Distribution Capacity Investment	Amount of Time Deferred Instance 3	years	0		
Deferred Distribution Capacity Investment	Amount of Time Deferred Instance 4	years	0		
Deferred Distribution Capacity Investment	Amount of Time Deferred Instance 5	years	0		
Deferred Distribution Capacity Investment	Description of Deferral	Text	N/A		
Deferred Distribution Capacity Investment	Description of Deferral Instance 2	Text	N/A		
Deferred Distribution Capacity Investment	Description of Deferral Instance 3	Text	N/A		
Deferred Distribution Capacity Investment	Description of Deferral Instance 4	Text	N/A		
Deferred Distribution Capacity Investment	Description of Deferral Instance 5	Text	N/A		
Equipment Failure Incidents	Transformers: Number of Failures (Distribution)	#	0		
Equipment Failure Incidents	Feeders: Number of Failures (Distribution)	#	5		
Equipment Failure Incidents	Other Major Distribution Equipment A: Number of Failures	#	0		
Equipment Failure Incidents	Other Major Distribution Equipment B: Number of Failures	#	0		
Equipment Failure Incidents	Other Major Distribution Equipment C: Number of Failures	#	0		
Equipment Failure Incidents	Other Major Distribution Equipment A: Description	Text	N/A		
Equipment Failure Incidents	Other Major Distribution Equipment B: Description	Text	N/A		
Equipment Failure Incidents	Other Major Distribution Equipment C: Description	Text	N/A		
Equipment Failure Incidents	Transformers: Reasons for Failures (Distribution)	Text	N/A		

Equipment Failure Incidents	Feeders: Reasons for Failures (Distribution)	Text	4 x Vegetation (Trees); 1 x Failure Wear		1 event cause was MANUAL, but appears to be equivalent to vegetation event
Equipment Failure Incidents	Other Major Distribution Equipment A: Reasons for Failures	Text	N/A		
Equipment Failure Incidents	Other Major Distribution Equipment B: Reasons for Failures	Text	N/A		
Equipment Failure Incidents	Other Major Distribution Equipment C: Reasons for Failures	Text	N/A		
Distribution losses	Avoided distribution losses: Total Cumulative MWh of Avoided Losses (mirror)	MWh	0		
Truck Rolls (Distribution)	Truck Rolls Avoided (Distribution) (mirror)	#	0		
SAIFI	SAIFI	Index	0.95038253		
SAIDI	SAIDI	Index	155.8434388		
CAIDI	CAIDI	Index	163.9796965		
SAIDI and SAIFI	Total number of customers served used in SAIDI and SAIFI calculation	#	13463		
Major Event Information	Major Event Information: Infrastructure involved	Text	N/A		
Major Event Information	Major Event Information: Infrastructure involved Instance 2	Text	N/A		
Major Event Information	Major Event Information: Infrastructure involved Instance 3	Text	N/A		
Major Event Information	Major Event Information: Infrastructure involved Instance 4	Text	N/A		
Major Event Information	Major Event Information: Infrastructure involved Instance 5	Text	N/A		
Major Event Information	Major Event Information: Cause of the event	Text	N/A		
Major Event Information	Major Event Information: Cause of the event Instance 2	Text	N/A		
Major Event Information	Major Event Information: Cause of the event Instance 3	Text	N/A		
Major Event Information	Major Event Information: Cause of the event Instance 4	Text	N/A		
Major Event Information	Major Event Information: Cause of the event Instance 5	Text	N/A		
Major Event Information	Major Event Information: Number of customers affected	#	0		
Major Event Information	Major Event Information: Number of customers affected Instance 2	#	0		
Major Event Information	Major Event Information: Number of customers affected Instance 3	#	0		
Major Event Information	Major Event Information: Number of customers affected Instance 4	#	0		
Major Event Information	Major Event Information: Number of customers affected Instance 5	#	0		

Major Event Information	Major Event Information: Number of customers that would have been affected without SGDP/RDSI DA technology	#	0		
Major Event Information	Major Event Information: Number of customers that would have been affected without SGDP/RDSI DA technology Instance 2	#	0		
Major Event Information	Major Event Information: Number of customers that would have been affected without SGDP/RDSI DA technology Instance 3	#	0		
Major Event Information	Major Event Information: Number of customers that would have been affected without SGDP/RDSI DA technology Instance 4	#	0		
Major Event Information	Major Event Information: Number of customers that would have been affected without SGDP/RDSI DA technology Instance 5	#	0		
Major Event Information	Major Event Information: Total restoration time	hours	0		
Major Event Information	Major Event Information: Total restoration time Instance 2	hours	0		
Major Event Information	Major Event Information: Total restoration time Instance 3	hours	0		
Major Event Information	Major Event Information: Total restoration time Instance 4	hours	0		
Major Event Information	Major Event Information: Total restoration time Instance 5	hours	0		
Major Event Information	Major Event Information: Total restoration time without SGDP/RDSI DA technology	hours	0		
Major Event Information	Major Event Information: Total restoration time without SGDP/RDSI DA technology Instance 2	hours	0		
Major Event Information	Major Event Information: Total restoration time without SGDP/RDSI DA technology Instance 3	hours	0		
Major Event Information	Major Event Information: Total restoration time without SGDP/RDSI DA technology Instance 4	hours	0		
Major Event Information	Major Event Information: Total restoration time without SGDP/RDSI DA technology Instance 5	hours	0		
Major Event Information	Major Event Information: Other information	Text	N/A		
Major Event Information	Major Event Information: Other information Instance 2	Text	N/A		
Major Event Information	Major Event Information: Other information Instance 3	Text	N/A		
Major Event Information	Major Event Information: Other information Instance 4	Text	N/A		
Major Event Information	Major Event Information: Other information Instance 5	Text	N/A		
Distribution Operations Vehicle Miles	Avoided Distribution Operations Vehicle Miles (mirror)	miles	0		
CO2 Emissions	Avoided CO2 Emissions: Distribution, Vehicle (mirror)	tons	0		
CO2 Emissions	Avoided CO2 Emissions: Distribution, Reduced Losses or Reduction in Load (mirror)	tons	0		
Custom Metrics					
Metric Name		Units	Project Value	System Value	Comments
END	END	END			

Project Name		KCP&L Green Impact Zone Smart Grid Demonstration			PLEASE DO NOT UNPROTECT THE SHEET FOR ANY REASON. IF THERE IS AN ISSUE WITH THE TEMPLATE PLEASE:				
Project ID		DE-0E000221							
Metric	Metric Qualifier	Unit	2011 SUMMER	2011 WINTER	2012 SUMMER	2012 WINTER	2013 SUMMER	2013 WINTER	2014 SUMMER
Distribution feeder or equipment overload incidents	Feeder Line: Number of Incidents	#					0		
Distribution feeder or equipment overload incidents	Substation Transformer: Number of Incidents	#					0		
Distribution feeder or equipment overload incidents	Feeder Line: Average duration of incident	minutes					0		
Distribution feeder or equipment overload incidents	Substation Transformer: Average duration of incident	minutes					0		
Distribution feeder load	Aggregated Average Real Load	MW					0		
Distribution feeder load	Aggregated Average Reactive Load	MVAR					0		
Deferred Distribution Capacity Investment	Total Capital Cost	\$					0		
Deferred Distribution Capacity Investment	Total Capital Cost Instance 2	\$					0		
Deferred Distribution Capacity Investment	Total Capital Cost Instance 3	\$					0		
Deferred Distribution Capacity Investment	Total Capital Cost Instance 4	\$					0		
Deferred Distribution Capacity Investment	Total Capital Cost Instance 5	\$					0		
Deferred Distribution Capacity Investment	Amount of Time Deferred	years					0		
Deferred Distribution Capacity Investment	Amount of Time Deferred Instance 2	years					0		
Deferred Distribution Capacity Investment	Amount of Time Deferred Instance 3	years					0		
Deferred Distribution Capacity Investment	Amount of Time Deferred Instance 4	years					0		
Deferred Distribution Capacity Investment	Amount of Time Deferred Instance 5	years					0		
Deferred Distribution Capacity Investment	Description of Deferral	Text					N/A		
Deferred Distribution Capacity Investment	Description of Deferral Instance 2	Text					N/A		
Deferred Distribution Capacity Investment	Description of Deferral Instance 3	Text					N/A		
Deferred Distribution Capacity Investment	Description of Deferral Instance 4	Text					N/A		
Deferred Distribution Capacity Investment	Description of Deferral Instance 5	Text					N/A		
Equipment Failure Incidents	Transformers: Number of Failures (Distribution)	#					0		
Equipment Failure Incidents	Feeders: Number of Failures (Distribution)	#					0		
Equipment Failure Incidents	Other Major Distribution Equipment A: Number of Failures	#					0		
Equipment Failure Incidents	Other Major Distribution Equipment B: Number of Failures	#					0		
Equipment Failure Incidents	Other Major Distribution Equipment C: Number of Failures	#					0		
Truck Rolls (Distribution)	Truck Rolls Avoided (Distribution) (mirror)	#					0		
Distribution Operations Vehicle Miles	Avoided Distribution Operations Vehicle Miles (mirror)	miles					0		
CO2 Emissions	Avoided CO2 Emissions: Distribution, Vehicle (mirror)	tons					0		
CO2 Emissions	Avoided CO2 Emissions: Distribution, Reduced Losses or Reduction in Load (mirror)	tons					0		
Custom Metrics									
Metric Name	Units	2011 SUMMER	2011 WINTER	2012 SUMMER	2012 WINTER	2013 SUMMER	2013 WINTER	2014 SUMMER	
END	END	END							

Project Name	KCP&L Green Impact Zone Smart Grid Demonstration
Project ID	DE-OE0000221
Reporting Period	2012 WINTER

PLEASE DO NOT UNPROTECT THE SHEET FOR ANY REASON, IF THERE IS AN ISSUE WITH THE TEM

Metric	Metric Qualifier	Unit	Project Value	System Value	Comments
Annual Storage Dispatch	Total electricity discharged from storage system; repeat for each unique storage system model/design	kWh	0		
Average Energy Storage Efficiency	Roundtrip efficiency of the demonstration storage system; repeat for each unique storage system model/design	%	TBD		

Custom Metrics

Metric Name	Units	Project Value	System Value	Comments
END	END			



T.4 Summer 2013 (2013 Q2 – 2013 Q3)

Project Name KCP&L Green Impact Zone Smart Grid Demonstration Project ID DE-OE0000221 Reporting Period SUMMER 2011		PLEASE DO NOT UNPROTECT THE SHEET FOR ANY REASON. IF THERE IS AN ISSUE WITH THE TEM			
Metric	Metric Qualifier	Unit	Project Value	System Value	Comments
Vehicle Type AMI	What type of vehicle is dispatched (or would have been dispatched) on the majority of the miles (or avoided miles) reported?	Drop Down	Small field truck		
EPA eGRID Region	What geographic subregion is your project located in (see the Geographic Subregion Map for reference)?	Drop Down	SPND - SPP North		
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Residential Usage	8760 data	This will be reported using a separate sheet	This will be reported using a separate sheet	
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Residential Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Commercial Usage	8760 data	This will be reported using a separate sheet	This will be reported using a separate sheet	
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Commercial Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Industrial Usage	8760 data	This will be reported using a separate sheet	This will be reported using a separate sheet	
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Industrial Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Residential Usage	kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Residential Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Commercial Usage	kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Commercial Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Industrial Usage	kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Industrial Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Peak Load and Mix	Peak Load - Total Amount (AMI)	MW	50.3600307		
Peak Load and Mix	Peak Load - Customer Class A (AMI) (Optional)	MW	26.9170366		
Peak Load and Mix	Peak Load - Customer Class A Description (AMI) (Optional)	Text	AMI Meters- Residential		
Peak Load and Mix	Peak Load - Customer Class B (AMI) (Optional)	MW	23.4429941		
Peak Load and Mix	Peak Load - Customer Class B Description (AMI) (Optional)	Text	AMI Meters- Commercial		
Peak Load and Mix	Peak Load - Customer Class C (AMI) (Optional)	MW	N/A		
Peak Load and Mix	Peak Load - Customer Class C Description (AMI) (Optional)	Text	N/A		
Peak Load and Mix	Peak Load - Customer Class D (AMI) (Optional)	MW	N/A		
Peak Load and Mix	Peak Load - Customer Class D Description (AMI) (Optional)	Text	N/A		

Peak Load and Mix	Peak Load - Date and Time (AMI)	Date/Time	8/30/2013 16:00		
Peak Load and Mix	Peak Load Mix - Direct Load Control Available (AMI)	MW	N/A		
Peak Load and Mix	Peak Load Mix - Direct Load Control Dispatched at Peak (Optional) (AMI)	MW	N/A		
Number of Meter Tamper Detections	Number of Meter Tamper Detections: # Identified	#	N/A		
Number of Meter Tamper Detections	Number of Meter Tamper Detections: # Confirmed (Optional)	#	N/A		
Meter Operations Cost	Meter Operations Cost	\$	167090.1		
Truck Rolls	Truck Rolls Avoided (mirror)	#	4139		
Meter Operations Vehicle Miles	Meter Operations Vehicle Miles Avoided (mirror)	miles	66224		Assuming 16 miles round trip per truck roll based on distance from Dotson service center.
SAIFI	SAIFI	Index	2.670661803		
SAIDI	SAIDI	Index	255.4922355		
CAIDI	CAIDI	Index	95.66626341		
SAIDI and SAIFI	Total number of customers served used in SAIDI and SAIFI calculation	#	13433		
CO2 Emissions	Avoided CO2 Emissions: AMI, Vehicle (mirror)	tons	39.38120553		8.92 x 10 ⁻³ metric tons CO2/gallon of gasoline (http://www.epa.gov/cleanenergy/energy-resources/refs.html) Assuming 15 miles/gallon
Pollutant Emissions (SOx, NOx, PM-2.5)	Avoided SOx Emissions: AMI, Vehicle (mirror)	tons	Optional		
Pollutant Emissions (SOx, NOx, PM-2.5)	Avoided NOx Emissions: AMI, Vehicle (mirror)	tons	Optional		
Meter Data Completeness	Meter Data Completeness	%	98.55		
Meters Reporting Daily	Meters Reporting Daily (% of necessary data points reported)	%	98.11		
Custom Metrics					
Metric Name		Units	Project Value	System Value	Comments
END	END	END			

Project Name		KCP&L Green Impact Zone Smart Grid Demonstration		PLEASE DO NOT UNPROTECT THE SHEET FOR ANY REASON. IF THERE IS AN ISSUE WITH THE TEMPLATE PLEASE CONT						
Project ID		DE-GE0000221								
Metric	Metric Qualifier	Unit	2011 SUMMER	2011 WINTER	2012 SUMMER	2012 WINTER	2013 SUMMER	2013 WINTER	2014 SUMMER	
Meter Operations Cost	Meter Operations Cost	\$					50943.54			
Truck Rolls	Truck Rolls Avoided (mirror)	#					0			
Custom Metrics										
Metric Name	Units	2011 SUMMER	2011 WINTER	2012 SUMMER	2012 WINTER	2013 SUMMER	2013 WINTER	2014 SUMMER		
END	END	END								

Project Name	KCP&L Green Impact Zone Smart Grid Demonstration
Project ID	DE-OE000221
Reporting Period	SUMMER 2011

PLEASE DO NOT UNPROTECT THE SHEET FOR ANY REASON, IF THERE IS AN ISSUE WITH THE TEM

Metric	Metric Qualifier	Unit	Project Value	System Value	Comments
Vehicle Type Distribution	What type of vehicle is dispatched (or would have been dispatched) on the majority of the miles (or avoided miles) reported?	Drop Down	Bucket Truck		
EPA eGRID Region	What geographic subregion is your project located in (see the Geographic Subregion Map for reference)?	Drop Down	SPND - SPP North		
Distribution feeder or equipment overload incidents	Feeder Line: Number of Incidents	#	0		
Distribution feeder or equipment overload incidents	Substation Transformer: Number of Incidents	#	0		
Distribution feeder or equipment overload incidents	Feeder Line: Average duration of incident	minutes	0		
Distribution feeder or equipment overload incidents	Substation Transformer: Average duration of incident	minutes	0		
Distribution feeder load	Aggregated Average Real Load	MW	Optional		
Distribution feeder load	Aggregated Average Reactive Load	MVAR	Optional		
Distribution feeder load	Hourly Load Curves (Real Load)	MW	This will be reported using a separate sheet	This will be reported using a separate sheet	
Distribution feeder load	Hourly Load Curves (Reactive Load)	MVAR	This will be reported using a separate sheet	This will be reported using a separate sheet	
Deferred Distribution Capacity Investment	Total Capital Cost	\$	N/A		
Deferred Distribution Capacity Investment	Total Capital Cost Instance 2	\$	N/A		
Deferred Distribution Capacity Investment	Total Capital Cost Instance 3	\$	N/A		
Deferred Distribution Capacity Investment	Total Capital Cost Instance 4	\$	N/A		
Deferred Distribution Capacity Investment	Total Capital Cost Instance 5	\$	N/A		
Deferred Distribution Capacity Investment	Amount of Time Deferred	years	N/A		
Deferred Distribution Capacity Investment	Amount of Time Deferred Instance 2	years	N/A		
Deferred Distribution Capacity Investment	Amount of Time Deferred Instance 3	years	N/A		
Deferred Distribution Capacity Investment	Amount of Time Deferred Instance 4	years	N/A		
Deferred Distribution Capacity Investment	Amount of Time Deferred Instance 5	years	N/A		
Deferred Distribution Capacity Investment	Description of Deferral	Text	N/A		
Deferred Distribution Capacity Investment	Description of Deferral Instance 2	Text	N/A		
Deferred Distribution Capacity Investment	Description of Deferral Instance 3	Text	N/A		
Deferred Distribution Capacity Investment	Description of Deferral Instance 4	Text	N/A		
Deferred Distribution Capacity Investment	Description of Deferral Instance 5	Text	N/A		
Equipment Failure Incidents	Transformers: Number of Failures (Distribution)	#	0		
Equipment Failure Incidents	Feeders: Number of Failures (Distribution)	#	12		Cables & OH Wires
Equipment Failure Incidents	Other Major Distribution Equipment A: Number of Failures	#	1		Switch
Equipment Failure Incidents	Other Major Distribution Equipment B: Number of Failures	#	N/A		
Equipment Failure Incidents	Other Major Distribution Equipment C: Number of Failures	#	N/A		
Equipment Failure Incidents	Other Major Distribution Equipment A: Description	Text	Switch		
Equipment Failure Incidents	Other Major Distribution Equipment B: Description	Text	N/A		
Equipment Failure Incidents	Other Major Distribution Equipment C: Description	Text	N/A		
Equipment Failure Incidents	Transformers: Reasons for Failures (Distribution)	Text	N/A		
Equipment Failure Incidents	Feeders: Reasons for Failures (Distribution)	Text	Failure Wear		

Equipment Failure Incidents	Other Major Distribution Equipment A: Reasons for Failures	Text	Failure Wear	
Equipment Failure Incidents	Other Major Distribution Equipment B: Reasons for Failures	Text	N/A	
Equipment Failure Incidents	Other Major Distribution Equipment C: Reasons for Failures	Text	N/A	
Distribution losses	Avoided distribution losses: Total Cumulative MWh of Avoided Losses (mirror)	MWh	0	
Truck Rolls (Distribution)	Truck Rolls Avoided (Distribution) (mirror)	#	0	
SAIFI	SAIFI	Index	2.670661803	
SAIDI	SAIDI	Index	255.4922355	
CAIDI	CAIDI	Index	95.66626341	
SAIDI and SAIFI	Total number of customers served used in SAIDI and SAIFI calculation	#	13433	
Major Event Information	Major Event Information: Infrastructure involved	Text	N/A	
Major Event Information	Major Event Information: Infrastructure involved Instance 2	Text	N/A	
Major Event Information	Major Event Information: Infrastructure involved Instance 3	Text	N/A	
Major Event Information	Major Event Information: Infrastructure involved Instance 4	Text	N/A	
Major Event Information	Major Event Information: Infrastructure involved Instance 5	Text	N/A	
Major Event Information	Major Event Information: Cause of the event	Text	N/A	
Major Event Information	Major Event Information: Cause of the event Instance 2	Text	N/A	
Major Event Information	Major Event Information: Cause of the event Instance 3	Text	N/A	
Major Event Information	Major Event Information: Cause of the event Instance 4	Text	N/A	
Major Event Information	Major Event Information: Cause of the event Instance 5	Text	N/A	
Major Event Information	Major Event Information: Number of customers affected	#	0	
Major Event Information	Major Event Information: Number of customers affected Instance 2	#	0	
Major Event Information	Major Event Information: Number of customers affected Instance 3	#	0	
Major Event Information	Major Event Information: Number of customers affected Instance 4	#	0	
Major Event Information	Major Event Information: Number of customers affected Instance 5	#	0	
Major Event Information	Major Event Information: Number of customers that would have been affected without SGDP/RDSI DA technology	#	0	
Major Event Information	Major Event Information: Number of customers that would have been affected without SGDP/RDSI DA technology Instance 2	#	0	

Major Event Information	Major Event Information: Number of customers that would have been affected without SGDP/RDSI DA technology Instance 3	#	0		
Major Event Information	Major Event Information: Number of customers that would have been affected without SGDP/RDSI DA technology Instance 4	#	0		
Major Event Information	Major Event Information: Number of customers that would have been affected without SGDP/RDSI DA technology Instance 5	#	0		
Major Event Information	Major Event Information: Total restoration time	hours	0		
Major Event Information	Major Event Information: Total restoration time Instance 2	hours	0		
Major Event Information	Major Event Information: Total restoration time Instance 3	hours	0		
Major Event Information	Major Event Information: Total restoration time Instance 4	hours	0		
Major Event Information	Major Event Information: Total restoration time Instance 5	hours	0		
Major Event Information	Major Event Information: Total restoration time without SGDP/RDSI DA technology	hours	0		
Major Event Information	Major Event Information: Total restoration time without SGDP/RDSI DA technology Instance 2	hours	0		
Major Event Information	Major Event Information: Total restoration time without SGDP/RDSI DA technology Instance 3	hours	0		
Major Event Information	Major Event Information: Total restoration time without SGDP/RDSI DA technology Instance 4	hours	0		
Major Event Information	Major Event Information: Total restoration time without SGDP/RDSI DA technology Instance 5	hours	0		
Major Event Information	Major Event Information: Other information	Text	N/A		
Major Event Information	Major Event Information: Other information Instance 2	Text	N/A		
Major Event Information	Major Event Information: Other information Instance 3	Text	N/A		
Major Event Information	Major Event Information: Other information Instance 4	Text	N/A		
Major Event Information	Major Event Information: Other information Instance 5	Text	N/A		
Distribution Operations Vehicle Miles	Avoided Distribution Operations Vehicle Miles (mirror)	miles	0		
CO2 Emissions	Avoided CO2 Emissions: Distribution, Vehicle (mirror)	tons	Optional		
CO2 Emissions	Avoided CO2 Emissions: Distribution, Reduced Losses or Reduction in Load (mirror)	tons	Optional		
Custom Metrics					
Metric Name		Units	Project Value	System Value	Comments
END	END	END			

Project Name		KCP&L Green Impact Zone Smart Grid Demonstration			PLEASE DO NOT UNPROTECT THE SHEET FOR ANY REASON. IF THERE IS AN ISSUE WITH THE TEMPLATE PLEASE:				
Project ID		DE-0E000221							
Metric	Metric Qualifier	Unit	2011 SUMMER	2011 WINTER	2012 SUMMER	2012 WINTER	2013 SUMMER	2013 WINTER	2014 SUMMER
Distribution feeder or equipment overload incidents	Feeder Line: Number of Incidents	#							0
Distribution feeder or equipment overload incidents	Substation Transformer: Number of Incidents	#							0
Distribution feeder or equipment overload incidents	Feeder Line: Average duration of incident	minutes							0
Distribution feeder or equipment overload incidents	Substation Transformer: Average duration of incident	minutes							0
Distribution feeder load	Aggregated Average Real Load	MW							0
Distribution feeder load	Aggregated Average Reactive Load	MVAR							0
Deferred Distribution Capacity Investment	Total Capital Cost	\$							0
Deferred Distribution Capacity Investment	Total Capital Cost Instance 2	\$							0
Deferred Distribution Capacity Investment	Total Capital Cost Instance 3	\$							0
Deferred Distribution Capacity Investment	Total Capital Cost Instance 4	\$							0
Deferred Distribution Capacity Investment	Total Capital Cost Instance 5	\$							0
Deferred Distribution Capacity Investment	Amount of Time Deferred	years							0
Deferred Distribution Capacity Investment	Amount of Time Deferred Instance 2	years							0
Deferred Distribution Capacity Investment	Amount of Time Deferred Instance 3	years							0
Deferred Distribution Capacity Investment	Amount of Time Deferred Instance 4	years							0
Deferred Distribution Capacity Investment	Amount of Time Deferred Instance 5	years							0
Deferred Distribution Capacity Investment	Description of Deferral	Text						N/A	
Deferred Distribution Capacity Investment	Description of Deferral Instance 2	Text						N/A	
Deferred Distribution Capacity Investment	Description of Deferral Instance 3	Text						N/A	
Deferred Distribution Capacity Investment	Description of Deferral Instance 4	Text						N/A	
Deferred Distribution Capacity Investment	Description of Deferral Instance 5	Text						N/A	
Equipment Failure Incidents	Transformers: Number of Failures (Distribution)	#							0
Equipment Failure Incidents	Feeders: Number of Failures (Distribution)	#							0
Equipment Failure Incidents	Other Major Distribution Equipment A: Number of Failures	#							0
Equipment Failure Incidents	Other Major Distribution Equipment B: Number of Failures	#							0
Equipment Failure Incidents	Other Major Distribution Equipment C: Number of Failures	#							0
Truck Rolls (Distribution)	Truck Rolls Avoided (Distribution) (mirror)	#							0
Distribution Operations Vehicle Miles	Avoided Distribution Operations Vehicle Miles (mirror)	miles							0
CO2 Emissions	Avoided CO2 Emissions: Distribution, Vehicle (mirror)	tons							0
CO2 Emissions	Avoided CO2 Emissions: Distribution, Reduced Losses or Reduction in Load (mirror)	tons							0
Custom Metrics									
Metric Name	Units	2011 SUMMER	2011 WINTER	2012 SUMMER	2012 WINTER	2013 SUMMER	2013 WINTER	2014 SUMMER	
END	END	END							



Project Name	KCP&L Green Impact Zone Smart Grid Demonstration
Project ID	DE-OE0000221
Reporting Period	2013 SUMMER

PLEASE DO NOT UNPROTECT THE SHEET FOR ANY REASON. IF THERE IS AN ISSUE WITH THE TEM

Metric	Metric Qualifier	Unit	Project Value	System Value	Comments
Annual Storage Dispatch	Total electricity discharged from storage system; repeat for each unique storage system model/design	kWh	12,760		
Average Energy Storage Efficiency	Roundtrip efficiency of the demonstration storage system; repeat for each unique storage system model/design	%	29.04		

Custom Metrics

Metric Name	Units	Project Value	System Value	Comments
END	END			

T.5 Winter 2013 (2013 Q4 – 2014 Q1)

Project Name KCP&L Green Impact Zone Smart Grid Demonstration Project ID DE-OE0000221 Reporting Period SUMMER 2011		PLEASE DO NOT UNPROTECT THE SHEET FOR ANY REASON. IF THERE IS AN ISSUE WITH THE TEM			
Metric	Metric Qualifier	Unit	Project Value	System Value	Comments
Vehicle Type AMI	What type of vehicle is dispatched (or would have been dispatched) on the majority of the miles (or avoided miles) reported?	Drop Down	Small field truck		
EPA eGRID Region	What geographic subregion is your project located in (see the Geographic Subregion Map for reference)?	Drop Down	SPND - SPP North		
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Residential Usage	8760 data	This will be reported using a separate sheet	This will be reported using a separate sheet	
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Residential Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Commercial Usage	8760 data	This will be reported using a separate sheet	This will be reported using a separate sheet	
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Commercial Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Industrial Usage	8760 data	This will be reported using a separate sheet	This will be reported using a separate sheet	
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Industrial Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Residential Usage	kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Residential Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Commercial Usage	kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Commercial Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Industrial Usage	kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Industrial Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Peak Load and Mix	Peak Load - Total Amount (AMI)	MW	45,2065747		
Peak Load and Mix	Peak Load - Customer Class A (AMI) (Optional)	MW	25.9730479		
Peak Load and Mix	Peak Load - Customer Class A Description (AMI) (Optional)	Text	AMI Meters - Residential		
Peak Load and Mix	Peak Load - Customer Class B (AMI) (Optional)	MW	19.2335268		
Peak Load and Mix	Peak Load - Customer Class B Description (AMI) (Optional)	Text	AMI Meters - Commercial		
Peak Load and Mix	Peak Load - Customer Class C (AMI) (Optional)	MW	N/A		
Peak Load and Mix	Peak Load - Customer Class C Description (AMI) (Optional)	Text	N/A		
Peak Load and Mix	Peak Load - Customer Class D (AMI) (Optional)	MW	N/A		
Peak Load and Mix	Peak Load - Customer Class D Description (AMI) (Optional)	Text	N/A		

Peak Load and Mix	Peak Load - Date and Time (AMI)	Date/Time	1/6/2014 18:00		
Peak Load and Mix	Peak Load Mix - Direct Load Control Available (AMI)	MW	Optional		
Peak Load and Mix	Peak Load Mix - Direct Load Control Dispatched at Peak (Optional) (AMI)	MW	Optional		
Number of Meter Tamper Detections	Number of Meter Tamper Detections: # Identified	#	N/A		
Number of Meter Tamper Detections	Number of Meter Tamper Detections: # Confirmed (Optional)	#	N/A		
Meter Operations Cost	Meter Operations Cost	\$	167090.1		
Truck Rolls	Truck Rolls Avoided (mirror)	#	3366		
Meter Operations Vehicle Miles	Meter Operations Vehicle Miles Avoided (mirror)	miles	53856		Assuming 16 miles round trip per truck roll based on distance from Dotson service center.
SAIFI	SAIFI	Index	1.153726478		
SAIDI	SAIDI	Index	75.26078182		
CAIDI	CAIDI	Index	65.23277679		
SAIDI and SAIFI	Total number of customers served used in SAIDI and SAIFI calculation	#	13498		
CO2 Emissions	Avoided CO2 Emissions: AMI, Vehicle (mirror)	tons	32.026368		8.92 x 10 ⁻³ metric tons CO2/gallon of gasoline (http://www.epa.gov/cleanenergy/energy-resources/refs.html) Assuming 15 miles/gallon
Pollutant Emissions (SOx, NOx, PM-2.5)	Avoided SOx Emissions: AMI, Vehicle (mirror)	tons	Optional		
Pollutant Emissions (SOx, NOx, PM-2.5)	Avoided NOx Emissions: AMI, Vehicle (mirror)	tons	Optional		
Meter Data Completeness	Meter Data Completeness	%	99.01		
Meters Reporting Daily	Meters Reporting Daily (% of necessary data points reported)	%	99.14		
Custom Metrics					
Metric Name		Units	Project Value	System Value	Comments
END	END	END			

Project Name		KCP&L Green Impact Zone Smart Grid Demonstration		PLEASE DO NOT UNPROTECT THE SHEET FOR ANY REASON. IF THERE IS AN ISSUE WITH THE TEMPLATE PLEASE CONT						
Project ID		DE-GE0000221								
Metric	Metric Qualifier	Unit	2011 SUMMER	2011 WINTER	2012 SUMMER	2012 WINTER	2013 SUMMER	2013 WINTER	2014 SUMMER	
Meter Operations Cost	Meter Operations Cost	\$							50943.54	
Truck Rolls	Truck Rolls Avoided (mirror)	#							0	
Custom Metrics										
Metric Name	Units	2011 SUMMER	2011 WINTER	2012 SUMMER	2012 WINTER	2013 SUMMER	2013 WINTER	2014 SUMMER		
END	END	END								

Project Name	KCP&L Green Impact Zone Smart Grid Demonstration
Project ID	DE-OE000221
Reporting Period	SUMMER 2011

PLEASE DO NOT UNPROTECT THE SHEET FOR ANY REASON, IF THERE IS AN ISSUE WITH THE TEM

Metric	Metric Qualifier	Unit	Project Value	System Value	Comments
Vehicle Type Distribution	What type of vehicle is dispatched (or would have been dispatched) on the majority of the miles (or avoided miles) reported?	Drop Down	Bucket Truck		
EPA eGRID Region	What geographic subregion is your project located in (see the Geographic Subregion Map for reference)?	Drop Down	SPNO - SPP North		
Distribution feeder or equipment overload incidents	Feeder Line: Number of Incidents	#	0		
Distribution feeder or equipment overload incidents	Substation Transformer: Number of Incidents	#	0		
Distribution feeder or equipment overload incidents	Feeder Line: Average duration of incident	minutes	0		
Distribution feeder or equipment overload incidents	Substation Transformer: Average duration of incident	minutes	0		
Distribution feeder load	Aggregated Average Real Load	MW	Optional		
Distribution feeder load	Aggregated Average Reactive Load	MVAR	Optional		
Distribution feeder load	Hourly Load Curves (Real Load)	MW	This will be reported using a separate sheet	This will be reported using a separate sheet	
Distribution feeder load	Hourly Load Curves (Reactive Load)	MVAR	This will be reported using a separate sheet	This will be reported using a separate sheet	
Deferred Distribution Capacity Investment	Total Capital Cost	\$	N/A		
Deferred Distribution Capacity Investment	Total Capital Cost Instance 2	\$	N/A		
Deferred Distribution Capacity Investment	Total Capital Cost Instance 3	\$	N/A		
Deferred Distribution Capacity Investment	Total Capital Cost Instance 4	\$	N/A		
Deferred Distribution Capacity Investment	Total Capital Cost Instance 5	\$	N/A		
Deferred Distribution Capacity Investment	Amount of Time Deferred	years	N/A		
Deferred Distribution Capacity Investment	Amount of Time Deferred Instance 2	years	N/A		
Deferred Distribution Capacity Investment	Amount of Time Deferred Instance 3	years	N/A		
Deferred Distribution Capacity Investment	Amount of Time Deferred Instance 4	years	N/A		
Deferred Distribution Capacity Investment	Amount of Time Deferred Instance 5	years	N/A		
Deferred Distribution Capacity Investment	Description of Deferral	Text	N/A		
Deferred Distribution Capacity Investment	Description of Deferral Instance 2	Text	N/A		
Deferred Distribution Capacity Investment	Description of Deferral Instance 3	Text	N/A		
Deferred Distribution Capacity Investment	Description of Deferral Instance 4	Text	N/A		
Deferred Distribution Capacity Investment	Description of Deferral Instance 5	Text	N/A		
Equipment Failure Incidents	Transformers: Number of Failures (Distribution)	#	1		
Equipment Failure Incidents	Feeders: Number of Failures (Distribution)	#	1		OH Wire
Equipment Failure Incidents	Other Major Distribution Equipment A: Number of Failures	#	N/A		
Equipment Failure Incidents	Other Major Distribution Equipment B: Number of Failures	#	N/A		
Equipment Failure Incidents	Other Major Distribution Equipment C: Number of Failures	#	N/A		
Equipment Failure Incidents	Other Major Distribution Equipment A: Description	Text	N/A		
Equipment Failure Incidents	Other Major Distribution Equipment B: Description	Text	N/A		
Equipment Failure Incidents	Other Major Distribution Equipment C: Description	Text	N/A		
Equipment Failure Incidents	Transformers: Reasons for Failures (Distribution)	Text	Failure Wear		
Equipment Failure Incidents	Feeders: Reasons for Failures (Distribution)	Text	Failure Wear		

Equipment Failure Incidents	Other Major Distribution Equipment A: Reasons for Failures	Text	N/A	
Equipment Failure Incidents	Other Major Distribution Equipment B: Reasons for Failures	Text	N/A	
Equipment Failure Incidents	Other Major Distribution Equipment C: Reasons for Failures	Text	N/A	
Distribution losses	Avoided distribution losses: Total Cumulative MWh of Avoided Losses (mirror)	MWh	0	
Truck Rolls (Distribution)	Truck Rolls Avoided (Distribution) (mirror)	#	0	
SAIFI	SAIFI	Index	1.153726478	
SAIDI	SAIDI	Index	75.26078182	
CAIDI	CAIDI	Index	65.23277679	
SAIDI and SAIFI	Total number of customers served used in SAIDI and SAIFI calculation	#	13498	
Major Event Information	Major Event Information: Infrastructure involved	Text	N/A	
Major Event Information	Major Event Information: Infrastructure involved Instance 2	Text	N/A	
Major Event Information	Major Event Information: Infrastructure involved Instance 3	Text	N/A	
Major Event Information	Major Event Information: Infrastructure involved Instance 4	Text	N/A	
Major Event Information	Major Event Information: Infrastructure involved Instance 5	Text	N/A	
Major Event Information	Major Event Information: Cause of the event	Text	N/A	
Major Event Information	Major Event Information: Cause of the event Instance 2	Text	N/A	
Major Event Information	Major Event Information: Cause of the event Instance 3	Text	N/A	
Major Event Information	Major Event Information: Cause of the event Instance 4	Text	N/A	
Major Event Information	Major Event Information: Cause of the event Instance 5	Text	N/A	
Major Event Information	Major Event Information: Number of customers affected	#	0	
Major Event Information	Major Event Information: Number of customers affected Instance 2	#	0	
Major Event Information	Major Event Information: Number of customers affected Instance 3	#	0	
Major Event Information	Major Event Information: Number of customers affected Instance 4	#	0	
Major Event Information	Major Event Information: Number of customers affected Instance 5	#	0	
Major Event Information	Major Event Information: Number of customers that would have been affected without SGDP/RDSI DA technology	#	0	
Major Event Information	Major Event Information: Number of customers that would have been affected without SGDP/RDSI DA technology Instance 2	#	0	

Major Event Information	Major Event Information: Number of customers that would have been affected without SGDP/RDSI DA technology Instance 3	#	0		
Major Event Information	Major Event Information: Number of customers that would have been affected without SGDP/RDSI DA technology Instance 4	#	0		
Major Event Information	Major Event Information: Number of customers that would have been affected without SGDP/RDSI DA technology Instance 5	#	0		
Major Event Information	Major Event Information: Total restoration time	hours	0		
Major Event Information	Major Event Information: Total restoration time Instance 2	hours	0		
Major Event Information	Major Event Information: Total restoration time Instance 3	hours	0		
Major Event Information	Major Event Information: Total restoration time Instance 4	hours	0		
Major Event Information	Major Event Information: Total restoration time Instance 5	hours	0		
Major Event Information	Major Event Information: Total restoration time without SGDP/RDSI DA technology	hours	0		
Major Event Information	Major Event Information: Total restoration time without SGDP/RDSI DA technology Instance 2	hours	0		
Major Event Information	Major Event Information: Total restoration time without SGDP/RDSI DA technology Instance 3	hours	0		
Major Event Information	Major Event Information: Total restoration time without SGDP/RDSI DA technology Instance 4	hours	0		
Major Event Information	Major Event Information: Total restoration time without SGDP/RDSI DA technology Instance 5	hours	0		
Major Event Information	Major Event Information: Other information	Text	N/A		
Major Event Information	Major Event Information: Other information Instance 2	Text	N/A		
Major Event Information	Major Event Information: Other information Instance 3	Text	N/A		
Major Event Information	Major Event Information: Other information Instance 4	Text	N/A		
Major Event Information	Major Event Information: Other information Instance 5	Text	N/A		
Distribution Operations Vehicle Miles	Avoided Distribution Operations Vehicle Miles (mirror)	miles	0		
CO2 Emissions	Avoided CO2 Emissions: Distribution, Vehicle (mirror)	tons	Optional		
CO2 Emissions	Avoided CO2 Emissions: Distribution, Reduced Losses or Reduction in Load (mirror)	tons	Optional		
Custom Metrics					
Metric Name		Units	Project Value	System Value	Comments
END	END	END			

Project Name		KCP&L Green Impact Zone Smart Grid Demonstration			PLEASE DO NOT UNPROTECT THE SHEET FOR ANY REASON. IF THERE IS AN ISSUE WITH THE TEMPLATE PLEASE:				
Project ID		DE-0E000221							
Metric	Metric Qualifier	Unit	2011 SUMMER	2011 WINTER	2012 SUMMER	2012 WINTER	2013 SUMMER	2013 WINTER	2014 SUMMER
Distribution feeder or equipment overload incidents	Feeder Line: Number of Incidents	#							0
Distribution feeder or equipment overload incidents	Substation Transformer: Number of Incidents	#							0
Distribution feeder or equipment overload incidents	Feeder Line: Average duration of incident	minutes							0
Distribution feeder or equipment overload incidents	Substation Transformer: Average duration of incident	minutes							0
Distribution feeder load	Aggregated Average Real Load	MW							0
Distribution feeder load	Aggregated Average Reactive Load	MVAR							0
Deferred Distribution Capacity Investment	Total Capital Cost	\$							0
Deferred Distribution Capacity Investment	Total Capital Cost Instance 2	\$							0
Deferred Distribution Capacity Investment	Total Capital Cost Instance 3	\$							0
Deferred Distribution Capacity Investment	Total Capital Cost Instance 4	\$							0
Deferred Distribution Capacity Investment	Total Capital Cost Instance 5	\$							0
Deferred Distribution Capacity Investment	Amount of Time Deferred	years							0
Deferred Distribution Capacity Investment	Amount of Time Deferred Instance 2	years							0
Deferred Distribution Capacity Investment	Amount of Time Deferred Instance 3	years							0
Deferred Distribution Capacity Investment	Amount of Time Deferred Instance 4	years							0
Deferred Distribution Capacity Investment	Amount of Time Deferred Instance 5	years							0
Deferred Distribution Capacity Investment	Description of Deferral	Text						N/A	
Deferred Distribution Capacity Investment	Description of Deferral Instance 2	Text						N/A	
Deferred Distribution Capacity Investment	Description of Deferral Instance 3	Text						N/A	
Deferred Distribution Capacity Investment	Description of Deferral Instance 4	Text						N/A	
Deferred Distribution Capacity Investment	Description of Deferral Instance 5	Text						N/A	
Equipment Failure Incidents	Transformers: Number of Failures (Distribution)	#							0
Equipment Failure Incidents	Feeders: Number of Failures (Distribution)	#							0
Equipment Failure Incidents	Other Major Distribution Equipment A: Number of Failures	#							0
Equipment Failure Incidents	Other Major Distribution Equipment B: Number of Failures	#							0
Equipment Failure Incidents	Other Major Distribution Equipment C: Number of Failures	#							0
Truck Rolls (Distribution)	Truck Rolls Avoided (Distribution) (mirror)	#							0
Distribution Operations Vehicle Miles	Avoided Distribution Operations Vehicle Miles (mirror)	miles							0
CO2 Emissions	Avoided CO2 Emissions: Distribution, Vehicle (mirror)	tons							0
CO2 Emissions	Avoided CO2 Emissions: Distribution, Reduced Losses or Reduction in Load (mirror)	tons							0
Custom Metrics									
Metric Name	Units	2011 SUMMER	2011 WINTER	2012 SUMMER	2012 WINTER	2013 SUMMER	2013 WINTER	2014 SUMMER	
END	END	END							

Project Name	KCP&L Green Impact Zone Smart Grid Demonstration
Project ID	DE-OE0000221
Reporting Period	2013 WINTER

PLEASE DO NOT UNPROTECT THE SHEET FOR ANY REASON. IF THERE IS AN ISSUE WITH THE TEMPLATE, PLEASE CONTACT THE PROJECT MANAGER.

Metric	Metric Qualifier	Unit	Project Value	System Value	Comments
Annual Storage Dispatch	Total electricity discharged from storage system; repeat for each unique storage system model/design	kWh	47686		
Average Energy Storage Efficiency	Roundtrip efficiency of the demonstration storage system; repeat for each unique storage system model/design	%	53.98		

Custom Metrics

Metric Name	Units	Project Value	System Value	Comments
END	END			

T.6 Summer 2014 (2014 Q2 – 2014 Q3)

Project Name KCP&L Green Impact Zone Smart Grid Demonstration Project ID DE-OE0000221 Reporting Period SUMMER 2011		PLEASE DO NOT UNPROTECT THE SHEET FOR ANY REASON. IF THERE IS AN ISSUE WITH THE TEM			
Metric	Metric Qualifier	Unit	Project Value	System Value	Comments
Vehicle Type AMI	What type of vehicle is dispatched (or would have been dispatched) on the majority of the miles (or avoided miles) reported?	Drop Down	Small field truck		
EPA eGRID Region	What geographic subregion is your project located in (see the Geographic Subregion Map for reference)?	Drop Down	SPND - SPP North		
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Residential Usage	8760 data	This will be reported using a separate sheet	This will be reported using a separate sheet	
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Residential Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Commercial Usage	8760 data	This will be reported using a separate sheet	This will be reported using a separate sheet	
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Commercial Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Industrial Usage	8760 data	This will be reported using a separate sheet	This will be reported using a separate sheet	
Hourly Customer Electricity Usage	Hourly Customer Electricity Usage: Industrial Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Residential Usage	kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Residential Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Commercial Usage	kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Commercial Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Industrial Usage	kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Monthly Customer Electricity Usage	Monthly Customer Electricity Usage - Industrial Rate	\$/kWh	This will be reported using a separate sheet	This will be reported using a separate sheet	
Peak Load and Mix	Peak Load - Total Amount (AMI)	MW	49.4753562		
Peak Load and Mix	Peak Load - Customer Class A (AMI) (Optional)	MW	26.9865111		
Peak Load and Mix	Peak Load - Customer Class A Description (AMI) (Optional)	Text	AMI Meters - Residential		
Peak Load and Mix	Peak Load - Customer Class B (AMI) (Optional)	MW	22.488451		
Peak Load and Mix	Peak Load - Customer Class B Description (AMI) (Optional)	Text	AMI Meters - Commercial		
Peak Load and Mix	Peak Load - Customer Class C (AMI) (Optional)	MW	N/A		
Peak Load and Mix	Peak Load - Customer Class C Description (AMI) (Optional)	Text	N/A		
Peak Load and Mix	Peak Load - Customer Class D (AMI) (Optional)	MW	N/A		
Peak Load and Mix	Peak Load - Customer Class D Description (AMI) (Optional)	Text	N/A		

Peak Load and Mix	Peak Load - Date and Time (AMI)	Date/Time	8/25/2014 17:00		
Peak Load and Mix	Peak Load Mix - Direct Load Control Available (AMI)	MW	Optional		
Peak Load and Mix	Peak Load Mix - Direct Load Control Dispatched at Peak (Optional) (AMI)	MW	Optional		
Number of Meter Tamper Detections	Number of Meter Tamper Detections: # Identified	#	N/A		
Number of Meter Tamper Detections	Number of Meter Tamper Detections: # Confirmed (Optional)	#	N/A		
Meter Operations Cost	Meter Operations Cost	\$	167090.1		
Truck Rolls	Truck Rolls Avoided (mirror)	#	4043		
Meter Operations Vehicle Miles	Meter Operations Vehicle Miles Avoided (mirror)	miles	64688		Assuming 16 miles round trip per truck roll based on distance from Dotson service center.
SAIFI	SAIFI	Index	2.331273		
SAIDI	SAIDI	Index	235.4554		
CAIDI	CAIDI	Index	100.9986		
SAIDI and SAIFI	Total number of customers served used in SAIDI and SAIFI calculation	#	13427		
CO2 Emissions	Avoided CO2 Emissions: AMI, Vehicle (mirror)	tons	38.46779733		8.92 x 10 ⁻³ metric tons CO2/gallon of gasoline (http://www.epa.gov/cleanenergy/energy-resources/refs.html) Assuming 15 miles/gallon
Pollutant Emissions (SOx, NOx, PM-2.5)	Avoided SOx Emissions: AMI, Vehicle (mirror)	tons	Optional		
Pollutant Emissions (SOx, NOx, PM-2.5)	Avoided NOx Emissions: AMI, Vehicle (mirror)	tons	Optional		
Meter Data Completeness	Meter Data Completeness	%	99.27		
Meters Reporting Daily	Meters Reporting Daily (% of necessary data points reported)	%	99.22		
Custom Metrics					
Metric Name		Units	Project Value	System Value	Comments
END	END	END			

Project Name		KCP&L Green Impact Zone Smart Grid Demonstration		PLEASE DO NOT UNPROTECT THE SHEET FOR ANY REASON. IF THERE IS AN ISSUE WITH THE TEMPLATE PLEASE CONT							
Project ID		DE-GE0000221									
Metric	Metric Qualifier	Unit	2011 SUMMER	2011 WINTER	2012 SUMMER	2012 WINTER	2013 SUMMER	2013 WINTER	2014 SUMMER		
Meter Operations Cost	Meter Operations Cost	\$							50943.54		
Truck Rolls	Truck Rolls Avoided (mirror)	#							0		
Custom Metrics											
Metric Name	Units	2011 SUMMER	2011 WINTER	2012 SUMMER	2012 WINTER	2013 SUMMER	2013 WINTER	2014 SUMMER			
END	END	END									

Project Name	KCP&L Green Impact Zone Smart Grid Demonstration
Project ID	DE-OE000221
Reporting Period	SUMMER 2011

PLEASE DO NOT UNPROTECT THE SHEET FOR ANY REASON, IF THERE IS AN ISSUE WITH THE TEM

Metric	Metric Qualifier	Unit	Project Value	System Value	Comments
Vehicle Type Distribution	What type of vehicle is dispatched (or would have been dispatched) on the majority of the miles (or avoided miles) reported?	Drop Down	Bucket Truck		
EPA eGRID Region	What geographic subregion is your project located in (see the Geographic Subregion Map for reference)?	Drop Down	SPNO - SPP North		
Distribution feeder or equipment overload incidents	Feeder Line: Number of Incidents	#	0		
Distribution feeder or equipment overload incidents	Substation Transformer: Number of Incidents	#	0		
Distribution feeder or equipment overload incidents	Feeder Line: Average duration of incident	minutes	0		
Distribution feeder or equipment overload incidents	Substation Transformer: Average duration of incident	minutes	0		
Distribution feeder load	Aggregated Average Real Load	MW	Optional		
Distribution feeder load	Aggregated Average Reactive Load	MVAR	Optional		
Distribution feeder load	Hourly Load Curves (Real Load)	MW	This will be reported using a separate sheet	This will be reported using a separate sheet	
Distribution feeder load	Hourly Load Curves (Reactive Load)	MVAR	This will be reported using a separate sheet	This will be reported using a separate sheet	
Deferred Distribution Capacity Investment	Total Capital Cost	\$	N/A		
Deferred Distribution Capacity Investment	Total Capital Cost Instance 2	\$	N/A		
Deferred Distribution Capacity Investment	Total Capital Cost Instance 3	\$	N/A		
Deferred Distribution Capacity Investment	Total Capital Cost Instance 4	\$	N/A		
Deferred Distribution Capacity Investment	Total Capital Cost Instance 5	\$	N/A		
Deferred Distribution Capacity Investment	Amount of Time Deferred	years	N/A		
Deferred Distribution Capacity Investment	Amount of Time Deferred Instance 2	years	N/A		
Deferred Distribution Capacity Investment	Amount of Time Deferred Instance 3	years	N/A		
Deferred Distribution Capacity Investment	Amount of Time Deferred Instance 4	years	N/A		
Deferred Distribution Capacity Investment	Amount of Time Deferred Instance 5	years	N/A		
Deferred Distribution Capacity Investment	Description of Deferral	Text	N/A		
Deferred Distribution Capacity Investment	Description of Deferral Instance 2	Text	N/A		
Deferred Distribution Capacity Investment	Description of Deferral Instance 3	Text	N/A		
Deferred Distribution Capacity Investment	Description of Deferral Instance 4	Text	N/A		
Deferred Distribution Capacity Investment	Description of Deferral Instance 5	Text	N/A		
Equipment Failure Incidents	Transformers: Number of Failures (Distribution)	#	0		
Equipment Failure Incidents	Feeders: Number of Failures (Distribution)	#	3		Cables
Equipment Failure Incidents	Other Major Distribution Equipment A: Number of Failures	#	N/A		
Equipment Failure Incidents	Other Major Distribution Equipment B: Number of Failures	#	N/A		
Equipment Failure Incidents	Other Major Distribution Equipment C: Number of Failures	#	N/A		
Equipment Failure Incidents	Other Major Distribution Equipment A: Description	Text	N/A		
Equipment Failure Incidents	Other Major Distribution Equipment B: Description	Text	N/A		
Equipment Failure Incidents	Other Major Distribution Equipment C: Description	Text	N/A		
Equipment Failure Incidents	Transformers: Reasons for Failures (Distribution)	Text	N/A		
Equipment Failure Incidents	Feeders: Reasons for Failures (Distribution)	Text	Failure Wear		

Equipment Failure Incidents	Other Major Distribution Equipment A: Reasons for Failures	Text	N/A	
Equipment Failure Incidents	Other Major Distribution Equipment B: Reasons for Failures	Text	N/A	
Equipment Failure Incidents	Other Major Distribution Equipment C: Reasons for Failures	Text	N/A	
Distribution losses	Avoided distribution losses: Total Cumulative MWh of Avoided Losses (mirror)	MWh	N/A	
Truck Rolls (Distribution)	Truck Rolls Avoided (Distribution) (mirror)	#	N/A	
SAIFI	SAIFI	Index	2.331273	
SAIDI	SAIDI	Index	235.4554	
CAIDI	CAIDI	Index	100.9986	
SAIDI and SAIFI	Total number of customers served used in SAIDI and SAIFI calculation	#	13427	
Major Event Information	Major Event Information: Infrastructure involved	Text	N/A	
Major Event Information	Major Event Information: Infrastructure involved Instance 2	Text	N/A	
Major Event Information	Major Event Information: Infrastructure involved Instance 3	Text	N/A	
Major Event Information	Major Event Information: Infrastructure involved Instance 4	Text	N/A	
Major Event Information	Major Event Information: Infrastructure involved Instance 5	Text	N/A	
Major Event Information	Major Event Information: Cause of the event	Text	N/A	
Major Event Information	Major Event Information: Cause of the event Instance 2	Text	N/A	
Major Event Information	Major Event Information: Cause of the event Instance 3	Text	N/A	
Major Event Information	Major Event Information: Cause of the event Instance 4	Text	N/A	
Major Event Information	Major Event Information: Cause of the event Instance 5	Text	N/A	
Major Event Information	Major Event Information: Number of customers affected	#	N/A	
Major Event Information	Major Event Information: Number of customers affected Instance 2	#	N/A	
Major Event Information	Major Event Information: Number of customers affected Instance 3	#	N/A	
Major Event Information	Major Event Information: Number of customers affected Instance 4	#	N/A	
Major Event Information	Major Event Information: Number of customers affected Instance 5	#	N/A	
Major Event Information	Major Event Information: Number of customers that would have been affected without SGDP/RDSI DA technology	#	N/A	
Major Event Information	Major Event Information: Number of customers that would have been affected without SGDP/RDSI DA technology Instance 2	#	N/A	

Major Event Information	Major Event Information: Number of customers that would have been affected without SGDP/RDSI DA technology Instance 3	#	N/A		
Major Event Information	Major Event Information: Number of customers that would have been affected without SGDP/RDSI DA technology Instance 4	#	N/A		
Major Event Information	Major Event Information: Number of customers that would have been affected without SGDP/RDSI DA technology Instance 5	#	N/A		
Major Event Information	Major Event Information: Total restoration time	hours	N/A		
Major Event Information	Major Event Information: Total restoration time Instance 2	hours	N/A		
Major Event Information	Major Event Information: Total restoration time Instance 3	hours	N/A		
Major Event Information	Major Event Information: Total restoration time Instance 4	hours	N/A		
Major Event Information	Major Event Information: Total restoration time Instance 5	hours	N/A		
Major Event Information	Major Event Information: Total restoration time without SGDP/RDSI DA technology	hours	N/A		
Major Event Information	Major Event Information: Total restoration time without SGDP/RDSI DA technology Instance 2	hours	N/A		
Major Event Information	Major Event Information: Total restoration time without SGDP/RDSI DA technology Instance 3	hours	N/A		
Major Event Information	Major Event Information: Total restoration time without SGDP/RDSI DA technology Instance 4	hours	N/A		
Major Event Information	Major Event Information: Total restoration time without SGDP/RDSI DA technology Instance 5	hours	N/A		
Major Event Information	Major Event Information: Other information	Text	N/A		
Major Event Information	Major Event Information: Other information Instance 2	Text	N/A		
Major Event Information	Major Event Information: Other information Instance 3	Text	N/A		
Major Event Information	Major Event Information: Other information Instance 4	Text	N/A		
Major Event Information	Major Event Information: Other information Instance 5	Text	N/A		
Distribution Operations Vehicle Miles	Avoided Distribution Operations Vehicle Miles (mirror)	miles	N/A		
CO2 Emissions	Avoided CO2 Emissions: Distribution, Vehicle (mirror)	tons	Optional		
CO2 Emissions	Avoided CO2 Emissions: Distribution, Reduced Losses or Reduction in Load (mirror)	tons	Optional		
Custom Metrics					
Metric Name		Units	Project Value	System Value	Comments
END	END	END			

Project Name		KCP&L Green Impact Zone Smart Grid Demonstration			PLEASE DO NOT UNPROTECT THE SHEET FOR ANY REASON. IF THERE IS AN ISSUE WITH THE TEMPLATE PLEASE:						
Project ID		DE-0E000221									
Metric	Metric Qualifier	Unit	2011 SUMMER	2011 WINTER	2012 SUMMER	2012 WINTER	2013 SUMMER	2013 WINTER	2014 SUMMER		
Distribution feeder or equipment overload incidents	Feeder Line: Number of Incidents	#							0		
Distribution feeder or equipment overload incidents	Substation Transformer: Number of Incidents	#							0		
Distribution feeder or equipment overload incidents	Feeder Line: Average duration of incident	minutes							0		
Distribution feeder or equipment overload incidents	Substation Transformer: Average duration of incident	minutes							0		
Distribution feeder load	Aggregated Average Real Load	MW							0		
Distribution feeder load	Aggregated Average Reactive Load	MVAR							0		
Deferred Distribution Capacity Investment	Total Capital Cost	\$							0		
Deferred Distribution Capacity Investment	Total Capital Cost Instance 2	\$							0		
Deferred Distribution Capacity Investment	Total Capital Cost Instance 3	\$							0		
Deferred Distribution Capacity Investment	Total Capital Cost Instance 4	\$							0		
Deferred Distribution Capacity Investment	Total Capital Cost Instance 5	\$							0		
Deferred Distribution Capacity Investment	Amount of Time Deferred	years							0		
Deferred Distribution Capacity Investment	Amount of Time Deferred Instance 2	years							0		
Deferred Distribution Capacity Investment	Amount of Time Deferred Instance 3	years							0		
Deferred Distribution Capacity Investment	Amount of Time Deferred Instance 4	years							0		
Deferred Distribution Capacity Investment	Amount of Time Deferred Instance 5	years							0		
Deferred Distribution Capacity Investment	Description of Deferral	Text							N/A		
Deferred Distribution Capacity Investment	Description of Deferral Instance 2	Text							N/A		
Deferred Distribution Capacity Investment	Description of Deferral Instance 3	Text							N/A		
Deferred Distribution Capacity Investment	Description of Deferral Instance 4	Text							N/A		
Deferred Distribution Capacity Investment	Description of Deferral Instance 5	Text							N/A		
Equipment Failure Incidents	Transformers: Number of Failures (Distribution)	#							0		
Equipment Failure Incidents	Feeders: Number of Failures (Distribution)	#							0		
Equipment Failure Incidents	Other Major Distribution Equipment A: Number of Failures	#							0		
Equipment Failure Incidents	Other Major Distribution Equipment B: Number of Failures	#							0		
Equipment Failure Incidents	Other Major Distribution Equipment C: Number of Failures	#							0		
Truck Rollo (Distribution)	Truck Rollo Avoided (Distribution) (mirror)	#							0		
Distribution Operations Vehicle Miles	Avoided Distribution Operations Vehicle Miles (mirror)	miles							0		
CO2 Emissions	Avoided CO2 Emissions: Distribution, Vehicle (mirror)	tons							0		
CO2 Emissions	Avoided CO2 Emissions: Distribution, Reduced Losses or Reduction in Load (mirror)	tons							0		
Custom Metrics											
Metric Name	Units	2011 SUMMER	2011 WINTER	2012 SUMMER	2012 WINTER	2013 SUMMER	2013 WINTER	2014 SUMMER			
END	END	END									


Project Name		KCP&L Green Impact Zone Smart Grid Demonstration		PLEASE DO NOT UNPROTECT THE SHEET FOR ANY REASON. IF THERE IS AN ISSUE WITH THE TEMPLATE, CONTACT THE PROJECT MANAGER.	
Project ID		DE-OE0000221			
Reporting Period		2014 SUMMER			

Metric	Metric Qualifier	Unit	Project Value	System Value	Comments
Annual Storage Dispatch	Total electricity discharged from storage system; repeat for each unique storage system model/design	kWh	95864		
Average Energy Storage Efficiency	Roundtrip efficiency of the demonstration storage system; repeat for each unique storage system model/design	%	69.34		
Custom Metrics					
Metric Name		Units	Project Value	System Value	Comments
END	END	END			

Appendix U Smart Grid Computational Tool Analysis

U.1	Project Characterization Module (PCM)	U-2
U.2	Data Input Module (DIM)	U-9
U.3	Computational Module (CM)	U-15

U.1 Project Characterization Module (PCM)



PCM - Project Information

Please input project information below.


Organization Name: KCPL

Project Name: SmartGrid Demo

Project Start Year: 2013

NERC Region: 6. SPP

Buttons: Previous, Exit, Next



PCM - Choose Assets

Please select all assets that will be installed as part of the smart grid project. The choices on this page may represent a group or category of assets. If a particular asset that is being installed does not appear explicitly in this list choose the asset group that is most closely related to the asset being installed. The assets that are chosen on this page will determine the subset of functions that you will be able to choose from on the following page.

Customer Assets	Transmission Assets
<input checked="" type="checkbox"/> Customer EMS/Display/Portal	<input type="checkbox"/> Phase Angle Regulating Transformer
<input checked="" type="checkbox"/> Smart Appliances and Equipment (Customer)	<input type="checkbox"/> Phasor Measurement Technology
<input checked="" type="checkbox"/> Vehicle to Grid Charging Station	<input type="checkbox"/> Software - Advanced Analysis/Visualization

AMI Assets	Other Assets
<input checked="" type="checkbox"/> AMI/Smart Meters	<input type="checkbox"/> Enhanced Fault Detection Technology
<input type="checkbox"/> Advanced Interrupting Switch	<input type="checkbox"/> Equipment Health Sensor
<input type="checkbox"/> Controllable/regulating Inverter	<input type="checkbox"/> Flexible Alternating Current Transmission System (FACTS) Device
<input checked="" type="checkbox"/> Distribution Automabon	<input type="checkbox"/> Fault Current Limiter
<input checked="" type="checkbox"/> Distribution Management System	<input checked="" type="checkbox"/> Two-way Communications (high bandwidth)
<input checked="" type="checkbox"/> Loading Monitor	<input type="checkbox"/> Very Low Impedance (High Temperature Superconducting) cables
<input type="checkbox"/> Microgrid Controller	<input checked="" type="checkbox"/> Distributed Generator (diesel, PV, wind)
	<input checked="" type="checkbox"/> Electricity Storage device (e.g., battery, flywheel, PEV etc)

Buttons: Previous, Exit, Next

Mechanisms describe specifically how each function will be realized. In this page the applicable mechanisms for each enabled function should be selected. The combination of the functions and mechanisms determine which benefits the project may yield. Each tab in this page represents one of the enabled functions of this project. Please navigate to all enabled tabs and select all applicable mechanisms for each function. Be sure to navigate to all enabled tabs before proceeding to the next page.

Function 1 | Function 2 | Function 3 | Function 4 | Function 5 | **Function 6** | Function 7 | Function 8 | Function 9 | Function 10 | Function 11 | Function 12 | Function 13 | Function 14 | Function 15 |

Automated Feeder and Line Switching

- Reduces truck rolls
- Reduces manual labor hours associated with restoration
- Reduces fault location isolation service restoration (FLISR) time
- Reduces manual labor hours associated with line switching

Previous Previous Tab Exit Next Tab

Mechanisms describe specifically how each function will be realized. In this page the applicable mechanisms for each enabled function should be selected. The combination of the functions and mechanisms determine which benefits the project may yield. Each tab in this page represents one of the enabled functions of this project. Please navigate to all enabled tabs and select all applicable mechanisms for each function. Be sure to navigate to all enabled tabs before proceeding to the next page.

Function 1 | Function 2 | Function 3 | Function 4 | Function 5 | Function 6 | **Function 7** | Function 8 | Function 9 | Function 10 | Function 11 | Function 12 | Function 13 | Function 14 | Function 15 |

Automated Islanding and Reconnection

- Enables islanding or alternative power supply
- Reduces the number of crews needed to restore power

Previous Previous Tab Exit Next Tab Next

Mechanisms describe specifically how each function will be realized. In this page the applicable mechanisms for each enabled function should be selected. The combination of the functions and mechanisms determine which benefits the project may yield. Each tab in this page represents one of the enabled functions of this project. Please navigate to all enabled tabs and select all applicable mechanisms for each function. Be sure to navigate to all enabled tabs before proceeding to the next page.

Function 1 | Function 2 | Function 3 | Function 4 | Function 5 | Function 6 | Function 7 | Function 8 | Function 9 | Function 10 | Function 11 | Function 12 | Function 13 | Function 14 | Function 15 |

Automated Voltage and VAR Control

- Improves system power factor and voltage reducing the amount of voltage ancillary service required
- Optimizes voltage and VAR levels to reduce T&D losses
- Reduces emissions from carbon based fuel due to losses
- Reduces manual labor hours associated with capacitor switching and/or regulator operation

Previous Previous Tab Exit Next Tab Next

Mechanisms describe specifically how each function will be realized. In this page the applicable mechanisms for each enabled function should be selected. The combination of the functions and mechanisms determine which benefits the project may yield. Each tab in this page represents one of the enabled functions of this project. Please navigate to all enabled tabs and select all applicable mechanisms for each function. Be sure to navigate to all enabled tabs before proceeding to the next page.

Function 1 | Function 2 | Function 3 | Function 4 | Function 5 | Function 6 | Function 7 | Function 8 | Function 9 | Function 10 | Function 11 | Function 12 | Function 13 | Function 14 | Function 15 |

Diagnosis & Notification of Equipment Condition

- Reduces truck rolls
- Improves detection of pending failure
- Enables targeted maintenance

Previous Previous Tab Exit Next Tab Next

Mechanisms describe specifically how each function will be realized. In this page the applicable mechanisms for each enabled function should be selected. The combination of the functions and mechanisms determine which benefits the project may yield. Each tab in this page represents one of the enabled functions of this project. Please navigate to all enabled tabs and select all applicable mechanisms for each function. Be sure to navigate to all enabled tabs before proceeding to the next page.

Function 1 | Function 2 | Function 3 | Function 4 | Function 5 | Function 6 | Function 7 | Function 8 | Function 9 | Function 10 | Function 11 | Function 12 | Function 13 | Function 14 | Function 15 |

Real-Time Load Measurement & Management

- Enables load management
- Improves load models and forecasts
- Reduces truck rolls
- Optimizes load shape through direct load control to reduce electricity losses
- Identifies abnormal customer electricity consumption
- Following major damage to the system, detects the individual outages more precisely and quickly to reduce restoration time
- Reduces manual meter operations
- Enables faster restoration time
- Reduces fault location isolation service restoration (FLISR) time

Previous | Previous Tab | Exit | Next Tab | Next

Mechanisms describe specifically how each function will be realized. In this page the applicable mechanisms for each enabled function should be selected. The combination of the functions and mechanisms determine which benefits the project may yield. Each tab in this page represents one of the enabled functions of this project. Please navigate to all enabled tabs and select all applicable mechanisms for each function. Be sure to navigate to all enabled tabs before proceeding to the next page.

Function 1 | Function 2 | Function 3 | Function 4 | Function 5 | Function 6 | Function 7 | Function 8 | Function 9 | Function 10 | Function 11 | Function 12 | Function 13 | Function 14 | Function 15 |

Real-time Load Transfer

- Shifts loads among circuits to avoid overloading feeders or equipment
- Optimizes load shape by reconfiguring system to reduce electricity losses
- Reduces emissions from carbon based fuel due to losses
- Enables real-time feeder reconfiguration to restore service to a portion of customers quickly after a major event

Previous | Previous Tab | Exit | Next Tab | Next

Mechanisms describe specifically how each function will be realized. In this page the applicable mechanisms for each enabled function should be selected. The combination of the functions and mechanisms determine which benefits the project may yield. Each tab in this page represents one of the enabled functions of this project. Please navigate to all enabled tabs and select all applicable mechanisms for each function. Be sure to navigate to all enabled tabs before proceeding to the next page.

Function 1 | Function 2 | Function 3 | Function 4 | Function 5 | Function 6 | Function 7 | Function 8 | Function 9 | Function 10 | Function 11 | Function 12 | Function 13 | Function 14 | Function 15 |

Customer Electricity Use Optimization

- Shifts demand from peak time to reduce distribution peak load
- Shifts demand from peak time to reduce transmission peak load
- Shifts demand from peak time to reduce generation peak capacity required
- Shifts demand from peak time to reduce required ancillary services related to peak load
- Optimizes load shape through customer pricing and incentives to reduce electricity losses
- Reduces emissions from carbon based fuel due to losses
- Decreases loading on congested transmission pathways
- Provides customer with information which encourages alternate usage patterns or conservation resulting in reduced costs

Previous Previous Tab Exit Next Tab Next

Mechanisms describe specifically how each function will be realized. In this page the applicable mechanisms for each enabled function should be selected. The combination of the functions and mechanisms determine which benefits the project may yield. Each tab in this page represents one of the enabled functions of this project. Please navigate to all enabled tabs and select all applicable mechanisms for each function. Be sure to navigate to all enabled tabs before proceeding to the next page.

Function 1 | Function 2 | Function 3 | Function 4 | Function 5 | Function 6 | Function 7 | Function 8 | Function 9 | Function 10 | Function 11 | Function 12 | Function 13 | Function 14 | Function 15 |

Storing Electricity for Later Use

- Provides electricity at peak time to reduce distribution peak load
- Provides electricity at peak time to reduce generation peak capacity required
- Provides electricity at peak time to reduce transmission peak load
- Enables load following/smoothing allowing generators to remain in their optimum operating zone and avoid the dispatch of less efficient generation
- Provides electricity at peak time to reduce ancillary services related to peak load
- Provides electricity during times when price of "grid power" exceeds cost of providing electricity with the storage asset
- Acts as an uninterruptible power supply during a momentary outage
- Utilizes uninterrupted power supply capability to enable load to ride through voltage sags and swell
- Enables islanding or alternative power supply
- Decreases loading on congested transmission pathways
- Optimizes net load shape to reduce electricity losses
- Reduces emissions from carbon based fuel due to losses
- PEV's used as energy storage assets reduce gasoline consumption.

Previous Previous Tab Exit Next Tab Next

Mechanisms describe specifically how each function will be realized. In this page the applicable mechanisms for each enabled function should be selected. The combination of the functions and mechanisms determine which benefits the project may yield. Each tab in this page represents one of the enabled functions of this project. Please navigate to all enabled tabs and select all applicable mechanisms for each function. Be sure to navigate to all enabled tabs before proceeding to the next page.

Function 1 | Function 2 | Function 3 | Function 4 | Function 5 | **Function 6** | Function 7 | Function 8 | Function 9 | Function 10 | Function 11 | Function 12 | Function 13 | Function 14 | Function 15

Distributed Production of Electricity

- Generates electricity at peak time to reduce distribution peak load
- Generates electricity at peak time to reduce generation peak capacity required
- Generates electricity at peak time to reduce transmission peak load
- Enables more efficient generation mix to be dispatched by reducing the amount of central generation required during peak times
- Generates electricity at peak time to reduce required ancillary service related to peak load
- Reduces emissions from carbon based fuel due to losses and/or meets load with renewable sources
- Provides electricity during times when price of "grid power" exceeds cost of producing with the DG asset
- Optimizes net load shape to reduce electricity losses
- Enables islanding or alternative power supply
- Decreases loading on congested transmission pathways

Previous Previous Tab Exit Next Tab Next

The benefits in black font below represent the benefits this project could yield. For further explanation of the benefit click the button to the right of the benefit.

Optimized Generator Operation	Explanation	Reduced Electricity Losses	Explanation
Deferred Generation Capacity Investments	Explanation	Reduced Electricity Cost	Explanation
Reduced Ancillary Service Cost	Explanation	Reduced Sustained Outages	Explanation
Reduced Congestion Cost	Explanation	Reduced Major Outages	Explanation
Deferred Transmission Capacity Investments	Explanation	Reduced Restoration Cost	Explanation
Deferred Distribution Capacity Investments	Explanation	Reduced Momentary Outages	Explanation
Reduced Equipment Failures	Explanation	Reduced Sags and Swells	Explanation
Reduced T&D Equipment Maintenance Cost	Explanation	Reduced CO2 Emissions	Explanation
Reduced T&D Operations Cost	Explanation	Reduced SOx, NOx, and PM-2.5 Emissions	Explanation
Reduced Meter Reading Cost	Explanation	Reduced Oil Usage (not monetized)	Explanation
Reduced Electricity Theft	Explanation	Reduced Wide-scale Blackouts	Explanation

Previous Proceed to Function-Benefit Chart

Verify the Output of the PCM

Directions: Below is a chart that summarizes the output of the PCM. Along the top of the chart are listed all of the smart grid functions that a project could enable, along the side are listed all of the benefits that a project could yield. Based on your inputs in the PCM this chart has been populated with the benefits that your project may yield along with the functions that will lead to the benefits. Therefore, this chart should graphically summarize the objectives and expected benefits of your project. If the chart does adequately summarize your project click the blue button on the left to proceed to the next phase of the tool. If the chart does not adequately summarize your project click the button to the right to return to the PCM entry screens and adjust your inputs accordingly.

Function-Benefit Chart is
CORRECT
Proceed to the Data Input Module (DIM)

Function-Benefit Chart is
INCORRECT
Return to Initial Project Characterization Module (PCM)

Benefits			Smart Grid Functions															
			Delivery										Use	Other				
			Real Time Locating	Wide Area Monitoring, Visualization, and Control	Dynamic Capacity Rating	Power Flow Control	Adaptive Protection	Advanced Protection and Line Switching	Advanced Loading and Reconnection	Advanced Voltage and VAR Control	Diagnosis & Notification of Equipment Condition	Enhanced Fault Protection	Real Time Load Measurement & Management	Real Time Load Transfer	Customer Electricity Use Optimization	Energy Efficiency for Later Use	Decarbonized Production of Electricity	
Economic	Improved Asset Utilization	Optimized Generator Operation																
		Deferred Generation Capacity Investments																
		Reduced Auxiliary Service Cost																
	T&D Capital Savings	Reduced Congestion Cost																
		Deferred Transmission Capacity Investments																
		Reduced Equipment Failures																
	T&D O&M Savings	Reduced T&D Equipment Maintenance Cost																
Reduced T&D Operations Cost																		
Energy Efficiency	Reduced Meter Reading Cost																	
	Reduced Electricity Theft																	
	Reduced Electricity Losses																	
Reliability	Power Interruptions	Reduced Electricity Cost Savings																
		Reduced Sustained Outages																
Power Quality	Reduced Major Outages																	
	Reduced Restoration Cost																	
Environmental	Air Emissions	Reduced Momentary Outages																
		Reduced SO ₂ , NO _x , and PM-2.5 Emissions																
Security	Energy Security	Reduced Spills and Swells																
		Reduced Oil Usage (not monetized)																
		Reduced Wide-scale Blackouts																


U.2 Data Input Module (DIM)

Data Input Module (DIM) Main Page

Instructions

Welcome to the Data Input Module (DIM) phase of the Smart Grid Computational Tool. The DIM will help you navigate through the process of entering the required data. Its main purpose is to ensure that all the required data is entered in the proper format so that the benefits can be analyzed successfully. The DIM uses the project benefits identified by the IPSM to determine and present only a relevant subset of all possible tool inputs to the user. Once all required project data is entered the DIM will send the data to the next phase of the tool for analysis and calculation.

Progress through the DIM by clicking on the **blue buttons** below. Each button corresponds to a step in the DIM. The first three steps prompt the user to enter three different types of data: load curve and tariff data, benefit calculation input data, and project cost data. The fourth step allows the user to review their inputs before proceeding to the next module. The final step exits the DIM and brings the user to the Computational Module which uses the inputs provided by this module to calculate the benefits of the project.



Organization Name	KCPL
Project Name	SmartGrid Demo
NERC Region	6. SPP
Project Start Year	2013

Step I: Enter Number of Customers and Electricity Tariff Data

Step IV: Review DIM Cost and Benefit Calculation Inputs

Step II: Enter Benefit Calculation Input Data and Escalation Factors

Step V: Proceed to the Computational Module (CM) Module to complete Costs and Benefits Calculations

Step III: Enter Project Cost Data

DIM Step I : Number of Customers, and Electricity Tariff Data

Directions: In the outlined section below the user should enter the appropriate electricity tariff and customer population data. The user should refer to the detailed directions in the section below for instruction on how to enter data. If pasting data from another source into these tables please use the "Paste Value" function to avoid changing cell formatting or pasting formulas. Once all data has been entered click the button below to finish this step and return to the DIM Main Page. After finishing this step a new page will become visible which contains all of the data entered in this step, the user can view this page to review all data entered in

Finish Electricity Tariff and Customer Data Entry and Return to Main Page.

In this section the user should enter electricity tariff rates and information about the number of customers served. For **Table 1** at least one energy rate must be entered for each customer class and at least one demand charge must be entered for the commercial and industrial customer class. If there is no demand charge for a certain customer class a zero should be entered in the Average Demand Charge column of Table 1. Similarly for Table 2, a number must be entered for at least one sub-class for each customer class; if there are no customers served for a certain class a zero should be entered. Once the appropriate data has been entered in Tables 1 and 2 click the "Submit Rate and Number of Customers Served Data" button below to submit and store the entries.

Table 1: Electricity Rates by Customer Class in 2014			
	Average Energy Rate (\$/kWh)	Average Demand Charge (\$/kW-month)	
Residential Customer Class			
Residential Rate Sub-Class 1	\$ 0.108	\$ -	
Residential Rate Sub-Class 2			
Residential Rate Sub-Class 3			
Residential Rate Sub-Class 4			
Residential Rate Sub-Class 5			
Average Residential Rate	0.10837	0	
Commercial Customer Class			
Commercial Rate Sub-Class 1	\$ 0.057	\$ 2.650	
Commercial Rate Sub-Class 2			
Commercial Rate Sub-Class 3			
Commercial Rate Sub-Class 4			
Commercial Rate Sub-Class 5			
Average Commercial Rate	0.05692	2.65	
Industrial Customer Class			
Industrial Sub-Class 1	\$ 0.057	\$ 2.650	
Industrial Sub-Class 2			
Industrial Sub-Class 3			
Industrial Sub-Class 4			
Industrial Sub-Class 5			
Average Industrial Rate		2.65	
Average Retail Electricity Rate	0.082645	1.766666667	

Table 2: Number of Customeres Served by Class in 2014	
	Customers Served
Residential Customer Class	
Residential Rate Sub-Class 1	12,204
Residential Rate Sub-Class 2	
Residential Rate Sub-Class 3	
Residential Rate Sub-Class 4	
Residential Rate Sub-Class 5	
All Residential Classes	12,204
Commercial Customer Class	
Commercial Rate Sub-Class 1	1,223
Commercial Rate Sub-Class 2	
Commercial Rate Sub-Class 3	
Commercial Rate Sub-Class 4	
Commercial Rate Sub-Class 5	
All Commercial Classes	1,223
Industrial Customer Class	
Industrial Sub-Class 1	-
Industrial Sub-Class 2	
Industrial Sub-Class 3	
Industrial Sub-Class 4	
Industrial Sub-Class 5	
All Industrial Classes	-
All Customer Classes	13,427

Submit Rate and Number of Customers Served Data

DIM Step II: Enter Benefit Calculation Input Data, Escalation Factors

Directions: The Smart Grid Computational Tool can calculate costs and benefits of the smart grid project out to the year 2040. In order to complete this analysis escalation factors are applied to the inputs that have been entered. On this page the user can choose to use default escalation factors or they can enter their own escalation factors in the "Value" column. If pasting data from another source into this table please use the "Paste Value" function to avoid changing cell formatting or pasting formulas. To view a list of inputs affected by an escalation factor click the blue buttons in the "Inputs Affected" column. Additionally, the user can set the year in which project benefits decline to zero. If no values are entered in the "Value" column the default values will be used. After reviewing and/or entering all factors click the button below the chart to return to the DIM Main Page.

Escalation Factor	Description	Inputs Affected	Value	Default Value
Population Growth Factor	This escalation factor represents the customer population growth of the service area that the project impacts.	View List of Inputs		0.40%
Load Growth Factor	This escalation factor represents the electricity load growth of the service area that the project impacts.	View List of Inputs		1.80%
Economic Inflation Factor	This escalation factor represents the approximate economic inflation in the area that the project is located.	View List of Inputs		2.10%
Energy Price Factor	This escalation factor represents the approximate inflation rate of costs related to energy (i.e. whole sale electricity price, cost of ancillary services, congestion costs).	View List of Inputs Affected		1.40%
Final year of benefits	This parameter represents the final year that project will yield benefits; after this year all benefits will decline to zero. This parameter could be defined by the useful lifetime of smart grid assets installed.	This parameter affects all benefit calculations. This year determines when the benefits (calculated by determining the delta between project and baseline inputs) of the project decline to zero.		2038

[Return to DIM Main Page](#)

DIM Step III: Enter Project Cost Data

Directions: In this page the user can enter project cost information. This information will be used to complete a simple net present value cost benefit analysis. The user can enter total costs, initial and final spending years, and the interest rate and the tool will amortize the cost evenly over the spending period. Or the user can enter a customized cost schedule. If pasting data from another source into these tables please use the "Paste Value" function to avoid changing cell formatting or pasting formulas. When the cost information has been entered click the blue button at the bottom to submit and store the entries.

Project Start Year	yr	2013
Discount Rate	%	7%
Use Custom Cost Schedule	Yes/No	Yes
Initial Year of Project Spending	yr	
Final Year of Project Spending	yr	
Total Capital Cost of Project	\$	
Interest Rate	%	
Yearly Amortized Payment	\$	#DIV/0!

[Finish Cost Data Entry and Return to Main Page](#)

Year	2011	2012	2013	2014	2015
Capital (\$)	\$ -	\$ -	\$ 4,111,423	\$ 4,125,813	\$ 4,140,505

Year	2016	2017	2018	2019	2020	2021	2022	2023
Capital (\$)	\$ 4,155,506	\$ 4,170,822	\$ 4,186,459	\$ 4,202,425	\$ 4,218,726	\$ 4,235,369	\$ 4,252,362	\$ 4,269,712

Year	2024	2025	2026	2027	2028	2029	2030	2031
Capital (\$)	\$ 4,287,426	\$ 4,305,512	\$ 4,323,978	\$ 4,342,831	\$ 4,362,081	\$ 4,381,735	\$ 4,401,801	\$ 4,422,289

Year	2032	2033	2034	2035	2036	2037	2038
Capital (\$)	\$ 4,443,207	\$ 4,464,565	\$ 4,486,371	\$ 4,508,635	\$ 4,531,366	\$ 4,554,575	\$ 4,578,271

DIM Step IV: Review PDIM Cost and Benefit Calculation Inputs											
The tables below contain the benefit calculation inputs and project cost data that will be fed into the next phase of the Smart Grid Computational Tool. The purpose of this page is to give the user the opportunity to review the data before proceeding to the next phase of the tool. If the user finds data that has been entered erroneously, or if the user wishes to edit an entry they should navigate to the appropriate step in the DIM to do so.											
<div style="border: 1px solid black; padding: 5px; background-color: #4F81BD; color: white; display: inline-block; margin: 10px auto; width: 200px;">Finish Reviewing DIM Inputs and Return to Main Page</div>											
Input Name	Unit	Baseline 2013	Baseline 2014	Baseline 2015	Baseline 2016	Baseline 2017	2013	2014	2015	2016	2017
Annual Generation Cost	\$	0	0	0	0	0	-112244	-124488	-124488	-124488	-124488
Energy Storage Use at Annual Peak Time	MW	0.0	0.0	0.0	0.0	0.0	0.4	0.8	0.8	0.8	0.8
Distributed Generation Use at Annual Peak Time	MW	0.0	0.0	0.0	0.0	0.0	0.4	0.1	0.1	0.1	0.1
Price of Capacity at Annual Peak	\$/MW	95700	95700	95700	95700	95700	95700	95700	95700	95700	95700
Total Customer Peak Demand	MW	0.0	0.0	0.0	0.0	0.0	-0.3	-0.6	-0.6	-0.6	-0.6
Capital Carrying Charge of Distribution Upgrade	\$	0	0	0	0	0	338743	0	0	0	0
Distribution Investment Time Deferred	yrs	0.0	0.0	0.0	0.0	0.0	0.0	5.0	0.0	0.0	0.0
Capital Replacement of Failed Equipment	\$	0	0	0	0	0	0	-1250000	0	0	0
Portion Caused by Lack of Condition Diagnosis	%	100.0%	100.0%	100.0%	100.0%	100.0%	100.0%	100.0%	100.0%	100.0%	100.0%
Transmission Operations Cost	\$	0	0	0	0	0	0	0	0	0	0
Distribution Feeder Switching Operations	\$	0	0	0	0	0	0	0	0	0	0
Distribution Capacitor Switching Operations	\$	0	0	0	0	0	0	0	0	0	0
Other Distribution Operations Cost	\$	0	0	0	0	0	450.625	-901.25	-901.25	-901.25	-901.25
Meter Operations Cost	\$	0	0	0	0	0	-86283.5	-172567	-172567	-172567	-172567
Number of Meter Tamper Detections - Residential	#	0	0	0	0	0	5	10	10	10	10
Number of Meter Tamper Detections - Commercial	#	0	0	0	0	0	0	0	0	0	0
Number of Meter Tamper Detections - Industrial	#	0	0	0	0	0	0	0	0	0	0
Average Annual Customer Electricity Usage - Residential	kWh	7982	7982	7982	7982	7982	7982	7982	7982	7982	7982
Average Annual Customer Electricity Usage - Commercial	kWh	89715	89715	89715	89715	89715	89715	89715	89715	89715	89715
Average Annual Customer Electricity Usage - Industrial	kWh	0	0	0	0	0	0	0	0	0	0
Distribution Feeder Load	MVA	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Distribution Losses	%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
Transmission Line Load	MVA	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Transmission Losses	%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
Average Price of Wholesale Energy	\$/kWh	0.03321	0.03321	0.03321	0.03321	0.03321	0.03321	0.03321	0.03321	0.03321	0.03321
Total Residential Electricity Cost	\$	0	0	0	0	0	-90036.5	-180073	-180073	-180073	-180073
Total Commercial Electricity Cost	\$	0	0	0	0	0	-50899.5	-101799	-101799	-101799	-101799
Total Industrial Electricity Cost	\$	0	0	0	0	0	0	0	0	0	0
SAIDI (Impacted Feeders or Lines)	Index	3.03	3.03	3.03	3.03	3.03	2.50	1.97	1.97	1.97	1.97
Total Residential Customers Served by Impacted Feeders or Lines	#	12204	12204	12204	12204	12204	12204	12204	12204	12204	12204
Total Commercial Customers Served by Impacted Feeders or Lines	#	1223	1223	1223	1223	1223	1223	1223	1223	1223	1223
Total Industrial Customers Served by Impacted Feeders or Lines	#	0	0	0	0	0	0	0	0	0	0
Outage Time of Major Outage - Residential	hr	0	0	0	0	0	0	0	0	0	0
Number of Customers Affected by Major Outage - Residential	#	0	0	0	0	0	0	0	0	0	0
Outage Time of Major Outage - Commercial	hr	0	0	0	0	0	0	0	0	0	0
Number of Customers Affected by Major Outage - Commercial	#	0	0	0	0	0	0	0	0	0	0
Outage Time of Major Outage - Industrial	hr	0	0	0	0	0	0	0	0	0	0
Number of Customers Affected by Major Outage - Industrial	#	0	0	0	0	0	0	0	0	0	0
Value of Service - Residential	\$/kWh	2.27	2.32	2.37	2.42	2.47	2.27	2.32	2.37	2.42	2.47
Value of Service - Commercial	\$/kWh	99.34	99.34	101.43	103.56	105.73	97.30	99.34	101.43	103.56	105.73
Value of Service - Industrial	\$/kWh	17.33	17.70	18.07	18.45	18.83	17.33	17.70	18.07	18.45	18.83
Average Hourly Load Not Served During Outage per Customer - Residential	kW	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9
Average Hourly Load Not Served During Outage per Customer - Commercial	kW	10.2	10.2	10.2	10.2	10.2	10.2	10.2	10.2	10.2	10.2
Average Hourly Load Not Served During Outage per Customer - Industrial	kW	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Number of Outage Events	# of events	0	0	0	0	0	-38.5	-77	-77	-77	-77
Restoration Cost per Event	\$/event	260	265.46	271.03466	276.7263879	282.537642	260	265.46	271.03466	276.7263879	282.537642
Number of Feeder Switching or Maintenance Operations Completed	# of events	0	0	0	0	0	-38.5	-77	-77	-77	-77
Average Miles Traveled per Switching or Maintenance Operation	miles/event	20	20	20	20	20	20	20	20	20	20
Average Fuel Efficiency for Feeder Service Vehicle	miles/gallon	6.33	6.33	6.33	6.33	6.33	6.33	6.33	6.33	6.33	6.33
Number of Meter Reading Operations	# of events	0	0	0	0	0	-8375	-8375	-8375	-8375	-8375
Average Miles Traveled per meter read	miles/event	2.2	2.2	2.2	2.2	2.2	2.2	2.2	2.2	2.2	2.2
Average Fuel Efficiency for Real-Time Load Measurement/Management Service Vehicle	miles/gallon	11.83	11.83	11.83	11.83	11.83	11.83	11.83	11.83	11.83	11.83
kWh of Electricity Consumed by PEVs	kWh	0	0	0	0	0	14293	28586	28586	28586	28586
Electricity to Fuel Conversion Factor	gallons/kWh	0.130	0.130	0.130	0.130	0.130	0.130	0.130	0.130	0.130	0.130
CO2 Emissions per Gallon of Fuel	tons/gallon	0.010	0.010	0.010	0.010	0.010	0.010	0.010	0.010	0.010	0.010
CO2 Emissions	tons	0	0	0	0	0	-1629.75	-3259.5	-3259.5	-3259.5	-3259.5
Value of CO2	\$/ton	20	20	20	20	20	20	20	20	20	20
Sox Emissions per Gallon of Gas	tons/gallon	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
NOx Emissions per Gallon of Gas	tons/gallon	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
PM-2.5 per Gallon of Gas	tons/gallon	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
SOx Emissions	tons	0	0	0	0	0	-2.3105	-4.621	-4.621	-4.621	-4.621
NOx Emissions	tons	0	0	0	0	0	-1.738	-3.475	-3.475	-3.475	-3.475
PM-2.5 Emissions	tons	0	0	0	0	0	-0.01852	-0.03703	-0.03703	-0.03703	-0.03703
Value of SOx	\$/ton	520	520	520	520	520	520	520	520	520	520
Value of NOx	\$/ton	3000	3000	3000	3000	3000	3000	3000	3000	3000	3000
Value of PM-2.5	\$/ton	36000	36000	36000	36000	36000	36000	36000	36000	36000	36000

Cost Schedule								
Year					Total	2011	2012	2013
Yearly Capital Expenditure (\$)					\$ 112,463,764	\$ -	\$ -	\$ 4,111,423
Present Value of Yearly Capital Expenditure (\$)					\$ 53,695,656	\$ -	\$ -	\$ 4,111,423
2014	2015	2016	2017	2018	2019	2020	2021	
\$ 4,125,813	\$ 4,140,505	\$ 4,155,506	\$ 4,170,822	\$ 4,186,459	\$ 4,202,425	\$ 4,218,726	\$ 4,235,369	
\$ 3,854,335	\$ 3,613,542	\$ 3,388,001	\$ 3,176,736	\$ 2,978,833	\$ 2,793,439	\$ 2,619,753	\$ 2,457,028	
2022	2023	2024	2025	2026	2028	2029	2030	
\$ 4,252,362	\$ 4,269,712	\$ 4,287,426	\$ 4,305,512	\$ 4,323,978	\$ 4,362,081	\$ 4,381,735	\$ 4,401,801	
\$ 2,304,565	\$ 2,161,709	\$ 2,027,847	\$ 1,902,406	\$ 1,784,850	\$ 1,571,418	\$ 1,474,633	\$ 1,383,911	
2031	2032	2033	2034	2035	2036	2037	2038	
\$ 4,422,289	\$ 4,443,207	\$ 4,464,565	\$ 4,486,371	\$ 4,508,635	\$ 4,531,366	\$ 4,554,575	\$ 4,578,271	
\$ 1,298,867	\$ 1,219,141	\$ 1,144,396	\$ 1,074,317	\$ 1,008,607	\$ 946,991	\$ 889,210	\$ 835,022	

U.3 Computational Module (CM)

Computational Module (CM) Main Page




Instructions

Welcome to the Computational Module (CM) phase of the Smart Grid Computational Tool. The CM is the calculation engine of the tool, it crunches the numbers and generates the output. The CM also allows the user to complete a sensitivity analysis if desired. Before running the CM the user can review their inputs and the first five years of projected inputs using the tables below. If the user wishes to change any inputs they can return to the PDIM by clicking the arrow to the right of this directions box.

Running the CM with Reference Inputs - To run the CM with the inputs that were entered in the DIM phase, simply click the button in the "Reference Case" section that says "Run CM with Reference Case Inputs". The CM will take about 20 seconds to complete the analysis. Once the analysis is complete the results can be viewed by clicking the "View Reference Case Results" button.

Running the a Sensitivity Analysis - Before running a sensitivity analysis the CM should be run with the reference case inputs by following the directions above. To run a sensitivity analysis first change the High and Low sensitivity ranges of the desired inputs by using the toggles that are to the right of every input. After all of the desired sensitivity ranges have been set click the button in the "Sensitivity Analysis" section that says "Run CM with Sensitivity Case Inputs". The CM will take about a minute to complete the analysis. Once the analysis is complete the results can be viewed by clicking the "View Sensitivity Results" button. All of the sensitivity ranges can be reset to 100% by clicking the button above the toggle switches that says "Reset all values to 100%".



Reference Case

Run CM with Reference Case Inputs View Reference Case Results

Sensitivity Analysis


Run CM with Sensitivity Case Inputs View Sensitivity Results

Reset all values to 100%

Input Name	Unit	Select % using toggle			Reference Case Values (project)					Projections -->				
		Low	Reference	High	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022
Annual Generation Cost	\$	100%	100%	100%	(112,244)	(124,488)	(124,488)	(124,488)	(124,488)	(128,472)	(132,583)	(136,625)	(141,204)	(145,722)
Energy Storage Use at Annual Peak Time	MW	100%	100%	100%	0.4	0.8	0.8	0.8	0.8	0.8	0.8	0.8	0.9	0.9
Distributed Generation Use at Annual Peak Time	MW	100%	100%	100%	0.4	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1
Price of Capacity at Annual Peak	\$/MW	100%	100%	100%	95,700	95,700	95,700	95,700	95,700	97,040	98,398	99,776	101,173	102,589
Total Customer Peak Demand	MW	100%	100%	100%	(0.3)	(0.6)	(0.6)	(0.6)	(0.6)	(0.6)	(0.6)	(0.6)	(0.6)	(0.6)
Capital Carrying Charge of Distribution Upgrade	\$	100%	100%	100%	-	338,743	-	-	-	-	-	-	-	-
Distribution Investment Time Deferred	yrs	100%	100%	100%	-	5.0	-	-	-	-	-	-	-	-
Capital Replacement of Failed Equipment	\$	100%	100%	100%	-	(1,250,000)	-	-	-	-	-	-	-	-
Portion Caused by Lack of Condition Diagnosis	%	100%	100%	100%	100.0%	100.0%	100.0%	100.0%	100.0%	100.0%	100.0%	100.0%	100.0%	100.0%
Transmission Operations Cost	\$	100%	100%	100%	-	-	-	-	-	-	-	-	-	-
Distribution Feeder Switching Operations	\$	100%	100%	100%	-	-	-	-	-	-	-	-	-	-
Distribution Capacitor Switching Operations	\$	100%	100%	100%	-	-	-	-	-	-	-	-	-	-
Other Distribution Operations Cost	\$	100%	100%	100%	(451)	(901)	(901)	(901)	(901)	(920)	(939)	(959)	(979)	(1,000)
Meter Operations Cost	\$	100%	100%	100%	(86,284)	(172,567)	(172,567)	(172,567)	(172,567)	(176,191)	(179,891)	(183,669)	(187,526)	(191,464)
Number of Meter Tamper Detections - Residential	#	100%	100%	100%	5	10	10	10	10	10	10	10	10	10
Number of Meter Tamper Detections - Commercial	#	100%	100%	100%	-	-	-	-	-	-	-	-	-	-
Number of Meter Tamper Detections - Industrial	#	100%	100%	100%	-	-	-	-	-	-	-	-	-	-
Average Annual Customer Electricity Usage - Residential	kWh	100%	100%	100%	7,982	7,982	7,982	7,982	7,982	8,126	8,272	8,421	8,572	8,727
Average Annual Customer Electricity Usage - Commercial	kWh	100%	100%	100%	89,715	89,715	89,715	89,715	89,715	91,330	92,974	94,647	96,351	98,085
Average Annual Customer Electricity Usage - Industrial	kWh	100%	100%	100%	-	-	-	-	-	-	-	-	-	-
Distribution Feeder Load	MVA	100%	100%	100%	-	-	-	-	-	-	-	-	-	-
Distribution Losses	%	100%	100%	100%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
Transmission Line Load	MVA	100%	100%	100%	-	-	-	-	-	-	-	-	-	-
Transmission Losses	%	100%	100%	100%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
Average Price of Wholesale Energy	\$/kWh	100%	100%	100%	0	0	0	0	0	0	0	0	0	0
Total Residential Electricity Cost	\$	100%	100%	100%	(90,037)	(180,073)	(180,073)	(180,073)	(180,073)	(183,314)	(186,614)	(189,973)	(193,393)	(196,874)
Total Commercial Electricity Cost	\$	100%	100%	100%	(50,900)	(101,799)	(101,799)	(101,799)	(101,799)	(103,631)	(105,497)	(107,396)	(109,329)	(111,297)
Total Industrial Electricity Cost	\$	100%	100%	100%	-	-	-	-	-	-	-	-	-	-
SAIDI (Impacted Feeders or Lines)	index	100%	100%	100%	2,496	1,966	1,966	1,966	1,966	1,966	1,966	1,966	1,966	1,966
Total Residential Customers Served by Impacted Feeders or Lines	#	100%	100%	100%	12,204	12,204	12,204	12,204	12,204	12,204	12,204	12,204	12,204	12,204
Total Commercial Customers Served by Impacted Feeders or Lines	#	100%	100%	100%	1,223	1,223	1,223	1,223	1,223	1,223	1,223	1,223	1,223	1,223
Total Industrial Customers Served by Impacted Feeders or Lines	#	100%	100%	100%	-	-	-	-	-	-	-	-	-	-
Outage Time of Major Outage - Residential	hr	100%	100%	100%	-	-	-	-	-	-	-	-	-	-
Number of Customers Affected by Major Outage - Residential	#	100%	100%	100%	-	-	-	-	-	-	-	-	-	-
Outage Time of Major Outage - Commercial	hr	100%	100%	100%	-	-	-	-	-	-	-	-	-	-
Number of Customers Affected by Major Outage - Commercial	#	100%	100%	100%	-	-	-	-	-	-	-	-	-	-
Outage Time of Major Outage - Industrial	hr	100%	100%	100%	-	-	-	-	-	-	-	-	-	-
Number of Customers Affected by Major Outage - Industrial	#	100%	100%	100%	-	-	-	-	-	-	-	-	-	-
Value of Service - Residential	\$/kWh	100%	100%	100%	2	2	2	2	2	3	3	3	3	3
Value of Service - Commercial	\$/kWh	100%	100%	100%	97	99	101	104	106	108	110	113	115	117
Value of Service - Industrial	\$/kWh	100%	100%	100%	17	18	18	18	19	19	20	20	20	21
Average Hourly Load Not Served During Outage per Customer - Residential	kW	100%	100%	100%	1	1	1	1	1	1	1	1	1	1
Average Hourly Load Not Served During Outage per Customer - Commercial	kW	100%	100%	100%	10	10	10	10	10	10	11	11	11	11
Average Hourly Load Not Served During Outage per Customer - Industrial	kW	100%	100%	100%	-	-	-	-	-	-	-	-	-	-
Number of Outage Events	# of events	100%	100%	100%	(39)	(77)	(77)	(77)	(77)	(77)	(77)	(77)	(77)	(77)
Restoration Cost per Event	\$/event	100%	100%	100%	260	265	271	277	283	288	295	301	307	313
Number of Feeder Switching or Maintenance Operations Completed	# of events	100%	100%	100%	(39)	(77)	(77)	(77)	(77)	(77)	(77)	(77)	(77)	(77)
Average Miles Traveled per Switching or Maintenance Operation	miles/event	100%	100%	100%	20	20	20	20	20	20	20	20	20	20
Average Fuel Efficiency for Feeder Service Vehicle	miles/gallon	100%	100%	100%	6	6	6	6	6	6	6	6	6	6
Number of Meter Reading Operations	# of events	100%	100%	100%	(8,375)	(8,375)	(8,375)	(8,375)	(8,375)	(8,409)	(8,442)	(8,476)	(8,510)	(8,544)
Average Miles Traveled per meter read	miles/event	100%	100%	100%	2	2	2	2	2	2	2	2	2	2
Average Fuel Efficiency for Real-Time Load Measurement/Management Service Vehicle	miles/gallon	100%	100%	100%	12	12	12	12	12	12	12	12	12	12
kWh of Electricity Consumed by PEVs	kWh	100%	100%	100%	14,293	28,586	28,586	28,586	28,586	28,700	28,815	28,930	29,046	29,162
Electricity to Fuel Conversion Factor	gallons/kWh	100%	100%	100%	0.130	0.130	0.130	0.130	0.130	0.130	0.130	0.130	0.130	0.130
CO2 Emissions per Gallon of Fuel	tons/gallon	100%	100%	100%	0.010	0.010	0.010	0.010	0.010	0.010	0.010	0.010	0.010	0.010
CO2 Emissions	tons	100%	100%	100%	(1,630)	(3,260)	(3,260)	(3,260)	(3,260)	(3,260)	(3,260)	(3,260)	(3,260)	(3,260)
Value of CO2	\$/ton	100%	100%	100%	20	20	20	20	20	21	21	21	22	22
Sox Emissions per Gallon of Gas	tons/gallon	100%	100%	100%	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
NOx Emissions per Gallon of Gas	tons/gallon	100%	100%	100%	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
PM-2.5 per Gallon of Gas	tons/gallon	100%	100%	100%	-	-	-	-	-	-	-	-	-	-
SOx Emissions	tons	100%	100%	100%	(2)	(5)	(5)	(5)	(5)	(5)	(5)	(5)	(5)	(5)
NOx Emissions	tons	100%	100%	100%	(2)	(3)	(3)	(3)	(3)	(3)	(3)	(3)	(3)	(3)
PM-2.5 Emissions	tons	100%	100%	100%	(0)	(0)	(0)	(0)	(0)	(0)	(0)	(0)	(0)	(0)
Value of SOx	\$/ton	100%	100%	100%	520	520	520	520	520	531	542	553	565	577
Value of NOx	\$/ton	100%	100%	100%	3,000	3,000	3,000	3,000	3,000	3,063	3,127	3,191	3,256	3,320
Value of PM-2.5	\$/ton	100%	100%	100%	36,000	36,000	36,000	36,000	36,000	36,756	37,538	38,316	39,111	39,942
Number of Customers Residential Rate Sub-Class 1	#	100%	100%	100%	12,204	12,253	12,302	12,351	12,400	12,450	12,500	12,550	12,600	12,650
Number of Customers Residential Rate Sub-Class 2	#	100%	100%	100%	-	-	-	-	-	-	-	-	-	-
Number of Customers Residential Rate Sub-Class 3	#	100%	100%	100%	-	-	-	-	-	-	-	-	-	-
Number of Customers Residential Rate Sub-Class 4	#	100%	100%	100%	-	-	-	-	-	-	-	-	-	-
Number of Customers Residential Rate Sub-Class 5	#	100%	100%	100%	-	-	-	-	-	-	-	-	-	-
Number of Customers All Residential Classes	#	100%	100%	100%	12,204	12,253	12,302	12,351	12,400	12,450	12,500	12,550	12,600	12,650
Number of Customers Commercial Rate Sub-Class 1	#	100%	100%	100%	1,223	1,228	1,233	1,238	1,243	1,248	1,253	1,258	1,263	1,268
Number of Customers Commercial Rate Sub-Class 2	#	100%	100%	100%	-	-	-	-	-	-	-	-	-	-
Number of Customers Commercial Rate Sub-Class 3	#	100%	100%	100%	-	-	-	-	-	-	-	-	-	-
Number of Customers Commercial Rate Sub-Class 4	#	100%	100%	100%	-	-	-	-	-	-	-	-	-	-
Number of Customers Commercial Rate Sub-Class 5	#	100%	100%	100%	-	-	-	-	-	-	-	-	-	-
Number of Customers All Commercial Classes	#	100%	100%	100%	1,223	1,228	1,233	1,238	1,243	1,248	1,253	1,258	1,263	1,268
Number of Customers Industrial Sub-Class 1	#	100%	100%	100%	-	-	-	-	-	-	-	-	-	-
Number of Customers Industrial Sub-Class 2	#	100%	100%	100%	-	-	-	-	-	-	-	-	-	-
Number of Customers Industrial Sub-Class 3	#	100%	100%	100%	-	-	-	-	-	-	-	-	-	-
Number of Customers Industrial Sub-Class 4	#	100%	100%	100%	-	-	-	-	-	-	-	-	-	-
Number of Customers Industrial Sub-Class 5	#	100%	100%	100%	-	-	-	-	-	-	-	-	-	-
Number of Customers All Industrial Classes	#	100%	100%	100%	-	-	-	-	-	-	-	-	-	-


Reference Case Output: Cumulative Benefits by Category and Sub-Category

The pie charts below show the proportional breakdown of cumulative gross benefits, economic benefits, and reliability benefits by category and sub-category. The tables to the left of each chart displays the data that each chart summarizes. All dollar values are expressed in nominal dollars.




Cumulative Gross Benefits 2013 - 2040		
Economic	\$	24,629,720
Reliability	\$	53,452,464
Environmental	\$	2,552,834
Security	\$	-
Total	\$	80,635,019

Cumulative Economic Benefits 2013 - 2040



Cumulative Economic Benefits 2013 - 2040		
Improved Asset Utilization	\$	9,271,353
T&D Capital Savings	\$	1,347,714
T&D O&M Savings	\$	5,395,439
Reduced Electricity Theft	\$	101,966
Reduced Electricity Losses	\$	-
Reduced Electricity Costs	\$	8,513,248
Total	\$	24,629,720

Cumulative Reliability Benefits 2013 - 2040



Cumulative Reliability Benefits 2013 - 2040		
Reduced Sustained Outages	\$	53,450,501
Reduced Major Outages	\$	-
Reduced Restoration Cost	\$	1,964
Reduced Momentary Outages	\$	-
Reduced Sags and Swells	\$	-
Total	\$	53,452,464

Reference Case Output: Present Value Cost and Benefit Analysis



The table and graphs below summarize the present value of costs, benefits, and the net present value of the project. These results are displayed on an annual basis as well as on a cumulative basis.

	Total	Start Year of the Project			
		2011	2012	2013	2014
Annual Cost	\$ (112,463,764)	\$ -	\$ -	\$ (4,111,423)	\$ (4,125,813)
Annual Benefit	\$ 80,635,019	\$ -	\$ -	\$ 1,142,518	\$ 3,497,443
Annual Present Value (PV) Cost	\$ (53,695,656)	\$ -	\$ -	\$ (4,111,423)	\$ (3,854,335)
Annual PV Benefit	\$ 34,818,577	\$ -	\$ -	\$ 1,142,518	\$ 3,267,311
Annual PV of Net Benefit	\$ (18,877,079)	\$ -	\$ -	\$ (2,968,905)	\$ (587,023)
Cumulative PV Cost		\$ -	\$ -	\$ (4,111,423)	\$ (7,965,758)
Cumulative PV Benefit		\$ -	\$ -	\$ 1,142,518	\$ 4,409,829
Cumulative PV of Net Benefit		\$ -	\$ -	\$ (2,968,905)	\$ (3,555,929)

2015	2016	2017	2018	2019	2020	2021	2022
\$ (4,140,505)	\$ (4,155,506)	\$ (4,170,822)	\$ (4,186,459)	\$ (4,202,425)	\$ (4,218,726)	\$ (4,235,369)	\$ (4,252,362)
\$ 2,178,024	\$ 2,206,862	\$ 2,236,242	\$ 2,311,618	\$ 2,389,693	\$ 2,470,566	\$ 2,554,342	\$ 2,641,129
\$ (3,613,542)	\$ (3,388,001)	\$ (3,176,736)	\$ (2,978,833)	\$ (2,793,439)	\$ (2,619,753)	\$ (2,457,028)	\$ (2,304,565)
\$ 1,900,826	\$ 1,799,263	\$ 1,703,249	\$ 1,644,809	\$ 1,588,478	\$ 1,534,177	\$ 1,481,829	\$ 1,431,358
\$ (1,712,715)	\$ (1,588,738)	\$ (1,473,486)	\$ (1,334,024)	\$ (1,204,960)	\$ (1,085,576)	\$ (975,200)	\$ (873,207)
\$ (11,579,300)	\$ (14,967,301)	\$ (18,144,036)	\$ (21,122,869)	\$ (23,916,308)	\$ (26,536,061)	\$ (28,993,089)	\$ (31,297,655)
\$ 6,310,655	\$ 8,109,919	\$ 9,813,168	\$ 11,457,977	\$ 13,046,455	\$ 14,580,633	\$ 16,062,461	\$ 17,493,820
\$ (5,268,644)	\$ (6,857,382)	\$ (8,330,868)	\$ (9,664,892)	\$ (10,869,853)	\$ (11,955,428)	\$ (12,930,628)	\$ (13,803,835)

2023	2024	2025	2026	2027	2028	2029	2030
\$ (4,269,712)	\$ (4,287,426)	\$ (4,305,512)	\$ (4,323,978)	\$ (4,342,831)	\$ (4,362,081)	\$ (4,381,735)	\$ (4,401,801)
\$ 2,731,039	\$ 2,824,187	\$ 2,920,696	\$ 3,020,690	\$ 3,124,299	\$ 3,231,659	\$ 3,342,910	\$ 3,458,197
\$ (2,161,709)	\$ (2,027,847)	\$ (1,902,406)	\$ (1,784,850)	\$ (1,674,677)	\$ (1,571,418)	\$ (1,474,633)	\$ (1,383,911)
\$ 1,382,695	\$ 1,335,771	\$ 1,290,520	\$ 1,246,879	\$ 1,204,788	\$ 1,164,189	\$ 1,125,026	\$ 1,087,245
\$ (779,013)	\$ (692,076)	\$ (611,886)	\$ (537,971)	\$ (469,889)	\$ (407,229)	\$ (349,607)	\$ (296,666)
\$ (33,459,363)	\$ (35,487,210)	\$ (37,389,616)	\$ (39,174,466)	\$ (40,849,143)	\$ (42,420,560)	\$ (43,895,193)	\$ (45,279,104)
\$ 18,876,515	\$ 20,212,286	\$ 21,502,806	\$ 22,749,685	\$ 23,954,473	\$ 25,118,663	\$ 26,243,688	\$ 27,330,933
\$ (14,582,848)	\$ (15,274,924)	\$ (15,886,810)	\$ (16,424,780)	\$ (16,894,669)	\$ (17,301,898)	\$ (17,651,505)	\$ (17,948,171)

2031	2032	2033	2034	2035	2036	2037	2038
\$ (4,422,289)	\$ (4,443,207)	\$ (4,464,565)	\$ (4,486,371)	\$ (4,508,635)	\$ (4,531,366)	\$ (4,554,575)	\$ (4,578,271)
\$ 3,577,671	\$ 3,701,490	\$ 3,829,816	\$ 3,962,818	\$ 4,100,672	\$ 4,243,560	\$ 4,391,672	\$ 4,545,203
\$ (1,298,867)	\$ (1,219,141)	\$ (1,144,396)	\$ (1,074,317)	\$ (1,008,607)	\$ (946,991)	\$ (889,210)	\$ (835,022)
\$ 1,050,795	\$ 1,015,626	\$ 981,692	\$ 948,945	\$ 917,344	\$ 886,844	\$ 857,406	\$ 828,991
\$ (248,072)	\$ (203,515)	\$ (162,704)	\$ (125,371)	\$ (91,263)	\$ (60,147)	\$ (31,804)	\$ (6,031)
\$ (46,577,971)	\$ (47,797,112)	\$ (48,941,508)	\$ (50,015,825)	\$ (51,024,432)	\$ (51,971,423)	\$ (52,860,633)	\$ (53,695,656)
\$ 28,381,728	\$ 29,397,354	\$ 30,379,046	\$ 31,327,992	\$ 32,245,335	\$ 33,132,179	\$ 33,989,586	\$ 34,818,577
\$ (18,196,243)	\$ (18,399,757)	\$ (18,562,462)	\$ (18,687,833)	\$ (18,779,096)	\$ (18,839,244)	\$ (18,871,048)	\$ (18,877,079)



This page intentionally blank.

Appendix V Energy Storage Computational Tool Analysis – Grid

V.1	Asset Characterization Module (ACM)	V-2
V.2	Data Input Module (DIM)	V-8
V.3	Computational Module (CM)	V-10

V.1 Asset Characterization Module (ACM)

U.S. Department of Energy Storage Computational Tool (ESCT) Version 1.2

Purpose of Tool: ESCT guides the user through an analysis to calculate the benefits of an energy storage deployment, compare costs and benefits, and gain a clearer understanding of the value of energy storage technology in terms of monetary benefit. Furthermore, the ESCT can be used to analyze how the costs and benefits vary given different scenarios and assumptions.

Explanation of Output: The output of the ESCT consists of charts, graphs and tables that summarize the benefits and costs of an energy storage deployment. The benefits are monetized and calculated from actual or estimated metrics collected in the first five years of a project lifetime. Based on up to five years of data benefits can be projected out to 40 years in the future. The output also includes charts, graphs and tables that summarize the results of a sensitivity analysis. The user is able to set a high and low sensitivity range for each input in the tool and the output shows how the benefits are affected by variability of the inputs.

Directions: The ESCT is designed to be user-friendly and easy to navigate. However, it will be useful to review the overall methodology of the tool before beginning a new analysis. The diagram below illustrates the tool architecture and the analysis methodology. The tool is divided into three distinct phases: the Asset Characterization Module (ACM), the Data Input Module (DIM), and the Computational Module (CM). The first phase, the ACM, collects information about the deployment such as characteristics of the energy storage technology, cost information, and the applications the deployment will be used for. From this input, the ACM determines a list of benefits that the project could yield. These potential project benefits are then fed into the second phase of the tool, the DIM. The DIM uses the list of benefits to determine the inputs required to calculate the benefits. The DIM then helps the user navigate through the process of entering the required data. The DIM's main purpose is to ensure that all the required data is entered in the proper format so that the benefits can be analyzed successfully. The input data is then fed into the final phase, the CM. The CM is the calculation engine of the tool, it crunches the numbers and generates the output. The CM also allows the user to carry out a sensitivity analysis if desired. To start a new analysis, click the blue button below and follow the directions that appear in each phase of the tool.

```

graph TD
    subgraph Module1 [Module 1]
        A[Asset Location, Market and Applications] --> B[Asset Characterization Module: Characterizes how the storage asset will be used. Determines benefits the project will yield.]
    end
    subgraph Module2 [Module 2]
        C[Project Data] --> D[Data Input Module: Facilitates the data input required to calculate the energy storage benefits.]
    end
    B -- "Energy storage benefits" --> D
    D -- "Project Data" --> E[Module 3]
    subgraph Module3 [Module 3]
        E[Computational Module: Calculates and projects storage benefits; carries out sensitivity analysis.]
    end
    F[Sensitivity Analysis Input Interface (Optional): Allows the user to set the sensitivity range for specific variables (e.g. value of CO2).] -- "Sensitivity ranges" --> E
    E --> G[Results]
    
```

Key

- White arrow: = User Input
- Green arrow: = Data flow
- Light green box: = Input Interface
- Dark blue box: = Calculation engine

Begin the ESCT

Contact Information:

Warren Wang
Associate Director, Navigant, Energy Practice
W.wang@navigant.com

Colette Lamontagne
Director, Navigant, Energy Practice
Colette.Lamontagne@navigant.com

David Feliciano
Senior Consultant, Navigant, Energy Practice
David.Feliciano@navigant.com

Location, Market, Owner, Energy Storage Technology ☒

On this form please indicate the following:
1) The physical location of the energy storage deployment project,
2) The regulatory structure in which the storage deployment will operate in,
3) The owner of the storage device,
4) The type of storage technology the deployment utilizes.

Location

<input checked="" type="radio"/> Generation and Transmission	Definition
<input type="radio"/> Distribution	Definition
<input type="radio"/> End-User	Definition

Market

<input checked="" type="radio"/> Regulated	Definition
<input type="radio"/> Deregulated	Definition

Owner

<input checked="" type="radio"/> Utility	Definition
<input type="radio"/> Non-Utility Merchant/Independent Power Producer	Definition
<input type="radio"/> End-User	Definition

What type of storage technology does the deployment utilize? Battery, Lithium Ion ▼

Exit Next

Parameters

Please enter all of the system parameters for the energy storage deployment.

What is the total nameplate power output (kW)? kW

What is the total nameplate energy storage capacity (kWh)? kWh

What is the response time of the energy storage device(s) deployed? seconds

What is the nameplate round-trip efficiency of the energy storage device(s) deployed? %

What is the nameplate cycle life (cycles) of the energy storage device(s) deployed? cycles

What is the average or expected year over year demand growth of the electric system? %

Does the energy storage device(s) deployed have reactive power capabilities?

Please indicate the NERC Region in which the energy storage deployment is located.

Cost Parameters

Please enter the cost parameters for the energy storage deployment.

What is the expected lifetime (years) of this deployment? years

Please enter the average inflation rate (%) that will be used in the economic calculations. %

Please enter the discount rate (%) that will be used in the net present value analysis. %

Please enter the total installed cost (\$) of the deployment. \$

Please enter the fixed charge rate (%) that will be used to annualize the cost of the deployment. %

Please enter the average yearly operating and maintenance costs (\$/year) not related to energy. These costs may include may include fixed and variable operations and maintenance costs as well as replacement costs. \$/year

If you would prefer to enter a custom operating and maintenance cost schedule please check the box to the right.

Please enter the expected decommissioning and disposal costs (\$) in current nominal dollars. \$

Please enter the initial year (20xx) of this analysis. Year

Σ

Choose Primary Application

Please choose the primary application for this energy storage deployment. The primary application describes how the energy storage deployment will be used for the majority of the year. It is assumed that the primary application will yield the highest value to the owner in terms of benefits.

<input checked="" type="radio"/> Electric Energy Time-shift	<input type="button" value="Definition"/>
<input type="radio"/> Electric Supply Capacity	<input type="button" value="Definition"/>
<input type="radio"/> Load Following	<input type="button" value="Definition"/>
<input type="radio"/> Area Regulation	<input type="button" value="Definition"/>
<input type="radio"/> Electric Supply Reserve Capacity	<input type="button" value="Definition"/>
<input type="radio"/> Voltage Support	<input type="button" value="Definition"/>
<input type="radio"/> Transmission Support	<input type="button" value="Definition"/>
<input type="radio"/> Transmission Congestion Relief	<input type="button" value="Definition"/>
<input type="radio"/> Transmission & Distribution (T&D) Upgrade Deferral	<input type="button" value="Definition"/>
<input type="radio"/> Substation On-site Power	<input type="button" value="Definition"/>
<input type="radio"/> Time-of-use (TOU) Energy Cost Management	<input type="button" value="Definition"/>
<input type="radio"/> Demand Charge Management	<input type="button" value="Definition"/>
<input type="radio"/> Electric Service Reliability	<input type="button" value="Definition"/>
<input type="radio"/> Electric Service Power Quality	<input type="button" value="Definition"/>
<input type="radio"/> Renewables Energy Time-shift	<input type="button" value="Definition"/>
<input type="radio"/> Renewables Capacity Firming	<input type="button" value="Definition"/>
<input type="radio"/> Wind Generation Grid Integration - Short Duration	<input type="button" value="Definition"/>
<input type="radio"/> Wind Generation Grid Integration - Long Duration	<input type="button" value="Definition"/>

Previous

Exit

Next

Choose First Secondary Application ⌵

If applicable, please choose a second secondary application for this energy storage deployment. Secondary applications describe the ways in which the energy storage unit will be used when not being used for the primary application. There are a subset of applications that are especially appropriate given the primary application being pursued and given the technical characteristics of the energy storage technology. These synergistic applications are highlighted in blue.

<input type="radio"/> Electric Energy Time-shift	Definition	<input type="radio"/> Time-of-use (TOU) Energy Cost Management	Definition
<input checked="" type="radio"/> Electric Supply Capacity	Definition	<input type="radio"/> Demand Charge Management	Definition
<input type="radio"/> Load Following	Definition	<input type="radio"/> Electric Service Reliability	Definition
<input type="radio"/> Area Regulation	Definition	<input type="radio"/> Electric Service Power Quality	Definition
<input type="radio"/> Electric Supply Reserve Capacity	Definition	<input checked="" type="radio"/> Renewables Energy Time-shift	Definition
<input type="radio"/> Voltage Support	Definition	<input type="radio"/> Renewables Capacity Firming	Definition
<input type="radio"/> Transmission Support	Definition	<input type="radio"/> Wind Generation Grid Integration - Short Duration	Definition
<input checked="" type="radio"/> Transmission Congestion Relief	Definition	<input checked="" type="radio"/> Wind Generation Grid Integration - Long Duration	Definition
<input checked="" type="radio"/> Transmission & Distribution (T&D) Upgrade Deferral	Definition	<input type="radio"/> No Secondary Applications	
<input type="radio"/> Substation On-site Power	Definition		

Choose Second Secondary Application ⌵

If applicable, please choose a second secondary application for this energy storage deployment. Secondary applications describe the ways in which the energy storage unit will be used when not being used for the primary application. There are a subset of applications that are especially appropriate given the primary application being pursued and given the technical characteristics of the energy storage technology. These synergistic applications are highlighted in blue.

<input type="radio"/> Electric Energy Time-shift	Definition	<input type="radio"/> Time-of-use (TOU) Energy Cost Management	Definition
<input type="radio"/> Electric Supply Capacity	Definition	<input type="radio"/> Demand Charge Management	Definition
<input type="radio"/> Load Following	Definition	<input type="radio"/> Electric Service Reliability	Definition
<input type="radio"/> Area Regulation	Definition	<input type="radio"/> Electric Service Power Quality	Definition
<input type="radio"/> Electric Supply Reserve Capacity	Definition	<input checked="" type="radio"/> Renewables Energy Time-shift	Definition
<input type="radio"/> Voltage Support	Definition	<input type="radio"/> Renewables Capacity Firming	Definition
<input type="radio"/> Transmission Support	Definition	<input type="radio"/> Wind Generation Grid Integration - Short Duration	Definition
<input checked="" type="radio"/> Transmission Congestion Relief	Definition	<input checked="" type="radio"/> Wind Generation Grid Integration - Long Duration	Definition
<input checked="" type="radio"/> Transmission & Distribution (T&D) Upgrade Deferral	Definition	<input type="radio"/> No Secondary Applications	
<input type="radio"/> Substation On-site Power	Definition		

Benefits

The benefits highlighted in blue below represent the benefits that your energy storage project will yield based on primary and secondary applications that are being pursued. For further explanation of a benefit click the button to the right of the benefit.

Arbitrage Revenue	Definition	Deferred Transmission Investments	Definition
Capacity Market Revenue	Definition	Deferred Distribution Investments	Definition
Ancillary Services Revenue	Definition	Deferred Generation Capacity Investments	Definition
Reduced Electricity Cost (Consumer)	Definition	Reduced Outages (Consumer)	Definition
Reduced Electricity Cost (Utility/Ratepayer)	Definition	Reduced Outages (Utility/Ratepayer)	Definition
Reduced Congestion Costs (Non-Utility Merchant)	Definition	Improved Power Quality	Definition
Reduced Congestion Costs (Utility/Ratepayer)	Definition	Reduced CO2 Emissions	Definition
Optimized Generator Operation (Non-Utility Merchant)	Definition	Reduced SOx Emissions	Definition
Optimized Generator Operation (Utility/Ratepayer)	Definition	Reduced NOx Emissions	Definition
Reduced Electricity Losses	Definition	Reduced PM Emissions	Definition

Previous Finish

Verify the Applications and Benefits of the Project

Below is a table that summarizes the benefits that your project will yield. Each row represents a primary or secondary application your project is pursuing. All of the benefits a project could yield are listed along the top of the chart. Based on each row in the ADM, this chart has been populated with the benefits that your project may yield along with the applications that will lead to the benefits. Therefore, this chart should graphically summarize the objectives and expected benefits of your project. If the chart adequately summarizes your project click the blue button on the left to proceed to the next phase of the tool. If the chart does not adequately summarize your project click the button to the right to return to the ADM entry screen and adjust your inputs accordingly.

[Return to the Data Input Module \(DIM\)](#)
[Return to the Asset Characterization Module \(ADM\)](#)

Application vs. Benefits Matrix

Application	Market	Owner	Application	Arbitrage Revenue	Capacity Market Revenue	Ancillary Services Revenue	Reduced Electricity Cost (Non-Utility Merchant)	Reduced Electricity Cost (Utility/Ratepayer)	Reduced Congestion Costs (Non-Utility Merchant)	Reduced Congestion Costs (Utility/Ratepayer)	Optimized Generator Operation (Non-Utility Merchant)	Optimized Generator Operation (Utility/Ratepayer)	Reduced Electricity Losses	Deferred Transmission Investments	Deferred Distribution Investments	Deferred Generation Capacity Investments	Reduced Outages (Consumer)	Reduced Outages (Utility/Ratepayer)	Improved Power Quality	Reduced CO2 Emissions	Reduced SOx Emissions	Reduced NOx Emissions	Reduced PM Emissions
Generation and Transmission	Regulated	Utility	Storage Energy (Time-Shift)																				
Generation and Transmission	Regulated	Utility	Electric Supply (Electricity)																				
Generation and Transmission	Regulated	Utility	Transmission & Distribution (T&D) Upgrade (Deferral)																				

V.2 Data Input Module (DIM)

Data Input Module

Use the table below to enter the project data that will be used to calculate benefits. For each input the user must enter data for at least one project year before being able to submit entries and complete this step. When all data has been entered click the blue button at the bottom of the table to submit and store the data entries. If pasting data from another source into this table please use the "Paste Value" function to avoid changing cell formatting or pasting formulas. If the user does not have measured data to enter, they can leverage default values for most of the inputs. However, if default values are used the user should take care in interpreting the results since the default values tend to be general estimates, and the actual values for the user's project may vary greatly. Furthermore, default values do not take into account situations in which energy storage deployments are being used for multiple applications, rather they assume the storage is being used for a single application for an entire year. Therefore, if multiple applications are being pursued and default values are being used, the user must ensure that the default amount of energy discharge for each application is realistic considering that the storage is being used for more than one application throughout the year.

Data Input Module:
Requires the data input required to calculate the energy storage benefits.

Return to the Asset Characterization Module (ACM)

Input Name	Units	Input Definition	Default Values	Values				
				100	101	102	103	104
Total Energy Discharged for Arbitrage	MWh	The total amount of energy discharged from the energy storage device and used for arbitrage purposes over a year.	Enter Custom	\$ -	\$ -	\$ -	\$ -	\$ -
Total Energy Discharged for Energy Time-Shift	MWh	The total amount of energy discharged from the energy storage device for the purposes of shifting energy from an off-peak time to an on-peak time. This may allow a utility to decrease their costs by offsetting the need to run less efficient, more expensive peaking units.	Enter Custom	267	267	267	267	267
Average Variable Peak Generation Costs	\$/MWh	The average variable generation costs for marginal generation units used to meet peak demand.	Enter Custom	\$ 41	\$ 41	\$ 41	\$ 41	\$ 41
Average Variable Off-Peak Generation Costs	\$/MWh	The average variable generation costs for base load generation units.	Enter Custom	\$ 23	\$ 23	\$ 23	\$ 23	\$ 23
CO2 Emissions Factor for Generation on the Margin	lbs/MWh	The characteristic or average CO2 emissions factor for marginal generation units used to meet peak demand.	Use Default	1,151	1,151	1,151	1,151	1,151
CO2 Emissions Factor for Base Generation	lbs/MWh	The characteristic or average CO2 emissions factor for base load generation units.	Use Default	2,251	2,251	2,251	2,251	2,251
SOx Emissions Factor for Generation on the Margin	lbs/MWh	The characteristic or average SOx emissions factor for marginal generation units used to meet peak demand.	Use Default	0.012	0.012	0.012	0.012	0.012
SOx Emissions Factor for Base Generation	lbs/MWh	The characteristic or average SOx emissions factor for base load generation units.	Use Default	6.67	6.67	6.67	6.67	6.67
NOx Emissions Factor for Generation on the Margin	lbs/MWh	The characteristic or average NOx emissions factor for marginal generation units used to meet peak demand.	Use Default	1.41	1.41	1.41	1.41	1.41
NOx Emissions Factor for Base Generation	lbs/MWh	The characteristic or average NOx emissions factor for base load generation units.	Use Default	3.73	3.73	3.73	3.73	3.73
PM Emissions Factor for Generation on the Margin	lbs/MWh	The characteristic or average PM emissions factor for marginal generation units used to meet peak demand.	Use Default	0.040	0.040	0.040	0.040	0.040
PM Emissions Factor for Base Generation	lbs/MWh	The characteristic or average PM emissions factor for base load generation units.	Use Default	0.200	0.200	0.200	0.200	0.200
Value of CO2	\$/ton	The anticipated or current market price of carbon emissions.	Use Default	\$ 20	\$ 20	\$ 20	\$ 20	\$ 20
Value of SOx	\$/ton	The anticipated or current market price of SOx emissions.	Use Default	\$ 520	\$ 520	\$ 520	\$ 520	\$ 520
Value of NOx	\$/ton	The anticipated or current market price of NOx emissions.	Use Default	\$ 3,000	\$ 3,000	\$ 3,000	\$ 3,000	\$ 3,000
Value of PM	\$/ton	The anticipated or current market price of PM emissions.	Use Default	\$ 36,000	\$ 36,000	\$ 36,000	\$ 36,000	\$ 36,000
Generation Capacity Deferred	MW	The size of the generation investment deferred as a result of installing energy storage. Please only enter a single value per deferral in the initial year of deferral. If there is no deferral in a given year, leave that entry cell blank.	Enter Custom	-	1	-	-	-
Capital Cost of Deferred Generation Capacity	\$/MW	The base overnight capital cost of the deferred generation investment. Please only enter a single value per deferral in the initial year of deferral. If there is no deferral in a given year, leave that entry cell blank.	Enter Custom	\$ -	\$ 1,227,000	\$ -	\$ -	\$ -
Yearly O&M Costs of Deferred Generation Capacity	\$/MW-year	The expected fixed yearly operations and maintenance costs of the deferred generation investment. Please only enter a single value per deferral in the initial year of deferral. If there is no deferral in a given year, leave that entry cell blank.	Enter Custom	\$ -	\$ 14,000	\$ -	\$ -	\$ -
Annual Fixed Charge Rate for Generation Capital Investment	%	The rate used to convert capital plant installed cost into an annuity equivalent (payment) representing annual carrying charges for capital equipment. It includes consideration of interest and equity return rates, annual interest payments and return of debt principal, dividends and return of equity principal, income taxes, and property taxes. Please only enter a single value per deferral in the initial year of deferral. If there is no deferral in a given year, leave that entry cell blank.	Enter Custom	10	10	10	10	10
Initial Year of Generation Deferral	year	The first year that generation is deferred. Enter the value in 20XX format. Please only enter a single value per deferral in the initial year of deferral. If there is no deferral in a given year, leave that entry cell blank.	Enter Custom	0	2014	0	0	0
Final year of Generation Deferral	year	The last year that generation is deferred. Enter the value in 20XX format. Please only enter a single value per deferral in the initial year of deferral. If there is no deferral in a given year, leave that entry cell blank.	Enter Custom	0	2023	0	0	0
Transmission Capacity Deferred	kVA	The size of the transmission investment deferred as a result of installing energy storage. Please only enter a single value per deferral in the initial year of deferral. If there is no deferral in a given year, leave that entry cell blank.	Enter Custom	-	500	-	-	-
Annual Fixed Charge Rate for Transmission Capital Investment	%	The rate used to convert capital transmission installed cost into an annuity equivalent (payment) representing annual carrying charges for capital equipment. It includes consideration of interest and equity return rates, annual interest payments and return of debt principal, dividends and return of equity principal, income taxes, and property taxes. Please only enter a single value per deferral in the initial year of deferral. If there is no deferral in a given year, leave that entry cell blank.	Enter Custom	10	10	10	10	10
Capital Cost of Deferred Transmission Capacity	\$/kVA	The base overnight capital cost of the deferred transmission investment. Please only enter a single value per deferral in the initial year of deferral. If there is no deferral in a given year, leave that entry cell blank.	Enter Custom	\$ -	\$ 319	\$ -	\$ -	\$ -
Yearly O&M Costs of Deferred Transmission Capacity	\$/year	The expected fixed yearly operations and maintenance costs of the deferred transmission investment. Please only enter a single value per deferral in the initial year of deferral. If there is no deferral in a given year, leave that entry cell blank.	Use Default	\$ -	-	-	-	-
Initial Year of Transmission Deferral	year	The first year that transmission is deferred. Enter the value in 20XX format. Please only enter a single value per deferral in the initial year of deferral. If there is no deferral in a given year, leave that entry cell blank.	Enter Custom	0	2014	0	0	0
Final year of Transmission Deferral	year	The last year that transmission is deferred. Enter the value in 20XX format.	Enter Custom	0	2023	0	0	0
END			END					

Finish Data Entry

Review Benefit Calculation Inputs											
The table below contains the benefit calculation inputs that will be fed into the next phase of the Energy Storage Computational Tool. The purpose of this page is to give the user the opportunity to review the data before proceeding to the next phase of the tool. If the user finds data that has been entered erroneously, or if the user wishes to edit an entry they should navigate to back to the DIM and make the appropriate changes.											
Input Name	Units	Entered Data					Projected Data				
		2013	2014	2015	2016	2017	2018	2019	2020	2021	2022
Total Energy Discharged for Arbitrage	MWh	-	-	-	-	-	-	-	-	-	-
Total Energy Discharged for Energy Time-Shift	MWh	267	267	267	267	267	267	267	267	267	267
Average Variable Peak Generation Costs	\$/MWh	\$ 41	\$ 41	\$ 41	\$ 41	\$ 41	42	43	44	45	46
Average Variable Off-Peak Generation Costs	\$/MWh	\$ 23	\$ 23	\$ 23	\$ 23	\$ 23	23	24	24	25	25
CO2 Emissions Factor for Generation on the Margin	lbs/MWh	1,150.808500	1,150.808500	1,150.808500	1,150.808500	1,150.808500	1,151	1,151	1,151	1,151	1,151
CO2 Emissions Factor for Base Generation	lbs/MWh	2,251.176500	2,251.176500	2,251.176500	2,251.176500	2,251.176500	2,251	2,251	2,251	2,251	2,251
SOx Emissions Factor for Generation on the Margin	lbs/MWh	0.012200	0.012200	0.012200	0.012200	0.012200	0	0	0	0	0
SOx Emissions Factor for Base Generation	lbs/MWh	6.670700	6.670700	6.670700	6.670700	6.670700	7	7	7	7	7
NOx Emissions Factor for Generation on the Margin	lbs/MWh	1.411100	1.411100	1.411100	1.411100	1.411100	1	1	1	1	1
NOx Emissions Factor for Base Generation	lbs/MWh	3.731100	3.731100	3.731100	3.731100	3.731100	4	4	4	4	4
PM Emissions Factor for Generation on the Margin	lbs/MWh	0.040000	0.040000	0.040000	0.040000	0.040000	0	0	0	0	0
PM Emissions Factor for Base Generation	lbs/MWh	0.200000	0.200000	0.200000	0.200000	0.200000	0	0	0	0	0
Value of CO2	\$/ton	\$ 20	\$ 20	\$ 20	\$ 20	\$ 20	\$ 20	\$ 21	\$ 21	\$ 22	\$ 22
Value of SOx	\$/ton	\$ 520	\$ 520	\$ 520	\$ 520	\$ 520	\$ 531	\$ 542	\$ 553	\$ 565	\$ 577
Value of NOx	\$/ton	\$ 3,000	\$ 3,000	\$ 3,000	\$ 3,000	\$ 3,000	\$ 3,063	\$ 3,127	\$ 3,193	\$ 3,260	\$ 3,329
Value of PM	\$/ton	\$ 36,000	\$ 36,000	\$ 36,000	\$ 36,000	\$ 36,000	\$ 36,756	\$ 37,528	\$ 38,316	\$ 39,121	\$ 39,942
Generation Capacity Deferred	MW	-	1	-	-	-	-	-	-	-	-
Capital Cost of Deferred Generation Capacity	\$/MW	\$ -	\$ 1,227,000	\$ -	\$ -	\$ -	-	-	-	-	-
Yearly O&M Costs of Deferred Generation Capacity	\$/MW-year	\$ -	\$ 14,000	\$ -	\$ -	\$ -	-	-	-	-	-
Annual Fixed Charge Rate for Generation Capital Investment	%	10	10	10	10	10	10	10	10	10	10
Initial Year of Generation Deferral	year	0	2014	0	0	0	-	-	-	-	-
Final year of Generation Deferral	year	0	2023	0	0	0	-	-	-	-	-
Transmission Capacity Deferred	kVA	-	500	-	-	-	-	-	-	-	-
Annual Fixed Charge Rate for Transmission Capital Investment	%	10	10	10	10	10	10	10	10	10	10
Capital Cost of Deferred Transmission Capacity	\$/kVA	\$ -	\$ 319	\$ -	\$ -	\$ -	-	-	-	-	-
Yearly O&M Costs of Deferred Transmission Capacity	\$/year	-	-	-	-	-	-	-	-	-	-
Initial Year of Transmission Deferral	year	0	2014	0	0	0	-	-	-	-	-
Final year of Transmission Deferral	year	0	2023	0	0	0	-	-	-	-	-

V.3 Computational Module (CM)

Computational Module (CM) Main Page

Instructions

Welcome to the Computational Module (CM) phase of the Energy Storage Computational Tool (ESCT). The CM is the calculation engine of the tool, it crunches the numbers and generates the output. The CM also allows the user to complete a sensitivity analysis if desired.

Running the CM with Reference Inputs - To run the CM with the inputs that were entered in the DIM phase, simply click the button in the "Reference Case" section that says "Run CM with Reference Case Inputs". The CM will take about 20 seconds to complete the analysis. Once the analysis is complete the results can be viewed by clicking the "View Reference Case Results" button.

Running the a Sensitivity Analysis - Before running a sensitivity analysis the CM should be run with the reference case inputs by following the directions above. To run a sensitivity analysis first change the High and Low sensitivity ranges of the desired inputs by using the toggles that are to the right of every input. After all of the desired sensitivity ranges have been set click the button in the "Sensitivity Analysis" section that says "Run CM with Sensitivity Case Inputs". The CM will take about a 40 seconds to complete the analysis. Once the analysis is complete the results can be viewed by clicking the "View Sensitivity Results" button. All of the sensitivity ranges can be reset to 100% by clicking the button above the toggle switches that says "Reset all values to 100%".



Reference Case

Run CM with Reference Case Inputs

View Reference Case Results

Sensitivity Analysis

Run CM with Sensitivity Case Inputs

View Sensitivity Results

Reset all values to 100%

Input Name	Unit	Select % using toggle			2013 Values		
		Low	Reference	High	Low	Reference	High
Total Energy Discharged for Arbitrage	MWh	100%	100%	100%	\$ -	\$ -	\$ -
Total Energy Discharged for Energy Time-Shift	MWh	100%	100%	100%	267	267	267
Average Variable Peak Generation Costs	\$/MWh	100%	100%	100%	\$ 41	\$ 41	\$ 41
Average Variable Off-Peak Generation Costs	\$/MWh	100%	100%	100%	\$ 23	\$ 23	\$ 23
CO2 Emissions Factor for Generation on the Margin	lbs/MWh	100%	100%	100%	1,151	1,151	1,151
CO2 Emissions Factor for Base Generation	lbs/MWh	100%	100%	100%	2,251	2,251	2,251
SOx Emissions Factor for Generation on the Margin	lbs/MWh	100%	100%	100%	0.012	0.012	0.012
SOx Emissions Factor for Base Generation	lbs/MWh	100%	100%	100%	6.67	6.67	6.67
NOx Emissions Factor for Generation on the Margin	lbs/MWh	100%	100%	100%	1.41	1.41	1.41
NOx Emissions Factor for Base Generation	lbs/MWh	100%	100%	100%	3.73	3.73	3.73
PM Emissions Factor for Generation on the Margin	lbs/MWh	100%	100%	100%	0.040	0.040	0.040
PM Emissions Factor for Base Generation	lbs/MWh	100%	100%	100%	0.200	0.200	0.200
Value of CO2	\$/ton	100%	100%	100%	\$ 20	\$ 20	\$ 20
Value of SOx	\$/ton	100%	100%	100%	\$ 520	\$ 520	\$ 520
Value of NOx	\$/ton	100%	100%	100%	\$ 3,000	\$ 3,000	\$ 3,000
Value of PM	\$/ton	100%	100%	100%	\$ 36,000	\$ 36,000	\$ 36,000
Generation Capacity Deferred	MW	100%	100%	100%	-	-	-
Capital Cost of Deferred Generation Capacity	\$/MW	100%	100%	100%	\$ -	\$ -	\$ -
Yearly O&M Costs of Deferred Generation Capacity	\$/MW-year	100%	100%	100%	\$ -	\$ -	\$ -
Annual Fixed Charge Rate for Generation Capital Investment	%	100%	100%	100%	10	10	10
Initial Year of Generation Deferral	year	100%	100%	100%	0	0	0
Final year of Generation Deferral	year	100%	100%	100%	0	0	0
Transmission Capacity Deferred	kVA	100%	100%	100%	-	-	-
Annual Fixed Charge Rate for Transmission Capital Investment	%	100%	100%	100%	10	10	10
Capital Cost of Deferred Transmission Capacity	\$/kVA	100%	100%	100%	\$ -	\$ -	\$ -
Yearly O&M Costs of Deferred Transmission Capacity	\$/year	100%	100%	100%	\$ -	\$ -	\$ -
Initial Year of Transmission Deferral	year	100%	100%	100%	0	0	0
Final year of Transmission Deferral	year	100%	100%	100%	0	0	0

Reference Case Output: Annual and Cumulative Results Tables


The tables below display the annual and cumulative project benefits and costs. The benefits are organized by category. The total gross benefit, total cost, and net benefit are also displayed at the bottom of each chart. All values are present value terms. To calculate additional benefits navigate to the additional benefits worksheets from the Additional Benefits tab.

Annual Benefit and Cost Table


		Additional Benefits - Total Present Value over the Deployment Period	+	Primary and Secondary Benefits - Total Present Value over the Deployment Period	=	Total Benefit - Present Value over the Deployment Period	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022
Benefits																
Market Revenue	Arbitrage Revenue	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Capacity Market Revenue	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Ancillary Services Revenue	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Improved Asset Utilization	Optimized Generator Operation (Non-Utility Merchant)	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Optimized Generator Operation (Utility/Ratepayer)	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Deferred Generation Capacity Investments	\$ -		\$ 106,500		\$ 106,500	\$ -	\$ 106,500	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Reduced Congestion Costs (Non-Utility Merchant)	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
T&D Capital Savings	Deferred Transmission Investments	\$ -		\$ 15,600		\$ 15,600	\$ -	\$ 15,600	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Deferred Distribution Investments	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Energy Efficiency	Reduced Electricity Losses	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Reduced Electricity Cost (Consumer)	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Electricity Cost Savings	Reduced Electricity Cost (Utility/Ratepayer)	\$ -		\$ 38,400		\$ 38,400	\$ 5,000	\$ 4,700	\$ 4,300	\$ 4,100	\$ 3,800	\$ 3,600	\$ 3,500	\$ 3,300	\$ 3,100	\$ 3,000
	Reduced Outages (Consumer)	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Power Interruptions	Reduced Outages (Utility/Ratepayer)	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Improved Power Quality	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Air Emissions	Reduced CO2 Emissions	\$ -		\$ (22,400)		\$ (22,400)	\$ (2,900)	\$ (2,700)	\$ (2,600)	\$ (2,400)	\$ (2,200)	\$ (2,100)	\$ (2,000)	\$ (1,900)	\$ (1,800)	\$ (1,800)
	Reduced SOx Emissions	\$ -		\$ (3,600)		\$ (3,600)	\$ (500)	\$ (400)	\$ (400)	\$ (400)	\$ (400)	\$ (300)	\$ (300)	\$ (300)	\$ (300)	\$ (300)
	Reduced NOx Emissions	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Reduced PM Emissions	\$ -		\$ (6,000)		\$ (6,000)	\$ (800)	\$ (700)	\$ (700)	\$ (600)	\$ (600)	\$ (600)	\$ (500)	\$ (500)	\$ (500)	\$ (500)
Total Gross Benefit		\$ -		\$ 128,500		\$ 128,500	\$ 800	\$ 123,000	\$ 600	\$ 700	\$ 600	\$ 600	\$ 700	\$ 600	\$ 500	\$ 400
Costs																
Capital Cost of Deployment (fixed charge rate)				\$ 3,859,700		\$ 3,859,700	\$ 514,500	\$ 480,600	\$ 449,000	\$ 419,400	\$ 391,800	\$ 366,000	\$ 341,900	\$ 319,400	\$ 298,400	\$ 278,700
Operating and maintenance costs not related to energy (labor for operation, plant maintenance, equipment wear leading to loss-of-life)				\$ 157,500		\$ 157,500	\$ 21,000	\$ 19,600	\$ 18,300	\$ 17,100	\$ 16,000	\$ 14,900	\$ 14,000	\$ 13,000	\$ 12,200	\$ 11,400
Decommissioning and Disposal Costs				\$ 79,900		\$ 79,900	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 79,900
Total Annual Cost of Deployment				\$ 4,097,300		\$ 4,097,300	\$ 535,500	\$ 500,300	\$ 467,300	\$ 436,500	\$ 407,800	\$ 381,000	\$ 355,900	\$ 332,400	\$ 310,600	\$ 370,000
Total Net Benefit				\$ (3,968,800)		\$ (3,968,800)	\$ (534,700)	\$ (377,300)	\$ (466,700)	\$ (435,800)	\$ (407,200)	\$ (380,400)	\$ (355,200)	\$ (331,800)	\$ (310,100)	\$ (369,600)

Cumulative Benefit and Cost Table


		Additional Benefits - Total Present Value over the Deployment Period	+	Primary and Secondary Benefits - Total Present Value over the Deployment Period	=	Total Benefit - Present Value over the Deployment Period	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022
Benefits																
Market Revenue	Arbitrage Revenue	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Capacity Market Revenue	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Ancillary Services Revenue	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Improved Asset Utilization	Optimized Generator Operation (Non-Utility Merchant)	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Optimized Generator Operation (Utility/Ratepayer)	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Deferred Generation Capacity Investments	\$ -		\$ 106,500		\$ 106,500	\$ -	\$ 106,500	\$ 106,500	\$ 106,500	\$ 106,500	\$ 106,500	\$ 106,500	\$ 106,500	\$ 106,500	\$ 106,500
	Reduced Congestion Costs (Non-Utility Merchant)	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
T&D Capital Savings	Deferred Transmission Investments	\$ -		\$ 15,600		\$ 15,600	\$ -	\$ 15,600	\$ 15,600	\$ 15,600	\$ 15,600	\$ 15,600	\$ 15,600	\$ 15,600	\$ 15,600	\$ 15,600
	Deferred Distribution Investments	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Energy Efficiency	Reduced Electricity Losses	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Reduced Electricity Cost (Consumer)	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Electricity Cost Savings	Reduced Electricity Cost (Utility/Ratepayer)	\$ -		\$ 38,400		\$ 38,400	\$ 5,000	\$ 9,700	\$ 14,000	\$ 18,100	\$ 21,900	\$ 25,500	\$ 29,000	\$ 32,300	\$ 35,400	\$ 38,400
	Reduced Outages (Consumer)	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Power Interruptions	Reduced Outages (Utility/Ratepayer)	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Improved Power Quality	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Air Emissions	Reduced CO2 Emissions	\$ -		\$ (22,400)		\$ (22,400)	\$ (2,900)	\$ (5,600)	\$ (8,200)	\$ (10,600)	\$ (12,800)	\$ (14,900)	\$ (16,900)	\$ (18,800)	\$ (20,600)	\$ (22,400)
	Reduced SOx Emissions	\$ -		\$ (3,600)		\$ (3,600)	\$ (500)	\$ (900)	\$ (1,300)	\$ (1,700)	\$ (2,100)	\$ (2,400)	\$ (2,700)	\$ (3,000)	\$ (3,300)	\$ (3,600)
	Reduced NOx Emissions	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Reduced PM Emissions	\$ -		\$ (6,000)		\$ (6,000)	\$ (800)	\$ (1,500)	\$ (2,200)	\$ (2,800)	\$ (3,400)	\$ (4,000)	\$ (4,500)	\$ (5,000)	\$ (5,500)	\$ (6,000)
Total Gross Benefit		\$ -		\$ 128,500		\$ 128,500	\$ 800	\$ 123,800	\$ 124,400	\$ 125,100	\$ 125,700	\$ 126,300	\$ 127,000	\$ 127,600	\$ 128,100	\$ 128,500
Costs																
Capital Cost of Deployment (fixed charge rate)				\$ 3,859,700		\$ 3,859,700	\$ 514,500	\$ 995,100	\$ 1,444,100	\$ 1,863,500	\$ 2,255,300	\$ 2,621,300	\$ 2,963,200	\$ 3,282,600	\$ 3,581,000	\$ 3,859,700
Operating and maintenance costs not related to energy (labor for operation, plant maintenance, equipment wear leading to loss-of-life)				\$ 157,500		\$ 157,500	\$ 21,000	\$ 40,600	\$ 58,900	\$ 76,000	\$ 92,000	\$ 106,900	\$ 120,900	\$ 133,900	\$ 146,100	\$ 157,500
Decommissioning and Disposal Costs				\$ 79,900		\$ 79,900	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 79,900
Total Annual Cost of Deployment				\$ 4,097,300		\$ 4,097,300	\$ 535,500	\$ 1,035,800	\$ 1,503,100	\$ 1,939,600	\$ 2,347,400	\$ 2,728,400	\$ 3,084,300	\$ 3,416,700	\$ 3,727,300	\$ 4,097,300
Total Net Benefit				\$ (3,968,800)		\$ (3,968,800)	\$ (534,700)	\$ (912,000)	\$ (1,378,700)	\$ (1,814,500)	\$ (2,221,700)	\$ (2,602,100)	\$ (2,957,300)	\$ (3,289,100)	\$ (3,599,200)	\$ (3,968,800)



Cumulative Gross Benefits over the Deployment Period (Present Value)		Lifetime Benefit per kW of Energy Storage Installed
Arbitrage Revenue	\$ -	\$ -
Capacity Market Revenue	\$ -	\$ -
Ancillary Services Revenue	\$ -	\$ -
Optimized Generator Operation (Non-Utility Merchant)	\$ -	\$ -
Optimized Generator Operation (Utility/Ratepayer)	\$ -	\$ -
Deferred Generation Capacity Investments	\$ 106,500	\$ 107
Reduced Congestion Costs (Non-Utility Merchant)	\$ -	\$ -
Reduced Congestion Costs (Utility/Ratepayer)	\$ -	\$ -
Deferred Transmission Investments	\$ 15,600	\$ 16
Deferred Distribution Investments	\$ -	\$ -
Reduced Electricity Losses	\$ -	\$ -
Reduced Electricity Cost (Consumer)	\$ -	\$ -
Reduced Electricity Cost (Utility/Ratepayer)	\$ 38,400	\$ 38
Reduced Outages (Consumer)	\$ -	\$ -
Reduced Outages (Utility/Ratepayer)	\$ -	\$ -
Improved Power Quality	\$ -	\$ -
Reduced Emissions	\$ -	\$ -
Total Gross Benefit	\$ 160,500	\$ 161



	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022
Gross Benefit (Present Value Dollars)	\$ 800	\$ 123,000	\$ 600	\$ 700	\$ 600	\$ 600	\$ 700	\$ 600	\$ 500	\$ 400
Total Annual Cost of Deployment (Present Value Dollars)	\$ (535,500)	\$ (500,300)	\$ (467,300)	\$ (436,500)	\$ (407,800)	\$ (381,000)	\$ (355,900)	\$ (332,400)	\$ (310,600)	\$ (370,000)
Net Benefit (Present Value Dollars)	\$ (534,700)	\$ (377,300)	\$ (466,700)	\$ (435,800)	\$ (407,200)	\$ (380,400)	\$ (355,200)	\$ (331,800)	\$ (310,100)	\$ (369,600)



	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022
Cumulative Gross Benefit (Present Value Dollars)	\$ 800	\$ 123,800	\$ 124,400	\$ 125,100	\$ 125,700	\$ 126,300	\$ 127,000	\$ 127,600	\$ 128,100	\$ 128,500
Cumulative Cost of Deployment (Present Value Dollars)	\$ (535,500)	\$ (1,035,800)	\$ (1,503,100)	\$ (1,939,600)	\$ (2,347,400)	\$ (2,728,400)	\$ (3,084,300)	\$ (3,416,700)	\$ (3,727,300)	\$ (4,097,300)
Cumulative Net Benefit (Present Value Dollars)	\$ (534,700)	\$ (912,000)	\$ (1,378,700)	\$ (1,814,500)	\$ (2,221,700)	\$ (2,602,100)	\$ (2,957,300)	\$ (3,289,100)	\$ (3,599,200)	\$ (3,968,800)

This page intentionally blank.

Appendix W Energy Storage Computational Tool Analysis – Premise

W.1	Asset Characterization Module (ACM)	W-2
W.2	Data Input Module (DIM)	W-8
W.3	Computational Module (CM)	W-10

W.1 Asset Characterization Module (ACM)

U.S. Department of Energy Storage Computational Tool (ESCT) Version 1.2

Purpose of Tool: ESCT guides the user through an analysis to calculate the benefits of an energy storage deployment, compare costs and benefits, and gain a clearer understanding of the value of energy storage technology in terms of monetary benefit. Furthermore, the ESCT can be used to analyze how the costs and benefits vary given different scenarios and assumptions.

Explanation of Output: The output of the ESCT consists of charts, graphs and tables that summarize the benefits and costs of an energy storage deployment. The benefits are monetized and calculated from actual or estimated metrics collected in the first five years of a project lifetime. Based on up to five years of data benefits can be projected out to 40 years in the future. The output also includes charts, graphs and tables that summarize the results of a sensitivity analysis. The user is able to set a high and low sensitivity range for each input in the tool and the output shows how the benefits are affected by variability of the inputs.

Directions: The ESCT is designed to be user-friendly and easy to navigate. However, it will be useful to review the overall methodology of the tool before beginning a new analysis. The diagram below illustrates the tool architecture and the analysis methodology. The tool is divided into three distinct phases: the Asset Characterization Module (ACM), the Data Input Module (DIM), and the Computational Module (CM). The first phase, the ACM, collects information about the deployment such as characteristics of the energy storage technology, cost information, and the applications the deployment will be used for. From this input, the ACM determines a list of benefits that the project could yield. These potential project benefits are then fed into the second phase of the tool, the DIM. The DIM uses the list of benefits to determine the inputs required to calculate the benefits. The DIM then helps the user navigate through the process of entering the required data. The DIM's main purpose is to ensure that all the required data is entered in the proper format so that the benefits can be analyzed successfully. The input data is then fed into the final phase, the CM. The CM is the calculation engine of the tool, it crunches the numbers and generates the output. The CM also allows the user to carry out a sensitivity analysis if desired. To start a new analysis, click the blue button below and follow the directions that appear in each phase of the tool.

```

graph TD
    subgraph Module1 [Module 1]
        A[Asset Location, Market and Applications] --> B[Asset Characterization Module: Characterizes how the storage asset will be used. Determines benefits the project will yield.]
    end
    subgraph Module2 [Module 2]
        C[Project Data] --> D[Data Input Module: Facilitates the data input required to calculate the energy storage benefits.]
    end
    subgraph Module3 [Module 3]
        E[Computational Module: Calculates and projects storage benefits; carries out sensitivity analysis.]
    end
    B -- "Energy storage benefits" --> D
    D -- "Project Data" --> E
    F[Sensitivity Ranges] --> G[Sensitivity Analysis Input Interface (Optional): Allows the user to set the sensitivity range for specific variables (e.g. value of CO2).]
    G -- "Sensitivity ranges" --> E
    E --> H[Results]
    
```

Key

- = User Input
- = Input Interface
- = Data flow
- = Calculation engine

Begin the ESCT

Contact Information:

Warren Wang
Associate Director, Navigant, Energy Practice
W.wang@navigant.com

Colette Lamontagne
Director, Navigant, Energy Practice
Colette.Lamontagne@navigant.com

David Feliciano
Senior Consultant, Navigant, Energy Practice
David.Feliciano@navigant.com

V2.0 05/22/2015

W-2

Location, Market, Owner, Energy Storage Technology ✕

On this form please indicate the following:
1) The physical location of the energy storage deployment project,
2) The regulatory structure in which the storage deployment will operate in,
3) The owner of the storage device,
4) The type of storage technology the deployment utilizes.

Location

<input type="radio"/> Generation and Transmission	Definition
<input type="radio"/> Distribution	Definition
<input checked="" type="radio"/> End-User	Definition

Market

<input checked="" type="radio"/> Regulated	Definition
<input type="radio"/> Deregulated	Definition

Owner

<input type="radio"/> Utility	Definition
<input type="radio"/> Non-Utility Merchant/Independent Power Producer	Definition
<input checked="" type="radio"/> End-User	Definition

What type of storage technology does the deployment utilize?

Parameters
⌵

Please enter all of the system parameters for the energy storage deployment.

What is the total nameplate power output (kW)?	<input type="text" value="6"/>	kW	<input type="button" value="Use Default Value"/>	<input type="button" value="Definition"/>
What is the total nameplate energy storage capacity (kWh)?	<input type="text" value="12"/>	kWh	<input type="button" value="Use Default Value"/>	<input type="button" value="Definition"/>
What is the response time of the energy storage device(s) deployed?	<input type="text" value="0.005"/>	seconds	<input type="button" value="Use Default Value"/>	
What is the nameplate round-trip efficiency of the energy storage device(s) deployed?	<input type="text" value="86.45"/>	%	<input type="button" value="Use Default Value"/>	
What is the nameplate cycle life (cycles) of the energy storage device(s) deployed?	<input type="text" value="5,000"/>	cycles	<input type="button" value="Use Default Value"/>	<input type="button" value="Definition"/>
What is the average or expected year over year demand growth of the electric system?	<input type="text" value="1.8"/>	%	<input type="button" value="Use Default Value"/>	
Does the energy storage device(s) deployed have reactive power capabilities?	<input type="text" value="No"/>		<input type="button" value="Use Default Value"/>	
Please indicate the NERC Region in which the energy storage deployment is located.	<input type="text" value="SPP North"/>			

Cost Parameters
⌵

Please enter the cost parameters for the energy storage deployment.

What is the expected lifetime (years) of this deployment?	<input type="text" value="10"/>	years	<input type="button" value="Use Default Value"/>	
Please enter the average inflation rate (%) that will be used in the economic calculations.	<input type="text" value="2.1"/>	%	<input type="button" value="Use Default Value"/>	<input type="button" value="Definition"/>
Please enter the discount rate (%) that will be used in the net present value analysis.	<input type="text" value="5"/>	%	<input type="button" value="Use Default Value"/>	<input type="button" value="Definition"/>
Please enter the total installed cost (\$) of the deployment.	<input type="text" value="24,000"/>	\$	<input type="button" value="Use Default Value"/>	
Please enter the fixed charge rate (%) that will be used to annualize the cost of the deployment.	<input type="text" value="15"/>	%	<input type="button" value="Use Default Value"/>	
Please enter the average yearly operating and maintenance costs (\$/year) not related to energy. These costs may include may include fixed and variable operations and maintenance costs as well as replacement costs.	<input type="text" value="126"/>	\$/year	<input type="button" value="Use Default Value"/>	
If you would prefer to enter a custom operating and maintenance cost schedule please check the box to the right.	<input type="checkbox"/>			
Please enter the expected decommissioning and disposal costs (\$) in current nominal dollars.	<input type="text" value="885"/>	\$	<input type="button" value="Use Default Value"/>	
Please enter the initial year (20xx) of this analysis.	<input type="text" value="2014"/>	Year		

Choose Primary Application
✕

Please choose the primary application for this energy storage deployment. The primary application describes how the energy storage deployment will be used for the majority of the year. It is assumed that the primary application will yield the highest value to the owner in terms of benefits.

<input type="radio"/> Electric Energy Time-shift	<input type="button" value="Definition"/>
<input type="radio"/> Electric Supply Capacity	<input type="button" value="Definition"/>
<input type="radio"/> Load Following	<input type="button" value="Definition"/>
<input type="radio"/> Area Regulation	<input type="button" value="Definition"/>
<input type="radio"/> Electric Supply Reserve Capacity	<input type="button" value="Definition"/>
<input type="radio"/> Voltage Support	<input type="button" value="Definition"/>
<input type="radio"/> Transmission Support	<input type="button" value="Definition"/>
<input type="radio"/> Transmission Congestion Relief	<input type="button" value="Definition"/>
<input type="radio"/> Transmission & Distribution (T&D) Upgrade Deferral	<input type="button" value="Definition"/>
<input type="radio"/> Substation On-site Power	<input type="button" value="Definition"/>
<input checked="" type="radio"/> Time-of-use (TOU) Energy Cost Management	<input type="button" value="Definition"/>
<input type="radio"/> Demand Charge Management	<input type="button" value="Definition"/>
<input type="radio"/> Electric Service Reliability	<input type="button" value="Definition"/>
<input type="radio"/> Electric Service Power Quality	<input type="button" value="Definition"/>
<input type="radio"/> Renewables Energy Time-shift	<input type="button" value="Definition"/>
<input type="radio"/> Renewables Capacity Firming	<input type="button" value="Definition"/>
<input type="radio"/> Wind Generation Grid Integration - Short Duration	<input type="button" value="Definition"/>
<input type="radio"/> Wind Generation Grid Integration - Long Duration	<input type="button" value="Definition"/>

Previous

Exit

Next

Choose First Secondary Application
⌵

If applicable, please choose a second secondary application for this energy storage deployment. Secondary applications describe the ways in which the energy storage unit will be used when not being used for the primary application. There are a subset of applications that are especially appropriate given the primary application being pursued and given the technical characteristics of the energy storage technology. These synergistic applications are highlighted in blue.

<input type="radio"/> Electric Energy Time-shift <input type="radio"/> Electric Supply Capacity <input type="radio"/> Load Following <input type="radio"/> Area Regulation <input type="radio"/> Electric Supply Reserve Capacity <input type="radio"/> Voltage Support <input type="radio"/> Transmission Support <input type="radio"/> Transmission Congestion Relief <input type="radio"/> Transmission & Distribution (T&D) Upgrade Deferral <input type="radio"/> Substation On-site Power	<input type="radio"/> Time-of-use (TOU) Energy Cost Management <input type="radio"/> Demand Charge Management <input checked="" type="radio"/> Electric Service Reliability <input type="radio"/> Electric Service Power Quality <input checked="" type="radio"/> Renewables Energy Time-shift <input type="radio"/> Renewables Capacity Firming <input type="radio"/> Wind Generation Grid Integration - Short Duration <input type="radio"/> Wind Generation Grid Integration - Long Duration <input type="radio"/> No Secondary Applications
--	---

Previous

Exit

Next

Choose Second Secondary Application
⌵

If applicable, please choose a second secondary application for this energy storage deployment. Secondary applications describe the ways in which the energy storage unit will be used when not being used for the primary application. There are a subset of applications that are especially appropriate given the primary application being pursued and given the technical characteristics of the energy storage technology. These synergistic applications are highlighted in blue.

<input type="radio"/> Electric Energy Time-shift <input type="radio"/> Electric Supply Capacity <input type="radio"/> Load Following <input type="radio"/> Area Regulation <input type="radio"/> Electric Supply Reserve Capacity <input type="radio"/> Voltage Support <input type="radio"/> Transmission Support <input type="radio"/> Transmission Congestion Relief <input type="radio"/> Transmission & Distribution (T&D) Upgrade Deferral <input type="radio"/> Substation On-site Power	<input type="radio"/> Time-of-use (TOU) Energy Cost Management <input type="radio"/> Demand Charge Management <input checked="" type="radio"/> Electric Service Reliability <input type="radio"/> Electric Service Power Quality <input type="radio"/> Renewables Energy Time-shift <input type="radio"/> Renewables Capacity Firming <input type="radio"/> Wind Generation Grid Integration - Short Duration <input type="radio"/> Wind Generation Grid Integration - Long Duration <input type="radio"/> No Secondary Applications
--	---

Previous

Exit

Next

Benefits X

The benefits highlighted in blue below represent the benefits that your energy storage project will yield based on primary and secondary applications that are being pursued. For further explanation of a benefit click the button to the right of the benefit.

Arbitrage Revenue	Definition	Deferred Transmission Investments	Definition
Capacity Market Revenue	Definition	Deferred Distribution Investments	Definition
Ancillary Services Revenue	Definition	Deferred Generation Capacity Investments	Definition
Reduced Electricity Cost (Consumer)	Definition	Reduced Outages (Consumer)	Definition
Reduced Electricity Cost (Utility/Ratepayer)	Definition	Reduced Outages (Utility/Ratepayer)	Definition
Reduced Congestion Costs (Non-Utility Merchant)	Definition	Improved Power Quality	Definition
Reduced Congestion Costs (Utility/Ratepayer)	Definition	Reduced CO2 Emissions	Definition
Optimized Generator Operation (Non-Utility Merchant)	Definition	Reduced SOx Emissions	Definition
Optimized Generator Operation (Utility/Ratepayer)	Definition	Reduced NOx Emissions	Definition
Reduced Electricity Losses	Definition	Reduced PM Emissions	Definition

Previous
Finish

Verify the Applications and Benefits of the Project

Below is a table that summarizes the benefits that your project will yield. Each row represents a primary or secondary application your project is pursuing. All of the benefits a project would yield are listed along the top of the chart. Based on your inputs to the AGM, this chart has been populated with the benefits that your project may yield along with the applications that will lead to the benefits. Therefore, this chart should graphically summarize the objectives and expected benefits of your project. If the chart adequately summarizes your project, click the blue button on the left to proceed to the next phase of the tool. If the chart does not adequately summarize your project, click the button on the right to return to the


Proceed to the Data Input Module (DIM)
Return to the Asset Characteristics Module (ACM)

Application vs. Benefits Matrix

Location	Market	Owner	Application	Arbitrage Revenue	Capacity Market Revenue	Ancillary Services Revenue (Non-Utility Merchant)	Ancillary Services Revenue (Utility/Ratepayer)	Deferred Generation Capacity Investments (Non-Utility Merchant)	Deferred Generation Capacity Investments (Utility/Ratepayer)	Reduced Congestion Costs (Non-Utility Merchant)	Reduced Congestion Costs (Utility/Ratepayer)	Deferred Transmission Investments	Deferred Distribution Investments	Reduced Electricity Losses (Schedules)	Reduced Electricity Cost (Utility/Ratepayer)	Reduced Outages (Consumer)	Reduced Outages (Utility/Ratepayer)	Improved Power Quality	Reduced CO2 Emissions	Reduced SOx Emissions	Reduced NOx Emissions	Reduced PM Emissions
End-User	Regulated	End-User	Time-of-use (TOU) Energy Cost Management																			
End-User	Regulated	End-User	Electric Service Reliability																			
End-User	Regulated	End-User	Renewable Energy Time-shift																			

W.2 Data Input Module (DIM)

Data Input Module



Use the table below to enter the project data that will be used to calculate benefits. For each input the user must enter data for at least one project year before being able to submit entries and complete this step. When all data has been entered click the blue button at the bottom of the table to submit and store the data entries. If pasting data from another source into this table please use the "Paste Value" function to avoid changing cell formatting or pasting formulas. If the user does not have measured data to enter, they can leverage default values for most of the inputs. However, if default values are used the user should take care in interpreting the results since the default values tend to be general estimates, and the actual values for the user's project may vary greatly. Furthermore, default values do not take into account situations in which energy storage deployments are being used for multiple applications, rather they assume the storage is being used for a single application for an entire year. Therefore, if multiple applications are being pursued and default values are being used, the user must ensure that the default amount of energy discharge for each application is realistic considering that the storage is being used for more than one application throughout the year.

Return to the Asset Characterization Module (ACM)

Input Name	Units	Input Definition	Default Values	Values				
				100	101	102	103	104
Average On-Peak Price of Electricity	\$/MWh	The average on-peak price of wholesale electricity over a year.	Enter Custom	\$ 41	\$ 41	\$ 41	\$ 41	\$ 41
CO2 Emissions Factor for Generation on the Margin	lbs/MWh	The characteristic or average CO2 emissions factor for marginal generation units used to meet peak demand.	Use Default	1,151	1,151	1,151	1,151	1,151
SOx Emissions Factor for Generation on the Margin	lbs/MWh	The characteristic or average SOx emissions factor for marginal generation units used to meet peak demand.	Use Default	0.012	0.012	0.012	0.012	0.012
NOx Emissions Factor for Generation on the Margin	lbs/MWh	The characteristic or average NOx emissions factor for marginal generation units used to meet peak demand.	Use Default	1.41	1.41	1.41	1.41	1.41
PM Emissions Factor for Generation on the Margin	lbs/MWh	The characteristic or average PM emissions factor for marginal generation units used to meet peak demand.	Use Default	0.040	0.040	0.040	0.040	0.040
Value of CO2	\$/ton	The anticipated or current market price of carbon emissions.	Use Default	\$ 20	\$ 20	\$ 20	\$ 20	\$ 20
Value of SOx	\$/ton	The anticipated or current market price of SOx emissions.	Use Default	\$ 520	\$ 520	\$ 520	\$ 520	\$ 520
Value of NOx	\$/ton	The anticipated or current market price of NOx emissions.	Use Default	\$ 3,000	\$ 3,000	\$ 3,000	\$ 3,000	\$ 3,000
Value of PM	\$/ton	The anticipated or current market price of PM emissions.	Use Default	\$ 36,000	\$ 36,000	\$ 36,000	\$ 36,000	\$ 36,000
Total Energy Discharged for TOU Energy Cost Management	MWh	Total amount of energy discharged by the energy storage device to provide energy during peak-time so as to avoid paying peak prices.	Enter Custom	3	3	3	3	3
Average On-Peak Retail Price of Electricity	\$/MWh	Average on-peak retail price of electricity. This would be the price that was avoided as a result of the energy storage device.	Enter Custom	\$ 200	\$ 200	\$ 200	\$ 200	\$ 200
Average Off-Peak Retail Price of Electricity	\$/MWh	Average off-peak retail price of electricity. This would be the price that was paid for electricity used to charge the energy storage device.	Enter Custom	\$ 26	\$ 26	\$ 26	\$ 26	\$ 26
Outage Minutes Avoided by Residential Customers	minutes	The total outage minutes avoided by residential customers as a result of energy storage devices being used to provide power during system interruptions.	Enter Custom	476	476	476	476	476
Outage Minutes Avoided by Commercial Customers	minutes	The total outage minutes avoided by commercial customers as a result of energy storage devices being used to provide power during system interruptions.	Enter Custom	-	-	-	-	-
Outage Minutes Avoided by Industrial Customers	minutes	The total outage minutes avoided by industrial customers as a result of energy storage devices being used to provide power during system interruptions.	Enter Custom	-	-	-	-	-
Average Hourly Residential Load Not Served During Outage	kW	The average residential load unserved during outages. This parameter can be estimated by determining the average load of customers whose reliability will be impacted by the energy storage device.	Enter Custom	1.2	1.2	1.2	1.2	1
Average Hourly Commercial Load Not Served During Outage	kW	The average commercial load unserved during outages. This parameter can be estimated by determining the average load of customers whose reliability will be impacted by the energy storage device.	Enter Custom	-	-	-	-	-
Average Hourly Industrial Load Not Served During Outage	kW	The average industrial load unserved during outages. This parameter can be estimated by determining the average load of customers whose reliability will be impacted by the energy storage device.	Enter Custom	-	-	-	-	-
Residential VOS	\$/kWh	Represents the true value of the electricity service to the residential customer without regard to the actual cost of providing the service. This input captures the value of service reliability quantified by the willingness of customers to pay for service reliability, taking into account the resources (e.g., income) of the residential customer.	Enter Custom	\$ 2.3	\$ 2.3	\$ 2.3	\$ 2.3	\$ 2.3
Commercial VOS	\$/kWh	Represents the true value of the electricity service to the commercial customer without regard to the actual cost of providing the service. This input captures the value of service reliability quantified by the willingness of customers to pay for service reliability, taking into account the resources (e.g., income) of the commercial customer or by a firm's expected net revenues associated with the added reliability.	Enter Custom	\$ -	\$ -	\$ -	\$ -	\$ -
Industrial VOS	\$/kWh	Represents the true value of the electricity service to the commercial customer without regard to the actual cost of providing the service. This input captures the value of service reliability quantified by the willingness of customers to pay for service reliability, taking into account the resources (e.g., income) of the commercial customer or by a firm's expected net revenues associated with the added reliability.	Enter Custom	\$ -	\$ -	\$ -	\$ -	\$ -
Total Renewable Energy Discharged for Arbitrage	MWh	The total amount of renewable energy discharged from the energy storage device and used for arbitrage purposes over a year.	Enter Custom	-	-	-	-	-
Total Renewable Energy Discharged for Energy Time-Shift	MWh	The total amount of renewable energy discharged from the energy storage device for the purposes of shifting energy from an off-peak time to an on-peak time. This may allow an end user to avoid paying peak-prices for electricity or this may allow a utility to decrease their costs by offsetting the need to run less efficient, more expensive peaking units.	Enter Custom	-	-	-	-	-

Finish Data Entry

Review Benefit Calculation Inputs											
<p>The table below contains the benefit calculation inputs that will be fed into the next phase of the Energy Storage Computational Tool. The purpose of this page is to give the user the opportunity to review the data before proceeding to the next phase of the tool. If the user finds data that has been entered erroneously, or if the user wishes to edit an entry they should navigate to back to the DIM and make the appropriate changes.</p>											
Input Name	Units	Entered Data					Projected Data				
		2014	2015	2016	2017	2018	2019	2020	2021	2022	2023
Average On-Peak Price of Electricity	\$/MWh	\$ 41	\$ 41	\$ 41	\$ 41	\$ 41	42	43	44	45	46
CO2 Emissions Factor for Generation on the Margin	lbs/MWh	1,150.808500	1,150.808500	1,150.808500	1,150.808500	1,150.808500	1,151	1,151	1,151	1,151	1,151
SOx Emissions Factor for Generation on the Margin	lbs/MWh	0.012200	0.012200	0.012200	0.012200	0.012200	0	0	0	0	0
NOx Emissions Factor for Generation on the Margin	lbs/MWh	1.411100	1.411100	1.411100	1.411100	1.411100	1	1	1	1	1
PM Emissions Factor for Generation on the Margin	lbs/MWh	0.040000	0.040000	0.040000	0.040000	0.040000	0	0	0	0	0
Value of CO2	\$/ton	\$ 20	\$ 20	\$ 20	\$ 20	\$ 20	\$ 20	\$ 21	\$ 21	\$ 22	\$ 22
Value of SOx	\$/ton	\$ 520	\$ 520	\$ 520	\$ 520	\$ 520	\$ 531	\$ 542	\$ 553	\$ 565	\$ 577
Value of NOx	\$/ton	\$ 3,000	\$ 3,000	\$ 3,000	\$ 3,000	\$ 3,000	\$ 3,063	\$ 3,127	\$ 3,193	\$ 3,260	\$ 3,329
Value of PM	\$/ton	\$ 36,000	\$ 36,000	\$ 36,000	\$ 36,000	\$ 36,000	\$ 36,756	\$ 37,528	\$ 38,316	\$ 39,121	\$ 39,942
Total Energy Discharged for TOU Energy Cost Management	MWh	3	3	3	3	3	3	3	3	3	3
Average On-Peak Retail Price of Electricity	\$/MWh	\$ 200	\$ 200	\$ 200	\$ 200	\$ 200	205	209	213	218	222
Average Off-Peak Retail Price of Electricity	\$/MWh	\$ 26	\$ 26	\$ 26	\$ 26	\$ 26	27	27	28	29	29
Outage Minutes Avoided by Residential Customers	minutes	476	476	476	476	476	476	476	476	476	476
Outage Minutes Avoided by Commercial Customers	minutes	-	-	-	-	-	-	-	-	-	-
Outage Minutes Avoided by Industrial Customers	minutes	-	-	-	-	-	-	-	-	-	-
Average Hourly Residential Load Not Served During Outage	kW	1.2	1.2	1.2	1.2	1	1	1	1	1	1
Average Hourly Commercial Load Not Served During Outage	kW	-	-	-	-	-	-	-	-	-	-
Average Hourly Industrial Load Not Served During Outage	kW	-	-	-	-	-	-	-	-	-	-
Residential VOS	\$/kWh	\$ 2.3	\$ 2.3	\$ 2.3	\$ 2.3	\$ 2.3	2	2	2	2	3
Commercial VOS	\$/kWh	\$ -	\$ -	\$ -	\$ -	\$ -	-	-	-	-	-
Industrial VOS	\$/kWh	\$ -	\$ -	\$ -	\$ -	\$ -	-	-	-	-	-
Total Renewable Energy Discharged for Arbitrage	MWh	-	-	-	-	-	-	-	-	-	-
Total Renewable Energy Discharged for Energy Time-Shift	MWh	-	-	-	-	-	-	-	-	-	-



W.3 Computational Module (CM)

Computational Module (CM) Main Page

Instructions

Welcome to the Computational Module (CM) phase of the Energy Storage Computational Tool (ESCT). The CM is the calculation engine of the tool, it crunches the numbers and generates the output. The CM also allows the user to complete a sensitivity analysis if desired.

Running the CM with Reference Inputs - To run the CM with the inputs that were entered in the DIM phase, simply click the button in the "Reference Case" section that says "Run CM with Reference Case Inputs". The CM will take about 20 seconds to complete the analysis. Once the analysis is complete the results can be viewed by clicking the "View Reference Case Results" button.

Running the a Sensitivity Analysis - Before running a sensitivity analysis the CM should be run with the reference case inputs by following the directions above. To run a sensitivity analysis first change the High and Low sensitivity ranges of the desired inputs by using the toggles that are to the right of every input. After all of the desired sensitivity ranges have been set click the button in the "Sensitivity Analysis" section that says "Run CM with Sensitivity Case Inputs". The CM will take about a 40 seconds to complete the analysis. Once the analysis is complete the results can be viewed by clicking the "View Sensitivity Results" button. All of the sensitivity ranges can be reset to 100% by clicking the button above the toggle switches that says "Reset all values to 100%".



Reference Case

Run CM with Reference Case Inputs

View Reference Case Results

Sensitivity Analysis

Run CM with Sensitivity Case Inputs

View Sensitivity Results

Reset all values to 100%

Input Name	Unit	Select % using toggle			2014 Values		
		Low	Reference	High	Low	Reference	High
Average On-Peak Price of Electricity	\$/MWh	100%	100%	100%	\$ 41	\$ 41	\$ 41
CO2 Emissions Factor for Generation on the Margin	lbs/MWh	100%	100%	100%	1,151	1,151	1,151
SOx Emissions Factor for Generation on the Margin	lbs/MWh	100%	100%	100%	0.012	0.012	0.012
NOx Emissions Factor for Generation on the Margin	lbs/MWh	100%	100%	100%	1.41	1.41	1.41
PM Emissions Factor for Generation on the Margin	lbs/MWh	100%	100%	100%	0.040	0.040	0.040
Value of CO2	\$/ton	100%	100%	100%	\$ 20	\$ 20	\$ 20
Value of SOx	\$/ton	100%	100%	100%	\$ 520	\$ 520	\$ 520
Value of NOx	\$/ton	100%	100%	100%	\$ 3,000	\$ 3,000	\$ 3,000
Value of PM	\$/ton	100%	100%	100%	\$ 36,000	\$ 36,000	\$ 36,000
Total Energy Discharged for TOU Energy Cost Management	MWh	100%	100%	100%	3	3	3
Average On-Peak Retail Price of Electricity	\$/MWh	100%	100%	100%	\$ 200	\$ 200	\$ 200
Average Off-Peak Retail Price of Electricity	\$/MWh	100%	100%	100%	\$ 26	\$ 26	\$ 26
Outage Minutes Avoided by Residential Customers	minutes	100%	100%	100%	476	476	476
Outage Minutes Avoided by Commercial Customers	minutes	100%	100%	100%	-	-	-
Outage Minutes Avoided by Industrial Customers	minutes	100%	100%	100%	-	-	-
Average Hourly Residential Load Not Served During Outage	kW	100%	100%	100%	1.2	1.2	1.2
Average Hourly Commercial Load Not Served During Outage	kW	100%	100%	100%	-	-	-
Average Hourly Industrial Load Not Served During Outage	kW	100%	100%	100%	-	-	-
Residential VOS	\$/kWh	100%	100%	100%	\$ 2.3	\$ 2.3	\$ 2.3
Commercial VOS	\$/kWh	100%	100%	100%	\$ -	\$ -	\$ -
Industrial VOS	\$/kWh	100%	100%	100%	\$ -	\$ -	\$ -
Total Renewable Energy Discharged for Arbitrage	MWh	100%	100%	100%	-	-	-
Total Renewable Energy Discharged for Energy Time-Shift	MWh	100%	100%	100%	-	-	-

Reference Case Output: Annual and Cumulative Results Tables


The tables below display the annual and cumulative project benefits and costs. The benefits are organized by category. The total gross benefit, total cost, and net benefit are also displayed at the bottom of each chart. All values are present value terms. To calculate additional benefits navigate to the additional benefits worksheets from the Additional Benefits tab.

Annual Benefit and Cost Table


		Additional Benefits - Total Present Value over the Deployment Period	+	Primary and Secondary Benefits - Total Present Value over the Deployment Period	=	Total Benefit - Present Value over the Deployment Period	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	
Benefits																	
Market Revenue	Arbitrage Revenue	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Capacity Market Revenue	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Ancillary Services Revenue	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Improved Asset Utilization	Optimized Generator Operation (Non-Utility Merchant)	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Optimized Generator Operation (Utility/Ratepayer)	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Deferred Generation Capacity Investments	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
T&D Capital Savings	Reduced Congestion Costs (Non-Utility Merchant)	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Reduced Congestion Costs (Utility/Ratepayer)	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Deferred Transmission Investments	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Energy Efficiency	Deferred Distribution Investments	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Reduced Electricity Losses	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Electricity Cost Savings	\$ -		\$ 4,200		\$ 4,200	\$ 500	\$ 500	\$ 400	\$ 400	\$ 400	\$ 400	\$ 400	\$ 400	\$ 400	\$ 400	\$ 400
Power Interruptions	Reduced Electricity Cost (Consumer)	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Reduced Electricity Cost (Utility/Ratepayer)	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Reduced Outages (Consumer)	\$ -		\$ 200		\$ 200	\$ 20	\$ 20	\$ 20	\$ 20	\$ 20	\$ 20	\$ 20	\$ 20	\$ 20	\$ 20	\$ 20
Power Quality	Reduced Outages (Utility/Ratepayer)	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Improved Power Quality	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Reduced CO2 Emissions	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Air Emissions	Reduced SOx Emissions	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Reduced NOx Emissions	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Reduced PM Emissions	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Gross Benefit		\$ -		\$ 4,400		\$ 4,400	\$ 520	\$ 520	\$ 420	\$ 420	\$ 420	\$ 420	\$ 420	\$ 420	\$ 420	\$ 420	\$ 420
Costs																	
Capital Cost of Deployment (fixed charge rate)				\$ 28,800		\$ 28,800	\$ 3,600	\$ 3,400	\$ 3,200	\$ 3,100	\$ 2,900	\$ 2,800	\$ 2,600	\$ 2,500	\$ 2,400	\$ 2,300	
Operating and maintenance costs not related to energy (labor for operation, plant maintenance, equipment wear leading to loss-of-life)				\$ 1,000		\$ 100	\$ 100	\$ 100	\$ 100	\$ 100	\$ 100	\$ 100	\$ 100	\$ 100	\$ 100	\$ 100	\$ 100
Decommissioning and Disposal Costs				\$ 600		\$ 600	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Annual Cost of Deployment				\$ 30,400		\$ 30,400	\$ 3,700	\$ 3,500	\$ 3,400	\$ 3,200	\$ 3,000	\$ 2,900	\$ 2,700	\$ 2,600	\$ 2,500	\$ 2,300	
Total Net Benefit				\$ (26,000)		\$ (26,000)	\$ (3,180)	\$ (2,980)	\$ (2,980)	\$ (2,780)	\$ (2,580)	\$ (2,480)	\$ (2,280)	\$ (2,180)	\$ (2,080)	\$ (1,980)	

Cumulative Benefit and Cost Table


		Additional Benefits - Total Present Value over the Deployment Period	+	Primary and Secondary Benefits - Total Present Value over the Deployment Period	=	Total Benefit - Present Value over the Deployment Period	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023
Benefits																
Market Revenue	Arbitrage Revenue	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Capacity Market Revenue	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Ancillary Services Revenue	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Improved Asset Utilization	Optimized Generator Operation (Non-Utility Merchant)	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Optimized Generator Operation (Utility/Ratepayer)	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Deferred Generation Capacity Investments	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
T&D Capital Savings	Reduced Congestion Costs (Non-Utility Merchant)	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Reduced Congestion Costs (Utility/Ratepayer)	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Deferred Transmission Investments	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Energy Efficiency	Deferred Distribution Investments	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Reduced Electricity Losses	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Electricity Cost Savings	\$ -		\$ 4,200		\$ 4,200	\$ 500	\$ 1,000	\$ 1,400	\$ 1,800	\$ 2,200	\$ 2,600	\$ 3,000	\$ 3,400	\$ 3,800	\$ 4,200
Power Interruptions	Reduced Electricity Cost (Consumer)	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Reduced Electricity Cost (Utility/Ratepayer)	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Reduced Outages (Consumer)	\$ -		\$ 200		\$ 200	\$ 20	\$ 40	\$ 60	\$ 80	\$ 100	\$ 120	\$ 140	\$ 160	\$ 180	\$ 200
Power Quality	Reduced Outages (Utility/Ratepayer)	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Improved Power Quality	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Reduced CO2 Emissions	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Air Emissions	Reduced SOx Emissions	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Reduced NOx Emissions	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	Reduced PM Emissions	\$ -		\$ -		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Gross Benefit		\$ -		\$ 4,400		\$ 4,400	\$ 520	\$ 1,040	\$ 1,460	\$ 1,880	\$ 2,300	\$ 2,720	\$ 3,140	\$ 3,560	\$ 3,980	\$ 4,400
Costs																
Capital Cost of Deployment (fixed charge rate)				\$ 28,800		\$ 28,800	\$ 3,600	\$ 7,000	\$ 10,200	\$ 13,300	\$ 16,200	\$ 19,000	\$ 21,600	\$ 24,100	\$ 26,500	\$ 28,800
Operating and maintenance costs not related to energy (labor for operation, plant maintenance, equipment wear leading to loss-of-life)				\$ 1,000		\$ 100	\$ 100	\$ 200	\$ 300	\$ 400	\$ 500	\$ 600	\$ 700	\$ 800	\$ 900	\$ 1,000
Decommissioning and Disposal Costs				\$ 600		\$ 600	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Annual Cost of Deployment				\$ 30,400		\$ 30,400	\$ 3,700	\$ 7,200	\$ 10,600	\$ 13,800	\$ 16,800	\$ 19,700	\$ 22,400	\$ 25,000	\$ 27,500	\$ 30,400
Total Net Benefit				\$ (26,000)		\$ (26,000)	\$ (3,180)	\$ (6,160)	\$ (9,140)	\$ (11,920)	\$ (14,500)	\$ (16,980)	\$ (19,260)	\$ (21,440)	\$ (23,520)	\$ (26,000)



Cumulative Gross Benefits over the Deployment Period (Present Value)		Lifetime Benefit per kW of Energy Storage Installed
Arbitrage Revenue	\$ -	\$ -
Capacity Market Revenue	\$ -	\$ -
Ancillary Services Revenue	\$ -	\$ -
Optimized Generator Operation (Non-Utility Merchant)	\$ -	\$ -
Optimized Generator Operation (Utility/Ratepayer)	\$ -	\$ -
Deferred Generation Capacity Investments	\$ -	\$ -
Reduced Congestion Costs (Non-Utility Merchant)	\$ -	\$ -
Reduced Congestion Costs (Utility/Ratepayer)	\$ -	\$ -
Deferred Transmission Investments	\$ -	\$ -
Deferred Distribution Investments	\$ -	\$ -
Reduced Electricity Losses	\$ -	\$ -
Reduced Electricity Cost (Consumer)	\$ 4,200	\$ 700
Reduced Electricity Cost (Utility/Ratepayer)	\$ -	\$ -
Reduced Outages (Consumer)	\$ 200	\$ 33
Reduced Outages (Utility/Ratepayer)	\$ -	\$ -
Improved Power Quality	\$ -	\$ -
Reduced Emissions	\$ -	\$ -
Total Gross Benefit	\$ 4,400	\$ 733



	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023
Gross Benefit (Present Value Dollars)	\$ 520	\$ 520	\$ 420	\$ 420	\$ 420	\$ 420	\$ 420	\$ 420	\$ 420	\$ 420
Total Annual Cost of Deployment (Present Value Dollars)	\$ (3,700)	\$ (3,500)	\$ (3,400)	\$ (3,200)	\$ (3,000)	\$ (2,900)	\$ (2,700)	\$ (2,600)	\$ (2,500)	\$ (2,400)
Net Benefit (Present Value Dollars)	\$ (3,180)	\$ (2,980)	\$ (2,980)	\$ (2,780)	\$ (2,580)	\$ (2,480)	\$ (2,280)	\$ (2,180)	\$ (2,080)	\$ (1,980)



	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023
Cumulative Gross Benefit (Present Value Dollars)	\$ 520	\$ 1,040	\$ 1,460	\$ 1,880	\$ 2,300	\$ 2,720	\$ 3,140	\$ 3,560	\$ 3,980	\$ 4,400
Cumulative Cost of Deployment (Present Value Dollars)	\$ (3,700)	\$ (7,200)	\$ (10,600)	\$ (13,800)	\$ (16,800)	\$ (19,700)	\$ (22,400)	\$ (25,000)	\$ (27,500)	\$ (30,400)
Cumulative Net Benefit (Present Value Dollars)	\$ (3,180)	\$ (6,160)	\$ (9,140)	\$ (11,920)	\$ (14,500)	\$ (16,980)	\$ (19,260)	\$ (21,440)	\$ (23,520)	\$ (26,000)

DOE ACKNOWLEDGEMENT

This material is based upon work supported by the Department of Energy
under Award Number DE-OE0000221

FEDERAL DISCLAIMER

“This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.”