August 1, 2011 Plant of the Year: KCP&L's latan 2 Earns POWER's Highest Honor

By Dr. Robert Peltier, PE



Courtesy: KCP&L

Kansas City Power & Light (KCP&L) began engaging stakeholders in 2003 to develop consensus on a regional energy plan designed to balance customers' desire for low electricity costs with system reliability needs and environmental requirements. The culmination of that plan was the completion of latan 2, which entered service in August 2010. For executing an innovative energy plan that reduced overall fleet emissions, ensuring the region's future electricity supply, and completing an approximately \$2 billion project in time for the summer 2010 peak load by using innovative contracting and project controls, KCP&L's latan 2 is awarded POWER's 2011 Plant of the Year Award.

KCP&L, headquartered in Kansas City, Mo., serves about 820,000 customers in western Missouri and eastern Kansas. Great Plains Energy Inc. is the holding company of Kansas City Power & Light and KCP&L Greater Missouri Operations Co. (GMO, the former Aquila, purchased in July 2008). However, KCP&L is the brand name used to represent both of these utilities.

KCP&L has an installed capacity of approximately 6,700 MW. Its coal-fired latan Station, located about 30 miles northwest of Kansas City, near Weston, Mo., features the recently renovated approximately 700-MW Unit 1 and the 850-MW (net) Unit 2, which went into service in August 2010 (see Table 1). Iatan 2 (Figure 1) was KCP&L's first new baseload plant in nearly three decades. In addition, this milestone marked the finale of KCP&L's Comprehensive Energy Plan (CEP), initiated seven years earlier. The plant is named after latan, a chief of the Otoe tribe that fought battles with the Comanche (also called latan) around 1800.

Project milestones	Description	
Sept. 9, 2004	Engineering started/project definition report issued	
Feb. 1, 2005	Comprehensive Energy Plan Regulatory Plan approved by KCP&L Board of Directors	
July 28, 2005	Missouri stipulations	
Jan. 31, 2006	EPA issued air permit	
Mar. 2006	Turbine-generator agreement signed with Toshiba	
Aug. 5, 2006	Plant construction began	
Aug. 2006	EPC agreement signed with Alstom for latan 2 boiler and Unit 1 and 2 air quality control systems	
Mar. 2007	Collaboration agreement with Sierra Club signed, Alstom mobilizes on site	
June 2007	Kiewit issued notice to proceed	
Nov. 2007	Kiewit contract signed	
Oct. 2008 to Jan. 2009	latan 1 outage for environmental tie-in	
Apr. 19, 2009	latan 1 in-service criteria achieved	
July 2010	latan 2 achieves first synchronization with the grid	
July 2010	latan 2 achieves first fire on coal	
Aug. 26, 2010	latan 2 in-service criteria met	
Sept. 25, 2010	Provisional acceptance achieved	
Dec. 31, 2010	Full dispatch given to Southwest Power Pool	

 Table 1. Key milestones for the latan 2 project.
 latan 2, erected over a five-year period, was one of the largest and most complex construction projects in Missouri and KCP&L history.

 Source:
 KCP&L



1. Latest and greatest. The latan Generating Station is located on the banks of the Missouri River in western Missouri. Commercial operation of latan 2 in December 2010 added 850 MW to the approximately 700 MW produced by latan 1. latan 2 was the first new baseload power generator installed by KCP&L in nearly 30 years.

The Plan

In 2003, KCP&L began updating its energy development plans to meet expected regional demand growth for itself and its project partners. The goal of the CEP was to add needed baseload capacity while lowering the utility's overall emissions by strategically adding renewable energy projects and investing in energy efficiency, a synergistic package of improvements benefiting all stakeholders. KCP&L's fuel mix is about 80% coal, 17% nuclear (Wolf Creek Generating Station was the last baseload generation built, in 1985), 2% natural gas and oil, and 1% wind.

Specifically, the CEP proposed development of about 100 MW of wind energy, upgrading the air quality control equipment on latan 1, a selective catalytic reduction (SCR) system for LaCygne 2, a number of transmission and distribution system upgrades, a demand-side management program designed to help ratepayers reduce consumption, and the development of latan 2. William Downey, executive vice chairman and the company's senior executive on the project, noted in an interview with *POWER*, "When latan 2 was being built, it was one of the largest and most complex construction projects in KCP&L and Missouri history. Because of the benefits it brought to this region, it was a bright spot in a bleak economic time."

Downey also noted that portions of the CEP proposed financial processes that would allow the utility to maintain credit metrics throughout the construction process given that Missouri regulations do not allow construction work in process to be added to the rate base. The KCP&L cost analysis concluded that, from a baseload generation perspective, coal-fired generation still enjoys a significant cost advantage over other generation technologies, even when considering the cost of meeting challenging emissions-reduction goals.

Inclusive Resource Planning

Many utilities approach resource planning as a euphemism for building a new plant, regardless of the public's support. KCP&L's CEP took a radically different approach to gaining acceptance: It took the story directly to the public. The theme of the message was, "This is how we see our building evolving over the next decade or more, and here is our strategy for balancing projected demand for electricity with a sustainable environment." KCP&L hosted community workshops to explain and discuss all aspects of the plan, listen to consumers and their concerns, and feed that information back into the CEP development process. Similar discussions were held with regulators and Wall Street financial representatives, who critiqued the plan and suggested improvements that would reduce risk to ratepayers and stockholders.

Michael Chesser, chairman and CEO, commented on the uniqueness of this approach to resource planning: "In 2004, KCP&L recognized the need to generate additional electricity in order to meet growing demand. We took a new approach to figuring out how we would do this. We decided to collaborate with the community, and the outcome was the Comprehensive Energy Plan. Iatan 2 is the cornerstone of the Comprehensive Energy Plan, which provides affordable, reliable, and sustainable electricity for decades to come."

The CEP was approved by Kansas and Missouri regulators in 2005 with the plan that latan 2 would be online in the summer of 2010.

The uniqueness and efficiency of the KCP&L collaborative planning process was soon recognized by the entire power generation industry. For establishing the CEP planning process, The Edison Electric Institute

(EEI) awarded KCP&L its 2007 Edison Award for meeting the "region's growing demand for clean, affordable energy by developing new, clean energy sources, making proactive environmental and infrastructure improvements and creating innovative energy efficiency and demand-response programs." The EEI citation went on to say that "KCP&L has worked with a wide variety of stakeholders, establishing true partnerships within its communities to create political and regulatory environments that have allowed the company to deliver on its promises."

This isn't to say that KCP&L's early planning process didn't meet with strong opposition. For example, latan 2 was sailing through the regulatory approval process when the Sierra Club and Concerned Citizens of Platte County intervened in the Prevention of Significant Deterioration permit process in late September 2006. After several procedural moves, KCP&L and the other litigants negotiated an agreement that fulfilled the public's desires, as expressed in the CEP, and addressed the interveners' environmental concerns while ensuring that the utility would be able to meet its expected demand growth.

The Collaboration Agreement, signed in March 2007, gained KCP&L's agreement to offset an estimated 6 million tons of CO₂ emissions each year, add 100 MW of wind power by 2010 (which was already under development), and add another 300 MW of wind supply by 2012—the amount of wind capacity the utility believed was prudent given wind's variability. The agreement also included investment in energy-efficiency projects to reduce demand by 100 MW immediately, plus another 200 MW reduction by 2012. (KCP&L implemented 15 residential and commercial customer energy-saving pilot programs to meet this goal.) Mobilization of the construction site began shortly after this agreement was signed.

The Sierra Club described the result of the negotiation "a groundbreaking agreement that can serve as a model for environmental groups and utilities working together." You may recall City Water, Light & Power, the municipal utilities agency of the City of Springfield, III., negotiated a similar agreement to allow its Dallman 4 project to move forward. <u>Dallman 4</u> was *POWER*'s 2009 Plant of the Year (see the August 2009 issue in our online archives at www.powermag.com).

The price tag for all the projects included in the CEP was about \$3 billion and covered a variety of strategic investments:

- In 2007, \$81 million was invested in an SCR system that reduced NO_x by 87% at the utility's La Cygne plant.
- About \$265 million was invested in wind and energy efficiency/demand reduction projects.
- The balance went toward the \$2.4 billion price tag of the construction costs for latan 1 environmental retrofits, the construction of latan 2, and latan common facilities.

Output from the 850-MW latan 2 is owned by a consortium of utilities and power distributors. KCP&L and its affiliate KCP&L GMO own roughly 73% of the new plant; Empire District Electric owns 12%; Missouri Joint Municipal Electric Utility Commission owns 11.76% (equivalent to 100 MW); and Kansas Electric Power Cooperative owns 3.5%. KCP&L and GMO own 88% of latan 1. KCP&L is the plant operator and responsible for routine maintenance.

Work the Plan

Approval of the CEP by both the Missouri Public Service and Kansas Corporation Commissions cleared

the regulatory road for construction of latan 2, although KCP&L had began construction of the environmental upgrades for latan 1 the previous August.

Construction started on latan 2 in September 2007. Earlier that year, KCP&L had awarded a fixed-price contract to Alstom Power to engineer, design, and construct the boiler island, including the air quality control system (AQCS) for both units. The steam turbine was purchased from Toshiba. Burns & McDonnell was retained to provide engineering design services for both projects (Table 2).

What	Who	
Plant engineering and design	Burns & McDonnell, owner's engineer and designed the balance of plant	
Plant construction	Multiprime/Hybrid EPC	
Steam generator and erection services	Alstom Power	
Balance-of-plant construction and steam turbine erection	Kiewit Power	
Steam turbine generators	Toshiba	
Selective catalytic reduction systems	Alstom Power	
Cooling tower	SPX	
Fabric filter	Alstom Power	
Material handling	Automatic Systems Inc.	
Wet flue gas desulfurization	Alstom Power	
Distributed control system	Emerson	
Sootblowers and furnace wall cleaning	Diamond Power	
Condensers	Thermal Engineering International	
Feedwater heaters	Thermal Engineering International	
Circulating water pumps	Flowserve	
Condensate pumps	Flowserve	
Boiler feedwater pumps	Flowserve	
Boiler feedwater pumps, Unit 2 pump turbines	Flowserve	
Fuel handling	Automatic Systems Inc.	
Auxiliary transformers	Hyundai	
Large power transformers	Hyundai	
Dry ash handling	United Conveyor Corp.	
Limestone preparation	Automatic Systems Inc.	
Auxiliary boiler	Vapor Power	
Water systems	Ecotech/Aquatech/WesTech	

Table 2. Major contractors and equipment suppliers to the latan 2 project. Source: KCP&L

The supercritical latan 2 boiler, Alstom's largest sliding pressure boiler in the U.S., was designed to burn low-sulfur Powder River Basin coal with low-NO_x tangential burners. "latan 2 will be approximately 10% to 12% more efficient than a typical plant built in the 1970s," says Burns & McDonnell project manager Bob Reymond. "The state-of-the-art emissions control systems will remove about 98% of sulfur dioxide from the exhaust." The post-combustion AQCS begins with an SCR, fabric filter, and wet flue gas desulfurization (wet FGD). Activated carbon injection (ACI) was also added to the AQCS suite of equipment for mercury emissions reductions. The permitted levels of mercury emissions are based on

site emissions, thereby giving operators some discretion in how much activated carbon is injected into each unit (Figure 2).



2. Duplicated design. The design of the air quality control systems for the two units was very similar. On latan 1, the selective catalytic reduction (SCR) system was placed away from the unit because of retrofit space constraints; for latan 2, the SCR system was part of the integral design. Otherwise, the same catalyst type and size was used, and both boxes are able to hold four layers, although only two layers are currently used on each unit. *Courtesy: KCP&L*

For simplicity of common operating practices and cost-effective purchasing, the entire post-combustion AQCS for latan 1 is virtually identical to that of the new latan 2. Today, the NO_x emissions of both units are 53% lower, and SO₂ emissions are 74% lower, than those of only latan 1 prior to the AQCS upgrades. Using high-efficiency supercritical combustion technology also contributed greatly to the utility's CO₂ reduction goals, as higher combustion efficiency means less CO₂ is produced per ton of coal consumed. KCP&L continues to make focused investments in initiatives with the goal of improving the operating efficiency of its coal fleet 3% by 2013.

latan 2's sliding pressure boiler mode of operation also helps the plant meet the design goal of being capable of performing daily load swings from 40% to 100%. Of particular interest in the project technical specifications (Table 3) are the main and reheat steam temperatures, which are both 1,080F—more aggressive than the typical 1,050F of similar supercritical plants. Recent reports from the plant confirm that plant operation has been very stable with these near-state-of-the-art steam temperatures.

Parameter		latan 2
Net unit output		850 MW
Net plant heat rate		9,000 Btu/kWh
Turbine throttle conditions		3,700 psig/1,080F main steam; 686 psig/1,080F reheat steam
Fuel		Powder River Basin subituminous 8,200 to 8,800 Btu/lb range
Emissions	NO _x	0.070 lb/MMBtu
	SO ₂	0.060 lb/MMBtu
	CO	0.14 lb/MMBtu
	PM10 (filterable)	0.014 lb/MMBtu
	Hg	Activated carbon injection, Hg limited to 39x10 ⁻⁶ lb/gross MWH + 210 lb/yr total for the station
Boiler	Туре	Supercritical
	Steam pressure	3,700 psig
	Steam temperature	1,080F/1,080F
	Maximum continu- ous rating	6,246,000 lb/hr
Turbine	Rating	938 MWh
	Туре	Single-flow high-pressure turbine, double-flow intermediate- pressure (reheat) turbine, four flow low-pressure condensing turbines
	Rotational speed	3,600 rpm
	Condenser vacuum	3 inches HgA
	Feedwater heaters	Eight stages of feedwater heating, including deaerator
Generator	Voltage	24 kV
	Capacity	1,000 MVA @ 0.9 PF
Boiler feed pump configuration		Two 60%-sized pumps, steam turbine-driven
Water pretreatment system		Well water for service water and plant feedwater makeup
Zero-liquid discharge		latan 2 is a zero-liquid discharge facility

 Table 3. Key latan 2 performance parameters.
 latan 2 uses a supercritical steam generator and a system of air quality control devices to keep air emissions low.

 Source:
 KCP&L

Unique Contracting Approach

Once the long-lead equipment purchases were completed (over \$1 billion by August 2006), KCP&L made inquiries with experienced power industry contractors to assume the project lead but found little interest in constructing the plant on a turnkey basis. The challenge for contractors at the time was the rapidly increasing cost of commodities such as copper and steel plus nationwide high demand for limited journeyman construction talent for constructing new coal plants and retrofit AQCS systems. KCP&L decided to proceed with the project using a multi-prime approach combined with aggressive purchasing processes to limit the risk of future price increases. In essence, KCP&L would assume the responsibility and risk of the general contractor by using seven or eight smaller contractors to complete the balance-of-plant work on latan 2.

Alstom mobilized onsite to begin its work on boiler erection shortly after signing of the Collaboration Agreement. Fortuitously, the cancellation of another large project opened up the work schedule of Kiewit Power, a very experienced prime contractor in the power industry. Kiewit Power was subsequently selected as the contractor responsible for all balance-of-plant construction, construction interface with the boiler island, and assembly of the steam turbine generator.

Plant Systems' Design

The design of several plant systems deserves particular note given their unique approach for solving sticky problems, often with a simple solution.

Coal- and Ash-Handling Systems. Coal is delivered to the plant by BNSF railroad by one or two unit trains each day. The coal is dumped through a single rotary car dumper and delivered by a stacker reclaimer, a system that has proven its reliability since latan 1 was put into service. The design of latan 2 added a parallel stackout pile with the capacity to handle the coal delivered by two unit trains. Also added was a second delivery conveyor to latan 1 to match the redundant conveyors installed on latan 2. When operating at full load, each unit consumes about 10,000 tons a day, the equivalent of about one and one-half unit trains each day. The conveyors are fully enclosed and have a considerable number of dust collection stations, including the transfer towers (Figure 3). Automatic Systems Inc. supplied the fuel- and material-handling equipment and was responsible for its installation.



3. Carrying coal. Coal is delivered to each of the two units via a common, redundant conveyor system. The conveyor is enclosed with dust collectors, ensuring no fugitive emissions occur. *Courtesy: KCP&L*

The coal pile, sized to about 50 days' storage (about 1,000,000 tons) is managed using rubber-tired vehicles. The size of the stockpile at any time is usually determined by external factors, such as the projected conditions of the rail after flooding in the Missouri River basin.

latan 2's dry ash system, part of KCP&L's commitment to eliminate ash ponds and wet ash sluicing at latan, required construction of a new dry ash landfill with the requisite liners and leachate collection and monitoring systems to ensure that any water collected does not seep into the ground, particularly from rainfall and drainage. latan 1 was also retrofitted from wet sluice bottom and fly ash to dry ash.

Portions of the bottom dry ash are sold for construction materials, particularly as an additive in cement products, although the rate of sale closely follows construction demand. Gypsum from the wet FGD

system is transferred by truck to the dry ash landfill, located only about 2 miles from the plant. Unsold fly ash is also transferred by trucks from each unit's ash silos to the landfill. Unlike other plants with mercury control, ACI carryover into the dry ash has been minute and has not affected ash sales.

Water and Wastewater Systems. One of the design challenges facing KCP&L was treatment of the large amounts of wastewater produced by the two wet FGD systems. This additional wastewater, about 60 gpm, would have required the water discharge permits to be modified, causing a potential delay in the plant's permitting schedule. Adding to the water discharge challenge was the large amount of cooling tower blowdown from latan 2's 12-cell evaporative cooling tower that must also be treated and disposed. (latan 1 is a once-through cooling plant and does not have evaporative cooling towers.)

As part of the permitting process, KCP&L committed to regulators that latan would become a zero–liquid discharge (ZLD) plant. KCP&L assigned the task to engineer and construct the ZLD system to Burns & McDonnell. The conceptual approach was to minimize wastewater production by using evaporation followed by spreading the remaining concentrate on the fly ash, a much less expensive and much more reliable approach than using a conventional crystallizer and solids disposal. Essentially, the ZLD system takes all concentrated waste streams from plant processes and either reprocesses the water for plant reuse, or the surplus brine produced is used for ash dust control. The Burns & McDonnell system is simple yet very effective.

Water supply to the plant is much more complicated than merely drilling a well and dropping in a pump. Instead, another simple, yet inspired approach was taken. A vertical caisson collector well was placed into the sandy ground and sunk about 100 feet deep near the Missouri River. Operating opposite of the common septic leech field, a drain field was installed below the river water level. The effect is that river water is collected in the underground collector well through the equivalent of a massive sand filter. Clean water is collected and pumped to the plant using 10,000-gpm pumps, with a maximum of 14,500 gpm possible. By taking this approach to collect makeup water, the entire matter of water withdrawals avoids the expected requirements of the upcoming revisions to the Clean Water Act Section 316(b). Makeup water is subsequently clarified and used as supply water to the wet FGD or goes through further treatment before being used as boiler makeup water.

Air Quality Control Systems. On the exhaust gas side of the plant, similarly sized air quality systems supplied by Alstom Power were installed on both latan units. NO_x emission limits are based on a 30-day rolling average, giving the plant some operating flexibility. The boilers have proven capability to operate with NO_x levels in the 0.055 lb/million Btu range, well within the permit limit of 0.070 lb/million Btu (see Table 3). The plant has experienced little problem with ammonia slip.

The baghouses on both units are essentially identical, although latan 2 uses 25,000 bags while latan 1 uses slightly fewer and is outfitted with four fewer compartments than latan 2. Opacity permit limits are set at 15%, although the plant has operated reliably in the 1% to 3% range.

The wet FGD systems, using the same size vessel on both units, routinely operate at 99% removal, producing SO_2 levels in the exhaust gas well below the 0.06 lb/million Btu permit limit. Each vessel is equipped with five recycle pumps but usually runs only three or four, depending on operating conditions.

There are other common systems at the plant, such as the wet FGD reagent preparation equipment. In addition, the stack was constructed to enclose the stack gas exhausts from both units (Figure 4). The

ammonia preparation system, common to both units, uses truck-delivered normal aqueous ammonia and a common large storage tank. Another common system is the No. 2 diesel fuel system used for boiler startup; adding another system for latan 2 triggered new and expensive requirements, so the single system does double duty.



4. Combined stack. The two units' wet scrubber vessels are located on opposite sides of the new combined stack. Note that the SCR system is integrated into the structure of latan 2, unlike at latan 1, shown in Figure 2. *Courtesy: KCP&L*

Steam Turbine System. A unique feature of latan 2's design is the ability to peak the output of the plant while not burning any additional fuel. The steam turbine system is designed with five feedwater heaters on the low-pressure side and three on the high-pressure side (Figure 5). The top feedwater heater on the high-pressure side is designed to be closed, thereby taking the feedwater heater out of service. In this circumstance, the turbine extraction steam instead travels through the steam turbine to produce more power, up to 40 MW.



5. Supercritical steam turbine. Toshiba supplied the 930-MW (gross), 850-MW (net) steam turbine. A unique feature of latan 2 is the ability to valve out the top feedwater heater to produce an additional 40 MW at the penalty of about 100 Btu/kWh in heat rate. *Courtesy: KCP&L*

However, this additional power doesn't come without a cost. The additional steam flow to the condenser, after passing through the steam turbine, produces lower feedwater temperatures and therefore suboptimal performance conditions at a constant fuel flow. This off-design operation results in a reduction in the plant heat rate of 100 Btu/kWh. No question this is cheap peaking power—a motor-operated valve costs much less than a 40-MW gas turbine.

Challenges Overcome

Downey believes that KCP&L's oversight of the project played a key role in the successful and on-time completion of latan 2. The project team was augmented by experienced project consultant Burns & MacDonnell and an executive oversight committee (EOC) joined by experts from the law firm of Schiff Hardin, specialists in energy law; construction contracting; and management of large, complex construction projects. The project team was responsible for the overall integrated project schedule and tight management of contractors on the job site.

The EOC, also with representatives on the job site, served as an independent voice reporting directly to Downey. The EOC, augmented by the company's legal, regulatory, and other senior company leadership, was responsible for producing the 18 quarterly reports to the Kansas and Missouri commissions and for preparing regulatory testimony at the end of the project to justify the project schedule and expenditures. Downey said that the prime rule on the project was total transparency in all actions taken by all team members.

The project team, led by Bob Bell, senior director of construction, was given much flexibility to deal quickly with emerging business issues. One change discussed earlier was the switch from direct contracting to selecting Kiewit Power to manage the balance-of-plant portion of the project, a decision that paid dividends over the course of the project.

To many, the relatively deep involvement of the EOC in the affairs of the project would be a source of friction. Instead, this EOC was very supportive of the project team and able to make decisions quickly when the project ran into hard spots, because its members were always up to speed on the business side of the project.

A good example of the function of the EOC was the mediation process used. If a contractor believed a scope change was warranted, the documentation was to be submitted immediately rather than being held until the end of the project. If the project team and the contractor were unable to reach an agreeable resolution on the contractor's claim, then an outside mediation process was required to vet the disagreements, be a sounding board to challenge both parties, and reach a conclusion.

KCP&L believes that the strong presence of the project team and the EOC on the project site put it in a strong position when negotiating these claims. Downey said the process was not without pain. Four or five major claims reached the mediation process during the five-year project, usually requiring senior leadership of the parties to get in a room for a couple of days with the mediator to work out a suitable decision. According to Brent Davis, KCP&L director of projects and supply, "The support of the senior leadership team was key to the overall success of this project."

Another major challenge for the project team, according to Davis, was the overall project schedule

integration. At the peak of construction, there were up to 4,000 people on site at the same time in a very constrained work area (Figure 6). The KCP&L construction management staff peaked at 200 people, including those responsible for monitoring project costs and schedule, quality control, and inspection. However, site logistics were difficult when the AQCS upgrades on latan 1 and the boiler construction of latan 2 were fighting for worksite space, especially during the period from the fall 2008 latan 1 outage to connect up the AQCS through the late summer of 2009.



6. Tight site. The project team was responsible for managing a very constrained work site where multiple contractors were working on the air quality control equipment upgrades on latan 1 at the same time as latan 2 was under construction. At the project peak, 4,000 workers were on site. *Courtesy: KCP&L*

Developing New Staff

Maintenance for the entire plant is conducted by a single department, though the operators are assigned to a particular unit. Common equipment between the units is operated by more junior operators. Until recently, each unit had a separate control room, but this spring, the control rooms were integrated into a single space, a move that has paid dividends with increased teamwork.

On latan 1, the old Bailey I90 system was replaced with new digital controls supplied by Emerson (Figure 7), virtually identical to those supplied for latan 2. (The older unit is a subcritical unit; latan 2 operates at supercritical steam conditions.) The old latan 1 control room will not go to waste, however. KCP&L has purchased a high-fidelity simulator for each unit that was used for operator training and testing purposes prior to startup of each unit. (The operators were put through a training regimen using not only the simulator but also other vendor-supplied training before startup began.) These simulators are scheduled to be installed in the old control room with the goal of reproducing the look and feel of the actual control room, enhancing the operator training process.



7. Consolidated controls. The decade-old controls on latan 1 were replaced with state-of-the-art Emerson controls to match those installed on latan 2, and the control panels were colocated in a single control room. In addition, high-fidelity simulators, one for each unit, were used to train operators prior to startup. The simulators will soon be placed in the old latan 1 control room, which will be configured to look much like the actual plant control room. *Courtesy: KCP&L*

Startup Moved Quickly

The startup of latan 2 was, well, mostly uneventful. This lack of drama was attributed by Davis to the project team doing its homework. The team prepared risk assessements of the startup, ensured that operators had completed needed training, and dispatched myriad technical details before the day the unit was first synchronized to the grid. First fire in the boiler was on March 25, 2010, followed by steam blows on June 3, 2010—a suprisingly short time. First synchronization was on July 20, and coal was introduced to the boiler on the same day, an unusually quick process. In fact, the unit continued to run so well that all of the contract-required in-service criteria established by both state commissions were met on August 26, 2010.

The project team resolved typical punch list items while the plant continued to run over the next three months. On December 7, 2010, Missouri Governor Jay Nixon dedicated latan 2 along with officials representing the plant ownership. The governor marked the occasion by flipping a switch that symbolically put the plant into normal operating mode. The plant was declared commercial on December 31, 2010, and released to the Southwest Power Pool for dispatch.

At the plant dedication, Chesser noted that, "Meeting the in-service requirements for latan 2 this summer is a testament to the quality of work done by our engineering, construction and start-up teams.... This will mark the successful completion of our Comprehensive Energy Plan, which will provide customers affordable and reliable energy to meet our region's growing energy demand for generations to come."

Davis summed up his experiences, and surely those of the entire project team, when he said, "There are few undertakings in this industry more difficult and complex than constructing a coal plant." He added, "Having been involved in the project from day one, I can proudly say that our execution in the construction and startup of latan 2 was world class." We agree.

-Dr. Robert Peltier, PE is POWER's editor-in-chief.

Close Window