Exhibit No.:

Issue: Dismantlement Costs

Witness: Christopher "Chris" Robert Rogers

Type of Exhibit: Direct Testimony

Sponsoring Party: KCP&L Greater Missouri Operations Company

Case No.: ER-2016-0156

Date Testimony Prepared: February 23, 2016

MISSOURI PUBLIC SERVICE COMMISSION

CASE NO.: ER-2016-0156

DIRECT TESTIMONY

OF

CHRISTOPHER "CHRIS" ROBERT ROGERS

ON BEHALF OF

KCP&L GREATER MISSOURI OPERATIONS COMPANY

Kansas City, Missouri February 2016

DIRECT TESTIMONY

OF

CHRISTOPHER "CHRIS" ROBERT ROGERS

Case No. ER-2016-0156

1	Q:	Please state your name and business address.
2	A:	My name is Christopher "Chris" Robert Rogers and my business address is Sega, Inc.,
3		16041 Foster Street, Overland Park, Kansas 66085.
4	Q:	On whose behalf are you testifying?
5	A:	I am testifying on behalf of KCP&L Greater Missouri Operations Company ("GMO" or
6		the "Company").
7	Q:	What is the purpose of your testimony?
8	A:	The purpose of my testimony is to present and support the report attached to my
9		testimony as Schedule CRR-2 which separately addresses the near-term costs of
10		retirement and the potential future costs for dismantlement of GMO's fossil-fueled
11		electric generating units. All costs are presented in 2015 dollars as if incurred over night.
12		No timeline for retirement or dismantlement was considered in this study. As further
13		described later, certain activities are required by permit or regulation to be performed
14		upon retirement of a unit and their resulting costs would be incurred immediately at
15		retirement.
16	Q:	Please describe your educational background, professional training and experience.
17	A:	Since graduating from Kansas State University with a Bachelor of Science in Mechanical
18		Engineering, I have practiced engineering, principally in the power industry, for more
19		than 40 years. During the first decade of my career, I performed design, construction

contracting, scheduling, and resident construction management services for new coalfired electric generating stations with a nationally-recognized architect/engineer firm in Kansas City. During this interval I also completed a Master of Science in Civil Engineering specializing in construction management from the University of Missouri-Columbia.

From 1983 through 1986 I served as the Manager of Generating Facilities on the staff of the Missouri Public Service Commission ("Commission" or "MPSC") and participated in several major rate cases, including the AmerenUE Callaway Nuclear Plant and KCP&L Wolf Creek Nuclear Plant rate cases before the MPSC. Later while employed as a consultant, I provided testimony on behalf of Aquila, Inc. in the South Harper Generating Facility certification case before the MPSC. I have also testified before the Hawaii Public Utilities Commission on behalf of the Hawaii State Consumer Advocate.

I am currently an employee-owner and Vice President of Sega, Inc., ("Sega") an engineering and technical services firm located in Overland Park, Kansas. Among other duties, I provide consulting and project management services for Sega's electric power generating clients. Since joining Sega in 1994, I have worked on many projects for KCP&L and our other electric utility clients. Sega has provided engineering services for numerous plant betterment and new capacity projects for KCP&L's generation stations.

In 2012, I provided pre-filed testimony in support of KCP&L before the Kansas Corporation Commission in Docket No. 12-KCPE-764-RTS regarding the near term costs of retirement and the potential future costs for dismantlement of the Company's

1		fossil-fueled electric generating units. In 2014, I also provided pre-filed testimony for
2		KCP&L before the MPSC in Case No. ER-2014-0370 on this issue.
3	Q:	Do you hold any professional licenses?
4	A:	Yes. I am a licensed professional engineer in the State of Missouri (License No. 21087)
5		and 12 other states. I also hold a Certificate of Record from the National Council of
6		Examiners for Engineering and Surveying (No. 19249).
7	Q:	Have you prepared an appendix that describes your training, licenses and power
8		industry experience?
9	A:	Yes. My professional qualifications are provided in Schedule CRR-1.
10	Q:	Have you previously testified in a proceeding before the MPSC or before any other
11		utility regulatory agency?
12	A:	Yes, I have previously testified before the MPSC, the Public Utility Commission of the
13		State of Hawaii and the Kansas Corporation Commission. The subject matter and
14		references for the cases in which I participated are provided at the back of Schedule
15		CRR-1.
16		SUMMARY
17	Q:	Would you briefly describe the retirement and dismantlement costs developed for
18		GMO's non-nuclear generating units?
19	A:	Sega was retained by GMO to study the cost of decommissioning GMO's non-nuclear
20		generating units. Decommissioning is the planned and orderly retirement of a generating
21		unit and the dismantlement and reclamation of the site. The term decommissioning
22		includes both retirement and dismantlement activities. Upon retirement from service, a
23		generating unit may either be rendered safe and stored almost indefinitely through on-

going maintenance and security measures or it can be dismantled completely and the site reclaimed for other uses. Based upon Sega's experience in the electric generation industry at large and our familiarity with GMO's generating fleet, Sega developed an opinion of the probable costs for GMO to retire each of its fossil-fueled generating units. Costs for dismantlement were also developed separately for each unit.

Please summarize retirement of an electric generating unit.

Q:

A:

Retirement, as used in this study, refers to the planned, orderly and safe shutdown and removal from service of an electric generating unit, and assumes that the unit will not be used for service again. No actions will be taken to preserve the unit or any of its components for reuse. Retirement activities are specific to each unit and to the common facilities at sites with multiple generating units. Common site facilities are presumed to remain in service until the last unit on that site is retired.

Approximately three to six months before initiating retirement, a specific retirement plan will be prepared for each unit that takes into account the requirements of environmental permits and regulations for removing that unit from service. The retirement plan will also provide for necessary safety and security measures during retirement of the unit and for the time period from retirement until dismantlement.

First, the unit is rendered safe by de-energizing it and disconnecting it from providing output to the electric grid. The switchyards at each unit will remain in service, but isolated from the retired facility. Mechanical systems are de-energized as well. Fuel unloading, handling and storage facilities will be cleaned out, as well as all liquids, chemicals, coolants and reagents. Certain activities are required by specific unit permits and/or state or federal regulations to be performed when the unit ceases operations.

These may include closure of ash landfills, removal of river water intakes, and/or removal of fuel oil storage tanks. However, retirement activities do not include asbestos and lead paint abatement measures that are typically handled as ongoing maintenance expenses during the operating life of the unit and continuing if necessary after retirement. More detail is provided on retirement activities in our report, which is Schedule CRR-2.

Please summarize dismantlement of an electric generating unit.

Q:

A:

Q:

A:

Once the unit or facility has been retired and its dismantlement is scheduled, an engineer will be retained to assist with environmental issues and technical details and develop a detailed dismantlement plan. The unit or facility will be characterized and the boundaries for demolition defined to set the scope of the work. A specialty demolition contractor will be hired to perform dismantlement and salvage. Dismantlement as contemplated in this study provides for the orderly removal of the unit's components to maximize safety and scrap value while preventing damage to the surrounding facilities. The assumptions for dismantlement for each of the units and facilities are provided in Schedule CRR-2.

Did you consider salvage value in reaching your opinion of probable dismantlement costs for these units?

Yes, the approximate scrap values for iron and steel and non-ferrous metals were tallied for each unit or facility, based upon estimated quantities and averaged current-year scrap prices. These scrap values were listed separately because the scrap metal prices vary considerably, depending on industrial trends, international events and uncontrollable circumstances at the time of the salvage transactions.

Q: What are the results of your study?

A:

The opinion of the probable costs for retirement and dismantlement developed by Sega for each of GMO's fossil-fueled units and the common facilities at each plant site are provided below in Table 1. All costs shown are in 2015 dollars as if the activities were performed in the current year and do not account for ownership percentages and jurisdictional allocations. The development of these costs is described and supported by the report in Schedule CRR-2.

In addition, Table 1 also contains a line item for retirement of common facilities at the Jeffery Energy Center (JEC). Sega did not perform a study of the costs for decommissioning the JEC. GMO owns a portion of the JEC, and Westar is the owner and operator of this generating plant. As with the other GMO-owned plants, certain activities are required by specific unit permits and/or state or federal regulations to be performed when the unit ceases operations. In the case of the JEC this includes closure of ash landfills. Since the costs for ash landfill closure are documented by Westar and submitted annually to the Kansas Department of Health and Environment, these costs were included in this Table 1. GMO will certainly have additional retirement costs when JEC is retired, but such costs have not yet been determined.

As shown below in Table 1, there is a significant difference in cost between retiring and dismantling a power plant. The costs to retire all of GMO's non-nuclear generating units and the additional costs for the JEC ash landfill closure at retirement are estimated to be approximately \$87.3 million. To dismantle all of GMO's non-nuclear units, I estimate that it would cost an additional \$208.3 million, which does not include JEC. Some components could be sold for scrap during dismantlement thereby recovering

- 1 an estimated \$38.5 million and bringing the estimated Net Terminal Value (cost to
- dismantle less salvage) for all of GMO's fossil-fueled plants to \$169.9 million. This
- 3 amount does not include JEC.

Table 1 - Opinion of The Probable Costs for Decommissioning GMO's Electric Generating Units

(All cost values in 2015 dollars)

			First Year In Service	Retirement			Dismantlement			
Name	Unit No.	Total Unit Capability ⁽¹⁾ _{MW}			Activities Required by Permit, Regulation ⁽²⁾ , or Agreement ⁽³⁾	Total Retirement	Dismantlement	Scrap Value ⁽⁴⁾	Net Terminal Cost	
	1	49.8	1960	\$482,368		\$482,368	\$6,034,974	\$848,154	\$5,186,820	
Sibley	2	47.1	1962	\$482,368		\$482,368	\$6,034,974	\$848,154	\$5,186,820	
,	3	364.1	1969	\$535,958	4	\$535,958	\$16,835,426	\$2,757,087	\$14,078,339	
	Common			\$531,710	\$13,950,965	\$14,482,675	\$10,134,174	\$1,564,206	\$8,569,968	
O + 1 1	1	101.2	0005	£404.005		£404.005	© 0.000.405	#050.040	CO 004 470	
South Harper	2 3	102.1 100.0	2005	\$404,885		\$404,885	\$9,383,425	\$358,946	\$9,024,479	
	1	60.7	1975							
	2	61.7	1975							
Greenwood	3	63.0	1977	\$413,021	\$471,333	\$884,354	\$11,063,645	\$353,736	\$10,709,909	
	4	60.7	1979							
	1	75.4								
Crossroads	2	77.9	2002	\$400,303		\$400,303	\$11,249,327	\$389,486	\$10,859,841	
Orosoroads	3	75.9	2002	ψ100,000		Ψ100,000	Ψ11,240,027	φοσο, 100	Ψ10,000,041	
	4	77.8								
KCI	1 2	0	1971	\$227,662		\$227,662	\$2,789,050	\$91,317	\$2,697,733	
Nevada	1	17.7	1974	\$281,190	\$56,530	\$337,720	\$6,434,106	\$45,397	\$6,388,709	
Ralph Green	3	70.9	1981	\$285,572	\$81,385	\$366,957	\$6,156,152	\$95,230	\$6,060,922	
	Boiler 1	N/A	1962	\$120,344		\$120,344	\$3,098,749	\$117,312	\$2,981,437	
	Boiler 2	N/A	1962	\$120,344		\$120,344	\$3,098,749	\$117,312	\$2,981,437	
	Boiler 3	N/A	1937	\$161,768		\$161,768	\$3,611,257	\$151,376	\$3,459,881	
	Boiler 4	N/A	1951	\$138,357		\$138,357	\$4,045,457	\$196,024	\$3,849,433	
	Boiler 5	N/A	1957	\$183,266	\$1,175,349	\$1,358,615	\$6,388,857	\$224,107	\$6,164,750	
	Boiler 8	N/A	2006	\$105,550		\$105,550	\$2,250,354	\$224,107	\$2,026,247	
Lake Road	#4 / #6	96.3	1966	\$386,400	\$637,591	\$1,023,991	\$8,380,637	\$1,262,740	\$7,117,897	
	Generator 1	9.4	1950	\$49,349		\$49,349	\$2,375,879	\$38,162	\$2,337,717	
	Generator 2	19.0	1958	\$49,349		\$49,349	\$2,615,898	\$43,797	\$2,572,101	
	Generator 3	6.6	1962	\$43,656		\$43,656	\$1,874,480	\$25,661	\$1,848,819	
	CT 5	67.0	1974	\$209,711		\$209,711	\$2,414,288	\$88,266	\$2,326,022	
	CT 6 CT 7	21.0 20.5	1989 1990	\$159,554		\$159,554	\$1,665,869	\$91,317	\$1,574,552	
	Common	20.5	1990	\$875,025	\$174,289	\$1,049,314	\$4,054,680	\$248,964	\$3,805,716	
	1	712.9	1980	\$1,035,765	\$36,970,077	\$38,005,842	\$24,018,833	\$10,000,000	\$14,018,833	
latan	2	881.5	2010	\$1,031,343	ψου,υ. υ,υτι	\$1,031,343	\$27,449,519	\$11,430,000	\$16,019,519	
	Common			\$590,627	\$6,042,837	\$6,633,464	\$24,874,543	\$6,850,000	\$18,024,543	
loffon	1	718.0	1978		. , , , , , , , , , , , , , , , , , , ,		. , , , , , ,	. , , , , , , , , , , , , , , , , , , ,	, , ,	
Jeffery Energy	2	715.0	1980							
Center ⁽³⁾	3	722.0	1983							
Center.	Common				\$18,426,409	\$18,426,409				
тот	ALS	5,395	N/A	\$9,305,445	\$77,986,765	\$87,292,210	\$208,333,302	\$38,460,858	\$169,872,444	

- $\frac{\underline{\text{Notes}}}{\text{Current net SPP accredited unit capability, MW}}.$
- (2) Activities required by permits and/or regulations that are to occur upon ceasing operations, including ash landfill closures, and river water intake.
 (3) GMO owns a percentage of Jeffery Energy Center. Westar is the controlling owner.
- (4) Current scrap values per averaged indices.

1 Q: Are retirement costs optional for GMO?

At present, GMO is not required to dismantle its plants upon retirement, and therefore, it is not known when, or even if, the portion of the costs in my study related only to dismantlement will be incurred. However, that is not the case for the costs of retiring the generating units and common facilities. Retirement costs are the costs that will be unavoidably incurred by the Company when the plant is shut-down, even if the closed plant is never dismantled.

8 Q: How have the results of your study been used in this case?

9 A: It is my understanding that the retirement costs I have identified have been incorporated into the depreciation study performed for GMO by Company witness, Mr. John Spanos.

It is also my understanding that Mr. Spanos has not included the dismantling costs from my study in his depreciation study. By keeping the two categories of costs separate in my study, I have facilitated Mr. Spanos' efforts in this regard, and I have provided substantial evidence to the Commission clearly showing the distinction between the two categories of costs.

16 Q: Was the Schedule CRR-2 study prepared under your direction and supervision?

17 A: Yes. I am the Officer-in-Charge at Sega for this study and participated in determining the
18 methodology and in the performance of the work with our team. I visited each of the
19 plant sites, provided oversight during preparation of the report, and reviewed the results
20 for reasonableness and appropriateness.

21 Q: Does this conclude your testimony?

22 A: Yes.

BEFORE THE PUBLIC SERVICE COMMISSION OF THE STATE OF MISSOURI

In the Matter of KCP&L Greater Missouri Operations Company's Request for Authority to Implement A General Rate Increase for Electric Service Case No. ER-2016-0156
AFFIDAVIT OF CHRISTOPHER R. ROGERS
STATE OF KANSAS)) ss COUNTY OF JOHNSON)
Christopher R. Rogers, being first duly sworn on his oath, states:
1. My name is Christopher R. Rogers. I am employed by Sega, Inc. I have been
retained to serve as an expert witness to provide testimony on behalf of KCP&L Greater
Missouri Operations Company.
2. Attached hereto and made a part hereof for all purposes is my Direct Testimony
on behalf of KCP&L Greater Missouri Operations Company consisting of <u>Sight</u>
() pages, having been prepared in written form for introduction into evidence in the above-
captioned docket.
3. I have knowledge of the matters set forth therein. I hereby swear and affirm that
my answers contained in the attached testimony to the questions therein propounded, including
any attachments thereto, are true and accurate to the best of my knowledge, information and
Christopher R. Rogers
Subscribed and sworn before me this 5^{+k} day of February, 2016.

Notary Public

My commission expires: December 29, 2018

Vice President, Sega Inc. **POSITION**

EDUCATION B.S.M.E., 1974

> Kansas State University Manhattan, Kansas

M.S.C.E. Civil Engineering – Construction Management, 1981

University of Missouri-Columbia

Columbia, Missouri

LICENSES Professional Engineer Licenses

> California Illinois

 Colorado Kansas

Florida

 Kentucky Hawaii Michigan

Idaho Missouri Montana

North Carolina

Utah

NCEES Record Certificate

AFFILIATIONS American Society of Mechanical Engineers

EXPERIENCE SUMMARY

Mr. Rogers is a Vice President of Sega Inc. and a licensed professional engineer with 40 years of experience in the power industry. He leads the firm's corporate risk management activities and directs the firm's planning and studies practice. Mr. Rogers also provides project management and engineering services for Sega's electric power generating clients.

He has provided engineering and management services for many types of electric generating projects, including simple and combined cycle combustion turbine units, coal and waste coal-fired fluidized bed boiler plants, pulverized coal units, and biomass-fired plants. He has performed engineering and feasibility reviews for financing, construction monitoring, and performance testing of numerous generating facilities.

Mr. Rogers was the Manager of Generating Facilities in the Electric Department of the staff of the Missouri Public Service Commission from 1983 through 1986. He supervised the construction management audits in the rate cases for the Callaway Plant and Wolfcreek Nuclear Generating Station, had limited participation in the Grand Gulf Nuclear Station rate case, and performed other assignments concerning regulated generating facilities throughout the State of Missouri.

During the first decade of his career, Mr. Rogers performed mechanical engineering design services for large utility-owned coal-fired central generating facilities while employed by a nationally recognized consulting engineering firm. He served on project design teams in the main office and as the chief mechanical resident engineer on a green-field, coal-fired power plant construction site.

SELECTED PROJECT EXPERIENCE

Kansas City Power & Light Company, Kansas City, Missouri - Officer-in-charge of study for the 2016 Kansas City Power & Light – Greater Missouri Operations Company (GMO) Missouri rate case providing opinion of probable costs of retirement and dismantlement of 25 fossil-fueled generating units totaling approximately 1,720-MW of capacity, including six (6) coal-fired units, and fifteen (19) combustion turbines. Prepared direct testimony for filing with the Missouri Public Service Commission sponsoring Sega's report in Case No. ER-2014-_____.

Officer-in-charge of study for the 2014 Missouri rate case providing opinion of probable costs of retirement and dismantlement of 24 fossil-fueled generating units and 99 wind turbine generators totaling 5,306-MW of capacity, including eight (8) coal-fired units, one (1) combined-cycle plant, and fifteen (15) combustion turbines. Submitted pre-filed direct testimony before the Missouri Public Service Commission sponsoring Sega's report in Case No. ER-2014-0370.

Officer-in-charge of study for the 2014 Kansas rate case providing opinion of probable costs of retirement and dismantlement of 24 fossil-fueled generating units and 99 wind turbine generators totaling 5,306-MW of capacity, including eight (8) coal-fired units, one (1) combined-cycle plant, and fifteen (15) combustion turbines. Prepared direct testimony for filing with the Kansas Corporation Commission sponsoring Sega's report for Docket No. 15-KCPE-116-RTS.

Officer-in-charge of study for the 2012 Kansas rate case providing opinion of probable costs for retirement and dismantlement of 24 fossil-fueled generating units totaling 5,260-MW of capacity, including eight (8) coal-fired units, one (1) combined-cycle plant, and fifteen (15) combustion turbines. Provided pre-filed direct and rebuttal testimony before the Kansas Corporation Commission sponsoring Sega's report in Docket No. 12-KCPE-764-RTS.

Kansas City Power & Light Company, Kansas City, Missouri - Officer-in-charge and
project manager for 2014 power plant siting study to identify and evaluate multiple
candidate sites for potential location of a new combined-cycle plants, simple-cycle
peaking turbines, and reciprocating engine generating plants. Provided detailed report
of findings to Kansas City Power & Light Company Resource Planning Department.

Officer-in-charge and project manager for 2010 Great Plains Energy combined cycle plant siting study to identify and evaluate multiple candidate sites for potential location of new 600-MW class combined-cycle plant. Provided detailed report of findings to Kansas City Power & Light Company Resource Planning Department.

- Kansas City Power & Light Company GMO, Lake Road Generating Station, St. Joseph, Missouri Officer-in-charge and project manager for a study that assessed the feasibility of the KCP&L industrial steam generation and delivery system to serve its industrial steam customers.
- Kansas City Power & Light GMO (Formerly Aquila), South Harper Peaking
 Facility, Peculiar, Missouri 315-MW simple-cycle peaking plant. Project manager of
 Owner's Engineer for siting, permitting support, detailed installation design, balance of
 plant procurement, construction management services, commissioning, and
 documentation support. Sega's project manager and site manager.
- Kansas City Power & Light, West Gardner and Osawatomie Generating Stations –
 Two simple-cycle peaking projects. Sega, Inc's turnkey proposal manager for engineer-led EPC proposal for 400-MW of GE 7E gas turbine generator sets.
- Independence Power & Light Department, Independence, Missouri Master plan study for a nominal 320-MW municipal utility. Project manager for five-year planning study including existing generation assessment, transmission system assessment, load forecast, alternative power supply analysis and economic evaluation.
- State of Hawaii Division of Consumer Advocacy Investigated island-wide blackouts that occurred on Oahu and Maui after the earthquakes on October 15, 2006 and again on Oahu after lightning events on December 26, 2008. Officer-in-charge and project manager of team investigating causes of the outages, assessing utility outage recovery operations and identifying potential improvements to prevent or minimize future outages.
- Utah Municipal Power Agency, Spanish Fork, Utah Officer-in-charge and project manager for due diligence assessment of a simple cycle 200-MW peaking plant consisting of five GE LM6000 combustion turbine generator sets.
- Utah Municipal Power Agency, Spanish Fork, Utah Officer-in-Charge and Project manager for a study assessing the feasibility of potential sites and development of opinions of probable cost for installation of simple-cycle combustion turbines and reciprocating engine generating sets as a subcontractor to Sawvel and Associates of Findlay, Ohio.

- Kansas City Board of Public Utilities, Nearman Creek CT4, Kansas City, Kansas 85-MW simple-cycle peaking unit. Owner's Engineer (Sega, Inc.) site manager for commissioning, including checkout, performance testing, emissions testing and management of construction completion closeout activities.
- Trigen Kansas City Energy Corporation, Kansas City, Missouri Sega, Inc.'s project manager for feasibility study to repower a district heating plant with an 80-MW combustion turbine and heat recovery steam generator cogeneration project.
- Conserve Energy System, Centralia, Illinois Sega, Inc.'s project manager on a technical feasibility study for a 215-MW coal-fired atmospheric circulating fluidized bed boiler steam electric generating plant.
- Cargill, Inc., Blair, Nebraska Sega, Inc.'s project manager for feasibility study for an 100-MW net combustion turbine and heat recovery steam generator cogeneration project.
- Independence Power & Light Department, Independence, Missouri Sega, Inc.'s project manager for major refurbishment program on six GE Frame 5 and one GE 7B-regenerative, oil and gas-fired gas turbines. Project included condition assessments, specifications, and contracting for renewal and upgrade components, unit controls replacement, remote digital controls addition, and major overhaul of each unit.
- Somerset Generating Station, Somerset, Massachusetts Black & Veatch's project manager on independent engineering review, performing condition assessments for Montaup Electric Company's divestiture of a 40-MW net, oil-fired combustion turbine (2 x FT4) black start peaking unit, a 100-MW coal-fired power plant, a total of 16-MW of diesel generators (8 x 2-MW GM-EMD) and a 2-MW hydro electric plant.
- Constellation Energy, Freehold, New Jersey Sega, Inc.'s project manager for review of project proforma and preparation of testimony before the New Jersey Board of Public Utilities concerning net present value of a 110-MW net, gas-fired combined cycle cogeneration project.
- Cherokee County Cogeneration Project, Gaffney, South Carolina Sega, Inc.'s
 project manager for an 80-MW net, gas-fired combined cycle (GE 106FA) cogeneration
 project in Gaffney, South Carolina for Prudential Power Financing. Performed technical
 review of project during design, permitting, contracting, and financing. Conducted
 construction monitoring for lender. Also served as interim president of project
 development entity during lender's takeover of project and equity sale to FP&L.

- Independence Power and Light, Independence, Missouri Sega, Inc.'s project
 manager for study of 100-MW coal-fired steam electric unit, including conceptual design
 and estimating performance and cost for client's comparison to participation in latan II
 Project. Compiled and compared capital and operation and maintenance cost of
 alternative 100-MW coal-fired steam electric plants including pulverized coal and CFB
 plants, and natural gas-fired combined cycle and simple cycle units of the same size.
- Florida State Correction Facility, Starke, Florida Bibb and Associates' project manager for independent review for potential equity investor, KLT Power, Inc. on a 23-MW, wood gasification and natural gas-fired, combined-cycle cogeneration project proposed near Starke, Florida.
- Indeck-Oswego Energy Center, Oswego, New York Bibb and Associates' project manager on independent engineering review for BA Securities, Inc. regarding the power sales agreement during term of financing of 51-MW, gas-fired combined-cycle (GE6B) cogeneration project in Oswego, New York.
- North Carolina EMC, Raleigh, North Carolina Bibb and Associates' project manager
 of the Owner's Engineer team that wrote specifications and evaluated EPC proposals
 for a 330-MW gas-fired combined-cycle project and 100-MW gas-fired simple-cycle
 project in North Carolina.
- Indeck-Olean Energy Center, Olean, New York Bibb and Associates' project
 manager on independent engineering review for bank group consisting of Canadian
 Imperial Bank of Commerce, BOT Financial, Inc., Westpac Banking Corporation, and
 Toronto Dominion Bank. Project was a 79-MW, gas-fired combined-cycle (GE 6B)
 cogeneration project in Olean, New York. Scope included review of technical feasibility
 and economic viability of project for financing, construction progress monitoring and
 oversight of performance demonstration tests.
- Orlando CoGen Limited, L.P, Orlando, Florida. Bibb and Associates' project manager for independent engineering review for senior lender, the Sumitomo Bank, Limited of a 120-MW gas-fired, single-shaft combined cycle (ABB11N1/VAX) cogeneration project in Orlando, Florida developed by Air Products and Chemicals, Inc. and Utilicorp United.
- ACE Cogeneration Project, Trona, California Bibb and Associates' project manager for independent engineering assessment for equity investor, US West Capital, Inc., including design, permit status, operations and maintenance of an existing 96-MW, coal-fired CFB steam electric plant.

- Arroyo Cogeneration, Escondido, California Bibb and Associates' project manager for engineering review of project for development financing for Heller Financial, Inc, including alternate site selection program for a 49.9-MW, gas-fired, combined cycle (GE LM6000) cogeneration project.
- Nestles Freehold Cogeneration Project, Freehold, New Jersey Bibb and Associates' project manager for independent engineering review for development financing by Heller Financial, Inc. of a proposed 110-MW, gas-fired, single-shaft combined cycle (ABB11N1/VAX) cogeneration project by Constellation Energy.
- Intercontinental Energy, Bellingham, Massachusetts and Sayreville, New Jersey –
 Bibb and Associates' project manager for independent engineering review for potential
 equity investor, American Energy Division of Potomac Capital Investment Corporation,
 for two 300-MW, gas-fired combined cycle (2 x W501D) cogeneration projects.
- Sunnyside Cogeneration Project, Carbon County, Utah RW Beck and Associates' project manager for independent engineering review for senior lender, Swiss Bank Corporation, of the design and permitting review of a 50-MW waste coal-fired circulating fluidized bed boiler electric generating plant.
- North Branch Power Project, Bayard, West Virginia RW Beck and Associates' project manager on independent engineering review for financing and construction monitoring for senior lender, Security Pacific Bank of a 80-MW waste coal-fired, circulating fluidized bed boiler project.
- Unocal Geothermal, Monterey, California RW Beck and Associates' engineer, retained by Unocal to provide independent third-party oversight and monitoring of biennial performance tests by Pacific Gas and Electric Company at the Moss Landing Power Station (two 750-MW super-critical, gas and oil-fired steam electric generating units) related to geothermal steam pricing at Unocal's Geysers Geothermal projects.
- St. Nicholas Power Project, Mahanoy Township, Pennsylvania RW Beck and Associates' project manager on independent engineering review for financing, construction monitoring and performance test monitoring for senior lender, Bank of New England for an 80-MW waste coal-fired steam electric plant.
- Callaway Nuclear Generating Station, Fulton, Missouri Manager of Generating
 Facilities for the Missouri PSC staff, investigated and/or provided testimony concerning
 project construction management, in-service criteria, net electric capability,
 decommissioning funding, and in-service completion in rate case for an 1150-MW, PWR
 nuclear generating station.

- Wolf Creek Nuclear Generating Station, Burlington, Kansas Manager of Generating Facilities for the Missouri PSC staff, investigated and/or provided testimony concerning project construction management, in-service criteria and startup, related fossil-fuel plant retirements, related plant accreditations, depreciation, and net electric capability in rate case for an 1120-MW PWR nuclear generating station.
- Grand Gulf Generating Station I, Grand Gulf, Mississippi –. Manager of Generating Facilities for the Missouri PSC staff, investigated and provided testimony concerning inservice criteria, in-service status, and overall project NRC inspection and licensing status for a 1250-MW BWR nuclear generating station.
- Plains-Escalante Generating Station, Unit 1, Prewitt, New Mexico Burns & McDonnell's senior mechanical design engineer for mechanical equipment and systems, equipment procurement, construction contracting and coordination; and chief resident mechanical engineer during construction of a 220-MW pulverized coal power plant.
- Basin Electric Power Cooperative, Inc., Laramie River Station, Wheatland, Wyoming - Burns & McDonnell's mechanical design engineer for equipment and systems, equipment procurement, and construction contracting and CPM scheduler for coordination of construction completion of systems with sequenced system start-up program for three, 600-MW, pulverized coal-generating units for the Missouri Basin Joint Power Project Agency, lead by the Basin Electric Power Cooperative, Inc.

TESTIMONY BEFORE THE MISSOURI PUBLIC SERVICE COMMISSION

Issue Description	Exhibit No.		Transcript Vol. No.	Page Nos.
CASE NOS. EO-85-17 & Phase I – Inservice Criteria	AMEREN ER-84-168 (on b Direct Rebuttal Surrebuttal	ehalf of t l A-7 A-12 A-14	he MO PSC Staff)	492-83
Phase II – Net Electric Capability	Direct Surrebuttal	C-76 C-77	30	2852-2868
Phase III – Funding Decommissioning	Surrebuttal	C-38	28	2434-2440
Phase III – Inservice Review	Supplemental (1-28-85)	NA	NA	NA
CASE NO. ER-85 Status of Grand Gulf 1 and Waterford 3 KANSAS CASE NO. ER-85-128 & Phase I – Inservice Criteria Startup	Supplemental CITY POWER	12 & LIGHT ehalf of the	4	118-181 NA
Phase IV – Fossil Plant Retirement Dates	Direct Direct Surrebuttal	262 266	23	1798-1817
Phase IV – Depreciation – Wolf Creek	Rebuttal	259		
Phase IV – AWS Structural Steel Welding	Direct Surrebuttal	301 302	26	2294-2329
Phase IV – Net Electric Capability	Direct Surrebuttal	399 400	33	3682-3699
Phase IV – Accreditation Overview	Direct Surrebuttal Appendices (9/10/82)	262 436 263	23 7	1798-1817 4451-4483

TESTIMONY BEFORE THE MISSOURI PUBLIC SERVICE COMMISSION (Cont'd)

		•	0.011 (00111 4)	
Issue Description	Exhibit No	0	Transcript Vol. No.	Page Nos.
CASE NO. ER Functionalization and Classification of Costs (Jurisdictional Allocations)	AMEREN -85-265 (on behalf of Surrebuttal	the MO 89	PSC Staff) 6	844-848
	POWER & LIGHT (Fo N-2006-0309 (on beha Direct (filed 01/2	If of the		N/A
	TY POWER & LIGH R-2014-0370 (on beh		•	
The Costs of Retirement and Dismantlement: Decommissioning KCP&L Fossil-Fueled Generating Units	Direct Testimony	131	N/A	N/A

TESTIMONY BEFORE THE PUBLIC UTILITIES COMMISSION OF THE STATE OF HAWAII

Issue Description	Exhibit No.	Transcript Vol. No.	Page Nos.					
HAWAII ELECTRIC LIGHT COMPANY, INC. DOCKET NO. 99-207 (on behalf of Consumer Advocate)								
Keahole Projects or Facilities: 1. Shop/Warehouse Building 2. Fire Protection System 3. Water Treatment System 4. Inclusion in Rate Base Amounts	Direct Pre-filed CA-T- 12 Direct Examination Commissioners' Exam	II II	288 – 301 301 – 309 309 - 313					

HAWAII ELECTRIC COMPANY, INC., MAUI ELECTRIC COMPANY, LTD., AND HAWAII ELECTRIC LIGHT COMPANY, INC. DOCKET NO. 2006-0431 (on behalf of Consumer Advocate)

Consumer Advocates Statement of Filed August 24, 2007 Position: Filed: September, 19,

Consumer Advocate's Supplement 2008

TESTIMONY BEFORE THE KANSAS CORPORATION COMMISSION

Issue Description Exhibit No. Transcript Vol. No. Page Nos.

KANSAS CITY POWER & LIGHT COMPANY, INC. DOCKET NO. 12-KCPE-764-RTS

The Costs of Retirement and Dismantlement:
Decommissioning KCP&L
Fossil-Fueled Generating Units

Pre-filed Direct Testimony
Pre-filed Rebuttal Testimony

Kansas City Power & Light Co.





The Costs of Retirement and Dismantlement:

Decommissioning KCP&L-GMO's Generating Units

Final, Rev. 1





Kansas City Power & Light Co.



The Costs of Retirement and **Dismantlement: Decommissioning** KCP&L-GMO's **Generating Units**

Final, Rev. 1

Sega, Inc. provides this report for the exclusive use and benefit of its Client and, without Sega, Inc.'s written consent, no one else may use or rely upon the contents of this report. Sega, Inc. makes no warranty, express or implied, regarding this report or its services.



TABLE OF CONTENTS

TABLE OF CONTENTS

			<u>Page</u>
CERTIFIC	CAT	'ION	ii-
SECTION	1	EXECUTIVE SUMMARY	1-1
1.1		Introduction	1-1
1.2		Description of Facilities	1-2
1.3		Approach	1-5
1.4		Results	1-6
SECTION	2	RETIREMENT	2-1
2.1		Introduction	2-1
2.2		Opinion of Probable Cost Basis	2-1
2.3		Retirement Activities	2-2
2.4		ARO Activities	2-4
SECTION	3	DISMANTLEMENT	3-1
3.1		Introduction	3-1
3.2		Opinion of Probable Cost Basis	3-1
3.3		Dismantlement Activities	3-2
3.4		Project Closure Activities	3-7
3.5		Scrap Metal Values	3-7
SECTION	4	APPENDICES	
A		Opinions of Costs by Units	
		Sibley South Harper Greenwood Crossroads KCI Nevada Ralph Green Lake Road Iatan	
В		Opinions of Cost for Scrap	
\mathbf{C}		Reference Documents	
D		ARO - Source of Requirement	

CERTIFICATION

I hereby certify that this document was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Missouri.



Christopher R. Rogers, P.E. State of Missouri P.E. No. 021087

SECTION 1

EXECUTIVE SUMMARY

EXECUTIVE SUMMARY

1.1 INTRODUCTION

Kansas City Power & Light Company Greater Missouri Operations (GMO) Company retained Sega, Inc. (Sega) to provide an opinion of probable costs for retirement and dismantlement of its generating units. This report presents the results of Sega's study of the costs for decommissioning these facilities.

Decommissioning is comprised of two principal phases: retirement and dismantlement. Retirement is the shutdown or closure and removal from service of a generating unit or facility, and includes disconnection, de-energization, cleanout, and securing of the units to render them safe. Retirement triggers unavoidable costs for compliance with the mandatory provisions of the various plants' permits and with the specific requirements of State and Federal regulations for the closure of ash landfills, the removal and remediation of fuel-oil tanks, and the reclamation of river water intakes.

GMO is not required to dismantle its plants upon retirement, and therefore, it is not known when, or even if, dismantlement costs will be incurred. Often a unit may not be dismantled until sometime after it is retired, particularly if there are other operational generating units on the same site. *Dismantlement* is the orderly demolition of the unit in a controlled and safe manner so as to preserve the scrap value of reclaimed materials while appropriately protecting the workers and the environment. Scrap values are considered separately from dismantlement costs because scrap values have proven volatile over time. Scrap values in this report were developed from current average index prices, and were netted out against dismantlement costs to produce net terminal costs for each unit. All costs are provided in current day, 2015 dollars.

1.2 DESCRIPTION OF FACILITIES

The GMO generating facilities are located on eight sites and include 18 simple-cycle combustion turbines, four steam electric generating units, and a steam production facility utilizing six boilers that can be fired to generate electricity by supplying steam to three turbine generators or supplying steam to commercial customers. The major attributes of each unit are provided in Figure 1.1 and further described below.

Plant Name	Unit No.			Fuel / Type	
rane		MW	In Service		
C:1-1	1	51	1960	Coal/Steam	
Sibley	2	51 363.8	1962 1969	Coal/Steam	
	3	104.5	2005		
South	2	105.6	2005	Natural Gas-Fired	
Harper	3	103.8	2005	Combustion Turbines	
	1	62.5	1975		
	2	60.8	1975	Distillate-Fired/	
Greenwood	3	65.8	1977	Natural Gas-Fired	
	4	63.3	1979	Combustion Turbines	
	1	74.9	2002		
	2	72.9	2002	Natural Gas-Fired	
Crossroads	3	74.6	2002	Combustion Turbines	
	4	74.4	2002		
TTOT	1	0	1971	Natural Gas-Fired	
KCI	2	0	1971	Combustion Turbines	
Nevada	1	20.8	1974	Distillate-Fired Combustion Turbine	
Ralph Green	3	71.5	1981	Natural Gas-Fired Combustion Turbine	
	Boiler 1	N/A	1962	Distillate-Fired/ Natural Gas-Fired Boiler	
	Boiler 2	N/A	1962	Distillate-Fired/ Natural Gas-Fired Boiler	
	Boiler 3	N/A	1936	Natural Gas Fired Boiler	
	Boiler 4	N/A	1951	Distillate-Fired/ Natural Gas-Fired Boiler	
	Boiler 5	N/A	1959	Coal-Fired/Natural Gas- Fired Boiler	
1	Boiler 8	N/A	2006	Distillate-Fired/ Natural Gas-Fired Boiler	
Lake Road	#4/#6	99.0	1967	Coal-Fired/Natural Gas- Fired	
	Generator 1	21.7	1951	Distillate-Fired/ Natural Gas-Fired Coal- Fired	
	Generator 2	27.3	1957	Distillate-Fired/ Natural Gas-Fired Coal- Fired	
	Generator 3	11.2	1962	Distillate-Fired/ Natural Gas-Fired Coal- Fired	
	#5	63.0	1973	Distillate-Fired/ Natural Gas-Fired	
	#6	21.0	1989	Distillate-Fired Combustion Turbine	
	#7	21.7	1990	Distillate-Fired Combustion Turbine	
T - I	1	705	1980	Coal/Steam	
Iatan	2	881	2010	Coal/Steam	

Figure 1.1 - GMO Electric Generating Units

1.2.1 <u>Facility Descriptions</u>

Sibley Generating Station is a three-unit, coal-fired electric generating station located in Jackson County, near the town of Sibley, Missouri. Sibley Units 1 and 2 have sub-critical boilers, electrostatic precipitators (ESPs), and an SNCR. Sibley Unit 3 is a super-critical boiler, ESP, and an SCR.

South Harper Generating Station is a three-unit, natural gas-fired combustion turbine peaking plant in Cass County, near the town of Peculiar, Missouri.

Greenwood Generating Station is a four-unit distillate and natural gas-fired combustion turbine peaking plant in Jackson County, near the town of Greenwood, Missouri.

Crossroads Generating Station is a four-unit natural gas-fired combustion turbine peaking plant in Clarksdale, Mississippi.

KCI Generating Station is a two-unit, natural gas-fired combustion turbine peaking plant in Platte County, Missouri on the eastern edge of the Kansas City International Airport property.

Nevada Generating Station is a single-unit, distillate and natural gas-fired combustion turbine peaking plant located in Vernon County, near Nevada, Missouri.

Ralph Green Station is a single-unit, natural gas-fired combustion turbine peaking plant located in Cass County, in Pleasant Hill, Missouri.

Lake Road Generating Station is a multi-unit facility located in Buchanan County in St. Joseph, Missouri. Lake Road generates electricity from four steam turbine generators that receive steam from seven different boilers. These boilers burn either gas, distillate, or coal. These same boilers also produce steam that is sold to local steam customers. Lake Road also includes three combustion turbines that fire distillate (CTG 5, CTG 6, and CTG 7) or natural gas (CTG 5).

Iatan Generating Station is located in rural Platte County, near the town of Weston, Missouri. Unit 1 is a pulverized coal-fired, sub-critical steam electric plant with an SCR, baghouse, and wet scrubber. Unit 2 is a pulverized coal-fired, super-critical steam electric plant with an SCR, baghouse, and wet scrubber.

1.3 APPROACH

Sega met with representatives of GMO to gather information about the generating units and visited each of the plant sites (with the exception of the Crossroads facility). Discussions were held with certain plant staff, further documentation was obtained, and a walkdown of each unit was conducted. Sega utilized Microsoft® Project 2010 (MS Project) software with resource loading to develop and compile opinions of probable costs and schedules for the retirement of each unit. Costs were developed based on GMO's current labor rates and those of its present maintenance contractors. Site-specific retirement costs were developed using a bottom-up approach for each task.

The basis and limits for retiring or dismantling each unit were defined while visiting the plant sites. For instance, it was assumed that the switchyard and/or substation (as applicable) for each generator would remain in service following either retirement or dismantlement. In general, plant roads, fencing, and site grading were presumed to remain undisturbed unless otherwise specifically required to be removed. Closure of ash landfills, and the removal and remediation of river water intakes and fuel oil storage tanks were included in the retirement phase as required by applicable permits.

Dismantlement costs for Sibley Unit 3 was developed from the ground up. It was assumed that common facilities at each plant site, such as coal unloading, storage and handling systems, water treatment systems, ash handling systems, and office buildings, would remain in service until the last unit is retired. For multiple-unit sites, retirement and dismantlement costs were developed separately for the common plant facilities. For instance, applicable ash landfill closure costs for the units were included in the common plant category rather than for individual units.

The estimates of probable cost for "stack removal" and "final site grading and drainage" for the various sites were not developed using MS Project software. The "stack removal" costs for the various stacks were based on a budgetary estimate for the demolition of the existing Iatan Unit 1 stack. This estimate was scaled to estimate the demolition for the other stacks involved in this study. The "final site grading and drainage" estimate of probable cost was developed by Sega but was not developed in an MS Project schedule. Both of these activities are represented in the MS Project schedule in Appendix A for the applicable units as a one-time cost/use in the resource allocation section of the file; therefore, they appear as a one-day activity in the schedule with the estimated costs as a one-time expense.

1.4 RESULTS

The opinion of the probable costs for retirement and dismantlement developed by Sega for each of GMO's units and the common facilities at each plant site are provided in Figure 1.2. All costs shown are in 2015 dollars. The costs are provided for the full ownership of these generating facilities. Fractional shares of ownership and jurisdictional allocations have not been taken into account in these costs. Ongoing expenses for the sites such as security, routine inspections, groundwater monitoring, etc., which would continue as long as the Company continues to own the sites, are not included in the decommissioning costs. Retirement costs are separately provided for each unit and for related common plant facilities. The costs of dismantlement and scrap values are provided for each unit and for common plant, as well as the final net terminal costs.

As shown in Figure 1.2, there is a significant difference between the costs of retiring and the costs of dismantling a power plant. In Sega's opinion, the probable cost to dismantle all of GMO's units is approximately \$208 million. Some materials could be sold for scrap, thereby recovering approximately \$38 million and bringing the estimated net terminal value for dismantling all of GMO's plants to \$170 million, based upon the current averaged scrap indices.

However, were GMO to retire its generating units in place without dismantlement, Sega believes the cost would be approximately \$68.9 million.

	Unit No.	Retirement			Dismantlement			
Name		Unit Retirement	Activities Required by Permit Agreement or Regulation ⁽²⁾	Total Retirement	Dismantlement	Scrap Value ⁽³⁾	Net Terminal Cost	
	1	\$482,368		\$482,368	\$6,034,974	\$848,154	\$5,186,820	
Sibley	2	\$482,368		\$482,368	\$6,034,974	\$848,154	\$5,186,820	
Sibley	3	\$535,958		\$535,958	\$16,835,426	\$2,757,087	\$14,078,339	
	Common	\$531,710	\$13,950,965	\$14,482,675	\$10,134,174	\$1,564,206	\$8,569,968	
	1							
South Harper	2	\$404,885		\$404,885	\$9,383,425	\$358,946	\$9,024,479	
	3							
	1							
Greenwood	2	\$413,021	\$471,333	\$884,354	\$11,063,645	\$353,746	\$10,709,899	
Greenwood	3							
	4							
	1							
Crossroads	2							
Ciossidads	3	\$400,303		\$400,303	\$11,249,327	\$389,486	\$10,859,841	
	4							
KCI	1							
KCI	2	\$227,662		\$227,662	\$2,789,050	\$91,317	\$2,697,733	
Nevada	1	\$281,190	\$56,530	\$337,720	\$6,434,106	\$45,397	\$6,388,709	
Ralph Green	3	\$285,572	\$81,385	\$366,957	\$6,156,152	\$95,230	\$6,060,922	
	Boiler 1	\$120,344		\$120,344	\$3,098,749	\$117,312	\$2,981,437	
	Boiler 2	\$120,344		\$120,344	\$3,098,749	\$117,312	\$2,981,437	
	Boiler 3	\$161,768		\$161,768	\$3,611,257	\$151,376	\$3,459,881	
	Boiler 4	\$138,357		\$138,357	\$4,045,457	\$196,024	\$3,849,433	
	Boiler 5	\$183,266	\$1,175,349	\$1,358,615	\$6,388,857	\$224,107	\$6,164,750	
	Boiler 8	\$105,550		\$105,550	\$2,250,354	\$224,107	\$2,026,247	
Lake Road	#4 / #6	\$386,400	\$637,591	\$1,023,991	\$8,380,637	\$1,262,740	\$7,117,897	
	Generator 1	\$49,349		\$49,349	\$2,375,879	\$38,162	\$2,337,717	
	Generator 2	\$49,349		\$49,349	\$2,615,898	\$43,797	\$2,572,101	
	Generator 3	\$43,656		\$43,656	\$1,874,480	\$25,661	\$1,848,819	
	CT 5	\$209,711		\$209,711	\$2,414,288	\$88,266	\$2,326,022	
	CT 6 & 7	\$159,554		\$159,554	\$1,665,869	\$91,317	\$1,574,552	
	Common	\$875,025	\$174,289	\$1,049,314	\$4,054,680	\$248,964	\$3,805,716	
	1	\$1,035,765	\$36,970,077	\$38,005,842	\$24,018,833	\$10,000,000	\$14,018,833	
latan	2	\$1,031,343		\$1,031,343	\$27,449,519	\$11,430,000	\$16,019,519	
	Common	\$590,627	\$6,042,837	\$6,633,464	\$24,874,543	\$6,850,000	\$18,024,543	
		\$9,305,445	\$59,560,356	\$68,865,801	\$208,333,302	\$38,460,868	\$169,872,434	

 $\begin{array}{c} \textbf{Figure 1.2 - Probable Costs of Decommissioning} \\ \textbf{GMO Electric Generating Units}^{(1)} \end{array}$

- (1) All values in 2015 U.S. dollars.
- (2) Activities required by permits and/or regulations that are to occur upon ceasing operations, including ash landfill closures and river water intake structures.
- (3) Current scrap values per averaged indices.

SECTION 2

RETIREMENT

RETIREMENT

2.1 INTRODUCTION

Sega developed an opinion of probable cost to retire the GMO facilities previously listed in Figure 1.1 and further described in Appendix A. The opinion of probable cost is a buildup of estimated costs to perform the retirement activities to leave each facility in a safe state. A resource-loaded MS Project schedule was developed for the retirement of each facility. Each schedule includes the activity, duration of the activity, resources required for each activity, and the probable cost of each activity. The results for each facility are provided in Appendix A of this report.

The opinion of probable cost for the retirement of each coal-fired generating facility is broken down into the retirement of each unit (or boiler, turbine, and CTG in the case of Lake Road), plus the retirement of the common facilities. The common facilities will be retired when the last unit is retired at a site.

2.2 OPINION OF PROBABLE COST BASIS

Retirement activities will be performed by KCP&L bargaining unit personnel and managed by GMO. Man-hour costs for both management and bargaining unit personnel were provide by GMO. At the direction of GMO, the direct man-hour rate was multiplied by 1.4 to account for benefits and overhead loadings.

The estimates of probable cost to retire the combustion turbines are based on retiring all of the combustion turbines at a given site, not on an individual combustion turbine retirement basis. The only exception is at Lake Road. At Lake Road, CTG 5 is retired as a single unit and CTGs 6 and 7 are retired together per direction from the Lake Road plant staff.

A 5-percent "Owner Internal Costs" is included in the opinion of probable cost. This line item is included to cover the costs of various internal GMO departments that will charge to the project during the implementation of the retirement activities.

A 25-percent "Owner Contingency" is included in the opinion of probable cost. This level of contingency is consistent with Association for the Advancement of Cost Engineering (AACE-International) contingency level guidelines based on the engineering progress completed at the point when the cost estimate was developed.

2.3 RETIREMENT ACTIVITIES

Prior to starting the actual retirement activities, a retirement plan will be developed. This plan will address any laws, ordinances, regulations, and standards dictating how ash, slag, scrubber by-products, and any other waste stream is stored and/or removed from the plant site. An environmental assessment will be performed to develop a plan to address these issues and to assure that permits required to complete the retirement activities are in place. The retirement plan will also address plant safety during the time interval between plant retirement and eventual dismantlement. This plan should include the requirements for periodic inspections to assess the condition and integrity of the plant structures so that contractors can safely demolish the plant when so required. The costs to perform these activities are estimated in the "Pre-Retirement Activities" line item of each facility's opinion of probable cost.

The following activities and conditions are required to leave a generating facility (unit, common facilities, or entire plant, as may be applicable) in a safe state and are included in each facility's opinion of probable cost:

- 1. All equipment, tanks, vessels, containers, drums, headers, exchangers, and sumps will be drained and vented. Fuel oil, lubricating oil, liquid propane, bulk hydrogen, Halon, liquid ammonia, water treatment chemicals, lab chemicals, cleaning solutions, and Freon will be handled per plant procedures and plan permitting requirements. Man-ways, hand-holes, vents, and drains will be opened to ensure drainage. Drains will remain open.
- 2. The electrical sources will be isolated from the facility. The exact details of this scope of work will be determined during the pre-retirement activities phase. At a minimum, all electrical buses will be disconnected at the source. The medium- and low-voltage switchgear will be racked out by fully withdrawing the circuit breakers. Fuses will be removed, and circuit breakers and disconnect switches will be left in the open position. Motors

- will be disconnected at the source and motor lube oil will be drained (as applicable).
- 3. Fuel yard equipment will be cleaned and vacuumed to reduce or eliminate the hazards of fugitive coal dust.
- 4. To the maximum extent possible, all drains will be emptied and vented. Low-point drains will remain open.
- 5. Fuel gas piping and city/rural water piping will be cut and capped at the property line.
- 6. Chimney Federal Aviation Agency (FAA) required lighting will be kept in service.
- 7. Buildings will be "secured". The determination of the detailed activities required to leave a building in a secure state is included in the pre-retirement activities and will include isolating all power sources, draining potable water lines, draining and venting sewage lines, securing doors and windows, capping any means of egress for vermin, removing hazardous materials, and moving any relevant plant documentation to alternate off-site storage sites.
- 8. Fuel oil and waste oil will be drained and removed.
- 9. Boiler chemicals will be drained and removed.
- 10. Boilers and HRSGs will be drained. The water and steam side will be vented. The gas side will be vacuumed to remove ash and slag. Drum doors and boiler doors will be left open. Bottom ash systems will be drained, cleaned, and vented.
- 11. Ductwork will be vacuumed and left open.
- 12. Condensate and feedwater piping will be drained and vented.
- 13. Feedwater heaters will be drained and vented.
- 14. Deaerator and deaerator storage tanks will be drained and vented.
- 15. The turbine and condenser will be drained and vented.
- 16. The generator will be electrically and mechanically isolated. The generator and exciter cooling water systems will be drained and vented. Hydrogen gas tanks and the generator hydrogen systems will be vented.
- 17. Compressed air systems will be drained and vented. Desiccant will be removed from the compressed air dryer systems.

- 18. Circulating water systems and turbine cooling water systems will be drained and vented. Circulating water chemical feeds will be drained and vented.
- 19. Baghouses will be opened, cleaned, and vented. Filter bags and cages will be removed.
- 20. Wet Flue Gas Desulfurization (FGD) systems will be drained, opened, cleaned, and vented.
- 21. Dry FGD systems will be drained, opened, cleaned, and vented.
- 22. Re-agent preparation facilities will be drained, opened, cleaned, and vented.
- 23. SCRs will be opened, cleaned, and vented. Catalyst will be removed. Ammonia storage tanks will be emptied and vented.
- 24. The battery systems will have the battery electrolytes and battery cells removed and disposed.
- 25. Sewage treatment facilities will be drained, cleaned, and vented.
- 26. Oily drain tanks will be opened and pumped out.
- 27. CO₂ systems used for fire protection will be drained, opened, and vented.
- 28. Any other activities required by law, regulation or permit for a specific unit, common facility or plant site will be performed.

Once the site retirement activities are complete, several months of post-retirement activities will commence. These activities include determining the disposition of site documentation, assuring permits are in correct condition, developing plans to monitor the retired facility, accounting and environmental activities, and re-assigning personnel as required.

2.4 ARO ACTIVITIES

Asset Retirement Obligations (AROs) are a means that GMO utilizes to track the costs of activities that are required to be performed when one of its generating units ceases operation and is removed from service. These are activities that are required to be performed upon retirement according to permits, statutes, agreements, and regulations. For certain activities, such as ash landfill closures, GMO is required to periodically report

estimated cost updates to state environmental agencies (Kansas Department of Health and Environment and Missouri Department of Natural Resources). These agencies require GMO to periodically demonstrate the ability to fund these closure activities. This is because the costs for ash landfill closures and post-closure activities are significant.

Other activities, such as the removal of river water intakes, are stated requirements in the standard form permits issued by the United States Army Corp of Engineers. Also included in AROs are amounts for the abatement and removal of fuel oil storage tanks of the plants located in Missouri (Greenwood, Nevada, Lake Road, and Iatan Generating Stations).

While GMO accounts for asbestos abatement activities in AROs for the Greenwood, Nevada, and Sibley Generating Stations, these activities were excluded from the retirement and decommissioning costs. Asbestos abatement activities are ongoing at each of these sites during the life of the units, and will continue to be performed after retirement, but before dismantlement. Thus, asbestos abatement was not included in this decommissioning study.

Wherever KCP&L already had estimates and a basis for valuing the costs of such ARO closure activities, Sega reviewed and utilized these estimates, adjusting to 2015 present-day dollars. Where there was no prior estimate available, Sega developed an opinion of probable costs for their closure. Each of these costs is provided in Appendix A.

Appendix D is a table showing the source of the requirement that dictates each ARO activity.

SECTION 3

DISMANTLEMENT

DISMANTLEMENT

3.1 INTRODUCTION

Sega developed an opinion of probable cost to dismantle the GMO facilities that are listed in Appendix A. The opinion of probable cost is a buildup of estimated costs to perform the dismantlement activities to remove equipment and building superstructures down to gradelevel foundations. Below-grade foundations, piping, and duct banks will be abandoned in place. A resource-loaded MS Project schedule was developed for the dismantlement of the facilities. Each schedule includes the activity, duration of the activity, resource required for each activity, and the probable cost of each activity. The results for each of the facilities are provided in Appendix A.

The opinion of probable cost for the dismantlement of each coal-fired generating facility is broken down into the dismantlement of each unit, plus the dismantlement of the common facilities. The common facilities will be dismantled when the last unit at the site is dismantled.

The estimate of probable cost to dismantle the combustion turbines are based on dismantling all of the combustion turbines at the site, not on an individual combustion turbine dismantlement basis with the exception of Lake Road. At Lake Road, CTG 5 is dismantled as a single unit and CTGs 6 and 7 are dismantled together per direction from the Lake Road plant staff.

3.2 OPINION OF PROBABLE COST BASIS

The project will be managed by GMO staff. GMO will hire an Owner's Engineer to assist with environmental issues and the technical dismantlement details. GMO will hire a Demolition General Contractor (DGC) to perform the complete dismantlement of each unit.

The opinion of probable cost is presented as the straight netting of the DGC's firm price cost, minus the current scrap value of the equipment and materials.

At the initiation of dismantlement, this study assumes that the unit or common facility has been previously retired as detailed in Section 2 - Retirement.

A resource-loaded MS-Project dismantlement schedule and an opinion of probable cost was developed for Iatan Unit 1, Sibley Unit 3, South Harper (all three units), Greenwood (all four units), Crossroads (all four units), KCI (both units), Nevada (one unit), Ralph Green (one unit), and Lake Road Boiler 1, Lake Road Boiler 2, Lake Road Boiler 3, Lake Road Boiler 4, Lake Road Boiler 5, Lake Road Boiler 8, Lake Road CTGs 6 and 7, Lake Road CTG 5, Lake Road T-G 1, Lake Road T-G 2, Lake Road T-G 3, and the common facilities at Iatan, Sibley, and Lake Road. The opinion of probable costs developed for Sibley Unit 3 was used to derive the dismantlement costs for Sibley 1, Sibley 2, and Lake Road 4/6 using the AACE International Capacity Factor Method. The cost for Iatan Unit 2 was derived from the cost to dismantle Iatan Unit 1 using the AACE International Capacity Factor method.

A 5-percent "Owner Internal Cost" is included in the opinion of probable cost. This line item is included to cover the costs of various internal GMO departments that will charge to the project during the implementation of the dismantlement activities.

A 25-percent "Owner Contingency" is included in the opinion of probable cost. This level of contingency is consistent with the AACE International contingency level based on the engineering progress completed at the point when the cost estimate is developed.

3.3 DISMANTLEMENT ACTIVITIES

The dismantlement of a facility is divided into pre-dismantlement activities, dismantlement activities, and project closure activities.

3.3.1 Pre-Dismantlement Activities

Pre-dismantlement activities consist of the detailed pre-planning of the dismantlement process. This pre-planning includes establishing the GMO project management team; hiring an Owner's Engineer; developing a detailed dismantlement scope of work, including how to address any environmental issues; developing a level 1 project schedule; and contracting with a DGC.

The GMO project management team will be responsible for the project execution and will consist of a full-time project manager, two full-time engineers, a full-time project administrative assistant, and a part-time procurement specialist. This team will have the authority to manage the dismantlement of the plant.

The Owner's Engineer will assist GMO with the technical aspects of executing the project. The Owner's Engineer will help establish the boundaries of demolition, provide environmental consulting, and develop the technical specifications for the DGC contract request for proposal. The Owner's Engineer will provide 1-1/2 full-time equivalent field engineers during the demolition phase of the project. The Owner's Engineer will also provide detailed design for equipment that requires modifications to keep other units or common facilities in operation during demolition and after the unit is dismantled.

The KCP&L project management team and the Owner's Engineer will review all existing permits to assure that any relevant existing permit requirements are met during demolition. This team will also get any additional required permits in place for demolition (outside of the normal permits that are the responsibility of the DGC).

Prior to dismantlement activities, a detailed site characterization study will be performed. This study involves a series of site investigations to determine potential subsurface environmental issues at the site, a description of the hydrological and hydrogeological conditions on the site, and a determination of potential waste streams generated during the demolition work. Based on the outcome of the site characterization study, reclamation, and remediation plans that address the environmental issues and site conditions will be

developed. The site characterization study and the development of the remediation plans can take up to six months to complete. The site characterization study will be performed by the Owner's Engineer.

The GMO project management team will identify the boundaries of dismantlement and the location of system and equipment isolation points between the unit to be demolished, common facilities, and units to remain.

The GMO project management team will be responsible for bidding and contracting with a qualified DGC.

Prior to the DGC mobilizing on site, the GMO project management team will confirm that the unit to be dismantled is ready to be turned over to the DGC.

3.3.2 Dismantlement Activities for a Coal-Fired Unit

The demolition contractor will be structured into several crews that will bring equipment and materials to the ground. A separate dedicated crew will be responsible for classifying the scrap by type and removing the scrap from the site.

The coal-fired units will be demolished in a phased and sequential manner to assure worker safety and to minimize any interferences with surrounding equipment. Please refer to the man-power loaded schedule and graphs in Appendix A for the details of each demolition phase.

3.3.2.1 Phase 1 Demolition - Boiler and Turbine Equipment Removal

Mechanical and electrical equipment and material inside the boiler and turbine building footprints will be removed. The goal of this phase is to remove the majority of the equipment in the boiler and turbine buildings leaving only the boiler, turbine, building, and support steel.

In this phase of the project, the switchyard is disconnected from the generating facility.

3.3.2.2 Phase 2 Demolition - Boiler and Turbine Removal

The boiler equipment will be removed at the start of this phase. Then, the boiler furnace and backpass will be removed from the bottom up (boilers are hung from the top of the boiler structure) and the structural steel is removed from the top down. Once the structural steel and all equipment are removed, the boiler equipment foundations will be demolished to existing grade.

In parallel with the above activities, the turbine, condenser neck heat exchangers, condenser, and miscellaneous turbine equipment will be removed. The turbine building and turbine pedestal is then demolished to grade.

3.3.2.3 Phase 3 Demolition - Precipitator and AQCS Dismantlement

If the unit has a precipitator, the precipitator will be removed similar to the process for removing the boiler. The precipitator internals will be removed from the bottom up and the precipitator structural steel will be removed from the top down. The precipitator foundation will be removed down to grade.

If the unit has a wet or dry scrubber and/or a baghouse, the dismantlement will start at the stack and work back towards the boiler to avoid dismantlement activities interferences.

3.3.2.4 Phase 4 Demolition - Yard Demolition

This phase removes equipment and materials external to the boiler and turbine areas. Underground piping, conduit, and duct banks will be abandoned in place with the exception of the circulating water pipe. The concrete reinforced circulating water pipes will be excavated, collapsed by crushing, and backfilled. Electrical man-holes will be collapsed by crushing and backfilled. Special care will be taken to assure that any materials left in the ground will not adversely impact site drainage.

3.3.2.5 Phase 5 - Final Site Grading and Drainage

Final grading and drainage includes a minimum amount of grading to assure that the site drainage facilities remain in place and includes final seeding of the site.

3.3.3 Dismantlement Activities for a Combustion Turbine Site

The demolition contractor will be structured into several crews that will bring equipment and materials to the ground. A separate dedicated crew will be responsible for classifying the scrap by type and removing the scrap from the site.

The combustion turbines, auxiliary equipment, and buildings will be demolished in a phased and sequential manner to assure worker safety and to minimize any interferences with surrounding equipment. Please refer to the man-power loaded schedule and graphs in Appendix A for the details of each demolition phase.

Final grading and drainage includes a minimum amount of grading to assure that the site drainage facilities remain in place and includes final seeding of the site.

3.3.4 Dismantlement Activities for Common Facilities

The demolition contractor will be structured into several crews that will bring equipment and materials to the ground. A separate dedicated crew will be responsible for classifying the scrap by type and removing the scrap from the site.

The common facilities dismantlement activities consist primarily of the removal of chimneys, fuel yard equipment, removal of site-specific common equipment, and the removal of facility buildings. The phasing of the common dismantlement processes are site specific and will be determined during the pre-dismantlement activity phase of the project.

Final grading and drainage includes a minimum amount of grading to assure that the site drainage facilities remain in place and includes final seeding of the site.

3.4 PROJECT CLOSURE ACTIVITIES

This phase of the project confirms that the remediation and reclamation of the site has been successfully complete and that all required "record" documentation needed by GMO is complete and on file.

3.5 SCRAP METAL VALUES

Scrap metal weights were developed for a 700-MW coal-fired unit based on the actual quantities and materials documented in the original construction documents. These scrap metal weights were applied to the other coal-fired units using the AACE International Capacity Factor Method.

Scrap metal weights for the combustion turbines, boilers, and turbine generators were based on weights for similar-sized equipment from previous Sega projects.

Please see Appendix B for the opinion of current average scrap values for each unit.



APPENDIX A

OPINIONS OF COSTS BY UNITS

SIBLEY

SIBLEY STATION

The Sibley Generating Station consists of three coal-fired power plants.

Sibley Unit 1 has an SPP-accredited unit rating of 51 MW and was placed in service in 1960. Unit 1 has a sub-critical Babcock & Wilcox boiler and a Siemens turbine. River water is used for condenser cooling. Unit 1 has an electrostatic precipitator for particulate

removal and an SNCR system for $NO_{\boldsymbol{x}}$ control.

Sibley Unit 2 has an SPP-accredited unit rating of 51 MW and was placed in service in 1962. Unit 2 has a sub-critical Babcock & Wilcox boiler and a General Electric turbine. River water is used for condenser cooling. Unit 2 has an electrostatic precipitator for

particulate removal and an SNCR system for NO_x control.

Sibley Unit 3 has an SPP-accredited unit rating of 363.8 MW and was placed in service in 1969. Unit 3 has a super-critical Babcock & Wilcox boiler and a Siemens turbine. River water is used for condenser cooling. Unit 3 has an electrostatic precipitator for particulate

removal and an SCR for NO_x control.

The Sibley common fuel yard has a bottom car dumper that can transfer fuel to either a bituminous fuel storage pile or a sub-bituminous fuel storage pile. The two different fuels can be blended prior to being transported to either the crusher house or to the blended pile. The blended pile has a reclaim system that can transport blended fuel to the crusher house. Crushed fuel is then transported to the Units 1, 2, and 3 silos. The fuel yard also has a tire

chips storage and conveyor system that can transport tire chips to the Unit 3 silos.

All three Sibley units have a propane igniter system. The units are supplied with propane

from common propane storage tanks and a common propane vaporizer.

All three units beneficially use coal combustion products off site. Coal combustion products

that are not beneficially used off site are disposed of in the on-site solid waste landfill.

KCP&L-GMO Decommissioning Study A - 1

Project No. 14-0164 Final, Rev. 1 The following are the major systems and equipment that were included in the retirement and dismantlement of each unit and the major systems and equipment that were considered common (additional details are listed in the attached retirement and dismantlement schedules included in this Appendix).

SIBLEY UNIT 1

- 1. Boiler and boiler auxiliaries.
- 2. Turbine, heat balance equipment, and turbine auxiliaries.
- 3. Electrostatic precipitator.
- 4. Dedicated Unit 1 fuel handling equipment.
- 5. Dedicated Unit 1 propane equipment.
- 6. Dedicated Unit 1 SNCR process equipment.

SIBLEY UNIT 2

- 1. Boiler and boiler auxiliaries.
- 2. Turbine, heat balance equipment, and turbine auxiliaries.
- 3. Electrostatic precipitator.
- 4. Dedicated Unit 2 fuel handling equipment.
- 5. Dedicated Unit 2 propane equipment.
- 6. Dedicated Unit 2 SNCR process equipment.

SIBLEY UNIT 3

- 1. Boiler and boiler auxiliaries.
- 2. Turbine, heat balance equipment, and turbine auxiliaries.
- 3. Electrostatic precipitator.

- 4. Dedicated Unit 3 fuel handling equipment.
- 5. Dedicated Unit 3 propane equipment.
- 6. Dedicated Unit 3 SCR process equipment.

COMMON

- 1. Administration/Service building.
- 2. Fuel yard office building.
- 3. Temporary service building.
- 4. Warehouses.
- 5. Tractor shed and out building.
- 6. Water treatment and sewage treatment.
- 8. Common fuel handling equipment.
- 9. NO_x out ultra system
- 10. Fire water systems.
- 11. Stack.
- 12. Diesel generator.
- 13. Intake.

UNIT 1

Sibley Unit 1 Retirement

Owner Costs

Pre-Retirement Activities \$100,821
Retirement Activities \$240,134
Post-Retirement Activities \$26,564

Owner Direct Total \$367,519

Owner Internal Costs 5.00% \$18,376

Owner Contingency: 25.00% \$96,474

Sibley Unit 1 Retirement Opinion of Probable Cost:

\$482,368.69

D	Task Name	Cost
1	Sibley Unit 1 Retirement	\$367,519.09
2	Pre-Engineering	\$100,821.60
3	Permit review and engineering analysis, establish isolation points, and confirn	\$100,821.60
4	KCL&L Overhead Costs	\$83,646.00
5	KCP&L Retirement Manager	\$83,646.00
6	Equipment Rentals	\$28,339.20
7	Vacuum truck	\$28,339.20
8	Retirement	\$128,148.29
9	Electrical	\$18,911.68
10	Medium and Low Voltage Draw out Switchgear	\$2,679.84
11	De-energize all buses at the source.	\$446.64
12	Open all circuit breakers.	\$446.64
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	\$446.64
14	Verify that the closing/tripping springs are discharged.	\$446.64
15	De-energize control power and auxiliary power circuits of each circuit bro	\$893.28
16	Motor Control Centers	\$1,786.56
17	De-energize all buses at the source.	\$446.64
18	Open all circuit breakers and disconnect switches.	\$446.64
19	Remove all fuses in control circuits.	\$893.28
20	Low-voltage Switchboards and Panelboards	\$893.28
21	De-energize all buses at the source.	\$446.64
22	Open all circuit breakers and disconnect switches.	\$446.64
23	Oil-Filled Power Transformers	\$5,549.44
24	De-energize all transformer primaries and verify that the secondary is de	
25	De-energize all low-voltage AC or DC power sources for space heaters, co	
26	Drain and dispose of oil.	\$2,642.88
27	Clean up and dispose of oil on surface areas around the transformers on	\$1,120.00
28	Dry-type Power Transformers	\$1,786.56
29	De-energize all transformer primaries and verify that the secondary is de	
30	De-energize all low-voltage AC or DC power sources for space heaters, co	
31	Motors	\$6,216.00
32	De-energize all primary power at the source.	\$1,786.56
33	De-energize all low-voltage power sources for space heaters or other aux	
34	Drain lube oil system (if applicable) and dispose of oil.	\$2,642.88
35	Coal Handling	\$29,248.24
36	Isolate area K Unit 1 Silos.	\$8,522.80
37	Confirm all fuel lines and feedrs are clear of coal and coal dust.	\$1,685.44
38	Perform cleaning of the coal handling equipment to assure that all coal and	
39	Propane Igniter System	\$2,528.16
40	Isolate lines from source, open and vent.	\$2,528.16
41	Boiler Chemical Feed	\$1,685.44
42	Drain all chemical feed tanks.	\$1,685.44
43	Boiler	\$29,591.57
44	Open boiler doors.	\$880.96

)	Task Name	Cost
45	Gas side - perform cleaning of the boiler and bottom ash system.	\$16,800.00
46	Drain boiler, drums, downcomers and headers.	\$842.72
47	Open drum doors and blowdown tank doors.	\$880.96
48	Drain and vent the service water and ash sluice water systems	\$1,541.36
49	Clean bottom ash, economizer ash and fly ash system.	\$2,480.13
50	Open, flush with water and vent the SNCR/RRI piping	\$6,165.44
51	Precipitator	\$10,603.04
52	Multiple cleaning cycles for collection plates.	\$2,528.16
53	Clear hoppers of all ash	\$2,805.44
54	Disconnect tranformers.	\$1,786.56
55	Mechanically secure all compartment dampers and hopper outlet valves in	\$720.48
56	Disconnect ash transport piping and washdown hoppers and interior of case	\$1,000.48
57	Install bird screens across hopper ash outlet and ash line flanges.	\$880.96
58	Padlock or tack weld all hopper doors shut. (note: if ash hopper doors are i	\$880.9
59	Ductwork	\$6,480.9
60	Open ductwork doors.	\$880.9
61	Perform extensive cleaning of the ductwork.	\$5,600.0
62	Isolate ductwork at tie to ductwork common to Unit 2	\$0.00
63	Condensate and Feedwater Piping	\$2,528.1
64	Drain water from the system.	\$842.72
65	Leave open vents and drains.	\$842.72
66	Drain, open and vent condensate storage tanks	\$842.72
67	Feedwater heaters	\$2,528.10
68	Drain feedwater heaters	\$842.72
69	Leave open vents and drains.	\$1,685.44
70	Turbine and Condenser	\$4,385.68
71	Drain hotwell and leave doors open.	\$861.84
72	Open main turbine doors.	\$880.96
73	Remove lube oil.	\$2,642.88
74	Drain Gland Water Tank and Condensate Collection Tank	\$0.00
75	Generator	\$6,095.70
76	Verify that generator circuit breaker is open and racked out or that high-vo	\$446.64
77	Verify that generator field breaker or contactor (if applicable) is open.	\$446.64
78	De-energize power supplies to generator excitation system at the source.	\$446.64
79	De-energize AC and DC power supplies to generator and exciter space heat	·
80	Drain generator and exciter cooling water systems (if applicable).	\$861.84
81	Disconnect and remove hydrogen gas tanks and purge generator hydrogen	· ·
82	Disconnect and remove fire protection system gas/foam tanks and purge fi	
83	Circulation Water and Turbine Cooling Water System	\$3,409.12
84	Drain.	\$1,685.44
85	Open water box doors.	\$880.96
86	Drain any circulating water chemical feed tanks.	\$842.72
87	Compressed Air System	\$842.72
88	Open vents and drains.	\$842.72

Sibley Unit	1 Retirement	Costs
-------------	--------------	-------

ID	Task Name	Cost
89	Auxiliary Steam System	\$2,528.16
90	Drain water from system.	\$842.72
91	Open and vent F.D. Fan Steam Coils	\$1,685.44
92	Bearing Cooling Water and Boiler Cooling Water System	\$842.72
93	Drain water from system and vent.	\$842.72
94	Condenser Air Extraction System	\$842.72
95	Drain water from system.	\$842.72
96	Building Heating System	\$842.72
97	Drain water from system.	\$842.72
98	Battery System	\$4,253.28
99	De-energize all battery chargers from the source.	\$446.64
100	Open all AC and DC circuit breakers and/or fused switches on battery charg	\$446.64
101	Remove and dispose of battery electrolyte.	\$1,680.00
102	Remove and dispose of battery cells.	\$1,120.00
103	Clean up and dispose of electrolyte on surface areas around batteries.	\$560.00
104	Post Retirement Activities	\$26,564.00
105	Post Retirement Activities	\$26,564.00

	Task Name	Duration	1st Quarter	2nd Quarter	3rd Quarter	4th Quart
1	Sibley Unit 1 Retirement	241 days				
2	Pre-Engineering	66 days				
3	Permit review and engineering analysis, establish isolation points, and confirm fuel yard inventory has been reduced to zero tons.	66 days				
4	KCL&L Overhead Costs	135 days				
5	KCP&L Retirement Manager	135 days				
6	Equipment Rentals	135 days				
7	Vacuum truck	135 days				
8	Retirement	135 days				_
9	Electrical	22 days			•	
10	Medium and Low Voltage Draw out Switchgear	3 days				
11	De-energize all buses at the source.	0.5 days		h		
12	Open all circuit breakers.	0.5 days		ħ		
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	0.5 days		h		
14	Verify that the closing/tripping springs are discharged.	0.5 days		h		
15	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each breaker cubicle.	1 day		Ť		
16	Motor Control Centers	2 days				
17	De-energize all buses at the source.	0.5 days		I, ▼		
18	Open all circuit breakers and disconnect switches.	0.5 days		ħ		
19	Remove all fuses in control circuits.	1 day		Ť		
20	Low-voltage Switchboards and Panelboards	1 day				
21	De-energize all buses at the source.	0.5 days		η		
22	Open all circuit breakers and disconnect switches.	0.5 days		Ĭ		
23	Oil-Filled Power Transformers	7 days		•		
24	De-energize all transformer primaries and verify that the secondary is de-energized.	1 day		h		
25	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	1 day		ħ		
26	Drain and dispose of oil.	3 days		*		

	Task Name	Duration	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Quart
27	Clean up and dispose of oil on surface areas around the transformers on in containment pits.	2 days		ľ			
28	Dry-type Power Transformers	2 days		w)		
29	De-energize all transformer primaries and verify that the secondary is de-energized.	1 day		h			
30	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	1 day		ľ			
31	Motors	7 days					
32	De-energize all primary power at the source.	2 days		h	▼		
33	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	2 days		F			
34	Drain lube oil system (if applicable) and dispose of oil.	3 days					
35	Coal Handling	24 days					
36	Isolate area K Unit 1 Silos.	5 days			*		
37	Confirm all fuel lines and feedrs are clear of coal and coal dust.	2 days			h		
38	Perform cleaning of the coal handling equipment to assure that al coal and coal dust has been removed from site.	l 17 days					
39	Propane Igniter System	3 days					
40	Isolate lines from source, open and vent.	3 days			K		
41	Boiler Chemical Feed	2 days					
42	Drain all chemical feed tanks.	2 days			ξ		
43	Boiler	28 days					
44	Open boiler doors.	1 day			Ϋ́		
45	Gas side - perform cleaning of the boiler and bottom ash system.	15 days					
46	Drain boiler, drums, downcomers and headers.	1 day			ħ		
47	Open drum doors and blowdown tank doors.	1 day			Ϋ́		
48	Drain and vent the service water and ash sluice water systems	1 day			Ь		
49	Clean bottom ash, economizer ash and fly ash system.	5 days			*		
50	Open, flush with water and vent the SNCR/RRI piping	4 days			Ť		
51	Precipitator	13 days				₩	
52	Multiple cleaning cycles for collection plates.	3 days			*	· I	

	Task Name	Duration	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Qu
53	Clear hoppers of all ash	4 days				ή	
54	Disconnect tranformers.	2 days				Ϋ́	
55	Mechanically secure all compartment dampers and hopper outlet valves in open position.	1 day					
56	Disconnect ash transport piping and washdown hoppers and interior of casing.	1 day				Ĭ,	
57	Install bird screens across hopper ash outlet and ash line flanges.	1 day				Ϋ́	
58	Padlock or tack weld all hopper doors shut. (note: if ash hopper doors are indoors, they could be removed and the opening covered with bird screens.)	1 day				ř	
59	Ductwork	7 days					
60	Open ductwork doors.	1 day				<u>K</u>	
61	Perform extensive cleaning of the ductwork.	5 days					
62	Isolate ductwork at tie to ductwork common to Unit 2	1 day				I	
63	Condensate and Feedwater Piping	3 days					
64	Drain water from the system.	1 day				5	
65	Leave open vents and drains.	1 day				5	
66	Drain, open and vent condensate storage tanks	1 day				M	
67	Feedwater heaters	3 days				•	
68	Drain feedwater heaters	1 day				Ь_	
69	Leave open vents and drains.	2 days				Š	
70	Turbine and Condenser	6 days				—	
71	Drain hotwell and leave doors open.	1 day				ř.	
72	Open main turbine doors.	1 day				<u>K</u>	
73	Remove lube oil.	3 days				<u>~</u>	
74	Drain Gland Water Tank and Condensate Collection Tank	1 day				ľ	
75	Generator	7 days				T	
76	Verify that generator circuit breaker is open and racked out or that high-voltage disconnect switch on substation side of GSU transformer is locked in the open position.	0.5 days				h	
77	Verify that generator field breaker or contactor (if applicable) is open	0.5 days				Б	
78	De-energize power supplies to generator excitation system at the source.	0.5 days				h	

D	Task Name	Duration	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Quarter
79	De-energize AC and DC power supplies to generator and exciter space heaters, cooling equipment, controls, lighting, etc. at the source and open circuit breakers or remove fuses at the generator	0.5 days				ř	
80	Drain generator and exciter cooling water systems (if applicable).	1 day				Ϋ́	
81	Disconnect and remove hydrogen gas tanks and purge generator hydrogen system.	2 days					
82	Disconnect and remove fire protection system gas/foam tanks and purge fire protection system.	2 days				ř	
83	Circulation Water and Turbine Cooling Water System	3 days					
84	Drain.	2 days					
85	Open water box doors.	1 day					
86	Drain any circulating water chemical feed tanks.	1 day				Ť	
87	Compressed Air System	1 day					
88	Open vents and drains.	1 day				I	
89	Auxiliary Steam System	3 days					
90	Drain water from system.	1 day				Ь	
91	Open and vent F.D. Fan Steam Coils	2 days					
92	Bearing Cooling Water and Boiler Cooling Water System	1 day					
93	Drain water from system and vent.	1 day				I	
94	Condenser Air Extraction System	1 day				—	
95	Drain water from system.	1 day				I	
96	Building Heating System	1 day					
97	Drain water from system.	1 day				I	
98	Battery System	7 days				•	
99	De-energize all battery chargers from the source.	0.5 days				P_	
100	Open all AC and DC circuit breakers and/or fused switches on battery chargers and disconnect cables from batteries.	0.5 days				Ĭ,	
101	Remove and dispose of battery electrolyte.	3 days				*	
102	Remove and dispose of battery cells.	2 days				K	
103	Clean up and dispose of electrolyte on surface areas around batter	i 1 day				Ĭ	
104	Post Retirement Activities	40 days					—
105	Post Retirement Activities	40 days					

Sibley Unit 1 Dismantlement

Owner Costs

Pre-Dismantlement Activities \$892,760

Overhead During Dismantlement \$492,984

Post-Dismantlement Activities \$49,140

Owner Costs Total* \$1,434,884

Demolition General Contractor (DGC) Costs

 Site Management
 \$268,729

 Equipment Rental
 \$457,572

 Consummables
 \$456,510

 Scrap Crew(s)
 \$452,980

 Dismantlement
 \$1,008,001

Contractor Direct Cost* \$2,643,792

Contractor Allowances

DGC Insurance 2.00% \$52,876

Contingency/Profit 15.00% \$404,500

Performance Bond 2.00% \$62,023.36

Contractor Costs Total: \$3,163,191

Total: \$4,598,075

Owner Internal Costs: 5.00% \$229,904

Owner Contingency: 25.00% \$1,206,995

Sibley Unit 1 Dismantlement Opinion of Probable Cost: \$6,034,974

^{*}Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances = \$4,078,676

UNIT 2

Sibley Unit 2 Retirement

Owner Costs

Pre-Retirement Activities \$100,821
Retirement Activities \$240,134
Post-Retirement Activities \$26,564

Owner Direct Total \$367,519

Owner Internal Costs 5.00% \$18,376

Owner Contingency: 25.00% \$96,474

Sibley Unit 2 Retirement Opinion of Probable Cost:

\$482,368.69

D	Task Name	Cost
1	Sibley Unit 2 Retirement	\$367,519.09
2	Pre-Engineering	\$100,821.60
3	Permit review and engineering analysis, establish isolation points, and confirn	\$100,821.60
4	KCL&L Overhead Costs	\$83,646.00
5	KCP&L Retirement Manager	\$83,646.00
6	Equipment Rentals	\$28,339.20
7	Vacuum truck	\$28,339.20
8	Retirement	\$128,148.29
9	Electrical	\$18,911.68
10	Medium and Low Voltage Draw out Switchgear	\$2,679.84
11	De-energize all buses at the source.	\$446.64
12	Open all circuit breakers.	\$446.64
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	\$446.64
14	Verify that the closing/tripping springs are discharged.	\$446.64
15	De-energize control power and auxiliary power circuits of each circuit bro	\$893.28
16	Motor Control Centers	\$1,786.56
17	De-energize all buses at the source.	\$446.64
18	Open all circuit breakers and disconnect switches.	\$446.64
19	Remove all fuses in control circuits.	\$893.28
20	Low-voltage Switchboards and Panelboards	\$893.28
21	De-energize all buses at the source.	\$446.64
22	Open all circuit breakers and disconnect switches.	\$446.64
23	Oil-Filled Power Transformers	\$5,549.44
24	De-energize all transformer primaries and verify that the secondary is de	
25	De-energize all low-voltage AC or DC power sources for space heaters, co	
26	Drain and dispose of oil.	\$2,642.88
27	Clean up and dispose of oil on surface areas around the transformers on	\$1,120.00
28	Dry-type Power Transformers	\$1,786.56
29	De-energize all transformer primaries and verify that the secondary is de	
30	De-energize all low-voltage AC or DC power sources for space heaters, co	
31	Motors	\$6,216.00
32	De-energize all primary power at the source.	\$1,786.56
33	De-energize all low-voltage power sources for space heaters or other aux	
34	Drain lube oil system (if applicable) and dispose of oil.	\$2,642.88
35	Coal Handling	\$29,248.24
36	Isolate area K Unit 1 Silos.	\$8,522.80
37	Confirm all fuel lines and feedrs are clear of coal and coal dust.	\$1,685.44
38	Perform cleaning of the coal handling equipment to assure that all coal and	
39	Propane Igniter System	\$2,528.16
40	Isolate lines from source, open and vent.	\$2,528.16
41	Boiler Chemical Feed	\$1,685.44
42	Drain all chemical feed tanks.	\$1,685.44
43	Boiler	\$29,591.57
44	Open boiler doors.	\$880.96

D	Task Name	Cost
45	Gas side - perform cleaning of the boiler and bottom ash system.	\$16,800.00
46	Drain boiler, drums, downcomers and headers.	\$842.72
47	Open drum doors and blowdown tank doors.	\$880.96
48	Drain and vent the service water and ash sluice water systems	\$1,541.36
49	Clean bottom ash, economizer ash and fly ash system.	\$2,480.13
50	Open, flush with water and vent the SNCR/RRI piping	\$6,165.44
51	Precipitator	\$10,603.04
52	Multiple cleaning cycles for collection plates.	\$2,528.16
53	Clear hoppers of all ash	\$2,805.44
54	Disconnect tranformers.	\$1,786.56
55	Mechanically secure all compartment dampers and hopper outlet valves in	\$720.48
56	Disconnect ash transport piping and washdown hoppers and interior of case	\$1,000.48
57	Install bird screens across hopper ash outlet and ash line flanges.	\$880.96
58	Padlock or tack weld all hopper doors shut. (note: if ash hopper doors are	\$880.96
59	Ductwork	\$6,480.96
60	Open ductwork doors.	\$880.96
61	Perform extensive cleaning of the ductwork.	\$5,600.00
62	Isolate ductwork at tie to ductwork common to Unit 2	\$0.00
63	Condensate and Feedwater Piping	\$2,528.16
64	Drain water from the system.	\$842.72
65	Leave open vents and drains.	\$842.72
66	Drain, open and vent condensate storage tanks	\$842.72
67	Feedwater heaters	\$2,528.16
68	Drain feedwater heaters	\$842.72
69	Leave open vents and drains.	\$1,685.44
70	Turbine and Condenser	\$4,385.68
71	Drain hotwell and leave doors open.	\$861.84
72	Open main turbine doors.	\$880.96
73	Remove lube oil.	\$2,642.88
74	Drain Gland Water Tank and Condensate Collection Tank	\$0.00
75	Generator	\$6,095.76
76	Verify that generator circuit breaker is open and racked out or that high-vo	\$446.64
77	Verify that generator field breaker or contactor (if applicable) is open.	\$446.64
78	De-energize power supplies to generator excitation system at the source.	\$446.64
79	De-energize AC and DC power supplies to generator and exciter space heat	\$446.64
80	Drain generator and exciter cooling water systems (if applicable).	\$861.84
81	Disconnect and remove hydrogen gas tanks and purge generator hydrogen	\$1,685.44
82	Disconnect and remove fire protection system gas/foam tanks and purge fi	\$1,761.92
83	Circulation Water and Turbine Cooling Water System	\$3,409.12
84	Drain.	\$1,685.44
85	Open water box doors.	\$880.96
86	Drain any circulating water chemical feed tanks.	\$842.72
87	Compressed Air System	\$842.72
88	Open vents and drains.	\$842.72

CILI		_	n
Siblev	Unit	2	Retirement

ID	Task Name	Cost
89	Auxiliary Steam System	\$2,528.16
90	Drain water from system.	\$842.72
91	Open and vent F.D. Fan Steam Coils	\$1,685.44
92	Bearing Cooling Water and Boiler Cooling Water System	\$842.72
93	Drain water from system and vent.	\$842.72
94	Condenser Air Extraction System	\$842.72
95	Drain water from system.	\$842.72
96	Building Heating System	\$842.72
97	Drain water from system.	\$842.72
98	Battery System	\$4,253.28
99	De-energize all battery chargers from the source.	\$446.64
100	Open all AC and DC circuit breakers and/or fused switches on battery charg	\$446.64
101	Remove and dispose of battery electrolyte.	\$1,680.00
102	Remove and dispose of battery cells.	\$1,120.00
103	Clean up and dispose of electrolyte on surface areas around batteries.	\$560.00
104	Post Retirement Activities	\$26,564.00
105	Post Retirement Activities	\$26,564.00

)	Task Name	Duration	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Quarte
1	Sibley Unit 2 Retirement	241 days	—				—
2	Pre-Engineering	66 days	—				
3	Permit review and engineering analysis, establish isolation points, and confirm fuel yard inventory has been reduced to zero tons.	66 days					
4	KCL&L Overhead Costs	135 days		—			
5	KCP&L Retirement Manager	135 days					
6	Equipment Rentals	135 days		-		_	
7	Vacuum truck	135 days					
8	Retirement	135 days		<u> </u>			
9	Electrical	22 days		-			
10	Medium and Low Voltage Draw out Switchgear	3 days					
11	De-energize all buses at the source.	0.5 days		h			
12	Open all circuit breakers.	0.5 days		h			
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	0.5 days		h			
14	Verify that the closing/tripping springs are discharged.	0.5 days		ħ			
15	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each breaker cubicle.	1 day		Ĭ			
16	Motor Control Centers	2 days					
17	De-energize all buses at the source.	0.5 days		_L , ★			
18	Open all circuit breakers and disconnect switches.	0.5 days		I,			
19	Remove all fuses in control circuits.	1 day		†			
20	Low-voltage Switchboards and Panelboards	1 day		₩			
21	De-energize all buses at the source.	0.5 days		h h			
22	Open all circuit breakers and disconnect switches.	0.5 days		I			
23	Oil-Filled Power Transformers	7 days			1		
24	De-energize all transformer primaries and verify that the secondary is de-energized.	1 day		h			
25	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	1 day		h			
26	Drain and dispose of oil.	3 days		*			

	Task Name	Duration	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Qua
27	Clean up and dispose of oil on surface areas around the transformers on in containment pits.	2 days					
28	Dry-type Power Transformers	2 days		W			
29	De-energize all transformer primaries and verify that the secondary is de-energized.	1 day		h			
30	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	1 day		ľ			
31	Motors	7 days		•			
32	De-energize all primary power at the source.	2 days		H	▼ 		
33	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	2 days		F			
34	Drain lube oil system (if applicable) and dispose of oil.	3 days			ή.		
35	Coal Handling	24 days					
36	Isolate area K Unit 1 Silos.	5 days			*		
37	Confirm all fuel lines and feedrs are clear of coal and coal dust.	2 days			5		
38	Perform cleaning of the coal handling equipment to assure that all coal and coal dust has been removed from site.	17 days					
39	Propane Igniter System	3 days					
40	Isolate lines from source, open and vent.	3 days			†		
41	Boiler Chemical Feed	2 days					
42	Drain all chemical feed tanks.	2 days			ħ		
43	Boiler	28 days					
44	Open boiler doors.	1 day			\mathbf{F}		
45	Gas side - perform cleaning of the boiler and bottom ash system.	15 days					
46	Drain boiler, drums, downcomers and headers.	1 day			\mathbf{r}		
47	Open drum doors and blowdown tank doors.	1 day			, , ,		
48	Drain and vent the service water and ash sluice water systems	1 day			片		
49	Clean bottom ash, economizer ash and fly ash system.	5 days			*		
50	Open, flush with water and vent the SNCR/RRI piping	4 days			T		
51	Precipitator	13 days				—	
52	Multiple cleaning cycles for collection plates.	3 days			†	,)	

	Task Name	Duration	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Qua
53	Clear hoppers of all ash	4 days				5	
54	Disconnect tranformers.	2 days				Ϋ́	
55	Mechanically secure all compartment dampers and hopper outlet valves in open position.	1 day				ř	
56	Disconnect ash transport piping and washdown hoppers and interior of casing.	1 day				K	
57	Install bird screens across hopper ash outlet and ash line flanges.	1 day				Ϋ́	
58	Padlock or tack weld all hopper doors shut. (note: if ash hopper doors are indoors, they could be removed and the opening covered with bird screens.)	1 day				F	
59	Ductwork	7 days					
60	Open ductwork doors.	1 day				Ϋ́	
61	Perform extensive cleaning of the ductwork.	5 days					
62	Isolate ductwork at tie to ductwork common to Unit 2	1 day				Ĭ	
63	Condensate and Feedwater Piping	3 days					
64	Drain water from the system.	1 day				Ь	
65	Leave open vents and drains.	1 day				<u>Б</u>	
66	Drain, open and vent condensate storage tanks	1 day				Ĭ	
67	Feedwater heaters	3 days					
68	Drain feedwater heaters	1 day				Ρ	
69	Leave open vents and drains.	2 days				h	
70	Turbine and Condenser	6 days				•	
71	Drain hotwell and leave doors open.	1 day				<u> </u>	
72	Open main turbine doors.	1 day				Ь	
73	Remove lube oil.	3 days				5	
74	Drain Gland Water Tank and Condensate Collection Tank	1 day				I	
75	Generator	7 days					
76	Verify that generator circuit breaker is open and racked out or that high-voltage disconnect switch on substation side of GSU transformer is locked in the open position.	0.5 days				h	
77	Verify that generator field breaker or contactor (if applicable) is op-	0.5 days				5	
78	De-energize power supplies to generator excitation system at the source.	0.5 days				F	

D	Task Name	Duration	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Quarter
79	De-energize AC and DC power supplies to generator and exciter space heaters, cooling equipment, controls, lighting, etc. at the source and open circuit breakers or remove fuses at the generator	0.5 days				h	
80	Drain generator and exciter cooling water systems (if applicable).	1 day				ξ	
81	Disconnect and remove hydrogen gas tanks and purge generator hydrogen system.	2 days					
82	Disconnect and remove fire protection system gas/foam tanks and purge fire protection system.	2 days					
83	Circulation Water and Turbine Cooling Water System	3 days					
84	Drain.	2 days				•	
85	Open water box doors.	1 day				Ť	
86	Drain any circulating water chemical feed tanks.	1 day				Ť	
87	Compressed Air System	1 day					
88	Open vents and drains.	1 day				I	
89	Auxiliary Steam System	3 days					
90	Drain water from system.	1 day				h	
91	Open and vent F.D. Fan Steam Coils	2 days					
92	Bearing Cooling Water and Boiler Cooling Water System	1 day					
93	Drain water from system and vent.	1 day				I	
94	Condenser Air Extraction System	1 day					
95	Drain water from system.	1 day				I	
96	Building Heating System	1 day					
97	Drain water from system.	1 day				I	
98	Battery System	7 days				—	
99	De-energize all battery chargers from the source.	0.5 days				₽ →	
100	Open all AC and DC circuit breakers and/or fused switches on battery chargers and disconnect cables from batteries.	0.5 days				Ĭ,	
101	Remove and dispose of battery electrolyte.	3 days				片	
102	Remove and dispose of battery cells.	2 days				K	
103	Clean up and dispose of electrolyte on surface areas around batter	i 1 day				Ť	
104	Post Retirement Activities	40 days					
105	Post Retirement Activities	40 days					

Sibley Unit 2 Dismantlement

Owner Costs

Pre-Dismantlement Activities \$892,760

Overhead During Dismantlement \$492,984

Post-Dismantlement Activities \$49,140

Owner Costs Total* \$1,434,884

Demolition General Contractor (DGC) Costs

 Site Management
 \$268,729

 Equipment Rental
 \$457,572

 Consummables
 \$456,510

 Scrap Crew(s)
 \$452,980

 Dismantlement
 \$1,008,001

Contractor Direct Cost* \$2,643,792

Contractor Allowances

DGC Insurance 2.00% \$52,876

Contingency/Profit 15.00% \$404,500

Performance Bond 2.00% \$62,023.36

Contractor Costs Total: \$3,163,191

Total: \$4,598,075

Owner Internal Costs: 5.00% \$229,904

Owner Contingency: 25.00% \$1,206,995

Sibley Unit 2 Dismantlement Opinion of Probable Cost: \$6,034,974

^{*}Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances = \$4,078,676

UNIT 3

Sibley Unit 3 Retirement

Owner Costs

Pre-Retirement Activities \$100,821
Retirement Activities \$280,964
Post-Retirement Activities \$26,564

Owner Direct Total \$408,349

Owner Internal Costs 5.00% \$20,417

Owner Contingency: 25.00% \$107,192

Sibley Unit 3 Retirement Opinion of Probable Cost:

\$535,958.06

D	Task Name	Cost
1	Sibley Unit 3 Retirement	\$408,350.61
2	Pre-Engineering	\$100,821.60
3	Permit review and engineering analysis, establish isolation points, and	\$100,821.60
	confirm fuel yard inventory has been reduced to zero tons.	
4	KCL&L Overhead Costs	\$99,755.60
5	KCP&L Retirement Manager	\$99,755.60
6	Equipment Rentals	\$33,797.12
7	Vacuum truck	\$33,797.12
8	Retirement	\$147,412.29
9	Electrical	\$18,911.68
10	Medium and Low Voltage Draw out Switchgear	\$2,679.84
11	De-energize all buses at the source.	\$446.64
12	Open all circuit breakers.	\$446.64
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	\$446.64
14	Verify that the closing/tripping springs are discharged.	\$446.64
15	De-energize control power and auxiliary power circuits of each	\$893.28
	circuit breaker at the source and by opening control power circuit	
	breakers or removing fuses in each breaker cubicle.	
16	Motor Control Centers	\$1,786.56
17	De-energize all buses at the source.	\$446.64
18	Open all circuit breakers and disconnect switches.	\$446.64
19	Remove all fuses in control circuits.	\$893.28
20	Low-voltage Switchboards and Panelboards	\$893.28
21	De-energize all buses at the source.	\$446.64
22	Open all circuit breakers and disconnect switches.	\$446.64
23	Oil-Filled Power Transformers	\$5,549.44
24	De-energize all transformer primaries and verify that the secondary is de-energized.	\$893.28
25	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	\$893.28
26	Drain and dispose of oil.	\$2,642.88
27	Clean up and dispose of oil on surface areas around the transformers on in containment pits.	\$1,120.00
28	Dry-type Power Transformers	\$1,786.56
29	De-energize all transformer primaries and verify that the secondary is de-energized.	\$893.28
30	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	\$893.28
31	Motors	\$6,216.00
32	De-energize all primary power at the source.	\$1,786.56

	Task Name	Cost
33	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	\$1,786.56
34	Drain lube oil system (if applicable) and dispose of oil.	\$2,642.88
35	Coal Handling	\$25,790.00
36	Empty all silos in Area M.	\$1,704.56
37	Confirm conveyors are run out of fuel.	\$1,685.44
38	Perform cleaning of the coal handling equipment to assure that all	\$22,400.00
	coal and coal dust has been removed from area.	. ,
39	Propane Igniter System	\$2,528.16
40	Isolate lines from source, open and vent.	\$2,528.16
41	Boiler Chemical Feed	\$1,685.44
42	Drain all chemical feed tanks.	\$1,685.44
43	Condensate Polisher	\$4,529.12
44	Drain water from system.	\$842.72
45	Drain acid and caustic tanks.	\$1,685.44
46	Open tanks and vessels.	\$880.96
47	Remove resin.	\$1,120.00
48	Boiler	\$32,108.85
49	Open boiler doors.	\$880.96
50	Gas side - perform cleaning of the boiler and bottom ash system.	\$22,400.00
51	Drain boiler, drum, downcomers and headers.	\$842.72
52	Open drum doors.	\$880.96
53	Drain, vent and clean the fly ash, slag and transport water system	\$2,480.13
54	Drain and vent the steam coil air heaters and piping	\$1,541.36
55	Drain and vent the steam coil air heater drain tanks	\$1,541.36
56	Drain and vent boiler sampling system panel and piping	\$1,541.36
57	Precipitator	\$9,901.68
58	Multiple cleaning cycles for collection plates.	\$2,528.16
59	Clear hoppers of all ash	\$2,104.08
60	Disconnect transformers.	\$1,786.56
61	Mechanically secure all compartment dampers and hopper outlet valves in open position.	\$720.48
62	Disconnect ash transport piping and washdown hoppers and interior of casing.	\$1,000.48
63	Install bird screens across hopper ash outlet and ash line flanges.	\$880.96
64	Padlock or tack weld all hopper doors shut. (note: if ash hopper	\$880.96
	doors are indoors, they could be removed and the opening covered with bird screens.)	7555
65	Ductwork	\$12,080.96
66	Open ductwork doors.	\$880.96
67	Perform extensive cleaning of the ductwork.	\$11,200.00
68	Isolate ductwork at tie to common ductwork.	\$0.00
69	Condensate and Feedwater Piping	\$1,685.44
70	Drain water from the system.	\$842.72

	Task Name	Cost
71	Leave open vents and drains.	\$842.72
72	Feedwater heaters	\$3,370.88
73	Drain feedwater heaters	\$842.72
74	Leave open vents and drains.	\$1,685.44
75	Drain and vent the heater drain piping.	\$842.72
76	Deaerator and Deaerator Storage Tank	\$1,685.44
77	Drain Deaerator and Storage	\$842.72
78	Leave open vents and drains.	\$842.72
79	SCR	\$9,053.52
80	Vacuum fly ash from catalyst.	\$1,680.00
81	Remove catalyst of salvage or disposal.	\$2,441.44
82	Padlock or tack weld access doors shut.	\$880.96
83	Remove ammonia from storage tank for resale.	\$701.36
84	Wash out and drain storage tank and supply piping.	\$701.36
85	Vent storage tank and all piping. Leave vent and drain valves open or remove. Install bird screens.	\$861.84
86	Pull electrical supply breakers on all electrical equipment except lighting and HVAC components that are to remain in service.	\$1,786.56
87	Turbine(s) and Condenser	\$5,266.64
88	Drain hotwell and leave doors open.	\$861.84
89	Open main turbine doors.	\$880.96
90	Open bfp turbine doors.	\$880.96
91	Remove lube oil.	\$2,642.88
92	Generator	\$6,095.76
93	Verify that generator circuit breaker is open and racked out or that	\$446.64
	high-voltage disconnect switch on substation side of GSU transformer is locked in the open position.	· ·
94	Verify that generator field breaker or contactor (if applicable) is open.	\$446.64
95	De-energize power supplies to generator excitation system at the source.	\$446.64
96	De-energize AC and DC power supplies to generator and exciter space heaters, cooling equipment, controls, lighting, etc. at the source and open circuit breakers or remove fuses at the generator and exciter.	\$446.64
97	Drain generator and exciter cooling water systems (if applicable).	\$861.84
98	Disconnect and remove hydrogen gas tanks and purge generator	\$1,685.44
	hydrogen system.	
99	Disconnect and remove fire protection system gas/foam tanks and purge fire protection system.	\$1,761.92
100	Circulation Water and Turbine Cooling Water System	\$3,409.12
101	Drain.	\$1,685.44
102	Open water box doors.	\$880.96
103	Drain any circulating water chemical feed tanks.	\$842.72

Sibley	Unit	3	Retirement	t

ID	Task Name	Cost
104	Compressed Air System	\$842.72
105	Open vents and drains.	\$842.72
106	Auxiliary Steam System	\$842.72
107	Drain water from system.	\$842.72
108	Station Cooling Water System	\$1,685.44
109	Drain water from system.	\$842.72
110	Vent piping.	\$842.72
111	Condenser Air Extraction	\$842.72
112	Drain water from system.	\$842.72
113	Building Heating System	\$842.72
114	Drain water from system.	\$842.72
115	Battery System	\$4,253.28
116	De-energize all battery chargers from the source.	\$446.64
117	Open all AC and DC circuit breakers and/or fused switches on battery chargers and disconnect cables from batteries.	\$446.64
118	Remove and dispose of battery electrolyte.	\$1,680.00
119	Remove and dispose of battery cells.	\$1,120.00
120	Clean up and dispose of electrolyte on surface areas around batteries.	\$560.00
121	Post Retirement Activities	\$26,564.00
122	Post Retirement Activities	\$26,564.00

D	Task Name	Duration	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Q
1	Sibley Unit 3 Retirement	267 days	—				
2	Pre-Engineering	66 days	—				
3	Permit review and engineering analysis, establish isolation points, and confirm fuel yard inventory has been reduced to	66 days					
4	KCL&L Overhead Costs	161 days		-			
5	KCP&L Retirement Manager	161 days					
6	Equipment Rentals	161 days		-			
7	Vacuum truck	161 days					
8	Retirement	161 days					
9	Electrical	22 days			₩		
10	Medium and Low Voltage Draw out Switchgear	3 days					
11	De-energize all buses at the source.	0.5 days		Ъ			
12	Open all circuit breakers.	0.5 days		F_			
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	0.5 days		H			
14	Verify that the closing/tripping springs are discharged.	0.5 days		ħ			
15	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each breaker cubicle.	·		i			
16	Motor Control Centers	2 days					
17	De-energize all buses at the source.	0.5 days		h			
18	Open all circuit breakers and disconnect switches.	0.5 days		Ϊ́			
19	Remove all fuses in control circuits.	1 day		ĭ			
20	Low-voltage Switchboards and Panelboards	1 day					
21	De-energize all buses at the source.	0.5 days		Ь			
22	Open all circuit breakers and disconnect switches.	0.5 days		I			
23	Oil-Filled Power Transformers	7 days		-	ו		
24	De-energize all transformer primaries and verify that the secondary is de-energized.	1 day		h			

	Task Name	Duration	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Quarte
25	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	1 day		F			
26	Drain and dispose of oil.	3 days		<u>~</u>			
27	Clean up and dispose of oil on surface areas around the transformers on in containment pits.	2 days		ľ			
28	Dry-type Power Transformers	2 days		•			
29	De-energize all transformer primaries and verify that the secondary is de-energized.	1 day		h			
30	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	1 day					
31	Motors	7 days		-	•		
32	De-energize all primary power at the source.	2 days		H	▼)		
33	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	2 days					
34	Drain lube oil system (if applicable) and dispose of oil.	3 days		`	ή,		
35	Coal Handling	23 days		ι			
36	Empty all silos in Area M.	1 day			h		
37	Confirm conveyors are run out of fuel.	2 days			5		
38	Perform cleaning of the coal handling equipment to assure that all coal and coal dust has been removed from area.	20 days					
39	Propane Igniter System	3 days					
40	Isolate lines from source, open and vent.	3 days			Ϋ́		
41	Boiler Chemical Feed	2 days			•		
42	Drain all chemical feed tanks.	2 days			S		
43	Condensate Polisher	6 days			—		
44	Drain water from system.	1 day			<u> </u>		
45	Drain acid and caustic tanks.	2 days			5		
46	Open tanks and vessels.	1 day			<u> </u>		
47	Remove resin.	2 days					
48	Boiler	30 days			—	—	

	Task Name	Duration	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Quarte
49	Open boiler doors.	1 day			I		
50	Gas side - perform cleaning of the boiler and bottom ash system.	20 days					
51	Drain boiler, drum, downcomers and headers.	1 day			h l		
52	Open drum doors.	1 day			ř		
53	Drain, vent and clean the fly ash, slag and transport water system	5 days					
54	Drain and vent the steam coil air heaters and piping	1 day				F	
55	Drain and vent the steam coil air heater drain tanks	1 day				<u>F</u>	
56	Drain and vent boiler sampling system panel and piping	1 day				h	
57	Precipitator	12 days					
58	Multiple cleaning cycles for collection plates.	3 days				<u></u>	
59	Clear hoppers of all ash	3 days				<u></u>	
60	Disconnect transformers.	2 days				<u>Š</u>	
61	Mechanically secure all compartment dampers and hoppe	ı 1 day				<u>Ļ</u>	
62	Disconnect ash transport piping and washdown hoppers a	ır 1 day				<u>K</u>	
63	Install bird screens across hopper ash outlet and ash line f	l 1 day				<u>K</u>	
64	Padlock or tack weld all hopper doors shut. (note: if ash ho	o 1 day				Η̈́	
65	Ductwork	13 days					
66	Open ductwork doors.	1 day				<u>L</u>	
67	Perform extensive cleaning of the ductwork.	10 days					
68	Isolate ductwork at tie to common ductwork.	2 days				ď	
69	Condensate and Feedwater Piping	2 days				T	
70	Drain water from the system.	1 day				5	
71	Leave open vents and drains.	1 day				ђ	
72	Feedwater heaters	4 days				<u> </u>	
73	Drain feedwater heaters	1 day				<u>K</u>	
74	Leave open vents and drains.	2 days				5	
75	Drain and vent the heater drain piping.	1 day				$oldsymbol{ar{f{f}}}$	
76	Deaerator and Deaerator Storage Tank	2 days				<u> </u>	
77	Drain Deaerator and Storage	1 day				K	
78	Leave open vents and drains.	1 day				Ϋ́	
79	SCR	12 days					

	Task Name	Duration	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Quarte
80	Vacuum fly ash from catalyst.	3 days				5	
81	Remove catalyst of salvage or disposal.	3 days				*	
82	Padlock or tack weld access doors shut.	1 day				, T	
83	Remove ammonia from storage tank for resale.	1 day				Ϋ́	
34	Wash out and drain storage tank and supply piping.	1 day				Ϋ́	
85	Vent storage tank and all piping. Leave vent and drain valves open or remove. Install bird screens.	1 day				, in the second	
86	Pull electrical supply breakers on all electrical equipment except lighting and HVAC components that are to remain ir service.	2 days					
87	Turbine(s) and Condenser	6 days					
38	Drain hotwell and leave doors open.	1 day				Ϋ́	
39	Open main turbine doors.	1 day				Ϋ́	
90	Open bfp turbine doors.	1 day				ħ	
91	Remove lube oil.	3 days				T ₁	
92	Generator	7 days					
93	Verify that generator circuit breaker is open and racked out or that high-voltage disconnect switch on substation side of GSU transformer is locked in the open position.	t0.5 days				F .	
94	Verify that generator field breaker or contactor (if applicable) is open.	0.5 days				h	
95	De-energize power supplies to generator excitation system at the source.	0.5 days				h	
96	De-energize AC and DC power supplies to generator and exciter space heaters, cooling equipment, controls, lighting, etc. at the source and open circuit breakers or remove fuses at the generator and exciter.	0.5 days				ř	
97	Drain generator and exciter cooling water systems (if applicable).	1 day				ħ	
98	Disconnect and remove hydrogen gas tanks and purge generator hydrogen system.	2 days				Ť	
99	Disconnect and remove fire protection system gas/foam tanks and purge fire protection system.	2 days					•
100	Circulation Water and Turbine Cooling Water System	4 days				•	,

)	Task Name	Duration	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Quarte
101	Drain.	2 days					
102	Open water box doors.	1 day					h
103	Drain any circulating water chemical feed tanks.	1 day					Ь
104	Compressed Air System	1 day				•	
105	Open vents and drains.	1 day					Ь
106	Auxiliary Steam System	1 day					—
107	Drain water from system.	1 day					Ϋ́,
108	Station Cooling Water System	2 days					
109	Drain water from system.	1 day					Ь
110	Vent piping.	1 day					Ь
111	Condenser Air Extraction	1 day					
112	Drain water from system.	1 day					Ĭ
113	Building Heating System	1 day					
114	Drain water from system.	1 day					I
115	Battery System	7 days					—
116	De-energize all battery chargers from the source.	0.5 days					h
117	Open all AC and DC circuit breakers and/or fused switches	0.5 days					Ĭ,
	on battery chargers and disconnect cables from batteries.						
118	Remove and dispose of battery electrolyte.	3 days					<u></u>
119	Remove and dispose of battery cells.	2 days					5
120	Clean up and dispose of electrolyte on surface areas around batteries.	1 day					l
121	Post Retirement Activities	40 days					
122	Post Retirement Activities	40 days					_

Sibley Unit 3 Dismantlement

Owner Costs

Pre-Dismantlement Activities \$892,760

Overhead During Dismantlement \$1,602,538

Post-Dismantlement Activities \$49,140

Owner Costs Total* \$2,544,438

Demolition General Contractor (DGC) Costs

 Site Management
 \$873,555

 Equipment Rental
 \$1,487,425

 Consummables
 \$1,483,973

 Scrap Crew(s)
 \$1,472,497

 Dismantlement
 \$3,276,697

Contractor Direct Cost* \$8,594,147

Contractor Allowances

DGC Insurance 2.00% \$171,883

Contingency/Profit 15.00% \$1,314,904

Performance Bond 2.00% \$201,618.69

Contractor Costs Total: \$10,282,553

Total: \$12,826,991

Owner Internal Costs: 5.00% \$641,350

Owner Contingency: 25.00% \$3,367,085

Sibley Unit 3 Dismantlement Opinion of Probable Cost: \$16,835,426

^{*}Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances = \$11,138,585

	Task Name	Cost
1	Sibley Unit 3 Dismantlement	\$11,138,588.64
2	Pre-Dismantlement Activities	\$892,760.32
3	Detailed Planning & Hire Owner's Engineer	\$104,441.28
4	Detailed Site Characterization Study	\$610,335.44
5	Hire Demolition General Contractor	\$167,184.00
6	KCP&L Prepares Unit for Dismantlement	\$10,799.60
7	Demolition Contractor Mobilizes on Site	\$0.00
8	KCP&L Overhead during Dismantlement	\$1,602,538.32
9	KCP&L Project Manager	\$254,655.60
10	KCP&L Administrative Support	\$94,168.32
11	KCP&L Engineer	\$418,562.40
12	Owners Engineer Project Manager	\$124,944.00
13	Owners Engineer - Engineer	\$710,208.00
14	Demoliton Contractor Overhead during Dismantlement	\$873,555.84
15	Demolition Contractor Project Manager	\$247,158.96
16	Demolition Contractor Safety Manager	\$220,065.84
17	Demolition Contractor Superintendent	\$406,331.04
18	Demolition Contractor Equipment Rental Costs	\$1,487,425.44
19	Equipment Rental	\$1,487,425.44
20	Demolition Contractor Consummables	\$1,483,973.04
21	Consummables	\$1,483,973.04
22	Scrap Crew(s)	\$1,472,497.92
23	Crew to Handle Scrap Material(s)	\$1,472,497.92
24	Dismantlement Directs	\$3,276,697.76
25	Phase 1 Demolition	\$775,861.84
26	Electrical Demolition	\$342,149.76
27	Electrical Demolition Equipment	\$342,149.76
28	Condensate System	\$73,445.76
29	Condensate Pumps	\$3,582.72
30	Condensate Booster Pumps	\$1,791.36
31	Gland Steam Condenser	\$3,582.72
32	Low Pressure Heaters (except the condenser neck heat	\$26,870.40
33	exchangers) Deaerator	\$7,165.44
34	Deaerator Deaerator Storage Tank	\$7,165.44
35	Condensate Piping	\$17,913.60
36	, -	\$17,913.00
37	Polisher Vessels, Regen Vessels and Support Skids Boiler Feed System	
38	•	\$42,298.88
39	Boiler Feed Pump Turbines (2) and Exhaust	\$10,054.40
	Boiler Feed Pumps - Turbine Driven	\$14,330.88
40	Start-up Boiler Feed Pump	\$0.00
41	High Pressure Heaters	\$17,913.60
42	Feedwater piping Critical Piping	\$0.00 \$69,863.0 4

	Task Name	Cost
44	Main Steam Piping	\$23,287.68
45	Cold Reheat Piping	\$23,287.68
46	Hot Reheat Piping	\$23,287.68
47	Extraction Steam System	\$17,913.60
48	Piping and Valves	\$17,913.60
49	Heater Drips	\$8,956.80
50	Heater Drip Pump	\$1,791.36
51	Piping	\$7,165.44
52	Auxiliary Steam	\$12,539.52
53	Auxiliary Steam Piping, Tanks and Misc. Equipment	\$12,539.52
54	Circulating Water (plant side)	\$5,374.08
55	Waterboxes	\$5,374.08
56	Station Cooling Water	\$16,122.24
57	Station Cooling Water Pumps	\$1,791.36
58	Station Cooling Water Heat Exchanger	\$3,582.72
59	Station Cooling Water Piping	\$10,748.10
60	Chemical Mixing Tank	\$0.00
61	Station Cooling Water Head Tank	\$0.00
62	Service Water	\$12,539.52
63	Service Water Piping	\$12,539.52
64	Propane System (plant side)	\$16,122.24
65	Propane Piping and Valves	\$7,165.4
66	Igniters	\$8,956.80
67	Air Preheat System	\$7,165.44
68	Steam Coil Air Heater Piping	\$3,582.72
69	Steam Coil Drain Pumps	\$1,791.36
70	Steam Coil Drain Tanks	\$1,791.30
71	Condenser Air Extraction System	\$12,539.52
72	Vacuum Pumps	\$7,165.44
73	Vacuum Priming Pump	\$1,791.36
74	Vacuum Pump Piping	\$3,582.72
75	Turbine Seals and Drains	\$7,165.44
76	Piping	\$7,165.44
77	Turbine Lube Oil System	\$20,564.40
78	Turbine Lube Oil Tank	\$9,816.24
79	Turbine Lube Oil Pumps	\$7,165.44
80	Turbine Oil Mist Eliminator	\$3,582.72
81	Generator Auxiliary Systems	\$25,079.04
82	Hydrogen Cooler Skid and Piping	\$5,374.08
83	Stator Cooling Water Skid and Piping	\$5,374.08
84	Isophase Bus Duct	\$7,165.44
85	Exciter Heat Exchanger	\$3,582.72
86	EHC Coolers	\$3,582.72
87	Chemical Feed Systems	\$14,330.88

)	Task Name	Cost
88	Tanks	\$3,582.72
89	Pumps	\$5,374.08
90	Piping	\$5,374.08
91	Sampling Systems	\$10,017.12
92	Field Mounted Heat Exchangers	\$3,582.72
93	Piping	\$2,851.68
94	Sample Panel	\$3,582.72
95	Building Heating Systems	\$13,307.84
96	Steam Unit Heaters	\$9,505.60
97	Steam Piping	\$3,802.24
98	Compressed Air System	\$26,870.40
99	Air Compressors	\$7,165.44
100	Air Drying Equipment	\$5,374.08
101	Air Reciever Tanks	\$5,374.08
102	Compressed Air Piping	\$8,956.80
103	Miscellaneous Equipment	\$21,496.32
104	Miscellaneous Equipment (including Fire Protection)	\$21,496.32
105	Phase 2 Demolition	\$2,409,476.50
106	Precipitator	\$107,481.60
107	Remove Precipitator	\$107,481.60
108	Boiler Equipment	\$536,314.50
109	Fans	\$53,740.80
110	Bottom Ash	\$16,451.52
111	Air Heater	\$143,308.80
112	Steam Drum	\$71,654.40
113	Coal Bunkers	\$71,654.40
114	Soot Blowers	\$25,447.68
115	Ductwork	\$100,316.10
116	SCR	\$53,740.80
117	Boiler Removal	\$329,610.24
118	Furnace	\$179,136.00
119	Back Pass	\$150,474.24
120	Boiler Steel Framing	\$616,227.84
121	Hanger Girders at Top	\$107,481.60
122	All Other Framing	\$286,617.60
123	Bracing and Girts	\$143,308.80
124	Columns	\$78,819.84
125	Boiler Foundations	\$128,977.92
126	Equipment Foundation Demolition to Grade	\$128,977.92
127	Remove Turbine	\$690,864.40
128	Remove HP Turbine	\$26,321.60
129	Remove IP Turbine	\$26,321.60
130	Remove LP Turbine	\$26,321.60
131	Remove Generator	\$39,482.40

D	Task Name	Cost
132	Remove Condenser Neck Heat Exchanger	\$13,160.80
133	Remove Condenser	\$26,321.60
134	Remove Misc. Auxiliary Turbine Equipment	\$39,482.40
135	Turbine Pedestal Demolition to Grade	\$197,412.00
136	Top Slab and Beams	\$78,964.80
137	Columns	\$118,447.20
138	Remove Turbine Building	\$296,040.40
139	Siding and Roofing	\$92,778.00
140	All Framing Elevations	\$131,608.00
141	Bracing and Girts	\$52,643.20
142	Columns	\$19,011.20
143	Phase 3 Demolition	\$91,359.36
144	Yard Demolition	\$91,359.36
145	Remove Ash Handling Equipment and Piping	\$62,697.60
146	Slag Tank	\$17,913.60
147	Hydrovayer Pumps	\$8,956.80
148	Slag Tank Pumps	\$3,582.72
149	Hydrovayer Fly Ash System	\$8,956.80
150	Vacuum Filter System	\$5,374.08
151	Remove Slag Transport System Piping and Misc. Equipment	\$17,913.60
152	Remove Fuel Yard Equipment	\$19,704.96
153	Remove Conveyor 10	\$8,956.80
154	Remove Conveyor 10A	\$3,582.72
155	Remove Conveyor 10AA	\$3,582.72
156	Remove Conveyor 10AB	\$3,582.72
157	Remove Condensate Storage Tanks (2)	\$8,956.80
158	Project Close-Out	\$49,140.00
159	Project Close-Out Activities	\$49,140.00

)	Task Name	Duration		201	2		2013			2014		2015		2016
			H2	<u> </u>	11	H2	H1		H2	H1	H2	H1	H2	H1
1	Sibley Unit 3 Dismantlement	706 days												
2	Pre-Dismantlement Activities	265 days		4										
3	Detailed Planning & Hire Owner's Engineer	3 mons												
4	Detailed Site Characterization Study	130 days					_							
5	Hire Demolition General Contractor	3 mons												
6	KCP&L Prepares Unit for Dismantlement	2 wks					<u></u>							
7	Demolition Contractor Mobilizes on Site	5 days												
8	KCP&L Overhead during Dismantlement	411 days												
9	KCP&L Project Manager	411 days												
10	KCP&L Administrative Support	411 days												
11	KCP&L Engineer	411 days												
12	Owners Engineer Project Manager	411 days												
13	Owners Engineer - Engineer	411 days												
14	Demoliton Contractor Overhead during Dismantle	men 411 days												
15	Demolition Contractor Project Manager	411 days												
16	Demolition Contractor Safety Manager	411 days												
17	Demolition Contractor Superintendent	411 days												
18	Demolition Contractor Equipment Rental Costs	411 days												
19	Equipment Rental	411 days												
20	Demolition Contractor Consummables	411 days												
21	Consummables	411 days												
22	Scrap Crew(s)	411 days												
23	Crew to Handle Scrap Material(s)	411 days						_	_	_				
24	Dismantlement Directs	411 days												
25	Phase 1 Demolition	191 days												
26	Electrical Demolition	191 days							_					
27	Electrical Demolition Equipment	191 days						_						
28	Condensate System	41 days												
29	Condensate Pumps	2 days					H							
30	Condensate Booster Pumps	1 day					H							
31	Gland Steam Condenser	2 days					#							


	Task Name	Duration		2012		2013		2014			2015		2016
			H2	H1	H2	H1	H2	H1	H:	2	H1	H2	Н
32	Low Pressure Heaters (except the condenser	15 days				Ť							
	neck heat exchangers)												
33	Deaerator	4 days											
34	Deaerator Storage Tank	4 days											
35	Condensate Piping	10 days											
36	Polisher Vessels, Regen Vessels and Support Sk	•											
37	Boiler Feed System	30 days											
38	Boiler Feed Pump Turbines (2) and Exhaust	5 days				5							
39	Boiler Feed Pumps - Turbine Driven	8 days				1							
40	Start-up Boiler Feed Pump	2 days				1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1							
41	High Pressure Heaters	10 days				1 5							
42	Feedwater piping	5 days				ľ							
43	Critical Piping	39 days											
44	Main Steam Piping	13 days				1							
45	Cold Reheat Piping	13 days				5							
46	Hot Reheat Piping	13 days				-							
47	Extraction Steam System	10 days											
48	Piping and Valves	10 days				Į Š							
49	Heater Drips	5 days											
50	Heater Drip Pump	1 day				I,							
51	Piping	4 days				Ь							
52	Auxiliary Steam	7 days				—							
53	Auxiliary Steam Piping, Tanks and Misc. Equipm	7 days				ľ							
54	Circulating Water (plant side)	3 days											
55	Waterboxes	3 days				H							
56	Station Cooling Water	11 days				#							
57	Station Cooling Water Pumps	1 day				H							
58	Station Cooling Water Heat Exchanger	2 days				H							
59	Station Cooling Water Piping	6 days				<u> </u>							
60	Chemical Mixing Tank	1 day				*							
61	Station Cooling Water Head Tank	1 day											
62	Service Water	7 days											

)	Task Name	Duration		20)12		2	2013		2	2014			2015		2016
			H2		H1	H2		H1	H2		H1	Н	12	H1	H2	H1
63	Service Water Piping	7 days						h								
64	Propane System (plant side)	9 days														
65	Propane Piping and Valves	4 days						Ь								
66	Igniters	5 days						h								
67	Air Preheat System	4 days														
68	Steam Coil Air Heater Piping	2 days						1 1 1 1 1 1 1 1 1 1								
69	Steam Coil Drain Pumps	1 day						Ь								
70	Steam Coil Drain Tanks	1 day						Ь								
71	Condenser Air Extraction System	7 days														
72	Vacuum Pumps	4 days						K								
73	Vacuum Priming Pump	1 day														
74	Vacuum Pump Piping	2 days						Ъ								
75	Turbine Seals and Drains	4 days														
76	Piping	4 days						H								
77	Turbine Lube Oil System	15 days														
78	Turbine Lube Oil Tank	9 days						K								
79	Turbine Lube Oil Pumps	4 days						K								
80	Turbine Oil Mist Eliminator	2 days						Η								
81	Generator Auxiliary Systems	14 days														
82	Hydrogen Cooler Skid and Piping	3 days						Image: Control of the								
83	Stator Cooling Water Skid and Piping	3 days						Ь								
84	Isophase Bus Duct	4 days						K								
85	Exciter Heat Exchanger	2 days						T T T T T T T								
86	EHC Coolers	2 days						K								
87	Chemical Feed Systems	8 days														
88	Tanks	2 days														
89	Pumps	3 days						15								
90	Piping	3 days														
91	Sampling Systems	7 days														
92	Field Mounted Heat Exchangers	2 days						In								
93	Piping	3 days						K								
94	Sample Panel	2 days						İ								

)	Task Name	Duration		2012		2013		2014			2015		2016
			H2	H1	 H2	H1	H2	H1	F	12	H1	H2	H:
95	Building Heating Systems	14 days				7							
96	Steam Unit Heaters	10 days				<u> </u>	,						
97	Steam Piping	4 days				ľή							
98	Compressed Air System	15 days				<u> </u>							
99	Air Compressors	4 days				F	_						
100	Air Drying Equipment	3 days				Ē	L						
101	Air Reciever Tanks	3 days				Ĥ							
102	Compressed Air Piping	5 days				i							
103	Miscellaneous Equipment	12 days				4							
104	Miscellaneous Equipment (including Fire Prote	c 12 days				i	ή						
105	Phase 2 Demolition	332 days				į.				, -			
106	Precipitator	30 days				ı							
107	Remove Precipitator	30 days											
108	Boiler Equipment	152 days											
109	Fans	15 days					1						
110	Bottom Ash	6 days					5						
111	Air Heater	40 days											
112	Steam Drum	20 days					*	·]					
113	Coal Bunkers	20 days						5					
114	Soot Blowers	8 days						5					
115	Ductwork	28 days											
116	SCR	15 days						T Cı	ew 1-2	Labor	er[600%	[],Crew	1-2 Op
117	Boiler Removal	46 days											
118	Furnace	25 days											
119	Back Pass	21 days							h				
120	Boiler Steel Framing	86 days											
121	Hanger Girders at Top	15 days							*				
122	All Other Framing	40 days											
123	Bracing and Girts	20 days											
124	Columns	11 days							K				
125	Boiler Foundations	18 days							<u>u</u>				
126	Equipment Foundation Demolition to Grade	18 days											

)	Task Name	Duration		2012		2013		2014		2015		2016
			H2	H1	H2	H1	H2	H1	H2	H1	H2	H1
127	Remove Turbine	275 days				•			·			
128	Remove HP Turbine	10 days					<u>L</u>					
129	Remove IP Turbine	10 days					<u>L</u>					
130	Remove LP Turbine	10 days					<u></u>					
131	Remove Generator	15 days										
132	Remove Condenser Neck Heat Exchanger	5 days					h					
133	Remove Condenser	10 days					5					
134	Remove Misc. Auxiliary Turbine Equipment	15 days					5					
135	Turbine Pedestal Demolition to Grade	75 days						•				
136	Top Slab and Beams	30 days										
137	Columns	45 days										
138	Remove Turbine Building	125 days							ı			
139	Siding and Roofing	35 days										
140	All Framing Elevations	50 days										
141	Bracing and Girts	20 days						*				
142	Columns	20 days						Ĭ				
143	Phase 3 Demolition	46 days										
144	Yard Demolition	46 days										
145	Remove Ash Handling Equipment and Piping	30 days										
146	Slag Tank	10 days				5						
147	Hydrovayer Pumps	5 days				ħ						
148	Slag Tank Pumps	2 days				☆ Ya	rd Crew C	Operator,Ya	ard Cre	w Labore	r[300%]	
149	Hydrovayer Fly Ash System	5 days				<u>∓</u> Ya	rd Crew C	Operator,Ya	ard Cre	w Labore	r[300%]	
150	Vacuum Filter System	3 days				<u>⊤</u> Ya	rd Crew C	Operator,Ya	ard Cre	w Labore	r[300%]	
151	Remove Slag Transport System Piping and	10 days				*						
	Misc. Equipment											
152	Remove Fuel Yard Equipment	11 days				•						
153	Remove Conveyor 10	5 days				, in						
154	Remove Conveyor 10A	2 days				κ̈́						
155	Remove Conveyor 10AA	2 days				ħ						
156	Remove Conveyor 10AB	2 days				ħ						
157	Remove Condensate Storage Tanks (2)	5 days				*						

Sibley	Unit 3 Dismantlement											
ID	Task Name	Duration		2012		2013		2014		2015		2016
			H2	H1								
158	Project Close-Out	30 days										
159	Project Close-Out Activities	30 days										



Sibley Common Retirement

Owner Costs

Pre-Retirement Activities \$52,488
Retirement Activities \$326,401
Post-Retirement Activities \$26,224

Owner Direct Total \$405,113

Owner Internal Costs 5.00% \$20,256

Owner Contingency: 25.00% \$106,342

Sibley Common Retirement Opinion of Probable Cost: \$531,710.81


Activities Required by Permit or Regulation

Propane Storage Tanks \$32,531
Units 1 & 2 River Intake \$592,147
Unit 3 River Intake \$592,147
Landfill Stage A \$1,150,440
Sibley Landfill Post Closure \$2,082,900
Sibley Ash Pond Closure \$9,500,800

Activities Required by Permit or Regulation: \$13,950,965

)	Task Name	Cost
1	Sibley Common Retirement	\$405,075.52
2	Pre-Retirement Activities	\$52,448.80
3	Permitting Review	\$26,224.40
4	Develop Detailed Retirement Plan	\$26,224.40
5	Overheads	\$170,845.92
6	Retirement Overheads	\$149,434.08
7	Added Overhead Staff for Common Retirement	\$149,434.08
8	Common Removal Equipment Rental	\$21,411.84
9	Common Removal Equipment Rental	\$21,411.84
10	Retirement Activities	\$155,556.40
11	Administration/Service Building	\$9,342.40
12	Secure Administration/Service Building	\$9,342.40
13	Fuel Yard Office Building	\$5,605.44
14	Secure Fuel Yard Office Building	\$5,605.44
15	Temporary Service Building	\$1,868.48
16	Secure Temporary Service Building	\$1,868.48
17	Warehouse	\$5,605.44
18	Secure Warehouse and Middle Warehouse	\$5,605.44
19	Tractor Shed	\$4,630.24
20	Secure Tractor Shed	\$4,630.24
21	Out Buildings	\$3,736.96
22	Secure the Insulators Shack and Hedrick Hall	\$3,736.96
23	Fuel Yard	\$72,354.40
24	Empty Rotary Car Dumper and Clean (Area A)	\$2,941.36
25	Empty Sample House and Clean (Area B)	\$3,784.08
26	Empty Transfer Hoppers and Clean Transfer House 1 (AreaD)	\$3,784.08
27	Empty and Clean the Bituminous Stackout Reclaim (Area C)	\$3,784.08
28	Empty and Clean the Sub-Bituminous Stackout/Reclaim (Area E)	\$3,784.08
29	Empty Transfer Hoppers and Clean Transfer House 2 (Area F)	\$3,784.08
30	Empty Transfer Hoppers and Clean the New Crusher House (Area G)	\$3,784.08
31	Empty and Clean the Blended Stackout/Reclaim (Area H)	\$3,784.08
32	Empty and Clean the Old Crusher House (Area I)	\$3,784.08
33	Empty and Clean Silo E	\$2,941.36
34	Empty Transfer Hoppers and Clean Transfer House (Area J)	\$3,784.08
35	Conveyors	\$20,181.76
36	Clean Conveyors - 5, 5A, 6, 6A, 16, 17, 7W, 7E, 7, 18, 18S, 18N, 11, 15, 8, 10C, 9A, 9, 12, 12A, 13, 14, 14A, 3 and 3A	\$20,181.76
37	Remove Bags and Clean Dust Collectors	\$5,926.40
38	Clean and Secure Miscellaneous Fuel Yard Equipment and clean	\$6,306.80
	laydown yards	70,300.00
39	Nox Out Ultra System	\$17,861.28
40	Drain and clean Tank 1100, 1200 and 1300	\$3,784.08
41	Drain and clean trank 1100, 1200 and 1300 Drain and clean the Solutionizing Tank	\$3,784.08

D	Task Name	Cost
42	Drain and clean the equipment in the HFD Enclosure	\$3,859.92
43	Open, clean and vent the equipment and piping by the MDM	\$6,433.20
	building	
44	Intake Structures and Intake Chemical Feed System	\$842.72
45	Remove Chemicals	\$842.72
46	Underground Circulating Water Piping	\$3,849.60
47	Drain the Underground Circulating Water Piping	\$3,849.60
48	Sewage Treatment	\$4,202.72
49	Clean the Sewage Treatment Facility	\$4,202.72
50	Water Treatment	\$21,443.12
51	Drain and clean clarifier	\$2,522.72
52	Empty, clean and vent gravity filters	\$2,522.72
53	Open and vent storage tanks	\$1,261.36
54	Empty, clean and vent carbon filters	\$3,784.08
55	Remove RO membranes and open membrane housings	\$1,261.36
56	Remove deminerilizer resins, clean and vent vessels	\$5,045.44
57	Remove chemicals and flush storage tanks	\$2,522.72
58	Flush and vent all water treatment piping.	\$2,522.72
59	Fuel Storage	\$3,370.88
60	Remove propane from propane storage tanks and vent.	\$842.72
61	Vent propane piping and vaporizer.	\$842.72
62	Drain and vent the Diesel Fuel Tank	\$1,685.44
63	Unit 3 Diesel Generator	\$842.72
64	Drain and vent diesel generator tank	\$842.72
65	Post Retirement Closure Activities	\$26,224.40
66	Post Retirement Closure Activities	\$26,224.40



	Task Name	Duration		1st Quar	ter		2nd Qu	artei	-			3rd	Quart	er
			Dec	Jan	Feb	Mar	Apr		May	Jun	1	J	ul	Δ
29	Empty Transfer Hoppers and Clean Transfer House 2 (Area F)	3 days												
30	Empty Transfer Hoppers and Clean the New Crusher House (Area G)	3 days												
31	Empty and Clean the Blended Stackout/Reclaim (Area H)	3 days												
32	Empty and Clean the Old Crusher House (Are	3 days					T							
33	Empty and Clean Silo E	3 days					*							
34	Empty Transfer Hoppers and Clean Transfer House (Area J)	3 days												
35	Conveyors	16 days												
36	Clean Conveyors - 5, 5A, 6, 6A, 16, 17, 7W, 7E, 7, 18, 18S, 18N ,11, 15, 8, 10C, 9A, 9, 12, 12A, 13, 14, 14A, 3 and 3A	16 days												
37	Remove Bags and Clean Dust Collectors	4 days							5					
38	Clean and Secure Miscellaneous Fuel Yard Equipment and clean laydown yards	5 days												
39	Nox Out Ultra System	14 days												
40	Drain and clean Tank 1100, 1200 and 1300	3 days												
41	Drain and clean the Solutionizing Tank	3 days								,]				
42	Drain and clean the equipment in the HFD Enclosure	3 days							`					
43	Open, clean and vent the equipment and piping by the MDM building	5 days												
44	Intake Structures and Intake Chemical Feed System	1 day												
45	Remove Chemicals	1 day								K				
46	Underground Circulating Water Piping	3 days												
47	Drain the Underground Circulating Water Piping	3 days												
48	Sewage Treatment	4 days									,			
49	Clean the Sewage Treatment Facility	4 days								Y -)			
50	Water Treatment	17 days								_				

D	Task Name	Duration		1st Quarte	r		2nd Qua	rter		3rd Quarter		
			Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Au	
51	Drain and clean clarifier	2 days							5			
52	Empty, clean and vent gravity filters	2 days							, in			
53	Open and vent storage tanks	1 day							Τ,			
54	Empty, clean and vent carbon filters	3 days							Ť	,]		
55	Remove RO membranes and open membrane housings	1 day							Ĩ			
56	Remove deminerilizer resins, clean and vent vessels	4 days							`			
57	Remove chemicals and flush storage tanks	2 days										
58	Flush and vent all water treatment piping.	2 days								Š		
59	Fuel Storage	4 days										
60	Remove propane from propane storage tanks and vent.	1 day										
61	Vent propane piping and vaporizer.	1 day								K		
62	Drain and vent the Diesel Fuel Tank	2 days								*		
63	Unit 3 Diesel Generator	1 day										
64	Drain and vent diesel generator tank	1 day								Ϋ́		
65	Post Retirement Closure Activities	20 days									-	
66	Post Retirement Closure Activities	20 days								<u> </u>		

Sibley Common Dismantlement

Owner Additional Costs

Pre-Dismantlement Activities \$0
Overhead During Dismantlement \$0

Owner Costs Total* \$0

Demolition General Contractor (DGC) Costs

Additional Site Management \$123,085
Equipment Rental \$600,070
Consummables \$899,049
Scrap Crew(s) \$892,097
Dismantlement \$3,939,133

Contractor Direct Cost* \$6,453,434

Contractor Allowances

DGC Insurance 2.00% \$129,069

Contingency/Profit 15.00% \$987,375

Performance Bond 2.00% \$151,398

Contractor Costs Total: \$7,721,276

Total: \$7,721,276

Owner Internal Costs: 5.00% \$386,064

Owner Contingency: 25.00% \$2,026,835

\$10,134,174

Sibley Common Dismantlement Opinion of Probable Cost:

*Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances = \$6,453,434

)	Task Name	Cost
1	Sibley Common Dismantlement	\$6,453,436.0
2	Overheads	\$2,514,302.4
3	Common Removal Overheads	\$123,085.
4	Added Overhead Staff for Common Removals	\$123,085.0
5	Common Removal Equipment Rental	\$600,070.
6	Common Removal Equipment Rental	\$600,070.0
7	Demolition Contractor Consummables	\$899,049.3
8	Consummables	\$899,049.3
9	Scrap Crew	\$892,097.
10	Crew(s) to Handle Scrap Material	\$892,097.
11	Dismantlement Activities	\$3,939,133.
12	Administration/Service Building	\$53,740.
13	Remove Administration/Service Building	\$53,740.
14	Fuel Yard Office Building	\$17,913.
15	Remove Fuel Yard Office Building	\$17,913.
16	Temporary Service Building	\$7,165.
17	Remove Temporary Service Building	\$7,165.
18	Parking Lots and Plant Roads	\$64,488.
19	Plant Roads and Parking Areas	\$53,740.
20	Guard Shack	\$10,748.
21	Warehouse(s)	\$35,827.
22	Remove Main Warehouse	\$21,496.
23	Remove Middle Warehouse	\$14,330
24	Tractor Shed	\$14,330.
25	Remove Tractor Shed	\$14,330
26	Out Buildings	\$11,607.
27	Remove Insulators Shack	\$4,643.
28	Remove Hedrick Hall	\$6,964.
29	Fuel Equipment	\$25,536
30	Remove Propane Tanks and above ground piping	\$11,607.
31	Remove Vaporizer	\$9,286.
32	Remove Diesel Generator Tank	\$4,643
33	Fuel Yard	\$302,143.
34	Remove Rotary Car Dumper	\$23,215.
35	Remove Sample House	\$23,215.
36	Remove Transfer Hoppers	\$11,607
37	Remove Bituminous Stackout Reclaim	\$16,250.
38	Remove Sub-Bituminous Stackout/Reclaim	\$16,250.
39	Remove Transfer House 2	\$13,929.
40	Remove New Crusher House	\$34,822.
41	Remove the Blended Stackout/Reclaim	\$16,250.
42	Remove Old Crusher House	\$27,858.
43	Remove Transfer House	\$13,929.
44	Conveyors	\$46,430.

D	Task Name	Cost
45	Remove Conveyors - 5, 5A, 6, 6A, 16, 17, 7W, 7E, 7, 18, 18S, 18N ,1	\$46,430.40
46	Remove Dust Collectors	\$4,643.04
47	Remove Miscellaneous Fuel Yard Equipment	\$53,740.80
48	Nox Out Ultra System	\$18,572.16
49	Remove Tank 1100, 1200 and 1300	\$4,643.04
50	Remove Solutionizing Tank	\$4,643.04
51	Remove HFD Enclosure	\$6,964.56
52	Remove miscellaneous piping and steel.	\$2,321.52
53	Underground Circulating Water Piping	\$53,740.80
54	Excavate Underground Circulating Water Piping	\$17,913.60
55	Collapse Underground Circulating Water Piping	\$10,748.16
56	Backfill and Compact Over Circulating Water Piping	\$25,079.04
57	Sewage Treatment	\$21,496.32
58	Remove Sewage Treatment Pumps and Miscellaneous Equipment	\$7,165.44
59	Remove Sewage Treatment Concrete Structures	\$14,330.88
60	Yard Fire Water Systems	\$21,496.3
61	Remove Hydrants and Fire Water System Piping Down to 3' Below Grade	\$21,496.32
62	Water Treatment	\$46,430.40
63	Remove clarifier	\$4,643.0
64	Remove gravity filters	\$4,643.04
65	Remove storage tanks	\$9,286.0
66	Remove carbon filters	\$4,643.04
67	Remove RO skids	\$4,643.04
68	Remove demineralizer vessels	\$6,964.5
69	Remove regeneration equipment	\$6,964.5
70	Remove miscellanous piping and support equipment	\$4,643.0
71	Unit 3 Diesel Generator	\$4,643.0
72	Remove Unit 3 Diesel Generator	\$4,643.04
73	Common Stack	\$3,240,000.0
74	Remove Common Stack to Grade	\$3,240,000.00
75	Final Site Grading and Drainage	\$0.00
76	Final Site Grading and Drainage	\$0.00

	Task Name	Duration		2012		1				2013	
	Cibles Common Discountlement	250 4-	Qtr 4	Qt	tr 1	Qtr 2	Q	tr 3	Qtr 4	Qtr 1	Qt
1	Sibley Common Dismantlement	250 days	_								
2	Overheads	249 days	-								
3	Common Removal Overheads	249 days	-								
4	Added Overhead Staff for Common Removals	249 days	_								
5	Common Removal Equipment Rental	249 days	_								
6	Common Removal Equipment Rental	249 days	_								
7	Demolition Contractor Consummables	249 days	_								
8	Consummables	249 days	_								
9	Scrap Crew	249 days	_								
10	Crew(s) to Handle Scrap Material	249 days	_								
11	Dismantlement Activities	249 days	_								
12	Administration/Service Building	15 days									
13	Remove Administration/Service Building	15 days	_			ከ					
14	Fuel Yard Office Building	5 days	-			T					
15	Remove Fuel Yard Office Building	5 days	-			-					
16	Temporary Service Building	2 days	-			4					
17	Remove Temporary Service Building	2 days				ň					
18	Parking Lots and Plant Roads	18 days				T					
19	Plant Roads and Parking Areas	15 days									
20	Guard Shack	3 days				ΐ					
21	Warehouse(s)	10 days									
22	Remove Main Warehouse	6 days				<u> </u>					
23	Remove Middle Warehouse	4 days				ď					
24	Tractor Shed	4 days									
25	Remove Tractor Shed	4 days				Ť					
26	Out Buildings	5 days				•					
27	Remove Insulators Shack	2 days				<u> </u>					
28	Remove Hedrick Hall	3 days				h					
29	Fuel Equipment	11 days				-					
30	Remove Propane Tanks and above ground piping	5 days									
31	Remove Vaporizer	4 days				ì	ή				
32	Remove Diesel Generator Tank	2 days					K				

)	Task Name	Duration		2	012							2013		
33	Fuel Yard	122 days	Qtr 4		Qtr	1	Qtr 2	2	Qtr 3	Qt	r 4	Qt	r 1	Qtr 2
34		122 days						T			_			
	Remove Rotary Car Dumper	10 days												
35 36	Remove Sample House	10 days												
	Remove Transfer Hoppers	5 days												
37	Remove Bituminous Stackout Reclaim	7 days												
38	Remove Sub-Bituminous Stackout/Reclaim	7 days	_											
39	Remove Transfer House 2	6 days												
40	Remove New Crusher House	15 days								•				
41	Remove the Blended Stackout/Reclaim	7 days												
42	Remove Old Crusher House	12 days												
43	Remove Transfer House	6 days												
44	Conveyors	20 days												
45	Remove Conveyors - 5, 5A, 6, 6A, 16, 17, 7W, 7E, 7, 18, 18S 18N ,11, 15, 8, 10C, 9A, 9, 12, 12A, 13, 14, 14A, 3 and 3A	, 20 days												
46	Remove Dust Collectors	2 days								Ì	L			
47	Remove Miscellaneous Fuel Yard Equipment	15 days												
48	Nox Out Ultra System	8 days												
49	Remove Tank 1100, 1200 and 1300	2 days									<u>h</u>			
50	Remove Solutionizing Tank	2 days									K			
51	Remove HFD Enclosure	3 days									K			
52	Remove miscellaneous piping and steel.	1 day									Ъ	•		
53	Underground Circulating Water Piping	15 days										—		
54	Excavate Underground Circulating Water Piping	5 days									ř			
55	Collapse Underground Circulating Water Piping	3 days												
56	Backfill and Compact Over Circulating Water Piping	7 days									İ			
57	Sewage Treatment	6 days										•		
58	Remove Sewage Treatment Pumps and Miscellaneous Equipment	2 days												

)	Task Name	Duration		2012			1	2013	
			Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr
59	Remove Sewage Treatment Concrete Structures	4 days						Ť	
60	Yard Fire Water Systems	6 days						•	
61	Remove Hydrants and Fire Water System Piping Down to 3' Below Grade	6 days							
62	Water Treatment	20 days							
63	Remove clarifier	2 days						Ϋ́	
64	Remove gravity filters	2 days						K	
65	Remove storage tanks	4 days						ξ	
66	Remove carbon filters	2 days						Ϋ́	
67	Remove RO skids	2 days						Κ	
68	Remove demineralizer vessels	3 days						K	
69	Remove regeneration equipment	3 days						F	
70	Remove miscellanous piping and support equipment	2 days							
71	Unit 3 Diesel Generator	2 days						•	
72	Remove Unit 3 Diesel Generator	2 days						K	
73	Common Stack	1 day							
74	Remove Common Stack to Grade	1 day		4					
75	Final Site Grading and Drainage	1 day						•	
76	Final Site Grading and Drainage	1 day							

SOUTH HARPER

SOUTH HARPER STATION

The South Harper Generating Station consists of three natural gas-fired combustion turbine generator sets.

Combined, these combustion turbines have an SPP-accredited unit rating of 313.9 MW. South Harper was placed into service in 2005. Each unit is comprised of a Siemens Model 504D5A combustion turbine with a generator step-up transformer and auxiliary power transformer.

The following are the major systems and equipment that were included in the retirement and dismantlement of the South Harper Generating Station.

- 1. Combustion turbine generator sets and auxiliaries.
- 2. Generation step-up and auxiliary transformers.
- 3. Outdoor switchgear.
- 4. Exhaust stacks.
- 5. Administration building.
- 6. Natural gas filtering skid.
- 7. Flammable material storage building.
- 8. Service/Instrument air compressors.
- 9. Waste water tank.

South Harper Retirement

Owner Costs

Pre-Retirement Activities \$43,834
Retirement Activities \$219,498
Post-Retirement Activities \$45,152

Owner Direct Total \$308,484

Owner Internal Costs 5.00% \$15,424

Owner Contingency: 25.00% \$80,977

South Harper Retirement Opinion of Probable Cost:

\$404,885.25

)	Task Name	Cost
1	South Harper Retirement	\$308,484.94
2	Pre-Retirement Activities	\$43,834.00
3	Permitting Review	\$23,466.00
4	Develop Detailed Retirement Plan	\$20,368.00
5	Retirement	\$219,498.94
6	Project Management During Retirement	\$98,648.46
7	Project Management During Retirement	\$98,648.46
8	Retirement Activities	\$119,567.28
9	Electrical	\$44,664.00
10	Medium and Low Voltage Drawout Switchgear	\$12,505.92
11	De-energize all buses at the source.	\$2,679.84
12	Open all circuit breakers.	\$2,679.84
13	Rack all circuit breakers into the fully withdrawn, disconnected	\$2,679.84
	position.	
14	Verify that the closing/tripping springs are discharged.	\$2,679.84
15	De-energize control power and auxiliary power circuits of each	\$1,786.56
	circuit breaker at the source and by opening control power	
	circuit breakers or removing fuses in each breaker cubicle.	
16	Motor Control Centers	\$6,252.90
17	De-energize all buses at the source.	\$893.28
18	Open all circuit breakers and disconnect switches.	\$2,679.84
19	Remove all fuses in control circuits.	\$2,679.84
20	Low-voltage Switchboards and Panelboards	\$5,359.68
21	De-energize all buses at the source.	\$2,679.84
22	Open all circuit breakers and disconnect switches.	\$2,679.84
23	Oil-Filled Power Transformers	\$9,826.08
24	De-energize all buses at the source.	\$2,679.84
25	Open all circuit breakers and disconnect switches.	\$1,786.56
26	De-energize all buses at the source.	\$2,679.84
27	Open all circuit breakers and disconnect switches.	\$2,679.84
28	Dry-type Power Transformers	\$4,466.40
29	De-energize all transformer primaries and verify that the secondary is de-energized.	\$2,679.84
30	De-energize all low-voltage AC or DC power sources for space	\$1,786.50
	heaters, cooling equipment, controls, etc. at the source and	Ψ1), σσισί
	open circuit breakers or remove fuses at transformer end.	
31	Motors	\$6,252.90
32	De-energize all primary power at the source.	\$1,786.56
33	De-energize all low-voltage power sources for space heaters or	
	other auxiliary equipment at the source.	71,700.30
34	Drain lube oil system (if applicable) and dispose of oil.	\$2,679.84
35	Administration Building	\$9,342.40
36	Secure the Administration Building	\$9,342.40

South I	Harper	Retirement
---------	--------	------------

ID	Task Name	Cost
37	Flammabe Material Storage Building	\$5,605.44
38	Secure the Flammable Material Storage Building	\$5,605.44
39	Fuel Gas System	\$10,783.04
40	Isolate Fuel Gas System	\$3,907.44
41	Vent Fuel Gas Piping and Equipment	\$2,528.16
42	Open and Vent Knock-Out Drum	\$861.84
43	Drain, Open and Vent the Drain Tank	\$861.84
44	Empty the Coalescing Filter	\$1,761.92
45	Open and Vent Equipment on the CT Gas Valve Module	\$861.84
46	Lube Oil Cooling Water System	\$7,756.56
47	Open and Drain the Water Side of the Lube Oil Coolers	\$5,171.04
48	Open and Vent the Coolers and Expansion Tank	\$2,585.52
49	Oily Drain Tank	\$3,954.00
50	Open and Pump Out the Oily Drain Tank	\$3,954.00
51	Wash Water Skid	\$5,171.04
52	Open and Drain the Detergent Tank	\$1,723.68
53	Open and Drain the Demineralized Water Tank	\$1,723.68
54	Empty the Demineralized Water Tank	\$1,723.68
55	Compressed Air	\$3,447.36
56	Empty Dessiccant Air Dryers and Vent	\$1,723.68
57	Open and Vent the Air Reciever	\$1,723.68
58	Miscelleaneous Piping	\$7,756.56
59	Open and Vent the Exhaust Frame Cooling Piping	\$2,585.52
60	Open and Vent the CT Air Processing Piping	\$0.00
61	Open and Vent the Inlet Air Heating Piping	\$2,585.52
62	Open and Vent the CT Air Processing Piping	\$2,585.52
63	Fire Protection Piping	\$6,856.48
64	Empty the CO2 Storage Tank	\$5,132.80
65	Open and Vent the Fire Protection Piping	\$1,723.68
66	Lube Oil System	\$11,587.04
67	Empty and Remove from Site the Lubricating Oil	\$6,416.00
68	Drain Lubricating Oil Piping	\$3,447.36
69	Open and Vent Lubricating Oil Piping	\$1,723.68
70	Potable Water	\$2,643.36
71	Disconnect Potable Water at Property Boundary	\$2,643.36
72	Waste Water Tank	\$1,283.20
73	Open, Drain and Vent Waste Water Tank	\$1,283.20
74	Post Retirement Closure Activity	\$45,152.00
75	Post Retirement Closure Activity	\$45,152.00

D	Task Name	Duration	3rd Quar	rter		4th Qu	ıarter		1st	Quarte	er		2nd Q	uarter		3rd C
			Jul	Aug S	Sep	Oct	Nov	Dec	Ja	n Fe	eb Mar	r	Apr	May	Jun	Jul
1	South Harper Retirement	204 days														
2	Pre-Retirement Activities	40 days														
3	Permitting Review	20 days					KCP&	L Proje	ct Ma	anager	[25%],KC	CP&	L Eng	ineer[200%]	
4	Develop Detailed Retirement Plan	20 days				ĺ										
5	Retirement	124 days					•									
6	Project Management During Retirement	123 days					—									
7	Project Management During Retirement	123 days							_	_			_			
8	Retirement Activities	123 days					•									
9	Electrical	50 days														
10	Medium and Low Voltage Drawout Switchg	14 days					•									
11	De-energize all buses at the source.	3 days														
12	Open all circuit breakers.	3 days					,	5								
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	3 days														
14	Verify that the closing/tripping springs are discharged.	3 days														
15	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each	2 days														
16	Motor Control Centers	7 days							ı							
17	De-energize all buses at the source.	1 day						片								
18	Open all circuit breakers and disconnect switches.	3 days														
19	Remove all fuses in control circuits.	3 days						*)							
20	Low-voltage Switchboards and Panelboard	s 6 days														
21	De-energize all buses at the source.	3 days														
22	Open all circuit breakers and disconnect switches.	3 days						,								
23	Oil-Filled Power Transformers	11 days														
24	De-energize all buses at the source.	3 days							*							
25	Open all circuit breakers and disconnect switches.	2 days							+							

D	Task Name	Duration	3rd Q	uarter		4th Q	uarter		1st	Quar	ter		2nd C	Quarte	er	3rd (
			Jul	Aug	Sep	Oct	Nov	Dec	Ja	n	Feb N	Иar	Apr	Ma	ay Ju	n Jul
26	De-energize all buses at the source.	3 days							ď	l						
27	Open all circuit breakers and disconnect switches.	3 days														
28	Dry-type Power Transformers	5 days							•							
29	De-energize all transformer primaries and verify that the secondary is de-energized.	3 days														
30	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses	2 days														
31	Motors	7 days														
32	De-energize all primary power at the source.	2 days														
33	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	2 days														
34	Drain lube oil system (if applicable) and dispose of oil.	3 days														
35	Administration Building	5 days								-						
36	Secure the Administration Building	5 days									ή					
37	Flammabe Material Storage Building	3 days								Į	•					
38	Secure the Flammable Material Storage Build	3 days									ή					
39	Fuel Gas System	11 days														
40	Isolate Fuel Gas System	3 days									4					
41	Vent Fuel Gas Piping and Equipment	3 days									4					
42	Open and Vent Knock-Out Drum	1 day									K					
43	Drain, Open and Vent the Drain Tank	1 day									Ь					
44	Empty the Coalescing Filter	2 days									h					
45	Open and Vent Equipment on the CT Gas Valve Module	1 day									h					
46	Lube Oil Cooling Water System	9 days									-					
47	Open and Drain the Water Side of the Lube Oil Coolers	6 days									*	ከ				

)	Task Name	Duration	3rd Qເ			4th Qι			1st Qı				uarter	T	3rd Q
		_	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul
48	Open and Vent the Coolers and Expansion Ta										Ť				
49	Oily Drain Tank	3 days									T				
50	Open and Pump Out the Oily Drain Tank	3 days													
51	Wash Water Skid	6 days										l			
52	Open and Drain the Detergent Tank	2 days									Ť				
53	Open and Drain the Demineralized Water Tar	2 days									<u> </u>	_			
54	Empty the Demineralized Water Tank	2 days									(F				
55	Compressed Air	4 days									—				
56	Empty Dessiccant Air Dryers and Vent	2 days									Ì				
57	Open and Vent the Air Reciever	2 days										ή			
58	Miscelleaneous Piping	17 days									ı	-			
59	Open and Vent the Exhaust Frame Cooling Pip	3 days										5			
60	Open and Vent the CT Air Processing Piping	8 days													
61	Open and Vent the Inlet Air Heating Piping	3 days										4			
62	Open and Vent the CT Air Processing Piping	3 days											7 		
63	Fire Protection Piping	6 days										•			
64	Empty the CO2 Storage Tank	4 days											ή		
65	Open and Vent the Fire Protection Piping	2 days											5		
66	Lube Oil System	9 days													
67	Empty and Remove from Site the Lubricating	5 days													
68	Drain Lubricating Oil Piping	4 days													
69	Open and Vent Lubricating Oil Piping	2 days											Š		
70	Potable Water	3 days											•		
71	Disconnect Potable Water at Property Bound	3 days											*		
72	Waste Water Tank	1 day											*		
73	Open, Drain and Vent Waste Water Tank	1 day											h		
74	Post Retirement Closure Activity	40 days											—		—
75	Post Retirement Closure Activity	40 days											*		

South Harper Dismantlement

Owner Costs

Pre-Dismantlement Activities \$892,760

Overhead During Dismantlement \$1,493,362

Post-Dismantlement Activities \$49,140

Owner Costs Total* \$2,435,262

Demolition General Contractor (DGC) Costs

 Site Management
 \$814,043

 Equipment Rental
 \$1,386,092

 Consummables
 \$138,875

 Scrap Crew(s)
 \$364,064

 Dismantlement
 \$1,236,894

Contractor Direct Cost* \$3,939,968

Contractor Allowances

DGC Insurance 2.00% \$78,799

Contingency/Profit 15.00% \$602,815

Performance Bond 2.00% \$92,431.65

Contractor Costs Total: \$4,714,014

Total: \$7,149,276

Owner Internal Costs: 5.00% \$357,464

Owner Contingency: 25.00% \$1,876,685

South Harper Dismantlement Opinion of Probable Cost: \$9,383,425

^{*}Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances = \$6,375,230

D	Task Name	Cost
1	South Harper CT Dismantlement	\$6,375,218.4
2	Pre-Demolition Activities	\$892,760.3
3	Detailed Planning & Hire Owner's Engineer	\$104,441.2
4	Detailed Site Characterization Study	\$610,335.4
5	Hire Demolition general Contractor	\$167,184.0
6	KCP&L Prepares Unit for Dismantlement	\$10,799.6
7	Demolition Contractor Mobilizes on Site	\$0.0
8	KCP&L Overhead during Dismantlement	\$1,493,362.9
9	KCP&L Project Manager	\$237,306.8
10	KCP&L Administrative Support	\$87,752.9
11	KCP&L Engineer	\$390,047.2
12	Owners Engineer Project Manager	\$116,432.0
13	Owners Engineer - Engineer	\$661,824.0
14	Demolition Contractor Overhead during Dismantlement	\$814,043.5
15	Demolition Contractor Project Manager	\$230,320.8
16	Demolition Contractor Safety Manager	\$205,073.5
17	Demolition Contractor Superintendent	\$378,649.1
18	Demolition Contractor Equipment Rental Cost	\$1,386,092.3
19	Equipment Rental	\$1,386,092.3
20	Demolition Contractor Consumables	\$138,860.4
21	Consumables	\$138,860.4
22	Scrap Crews	\$364,064.4
23	Crew to Handle Scrap Material(s)	\$364,064.4
25	Dismantlement	\$1,236,894.3
26	Electrical	\$197,049.6
27	Electrical Demolition of Equipment	\$197,049.6 \$21,113.2
28	Fuel Gas System Remove all above grade fuel gas piping.	\$6,782.3
29	Gas Filter Skid	\$14,330.8
30	Lube Oil System	\$14,530.8 \$53,740.8
31	Lube Oil Piping	\$14,330.8
32	Lube Oil Pumps	\$17,913.6
33	Lube Oil Tanks	\$21,496.3
34	Compressed Air System	\$21,496.3
35	Compressed Air Piping	\$10,748.1
36	Compressors	\$5,374.0
37	Air Receiver	\$3,582.7
38	Dryer	\$1,791.3
39	Fire Protection	\$26,870.4
40	Fire Protection Piping	\$19,704.9
41	CO2 Storage Tank	\$7,165.4
42	Wash Water Skid	\$10,748.1
43	Detergent Tank	\$10,748.1
44	Miscellaneous Piping	\$62,697.6

D	Task Name	Cost
45	Exhaust Frame Cooling Piping	\$17,913.60
46	CT Air Processing Piping	\$21,496.32
47	Inlet Air Heating Piping	\$23,287.68
48	Generator	\$0.00
49	Generators	\$0.00
50	Combustion Turbine	\$263,329.92
51	Inlet Heaters	\$17,913.60
52	Inlet ducts	\$26,870.40
53	Exhaust ducts	\$35,827.20
54	Combustion Turbines	\$62,697.60
55	Combustion Turbine Foundations	\$66,280.3
56	Enclosures	\$53,740.80
57	CEMS	\$42,992.6
58	CEMS Building	\$21,496.3
59	CEMS Building Foundation	\$21,496.3
60	Stack	\$80,611.2
61	Stacks	\$80,611.2
62	Buildings	\$23,287.6
63	Remove Administration Building	\$17,913.6
64	Remove Flammable Material Storage Building	\$5,374.0
65	Waste Water Tank	\$8,956.8
66	Remove Waste Water Tank	\$8,956.80

67

68

69

70

Site Prep

Final Grading and Drainage

Post Dismantlement Activities


Post Dismantlement Activities

\$424,000.00

\$424,000.00

\$49,140.00

\$49,140.00



	Task Name	Duration		2014		2015	ı	201
33	Lube Oil Tanks	12 days	Qtr 2 Qtr 3 Qtr 4	Qtr 1 Qtr 2	Qtr 3 Qtr 4	Qtr 1 Qtr 2	Qtr 3 Qtr 4	Qtr
		12 days						
34	Compressed Air System	12 days				\downarrow		
	Compressed Air Piping	6 days						
36	Compressors	3 days				h		
37	Air Receiver	2 days				\supset		
38	Dryer	1 day				1		
39	Fire Protection	15 days						
40	Fire Protection Piping	11 days						
41	CO2 Storage Tank	4 days						
42	Wash Water Skid	6 days						
43	Detergent Tank	6 days	_					
44	Miscellaneous Piping	35 days						
45	Exhaust Frame Cooling Piping	10 days				•		
46	CT Air Processing Piping	12 days						
47	Inlet Air Heating Piping	13 days						
48	Generator	29 days						
49	Generators	29 days						
50	Combustion Turbine	147 days						
51	Inlet Heaters	10 days				5		
52	Inlet ducts	15 days				<u> </u>		
53	Exhaust ducts	20 days				Ě	L	
54	Combustion Turbines	35 days						
55	Combustion Turbine Foundations	37 days						
56	Enclosures	30 days						
57	CEMS	24 days						
58	CEMS Building	12 days						
59	CEMS Building Foundation	12 days						
60	Stack	45 days					Į.	+
61	Stacks	45 days						
62	Buildings	13 days						•
63	Remove Administration Building	10 days						
64	Remove Flammable Material Storage Building	3 days						

South	Harper Dismantlement			
ID	Task Name	Duration	2014 2015 20	016
			Qtr 2 Qtr 3 Qtr 4 Qtr 1 Qtr 2 Qtr 3 Qtr 4 Qtr 1 Qtr 2 Qtr 3 Qtr 4 Qtr 1	tr 1 Qtr 2
65	Waste Water Tank	5 days		#
66	Remove Waste Water Tank	5 days		
67	Site Prep	20 days		
68	Final Grading and Drainage	20 days		
69	Post Dismantlement Activities	30 days		
70	Post Dismantlement Activities	30 days		

GREENWOOD

GREENWOOD STATION

The Greenwood Generating Station consists of four natural gas-fired and distillate-fired combustion turbine generator sets.

Combined, these combustion turbines have an SPP-accredited unit rating of 252.7 MW. Greenwood Units 1 and 2 were placed in service in 1975. Greenwood Unit 3 was placed in service in 1977. Greenwood Unit 4 was placed in service in 1979. Each unit is comprised of a GE Model MA7001B combustion turbine with a generator step-up transformer and auxiliary power transformer.

The following are the major systems and equipment that were included in the retirement and dismantlement of the Greenwood Generating Station.

- 1. Combustion turbine generator sets and auxiliaries.
- 2. Generation step-up and auxiliary transformers.
- 3. Outdoor switchgear.
- 4. Exhaust stacks.
- 5. Administration building.
- 6. Combustion turbine building.
- 7. Natural gas filtering skid.
- 8. Water treatment.
- 9. Service/Instrument air compressors.
- 10. Diesel generator.
- 11. Fuel oil storage and transfer equipment.

Greenwood Retirement

Owner Costs

Pre-Retirement Activities \$43,834
Retirement Activities \$225,697
Post-Retirement Activities \$45,152

Owner Direct Total \$314,683

Owner Internal Costs 5.00% \$15,734

Owner Contingency: 25.00% \$82,604

Greenwood Retirement Opinion of Probable Cost: \$413,021.44

Activities Required by Permit or Regulation

Greenwood Storage Tank \$157,111
Greenwood Storage Tank (2) \$157,111
Greenwood Storage Tank (3) \$157,111

Activities Required by Permit or Regulation: \$471,333

)	Task Name	Cost
1	Greenwood Retirement	\$314,683.28
2	Pre-Retirement Activities	\$43,834.00
3	Permitting Review	\$23,466.00
4	Develop Detailed Retirement Plan	\$20,368.00
5	Retirement	\$225,697.28
6	Project Management During Retirement	\$105,866.64
7	Project Management During Retirement	\$105,866.64
8	Retirement Activities	\$119,830.64
9	Electrical	\$44,664.00
10	Medium and Low Voltage Drawout Switchgear	\$12,505.92
11	De-energize all buses at the source.	\$2,679.84
12	Open all circuit breakers.	\$2,679.84
13	Rack all circuit breakers into the fully withdrawn,	\$2,679.84
	disconnected position.	
14	Verify that the closing/tripping springs are discharged.	\$2,679.84
15	De-energize control power and auxiliary power circuits of	\$1,786.56
	each circuit breaker at the source and by opening control	
	power circuit breakers or removing fuses in each breaker	
	cubicle.	
16	Motor Control Centers	\$6,252.96
17	De-energize all buses at the source.	\$893.28
18	Open all circuit breakers and disconnect switches.	\$1,786.56
19	Remove all fuses in control circuits.	\$3,573.12
20	Low-voltage Switchboards and Panelboards	\$5,359.68
21	De-energize all buses at the source.	\$2,679.84
22	Open all circuit breakers and disconnect switches.	\$2,679.84
23	Oil-Filled Power Transformers	\$9,826.08
24	De-energize all buses at the source.	\$2,679.84
25	Open all circuit breakers and disconnect switches.	\$1,786.56
26	De-energize all buses at the source.	\$2,679.84
27	Open all circuit breakers and disconnect switches.	\$2,679.84
28	Dry-type Power Transformers	\$4,466.40
29	De-energize all transformer primaries and verify that the	\$2,679.84
	secondary is de-energized.	
30	De-energize all low-voltage AC or DC power sources for	\$1,786.56
	space heaters, cooling equipment, controls, etc. at the	
	source and open circuit breakers or remove fuses at	
	transformer end.	
31	Motors	\$6,252.96
32	De-energize all primary power at the source.	\$1,786.56
33	De-energize all low-voltage power sources for space	\$1,786.56
	heaters or other auxiliary equipment at the source.	
34	Drain lube oil system (if applicable) and dispose of oil.	\$2,679.84
35	Administration Building	\$7,473.92

	Task Name	Cost
36	Secure the Administration Building/Maintenance Shop	\$7,473.92
37	Combustion Turbine Buildings	\$0.00
38	Secure the Combustion Turbine Buildings	\$0.00
39	Fuel Gas System	\$10,783.04
40	Isolate Fuel Gas System	\$3,907.44
41	Vent Fuel Gas Piping and Equipment	\$2,528.16
42	Open and Vent Knock-Out Drum	\$861.84
43	Drain, Open and Vent the Drain Tank	\$861.84
44	Empty the Coalescing Filter	\$1,761.92
45	Open and Vent Equipment on the CT Gas Valve Module	\$861.84
46	Lube Oil Cooling Water System	\$7,756.56
47	Open and Drain the Water Side of the Lube Oil Coolers	\$5,171.04
48	Open and Vent the Coolers and Expansion Tank	\$2,585.52
49	Oily Drain Tank	\$3,954.00
50	Open and Pump Out the Oily Drain Tank	\$3,954.00
51	Wash Water Skid	\$5,171.04
52	Open and Drain the Detergent Tank	\$1,723.68
53	Open and Drain the Demineralized Water Tank	\$1,723.68
54	Empty the Demineralized Water Tank	\$1,723.68
55	Compressed Air	\$3,447.36
56	Empty Dessiccant Air Dryers and Vent	\$1,723.68
57	Open and Vent the Air Reciever	\$1,723.68
58	Miscelleaneous Piping	\$7,756.56
59	Open and Vent the Exhaust Frame Cooling Piping	\$2,585.52
60	Open and Vent the CT Air Processing Piping	\$0.00
61	Open and Vent the Inlet Air Heating Piping	\$2,585.52
62	Open and Vent the CT Air Processing Piping	\$2,585.52
63	Fire Protection Piping	\$6,856.48
64	Empty the CO2 Storage Tank	\$5,132.80
65	Open and Vent the Fire Protection Piping	\$1,723.68
66	Lube Oil System	\$11,587.04
67	Empty and Remove from Site the Lubricating Oil	\$6,416.00
68	Drain Lubricating Oil Piping	\$3,447.36
69	Open and Vent Lubricating Oil Piping	\$1,723.68
70	Fuel Oil Storage and Unloading	\$861.84
71	Remove Fuel Oil from Fuel Oil Storage and Vent	\$861.84
72	Water Treatment	\$7,756.56
73	Drain All Tanks and Vessels	\$1,723.68
74	Remove Resin from Vessels	\$2,585.52
75	Remove Chemicals	\$2,585.52
76	Open and Vent Vessels	\$861.84
77	Diesel Generator	\$0.00
78	Empty and Vent Diesel Generator F.O. Tank	\$0.00
79	Potable Water	\$1,762.24

1.	Tack Nama	Cost	
)	Task Name	Cost	¢1.762.24
	Disconnect Potable Water at Property Boundary		\$1,762.24
-	Post Retirement Closure Activity		\$45,152.00
2	Post Retirement Closure Activity		\$45,152.00

	Task Name	Duration	er	2nd Quarter	3rd Quarter	4th Quarter	1st Quarter	2nd Quarter	
			Mar	Apr May Jun	Jul Aug Sep	Oct Nov Dec	Jan Feb Mar	Apr May Jur	-
1	Greenwood Retirement	212 days				V			
2	Pre-Retirement Activities	40 days			•				
3	Permitting Review	20 days				KCP&L Pro	oject Manager[2	25%],KCP&L En	į
4	Develop Detailed Retirement Plan	20 days							
5	Retirement	132 days							
6	Project Management During Retirement	132 days							
7	Project Management During Retirement	132 days							
8	Retirement Activities	132 days							
9	Electrical	50 days							
10	Medium and Low Voltage Drawout Switchg	14 days							
11	De-energize all buses at the source.	3 days				<u>~</u>			
12	Open all circuit breakers.	3 days				5			
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	3 days							
14	Verify that the closing/tripping springs are discharged.	3 days				*			
15	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each	2 days				ř			
16	Motor Control Centers	7 days							
17	De-energize all buses at the source.	1 day				K			
18	Open all circuit breakers and disconnect switches.	2 days				Ť			
19	Remove all fuses in control circuits.	4 days							
20	Low-voltage Switchboards and Panelboards	6 days				—			
21	De-energize all buses at the source.	3 days)		
22	Open all circuit breakers and disconnect switches.	3 days				1			
23	Oil-Filled Power Transformers	11 days				•	-		
24	De-energize all buses at the source.	3 days					*		
25	Open all circuit breakers and disconnect switches.	2 days					†		

)	Task Name	Duration	er	2nd Quarter	3rd Quarter	4th Quarter	1st Quarter	2nd Quarte
			Mar	Apr May Jun	Jul Aug Sep	Oct Nov Dec	Jan Feb Mar	Apr May J
26	De-energize all buses at the source.	3 days					•	
27	Open all circuit breakers and disconnect switches.	3 days						
28	Dry-type Power Transformers	5 days					•	
29	De-energize all transformer primaries and verify that the secondary is de-energized.	3 days						
30	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses	2 days						
31	Motors	7 days						
32	De-energize all primary power at the source.	2 days					7	
33	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	2 days						
34	Drain lube oil system (if applicable) and dispose of oil.	3 days						
35	Administration Building	4 days					•	
36	Secure the Administration Building/Maintenance Shop	4 days						
37	Combustion Turbine Buildings	3 days					•	
38	Secure the Combustion Turbine Buildings	3 days					Τ,	
39	Fuel Gas System	11 days						
40	Isolate Fuel Gas System	3 days					5	
41	Vent Fuel Gas Piping and Equipment	3 days					Š	
42	Open and Vent Knock-Out Drum	1 day					<u>F</u>	
43	Drain, Open and Vent the Drain Tank	1 day					<u> </u>	
44	Empty the Coalescing Filter	2 days					5	
45	Open and Vent Equipment on the CT Gas Valve Module	1 day						
46	Lube Oil Cooling Water System	9 days						

)	Task Name	Duration	er	2nd Quarter	3rd Quarter	4th Quarter	1st Quarter	2nd Quarter	3
			Mar	Apr May Jun	Jul Aug Sep	Oct Nov Dec	Jan Feb Mar	Apr May Jun	
47	Open and Drain the Water Side of the Lube Oil Coolers	6 days							
48	Open and Vent the Coolers and Expansion Ta	3 days					T ₁		
49	Oily Drain Tank	3 days					•		
50	Open and Pump Out the Oily Drain Tank	3 days							
51	Wash Water Skid	6 days							
52	Open and Drain the Detergent Tank	2 days					h		
53	Open and Drain the Demineralized Water Tar	2 days					6		
54	Empty the Demineralized Water Tank	2 days							
55	Compressed Air	4 days					•	•	
56	Empty Dessiccant Air Dryers and Vent	2 days					ì		
57	Open and Vent the Air Reciever	2 days						5	
58	Miscelleaneous Piping	17 days					1		
59	Open and Vent the Exhaust Frame Cooling Pi	3 days						<u></u>	
60	Open and Vent the CT Air Processing Piping	8 days							
61	Open and Vent the Inlet Air Heating Piping	3 days						<u> </u>	
62	Open and Vent the CT Air Processing Piping	3 days						Ŋ	
63	Fire Protection Piping	6 days						*	
64	Empty the CO2 Storage Tank	4 days							
65	Open and Vent the Fire Protection Piping	2 days						, in the second	
66	Lube Oil System	9 days							
67	Empty and Remove from Site the Lubricating	5 days							
68	Drain Lubricating Oil Piping	4 days							
69	Open and Vent Lubricating Oil Piping	2 days						h	
70	Fuel Oil Storage and Unloading	1 day						—	
71	Remove Fuel Oil from Fuel Oil Storage and V	1 day						Ϋ́	
72	Water Treatment	9 days							
73	Drain All Tanks and Vessels	2 days						<u>~</u>	
74	Remove Resin from Vessels	3 days						<u>~</u>	
75	Remove Chemicals	3 days						<u> </u>	
76	Open and Vent Vessels	1 day						ξ	
77	Diesel Generator	1 day						•	

Green	wood Retirement													
ID	Task Name	Duration	er	2nd Quarter	3rd (Quarter	4th (Quarter	1st (Quarter	2nd	Quart	er	3rd C
			Mar	Apr May Jun	Jul	Aug Sep	Oct	Nov Dec	Jan	Feb Mar	Apr	May	Jun	Jul
78	Empty and Vent Diesel Generator F.O. Tank	1 day										H		
79	Potable Water	2 days												
80	Disconnect Potable Water at Property Bound	2 days										ì	▼	
81	Post Retirement Closure Activity	40 days										•		—
82	Post Retirement Closure Activity	40 days										ì		

Greenwood Dismantlement

Owner Costs

Pre-Dismantlement Activities \$892,760

Overhead During Dismantlement \$1,477,766

Post-Dismantlement Activities \$49,140

Owner Costs Total* \$2,419,666

Demolition General Contractor (DGC) Costs

 Site Management
 \$805,541

 Equipment Rental
 \$1,371,616

 Consummables
 \$1,368,432

 Scrap Crew(s)
 \$360,262

 Dismantlement
 \$1,117,115

Contractor Direct Cost* \$5,022,966

Contractor Allowances

DGC Insurance 2.00% \$100,459

Contingency/Profit 15.00% \$768,514

Performance Bond 2.00% \$117,838.78

Contractor Costs Total: \$6,009,778

Total: \$8,429,444

Owner Internal Costs: 5.00% \$421,472


Owner Contingency: 25.00% \$2,212,729

Greenwood Dismantlement Opinion of Probable Cost: \$11,063,645

^{*}Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances = \$7,442,632


)	Task Name	Cost
1	Greenwood Dismantlement	\$7,442,635.44
2	Pre-Demolition Activities	\$892,760.32
3	Detailed Planning & Hire Owner's Engineer	\$104,441.28
4	Detailed Site Characterization Study	\$610,335.44
5	Hire Demolition general Contractor	\$167,184.00
6	KCP&L Prepares Unit for Dismantlement	\$10,799.60
7	Demolition Contractor Mobilizes on Site	\$0.00
8	KCP&L Overhead during Dismantlement	\$1,477,766.48
9	KCP&L Project Manager	\$234,828.40
10	KCP&L Administrative Support	\$86,836.48
11	KCP&L Engineer	\$385,973.60
12	Owners Engineer Project Manager	\$115,216.00
13	Owners Engineer - Engineer	\$654,912.00
14	Demolition Contractor Overhead during Dismantlement	\$805,541.76
15	Demolition Contractor Project Manager	\$227,915.44
16	Demolition Contractor Safety Manager	\$202,931.76
17	Demolition Contractor Superintendent	\$374,694.56
18	Demolition Contractor Equipment Rental Cost	\$1,371,616.16
19	Equipment Rental	\$1,371,616.16
20	Demolition Contractor Consumables	\$1,368,432.56
21	Consumables	\$1,368,432.56
22	Scrap Crews	\$360,262.24
23	Crew to Handle Scrap Material(s)	\$360,262.24
24	Dismantlement	\$1,117,115.92
25	Electrical	\$197,049.60
26	Electrical Demolition of Equipment	\$197,049.60
27	Fuel Gas System	\$17,932.24
28	Remove all above grade fuel gas piping.	\$3,601.36
29	Gas Filter Skid	\$14,330.88
30	Fueil Oil System	\$17,913.60
31	Remove above grade fuel oil piping	\$12,539.52
32	Remove fuel oil forwarding equipment	\$5,374.08
33	Remove fuel oil forwarding building	\$0.00
34	Demineralizer	\$17,913.60
35	Remove demineralizer vessels	\$3,582.72
36	Remove acid and caustic tanks	\$7,165.44
37	Remove hot water tank	\$3,582.72
38	Remove misc. demineralizer piping.	\$3,582.72
39	Lube Oil System	\$53,740.80
40	Lube Oil Piping	\$14,330.88
41	Lube Oil Pumps	\$17,913.60
42	Lube Oil Tanks	\$21,496.32
43	Compressed Air System	\$21,496.32
44	Compressed Air Piping	\$10,748.16

)	Task Name	Cost
45	Compressors	\$5,374.08
46	Air Receiver	\$3,582.72
47	Dryer	\$1,791.36
48	Fire Protection	\$26,870.40
49	Fire Protection Piping	\$19,704.96
50	CO2 Storage Tank	\$7,165.44
51	Wash Water Skid	\$10,748.16
52	Detergent Tank	\$10,748.16
53	Miscellaneous Piping	\$62,697.60
54	Exhaust Frame Cooling Piping	\$17,913.60
55	CT Air Processing Piping	\$21,496.32
56	Inlet Air Heating Piping	\$23,287.68
57	Generator	\$51,949.44
58	Generators	\$51,949.44
59	Combustion Turbine	\$263,329.92
60	Inlet Heaters	\$17,913.60
61	Inlet ducts	\$26,870.40
62	Exhaust ducts	\$35,827.20
63	Combustion Turbines	\$62,697.60
64	Combustion Turbine Foundations	\$66,280.32
65	Enclosures	\$53,740.80
66	Diesel Generator	\$3,582.72
67	Remove diesel generator	\$3,582.72
68	CEMS	\$42,992.64
69	CEMS Building	\$21,496.32
70	CEMS Building Foundation	\$21,496.32
71	Stack	\$80,611.20
72	Stacks	\$80,611.20
73	Buildings	\$23,287.68
74	Remove Administration/Maintenance Building	\$17,913.60
75	Remove CT Buildings including gantry crane	\$5,374.08
76	Site Prep	\$225,000.00
77	Final Grading and Drainage	\$225,000.00
78	Post Dismantlement Activities	\$49,140.00
79	Post Dismantlement Activities	\$49,140.00



)	Task Name	Duration		2014	2015	
			Qtr 2 Qtr 3 Qtr 4	Qtr 1 Qtr 2 Qtr 3	Qtr 4 Qtr 1 Qtr	2 Qtr 3 Qti
33	Remove fuel oil forwarding building	3 days			h	
34	Demineralizer	10 days				
35	Remove demineralizer vessels	2 days			1	
36	Remove acid and caustic tanks	4 days			L	
37	Remove hot water tank	2 days			<u>K</u>	
38	Remove misc. demineralizer piping.	2 days			I	
39	Lube Oil System	30 days				
40	Lube Oil Piping	8 days			1	
41	Lube Oil Pumps	10 days				
42	Lube Oil Tanks	12 days			7	
43	Compressed Air System	12 days				
44	Compressed Air Piping	6 days				
45	Compressors	3 days			1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
46	Air Receiver	2 days				
47	Dryer	1 day			I	
48	Fire Protection	15 days			••	
49	Fire Protection Piping	11 days				
50	CO2 Storage Tank	4 days			*	
51	Wash Water Skid	6 days				
52	Detergent Tank	6 days			•	
53	Miscellaneous Piping	35 days			—	
54	Exhaust Frame Cooling Piping	10 days				
55	CT Air Processing Piping	12 days				
56	Inlet Air Heating Piping	13 days			*	
57	Generator	29 days				
58	Generators	29 days			=	
59	Combustion Turbine	147 days			—	J
60	Inlet Heaters	10 days				
61	Inlet ducts	15 days)
62	Exhaust ducts	20 days				5
63	Combustion Turbines	35 days				
64	Combustion Turbine Foundations	37 days				

D	Task Name	Duration				2014				2015				2016	
			Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2
65	Enclosures	30 days										ĺ			
66	Diesel Generator	2 days													
67	Remove diesel generator	2 days											5		
68	CEMS	24 days											-	ካ	
69	CEMS Building	12 days													
70	CEMS Building Foundation	12 days													
71	Stack	45 days											•		
72	Stacks	45 days													
73	Buildings	13 days													
74	Remove Administration/Maintenance Building	10 days													
75	Remove CT Buildings including gantry crane	3 days													
76	Site Prep	20 days													
77	Final Grading and Drainage	20 days													
78	Post Dismantlement Activities	30 days												-	➡
79	Post Dismantlement Activities	30 days													



CROSSROADS STATION

The Crossroads Generating Station consists of four natural gas-fired combustion turbine generator sets.

Combined, these combustion turbines have an SPP-accredited unit rating of 276.8 MW. Crossroads was placed into service in 2002. Each unit is comprised of a GE Model MS7001EA combustion turbine with a generator step-up transformer and auxiliary power transformer.

The following are the major systems and equipment that were included in the retirement and dismantlement of the Crossroads Generating Station.

- 1. Combustion turbine generator sets and auxiliaries.
- 2. Generation step-up and auxiliary transformers.
- 3. Outdoor switchgear.
- 4. Exhaust stacks.
- 5. Maintenance building.
- 6. Natural gas filtering skid.
- 7. Service/Instrument air compressors.

Crossroads Retirement

Owner Costs

Pre-Retirement Activities \$43,834
Retirement Activities \$215,997
Post-Retirement Activities \$45,162

Owner Direct Total \$304,993

Owner Internal Costs 5.00% \$15,250

Owner Contingency: 25.00% \$80,061

Crossroads Retirement Opinion of Probable Cost:

\$400,303.31

-	Task Name	Cost
1	Crossroads Retirement	\$304,983.84
2	Pre-Retirement Activities	\$43,834.00
3	Permitting Review	\$23,466.00
4	Develop Detailed Retirement Plan	\$20,368.00
5	Retirement	\$215,997.84
6	Project Management During Retirement	\$99,450.48
7	Project Management During Retirement	\$99,450.48
8	Retirement Activities	\$116,547.36
9	Electrical	\$44,664.00
10	Medium and Low Voltage Drawout Switchgear	\$12,505.92
11	De-energize all buses at the source.	\$2,679.84
12	Open all circuit breakers.	\$2,679.84
13	Rack all circuit breakers into the fully withdrawn,	\$2,679.84
	disconnected position.	
14	Verify that the closing/tripping springs are discharged.	\$2,679.84
15	De-energize control power and auxiliary power circuits of	\$1,786.56
	each circuit breaker at the source and by opening control	
	power circuit breakers or removing fuses in each breaker	
	cubicle.	
16	Motor Control Centers	\$6,252.96
17	De-energize all buses at the source.	\$893.28
18	Open all circuit breakers and disconnect switches.	\$2,679.84
19	Remove all fuses in control circuits.	\$2,679.84
20	Low-voltage Switchboards and Panelboards	\$5,359.68
21	De-energize all buses at the source.	\$2,679.84
22	Open all circuit breakers and disconnect switches.	\$2,679.84
23	Oil-Filled Power Transformers	\$9,826.08
24	De-energize all buses at the source.	\$2,679.84
25	Open all circuit breakers and disconnect switches.	\$1,786.56
26	De-energize all buses at the source.	\$2,679.84
27	Open all circuit breakers and disconnect switches.	\$2,679.84
28	Dry-type Power Transformers	\$4,466.40
29	De-energize all transformer primaries and verify that the	\$2,679.84
	secondary is de-energized.	
30	De-energize all low-voltage AC or DC power sources for	\$1,786.56
	space heaters, cooling equipment, controls, etc. at the	
	source and open circuit breakers or remove fuses at	
	transformer end.	
31	Motors	\$6,252.96
32	De-energize all primary power at the source.	\$1,786.56
33	De-energize all low-voltage power sources for space heaters	\$1,786.56
	or other auxiliary equipment at the source.	
34	Drain lube oil system (if applicable) and dispose of oil.	\$2,679.84
35	Maintenance Building	\$9,342.40

ID	Task Name	Cost
36	Secure the Maintenance Building	\$9,342.40
37	Fuel Gas System	\$10,783.04
38	Isolate Fuel Gas System	\$3,907.44
39	Vent Fuel Gas Piping and Equipment	\$2,528.16
40	Open and Vent Knock-Out Drum	\$861.84
41	Drain, Open and Vent the Drain Tank	\$861.84
42	Empty the Coalescing Filter	\$1,761.92
43	Open and Vent Equipment on the CT Gas Valve Module	\$861.84
44	Lube Oil Cooling Water System	\$7,756.56
45	Open and Drain the Water Side of the Lube Oil Coolers	\$5,171.04
46	Open and Vent the Coolers and Expansion Tank	\$2,585.52
47	Oily Drain Tank	\$3,954.00
48	Open and Pump Out the Oily Drain Tank	\$3,954.00
49	Wash Water Skid	\$5,171.04
50	Open and Drain the Detergent Tank	\$1,723.68
51	Open and Drain the Demineralized Water Tank	\$1,723.68
52	Empty the Demineralized Water Tank	\$1,723.68
53	Compressed Air	\$3,447.36
54	Empty Dessiccant Air Dryers and Vent	\$1,723.68
55	Open and Vent the Air Reciever	\$1,723.68
56	Miscelleaneous Piping	\$10,342.08
57	Open and Vent the Exhaust Frame Cooling Piping	\$3,447.36
58	Open and Vent the CT Air Processing Piping	\$0.00
59	Open and Vent the Inlet Air Heating Piping	\$3,447.36
60	Open and Vent the CT Air Processing Piping	\$3,447.36
61	Fire Protection Piping	\$6,856.48
62	Empty the CO2 Storage Tank	\$5,132.80
63	Open and Vent the Fire Protection Piping	\$1,723.68
64	Lube Oil System	\$11,587.04
65	Empty and Remove from Site the Lubricating Oil	\$6,416.00
66	Drain Lubricating Oil Piping	\$3,447.36
67	Open and Vent Lubricating Oil Piping	\$1,723.68
68	Potable Water	\$2,643.36
69	Disconnect Potable Water at Property Boundary	\$2,643.36
70	Post Retirement Closure Activity	\$45,152.00
71	Post Retirement Closure Activity	\$45,152.00

	Task Name	Duration	2nd Quarter	3rd Quarter	4th Quarter	1st Quarter	2nd Quarter
			Apr May Jun	Jul Aug Sep	Oct Nov Dec	Jan Feb Mar	Apr May Jur
1	Crossroads Retirement	204 days		•			
2	Pre-Retirement Activities	40 days					
3	Permitting Review	20 days			KCP&L Pro	ject Manager[25	5%],KCP&L Engin
4	Develop Detailed Retirement Plan	20 days					
5	Retirement	124 days					
6	Project Management During Retirement	124 days					
7	Project Management During Retirement	124 days					
8	Retirement Activities	124 days					
9	Electrical	50 days					
10	Medium and Low Voltage Drawout Switchg	14 days					
11	De-energize all buses at the source.	3 days			<u> </u>		
12	Open all circuit breakers.	3 days			<u> </u>		
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	3 days					
14	Verify that the closing/tripping springs are discharged.	3 days			*		
15	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each	2 days			ř		
16	Motor Control Centers	7 days			•		
17	De-energize all buses at the source.	1 day			K		
18	Open all circuit breakers and disconnect switches.	3 days			7		
19	Remove all fuses in control circuits.	3 days			5		
20	Low-voltage Switchboards and Panelboards	6 days			—	•	
21	De-energize all buses at the source.	3 days			ř	7	
22	Open all circuit breakers and disconnect switches.	3 days			ì		
23	Oil-Filled Power Transformers	11 days			· ·		
24	De-energize all buses at the source.	3 days				5	
25	Open all circuit breakers and disconnect switches.	2 days				Ť	

)	Task Name	Duration	2nd Quarter	3rd Quarter	4th Quarter	1st Quarter	2nd Quarter	3rd
			Apr May Jun		Oct Nov Dec	Jan Feb Mar	Apr May Jun	Jul
26	De-energize all buses at the source.	3 days				<u>~</u>		
27	Open all circuit breakers and disconnect switches.	3 days						
28	Dry-type Power Transformers	5 days						
29	De-energize all transformer primaries and verify that the secondary is de-energized.	3 days						
30	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses	2 days						
31	Motors	7 days				-		
32	De-energize all primary power at the source.	2 days						
33	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	2 days						
34	Drain lube oil system (if applicable) and dispose of oil.	3 days						
35	Maintenance Building	5 days				-		
36	Secure the Maintenance Building	5 days				*		
37	Fuel Gas System	11 days				-		
38	Isolate Fuel Gas System	3 days				5		
39	Vent Fuel Gas Piping and Equipment	3 days						
40	Open and Vent Knock-Out Drum	1 day				h		
41	Drain, Open and Vent the Drain Tank	1 day				Ь_		
42	Empty the Coalescing Filter	2 days				5		
43	Open and Vent Equipment on the CT Gas Valve Module	1 day				H		
44	Lube Oil Cooling Water System	9 days				-		
45	Open and Drain the Water Side of the Lube Oil Coolers	6 days						
46	Open and Vent the Coolers and Expansion Ta	3 days				*		
47	Oily Drain Tank	3 days						

	Task Name	Duration	2nd Quarter	3rd (Qua	arter		4th	Quart	er	1st C	Quarter	2nd	Quarter	3rd
			Apr May Jun	Jul	Α	ug S	ер	Oct	Nov	Dec	Jan	Feb Mar	Apr	May Jur	Jul
48	Open and Pump Out the Oily Drain Tank	3 days										, in			
49	Wash Water Skid	6 days													
50	Open and Drain the Detergent Tank	2 days										Š			
51	Open and Drain the Demineralized Water Tar	2 days										Ϋ́			
52	Empty the Demineralized Water Tank	2 days										Ķ			
53	Compressed Air	4 days										Ų.			
54	Empty Dessiccant Air Dryers and Vent	2 days													
55	Open and Vent the Air Reciever	2 days										Ì			
56	Miscelleaneous Piping	21 days										•			
57	Open and Vent the Exhaust Frame Cooling Pi	4 days											*		
58	Open and Vent the CT Air Processing Piping	9 days													
59	Open and Vent the Inlet Air Heating Piping	4 days												,]	
60	Open and Vent the CT Air Processing Piping	4 days												ή	
61	Fire Protection Piping	6 days											Ţ		
62	Empty the CO2 Storage Tank	4 days												T	
63	Open and Vent the Fire Protection Piping	2 days												5	
64	Lube Oil System	9 days													
65	Empty and Remove from Site the Lubricating	5 days													
66	Drain Lubricating Oil Piping	4 days												F	
67	Open and Vent Lubricating Oil Piping	2 days												ħ	
68	Potable Water	3 days													
69	Disconnect Potable Water at Property Bound	3 days												*	
70	Post Retirement Closure Activity	40 days												—	-
71	Post Retirement Closure Activity	40 days													

Crossroads Dismantlement

Owner Costs

Pre-Dismantlement Activities \$887,360

Overhead During Dismantlement \$1,551,849

Post-Dismantlement Activities \$49,140

Owner Costs Total* \$2,488,349

Demolition General Contractor (DGC) Costs

 Site Management
 \$845,925

 Equipment Rental
 \$1,440,377

 Consummables
 \$1,437,034

 Scrap Crew(s)
 \$378,322

 Dismantlement
 \$982,145

Contractor Direct Cost* \$5,083,803

Contractor Allowances

DGC Insurance 2.00% \$101,676

Contingency/Profit 15.00% \$777,822

Performance Bond 2.00% \$119,266.02

Contractor Costs Total: \$6,082,567

Total: \$8,570,916

Owner Internal Costs: 5.00% \$428,546


Owner Contingency: 25.00% \$2,249,865

Crossroads Dismantlement Opinion of Probable Cost: \$11,249,327

^{*}Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances = \$7,572,152

D	Task Name	Cost
1	Crossroads Dismantlement	\$7,572,156.16
2	Pre-Demolition Activities	\$887,360.52
3	Detailed Planning & Hire Owner's Engineer	\$104,441.28
4	Detailed Site Characterization Study	\$610,335.44
5	Hire Demolition general Contractor	\$167,184.00
6	KCP&L Prepares Unit for Dismantlement	\$5,399.80
7	Demolition Contractor Mobilizes on Site	\$0.00
8	KCP&L Overhead during Dismantlement	\$1,551,849.76
9	KCP&L Project Manager	\$246,600.80
10	KCP&L Administrative Support	\$91,189.76
11	KCP&L Engineer	\$405,323.20
12	Owners Engineer Project Manager	\$120,992.00
13	Owners Engineer - Engineer	\$687,744.00
14	Demolition Contractor Overhead during Dismantlement	\$845,925.12
15	Demolition Contractor Project Manager	\$239,341.28
16	Demolition Contractor Safety Manager	\$213,105.12
17	Demolition Contractor Superintendent	\$393,478.72
18	Demolition Contractor Equipment Rental Cost	\$1,440,377.92
19	Equipment Rental	\$1,440,377.92
20	Demolition Contractor Consumables	\$1,437,034.72
21	Consumables	\$1,437,034.72
22	Scrap Crews	\$378,322.88
23	Crew to Handle Scrap Material(s)	\$378,322.88
24	Dismantlement	\$982,145.24
25	Electrical	\$197,049.60
26	Electrical Demolition of Equipment	\$197,049.60
27	Fuel Gas System	\$21,113.20
28	Remove all above grade fuel gas piping.	\$6,782.32
29	Gas Filter Skid	\$14,330.88
30	Lube Oil System	\$53,740.80
31	Lube Oil Piping	\$14,330.88
32	Lube Oil Pumps	\$17,913.60
33	Lube Oil Tanks	\$21,496.32
34	Compressed Air System	\$21,496.32
35	Compressed Air Piping	\$10,748.16
36	Compressors	\$5,374.08
37	Air Receiver	\$3,582.72
38	Dryer	\$1,791.36
39	Fire Protection	\$26,870.40
40	Fire Protection Piping	\$19,704.96
41	CO2 Storage Tank	\$7,165.44
42	Wash Water Skid	\$10,748.16
43	Detergent Tank	\$10,748.16
44	Miscellaneous Piping	\$62,697.60

)	Task Name	Cost
45	Exhaust Frame Cooling Piping	\$17,913.60
46	CT Air Processing Piping	\$21,496.32
47	Inlet Air Heating Piping	\$23,287.68
48	Generator	\$0.00
49	Generators	\$0.00
50	Combustion Turbine	\$263,329.92
51	Inlet Heaters	\$17,913.60
52	Inlet ducts	\$26,870.40
53	Exhaust ducts	\$35,827.20
54	Combustion Turbines	\$62,697.60
55	Combustion Turbine Foundations	\$66,280.32
56	Enclosures	\$53,740.80
57	CEMS	\$42,992.64
58	CEMS Building	\$21,496.32
59	CEMS Building Foundation	\$21,496.32
60	Stack	\$80,611.20
61	Stacks	\$80,611.20
62	Buildings	\$17,913.60
63	Remove Maintenance Building	\$17,913.60
64	Waste Water Tank	\$8,956.80
65	Remove Waste Water Tank	\$8,956.80
66	Site Prep	\$174,625.00
67	Final Grading and Drainage	\$174,625.00
68	Post Dismantlement Activities	\$49,140.00
69	Post Dismantlement Activities	\$49,140.00



)	Task Name	Duration		2014	2015		2
22	Luka Oil Tardia	42.1.	Qtr 2 Qtr 3 Qtr 4	Qtr 1 Qtr 2 Qtr 3 Qtr 4	Qtr 1 Qtr 2 Qtr	3 Qtr 4	C
33	Lube Oil Tanks	12 days		<u>"</u>			
34	Compressed Air System	12 days					
35	Compressed Air Piping	6 days					
36	Compressors	3 days			5		
37	Air Receiver	2 days			5		
38	Dryer	1 day			I		
39	Fire Protection	15 days					
40	Fire Protection Piping	11 days			-		
41	CO2 Storage Tank	4 days					
42	Wash Water Skid	6 days					
43	Detergent Tank	6 days					
44	Miscellaneous Piping	35 days					
45	Exhaust Frame Cooling Piping	10 days					
46	CT Air Processing Piping	12 days					
47	Inlet Air Heating Piping	13 days					
48	Generator	29 days					
49	Generators	29 days					
50	Combustion Turbine	147 days			<u> </u>		
51	Inlet Heaters	10 days					
52	Inlet ducts	15 days					
53	Exhaust ducts	20 days			*		
54	Combustion Turbines	35 days					
55	Combustion Turbine Foundations	37 days					
56	Enclosures	30 days					
57	CEMS	24 days				-	ካ
58	CEMS Building	12 days					
59	CEMS Building Foundation	12 days				*	
60	Stack	45 days					+
61	Stacks	45 days					+
62	Buildings	10 days					
63	Remove Maintenance Building	10 days					
64	Waste Water Tank	5 days					

Crossr	oads Dismantlement														
ID	Task Name	Duration				2014				2015				2016	
			Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2
65	Remove Waste Water Tank	5 days												, j	
66	Site Prep	20 days													▼
67	Final Grading and Drainage	20 days													ή ·
68	Post Dismantlement Activities	30 days												(
69	Post Dismantlement Activities	30 days													



KCI STATION

The KCI Generating Station consists of two natural gas-fired combustion turbine generator sets.

Combined, these combustion turbines have an SPP-accredited unit rating of 0 MW. KCI was placed into service in 1971. Each unit is comprised of a Pratt & Whitney GG4A-7 combustion turbine with a generator step-up transformer and auxiliary power transformer.

The following are the major systems and equipment that were included in the retirement and dismantlement of the KCI Generating Station.

- 1. Combustion turbine generator sets and auxiliaries.
- 2. Generation step-up and auxiliary transformers.
- 3. Outdoor switchgear.
- 4. Exhaust stacks.
- 5. Control Room/Maintenance building.
- 6. Gas compressor building and equipment.
- 7. Black-start generator.
- 8. Service/Instrument air compressors.
- 9. Glycol cooling towers.
- 10. Fire protection systems.

KCI Retirement

Owner Costs

Pre-Retirement Activities \$43,834
Retirement Activities \$112,691
Post-Retirement Activities \$16,932

Owner Direct Total \$173,457

Owner Internal Costs 5.00% \$8,673

Owner Contingency: 25.00% \$45,532

KCI Retirement Opinion of Probable Cost: \$227,662.31

)	Task Name	Cost
1	KCI Retirement	\$173,457.84
2	Pre-Retirement Activities	\$43,834.00
3	Permitting Review	\$23,466.00
4	Develop Detailed Retirement Plan	\$20,368.00
5	Retirement	\$112,691.84
6	Project Management During Retirement	\$48,121.20
7	Project Management During Retirement	\$48,121.20
8	Retirement Activities	\$64,570.64
9	Electrical	\$19,652.16
10	Medium and Low Voltage Drawout Switchgear	\$5,359.68
11	De-energize all buses at the source.	\$893.28
12	Open all circuit breakers.	\$1,786.56
13	Rack all circuit breakers into the fully withdrawn,	\$893.28
	disconnected position.	
14	Verify that the closing/tripping springs are discharged.	\$893.28
15	De-energize control power and auxiliary power circuits of	\$893.28
	each circuit breaker at the source and by opening control	
	power circuit breakers or removing fuses in each breaker	
	cubicle.	
16	Motor Control Centers	\$2,679.84
17	De-energize all buses at the source.	\$893.28
18	Open all circuit breakers and disconnect switches.	\$893.28
19	Remove all fuses in control circuits.	\$893.28
20	Low-voltage Switchboards and Panelboards	\$1,786.56
21	De-energize all buses at the source.	\$893.28
22	Open all circuit breakers and disconnect switches.	\$893.28
23	Oil-Filled Power Transformers	\$4,466.40
24	De-energize all buses at the source.	\$893.28
25	Open all circuit breakers and disconnect switches.	\$1,786.56
26	De-energize all buses at the source.	\$893.28
27	Open all circuit breakers and disconnect switches.	\$893.28
28	Dry-type Power Transformers	\$1,786.56
29	De-energize all transformer primaries and verify that the	\$893.28
	secondary is de-energized.	
30	De-energize all low-voltage AC or DC power sources for	\$893.28
	space heaters, cooling equipment, controls, etc. at the	
	source and open circuit breakers or remove fuses at	
	transformer end.	
31	Motors	\$3,573.12
32	De-energize all primary power at the source.	\$893.28
33	De-energize all low-voltage power sources for space heaters	\$893.28
	or other auxiliary equipment at the source.	
34	Drain lube oil system (if applicable) and dispose of oil.	\$1,786.56
35	Enclosure Building	\$3,736.96

D	Task Name	Cost
36	Secure the Enclosure Building	\$3,736.96
37	Gas Compressor Building	\$1,868.48
38	Secure the Gas Compressor Building	\$1,868.48
39	Shop Building	\$3,736.96
40	Secure the Shop Building	\$3,736.96
41	Cooling Towers	\$5,209.92
42	Drain Cooling Tower	\$3,907.44
43	Drain Cooling Tower Chemical Storage Tanks	\$1,302.48
44	Fuel Gas System	\$5,612.00
45	Isolate Fuel Gas System	\$3,907.44
46	Vent Fuel Gas Piping and Equipment	\$842.72
47	Open and Vent Equipment on the CT Gas Valve Module	\$861.84
48	Lube Oil Cooling Water System	\$2,585.52
49	Open and Drain the Glycol Side of the Lube Oil Coolers	\$1,723.68
50	Open and Vent the Coolers and Expansion Tank	\$861.84
51	Sump	\$3,954.00
52	Open and Pump Out the Sump	\$3,954.00
53	Miscelleaneous Piping	\$2,585.52
54	Open and Vent Miscellaneous Piping	\$2,585.52
55	Fire Protection Piping	\$3,428.24
56	Empty the CO2 Storage Tank	\$2,566.40
57	Open and Vent the Fire Protection Piping	\$861.84
58	Lube Oil System	\$5,151.92
59	Empty and Remove from Site the Lubricating Oil	\$2,566.40
60	Drain Lubricating Oil Piping	\$1,723.68
61	Open and Vent Lubricating Oil Piping	\$861.84
62	Service Piping	\$5,286.72
63	Disconnect Potable Water at Property Boundary	\$2,643.36
64	Disconnect Compressed Air at Property Boundary	\$2,643.36
65	Black Start Engine	\$1,762.24
66	Vent Fuel Gas Piping to Black Start Enginer	\$881.12
67	Post Retirement Closure Activity	\$16,932.00
68	Post Retirement Closure Activity	\$16,932.00

D	Task Name	Duration	2nd Quarter	3rd Quarter	4th Quarter	1st Quarter	
			Apr May Jun	Jul Aug Sep	Oct Nov Dec	Jan Feb	Ma
1	KCI Retirement	115 days			—		—
2	Pre-Retirement Activities	40 days					
3	Permitting Review	20 days			KCP&L Projec	t Manager[25%]],K¢P
4	Develop Detailed Retirement Plan	20 days					
5	Retirement	60 days					
6	Project Management During Retirement	60 days					
7	Project Management During Retirement	60 days					
8	Retirement Activities	60 days					
9	Electrical	22 days				•	
10	Medium and Low Voltage Drawout Switchg	6 days			•		
11	De-energize all buses at the source.	1 day			ή		
12	Open all circuit breakers.	2 days			K		
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	1 day					
14	Verify that the closing/tripping springs are discharged.	1 day			*		
15	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each	1 day			†		
16	Motor Control Centers	3 days			•		
17	De-energize all buses at the source.	1 day			<u> </u>		
18	Open all circuit breakers and disconnect switches.	1 day			5		
19	Remove all fuses in control circuits.	1 day			, in the second		
20	Low-voltage Switchboards and Panelboards	2 days			•		
21	De-energize all buses at the source.	1 day			†		
22	Open all circuit breakers and disconnect switches.	1 day			7		
23	Oil-Filled Power Transformers	5 days					
24	De-energize all buses at the source.	1 day			r i		
25	Open all circuit breakers and disconnect switches.	2 days					

D	Task Name	Duration	2nd Qu	ıarter		3rd Qı	uarter		4th Qι	ıarter		1st Qı	uarter	
			Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Ma
26	De-energize all buses at the source.	1 day									5			
27	Open all circuit breakers and disconnect switches.	1 day									ľ			
28	Dry-type Power Transformers	2 days												
29	De-energize all transformer primaries and verify that the secondary is de-energized.	1 day									Image: Control of the control of the			
30	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses	1 day												
31	Motors	4 days									-	į		
32	De-energize all primary power at the source.	1 day									Š			
33	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	1 day									7			
34	Drain lube oil system (if applicable) and dispose of oil.	2 days									F			
35	Enclosure Building	2 days									W			
36	Secure the Enclosure Building	2 days										/		
37	Gas Compressor Building	1 day									Ţ	•		
38	Secure the Gas Compressor Building	1 day									`	ሻ		
39	Shop Building	2 days									Ţ			
40	Secure the Shop Building	2 days										h		
41	Cooling Towers	4 days										*		
42	Drain Cooling Tower	3 days												
43	Drain Cooling Tower Chemical Storage Tanks	1 day										ή		
44	Fuel Gas System	5 days												
45	Isolate Fuel Gas System	3 days										5		
46	Vent Fuel Gas Piping and Equipment	1 day										h		
47	Open and Vent Equipment on the CT Gas Valve Module	1 day												
48	Lube Oil Cooling Water System	3 days												

	Task Name	Duration	2nd Qı	uartor		2rd O	uarter		4th Qu	artor		1st Quarter	
,	lask Name	Duration	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan Feb	Ma
49	Open and Drain the Glycol Side of the Lube Oil Coolers	2 days		, , , ,			1	, , , ,				h	
50	Open and Vent the Coolers and Expansion Ta	1 day										ř.	
51	Sump	3 days											
52	Open and Pump Out the Sump	3 days										T	
53	Miscelleaneous Piping	3 days										-	
54	Open and Vent Miscellaneous Piping	3 days										*	
55	Fire Protection Piping	3 days											
56	Empty the CO2 Storage Tank	2 days										Š	
57	Open and Vent the Fire Protection Piping	1 day										Ϋ́	
58	Lube Oil System	5 days										-	
59	Empty and Remove from Site the Lubricating	2 days											
60	Drain Lubricating Oil Piping	2 days										\(\right\)	
61	Open and Vent Lubricating Oil Piping	1 day										Ϋ́	
62	Service Piping	6 days										-	
63	Disconnect Potable Water at Property Bound	3 days											
64	Disconnect Compressed Air at Property Boun	3 days										5	
65	Black Start Engine	1 day										•	
66	Vent Fuel Gas Piping to Black Start Enginer	1 day										Ť,	
67	Post Retirement Closure Activity	15 days											—
68	Post Retirement Closure Activity	15 days										¥	

KCI Dismantlement

Owner Costs

Pre-Dismantlement Activities \$473,576

Overhead During Dismantlement \$279,378

Post-Dismantlement Activities \$32,760

Owner Costs Total* \$785,714

Demolition General Contractor (DGC) Costs

 Site Management
 \$176,411

 Equipment Rental
 \$300,380

 Consummables
 \$299,683

 Scrap Crew(s)
 \$78,896

 Dismantlement
 \$263,996

Contractor Direct Cost* \$1,119,366

Contractor Allowances

DGC Insurance 2.00% \$22,387

Contingency/Profit 15.00% \$171,263

Performance Bond 2.00% \$26,260.33

Contractor Costs Total: \$1,339,277

Total: \$2,124,991

Owner Internal Costs: 5.00% \$106,250

Owner Contingency: 25.00% \$557,810

KCI Dismantlement Opinion of Probable Cost: \$2,789,050

^{*}Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances = \$1,905,080

D	Task Name	Cost
1	KCI Dismantlement	\$1,905,082.52
2	Pre-Demolition Activities	\$473,576.40
3	Detailed Planning & Hire Owner's Engineer	\$69,627.52
4	Detailed Site Characterization Study	\$281,693.28
5	Hire Demolition general Contractor	\$111,456.00
6	KCP&L Prepares Unit for Dismantlement	\$10,799.60
7	Demolition Contractor Mobilizes on Site	\$0.00
8	KCP&L Overhead during Dismantlement	\$279,378.00
9	KCP&L Project Manager	\$51,426.80
10	KCP&L Engineer	\$84,527.20
11	Owners Engineer - Engineer	\$143,424.00
12	Demolition Contractor Overhead during Dismantlement	\$176,411.52
13	Demolition Contractor Project Manager	\$49,912.88
14	Demolition Contractor Safety Manager	\$44,441.52
15	Demolition Contractor Superintendent	\$82,057.12
16	Demolition Contractor Equipment Rental Cost	\$300,380.32
17	Equipment Rental	\$300,380.32
18	Demolition Contractor Consumables	\$299,683.12
19	Consumables	\$299,683.12
20	Scrap Crews	\$78,896.48
21	Crew to Handle Scrap Material(s)	\$78,896.48
22	Dismantlement	\$263,996.68
23	Electrical	\$53,740.80
24	Electrical Demolition of Equipment	\$53,740.80
25	Shop Building	\$7,165.44
26	Remove the Shop Building	\$7,165.44
27	Fuel Gas System	\$10,437.52
28	Remove all above grade fuel gas piping.	\$1,480.72
29	Remove Gas Compressor Equipment	\$5,374.08
30	Remove Gas Compressor Building	\$3,582.72
31	Lube Oil System	\$10,748.16
32	Lube Oil Piping	\$1,791.36
33	Lube Oil Pumps	\$3,582.72
34	Lube Oil Tanks	\$5,374.08
35	Compressed Air System	\$1,791.36
36	Remove Above Ground Compressed Air Piping	\$1,791.36
37	Fire Protection	\$10,748.16
38	Fire Protection Piping	\$3,582.72
39	CO2 Storage Tank	\$7,165.44
40	Miscellaneous Piping	\$10,748.16
41	Remove Miscellaneous Piping	\$8,956.80
42	Remove Above Ground Service Water Piping	\$1,791.36
43	Generator	\$17,913.60
44	Generators	\$17,913.60

KCI Dismantlement

ID	Task Name	Cost
45	Combustion Turbine	\$62,697.60
46	Inlet ducts	\$7,165.44
47	Exhaust ducts	\$7,165.44
48	Combustion Turbines	\$17,913.60
49	Combustion Turbine Foundation	\$21,496.32
50	Combustion Turbine Enclosure Building	\$8,956.80
51	Cooling Towers	\$10,748.16
52	Remove Cooling Towers	\$10,748.16
53	Stack	\$3,582.72
54	Stacks	\$3,582.72
55	Site Prep	\$63,675.00
56	Final Grading and Drainage	\$63,675.00
57	Post Dismantlement Activities	\$32,760.00
58	Post Dismantlement Activities	\$32,760.00

	Task Name	Duration		2013				2014				2015	
			Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	_
1	KCI Dismantlement	633 days											i
2	Pre-Demolition Activities	155 days	_	—									
3	Detailed Planning & Hire Owner's Engineer	2 mons											
4	Detailed Site Characterization Study	60 days											
5	Hire Demolition general Contractor	2 mons											
6	KCP&L Prepares Unit for Dismantlement	2 wks											
7	Demolition Contractor Mobilizes on Site	5 days				5							
8	KCP&L Overhead during Dismantlement	83 days											
9	KCP&L Project Manager	83 days											
10	KCP&L Engineer	83 days											
11	Owners Engineer - Engineer	83 days											
12	Demolition Contractor Overhead during Dismantle	emer 83 days											
13	Demolition Contractor Project Manager	83 days											
14	Demolition Contractor Safety Manager	83 days											
15	Demolition Contractor Superintendent	83 days											
16	Demolition Contractor Equipment Rental Cost	83 days											
17	Equipment Rental	83 days											
18	Demolition Contractor Consumables	83 days											
19	Consumables	83 days											
20	Scrap Crews	83 days											
21	Crew to Handle Scrap Material(s)	83 days											
22	Dismantlement	83 days											
23	Electrical	30 days					ı						
24	Electrical Demolition of Equipment	30 days											
25	Shop Building	4 days											
26	Remove the Shop Building	4 days				H .							
27	Fuel Gas System	7 days				•							
28	Remove all above grade fuel gas piping.	2 days				Ĭ,							
29	Remove Gas Compressor Equipment	3 days				K							
30	Remove Gas Compressor Building	2 days				K							
31	Lube Oil System	6 days											
32	Lube Oil Piping	1 day				K							

	Task Name	Duration		201					2014				2015	
			Qtr 4	Qtr	1 Qt	r 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	С
3	Lube Oil Pumps	2 days					5							
34	Lube Oil Tanks	3 days					١							
35	Compressed Air System	1 day												
36	Remove Above Ground Compressed Air Piping	1 day					Ь							
37	Fire Protection	6 days					<u> </u>							
38	Fire Protection Piping	2 days					<u> 1</u>							
39	CO2 Storage Tank	4 days												
40	Miscellaneous Piping	6 days					-							
41	Remove Miscellaneous Piping	5 days					F	,						
42	Remove Above Ground Service Water Piping	1 day					F							
43	Generator	10 days												
44	Generators	10 days						ή						
45	Combustion Turbine	35 days												
46	Inlet ducts	4 days						\mathcal{K}						
47	Exhaust ducts	4 days						Ϋ́						
48	Combustion Turbines	10 days						4						
49	Combustion Turbine Foundation	12 days												
50	Combustion Turbine Enclosure Building	5 days						Š						
51	Cooling Towers	6 days						•						
52	Remove Cooling Towers	6 days						Š						
53	Stack	2 days												
54	Stacks	2 days						Τ̈́						
55	Site Prep	1 day												
56	Final Grading and Drainage	1 day					Ĭ							
57	Post Dismantlement Activities	20 days						-						
58	Post Dismantlement Activities	20 days												

NEVADA UNIT 1

NEVADA STATION

The Nevada Generating Station consists of a single distillate-fired combustion turbine generator set.

Nevada has an SPP-accredited unit rating of 20.8 MW. Nevada was placed into service in 1974. The unit is comprised of a GE Model MS5001P combustion turbine with a generator step-up transformer and auxiliary power transformer.

The following are the major systems and equipment that were included in the retirement and dismantlement of the Nevada Generating Station.

- 1. Combustion turbine generator sets and auxiliaries.
- 2. Generation step-up and auxiliary transformers.
- 3. Outdoor switchgear.
- 4. Exhaust stacks.
- 5. Maintenance building.
- 6. Fuel oil transfer equipment.
- 7. Service/Instrument air compressors.
- 8. Fuel oil storage.

Nevada Retirement

Owner Costs

Pre-Retirement Activities \$43,834
Retirement Activities \$125,254
Post-Retirement Activities \$45,152

Owner Direct Total \$214,240

Owner Internal Costs 5.00% \$10,712

Owner Contingency: 25.00% \$56,238

Nevada Retirement Opinion of Probable Cost: \$281,190.00

Activities Required by Permit or Regulation

Nevada Storage Tank \$56,530

Activities Required by Permit or Regulation: \$56,530

	Task Name	Cost
1	Nevada Retirement	\$214,240.42
2	Pre-Retirement Activities	\$43,834.00
3	Permitting Review	\$23,466.00
4	Develop Detailed Retirement Plan	\$20,368.00
5	Retirement	\$125,254.42
6	Project Management During Retirement	\$55,339.38
7	Project Management During Retirement	\$55,339.38
8	Retirement Activities	\$69,915.04
9	Electrical	\$27,691.68
10	Medium and Low Voltage Drawout Switchgear	\$5,359.68
11	De-energize all buses at the source.	\$893.28
12	Open all circuit breakers.	\$893.28
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	\$893.28
14	Verify that the closing/tripping springs are discharged.	\$1,786.56
15	De-energize control power and auxiliary power circuits of each	\$893.28
	circuit breaker at the source and by opening control power	•
	circuit breakers or removing fuses in each breaker cubicle.	
16	Motor Control Centers	\$2,679.84
17	De-energize all buses at the source.	\$893.28
18	Open all circuit breakers and disconnect switches.	\$893.28
19	Remove all fuses in control circuits.	\$893.28
20	Low-voltage Switchboards and Panelboards	\$1,786.56
21	De-energize all buses at the source.	\$893.28
22	Open all circuit breakers and disconnect switches.	\$893.28
23	Oil-Filled Power Transformers	\$7,146.24
24	De-energize all buses at the source.	\$893.28
25	Open all circuit breakers and disconnect switches.	\$893.28
26	De-energize all buses at the source.	\$893.28
27	Open all circuit breakers and disconnect switches.	\$4,466.40
28	Dry-type Power Transformers	\$4,466.40
29	De-energize all transformer primaries and verify that the	\$893.28
	secondary is de-energized.	
30	De-energize all low-voltage AC or DC power sources for space	\$3,573.12
	heaters, cooling equipment, controls, etc. at the source and	. ,
	open circuit breakers or remove fuses at transformer end.	
31	Motors	\$6,252.96
32	De-energize all primary power at the source.	\$893.28
33	De-energize all low-voltage power sources for space heaters or	\$893.28
	other auxiliary equipment at the source.	, =====
34	Drain lube oil system (if applicable) and dispose of oil.	\$4,466.40
35	Maintenance Building	\$3,736.96
36	Secure the Maintenance Building	\$3,736.96
37	Fuel Oil System	\$5,631.12

)	Task Name	Cost
38	Isolate Fuel Oil System	\$3,907.44
39	Drain and Vent Fuel Oil Piping	\$1,723.68
40	Lube Oil Cooling Water System	\$2,585.52
41	Open and Drain the Water Side of the Lube Oil Coolers	\$1,723.68
42	Open and Vent the Coolers and Expansion Tank	\$861.84
43	Oily Drain Tank	\$3,954.00
44	Open and Pump Out the Oily Drain Tank	\$3,954.00
45	Compressed Air	\$2,585.52
46	Empty Dessiccant Air Dryers and Vent	\$861.84
47	Open and Vent the Air Reciever	\$1,723.68
48	Miscelleaneous Piping	\$5,171.04
49	Open and Vent the Exhaust Frame Cooling Piping	\$861.84
50	Open and Vent the Inlet Air Heating Piping	\$861.84
51	Open & Vent the CT Air Process Piping	\$861.84
52	Open and Vent the CT Air Processing Piping	\$2,585.52
53	Fire Protection Piping	\$3,428.24
54	Empty the CO2 Storage Tank	\$2,566.40
55	Open and Vent the Fire Protection Piping	\$861.84
56	Lube Oil System	\$8,580.16
57	Empty and Remove from Site the Lubricating Oil	\$5,132.80
58	Drain Lubricating Oil Piping	\$1,723.68
59	Open and Vent Lubricating Oil Piping	\$1,723.68
60	Potable Water	\$2,643.36
61	Disconnect Potable Water at Property Boundary	\$2,643.36
62	Waste Water	\$3,907.44
63	Disconnect Waste Water at Property Boundary	\$3,907.44
64	Post Retirement Closure Activity	\$45,152.00
65	Post Retirement Closure Activity	\$45,152.00

)	Task Name	Duration		4th Quart	er			15	t Quart	er			2nd Quar
			Sep	Oct		Nov	Dec		Jan		Feb	Mar	Apr
1	Nevada Retirement	149 days											
2	Pre-Retirement Activities	40 days											
3	Permitting Review	20 days			KC	P&L Proje	ct Manag	er[25	%],KCP	&L Er	ngineer[200%]	
4	Develop Detailed Retirement Plan	20 days											
5	Retirement	69 days											
6	Project Management During Retirement	69 days											
7	Project Management During Retirement	69 days				¥				_			
8	Retirement Activities	69 days										_	
9	Electrical	31 days											
10	Medium and Low Voltage Drawout Switchgear	6 days					—						
11	De-energize all buses at the source.	1 day				Š							
12	Open all circuit breakers.	1 day				K	r						
13	Rack all circuit breakers into the fully withdrawn, disconnected	1 day				ř							
14	Verify that the closing/tripping springs are discharged.	2 days											
15	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each	1 day					ř						
16	Motor Control Centers	3 days											
17	De-energize all buses at the source.	-					†						
18	Open all circuit breakers and disconnect switches.	1 day					4						
19	Remove all fuses in control circuits.	1 day					T						
20	Low-voltage Switchboards and Panelboards	2 days					•						
21	De-energize all buses at the source.	1 day					<u> </u>						
22	Open all circuit breakers and disconnect switches.	1 day					<u> </u>						
23	Oil-Filled Power Transformers	8 days											

Page 1

D	Task Name	Duration		4th Quarte	er			1st Quarte	r		2nd Quarte
			Sep	Oct		Nov	Dec	Jan	Feb	Mar	Apr
24	De-energize all buses at the source.	1 day					Ď				
25	Open all circuit breakers and disconnect switches.	1 day									
26	De-energize all buses at the source.	1 day					T_{I}				
27	Open all circuit breakers and disconnect switches.	5 days									
28	Dry-type Power Transformers	5 days					_	V			
29	De-energize all transformer primaries and verify that the secondary is de-energized.	1 day									
30	De-energize all low-voltage AC or DO power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	·									
31	Motors	7 days					ı				
32	De-energize all primary power at the source.	1 day									
33	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	1 day									
34	Drain lube oil system (if applicable) and dispose of oil.	5 days									
35	Maintenance Building	2 days						•			
36	Secure the Maintenance Building	2 days						Š			
37	Fuel Oil System	5 days						-			
38	Isolate Fuel Oil System	3 days						T			
39	Drain and Vent Fuel Oil Piping	2 days						Š			
40	Lube Oil Cooling Water System	3 days						•			
41	Open and Drain the Water Side of the Lube Oil Coolers	2 days									
42	Open and Vent the Coolers and Expansion Tank	1 day									

D	Task Name	Duration		4th Quarter	-		1st Quarter			2nd Quarte
		_	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr
43	Oily Drain Tank	3 days					7			
44	Open and Pump Out the Oily Drain Tan	•								
45	Compressed Air	3 days]		
46	Empty Dessiccant Air Dryers and Vent	1 day					5	_		
47	Open and Vent the Air Reciever	2 days								
48	Miscelleaneous Piping	5 days					-			
49	Open and Vent the Exhaust Frame Cooling Piping	1 day								
50	Open and Vent the Inlet Air Heating Piping	1 day						T		
51	Open & Vent the CT Air Process Piping	1 day						Ĭ		
52	Open and Vent the CT Air Processing Piping	3 days								
53	Fire Protection Piping	3 days								
54	Empty the CO2 Storage Tank	2 days								
55	Open and Vent the Fire Protection Pipir	1 day						H		
56	Lube Oil System	8 days								
57	Empty and Remove from Site the Lubricating Oil	4 days								
58	Drain Lubricating Oil Piping	2 days						*		
59	Open and Vent Lubricating Oil Piping	2 days						Š		
60	Potable Water	3 days							ı	
61	Disconnect Potable Water at Property Boundary	3 days						*		
62	Waste Water	3 days						•		
63	Disconnect Waste Water at Property Boundary	3 days								
64	Post Retirement Closure Activity	40 days								
65	Post Retirement Closure Activity	40 days								

Nevada Dismantlement

Owner Costs

Pre-Dismantlement Activities \$892,760

Overhead During Dismantlement \$799,319

Post-Dismantlement Activities \$65,520

Owner Costs Total* \$1,757,599

Demolition General Contractor (DGC) Costs

 Site Management
 \$435,715

 Equipment Rental
 \$741,903

 Consummables
 \$740,181

 Scrap Crew(s)
 \$194,864

 Dismantlement
 \$515,571

Contractor Direct Cost* \$2,628,234

Contractor Allowances

DGC Insurance 2.00% \$52,565

Contingency/Profit 15.00% \$402,120

Performance Bond 2.00% \$61,658.37

Contractor Costs Total: \$3,144,577

Total: \$4,902,176

Owner Internal Costs: 5.00% \$245,109

Owner Contingency: 25.00% \$1,286,821

Nevada Dismantlement Opinion of Probable Cost: \$6,434,106

^{*}Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances = \$4,385,833

	Task Name	Cost
1	Nevada CT Dismantlement	\$4,385,836.20
2	Pre-Demolition Activities	\$892,760.32
3	Detailed Planning & Hire Owner's Engineer	\$104,441.28
4	Detailed Site Characterization Study	\$610,335.44
5	Hire Demolition general Contractor	\$167,184.00
6	KCP&L Prepares Unit for Dismantlement	\$10,799.60
7	Demolition Contractor Mobilizes on Sit	\$0.00
8	KCP&L Overhead during Dismantlement	\$799,319.60
9	KCP&L Project Manager	\$127,018.00
10	KCP&L Administrative Support	\$46,969.60
11	KCP&L Engineer	\$208,772.00
12	Owners Engineer Project Manager	\$62,320.00
13	Owners Engineer - Engineer	\$354,240.00
14	Demolition Contractor Overhead during Dismantlement	\$435,715.20
15	Demolition Contractor Project Manager	\$123,278.80
16	Demolition Contractor Safety Manager	\$109,765.20
17	Demolition Contractor Superintendent	\$202,671.20
18	Demolition Contractor Equipment Rental Cost	\$741,903.20
19	Equipment Rental	\$741,903.20
20	Demolition Contractor Consumables	\$740,181.20
21	Consumables	\$740,181.20
22	Scrap Crews	\$194,864.80
23	Crew to Handle Scrap Material(s)	\$194,864.80
24	Dismantlement	\$515,571.88
25	Electrical	\$107,481.60
26	Electrical Demolition of Equipment	\$107,481.60
27	Fuel Oil System	\$8,445.28
28	Remove Above Ground Fuel Oil Piping	\$3,071.20
29	Fuel Skids	\$5,374.08
30	Lube Oil System	\$17,913.60
31	Lube Oil Piping	\$5,374.08
32	Lube Oil Pumps	\$5,374.08
33	Lube Oil Tanks	\$7,165.44
34	Fire Protection	\$26,870.40
35	Fire Protection Piping	\$10,748.16
36	Firewater Tank	\$8,956.80
37	CO2 Storage Tank	\$7,165.44
38	Miscellaneous Piping	\$25,079.04
39	Exhaust Frame Cooling Piping	\$7,165.44
40	CT Air Processing Piping	\$8,956.80
41	Inlet Air Heating Piping	\$8,956.80
42	Generator	\$10,748.16
43	Generator	\$10,748.16
44	Combustion Turbine	\$93,150.72

)	Task Name	Cost
45	Inlet Heater	\$5,374.08
46	Inlet duct	\$10,748.16
47	Exhaust duct	\$14,330.88
48	Combustion Turbine	\$28,661.76
49	Combustion Turbine Foundation	\$16,122.24
50	Enclosure	\$17,913.60
51	CEMS	\$14,330.88
52	CEMS Building	\$7,165.44
53	CEMS Building Foundation	\$7,165.44
54	Stack	\$26,870.40
55	Stacks	\$26,870.40
56	Site Buildings	\$8,956.80
57	Remove Site Buildings	\$8,956.80
58	Site Prep	\$175,725.00
59	Final Grading and Drainage	\$175,725.00
60	Post Dismantlement Activities	\$65,520.00
61	Post Dismantlement Activities	\$65,520.00

)	Task Name	Duration
1	Nevada CT Dismantlement	944 days
2	Pre-Demolition Activities	130 days
3	Detailed Planning & Hire Owner's Engineer	3 mons
4	Detailed Site Characterization Study	130 days
5	Hire Demolition general Contractor	3 mons
6	KCP&L Prepares Unit for Dismantlement	2 wks
7	Demolition Contractor Mobilizes on Sit	5 days
8	KCP&L Overhead during Dismantlement	205 days
9	KCP&L Project Manager	205 days
10	KCP&L Administrative Support	205 days
11	KCP&L Engineer	205 days
12	Owners Engineer Project Manager	205 days
13	Owners Engineer - Engineer	205 days
14	Demolition Contractor Overhead during	205 days
	Dismantlement	
15	Demolition Contractor Project Manager	205 days
16	Demolition Contractor Safety Manager	205 days
17	Demolition Contractor Superintendent	205 days
18	Demolition Contractor Equipment Rental Cost	205 days
19	Equipment Rental	205 days
20	Demolition Contractor Consumables	205 days
21	Consumables	205 days
22	Scrap Crews	205 days
23	Crew to Handle Scrap Material(s)	205 days
24	Dismantlement	205 days
25	Electrical	60 days
26	Electrical Demolition of Equipment	60 days
27	Fuel Oil System	8 days
28	Remove Above Ground Fuel Oil Piping	5 days
29	Fuel Skids	3 days
30	Lube Oil System	10 days
31	Lube Oil Piping	3 days

Page 1

Task Name		Duration	
			Jan
32	Lube Oil Pumps	3 days	l l l l l l l l l l l l l l l l l l l
33	Lube Oil Tanks	4 days	ď
34	Fire Protection	15 days	—
35	Fire Protection Piping	6 days	The second secon
36	Firewater Tank	5 days	, and the second
37	CO2 Storage Tank	4 days	, in the second
38	Miscellaneous Piping	14 days	—
39	Exhaust Frame Cooling Piping	4 days	, l
40	CT Air Processing Piping	5 days	The state of the s
41	Inlet Air Heating Piping	5 days	The state of the s
42	Generator	6 days	
43	Generator	6 days	
44	Combustion Turbine	52 days	-
45	Inlet Heater	3 days	h h
46	Inlet duct	6 days	
47	Exhaust duct	8 days	
48	Combustion Turbine	16 days	
49	Combustion Turbine Foundation	9 days	
50	Enclosure	10 days	
51	CEMS	8 days	
52	CEMS Building	4 days	
53	CEMS Building Foundation	4 days	
54	Stack	15 days	
55	Stacks	15 days	
56	Site Buildings	5 days	
57	Remove Site Buildings	5 days	
58	Site Prep	65 days	
59	Final Grading and Drainage	65 days	_
60	Post Dismantlement Activities	40 days	→
61	Post Dismantlement Activities	40 days	

RALPH GREEN UNIT 3

RALPH GREEN STATION

The Ralph Green Generating Station consists of a single gas-fired combustion turbine generator set.

Ralph Green has an SPP-accredited unit rating of 71.5 MW and was placed into service in 1981. The unit is comprised of a GE Model MS7001E combustion turbine with a generator step-up transformer and auxiliary power transformer.

The following are the major systems and equipment that were included in the retirement and dismantlement of the Ralph Green Generating Station.

- 1. Combustion turbine generator sets and auxiliaries.
- 2. Generation step-up and auxiliary transformers.
- 3. Outdoor switchgear.
- 4. Exhaust stack.
- 5. Administrative/Maintenance building.
- 6. Water treatment equipment.
- 7. Service/Instrument air compressors.
- 8. Demineralized water tank.

Ralph Green Retirement

Owner Costs

Pre-Retirement Activities \$43,834
Retirement Activities \$128,593
Post-Retirement Activities \$45,152

Owner Direct Total \$217,579

Owner Internal Costs 5.00% \$10,879

Owner Contingency: 25.00% \$57,114

Ralph Green Retirement Opinion of Probable Cost: \$285,572.44

Activities Required by Permit or Regulation

Ash Pond Landfill Closure \$81,385

Activities Required by Permit or Regulation: \$81,385

	Task Name	Cost
1	Ralph Green Retirement	\$217,579.72
2	Pre-Retirement Activities	\$43,834.00
3	Permitting Review	\$23,466.00
4	Develop Detailed Retirement Plan	\$20,368.00
5	Retirement	\$128,593.72
6	Project Management During Retirement	\$56,141.40
7	Project Management During Retirement	\$56,141.40
8	Retirement Activities	\$72,452.32
9	Electrical	\$19,652.16
10	Medium and Low Voltage Drawout Switchgear	\$5,359.68
11	De-energize all buses at the source.	\$893.28
12	Open all circuit breakers.	\$893.28
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	\$893.28
14	Verify that the closing/tripping springs are discharged.	\$1,786.56
15	De-energize control power and auxiliary power circuits of each	\$893.28
	circuit breaker at the source and by opening control power circuit	,
	breakers or removing fuses in each breaker cubicle.	
16	Motor Control Centers	\$2,679.84
17	De-energize all buses at the source.	\$893.28
18	Open all circuit breakers and disconnect switches.	\$893.28
19	Remove all fuses in control circuits.	\$893.28
20	Low-voltage Switchboards and Panelboards	\$1,786.56
21	De-energize all buses at the source.	\$893.28
22	Open all circuit breakers and disconnect switches.	\$893.28
23	Oil-Filled Power Transformers	\$3,573.12
24	De-energize all buses at the source.	\$893.28
25	Open all circuit breakers and disconnect switches.	\$893.28
26	De-energize all buses at the source.	\$893.28
27	Open all circuit breakers and disconnect switches.	\$893.28
28	Dry-type Power Transformers	\$1,786.56
29	De-energize all transformer primaries and verify that the	\$893.28
	secondary is de-energized.	
30	De-energize all low-voltage AC or DC power sources for space	\$893.28
	heaters, cooling equipment, controls, etc. at the source and open	
	circuit breakers or remove fuses at transformer end.	
31	Motors	\$4,466.40
32	De-energize all primary power at the source.	\$893.28
33	De-energize all low-voltage power sources for space heaters or	\$893.28
	other auxiliary equipment at the source.	
34	Drain lube oil system (if applicable) and dispose of oil.	\$2,679.84
35	Administration/Maintenance Building	\$7,235.60
36	Secure Administration/Maintenance Building	\$7,235.60
37	Fuel Gas System	\$10,783.04

D	Task Name	Cost
38	Isolate Fuel Gas System	\$3,907.44
39	Vent Fuel Gas Piping and Equipment	\$2,528.16
40	Open and Vent Knock-Out Drum	\$861.84
41	Drain, Open and Vent the Drain Tank	\$861.84
42	Empty the Coalescing Filter	\$1,761.92
43	Open and Vent Equipment on the CT Gas Valve Module	\$861.84
44	Lube Oil Cooling Water System	\$2,585.52
45	Open and Drain the Water Side of the Lube Oil Coolers	\$1,723.68
46	Open and Vent the Coolers and Expansion Tank	\$861.84
47	Oily Drain Tank	\$3,954.00
48	Open and Pump Out the Oily Drain Tank	\$3,954.00
49	Wash Water Skid	\$2,585.52
50	Open and Drain the Detergent Tank	\$861.84
51	Open and Drain the Demineralized Water Tank	\$861.84
52	Empty the Demineralized Water Tank	\$861.84
53	Compressed Air	\$1,723.68
54	Empty Dessiccant Air Dryers and Vent	\$861.84
55	Open and Vent the Air Reciever	\$861.84
56	Miscelleaneous Piping	\$3,447.36
57	Open and Vent the Exhaust Frame Cooling Piping	\$861.84
58	Open and Vent the CT Air Processing Piping	\$861.84
59	Open and Vent the Inlet Air Heating Piping	\$861.84
60	Open and Vent the CT Air Processing Piping	\$861.84
61	Fire Protection Piping	\$3,428.24
62	Empty the CO2 Storage Tank	\$2,566.40
63	Open and Vent the Fire Protection Piping	\$861.84
64	Lube Oil System	\$7,718.32
65	Empty and Remove from Site the Lubricating Oil	\$5,132.80
66	Drain Lubricating Oil Piping	\$1,723.68
67	Open and Vent Lubricating Oil Piping	\$861.84
68	Water Treatment	\$9,338.88
69	Drain All Tanks and Vessels	\$1,723.68
70	Remove Resin from Vessels	\$2,585.52
71	Remove Chemicals	\$2,585.52
72	Open and Vent Vessels	\$861.84
73	Open and Vent the 2 Water Storage Tanks	\$861.84
74	Clean Neutralization Basin	\$720.48
75	Post Retirement Closure Activity	\$45,152.00
76	Post Retirement Closure Activity	\$45,152.00

	Task Name	Duration	2012				2013			
			Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr
1	Ralph Green Retirement	150 days								
2	Pre-Retirement Activities	40 days								
3	Permitting Review	20 days					KCP&	L Project Man	ager[25%],k	(CP&L E
4	Develop Detailed Retirement Plan	20 days								
5	Retirement	70 days								
6	Project Management During Retirement	70 days								
7	Project Management During Retirement	70 days								
8	Retirement Activities	70 days								
9	Electrical	22 days						₩		
10	Medium and Low Voltage Drawout Switchgear	6 days								
11	De-energize all buses at the source.	1 day					Ь			
12	Open all circuit breakers.	1 day					ħ			
13	Rack all circuit breakers into the fully withdrawn, disconnected	1 day					, in			
14	Verify that the closing/tripping springs are discharged.	2 days								
15	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each	1 day					ĥ			
16	Motor Control Centers	3 days								
17	De-energize all buses at the source.	1 day					ξ			
18	Open all circuit breakers and disconnect switches.	1 day					Ĭ			
19	Remove all fuses in control circuits.	1 day					h			
20	Low-voltage Switchboards and Panelboards	2 days								
21	De-energize all buses at the source.	1 day					K	•		
22	Open all circuit breakers and disconnect switches.	1 day					Ī	7		
23	Oil-Filled Power Transformers	4 days						J		

)	Task Name	Duration	2012					2013				
		- •	Qtr 1	 Qtr 2	Qtr 3	Qt	tr 4	Qtr 1	Qtr 2	Q	tr 3	Qtr 4
24	De-energize all buses at the source.							<u>F</u>	•			
25	Open all circuit breakers and disconnect switches.	1 day						Ĭ				
26	De-energize all buses at the source.	1 day						<u> </u>	_			
27	Open all circuit breakers and disconnect switches.	1 day						F				
28	Dry-type Power Transformers	2 days							I			
29	De-energize all transformer primaries and verify that the secondary is de-energized.	1 day						F				
30	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	1 day						F				
31	Motors	5 days						W				
32	De-energize all primary power at the source.	1 day						H				
33	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	1 day						Ĥ				
34		3 days						ì				
35	Administration/Maintenance Building	5 days										
36	Secure Administration/Maintenance Bu	5 days							ζ,			
37	Fuel Gas System	11 days										
38	Isolate Fuel Gas System	3 days							4			
39	Vent Fuel Gas Piping and Equipment	3 days							K			
40	Open and Vent Knock-Out Drum	1 day							Γ,			
41	Drain, Open and Vent the Drain Tank	1 day							Ϋ́			
42	Empty the Coalescing Filter	2 days							K			
43	Open and Vent Equipment on the CT Gas Valve Module	1 day							, in the second			

)	Task Name	Duration	2012						2013			
			Qtr 1	Qt	tr 2	Q	tr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4
44	Lube Oil Cooling Water System	3 days										
45	Open and Drain the Water Side of the Lube Oil Coolers	2 days										
46	Open and Vent the Coolers and Expansion Tank	1 day								ř.		
47	Oily Drain Tank	3 days								—		
48	Open and Pump Out the Oily Drain Tanl	3 days								h		
49	Wash Water Skid	3 days								W		
50	Open and Drain the Detergent Tank	1 day								Ь		
51	Open and Drain the Demineralized Water Tank	1 day								, in the second		
52	Empty the Demineralized Water Tank	1 day								Γ,		
53	Compressed Air	2 days								•		
54	Empty Dessiccant Air Dryers and Vent	1 day								Ϋ́		
55	Open and Vent the Air Reciever	1 day								h		
56	Miscelleaneous Piping	4 days								•		
57	Open and Vent the Exhaust Frame Cooling Piping	1 day								K		
58	Open and Vent the CT Air Processing Piping	1 day								F		
59	Open and Vent the Inlet Air Heating Piping	1 day								h		
60	Open and Vent the CT Air Processing Piping	1 day								F		
61	Fire Protection Piping	3 days								•		
62	Empty the CO2 Storage Tank	2 days								K		
63	Open and Vent the Fire Protection Pipir	1 day								, F		
64	Lube Oil System	6 days								•		
65	Empty and Remove from Site the Lubricating Oil	4 days										
66	Drain Lubricating Oil Piping	2 days								Ř		
67	Open and Vent Lubricating Oil Piping	1 day								Ϋ́		
68	Water Treatment	11 days								-		

Ralph	Green Retirement									
ID	Task Name	Duration	2012				2013			
			Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4
69	Drain All Tanks and Vessels	2 days						Б		
70	Remove Resin from Vessels	3 days						, in the second		
71	Remove Chemicals	3 days						<u>K</u>		
72	Open and Vent Vessels	1 day						Ĭ,		
73	Open and Vent the 2 Water Storage Ta	ar 1 day						Ϋ́		
74	Clean Neutralization Basin	1 day						ĥ		
75	Post Retirement Closure Activity	40 days							—	
76	Post Retirement Closure Activity	40 days								

Ralph Green Dismantlement

Owner Costs

Pre-Dismantlement Activities \$892,760

Overhead During Dismantlement \$748,631

Post-Dismantlement Activities \$32,760

Owner Costs Total* \$1,674,151

Demolition General Contractor (DGC) Costs

Site Management \$408,084
Equipment Rental \$694,855
Consummables \$693,242
Scrap Crew(s) \$182,507
Dismantlement \$542,291

Contractor Direct Cost* \$2,520,979

Contractor Allowances

DGC Insurance 2.00% \$50,420

Contingency/Profit 15.00% \$385,710

Performance Bond 2.00% \$59,142.17

Contractor Costs Total: \$3,016,251

Total: \$4,690,402

Owner Internal Costs: 5.00% \$234,520

Owner Contingency: 25.00% \$1,231,230

Ralph Green Dismantlement Opinion of Probable Cost: \$6,156,152

^{*}Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances = \$4,195,130

	ask Name	Cost
l R	alph Green Dismantlement	\$4,195,133.68
2	Pre-Demolition Activities	\$892,760.32
3	Detailed Planning & Hire Owner's Engineer	\$104,441.28
	Detailed Site Characterization Study	\$610,335.44
;	Hire Demolition general Contractor	\$167,184.00
,	KCP&L Prepares Unit for Dismantlement	\$10,799.60
'	Demolition Contractor Mobilizes on Sit	\$0.00
3	KCP&L Overhead during Dismantlement	\$748,631.04
)	KCP&L Project Manager	\$118,963.20
0	KCP&L Administrative Support	\$43,991.04
1	KCP&L Engineer	\$195,532.80
2	Owners Engineer Project Manager	\$58,368.00
3	Owners Engineer - Engineer	\$331,776.00
4	Demolition Contractor Overhead during Dismantlement	\$408,084.48
5	Demolition Contractor Project Manager	\$115,461.12
6	Demolition Contractor Safety Manager	\$102,804.48
7	Demolition Contractor Superintendent	\$189,818.88
8	Demolition Contractor Equipment Rental Cost	\$694,855.68
9	Equipment Rental	\$694,855.68
)	Demolition Contractor Consumables	\$693,242.88
L	Consumables	\$693,242.88
	Scrap Crews	\$182,507.52
3	Crew to Handle Scrap Material(s)	\$182,507.52
	Dismantlement	\$542,291.76
5	Electrical	\$107,481.60
5	Electrical Demolition of Equipment	\$107,481.60
	Buildings	\$17,913.60
3	Remove Administration/Maintenance Building	\$17,913.60
)	Fuel Gas System	\$8,445.28
)	Remove all above grade fuel gas piping.	\$3,071.20
_	Gas Filter Skid	\$5,374.08
2	Lube Oil System	\$17,913.60
3	Lube Oil Piping	\$5,374.08
4	Lube Oil Pumps	\$5,374.08
5	Lube Oil Tanks	\$7,165.44
6	Compressed Air System	\$23,287.68
7	Compressed Air Piping	\$5,374.08
3	Compressors	\$8,956.80
)	Air Receiver	\$3,582.72
	Dryer	\$5,374.08
L	Fire Protection	\$26,870.40
2	Fire Protection Piping	\$10,748.16
3	Firewater Tank	\$8,956.80
1	CO2 Storage Tank	\$7,165.44

Page 1

ID	Task Name	Cost
45	Wash Water Skid	\$14,330.88
46	Detergent Tank	\$7,165.44
47	Demineralized Water Tank	\$7,165.44
48	Miscellaneous Piping	\$25,079.04
49	Exhaust Frame Cooling Piping	\$7,165.44
50	CT Air Processing Piping	\$8,956.80
51	Inlet Air Heating Piping	\$8,956.80
52	Generator	\$0.00
53	Generator	\$0.00
54	Combustion Turbine	\$93,150.72
55	Inlet Heater	\$5,374.08
56	Inlet duct	\$10,748.16
57	Exhaust duct	\$14,330.88
58	Combustion Turbine	\$28,661.76
59	Combustion Turbine Foundation	\$16,122.24
60	Enclosure	\$17,913.60
61	CEMS	\$14,330.88
62	CEMS Building	\$7,165.44
63	CEMS Building Foundation	\$7,165.44
64	Stack	\$26,870.40
65	Stack	\$26,870.40
66	Demineralizer	\$23,287.68
67	Remove demineralizer vessels	\$3,582.72
68	Remove acid and caustic tanks	\$7,165.44
69	Remove hot water tank	\$3,582.72
70	Remove misc. demineralizer piping.	\$3,582.72
71	Remove 2 Demin. Water Storage Tanks	\$5,374.08
72	Site Prep	\$143,330.00
73	Final Grading and Drainage	\$143,330.00
74	Post Dismantlement Activities	\$32,760.00
75	Post Dismantlement Activities	\$32,760.00

)	Task Name	Duration	1st Quarter		
			Jan	Jan	
1	Ralph Green Dismantlement	319 days			_
2	Pre-Demolition Activities	130 days		_	V
3	Detailed Planning & Hire Owner's Engineer	3 mons			
4	Detailed Site Characterization Study	130 days			
5	Hire Demolition general Contractor	3 mons			
6	KCP&L Prepares Unit for Dismantlement	2 wks		1	
7	Demolition Contractor Mobilizes on Sit	5 days		I	
8	KCP&L Overhead during Dismantlement	192 days		_	ϕ
	KCP&L Project Manager	192 days			
)	KCP&L Administrative Support	192 days			
	KCP&L Engineer	192 days			
2	Owners Engineer Project Manager	192 days			
3	Owners Engineer - Engineer	192 days			
4	Demolition Contractor Overhead during Dismantlement	192 days			•
15	Demolition Contractor Project Manager	192 days			
6	Demolition Contractor Safety Manager	192 days			
7	Demolition Contractor Superintendent	192 days			
3	Demolition Contractor Equipment Rental Cost	192 days		-	•
9	Equipment Rental	192 days			
	Demolition Contractor Consumables	192 days		-	•
	Consumables	192 days			
2	Scrap Crews	192 days		-	•
3	Crew to Handle Scrap Material(s)	192 days			
1	Dismantlement	192 days		-	+
5	Electrical	60 days			•
6	Electrical Demolition of Equipment	60 days			*
27	Buildings	10 days			,
28	Remove Administration/Maintenance Building	10 days			→
29	Fuel Gas System	8 days			$\frac{1}{2}$
30	Remove all above grade fuel gas piping.	5 days		i	
1	Gas Filter Skid	3 days			\

)	Task Name	Duration	1st Quarter		1st Quarter	
			Jan	Jan	Jan	Ja
32	Lube Oil System	10 days			╨ 	
33	Lube Oil Piping	3 days		Į.		
34	Lube Oil Pumps	3 days		Ĥ		
35	Lube Oil Tanks	4 days		Ì		
36	Compressed Air System	13 days		•		
37	Compressed Air Piping	3 days		I	<u> </u>	
38	Compressors	5 days		j		
39	Air Receiver	2 days				
40	Dryer	3 days				
41	Fire Protection	15 days		-		
42	Fire Protection Piping	6 days				
43	Firewater Tank	5 days			Γ	
44	CO2 Storage Tank	4 days			ĭ	
45	Wash Water Skid	8 days			₽ <u>\</u>	
46	Detergent Tank	4 days			<u> </u>	
47	Demineralized Water Tank	4 days			Ĭ	
48	Miscellaneous Piping	14 days				
49	Exhaust Frame Cooling Piping	4 days			h	
50	CT Air Processing Piping	5 days			h	
51	Inlet Air Heating Piping	5 days			Ĭ	
52	Generator	6 days			₽	
53	Generator	6 days			I	
54	Combustion Turbine	52 days				
55	Inlet Heater	3 days			P.	
56	Inlet duct	6 days			<u> </u>	
57	Exhaust duct	8 days			\mathbf{K}	
58	Combustion Turbine	16 days			<u>K</u>	
59	Combustion Turbine Foundation	9 days			5	
60	Enclosure	10 days				
61	CEMS	8 days			—	
62	CEMS Building	4 days			Ы	
63	CEMS Building Foundation	4 days			ĭ	

)	Task Name	Duration	1st Quarter		1st Quarter	1st Quarter		
			Jan	Jan	Jan			
64	Stack	15 days			₩			
65	Stack	15 days			h			
66	Demineralizer	13 days						
67	Remove demineralizer vessels	2 days			ħ			
68	Remove acid and caustic tanks	4 days			h			
69	Remove hot water tank	2 days			ħ			
70	Remove misc. demineralizer piping.	2 days			ħ			
71	Remove 2 Demin. Water Storage Tanks	3 days			F			
72	Site Prep	20 days			—			
73	Final Grading and Drainage	20 days						
74	Post Dismantlement Activities	20 days						
75	Post Dismantlement Activities	20 days						

LAKE ROAD

LAKE ROAD STATION

The Lake Road Generating Station is a multi-unit facility that generates electricity from

four steam turbine generators that receive steam from seven different boilers. These

boilers burn either gas, distillate, or coal. These same boilers also produce steam that is

sold to local steam customers. Lake Road also includes three combustion turbines that fire

distillate (CTGs 5, 6, and 7) or natural gas (CTG 5).

Lake Road Boilers 1 and 2 are both package boilers rated at 85,000 lb/hr each. These

boilers fire either natural gas or distillate and were placed into service in 1962.

Lake Road Boiler 3 is rated at 130,000 lb/hr, fires natural gas, and was placed into service

in 1936.

Lake Road Boiler 4 is rated at 200,000 lb/hr, fires either natural gas or distillate, and was

placed into service in 1951.

Lake Road Boiler 5 is rated at 250,000 lb/hr, fires either natural gas or coal, and was placed

into service in 1959. This boiler has a precipitator for particulate control.

Lake Road Boiler 8 is rated at 250,000 lb/hr, fires either natural gas or distillate, and was

placed into service in 2006.

Lake Road 4/6 has an SPP-accredited unit rating of 99 MW and was placed into service in

1967. This unit can fire either coal (using cyclone burners) or natural gas and has an

electrostatic precipitator for particulate removal. River water is used for condenser cooling.

Lake Road Turbine Generator 1 has an SPP-accredited rating of 21.7 MW and was placed

into service in 1951. This unit has a condensing turbine that uses a three-cell cooling tower

for heat rejection.

Lake Road Turbine Generator 2 has an SPP-accredited rating of 27.3 MW and was placed

into service in 1957. This unit has a condensing turbine that uses a four-cell cooling tower

for heat rejection.

Lake Road Turbine Generator 3 has an SPP-accredited rating of 11.2 MW and was placed

into service in 1962.

Lake Road Combustion Turbine (CT) 5 has an SPP-accredited rating of 63 MW and was

placed into service in 1973. Lake Road CT 5 is comprised of a Westinghouse Model 501B

combustion turbine set with a generator step-up transformer and auxiliary power

transformer.

Lake Road Combustion Turbines 6 and 7 have an SPP-accredited rating of 42.7 MW and

was placed into service in 1989 and 1990, respectively. Lake Road CTs 6 and 7 are

comprised of P&W Model GG4A-7 combustion turbine set with a generator step-up

transformer and auxiliary power transformer.

The Lake Road fuel yard has a main car unloading facility, a fuel storage and reclaim

system, and a coal crusher facility that supplies coal to the units that can fire coal.

A detailed listing of the different equipment and systems included in each unit described

above can be found in the attached retirement and dismantlement schedules included in

this Appendix. The following is a detailed listing of the systems and equipment that are

considered common to the Lake Road facilities.

COMMON

1. Administration building.

2. Fuel yard office building.

3. Butler building.

4. Dozer building.

Kansas City Power & Light Co. Decommissioning Study A - 11

Project No. 14-0162 Final, Rev. 1

- 5. Laboratory.
- 6. Guard shack.
- 4. Warehouses.
- 5. Non-Potable/Fire protection water tank.
- 6. Wells and low side water treatment.
- 8. Common fuel handling equipment.
- 9. 900 lb and 200 lb steam header system.
- 10. Fire water systems.
- 11. Stacks.
- 13. Low side feedwater system.

BOILER 1

Lake Road Boiler 1 Retirement

Owner Costs

Pre-Retirement Activities \$25,969
Retirement Activities \$52,440
Post-Retirement Activities \$13,282

Owner Direct Total \$91,691

Owner Internal Costs 5.00% \$4,585

Owner Contingency: 25.00% \$24,069

Lake Road Boiler 1 Retirement Opinion of Probable Cost: \$120,344

)	Task Name	Cost
1	Lake Road Boiler 1 Retirement	\$91,691.28
2	Pre-Engineering	\$25,969.20
3	Permit review and engineering analysis and establish isolation points.	\$25,969.20
4	KCL&L Overhead Costs	\$17,348.80
5	KCP&L Retirement Manager	\$17,348.80
6	Equipment Rentals	\$5,877.76
7	Vacuum truck	\$5,877.76
8	Retirement	\$29,213.52
9	Electrical	\$10,037.04
10	Medium and Low Voltage Draw out Switchgear	\$2,679.84
11	De-energize all buses at the source.	\$446.64
12	Open all circuit breakers.	\$446.64
13	Rack all circuit breakers into the fully withdrawn, disconnected	\$446.64
	position.	
14	Verify that the closing/tripping springs are discharged.	\$446.64
15	De-energize control power and auxiliary power circuits of each	\$893.28
	circuit breaker at the source and by opening control power circuit	
	breakers or removing fuses in each breaker cubicle.	
16	Motor Control Centers	\$1,786.56
17	De-energize all buses at the source.	\$446.64
18	Open all circuit breakers and disconnect switches.	\$446.64
19	Remove all fuses in control circuits.	\$893.28
20	Low-voltage Switchboards and Panelboards	\$893.28
21	De-energize all buses at the source.	\$446.64
22	Open all circuit breakers and disconnect switches.	\$446.64
23	Motors	\$4,677.36
24	De-energize all primary power at the source.	\$446.64
25	De-energize all low-voltage power sources for space heaters or	\$446.64
	other auxiliary equipment at the source.	
26	Drain lube oil system (if applicable) and dispose of oil.	\$3,784.08
27	Fuel Systems	\$3,784.08
28	Isolate gas lines from source, open and vent.	\$1,261.36
29	Isolate fuel oil lines from source, drain, open and vent.	\$2,522.72
30	Boiler Chemical Feed	\$1,261.36
31	Drain all chemical feed tanks.	\$1,261.36
32	Boiler	\$7,084.64
33	Open boiler doors.	\$880.96
34	Gas side - perform cleaning of the boiler and bottom ash system.	\$4,480.00
35	Drain boiler, drum, downcomers and headers.	\$842.72
36	Open drum doors.	\$880.96
37	Ductwork	\$5,360.96
38	Open ductwork doors.	\$880.96
39	Perform extensive cleaning of the ductwork.	\$4,480.00
40	Feedwater Piping	\$842.72

Lake Road Boiler 1 Retirement ID Cost Task Name Drain water from the system. \$421.36 41 \$421.36 42 Leave open vents and drains. \$842.72 43 **Compressed Air System** \$842.72 44 Open vents and drains. 45 \$13,282.00 **Post Retirement Activities** \$13,282.00 46 Post Retirement Activities

Page 2

	Task Name	Duration	4th Quarter	1st Quarter	2nd Quarter	3rd Qua
1	Lake Road Boiler 1 Retirement	65 days		—	-	
2	Pre-Engineering	17 days		—	▼ 1	
3	Permit review and engineering analysis and establish	17 days				
	isolation points.					
4	KCL&L Overhead Costs	28 days				
5	KCP&L Retirement Manager	28 days				
6	Equipment Rentals	28 days				
7	Vacuum truck	28 days				
8	Retirement	28 days				
9	Electrical	10 days				
10	Medium and Low Voltage Draw out Switchgear	3 days				
11	De-energize all buses at the source.	0.5 days			P ₊	
12	Open all circuit breakers.	0.5 days			ħ	
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	0.5 days			ř	
14	Verify that the closing/tripping springs are discharged.	0.5 days			ř	
15	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each breaker cubicle.	1 day			F	
16	Motor Control Centers	2 days			•	
17	De-energize all buses at the source.	0.5 days			Ť l	
18	Open all circuit breakers and disconnect switches.	0.5 days			Ť l	
19	Remove all fuses in control circuits.	1 day			, The state of the	
20	Low-voltage Switchboards and Panelboards	1 day				
21	De-energize all buses at the source.	0.5 days			, in the second second	
22	Open all circuit breakers and disconnect switches.	0.5 days			i,	
23	Motors	4 days				
24	De-energize all primary power at the source.	0.5 days			, in the second	
25	De-energize all low-voltage power sources for space	0.5 days			i,	
	heaters or other auxiliary equipment at the source.	,				
26	Drain lube oil system (if applicable) and dispose of oil.	3 days				

)	Task Name	Duration	4th Quarter	1st Quarter	2nd Quarter	3rd Quarter
27	Fuel Systems	3 days			•	
28	Isolate gas lines from source, open and vent.	1 day			ħ l	
29	Isolate fuel oil lines from source, drain, open and vent.	2 days			T I	
30	Boiler Chemical Feed	1 day			•	
31	Drain all chemical feed tanks.	1 day			T ₁	
32	Boiler	7 days			-	
33	Open boiler doors.	1 day			<u> </u>	
34	Gas side - perform cleaning of the boiler and bottom ash system.	4 days				
35	Drain boiler, drum, downcomers and headers.	1 day			h l	
36	Open drum doors.	1 day			Ϋ́	
37	Ductwork	5 days				
38	Open ductwork doors.	1 day			Ϋ́	
39	Perform extensive cleaning of the ductwork.	4 days			*	
40	Feedwater Piping	1 day			•	
41	Drain water from the system.	0.5 days			ή	
42	Leave open vents and drains.	0.5 days			Γ, I	
43	Compressed Air System	1 day				
44	Open vents and drains.	1 day			Image: Control of the control of the	
45	Post Retirement Activities	20 days			-	
46	Post Retirement Activities	20 days				

Lake Road Boiler 1 Dismantlement

Owner Costs	Owner	Costs
-------------	-------	-------

Pre-Dismantlement Activities\$412,728Overhead During Dismantlement\$86,564Post-Dismantlement Activities\$16,380

Owner Costs Total* \$515,672

Demolition General Contractor (DGC) Costs

 Site Management
 \$129,546

 Equipment Rental
 \$307,618

 Consummables
 \$306,904

 Scrap Crew(s)
 \$304,531

 Dismantlement
 \$493,684

Contractor Direct Cost* \$1,542,283

Contractor Allowances

DGC Insurance 2.00% \$30,846

Contingency/Profit 15.00% \$235,969

Performance Bond 2.00% \$36,181.96

Contractor Costs Total: \$1,845,280

Total: \$2,360,952

Owner Internal Costs: 5.00% \$118,048

Owner Contingency: 25.00% \$619,750

Lake Road Boiler 1 Dismantlement Opinion of Probable Cost: \$3,098,749

^{*}Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances = \$2,057,955

	Task Name	Cost
1	Lake Road Boiler 1 Dismantlement	\$2,057,957.12
2	Pre-Dismantlement Activities	\$412,728.00
3	Detailed Characterization Study	\$234,744.40
4	Hire Demolition General Contractor	\$167,184.00
5	KCP&L Prepares Unit for Dismantlement	\$10,799.60
6	Demolition Contractor Mobilizes on Site	\$0.00
7	KCP&L Overhead during Dismantlement	\$86,564.00
8	KCP&L Engineer	\$86,564.00
9	Demoliton Contractor Overhead during Dismantlement	\$129,546.80
10	Demolition Contractor Safety Manager	\$45,512.40
11	Demolition Contractor Superintendent	\$84,034.40
12	Demolition Contractor Equipment Rental Costs	\$307,618.40
13	Equipment Rental	\$307,618.40
14	Demolition Contractor Consummables	\$306,904.40
15	Consummables	\$306,904.40
16	Scrap Crew(s)	\$304,531.20
17	Crew to Handle Scrap Material(s)	\$304,531.20
18	Dismantlement Directs	\$493,684.32
19	Phase 1 Demolition	\$493,684.32
20	Electrical Demolition	\$71,654.40
21	Electrical Demolition Equipment	\$71,654.40
22	Critical Piping	\$3,582.72
23	Main Steam Piping	\$3,582.72
24	Fuel Systems (plant side)	\$7,165.44
25	Gas Piping and Valves	\$1,791.36
26	Fuel Oil Piping and Valves	\$1,791.36
27	Igniters	\$3,582.72
28	Chemical Feed Systems	\$5,374.08
29	Tanks	\$1,791.36
30	Pumps	\$1,791.36
31	Piping	\$1,791.36
32	Sampling Systems	\$10,017.12
33	Field Mounted Heat Exchangers	\$3,582.72
34	Piping	\$2,851.68
35	Sample Panel	\$3,582.72
36	Miscellaneous Equipment	\$8,956.80
37	Miscellaneous Equipment (including Fire Protection)	\$8,956.80
38	Boiler Equipment	\$71,654.40
39	Fans	\$17,913.60
40	Drums	\$17,913.60
41	Ductwork	\$35,827.20
42	Boiler Removal	\$143,308.80
43	Furnace	\$143,308.80
44	Boiler Steel Framing	\$100,316.16

Lake Road Boiler 1 Dismantlement ID Task Name Cost \$35,827.20 45 Framing \$35,827.20 46 **Bracing and Girts** 47 \$28,661.76 Columns 48 \$71,654.40 **Boiler Foundations Equipment Foundation Demolition to Grade** \$71,654.40 49 **Project Close-Out** \$16,380.00 50 51 **Project Close-Out Activities** \$16,380.00

Page 2

)	Task Name	Duration		2012		2013
			H2	H1	H2	
1	Lake Road Boiler 1 Dismantlement	220 days				Y
2	Pre-Dismantlement Activities	125 days				
3	Detailed Characterization Study	50 days				
4	Hire Demolition General Contractor	3 mons				
5	KCP&L Prepares Unit for Dismantlement	2 wks				
6	Demolition Contractor Mobilizes on Site	5 days				
7	KCP&L Overhead during Dismantlement	85 days				וי
8	KCP&L Engineer	85 days				
9	Demoliton Contractor Overhead during Dismantle	men 85 days				ין
10	Demolition Contractor Safety Manager	85 days				
11	Demolition Contractor Superintendent	85 days				
12	Demolition Contractor Equipment Rental Costs	85 days				1
13	Equipment Rental	85 days				
14	Demolition Contractor Consummables	85 days				ı
15	Consummables	85 days				
16	Scrap Crew(s)	85 days				וי
17	Crew to Handle Scrap Material(s)	85 days				
18	Dismantlement Directs	85 days				וי
19	Phase 1 Demolition	85 days				ı
20	Electrical Demolition	40 days				
21	Electrical Demolition Equipment	40 days				
22	Critical Piping	2 days			•	
23	Main Steam Piping	2 days			Š	
24	Fuel Systems (plant side)	4 days				
25	Gas Piping and Valves	1 day			Ϋ́	
26	Fuel Oil Piping and Valves	1 day			Ĭ,	
27	Igniters	2 days			H	
28	Chemical Feed Systems	3 days			\(\psi\	
29	Tanks	1 day			Ϋ́	
30	Pumps	1 day			Ϋ́	
31	Piping	1 day			Ϋ́	
32	Sampling Systems	7 days			—	

)	Task Name	Duration	2012				2013	
			H2		H1	H2	H1	
33	Field Mounted Heat Exchangers	2 days				<u> </u>		
34	Piping	3 days				5		
35	Sample Panel	2 days				h		
36	Miscellaneous Equipment	5 days				•		
37	Miscellaneous Equipment (including Fire Prote	ec 5 days				K		
38	Boiler Equipment	20 days						
39	Fans	5 days				*		
40	Drums	5 days				Κ,		
41	Ductwork	10 days						
42	Boiler Removal	20 days						
43	Furnace	20 days						
44	Boiler Steel Framing	14 days						
45	Framing	5 days				T ₁		
46	Bracing and Girts	5 days				5		
47	Columns	4 days				Š		
48	Boiler Foundations	10 days					1	
49	Equipment Foundation Demolition to Grade	10 days				*		
50	Project Close-Out	10 days				•	•	
51	Project Close-Out Activities	10 days						

BOILER 2

Lake Road Boiler 2 Retirement

Owner Costs

Pre-Retirement Activities \$25,969
Retirement Activities \$52,440
Post-Retirement Activities \$13,282

Owner Direct Total \$91,691

Owner Internal Costs 5.00% \$4,585

Owner Contingency: 25.00% \$24,069

Lake Road Boiler 2 Retirement Opinion of Probable Cost: \$120,344

	Task Name	Cost
1	Lake Road Boiler 2 Retirement	\$91,691.28
2	Pre-Engineering	\$25,969.20
3	Permit review and engineering analysis and establish isolation points.	\$25,969.20
4	KCL&L Overhead Costs	\$17,348.80
5	KCP&L Retirement Manager	\$17,348.80
6	Equipment Rentals	\$5,877.76
7	Vacuum truck	\$5,877.76
8	Retirement	\$29,213.52
9	Electrical	\$10,037.04
10	Medium and Low Voltage Draw out Switchgear	\$2,679.84
11	De-energize all buses at the source.	\$446.64
12	Open all circuit breakers.	\$446.64
13	Rack all circuit breakers into the fully withdrawn, disconnected	\$446.64
	position.	
14	Verify that the closing/tripping springs are discharged.	\$446.64
15	De-energize control power and auxiliary power circuits of each	\$893.28
	circuit breaker at the source and by opening control power circuit	
	breakers or removing fuses in each breaker cubicle.	
16	Motor Control Centers	\$1,786.56
17	De-energize all buses at the source.	\$446.64
18	Open all circuit breakers and disconnect switches.	\$446.64
19	Remove all fuses in control circuits.	\$893.28
20	Low-voltage Switchboards and Panelboards	\$893.28
21	De-energize all buses at the source.	\$446.64
22	Open all circuit breakers and disconnect switches.	\$446.64
23	Motors	\$4,677.36
24	De-energize all primary power at the source.	\$446.64
25	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	\$446.64
26	Drain lube oil system (if applicable) and dispose of oil.	\$3,784.08
27	Fuel Systems	\$3,784.08
28	Isolate gas lines from source, open and vent.	\$1,261.36
29	Isolate fuel oil lines from source, drain, open and vent.	\$2,522.72
30	Boiler Chemical Feed	\$1,261.36
31	Drain all chemical feed tanks.	\$1,261.36
32	Boiler	\$7,084.64
33	Open boiler doors.	\$880.96
34	Gas side - perform cleaning of the boiler and bottom ash system.	\$4,480.00
35	Drain boiler, drum, downcomers and headers.	\$842.72
36	Open drum doors.	\$880.96
37	Ductwork	\$5,360.96
38	Open ductwork doors.	\$880.96
39	Perform extensive cleaning of the ductwork.	\$4,480.00
40	Feedwater Piping	\$842.72

ke Road Boiler 2 Retirement				
Task Name	Cost			
Drain water from the system.	\$421.36			
Leave open vents and drains.	\$421.36			
Compressed Air System	\$842.72			
Open vents and drains.	\$842.72			
Post Retirement Activities	\$13,282.00			
Post Retirement Activities	\$13,282.00			

Page 2

	Task Name	Duration	4th Quarter	1st Quarter	2nd Quarter	3rd Qua
1	Lake Road Boiler 2 Retirement	65 days		—	-	
2	Pre-Engineering	17 days		—	▼ 1	
3	Permit review and engineering analysis and establish	17 days				
	isolation points.					
4	KCL&L Overhead Costs	28 days				
5	KCP&L Retirement Manager	28 days				
6	Equipment Rentals	28 days				
7	Vacuum truck	28 days				
8	Retirement	28 days				
9	Electrical	10 days				
10	Medium and Low Voltage Draw out Switchgear	3 days				
11	De-energize all buses at the source.	0.5 days			h [★]	
12	Open all circuit breakers.	0.5 days			ξ,	
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	0.5 days			ř	
14	Verify that the closing/tripping springs are discharged.	0.5 days			ř	
15	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each breaker cubicle.	1 day			h	
16	Motor Control Centers	2 days				
17	De-energize all buses at the source.	0.5 days			<u> </u>	
18	Open all circuit breakers and disconnect switches.	0.5 days			ř l	
19	Remove all fuses in control circuits.	1 day			<u> </u>	
20	Low-voltage Switchboards and Panelboards	1 day				
21	De-energize all buses at the source.	0.5 days			Ť l	
22	Open all circuit breakers and disconnect switches.	0.5 days			Image: Control of the control of the	
23	Motors	4 days				
24	De-energize all primary power at the source.	0.5 days			h l	
25	De-energize all low-voltage power sources for space	0.5 days			i,	
	heaters or other auxiliary equipment at the source.	,				
26	Drain lube oil system (if applicable) and dispose of oil.	3 days				

)	Task Name	Duration	4th Quarter	1st Quarter	2nd Quarter	3rd Quarter
27	Fuel Systems	3 days			•	
28	Isolate gas lines from source, open and vent.	1 day			ħ l	
29	Isolate fuel oil lines from source, drain, open and vent.	2 days			T I	
30	Boiler Chemical Feed	1 day			•	
31	Drain all chemical feed tanks.	1 day			T ₁	
32	Boiler	7 days			-	
33	Open boiler doors.	1 day			<u> </u>	
34	Gas side - perform cleaning of the boiler and bottom ash system.	4 days				
35	Drain boiler, drum, downcomers and headers.	1 day			H	
36	Open drum doors.	1 day			Ϋ́	
37	Ductwork	5 days				
38	Open ductwork doors.	1 day			Ϋ́	
39	Perform extensive cleaning of the ductwork.	4 days			*	
40	Feedwater Piping	1 day			•	
41	Drain water from the system.	0.5 days			Ϋ́	
42	Leave open vents and drains.	0.5 days			H	
43	Compressed Air System	1 day				
44	Open vents and drains.	1 day			K	
45	Post Retirement Activities	20 days			-	
46	Post Retirement Activities	20 days				

Lake Road Boiler 2 Dismantlement

Owner Costs	Owner	Costs
-------------	-------	-------

Pre-Dismantlement Activities \$412,728

Overhead During Dismantlement \$86,564

Post-Dismantlement Activities \$16,380

Owner Costs Total* \$515,672

Demolition General Contractor (DGC) Costs

 Site Management
 \$129,546

 Equipment Rental
 \$307,618

 Consummables
 \$306,904

 Scrap Crew(s)
 \$304,531

 Dismantlement
 \$493,684

Contractor Direct Cost* \$1,542,283

Contractor Allowances

DGC Insurance 2.00% \$30,846

Contingency/Profit 15.00% \$235,969

Performance Bond 2.00% \$36,181.96

Contractor Costs Total: \$1,845,280

Total: \$2,360,952

Owner Internal Costs: 5.00% \$118,048

Owner Contingency: 25.00% \$619,750

Lake Road Boiler 2 Dismantlement Opinion of Probable Cost: \$3,098,749

^{*}Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances = \$2,057,955

	Task Name	Cost
1	Lake Road Boiler 2 Dismantlement	\$2,057,957.12
2	Pre-Dismantlement Activities	\$412,728.00
3	Detailed Characterization Study	\$234,744.40
4	Hire Demolition General Contractor	\$167,184.00
5	KCP&L Prepares Unit for Dismantlement	\$10,799.60
6	Demolition Contractor Mobilizes on Site	\$0.00
7	KCP&L Overhead during Dismantlement	\$86,564.00
8	KCP&L Engineer	\$86,564.00
9	Demoliton Contractor Overhead during Dismantlement	\$129,546.80
10	Demolition Contractor Safety Manager	\$45,512.40
11	Demolition Contractor Superintendent	\$84,034.40
12	Demolition Contractor Equipment Rental Costs	\$307,618.40
13	Equipment Rental	\$307,618.40
14	Demolition Contractor Consummables	\$306,904.40
15	Consummables	\$306,904.40
16	Scrap Crew(s)	\$304,531.20
17	Crew to Handle Scrap Material(s)	\$304,531.20
18	Dismantlement Directs	\$493,684.32
19	Phase 1 Demolition	\$493,684.32
20	Electrical Demolition	\$71,654.40
21	Electrical Demolition Equipment	\$71,654.40
22	Critical Piping	\$3,582.72
23	Main Steam Piping	\$3,582.72
24	Fuel Systems (plant side)	\$7,165.44
25	Gas Piping and Valves	\$1,791.36
26	Fuel Oil Piping and Valves	\$1,791.36
27	Igniters	\$3,582.72
28	Chemical Feed Systems	\$5,374.08
29	Tanks	\$1,791.36
30	Pumps	\$1,791.36
31	Piping	\$1,791.36
32	Sampling Systems	\$10,017.12
33	Field Mounted Heat Exchangers	\$3,582.72
34	Piping	\$2,851.68
35	Sample Panel	\$3,582.72
36	Miscellaneous Equipment	\$8,956.80
37	Miscellaneous Equipment (including Fire Protection)	\$8,956.80
38	Boiler Equipment	\$71,654.40
39	Fans	\$17,913.60
40	Drums	\$17,913.60
41	Ductwork	\$35,827.20
42	Boiler Removal	\$143,308.80
43	Furnace	\$143,308.80
44	Boiler Steel Framing	\$100,316.16

)	Task Name	Cost
45	Framing	\$35,827.2
46	Bracing and Girts	\$35,827.2
47	Columns	\$28,661.7
48	Boiler Foundations	\$71,654.4
49	Equipment Foundation Demolition to Grade	\$71,654.4
50	Project Close-Out	\$16,380.0
51	Project Close-Out Activities	\$16,380.0

Page 2

	Task Name	Duration		2012		2013
			H2	H1	H2	<u> </u> L
1	Lake Road Boiler 2 Dismantlement	220 days				,
2	Pre-Dismantlement Activities	125 days				
3	Detailed Characterization Study	50 days				
4	Hire Demolition General Contractor	3 mons				
5	KCP&L Prepares Unit for Dismantlement	2 wks				
6	Demolition Contractor Mobilizes on Site	5 days				
7	KCP&L Overhead during Dismantlement	85 days				
8	KCP&L Engineer	85 days				
9	Demoliton Contractor Overhead during Dismantle	men 85 days				
10	Demolition Contractor Safety Manager	85 days				
11	Demolition Contractor Superintendent	85 days				
12	Demolition Contractor Equipment Rental Costs	85 days				
13	Equipment Rental	85 days				
14	Demolition Contractor Consummables	85 days				
15	Consummables	85 days				
16	Scrap Crew(s)	85 days				
17	Crew to Handle Scrap Material(s)	85 days				
18	Dismantlement Directs	85 days				
19	Phase 1 Demolition	85 days				
20	Electrical Demolition	40 days				
21	Electrical Demolition Equipment	40 days				
22	Critical Piping	2 days				
23	Main Steam Piping	2 days			Š	
24	Fuel Systems (plant side)	4 days			•	
25	Gas Piping and Valves	1 day			Ϋ́	
26	Fuel Oil Piping and Valves	1 day			F	
27	Igniters	2 days			Ϋ́	
28	Chemical Feed Systems	3 days			•	
29	Tanks	1 day			Ϋ́	
30	Pumps	1 day			Ϋ́	
31	Piping	1 day			Ϋ́	
32	Sampling Systems	7 days			•	

)	Task Name	Duration	2012			2013	
			H2		H1	H2	H1
33	Field Mounted Heat Exchangers	2 days				<u>Ľ</u>	
34	Piping	3 days				ή	
35	Sample Panel	2 days				h	
36	Miscellaneous Equipment	5 days				•	
37	Miscellaneous Equipment (including Fire Prote	ec 5 days				Τ,	
38	Boiler Equipment	20 days					
39	Fans	5 days				Τ,	
40	Drums	5 days				Τ,	
41	Ductwork	10 days					
42	Boiler Removal	20 days					
43	Furnace	20 days					
44	Boiler Steel Framing	14 days					
45	Framing	5 days				T ₁	
46	Bracing and Girts	5 days				K	
47	Columns	4 days				5	
48	Boiler Foundations	10 days					
49	Equipment Foundation Demolition to Grade	10 days					
50	Project Close-Out	10 days				•	•
51	Project Close-Out Activities	10 days					

Lake Road Boiler 3 Retirement

Owner Costs

Pre-Retirement Activities \$25,969
Retirement Activities \$84,001
Post-Retirement Activities \$13,282

Owner Direct Total \$123,252

Owner Internal Costs 5.00% \$6,163

Owner Contingency: 25.00% \$32,354

Lake Road Boiler 3 Retirement Opinion of Probable Cost: \$161,768

Lake Road Bo	er 3 Retirement

D	Task Name	Cost
1	Lake Road Boiler 3 Retirement	\$123,252.08
2	Pre-Engineering	\$25,969.20
3	Engineering analysis and establish isolation points.	\$0.00
4	KCL&L Overhead Costs	\$27,882.00
5	KCP&L Retirement Manager	\$27,882.00
6	Equipment Rentals	\$9,446.40
7	Vacuum truck	\$9,446.40
8	Retirement	\$59,954.48
9	Motors	\$6,216.00
10	De-energize all primary power at the source.	\$1,786.56
11	De-energize all low-voltage power sources for space heaters or other	\$1,786.56
	auxiliary equipment at the source.	
12	Drain lube oil system (if applicable) and dispose of oil.	\$2,642.88
13	Fuel Gas Systems	\$1,685.44
14	Vent the Fuel Gas Systems	\$1,685.44
15	Boiler Chemical Feed	\$1,685.44
16	Drain all chemical feed tanks and piping	\$1,685.44
17	Boiler	\$25,004.64
18	Open boiler doors.	\$880.96
19	Gas side - perform cleaning of the boiler.	\$22,400.00
20	Drain boiler, drum, downcomers and headers.	\$842.72
21	Open drum doors.	\$880.96
22	Ductwork	\$12,080.96
23	Open ductwork doors.	\$880.96
24	Perform extensive cleaning of the ductwork.	\$11,200.00
25	Post Retirement Activities	\$13,282.00
26	Post Retirement Activities	\$13,282.00

)	Task Name	Duration	4th Quarter	1st Quarter	2nd Quarter	3rd Quart
1	Lake Road Boiler 3 Retirement	62 days		-		
2	Pre-Engineering	17 days		-	₹]	
3	Engineering analysis and establish isolation points.	17 days		_		
4	KCL&L Overhead Costs	45 days				
5	KCP&L Retirement Manager	45 days				
6	Equipment Rentals	45 days				
7	Vacuum truck	45 days				
8	Retirement	45 days		-		
9	Motors	7 days		₩		
10	De-energize all primary power at the source.	2 days		h		
11	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	2 days				
12	Drain lube oil system (if applicable) and dispose of oil.	3 days				
13	Fuel Gas Systems	2 days)	
14	Vent the Fuel Gas Systems	2 days		7	1	
15	Boiler Chemical Feed	2 days		•	4	
16	Drain all chemical feed tanks and piping	2 days			1	
17	Boiler	23 days		-		
18	Open boiler doors.	1 day		i		
19	Gas side - perform cleaning of the boiler.	20 days				
20	Drain boiler, drum, downcomers and headers.	1 day			†	
21	Open drum doors.	1 day			ĭ	
22	Ductwork	11 days				
23	Open ductwork doors.	1 day			h	
24	Perform extensive cleaning of the ductwork.	10 days				
25	Post Retirement Activities	20 days		-	→	
26	Post Retirement Activities	20 days				

Lake Road Boiler 3 Dismantlement

Owner Costs	Owner	Costs
-------------	-------	-------

Pre-Dismantlement Activities \$186,483

Overhead During Dismantlement \$298,939

Post-Dismantlement Activities \$16,380

Owner Costs Total* \$501,802

Demolition General Contractor (DGC) Costs

 Site Management
 \$149,359

 Equipment Rental
 \$354,665

 Consummables
 \$353,842

 Scrap Crew(s)
 \$351,016

 Dismantlement
 \$671,358

Contractor Direct Cost* \$1,880,240

Contractor Allowances

DGC Insurance 2.00% \$37,605

Contingency/Profit 15.00% \$287,677

Performance Bond 2.00% \$44,110.43

Contractor Costs Total: \$2,249,632

Total: \$2,751,434

Owner Internal Costs: 5.00% \$137,572

Owner Contingency: 25.00% \$722,251

Lake Road Boiler 3 Dismantlement Opinion of Probable Cost: \$3,611,257

^{*}Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances = \$2,382,042

)	Task Name	Cost
1	Lake Road Boiler 3 Dismantlement	\$2,382,135.80
2	Pre-Dismantlement Activities	\$186,483.32
3	Detailed Planning & Hire Owner's Engineer	\$69,627.52
4	Hire Demolition General Contractor	\$111,456.00
5	KCP&L Prepares Unit for Dismantlement	\$5,399.80
6	Demolition Contractor Mobilizes on Site	\$0.00
7	KCP&L Overhead during Dismantlement	\$298,939.20
8	KCP&L Engineer	\$99,803.20
9	Owners Engineer Project Manager	\$29,792.00
10	Owners Engineer - Engineer	\$169,344.00
11	Demoliton Contractor Overhead during Dismantlement	\$149,359.84
12	Demolition Contractor Safety Manager	\$52,473.12
13	Demolition Contractor Superintendent	\$96,886.72
14	Demolition Contractor Equipment Rental Costs	\$354,665.92
15	Equipment Rental	\$354,665.92
16	Demolition Contractor Consummables	\$353,842.72
17	Consummables	\$353,842.72
18	Scrap Crew(s)	\$351,106.56
19	Crew to Handle Scrap Material(s)	\$351,106.56
20	Dismantlement Directs	\$671,358.24
21	Phase 1 Demolition	\$671,358.24
22	Electrical Demolition	\$107,481.60
23	Electrical Demolition Equipment	\$107,481.60
24	Boiler Feed System	\$3,582.72
25	Feedwater piping	\$3,582.72
26	Critical Piping	\$3,582.72
27	Main Steam Piping	\$3,582.72
28	Fuel Systems (Plant Side)	\$5,374.08
29	Gas Piping and Equipment	\$3,582.72
30	Igniters	\$1,791.36
31	Air Preheat System	\$1,791.36
32	Steam Coil Air Heater Piping	\$1,791.36
33	Miscellaneous Equipment	\$8,956.80
34	Miscellaneous Equipment (including Fire Protection)	\$8,956.80
35	Boiler Equipment	\$67,669.92
36	Fans	\$17,913.60
37	Steam Drum	\$28,661.76
38	Soot Blowers	\$3,180.96
39	Ductwork	\$17,913.60
40	Boiler Removal	\$114,647.04
41	Furnace	\$57,323.52
42	Back Pass	\$57,323.52
43	Boiler Steel Framing	\$250,790.40
44	Hanger Girders at Top	\$35,827.20

	oad Boiler 3 Dismantlement	
D	Task Name	Cost
45	All Other Framing	\$71,654.40
46	Bracing and Girts	\$71,654.40
47	Columns	\$71,654.40
48	Boiler Foundations	\$107,481.60
49	Equipment Foundation Demolition to Grade	\$107,481.60
50	Project Close-Out	\$16,380.00
51	Project Close-Out Activities	\$16,380.00

Page 2

	Task Name	Duration		2012	
			H2	H1	H2
1	Lake Road Boiler 3 Dismantlement	163 days		<u> </u>	
2	Pre-Dismantlement Activities	55 days			
3	Detailed Planning & Hire Owner's Engineer	2 mons			
4	Hire Demolition General Contractor	2 mons			
5	KCP&L Prepares Unit for Dismantlement	1 wk		M ₁	
5	Demolition Contractor Mobilizes on Site	5 days			
7	KCP&L Overhead during Dismantlement	98 days			
8	KCP&L Engineer	98 days			
9	Owners Engineer Project Manager	98 days			
.0	Owners Engineer - Engineer	98 days		*	
1	Demoliton Contractor Overhead during Dismantle	men 98 days			
2	Demolition Contractor Safety Manager	98 days			
3	Demolition Contractor Superintendent	98 days			
14	Demolition Contractor Equipment Rental Costs	98 days			
15	Equipment Rental	98 days			
L6	Demolition Contractor Consummables	98 days			
17	Consummables	98 days			
18	Scrap Crew(s)	98 days			
L9	Crew to Handle Scrap Material(s)	98 days			
20	Dismantlement Directs	98 days			
1	Phase 1 Demolition	98 days			
22	Electrical Demolition	60 days			
23	Electrical Demolition Equipment	60 days			
24	Boiler Feed System	2 days			
25	Feedwater piping	2 days			
26	Critical Piping	2 days			
27	Main Steam Piping	2 days			
28	Fuel Systems (Plant Side)	3 days			
29	Gas Piping and Equipment	2 days			
30	Igniters	1 day		The state of the s	·
31	Air Preheat System	1 day			
32	Steam Coil Air Heater Piping	1 day			·

)	Task Name	Duration	2012			2013	
			H2		H1	H2	H1
33	Miscellaneous Equipment	5 days			•		
34	Miscellaneous Equipment (including Fire Prote	ec 5 days			<u> </u>		
35	Boiler Equipment	19 days					
36	Fans	5 days			*		
37	Steam Drum	8 days			*		
38	Soot Blowers	1 day			Ϋ́		
39	Ductwork	5 days			5		
40	Boiler Removal	16 days			-	-	
41	Furnace	8 days					
42	Back Pass	8 days				5	
43	Boiler Steel Framing	35 days			•		
44	Hanger Girders at Top	5 days				ξ	
45	All Other Framing	10 days					
46	Bracing and Girts	10 days					
47	Columns	10 days					
48	Boiler Foundations	15 days				-	
49	Equipment Foundation Demolition to Grade	15 days					
50	Project Close-Out	10 days					
51	Project Close-Out Activities	10 days					

Lake Road Boiler 4 Retirement

Owner Costs

Pre-Retirement Activities \$25,969
Retirement Activities \$66,164
Post-Retirement Activities \$13,282

Owner Direct Total \$105,415

Owner Internal Costs 5.00% \$5,271

Owner Contingency: 25.00% \$27,671

Lake Road Boiler 4 Retirement Opinion of Probable Cost: \$138,357

Lake Road Boiler 4 Retirement

ID	Task Name	Cost
1	Lake Road Boiler 4 Retirement	\$105,415.92
2	Pre-Engineering	\$25,969.20
3	Engineering analysis and establish isolation points.	\$0.00
4	KCL&L Overhead Costs	\$22,925.20
5	KCP&L Retirement Manager	\$22,925.20
6	Equipment Rentals	\$7,767.04
7	Vacuum truck	\$7,767.04
8	Retirement	\$35,472.48
9	Motors	\$6,216.00
10	De-energize all primary power at the source.	\$1,786.56
11	De-energize all low-voltage power sources for space heaters or other	\$1,786.56
	auxiliary equipment at the source.	
12	Drain lube oil system (if applicable) and dispose of oil.	\$2,642.88
13	Fuel Systems	\$1,685.44
14	Isolate and Vent the Fuel Gas Systems	\$1,685.44
15	Isolate and Vent the Fuel Oil Systems	\$0.00
16	Boiler Chemical Feed	\$1,685.44
17	Drain all chemical feed tanks and piping	\$1,685.44
18	Boiler	\$13,804.64
19	Open boiler doors.	\$880.96
20	Gas side - perform cleaning of the boiler.	\$11,200.00
21	Drain boiler, drum, downcomers and headers.	\$842.72
22	Open drum doors.	\$880.96
23	Ductwork	\$12,080.96
24	Open ductwork doors.	\$880.96
25	Perform extensive cleaning of the ductwork.	\$11,200.00
26	Post Retirement Activities	\$13,282.00
27	Post Retirement Activities	\$13,282.00

)	Task Name	Duration	4th Quarter	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter
1	Lake Road Boiler 4 Retirement	74 days		—	·		
2	Pre-Engineering	17 days			ካ		
3	Engineering analysis and establish isolation points.	17 days					
4	KCL&L Overhead Costs	37 days		₩			
5	KCP&L Retirement Manager	37 days			KCFL I	Retirement Man	ager
6	Equipment Rentals	37 days		=			
7	Vacuum truck	37 days			Vacuu	m Truck	
8	Retirement	37 days		-	-		
9	Motors	7 days		-			
10	De-energize all primary power at the source.	2 days			KCP&L Electric		
11	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	2 days			KCP&L Electric	cian[200%]	
12	Drain lube oil system (if applicable) and dispose of oil.	3 days			KCP&L Mecha	anic[200%]	
13	Fuel Systems	4 days			•		
14	Isolate and Vent the Fuel Gas Systems	2 days			KCP&L Opera	ator[200%]	
15	Isolate and Vent the Fuel Oil Systems	2 days			Ϋ́ I		
16	Boiler Chemical Feed	2 days					
17	Drain all chemical feed tanks and piping	2 days			KCP&L Oper	ator[200%]	
18	Boiler	13 days					
19	Open boiler doors.	1 day			KCP&L Med	hanic[200%]	
20	Gas side - perform cleaning of the boiler.	10 days			KCP&L PI	ant Helper[400%	6]
21	Drain boiler, drum, downcomers and headers.	1 day			*	perator[200%]	
22	Open drum doors.	1 day			KCP&I. N	lechanic[200%]	
23	Ductwork	11 days					
24	Open ductwork doors.	1 day			*	lechanic[200%]	
25	Perform extensive cleaning of the ductwork.	10 days			KCF&I	L Plant Helper[4	00%]
26	Post Retirement Activities	20 days			•		
27	Post Retirement Activities	20 days			— к	CPL Retirement	Manager[25

Lake Road Boiler 4 Dismantlement

Owner Costs	Owner	Costs
-------------	-------	-------

Pre-Dismantlement Activities \$186,483

Overhead During Dismantlement \$298,939

Post-Dismantlement Activities \$16,380

Owner Costs Total* \$501,802

Demolition General Contractor (DGC) Costs

 Site Management
 \$172,221

 Equipment Rental
 \$408,951

 Consummables
 \$408,002

 Scrap Crew(s)
 \$404,847

 Dismantlement
 \$762,717

Contractor Direct Cost* \$2,156,738

Contractor Allowances

DGC Insurance 2.00% \$43,135

Contingency/Profit 15.00% \$329,981

Performance Bond 2.00% \$50,597.07

Contractor Costs Total: \$2,580,451

Total: \$3,082,253

Owner Internal Costs: 5.00% \$154,113

Owner Contingency: 25.00% \$809,091

\$4,045,457

Lake Road Boiler 4 Dismantlement Opinion of Probable Cost:

*Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances = \$2,658,540

)	Task Name	Cost
1	Lake Road Boiler 4 Dismantlement	\$2,658,542.36
2	Pre-Dismantlement Activities	\$186,483.32
3	Detailed Planning & Hire Owner's Engineer	\$69,627.52
4	Hire Demolition General Contractor	\$111,456.00
5	KCP&L Prepares Unit for Dismantlement	\$5,399.80
6	Demolition Contractor Mobilizes on Site	\$0.00
7	KCP&L Overhead during Dismantlement	\$298,939.20
8	KCP&L Engineer	\$99,803.20
9	Owners Engineer Project Manager	\$29,792.00
10	Owners Engineer - Engineer	\$169,344.00
11	Demoliton Contractor Overhead during Dismantlement	\$172,221.04
12	Demolition Contractor Safety Manager	\$60,504.72
13	Demolition Contractor Superintendent	\$111,716.32
14	Demolition Contractor Equipment Rental Costs	\$408,951.52
15	Equipment Rental	\$408,951.52
16	Demolition Contractor Consummables	\$408,002.32
17	Consummables	\$408,002.32
18	Scrap Crew(s)	\$404,847.36
19	Crew to Handle Scrap Material(s)	\$404,847.36
20	Dismantlement Directs	\$762,717.60
21	Phase 1 Demolition	\$762,717.60
22	Electrical Demolition	\$116,438.40
23	Electrical Demolition Equipment	\$116,438.40
24	Boiler Feed System	\$3,582.72
25	Feedwater piping	\$3,582.72
26	Critical Piping	\$3,582.72
27	Main Steam Piping	\$3,582.72
28	Fuel Systems (Plant Side)	\$5,374.08
29	Gas Piping and Equipment	\$3,582.72
30	Fuel Oil Piping and Equipment	\$0.00
31	Igniters	\$1,791.36
32	Air Preheat System	\$1,791.36
33	Steam Coil Air Heater Piping	\$1,791.36
34	Miscellaneous Equipment	\$8,956.80
35	Miscellaneous Equipment (including Fire Protection)	\$8,956.80
36	Boiler Equipment	\$78,418.08
37	Fans	\$17,913.60
38	Steam Drum	\$32,244.48
39	Soot Blowers	\$3,180.96
40	Ductwork	\$17,913.60
41	Old Coal Bunkers	\$7,165.44
42	Boiler Removal	\$143,308.80
43	Furnace	\$71,654.40
44	Back Pass	\$71,654.40

D	Task Name	Cost
45	Boiler Steel Framing	\$279,452.16
46	Hanger Girders at Top	\$42,992.64
47	All Other Framing	\$78,819.84
48	Bracing and Girts	\$78,819.84
49	Columns	\$78,819.84
50	Boiler Foundations	\$121,812.48
51	Equipment Foundation Demolition to Grade	\$121,812.48
52	Project Close-Out	\$16,380.00
53	Project Close-Out Activities	\$16,380.00

	Task Name	Duration		201	12	12
			H2		Н	H1
1	Lake Road Boiler 4 Dismantlement	178 days		—		
2	Pre-Dismantlement Activities	55 days		†	_	
3	Detailed Planning & Hire Owner's Engineer	2 mons				
4	Hire Demolition General Contractor	2 mons				
5	KCP&L Prepares Unit for Dismantlement	1 wk				H
5	Demolition Contractor Mobilizes on Site	5 days			1	_
7	KCP&L Overhead during Dismantlement	98 days				
3	KCP&L Engineer	98 days			Ĭ	
9	Owners Engineer Project Manager	98 days				
LO	Owners Engineer - Engineer	98 days			4	
1	Demoliton Contractor Overhead during Dismantle	men 113 days				
L2	Demolition Contractor Safety Manager	113 days			*	
13	Demolition Contractor Superintendent	113 days				
14	Demolition Contractor Equipment Rental Costs	113 days				
.5	Equipment Rental	113 days				
6	Demolition Contractor Consummables	113 days				
7	Consummables	113 days				
8	Scrap Crew(s)	113 days				
9	Crew to Handle Scrap Material(s)	113 days				_
0	Dismantlement Directs	113 days				
1	Phase 1 Demolition	113 days				
2	Electrical Demolition	65 days				
23	Electrical Demolition Equipment	65 days				
24	Boiler Feed System	2 days				
25	Feedwater piping	2 days			<u></u>	
26	Critical Piping	2 days				
27	Main Steam Piping	2 days			<u> </u>	
28	Fuel Systems (Plant Side)	5 days				
29	Gas Piping and Equipment	2 days			<u> </u>	
30	Fuel Oil Piping and Equipment	2 days			<u>K</u>	
31	Igniters	1 day			P.	
32	Air Preheat System	1 day				

	Task Name	Duration		2012			2013
			H2		H1	H2	H1
33	Steam Coil Air Heater Piping	1 day			Ŋ		
34	Miscellaneous Equipment	5 days			<u> </u>		
35	Miscellaneous Equipment (including Fire Prote	•			4		
36	Boiler Equipment	22 days					
37	Fans	5 days			<u>~</u>		
38	Steam Drum	9 days					
39	Soot Blowers	1 day			<u> </u>		
40	Ductwork	5 days			<u> </u>	L	
41	Old Coal Bunkers	2 days					
42	Boiler Removal	20 days			_		
43	Furnace	10 days					
44	Back Pass	10 days					
45	Boiler Steel Framing	39 days					
46	Hanger Girders at Top	6 days					
47	All Other Framing	11 days				_ _	
48	Bracing and Girts	11 days					
49	Columns	11 days				T	
50	Boiler Foundations	17 days					
51	Equipment Foundation Demolition to Grade	17 days					
52	Project Close-Out	10 days					
53	Project Close-Out Activities	10 days					

Lake Road Boiler 5 Retirement

Owner Costs

Pre-Retirement Activities \$25,969
Retirement Activities \$100,380
Post-Retirement Activities \$13,282

Owner Direct Total \$139,631

Owner Internal Costs 5.00% \$6,982

Owner Contingency: 25.00% \$36,653

Lake Road Boiler 5 Retirement Opinion of Probable Cost: \$183,266

Activities Required by Permit or Regulation

Lake Road 5 Pond \$58,349 Lake Road Ash Pond Closure \$1,117,000

Activities Required by Permit or Regulation: \$1,175,349

1	Fask Name	Cost
1 L	ake Road Boiler 5 Retirement	\$139,631.92
2	Pre-Engineering	\$25,969.20
3	Engineering analysis and establish isolation points.	\$0.00
4	KCL&L Overhead Costs	\$29,740.80
5	KCP&L Retirement Manager	\$29,740.80
6	Equipment Rentals	\$10,076.16
7	Vacuum truck	\$10,076.16
8	Retirement	\$60,563.76
9	Motors	\$6,216.00
10	De-energize all primary power at the source.	\$1,786.56
11	De-energize all low-voltage power sources for space heaters or other	\$1,786.56
	auxiliary equipment at the source.	
12	Drain lube oil system (if applicable) and dispose of oil.	\$2,642.88
13	Sulfur Injection System	\$2,522.72
14	Empty, Clean and Vent the Storage Tank	\$2,522.72
15	Drain and Flush the Sulfur Injection System Piping and Vent	\$0.00
16	Fuel Systems	\$4,208.16
17	Open and Clean the Boiler 5 Bunker	\$1,685.44
18	Isolate and Vent the Gas Systems	\$2,522.72
19	Boiler Chemical Feed	\$842.72
20	Drain all chemical feed tanks and piping	\$842.72
21	Boiler	\$13,804.64
22	Open boiler doors.	\$880.96
23	Gas side - perform cleaning of the boiler.	\$11,200.00
24	Drain boiler, drum, downcomers and headers.	\$842.72
25	Open drum doors.	\$880.96
26	Open and Clean the Pulverizers	\$0.00
27	Open and Vent the Coal Piping	\$0.00
28	Precipitator	\$20,181.76
29	Multiple cleaning cycles for collection plates.	\$3,784.08
30	Clear hoppers of all ash	\$5,045.44
31	Disconnect tranformers.	\$2,522.72
32	Mechanically secure all compartment dampers and hopper outlet	\$1,261.36
	valves in open position.	
33	Disconnect ash transport piping and washdown baghouse hoppers and	\$1,261.36
	interior of casing.	
34	Install bird screens across hopper ash outlet and ash line flanges.	\$1,261.36
35	Padlock or tack weld all hopper doors shut. (note: if ash hopper doors	\$1,261.36
	are indoors, they could be removed and the opening covered with bird	
	screens.)	
36	Pull electrical supply breakers on all electrical equipment except lighting	\$3,784.08
	and HVAC components that are to remain in service.	
37	Ductwork	\$6,480.96
38	Open ductwork doors.	\$880.96

,	Task Name	Cost
39	Perform extensive cleaning of the ductwork.	\$5,600.00
40	Ash Handling	\$6,306.80
41	Open and Vacuum the Ash Silo	\$5,045.44
42	Open and Clean Ash Handling Equipment	\$1,261.36
43	Post Retirement Activities	\$13,282.00
44	Post Retirement Activities	\$13,282.00

Page 2

	Task Name	Duration	4th Quarter	1st Quarter	2nd Quarter	3rd Quai
1	Lake Road Boiler 5 Retirement	75 days		—		
2	Pre-Engineering	17 days			▼]	
3	Engineering analysis and establish isolation points.	17 days				
4	KCL&L Overhead Costs	48 days			<u> </u>	
5	KCP&L Retirement Manager	48 days				
6	Equipment Rentals	48 days			-	
7	Vacuum truck	48 days				
8	Retirement	48 days			-	
9	Motors	7 days				
10	De-energize all primary power at the source.	2 days				
11	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	2 days				
12	Drain lube oil system (if applicable) and dispose of oil.	3 days			Ϋ́,	
13	Sulfur Injection System	3 days			•	
14	Empty, Clean and Vent the Storage Tank	2 days			5	
15	Drain and Flush the Sulfur Injection System Piping and Vo	ent 1 day			h	
16	Fuel Systems	4 days			•	
17	Open and Clean the Boiler 5 Bunker	2 days			ή	
18	Isolate and Vent the Gas Systems	2 days			*	
19	Boiler Chemical Feed	1 day				
20	Drain all chemical feed tanks and piping	1 day			K	
21	Boiler	17 days				
22	Open boiler doors.	1 day			ξ	
23	Gas side - perform cleaning of the boiler.	10 days				
24	Drain boiler, drum, downcomers and headers.	1 day			K	
25	Open drum doors.	1 day			†	
26	Open and Clean the Pulverizers	2 days			*	
27	Open and Vent the Coal Piping	2 days			K	
28	Precipitator	16 days			 	
29	Multiple cleaning cycles for collection plates.	3 days			4	
30	Clear hoppers of all ash	4 days			*	
31	Disconnect tranformers.	2 days				

)	Task Name	Duration	4th Quarter	1st Quarter	2nd Quarter	3rd Quarter
32	Mechanically secure all compartment dampers and hopper outlet valves in open position.	1 day				
33	Disconnect ash transport piping and washdown baghouse hoppers and interior of casing.	1 day				
34	Install bird screens across hopper ash outlet and ash line flanges.	1 day				
35	Padlock or tack weld all hopper doors shut. (note: if ash hopper doors are indoors, they could be removed and the opening covered with bird screens.)	1 day				
36	Pull electrical supply breakers on all electrical equipment except lighting and HVAC components that are to remain ir service.					
37	Ductwork	6 days			-	
38	Open ductwork doors.	1 day			<u>L</u>	
39	Perform extensive cleaning of the ductwork.	5 days			T	
40	Ash Handling	5 days			<u> </u>	
41	Open and Vacuum the Ash Silo	4 days				
42	Open and Clean Ash Handling Equipment	1 day				
43	Post Retirement Activities	20 days			-	
44	Post Retirement Activities	20 days				

Lake Road Boiler 5 Dismantlement

Owner Costs

Pre-Dismantlement Activities \$186,483

Overhead During Dismantlement \$558,223

Post-Dismantlement Activities \$16,380

Owner Costs Total* \$761,086

Demolition General Contractor (DGC) Costs

 Site Management
 \$278,906

 Equipment Rental
 \$662,284

 Consummables
 \$660,747

 Scrap Crew(s)
 \$655,637

 Dismantlement
 \$1,174,730

Contractor Direct Cost* \$3,432,304

Contractor Allowances

DGC Insurance 2.00% \$68,646

Contingency/Profit 15.00% \$525,143

Performance Bond 2.00% \$80,521.85

Contractor Costs Total: \$4,106,614

Total: \$4,867,700

Owner Internal Costs: 5.00% \$243,385

Owner Contingency: 25.00% \$1,277,771

Lake Road Boiler 5 Dismantlement Opinion of Probable Cost: \$6,388,857

^{*}Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances = \$4,193,390

	Task Name	Cost
1	Lake Road Boiler 5 Dismantlement	\$4,193,392.76
2	Pre-Dismantlement Activities	\$186,483.32
3	Detailed Planning & Hire Owner's Engineer	\$69,627.52
4	Hire Demolition General Contractor	\$111,456.00
5	KCP&L Prepares Unit for Dismantlement	\$5,399.80
6	Demolition Contractor Mobilizes on Site	\$0.00
7	KCP&L Overhead during Dismantlement	\$558,223.20
8	KCP&L Engineer	\$186,367.20
9	Owners Engineer Project Manager	\$55,632.00
10	Owners Engineer - Engineer	\$316,224.00
11	Demoliton Contractor Overhead during Dismantlement	\$278,906.64
12	Demolition Contractor Safety Manager	\$97,985.52
13	Demolition Contractor Superintendent	\$180,921.12
14	Demolition Contractor Equipment Rental Costs	\$662,284.32
15	Equipment Rental	\$662,284.32
16	Demolition Contractor Consummables	\$660,747.12
17	Consummables	\$660,747.12
18	Scrap Crew(s)	\$655,637.76
19	Crew to Handle Scrap Material(s)	\$655,637.76
20	Dismantlement Directs	\$1,174,730.40
21	Phase 1 Demolition	\$1,174,730.40
22	Electrical Demolition	\$125,395.20
23	Electrical Demolition Equipment	\$125,395.20
24	Boiler Feed System	\$3,582.72
25	Feedwater piping	\$3,582.72
26	Critical Piping	\$3,582.72
27	Main Steam Piping	\$3,582.72
28	Gas Systems (Plant Side)	\$5,374.08
29	Gas Piping and Equipment	\$3,582.72
30	Igniters	\$1,791.36
31	Air Preheat System	\$1,791.36
32	Steam Coil Air Heater Piping	\$1,791.36
33	Miscellaneous Equipment	\$14,330.88
34	Miscellaneous Equipment (including Fire Protection)	\$14,330.88
35	Boiler Equipment	\$175,151.52
36	Fans	\$21,496.32
37	Steam Drum	\$35,827.20
38	Soot Blowers	\$3,180.96
39	Ductwork	\$21,496.32
40	Pulverizers	\$35,827.20
41	Coal Bunkers	\$14,330.88
42	Feeders	\$7,165.44
43	Ash Silo	\$17,913.60
44	Ash Handling Equipment	\$17,913.60

Lake Road Boiler 5 Dism	nantlement
-------------------------	------------

ID	Task Name	Cost
45	Boiler Removal	\$207,797.76
46	Furnace	\$107,481.60
47	Back Pass	\$100,316.16
48	Boiler Steel Framing	\$351,106.56
49	Hanger Girders at Top	\$71,654.40
50	All Other Framing	\$100,316.16
51	Bracing and Girts	\$100,316.16
52	Columns	\$78,819.84
53	Precipitator	\$143,308.80
54	Remove Precipitator	\$143,308.80
55	Boiler Foundations	\$143,308.80
56	Equipment Foundation Demolition to Grade	\$143,308.80
57	Project Close-Out	\$16,380.00
58	Project Close-Out Activities	\$16,380.00

)	Task Name	Duration		2012		2013	
			H2	H1	H2	H1	Н
1	Lake Road Boiler 5 Dismantlement	248 days		†			
2	Pre-Dismantlement Activities	55 days		•			
3	Detailed Planning & Hire Owner's Engineer	2 mons					
4	Hire Demolition General Contractor	2 mons					
5	KCP&L Prepares Unit for Dismantlement	1 wk			•		
6	Demolition Contractor Mobilizes on Site	5 days					
7	KCP&L Overhead during Dismantlement	183 days		-			
8	KCP&L Engineer	183 days					
9	Owners Engineer Project Manager	183 days					
10	Owners Engineer - Engineer	183 days					
11	Demoliton Contractor Overhead during Dismantle	men 183 days				—	
12	Demolition Contractor Safety Manager	183 days					
13	Demolition Contractor Superintendent	183 days					
14	Demolition Contractor Equipment Rental Costs	183 days				—	
15	Equipment Rental	183 days					
16	Demolition Contractor Consummables	183 days				—	
17	Consummables	183 days					
18	Scrap Crew(s)	183 days				—	
19	Crew to Handle Scrap Material(s)	183 days					
20	Dismantlement Directs	183 days					
21	Phase 1 Demolition	183 days					
22	Electrical Demolition	70 days					
23	Electrical Demolition Equipment	70 days					
24	Boiler Feed System	2 days					
25	Feedwater piping	2 days			Š		
26	Critical Piping	2 days		"			
27	Main Steam Piping	2 days			h		
28	Gas Systems (Plant Side)	3 days			.		
29	Gas Piping and Equipment	2 days			Ř		
30	Igniters	1 day			Ť,		
31	Air Preheat System	1 day					
32	Steam Coil Air Heater Piping	1 day			ħ		

	Task Name	Duration		2012		2013		
			H2	H1	H2	H1	H2	
33	Miscellaneous Equipment	8 days						
34	Miscellaneous Equipment (including Fire Prote							
35	Boiler Equipment	49 days						
36	Fans	6 days			_			
37	Steam Drum	10 days			<u>,</u>			
38	Soot Blowers	1 day						
39	Ductwork	6 days			5			
40	Pulverizers	10 days						
41	Coal Bunkers	4 days			Ŋ			
42	Feeders	2 days			Ϋ́			
43	Ash Silo	5 days			5			
44	Ash Handling Equipment	5 days			K			
45	Boiler Removal	29 days						
46	Furnace	15 days						
47	Back Pass	14 days						
48	Boiler Steel Framing	49 days						
49	Hanger Girders at Top	10 days			*			
50	All Other Framing	14 days						
51	Bracing and Girts	14 days						
52	Columns	11 days			Ĭ.	ı		
53	Precipitator	20 days			-			
54	Remove Precipitator	20 days						
55	Boiler Foundations	20 days						
56	Equipment Foundation Demolition to Grade	20 days						
57	Project Close-Out	10 days				•		
58	Project Close-Out Activities	10 days						

Lake Road Boiler 8 Retirement

Owner Costs

Pre-Retirement Activities \$22,914
Retirement Activities \$44,223
Post-Retirement Activities \$13,282

Owner Direct Total \$80,419

Owner Internal Costs 5.00% \$4,021

Owner Contingency: 25.00% \$21,110

Lake Road Boiler 8 Retirement Opinion of Probable Cost: \$105,550

	Fask Name	Cost
1	Lake Road Boiler 8 Retirement	\$80,419.36
2	Pre-Engineering	\$22,914.00
3	Permit review and engineering analysis and establish isolation points.	\$22,914.00
4	KCL&L Overhead Costs	\$14,870.40
5	KCP&L Retirement Manager	\$14,870.40
6	Equipment Rentals	\$5,038.08
7	Vacuum truck	\$5,038.08
8	Retirement	\$24,314.88
9	Electrical	\$10,037.04
10	Medium and Low Voltage Draw out Switchgear	\$2,679.84
11	De-energize all buses at the source.	\$446.64
12	Open all circuit breakers.	\$446.64
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	\$446.64
14	Verify that the closing/tripping springs are discharged.	\$446.64
15	De-energize control power and auxiliary power circuits of each	\$893.28
	circuit breaker at the source and by opening control power circuit	
	breakers or removing fuses in each breaker cubicle.	
16	Motor Control Centers	\$1,786.56
17	De-energize all buses at the source.	\$446.64
18	Open all circuit breakers and disconnect switches.	
19	Remove all fuses in control circuits. Low-voltage Switchboards and Panelboards	
20		
21	De-energize all buses at the source.	\$446.64
22	Open all circuit breakers and disconnect switches.	\$446.64
23	Motors	\$4,677.36
24	De-energize all primary power at the source.	\$446.64
25	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	\$446.64
26	Drain lube oil system (if applicable) and dispose of oil.	\$3,784.08
27	Fuel Systems	\$2,522.72
28	Isolate gas lines from source, open and vent.	\$1,261.36
29	Isolate fuel oil lines from source, drain, open and vent.	\$1,261.36
30	Boiler Chemical Feed	\$1,261.36
31	Drain all chemical feed tanks.	\$1,261.36
32	Boiler	\$4,844.64
33	Open boiler doors.	\$880.96
34	Gas side - perform cleaning of the boiler and bottom ash system.	\$2,240.00
35	Drain boiler, drum, downcomers and headers.	\$842.72
36	Open drum doors.	\$880.96
37	Ductwork	\$3,120.96
38	Open ductwork doors.	\$880.96
39	Perform extensive cleaning of the ductwork.	\$2,240.00
40	Feedwater Piping	\$842.72

D	Task Name	Cost
41	Drain water from the system.	\$421.36
42	Leave open vents and drains.	\$421.36
43	Deaerator and Deaerator Storage Tank	\$842.72
44	Drain Deaerator and Storage	\$421.36
45	Leave open vents and drains.	\$421.36
46	Compressed Air System	\$842.72
47	Open vents and drains.	\$842.72
48	Post Retirement Activities	\$13,282.00
49	Post Retirement Activities	\$13,282.00

	Task Name	Duration	4th Quarter	1st Quarter	2nd Quarter	3rd Quai
1	Lake Road Boiler 8 Retirement	59 days		—		
2	Pre-Engineering	15 days		—	₽]	
3	Permit review and engineering analysis and establish	15 days				
	isolation points.					
4	KCL&L Overhead Costs	24 days			-	
5	KCP&L Retirement Manager	24 days				
6	Equipment Rentals	24 days				
7	Vacuum truck	24 days				
8	Retirement	24 days				
9	Electrical	10 days				
10	Medium and Low Voltage Draw out Switchgear	3 days				
11	De-energize all buses at the source.	0.5 days			h	
12	Open all circuit breakers.	0.5 days			Ϋ́,	
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	0.5 days			ř i	
14	Verify that the closing/tripping springs are discharged.	0.5 days			F	
15	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each breaker cubicle.	1 day			F	
16	Motor Control Centers	2 days				
17	De-energize all buses at the source.	0.5 days			†	
18	Open all circuit breakers and disconnect switches.	0.5 days			†	
19	Remove all fuses in control circuits.	1 day			K	
20	Low-voltage Switchboards and Panelboards	1 day			•	
21	De-energize all buses at the source.	0.5 days			<u> </u>	
22	Open all circuit breakers and disconnect switches.	0.5 days			h	
23	Motors	4 days			•	
24	De-energize all primary power at the source.	0.5 days			h l	
25	De-energize all low-voltage power sources for space	0.5 days			ř l	
	heaters or other auxiliary equipment at the source.					
26	Drain lube oil system (if applicable) and dispose of oil.	3 days			*	

)	Task Name	Duration	4th Quarter	1st Quarter	2nd Quarter	3rd Quarter
27	Fuel Systems	2 days			•	
28	Isolate gas lines from source, open and vent.	1 day			ξ	
29	Isolate fuel oil lines from source, drain, open and vent.	1 day			Image: Control of the control of the	
30	Boiler Chemical Feed	1 day			•	
31	Drain all chemical feed tanks.	1 day			Ϋ́	
32	Boiler	5 days			+	
33	Open boiler doors.	1 day			Ϋ́	
34	Gas side - perform cleaning of the boiler and bottom ash system.	2 days				
35	Drain boiler, drum, downcomers and headers.	1 day			Ϋ́	
36	Open drum doors.	1 day			Ϋ́	
37	Ductwork	3 days			•	
38	Open ductwork doors.	1 day			ř l	
39	Perform extensive cleaning of the ductwork.	2 days			5	
40	Feedwater Piping	1 day				
41	Drain water from the system.	0.5 days			Ь	
42	Leave open vents and drains.	0.5 days			Ϊ́	
43	Deaerator and Deaerator Storage Tank	1 day			•	
44	Drain Deaerator and Storage	0.5 days			<u>F</u>	
45	Leave open vents and drains.	0.5 days			F	
46	Compressed Air System	1 day				
47	Open vents and drains.	1 day			ξ	
48	Post Retirement Activities	20 days			_	
49	Post Retirement Activities	20 days				

Lake Road Boiler 8 Dismantlement

Owner (Costs
---------	-------

Pre-Dismantlement Activities \$177,983

Overhead During Dismantlement \$67,214

Post-Dismantlement Activities \$16,380

Owner Costs Total* \$261,577

Demolition General Contractor (DGC) Costs

 Site Management
 \$140,279

 Equipment Rental
 \$238,856

 Consummables
 \$238,302

 Scrap Crew(s)
 \$236,459

 Dismantlement
 \$360,502

Contractor Direct Cost* \$1,214,398

Contractor Allowances

DGC Insurance 2.00% \$24,288

Contingency/Profit 15.00% \$185,803

Performance Bond 2.00% \$28,489.78

Contractor Costs Total: \$1,452,979

Total: \$1,714,556

Owner Internal Costs: 5.00% \$85,728

Owner Contingency: 25.00% \$450,071

Lake Road Boiler 8 Dismantlement Opinion of Probable Cost:

\$2,250,354

^{*}Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances = \$1,475,975

	Task Name	Cost
1	Lake Road Boiler 8 Dismantlement	\$1,475,977.84
2	Pre-Dismantlement Activities	\$177,983.60
3	Hire Demolition General Contractor	\$167,184.00
4	KCP&L Prepares Unit for Dismantlement	\$10,799.60
5	Demolition Contractor Mobilizes on Site	\$0.00
6	KCP&L Overhead during Dismantlement	\$67,214.40
7	KCP&L Engineer	\$67,214.40
8	Demoliton Contractor Overhead during Dismantlement	\$140,279.04
9	Demolition Contractor Project Manager	\$39,689.76
10	Demolition Contractor Safety Manager	\$35,339.04
11	Demolition Contractor Superintendent	\$65,250.24
12	Demolition Contractor Equipment Rental Costs	\$238,856.64
13	Equipment Rental	\$238,856.64
14	Demolition Contractor Consummables	\$238,302.24
15	Consummables	\$238,302.24
16	Scrap Crew(s)	\$236,459.52
17	Crew to Handle Scrap Material(s)	\$236,459.52
18	Dismantlement Directs	\$360,502.40
19	Phase 1 Demolition	\$360,502.40
20	Electrical Demolition	\$71,654.40
21	Electrical Demolition Equipment	\$71,654.40
22	Condensate System	\$8,956.80
23	Deaerator	\$3,582.72
24	Deaerator Storage Tank	\$1,791.36
25	Condensate Piping	\$3,582.72
26	Boiler Feed System	\$11,187.20
27	Boiler Feed Pumps	\$4,021.76
28	Feedwater piping	\$7,165.44
29	Critical Piping	\$5,374.08
30	Main Steam Piping	\$5,374.08
31	Fuel Systems	\$14,330.88
32	Fuel Oil Piping	\$3,582.72
33	Gas Piping	\$1,791.36
34	Igniters	\$8,956.80
35	Chemical Feed Systems	\$7,165.44
36	Tanks	\$1,791.36
37	Pumps	\$1,791.36
38	Piping	\$3,582.72
39	Sampling Systems	\$5,374.08
40	Field Mounted Heat Exchangers	\$1,791.36
41	Piping	\$1,791.36
42	Sample Panel	\$1,791.36
43	Miscellaneous Equipment	\$7,165.44
44	Miscellaneous Equipment (including Fire Protection)	\$7,165.44

D	Task Name	Cost
45	Boiler Equipment	\$28,661.76
46	Fans	\$3,582.72
47	Steam Drum	\$14,330.88
48	Ductwork	\$10,748.16
49	Boiler Removal	\$71,654.40
50	Furnace	\$71,654.40
51	Boiler Steel Framing	\$71,654.40
52	Framing and Supports	\$71,654.40
53	Boiler Building	\$21,496.32
54	Remove Boiler Building	\$21,496.32
55	Boiler Foundations	\$35,827.20

\$35,827.20

\$16,380.00

\$16,380.00

Equipment Foundation Demolition to Grade

56

57 58 **Project Close-Out**

Project Close-Out Activities

	Task Name	Duration		201	12
		_	H2		H1
1	Lake Road Boiler 8 Dismantlement	151 days			
2	Pre-Dismantlement Activities	75 days		—	
3	Hire Demolition General Contractor	3 mons			
4	KCP&L Prepares Unit for Dismantlement	2 wks			—
5	Demolition Contractor Mobilizes on Site	5 days			
6	KCP&L Overhead during Dismantlement	66 days			
7	KCP&L Engineer	66 days			
8	Demoliton Contractor Overhead during Dismantle	men 66 days			
9	Demolition Contractor Project Manager	66 days			
10	Demolition Contractor Safety Manager	66 days			
11	Demolition Contractor Superintendent	66 days			
12	Demolition Contractor Equipment Rental Costs	66 days			
13	Equipment Rental	66 days			
14	Demolition Contractor Consummables	66 days		•	
15	Consummables	66 days			
16	Scrap Crew(s)	66 days			
17	Crew to Handle Scrap Material(s)	66 days			
18	Dismantlement Directs	66 days			
19	Phase 1 Demolition	66 days			
20	Electrical Demolition	40 days		-	
21	Electrical Demolition Equipment	40 days			
22	Condensate System	5 days			ı
23	Deaerator	2 days			•
24	Deaerator Storage Tank	1 day		i i	
25	Condensate Piping	2 days			
26	Boiler Feed System	3 days			,
27	Boiler Feed Pumps	2 days			
28	Feedwater piping	1 day			H
29	Critical Piping	3 days			
30	Main Steam Piping	3 days			K
31	Fuel Systems	8 days			
32	Fuel Oil Piping	2 days			T

	Task Name	Duration		2012			2013	
			H2		H1	H2	H1	
33	Gas Piping	1 day			5			
34	Igniters	5 days			I			
35	Chemical Feed Systems	4 days			<u> </u>			
36	Tanks	1 day			Ι			
37	Pumps	1 day			<u>K</u>			
38	Piping	2 days			ď			
39	Sampling Systems	3 days						
40	Field Mounted Heat Exchangers	1 day			Ъ			
41	Piping	1 day			Ъ			
42	Sample Panel	1 day			Ь			
43	Miscellaneous Equipment	4 days			•			
44	Miscellaneous Equipment (including Fire Prote	ec 4 days			T ₁			
45	Boiler Equipment	8 days						
46	Fans	1 day			,			
47	Steam Drum	4 days			ħ			
48	Ductwork	3 days						
49	Boiler Removal	10 days			_	-		
50	Furnace	10 days				ή		
51	Boiler Steel Framing	10 days						
52	Framing and Supports	10 days				Y		
53	Boiler Building	3 days						
54	Remove Boiler Building	3 days				5		
55	Boiler Foundations	5 days				w		
56	Equipment Foundation Demolition to Grade	5 days						
57	Project Close-Out	10 days						
58	Project Close-Out Activities	10 days						

Lake Road 4/6 Retirement

Owner Costs

Pre-Retirement Activities \$61,104
Retirement Activities \$206,732
Post-Retirement Activities \$26,564

Owner Direct Total \$294,400

Owner Internal Costs 5.00% \$14,720

Owner Contingency: 25.00% \$77,280

Lake Road 4/6 Retirement Opinion of Probable Cost: \$386,400

Activities Required by Permit or Regulation

Lake Road 4 River Intake \$637,591

Activities Required by Permit or Regulation: \$637,591

	Task Name	Cost
1	Lake Road 4/6 Retirement	\$294,400.77
2	Pre-Engineering	\$61,104.00
3	Permit review and engineering analysis and establish isolation points.	\$61,104.00
4	KCL&L Overhead Costs	\$73,732.40
5	KCP&L Retirement Manager	\$73,732.40
6	Equipment Rentals	\$24,980.48
7	Vacuum truck	\$24,980.48
8	Retirement	\$108,019.89
9	Electrical	\$20,052.88
10	Medium and Low Voltage Draw out Switchgear	\$2,679.84
11	De-energize all buses at the source.	\$446.64
12	Open all circuit breakers.	\$446.64
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	\$446.64
14	Verify that the closing/tripping springs are discharged.	\$446.64
15	De-energize control power and auxiliary power circuits of each circuit	\$893.28
	breaker at the source and by opening control power circuit breakers	
	or removing fuses in each breaker cubicle.	
16	Motor Control Centers	\$1,786.56
17	De-energize all buses at the source.	\$446.64
18	Open all circuit breakers and disconnect switches.	\$446.64
19	Remove all fuses in control circuits.	\$893.28
20	Low-voltage Switchboards and Panelboards	\$893.28
21	De-energize all buses at the source.	\$446.64
22	Open all circuit breakers and disconnect switches.	\$446.64
23	Oil-Filled Power Transformers	\$5,549.44
24	De-energize all transformer primaries and verify that the secondary is de-energized.	\$893.28
25	De-energize all low-voltage AC or DC power sources for space heaters,	\$893.28
	cooling equipment, controls, etc. at the source and open circuit	7
	breakers or remove fuses at transformer end.	
26	Drain and dispose of oil.	\$2,642.88
27	Clean up and dispose of oil on surface areas around the transformers on in containment pits.	\$1,120.00
28	Dry-type Power Transformers	\$1,786.56
29	De-energize all transformer primaries and verify that the secondary is	\$893.28
	de-energized.	·
30	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	\$893.28
31	Motors	\$7,357.20
32	De-energize all primary power at the source.	\$1,786.56
33	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	\$1,786.56

	Task Name	Cost
34	Drain lube oil system (if applicable) and dispose of oil.	\$3,784.08
35	Coal Handling	\$5,466.80
36	Empty both coal silos.	\$1,682.72
37	Confirm conveyors are run out of fuel.	\$1,261.36
38	Perform cleaning of the coal handling equipment to assure that all coal and coal dust has been removed from area.	\$2,522.72
39	Gas System	\$2,522.72
40	Isolate lines from source, open and vent.	\$2,522.72
11	Boiler Chemical Feed	\$2,522.72
42	Drain all chemical feed tanks.	\$2,522.72
13	Demineralizer	\$5,371.84
14	Drain water from system.	\$842.72
1 5	Drain acid and caustic tanks.	\$1,685.44
16	Open tanks and vessels.	\$880.96
17	Remove resin.	\$1,120.00
18	Drain and Vent the Demineralized Water Storage Tank	\$842.72
19	Boiler	\$26,508.85
50	Open boiler doors.	\$880.96
51	Gas side - perform cleaning of the boiler and bottom ash system.	\$16,800.00
52	Drain boiler, drum, downcomers and headers.	\$842.72
53	Open drum doors.	\$880.96
54	Drain, vent and clean the fly ash, slag and transport systems	\$2,480.13
55	Drain and vent the steam coil air heaters and piping	\$1,541.36
56	Drain and vent the steam coil air heater drain tanks	\$1,541.36
57	Drain and vent boiler sampling system panel and piping	\$1,541.36
58	Precipitator	\$8,357.60
59	Multiple cleaning cycles for collection plates.	\$1,685.44
50	Clear hoppers of all ash	\$1,402.72
51	Disconnect transformers.	\$1,786.56
62	Mechanically secure all compartment dampers and hopper outlet valves in open position.	\$720.48
63	Disconnect ash transport piping and washdown hoppers and interior of casing.	\$1,000.48
64	Install bird screens across hopper ash outlet and ash line flanges.	\$880.96
65	Padlock or tack weld all hopper doors shut. (note: if ash hopper doors are indoors, they could be removed and the opening covered with bird	\$880.96
	screens.)	
66	Ductwork	\$9,840.96
57	Open ductwork doors.	\$880.96
58	Perform extensive cleaning of the ductwork.	\$8,960.00
69	Isolate ductwork at tie to common ductwork.	\$0.00
70	Condensate and Feedwater Piping	\$1,685.44
71	Drain water from the system.	\$842.72
72	Leave open vents and drains.	\$842.72

	Task Name	Cost
73	Feedwater heaters	\$3,370.88
74	Drain feedwater heaters	\$842.72
75	Leave open vents and drains.	\$1,685.44
76	Drain and vent the heater drain piping.	\$842.72
77	Deaerator and Deaerator Storage Tank	\$1,685.44
78	Drain Deaerator and Storage	\$842.72
79	Leave open vents and drains.	\$842.72
80	Turbine(s) and Condenser	\$3,504.72
81	Drain hotwell and leave doors open.	\$861.84
82	Open main turbine doors.	\$880.96
83	Remove lube oil.	\$1,761.92
84	Generator	\$6,095.76
85	Verify that generator circuit breaker is open and racked out or that	\$446.64
	high-voltage disconnect switch on substation side of GSU transformer is	
	locked in the open position.	
86	Verify that generator field breaker or contactor (if applicable) is open.	\$446.64
87	De-energize power supplies to generator excitation system at the	\$446.64
	source.	
88	De-energize AC and DC power supplies to generator and exciter space	\$446.64
	heaters, cooling equipment, controls, lighting, etc. at the source and	
	open circuit breakers or remove fuses at the generator and exciter.	
89	Drain generator and exciter cooling water systems (if applicable).	\$861.84
90	Disconnect and remove hydrogen gas tanks and purge generator	\$1,685.44
	hydrogen system.	
91	Disconnect and remove fire protection system gas/foam tanks and purge	\$1,761.92
	fire protection system.	
92	Circulation Water and Turbine Cooling Water System	\$2,566.40
93	Drain.	\$842.72
94	Open water box doors.	\$880.96
95	Drain any circulating water chemical feed tanks.	\$842.72
96	Compressed Air System	\$842.72
97	Open vents and drains.	\$842.72
98	Auxiliary Steam System	\$842.72
99	Drain water from system.	\$842.72
100	Closed Cooling Water System	\$1,685.44
101	Drain water from system.	\$842.72
102	Vent piping.	\$842.72
103	Condenser Air Extraction	\$842.72
104	Drain water from system.	\$842.72
105	Battery System	\$4,253.28
106	De-energize all battery chargers from the source.	\$446.64
107	Open all AC and DC circuit breakers and/or fused switches on battery	\$446.64
	chargers and disconnect cables from batteries.	
108	Remove and dispose of battery electrolyte.	\$1,680.00

	Гask Name	Cost
9	Remove and dispose of battery cells.	\$1,120.00
0	Clean up and dispose of electrolyte on surface areas around batteries.	\$560.00
1	Post Retirement Activities	\$26,564.00
2	Post Retirement Activities	\$26,564.00

	Task Name	Duration	4th O	uarter 1st Quarter	uarter 1st Quarter 2nd Quarter	uarter 1st Quarter 2nd Quarter 3rd Quarter 4t	uarter 1st Quarter 2nd Quarter 3rd Quarter 4th Quarte
1	Lake Road 4/6 Retirement	199 days		—	Ψ	V	•
2	Pre-Engineering	40 days		—	•	•	
3	Permit review and engineering analysis and establish isolation points.	40 days					
4	KCL&L Overhead Costs	119 days					▼
5	KCP&L Retirement Manager	119 days					
6	Equipment Rentals	119 days				· · · · · · · · · · · · · · · · · · ·	· · · · · · · · · · · · · · · · · · ·
7	Vacuum truck	119 days					
8	Retirement	119 days		-		· ·	
9	Electrical	22 days					
10	Medium and Low Voltage Draw out Switchgear	3 days				•	
11	De-energize all buses at the source.	0.5 days			l h	In the second se	h
12	Open all circuit breakers.	0.5 days			T T	j , , , , , , , , , , , , , , , , , , ,	j ķ
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	0.5 days			F	T T	
14	Verify that the closing/tripping springs are discharged.	0.5 days			Ĭ F	Ĭ,	T T
15	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each breaker cubicle.				h	h h	F I
16	Motor Control Centers	2 days					
17	De-energize all buses at the source.	0.5 days			 	 	T T
18	Open all circuit breakers and disconnect switches.	0.5 days			, in the second	 	T I
19	Remove all fuses in control circuits.	1 day			, in the second	Ĭ , ř	T T
20	Low-voltage Switchboards and Panelboards	1 day			•		
21	De-energize all buses at the source.	0.5 days			j j	, in the second	<u> </u>
22	Open all circuit breakers and disconnect switches.	0.5 days			Ĭ Ĭ	T F	Ĭ Ĭ
23	Oil-Filled Power Transformers	7 days			•	•	•
24	De-energize all transformer primaries and verify that the secondary is de-energized.	1 day			Ĭ,	h h	↑

)	Task Name	Duration	4th Quarter 1st Quarter 2nd Quarter 3rd
25	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	1 day	F F
26	Drain and dispose of oil.	3 days	The state of the s
27	Clean up and dispose of oil on surface areas around the transformers on in containment pits.	2 days	The state of the s
28	Dry-type Power Transformers	2 days	•
29	De-energize all transformer primaries and verify that the secondary is de-energized.	e 1 day	, in the second
30	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	1 day	, in the second
31	Motors	7 days	•
32	De-energize all primary power at the source.	2 days	<u> </u>
33	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	2 days	Ť
34	Drain lube oil system (if applicable) and dispose of oil.	3 days	The state of the s
35	Coal Handling	5 days	•
36	Empty both coal silos.	2 days	The state of the s
37	Confirm conveyors are run out of fuel.	1 day	, in the second
38	Perform cleaning of the coal handling equipment to assure that all coal and coal dust has been removed from area.	e 2 days	Ť
39	Gas System	2 days	•
40	Isolate lines from source, open and vent.	2 days	
41	Boiler Chemical Feed	2 days	—
42	Drain all chemical feed tanks.	2 days	l *
43	Demineralizer	7 days	•
44	Drain water from system.	1 day	ħ
45	Drain acid and caustic tanks.	2 days	The state of the s
46	Open tanks and vessels.	1 day	, in the second
47	Remove resin.	2 days	The state of the s
48	Drain and Vent the Demineralized Water Storage Tank	1 day	

	Task Name	Duration	4th Quarter 1st Quarter 2nd Quarter 3rd Quarter 4th Quarter
49	Boiler	26 days	
50	Open boiler doors.	1 day	
51	Gas side - perform cleaning of the boiler and bottom ash	15 days	
	system.		
52	Drain boiler, drum, downcomers and headers.	1 day	<u>\</u>
53	Open drum doors.	1 day	<u></u>
54	Drain, vent and clean the fly ash, slag and transport	5 days	
	systems		
55	Drain and vent the steam coil air heaters and piping	1 day	
56	Drain and vent the steam coil air heater drain tanks	1 day	j
57	Drain and vent boiler sampling system panel and piping	1 day	_
58	Precipitator	10 days	
59	Multiple cleaning cycles for collection plates.	2 days	<u></u>
60	Clear hoppers of all ash	2 days	
61	Disconnect transformers.	2 days	
62	Mechanically secure all compartment dampers and hoppe	er1 day	
63	Disconnect ash transport piping and washdown hoppers a	ar 1 day	
64	Install bird screens across hopper ash outlet and ash line	fl 1 day	\mathbf{h}
65	Padlock or tack weld all hopper doors shut. (note: if ash h	o1 day	
66	Ductwork	11 days	•
67	Open ductwork doors.	1 day	Ĭ,
68	Perform extensive cleaning of the ductwork.	8 days	
69	Isolate ductwork at tie to common ductwork.	2 days	Ϋ́
70	Condensate and Feedwater Piping	2 days	•
71	Drain water from the system.	1 day	, in the second
72	Leave open vents and drains.	1 day	, the second sec
73	Feedwater heaters	4 days	•
74	Drain feedwater heaters	1 day	
75	Leave open vents and drains.	2 days	T T T T T T T T T T T T T T T T T T T
76	Drain and vent the heater drain piping.	1 day	T T
77	Deaerator and Deaerator Storage Tank	2 days	•
78	Drain Deaerator and Storage	1 day	, the state of the
79	Leave open vents and drains.	1 day	<u> </u>

)	Task Name	Duration	4th Quarter 1st Quarter 2nd	id Quarte
80	Turbine(s) and Condenser	4 days		
81	Drain hotwell and leave doors open.	1 day		
82	Open main turbine doors.	1 day		
83	Remove lube oil.	2 days		
84	Generator	7 days		
85	Verify that generator circuit breaker is open and racked ou or that high-voltage disconnect switch on substation side of GSU transformer is locked in the open position.	t0.5 days		
86	Verify that generator field breaker or contactor (if applicable) is open.	0.5 days		
87	De-energize power supplies to generator excitation system at the source.	0.5 days		
88	De-energize AC and DC power supplies to generator and exciter space heaters, cooling equipment, controls, lighting, etc. at the source and open circuit breakers or remove fuses at the generator and exciter.	0.5 days		
89	Drain generator and exciter cooling water systems (if applicable).	1 day		
90	Disconnect and remove hydrogen gas tanks and purge generator hydrogen system.	2 days		
91	Disconnect and remove fire protection system gas/foam tanks and purge fire protection system.	2 days		
92	Circulation Water and Turbine Cooling Water System	3 days		
3	Drain.	1 day		
4	Open water box doors.	1 day		
95	Drain any circulating water chemical feed tanks.	1 day		
96	Compressed Air System	1 day		
97	Open vents and drains.	1 day		
98	Auxiliary Steam System	1 day		
99	Drain water from system.	1 day		
100	Closed Cooling Water System	2 days		
101	Drain water from system.	1 day		
102	Vent piping.	1 day		
103	Condenser Air Extraction	1 day		

D	Task Name	Duration	4th Quarter	1st Quart	er 2nd Quarter	3rd Quarter	4th Quarter	1st Quart
104	Drain water from system.	1 day				Ì		
105	Battery System	7 days				•		
106	De-energize all battery chargers from the source.	0.5 days				Ì		
107	Open all AC and DC circuit breakers and/or fused switches on battery chargers and disconnect cables from batteries.	0.5 days				Ì		
108	Remove and dispose of battery electrolyte.	3 days				Ì	Š	
109	Remove and dispose of battery cells.	2 days					ή	
110	Clean up and dispose of electrolyte on surface areas around batteries.	1 day					h	
111	Post Retirement Activities	40 days						
112	Post Retirement Activities	40 days						

Lake Road 4-6 Dismantlement

Owner Costs

Pre-Dismantlement Activities \$892,760

Overhead During Dismantlement \$733,959

Post-Dismantlement Activities \$49,140

Owner Costs Total* \$1,675,859

Demolition General Contractor (DGC) Costs

 Site Management
 \$400,086

 Equipment Rental
 \$681,238

 Consummables
 \$679,657

 Scrap Crew(s)
 \$674,401

 Dismantlement
 \$1,500,720

Contractor Direct Cost* \$3,936,101

Contractor Allowances

DGC Insurance 2.00% \$78,722

Contingency/Profit 15.00% \$602,224

Performance Bond 2.00% \$92,340.94

Contractor Costs Total: \$4,709,388

Total: \$6,385,247

Owner Internal Costs: 5.00% \$319,262

Owner Contingency: 25.00% \$1,676,127

Lake Road 4-6 Dismantlement Opinion of Probable Cost: \$8,380,637

^{*}Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances = \$5,611,960

TURBINE GENERATOR 1

Lake Road T/G 1 Retirement

Owner Costs

Pre-Retirement Activities \$7,638
Retirement Activities \$26,641
Post-Retirement Activities \$3,320

Owner Direct Total \$37,599

Owner Internal Costs 5.00% \$1,880

Owner Contingency: 25.00% \$9,870

Lake Road T/G 1 Retirement Opinion of Probable Cost: \$49,349

Labor Daniel	Tarada taran	C 4 1	Retirement
Lake Road	rurome	Generator i	Kenremeni

D	Task Name	Cost
1	Lake Road Turbine Generator 1 Retirement	\$37,599.30
2	Pre-Engineering	\$7,638.00
3	Engineering analysis and establish isolation points.	\$7,638.00
4	KCL&L Overhead Costs	\$13,631.20
5	KCP&L Retirement Manager	\$13,631.20
6	Retirement	\$13,009.60
7	Feedwater Piping	\$1,685.44
8	Drain water from the system and isolate from system.	\$842.72
9	Leave open vents and drains.	\$842.72
10	Turbine(s) and Condenser	\$4,385.68
11	Drain hotwell and leave doors open.	\$861.84
12	Open main turbine doors.	\$880.96
13	Remove lube oil.	\$2,642.88
14	Circulating Water System	\$0.00
15	Drain and Clean the Cooling Tower	\$0.00
16	Drain and Vent the Circulating Water Pipe	\$0.00
17	Drain, Clean and Vent the Cooling Tower Chemical Systems	\$0.00
18	Generator	\$6,095.76
19	Verify that generator circuit breaker is open and racked out or that high-voltage disconnect switch on substation side of GSU transformer is	\$446.64
	locked in the open position.	
20	Verify that generator field breaker or contactor (if applicable) is open.	\$446.64
21	De-energize power supplies to generator excitation system at the source.	\$446.64
22	De-energize AC and DC power supplies to generator and exciter space heaters, cooling equipment, controls, lighting, etc. at the source and open circuit breakers or remove fuses at the generator and exciter.	\$446.64
23	Drain generator and exciter cooling water systems (if applicable).	\$861.84
24	Disconnect and remove hydrogen gas tanks and purge generator hydrogen system.	\$1,685.44
25	Disconnect and remove fire protection system gas/foam tanks and purge fire protection system.	\$1,761.92
26	Condenser Air Extraction	\$842.72
27	Drain water from system.	\$842.72
28	Post Retirement Activities	\$3,320.50
29	Post Retirement Activities	\$3,320.50

)	Task Name	Duration	4th Quarter	1st Quarter	2nd Quarter	3rd (
1	Lake Road Turbine Generator 1 Retirement	32 days		-		
2	Pre-Engineering	5 days		₩		
3	Engineering analysis and establish isolation points.	5 days		•		
4	KCL&L Overhead Costs	22 days		-	—	
5	KCP&L Retirement Manager	22 days				
6	Retirement	22 days			—	
7	Feedwater Piping	2 days				
8	Drain water from the system and isolate from system.	1 day		l h →		
9	Leave open vents and drains.	1 day		K		
10	Turbine(s) and Condenser	5 days			•	
11	Drain hotwell and leave doors open.	1 day		l K		
12	Open main turbine doors.	1 day		l h		
13	Remove lube oil.	3 days				
14	Circulating Water System	7 days				
15	Drain and Clean the Cooling Tower	5 days				
16	Drain and Vent the Circulating Water Pipe	1 day			<u> </u>	
17	Drain, Clean and Vent the Cooling Tower Chemical Systems	s 1 day			K	
18	Generator	7 days				
19	Verify that generator circuit breaker is open and racked ou or that high-voltage disconnect switch on substation side of GSU transformer is locked in the open position.	t0.5 days			ř	
20	Verify that generator field breaker or contactor (if applicable) is open.	0.5 days			ř	
21	De-energize power supplies to generator excitation system at the source.	0.5 days			Ĭ,	
22	De-energize AC and DC power supplies to generator and exciter space heaters, cooling equipment, controls, lighting, etc. at the source and open circuit breakers or remove fuses at the generator and exciter.	0.5 days			Ť	
23	Drain generator and exciter cooling water systems (if applicable).	1 day			F	
24	Disconnect and remove hydrogen gas tanks and purge generator hydrogen system.	2 days			7	

Lake F	oad Turbine Generator 1 Retirement					
ID	Task Name	Duration	4th Quarter	1st Quarter	2nd Quarter	3rd Quarter
25	Disconnect and remove fire protection system gas/foam tanks and purge fire protection system.	2 days				
26	Condenser Air Extraction	1 day				
27	Drain water from system.	1 day			Ϋ́	
28	Post Retirement Activities	5 days				
29	Post Retirement Activities	5 days				

Lake Road T/G 1 Dismantlement

Owner Costs

Pre-Dismantlement Activities \$172,583

Overhead During Dismantlement \$92,674

Post-Dismantlement Activities \$8,190

Owner Costs Total* \$273,447

Demolition General Contractor (DGC) Costs

 Site Management
 \$89,966

 Equipment Rental
 \$329,332

 Consummables
 \$328,568

 Scrap Crew(s)
 \$326,027

 Dismantlement
 \$210,518

Contractor Direct Cost* \$1,284,411

Contractor Allowances

DGC Insurance 2.00% \$25,688

Contingency/Profit 15.00% \$196,515

Performance Bond 2.00% \$30,132.28

Contractor Costs Total: \$1,536,746

Total: \$1,810,193

Owner Internal Costs: 5.00% \$90,510

Owner Contingency: 25.00% \$475,176

Lake Road T/G 1 Dismantlement Opinion of Probable Cost: \$2,375,879

^{*}Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances = \$1,557,858

	Task Name	Cost
1	Lake Road T/G 1 Removal	\$1,557,861.80
2	Pre-Dismantlement Activities	\$172,583.80
3	Hire Demolition General Contractor	\$167,184.00
4	KCP&L Prepares Unit for Dismantlement	\$5,399.80
5	Demolition Contractor Mobilizes on Site	\$0.00
6	KCP&L Overhead during Dismantlement	\$92,674.40
7	KCP&L Engineer	\$92,674.40
8	Demoliton Contractor Overhead during Dismantlement	\$89,966.24
9	Demolition Contractor Superintendent	\$89,966.24
10	Demolition Contractor Equipment Rental Costs	\$329,332.64
11	Equipment Rental	\$329,332.64
12	Demolition Contractor Consummables	\$328,568.24
13	Consummables	\$328,568.24
14	Scrap Crew(s)	\$326,027.52
15	Crew to Handle Scrap Material(s)	\$326,027.52
16	Dismantlement Directs	\$210,518.96
17	Phase 1 Demolition	\$210,518.96
18	Critical Piping	\$3,582.72
19	Remove Main Steam Piping to the Turbine	\$3,582.72
20	Circulating Water (plant side)	\$3,582.72
21	Waterboxes	\$3,582.72
22	Condenser Air Extraction System	\$3,582.72
23	Vacuum Pumps	\$3,582.72
24	Turbine Seals and Drains	\$7,165.44
25	Piping	\$7,165.44
26	Turbine Lube Oil System	\$18,443.76
27	Turbine Lube Oil Tank	\$7,695.60
28	Turbine Lube Oil Pumps	\$7,165.44
29	Turbine Oil Mist Eliminator	\$3,582.72
30	Generator Auxiliary Systems	\$21,496.32
31	Hydrogen Cooler Skid and Piping	\$3,582.72
32	Stator Cooling Water Skid and Piping	\$3,582.72
33	Isophase Bus Duct	\$7,165.44
34	Exciter Heat Exchanger	\$3,582.72
35	EHC Coolers	\$3,582.72
36	Remove Turbine	\$126,343.68
37	Remove Turbine	\$26,321.60
38	Remove Generator	\$39,482.40
39	Remove Condenser Neck Heat Exchanger	\$7,896.48
40	Remove Condenser	\$13,160.80
41	Remove Misc. Auxiliary Turbine Equipment	\$39,482.40
42	Cooling Tower 1	\$26,321.60
43	Remove Cooling Tower 1	\$26,321.60
44	Project Close-Out	\$8,190.00

	oad Turbine Generator 1 Dismantlement	
ID	Task Name	Cost
45	Project Close-Out Activities	\$8,190.00
		Page 2

)	Task Name	Duration		2012		2013
			H2	H1	H2	
1	Lake Road T/G 1 Removal	171 days				
2	Pre-Dismantlement Activities	75 days				
3	Hire Demolition General Contractor	3 mons				
4	KCP&L Prepares Unit for Dismantlement	1 wk				
5	Demolition Contractor Mobilizes on Site	5 days				
6	KCP&L Overhead during Dismantlement	91 days				
7	KCP&L Engineer	91 days				
8	Demoliton Contractor Overhead during Dismantlem	en 91 days				
9	Demolition Contractor Superintendent	91 days				
10	Demolition Contractor Equipment Rental Costs	91 days				
11	Equipment Rental	91 days				
12	Demolition Contractor Consummables	91 days				
13	Consummables	91 days				
14	Scrap Crew(s)	91 days				
15	Crew to Handle Scrap Material(s)	91 days				
16	Dismantlement Directs	91 days				
17	Phase 1 Demolition	91 days				
18	Critical Piping	2 days				
19	Remove Main Steam Piping to the Turbine	2 days		5		
20	Circulating Water (plant side)	2 days				
21	Waterboxes	2 days		, in the second		
22	Condenser Air Extraction System	2 days				
23	Vacuum Pumps	2 days		h h		
24	Turbine Seals and Drains	4 days		•		
25	Piping	4 days		The state of the s		
26	Turbine Lube Oil System	11 days				
27	Turbine Lube Oil Tank	5 days				
28	Turbine Lube Oil Pumps	4 days				
29	Turbine Oil Mist Eliminator	2 days		i	<u> </u>	
30	Generator Auxiliary Systems	12 days				
31	Hydrogen Cooler Skid and Piping	2 days		,	<u> </u>	
32	Stator Cooling Water Skid and Piping	2 days			<u></u>	

D	Task Name	Duration	2012			2013	
			H2	H1	H2	H1	
33	Isophase Bus Duct	4 days			6		
34	Exciter Heat Exchanger	2 days			ή		
35	EHC Coolers	2 days			K		
36	Remove Turbine	48 days					
37	Remove Turbine	10 days					
38	Remove Generator	15 days					
39	Remove Condenser Neck Heat Exchanger	3 days			ή		
40	Remove Condenser	5 days			Κ		
41	Remove Misc. Auxiliary Turbine Equipment	15 days					
42	Cooling Tower 1	10 days					
43	Remove Cooling Tower 1	10 days			*		
44	Project Close-Out	5 days			•		
45	Project Close-Out Activities	5 days			7		

TURBINE GENERATOR 2

Lake Road T/G 2 Retirement

Owner Costs

Pre-Retirement Activities \$7,638
Retirement Activities \$26,641
Post-Retirement Activities \$3,320

Owner Direct Total \$37,599

Owner Internal Costs 5.00% \$1,880

Owner Contingency: 25.00% \$9,870

Lake Road T/G 2 Retirement Opinion of Probable Cost: \$49,349

lako Do	ad Turbina	Generator 2	Dotiromont
IAKP KO	an ilirnine	Generalor /	Kenremeni

ID	Task Name	Cost
1	Lake Road Turbine Generator 2 Retirement	\$37,599.30
2	Pre-Engineering	\$7,638.00
3	Engineering analysis and establish isolation points.	\$7,638.00
4	KCL&L Overhead Costs	\$13,631.20
5	KCP&L Retirement Manager	\$13,631.20
6	Retirement	\$13,009.60
7	Feedwater Piping	\$1,685.44
8	Drain water from the system and isolate from system.	\$842.72
9	Leave open vents and drains.	\$842.72
10	Turbine(s) and Condenser	\$4,385.68
11	Drain hotwell and leave doors open.	\$861.84
12	Open main turbine doors.	\$880.96
13	Remove lube oil.	\$2,642.88
14	Circulating Water System	\$0.00
15	Drain and Clean the Cooling Tower	\$0.00
16	Drain and Vent the Circulating Water Pipe	\$0.00
17	Drain, Clean and Vent the Cooling Tower Chemical Systems	\$0.00
18	Generator	\$6,095.76
19	Verify that generator circuit breaker is open and racked out or that	\$446.64
	high-voltage disconnect switch on substation side of GSU transformer is	
	locked in the open position.	
20	Verify that generator field breaker or contactor (if applicable) is open.	\$446.64
21	De-energize power supplies to generator excitation system at the source.	\$446.64
22	De-energize AC and DC power supplies to generator and exciter space heaters, cooling equipment, controls, lighting, etc. at the source and open circuit breakers or remove fuses at the generator and exciter.	\$446.64
23	Drain generator and exciter cooling water systems (if applicable).	\$861.84
24	Disconnect and remove hydrogen gas tanks and purge generator hydrogen system.	\$1,685.44
25	Disconnect and remove fire protection system gas/foam tanks and purge fire protection system.	\$1,761.92
26	Condenser Air Extraction	\$842.72
27	Drain water from system.	\$842.72
28	Post Retirement Activities	\$3,320.50
29	Post Retirement Activities	\$3,320.50

)	Task Name	Duration	4th Quarter	1st Quarter	2nd Quarter	3rd Qu
1	Lake Road Turbine Generator 2 Retirement	32 days			-	
2	Pre-Engineering	5 days		1		
3	Engineering analysis and establish isolation points.	5 days				
4	KCL&L Overhead Costs	22 days		-	—	
5	KCP&L Retirement Manager	22 days		🛊		
6	Retirement	22 days			—	
7	Feedwater Piping	2 days				
8	Drain water from the system and isolate from system.	1 day				
9	Leave open vents and drains.	1 day		Ϊ́		
10	Turbine(s) and Condenser	5 days				
11	Drain hotwell and leave doors open.	1 day		l K		
12	Open main turbine doors.	1 day				
13	Remove lube oil.	3 days				
14	Circulating Water System	7 days				
15	Drain and Clean the Cooling Tower	5 days				
16	Drain and Vent the Circulating Water Pipe	1 day			<u> </u>	
17	Drain, Clean and Vent the Cooling Tower Chemical System	s 1 day			K	
18	Generator	7 days				
19	Verify that generator circuit breaker is open and racked ou or that high-voltage disconnect switch on substation side of GSU transformer is locked in the open position.	ıt 0.5 days				
20	Verify that generator field breaker or contactor (if applicable) is open.	0.5 days			F	
21	De-energize power supplies to generator excitation system at the source.	n 0.5 days			Ĭ,	
22	De-energize AC and DC power supplies to generator and exciter space heaters, cooling equipment, controls, lighting, etc. at the source and open circuit breakers or remove fuses at the generator and exciter.	0.5 days			ř	
23	Drain generator and exciter cooling water systems (if applicable).	1 day				
24	Disconnect and remove hydrogen gas tanks and purge generator hydrogen system.	2 days			5	

Lake Road Turbine Generator 2 Retirement								
ID	Task Name	Duration	4th Quarter	1st Quarter	2nd Quarter	3rd Quarter		
25	Disconnect and remove fire protection system gas/foam tanks and purge fire protection system.	2 days						
26	Condenser Air Extraction	1 day						
27	Drain water from system.	1 day			Ϋ́			
28	Post Retirement Activities	5 days						
29	Post Retirement Activities	5 days						

Lake Road T/G 2 Dismantlement

Owner Costs

Pre-Dismantlement Activities \$172,583

Overhead During Dismantlement \$102,858

Post-Dismantlement Activities \$8,190

Owner Costs Total* \$283,631

Demolition General Contractor (DGC) Costs

 Site Management
 \$99,852

 Equipment Rental
 \$365,523

 Consummables
 \$364,674

 Scrap Crew(s)
 \$361,854

 Dismantlement
 \$236,840

Contractor Direct Cost* \$1,428,743

Contractor Allowances

DGC Insurance 2.00% \$28,575

Contingency/Profit 15.00% \$218,598

Performance Bond 2.00% \$33,518.31

Contractor Costs Total: \$1,709,434

Total: \$1,993,065

Owner Internal Costs: 5.00% \$99,653

Owner Contingency: 25.00% \$523,180

Lake Road T/G 2 Dismantlement Opinion of Probable Cost: \$2,615,898

^{*}Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances = \$1,712,374

1	Task Name	Cost
1 L	ake Road T/G 2 Removal	\$1,712,377.80
2	Pre-Dismantlement Activities	\$172,583.80
3	Hire Demolition General Contractor	\$167,184.00
4	KCP&L Prepares Unit for Dismantlement	\$5,399.80
5	Demolition Contractor Mobilizes on Site	\$0.00
6	KCP&L Overhead during Dismantlement	\$102,858.40
7	KCP&L Engineer	\$102,858.40
8	Demoliton Contractor Overhead during Dismantlement	\$99,852.64
9	Demolition Contractor Superintendent	\$99,852.64
10	Demolition Contractor Equipment Rental Costs	\$365,523.04
11	Equipment Rental	\$365,523.04
12	Scrap Crew(s)	\$361,854.72
13	Crew to Handle Scrap Material(s)	\$361,854.72
14	Demolition Contractor Consummables	\$364,674.64
15	Consummables	\$364,674.64
16	Dismantlement Directs	\$236,840.56
17	Phase 1 Demolition	\$236,840.56
18	Critical Piping	\$3,582.72
19	Remove Main Steam Piping to the Turbine	\$3,582.72
20	Circulating Water (plant side)	\$3,582.72
21	Waterboxes	\$3,582.72
22	Condenser Air Extraction System	\$3,582.72
23	Vacuum Pumps	\$3,582.72
24	Turbine Seals and Drains	\$7,165.44
25	Piping	\$7,165.44
26	Turbine Lube Oil System	\$18,443.76
27	Turbine Lube Oil Tank	\$7,695.60
28	Turbine Lube Oil Pumps	\$7,165.44
29	Turbine Oil Mist Eliminator	\$3,582.72
30	Generator Auxiliary Systems	\$21,496.32
31	Hydrogen Cooler Skid and Piping	\$3,582.72
32	Stator Cooling Water Skid and Piping	\$3,582.72
33	Isophase Bus Duct	\$7,165.44
34	Exciter Heat Exchanger	\$3,582.72
35	EHC Coolers	\$3,582.72
36	Remove Turbine	\$147,400.96
37	Remove Turbine	\$34,218.08
38	Remove Generator	\$44,746.72
39	Remove Condenser Neck Heat Exchanger	\$7,896.48
40	Remove Condenser	\$15,792.96
41	Remove Misc. Auxiliary Turbine Equipment	\$44,746.72
42	Cooling Tower 2	\$31,585.92
43	Remove Cooling Tower 2	\$31,585.92
44	Project Close-Out	\$8,190.00

[., <u>.</u>				
	oad Turbine Generator 2 Dismantlement			
ID	Task Name	Cost		
45	Project Close-Out Activities	\$8,190.00		
		Page 2		

)	Task Name	Duration		2012	
			H2	H1	H
1	Lake Road T/G 2 Removal	181 days			
2	Pre-Dismantlement Activities	75 days		•	
3	Hire Demolition General Contractor	3 mons			
4	KCP&L Prepares Unit for Dismantlement	1 wk			
5	Demolition Contractor Mobilizes on Site	5 days			
6	KCP&L Overhead during Dismantlement	101 days			
7	KCP&L Engineer	101 days			
8	Demoliton Contractor Overhead during Dismantlem	en 101 days			
9	Demolition Contractor Superintendent	101 days			
10	Demolition Contractor Equipment Rental Costs	101 days			
11	Equipment Rental	101 days			
12	Scrap Crew(s)	101 days			
13	Crew to Handle Scrap Material(s)	101 days			
14	Demolition Contractor Consummables	101 days			
15	Consummables	101 days			
16	Dismantlement Directs	101 days			
17	Phase 1 Demolition	101 days			
18	Critical Piping	2 days			
19	Remove Main Steam Piping to the Turbine	2 days		The state of the s	
20	Circulating Water (plant side)	2 days			
21	Waterboxes	2 days		<u> </u>	
22	Condenser Air Extraction System	2 days			
23	Vacuum Pumps	2 days		The state of the s	
24	Turbine Seals and Drains	4 days		•	
25	Piping	4 days		<u> </u>	
26	Turbine Lube Oil System	11 days			
27	Turbine Lube Oil Tank	5 days			,)
28	Turbine Lube Oil Pumps	4 days			
29	Turbine Oil Mist Eliminator	2 days			†
30	Generator Auxiliary Systems	12 days			
31	Hydrogen Cooler Skid and Piping	2 days			†
32	Stator Cooling Water Skid and Piping	2 days			*

D	Task Name	Duration		2012		2013
			H2	H1	H2	H1
33	Isophase Bus Duct	4 days			5	
34	Exciter Heat Exchanger	2 days			Ϋ́	
35	EHC Coolers	2 days			ή	
36	Remove Turbine	56 days			▼	
37	Remove Turbine	13 days				
38	Remove Generator	17 days				
39	Remove Condenser Neck Heat Exchanger	3 days			$\overline{\mathbf{h}}$	
40	Remove Condenser	6 days			*	
41	Remove Misc. Auxiliary Turbine Equipment	17 days			—	
42	Cooling Tower 2	12 days			-	
43	Remove Cooling Tower 2	12 days			*	
44	Project Close-Out	5 days			•	
45	Project Close-Out Activities	5 days			7	

TURBINE GENERATOR 3

Lake Road T/G 3 Retirement

Owner Costs

Pre-Retirement Activities \$7,638
Retirement Activities \$22,304
Post-Retirement Activities \$3,320

Owner Direct Total \$33,262

Owner Internal Costs 5.00% \$1,663

Owner Contingency: 25.00% \$8,731

\$43,656

Lake Road T/G 3 Retirement Opinion of Probable Cost:

Lake Road	Turhing	Generator 3	Retirement

ID	Task Name	Cost
1	Lake RoadTurbine Generator 3 Retirement	\$33,262.10
2	Pre-Engineering	\$7,638.00
3	Engineering analysis and establish isolation points.	\$7,638.00
4	KCL&L Overhead Costs	\$9,294.00
5	KCP&L Retirement Manager	\$9,294.00
6	Retirement	\$13,009.60
7	Feedwater Piping	\$1,685.44
8	Drain water from the system and isolate from system.	\$842.72
9	Leave open vents and drains.	\$842.72
10	Turbine(s) and Condenser	\$4,385.68
11	Drain hotwell and leave doors open.	\$861.84
12	Open main turbine doors.	\$880.96
13	Remove lube oil.	\$2,642.88
14	Generator	\$6,095.76
15	Verify that generator circuit breaker is open and racked out or that high-voltage disconnect switch on substation side of GSU transformer is locked in the open position.	\$446.64
16	Verify that generator field breaker or contactor (if applicable) is open.	\$446.64
17	De-energize power supplies to generator excitation system at the source.	\$446.64
18	De-energize AC and DC power supplies to generator and exciter space heaters, cooling equipment, controls, lighting, etc. at the source and open circuit breakers or remove fuses at the generator and exciter.	\$446.64
19	Drain generator and exciter cooling water systems (if applicable).	\$861.84
20	Disconnect and remove hydrogen gas tanks and purge generator hydrogen system.	\$1,685.44
21	Disconnect and remove fire protection system gas/foam tanks and purge fire protection system.	\$1,761.92
22	Condenser Air Extraction	\$842.72
23	Drain water from system.	\$842.72
24	Post Retirement Activities	\$3,320.50
25	Post Retirement Activities	\$3,320.50

	Task Name	Duration	4th Quarter	
1	Lake RoadTurbine Generator 3 Retirement	25 days	,	
2	Pre-Engineering	5 days		
3	Engineering analysis and establish isolation points.	5 days		
4	KCL&L Overhead Costs	15 days		
5	KCP&L Retirement Manager	15 days		
5	Retirement	15 days		
7	Feedwater Piping	2 days		
3	Drain water from the system and isolate from system.	1 day		
9	Leave open vents and drains.	1 day		
10	Turbine(s) and Condenser	5 days		
L1	Drain hotwell and leave doors open.	1 day		
2	Open main turbine doors.	1 day		
.3	Remove lube oil.	3 days		
L4	Generator	7 days		
.5	Verify that generator circuit breaker is open and racked ou or that high-voltage disconnect switch on substation side of GSU transformer is locked in the open position.	t0.5 days		
16	Verify that generator field breaker or contactor (if applicable) is open.	0.5 days		
17	De-energize power supplies to generator excitation system at the source.	0.5 days		
8	De-energize AC and DC power supplies to generator and exciter space heaters, cooling equipment, controls, lighting, etc. at the source and open circuit breakers or remove fuses at the generator and exciter.	0.5 days		
19	Drain generator and exciter cooling water systems (if applicable).	1 day		
20	Disconnect and remove hydrogen gas tanks and purge generator hydrogen system.	2 days		
21	Disconnect and remove fire protection system gas/foam tanks and purge fire protection system.	2 days		
22	Condenser Air Extraction	1 day		
:3	Drain water from system.	1 day		

Post Retirement Activities 5 days Post Retirement Activities 5 days	Post Retirement Activities 5 days	Post Retirement Activities 5 days		Task Name	Duration	4th Quarter	1st Quarter	2nd Quarter
Post Retirement Activities 5 days	Post Retirement Activities 5 days	Post Retirement Activities 5 days	1	Post Retirement Activities	5 days			
			5	Post Retirement Activities	5 days			

Lake Road T/G 3 Dismantlement

Owner Costs

Pre-Dismantlement Activities \$172,583

Overhead During Dismantlement \$71,288

Post-Dismantlement Activities \$8,190

Owner Costs Total* \$252,061

Demolition General Contractor (DGC) Costs

 Site Management
 \$69,204

 Equipment Rental
 \$253,332

 Consummables
 \$252,744

 Scrap Crew(s)
 \$250,790

 Dismantlement
 \$156,925

Contractor Direct Cost* \$982,995

Contractor Allowances

DGC Insurance 2.00% \$19,660

Contingency/Profit 15.00% \$150,398

Performance Bond 2.00% \$23,061

Contractor Costs Total: \$1,176,114

Total: \$1,428,175

Owner Internal Costs: 5.00% \$71,409

Owner Contingency: 25.00% \$374,896

Lake Road T/G 3 Dismantlement Opinion of Probable Cost: \$1,874,480

^{*}Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances = \$1,235,056

)	Task Name	Cost
1	Lake Road T/G 3 Removal	\$1,235,059.80
2	Pre-Dismantlement Activities	\$172,583.80
3	Hire Demolition General Contractor	\$167,184.00
4	KCP&L Prepares Unit for Dismantlement	\$5,399.80
5	Demolition Contractor Mobilizes on Site	\$0.00
6	KCP&L Overhead during Dismantlement	\$71,288.00
7	KCP&L Engineer	\$71,288.00
8	Demoliton Contractor Overhead during Dismantlement	\$69,204.80
9	Demolition Contractor Superintendent	\$69,204.80
10	Demolition Contractor Equipment Rental Costs	\$253,332.80
11	Equipment Rental	\$253,332.80
12	Demolition Contractor Consummables	\$252,744.80
13	Consummables	\$252,744.80
14	Scrap Crew(s)	\$250,790.40
15	Crew to Handle Scrap Material(s)	\$250,790.40
16	Dismantlement Directs	\$156,925.20
17	Phase 1 Demolition	\$156,925.20
18	Critical Piping	\$3,582.72
19	Remove Main Steam Piping to the Turbine	\$3,582.72
20	Circulating Water (plant side)	\$3,582.72
21	Waterboxes	\$3,582.72
22	Condenser Air Extraction System	\$3,582.72
23	Vacuum Pumps	\$3,582.72
24	Turbine Seals and Drains	\$7,165.44
25	Piping	\$7,165.44
26	Turbine Lube Oil System	\$18,443.76
27	Turbine Lube Oil Tank	\$7,695.60
28	Turbine Lube Oil Pumps	\$7,165.44
29	Turbine Oil Mist Eliminator	\$3,582.72
30	Generator Auxiliary Systems	\$17,913.60
31	Hydrogen Cooler Skid and Piping	\$1,791.36
32	Stator Cooling Water Skid and Piping	\$3,582.72
33	Isophase Bus Duct	\$5,374.08
34	Exciter Heat Exchanger	\$3,582.72
35	EHC Coolers	\$3,582.72
36	Remove Turbine	\$102,654.24
37	Remove Turbine	\$21,057.28
38	Remove Generator	\$34,218.08
39	Remove Condenser Neck Heat Exchanger	\$7,896.48
40	Remove Condenser	\$13,160.80
41	Remove Misc. Auxiliary Turbine Equipment	\$26,321.60
42	Project Close-Out	\$8,190.00
43	Project Close-Out Activities	\$8,190.00

Tas	sk Name	Duration		2012		2013
			H2	H1	H2	Н
	ke Road T/G 3 Removal	150 days				
	Pre-Dismantlement Activities	75 days				
3	Hire Demolition General Contractor	3 mons				
4	KCP&L Prepares Unit for Dismantlement	1 wk				
5	Demolition Contractor Mobilizes on Site	5 days				
6	KCP&L Overhead during Dismantlement	70 days				
7	KCP&L Engineer	70 days				
8	Demoliton Contractor Overhead during Dismantlem	en 70 days				
9	Demolition Contractor Superintendent	70 days				
10	Demolition Contractor Equipment Rental Costs	70 days				
11	Equipment Rental	70 days				
12	Demolition Contractor Consummables	70 days			——————————————————————————————————————	
13	Consummables	70 days				
14	Scrap Crew(s)	70 days				
15	Crew to Handle Scrap Material(s)	70 days				
16	Dismantlement Directs	70 days				
17	Phase 1 Demolition	70 days				
18	Critical Piping	2 days				
19	Remove Main Steam Piping to the Turbine	2 days		, in the second		
20	Circulating Water (plant side)	2 days				
21	Waterboxes	2 days		, in the second		
22	Condenser Air Extraction System	2 days				
23	Vacuum Pumps	2 days		<u> </u>		
24	Turbine Seals and Drains	4 days				
25	Piping	4 days		*		
26	Turbine Lube Oil System	11 days				
27	Turbine Lube Oil Tank	5 days				
28	Turbine Lube Oil Pumps	4 days				
29	Turbine Oil Mist Eliminator	2 days				
30	Generator Auxiliary Systems	10 days		•	-	
31	Hydrogen Cooler Skid and Piping	1 day		The state of the s		
32	Stator Cooling Water Skid and Piping	2 days				

)	Task Name	Duration		2012		2013
			H2	H1	H2	H1
33	Isophase Bus Duct	3 days			ή	
34	Exciter Heat Exchanger	2 days			ή	
35	EHC Coolers	2 days			Image: Control of the control of the	
36	Remove Turbine	39 days				
37	Remove Turbine	8 days				
38	Remove Generator	13 days				
39	Remove Condenser Neck Heat Exchanger	3 days			†	
40	Remove Condenser	5 days			*	
41	Remove Misc. Auxiliary Turbine Equipment	10 days			*	
42	Project Close-Out	5 days			•	
43	Project Close-Out Activities	5 days			*	

COMBUSTION TURBINE 5

Lake Road CT 5 Retirement

Owner Costs

Pre-Retirement Activities \$43,834
Retirement Activities \$93,370
Post-Retirement Activities \$22,576

Owner Direct Total \$159,780

Owner Internal Costs 5.00% \$7,989

Owner Contingency: 25.00% \$41,942

Lake Road CT 5 Retirement Opinion of Probable Cost: \$209,711

	Task Name	Cost
1	Lake Road CT 5 Retirement	\$159,780.68
2	Pre-Retirement Activities	\$43,834.00
3	Permitting Review	\$23,466.00
4	Develop Detailed Retirement Plan	\$20,368.00
5	Retirement	\$93,370.68
6	Project Management During Retirement	\$43,309.08
7	Project Management During Retirement	\$43,309.08
8	Retirement Activities	\$50,061.60
9	Electrical	\$27,691.68
10	Medium and Low Voltage Drawout Switchgear	\$5,359.68
11	De-energize all buses at the source.	\$893.28
12	Open all circuit breakers.	\$893.28
13	Rack all circuit breakers into the fully withdrawn,	\$893.28
	disconnected position.	
14	Verify that the closing/tripping springs are discharged.	\$1,786.56
15	De-energize control power and auxiliary power circuits of	\$893.28
	each circuit breaker at the source and by opening control	
	power circuit breakers or removing fuses in each breaker	
	cubicle.	
16	Motor Control Centers	\$2,679.84
17	De-energize all buses at the source.	\$893.28
18	Open all circuit breakers and disconnect switches.	\$893.28
19	Remove all fuses in control circuits.	\$893.28
20	Low-voltage Switchboards and Panelboards	\$1,786.56
21	De-energize all buses at the source.	\$893.28
22	Open all circuit breakers and disconnect switches.	\$893.28
23	Oil-Filled Power Transformers	\$7,146.24
24	De-energize all buses at the source.	\$893.28
25	Open all circuit breakers and disconnect switches.	\$893.28
26	De-energize all buses at the source.	\$893.28
27	Open all circuit breakers and disconnect switches.	\$4,466.40
28	Dry-type Power Transformers	\$4,466.40
29	De-energize all transformer primaries and verify that the	\$893.28
	secondary is de-energized.	·
30	De-energize all low-voltage AC or DC power sources for space	\$3,573.12
	heaters, cooling equipment, controls, etc. at the source and	. ,
	open circuit breakers or remove fuses at transformer end.	
31	Motors	\$6,252.96
32	De-energize all primary power at the source.	\$893.28
33	De-energize all low-voltage power sources for space heaters	\$893.28
	or other auxiliary equipment at the source.	
34	Drain lube oil system (if applicable) and dispose of oil.	\$4,466.40
35	Fuel System	\$3,466.80

Lake Ro	oad CT 5 Retirement	
D	Task Name	Cost
36	Isolate Fuel Oil System	\$2,604.96
37	Drain and Vent Fuel Oil Piping	\$861.84
38	Open and vent gas piping.	\$0.00
39	Lube Oil Cooling Water System	\$2,585.52
40	Open and Drain the Water Side of the Lube Oil Coolers	\$1,723.68
41	Open and Vent the Coolers and Expansion Tank	\$861.84
42	Miscelleaneous Piping	\$4,309.20
43	Open and Vent the Exhaust Frame Cooling Piping	\$861.84
44	Open & Vent the CT Air Process Piping	\$861.84
45	Open and Vent the CT Air Processing Piping	\$2,585.52
46	Fire Protection Piping	\$3,428.24
47	Empty the CO2 Storage Tank	\$2,566.40
48	Open and Vent the Fire Protection Piping	\$861.84
49	Lube Oil System	\$8,580.16
50	Empty and Remove from Site the Lubricating Oil	\$5,132.80
51	Drain Lubricating Oil Piping	\$1,723.68
52	Open and Vent Lubricating Oil Piping	\$1,723.68
53	Post Retirement Closure Activity	\$22,576.00
54	Post Retirement Closure Activity	\$22,576.00

	Task Name	Duration	3rd Quarte	r		4th Quart	er		1st Qua	rter		
			Jul	Aug	Sep	Oct	Nov	Dec	Jan	Fe	eb	Ma
1	Lake Road CT 5 Retirement	114 days										Ψ.
2	Pre-Retirement Activities	40 days										
3	Permitting Review	20 days					KCP&L Pro	ject Man	ager[25%]	KCP&L	Engine	er[20
4	Develop Detailed Retirement Plan	20 days										
5	Retirement	54 days										
6	Project Management During Retirement	54 days										
7	Project Management During Retirement	54 days										
8	Retirement Activities	54 days										
9	Electrical	31 days										
10	Medium and Low Voltage Drawout Switchgear	6 days						—				
11	De-energize all buses at the source.	1 day					K					
12	Open all circuit breakers.	1 day					F					
13	Rack all circuit breakers into the fully withdrawn, disconnected	1 day					Ĥ					
14	Verify that the closing/tripping springs are discharged.	2 days					`					
15	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each	1 day										
16	Motor Control Centers	3 days										
17	De-energize all buses at the source.	1 day						ħ				
18	Open all circuit breakers and disconnect switches.	1 day										
19	Remove all fuses in control circuits.	1 day						Τ,				
20	Low-voltage Switchboards and Panelboards	2 days						•				
21	De-energize all buses at the source.	1 day						†				
22	Open all circuit breakers and disconnect switches.	1 day						7				
23	Oil-Filled Power Transformers	8 days										

)	Task Name	Duration	3rd Quarte	er		4th Qu	uarter			1st Qua	rter			
			Jul	Aug	Sep	Oct	t	Nov	Dec	Jan		Feb	Щ	Mai
24	De-energize all buses at the source.	1 day							Ľ					
25	Open all circuit breakers and disconnect switches.	1 day												
26	De-energize all buses at the source.	1 day							ኻ					
27	Open all circuit breakers and disconnect switches.	5 days												
28	Dry-type Power Transformers	5 days							-					
29	De-energize all transformer primaries and verify that the secondary is de-energized.	1 day							Ť					
30	De-energize all low-voltage AC or DO power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	·							¥					
31	Motors	7 days							•					
32	De-energize all primary power at the source.	1 day												
33	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	1 day												
34	Drain lube oil system (if applicable) and dispose of oil.	5 days												
35	Fuel System	4 days												
36	Isolate Fuel Oil System	2 days								Ť				
37	Drain and Vent Fuel Oil Piping	1 day								Ť				
38	Open and vent gas piping.	1 day								Ϋ́				
39	Lube Oil Cooling Water System	3 days								•				
40	Open and Drain the Water Side of the Lube Oil Coolers	2 days												
41	Open and Vent the Coolers and Expansion Tank	1 day								Ť				
42	Miscelleaneous Piping	5 days												

D	Task Name	Duration	3rd Quarte	er		4th Quarte	er		1st Quarte	er	
			Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar
43	Open and Vent the Exhaust Frame	1 day							T ₁		
	Cooling Piping										
44	Open & Vent the CT Air Process Piping	1 day							Ķ		
45	Open and Vent the CT Air Processing	3 days							*		
	Piping										
46	Fire Protection Piping	3 days							•	,	
47	Empty the CO2 Storage Tank	2 days							T)	
48	Open and Vent the Fire Protection Pipir	1 day							F		
49	Lube Oil System	8 days							•		
50	Empty and Remove from Site the	4 days									
	Lubricating Oil										
51	Drain Lubricating Oil Piping	2 days								5	
52	Open and Vent Lubricating Oil Piping	2 days								*	
53	Post Retirement Closure Activity	20 days									→
54	Post Retirement Closure Activity	20 days								*	

Lake Road CT 5 Dismantlement

Owner Costs

Pre-Dismantlement Activities\$242,211Overhead During Dismantlement\$95,729Post-Dismantlement Activities\$16,380

Owner Costs Total* \$354,320

Demolition General Contractor (DGC) Costs

 Site Management
 \$199,791

 Equipment Rental
 \$340,189

 Consummables
 \$339,400

 Scrap Crew(s)
 \$89,352

 Dismantlement
 \$272,506

Contractor Direct Cost* \$1,241,238

Contractor Allowances

DGC Insurance 2.00% \$24,825

Contingency/Profit 15.00% \$189,909

Performance Bond 2.00% \$29,119

Contractor Costs Total: \$1,485,092

Total: \$1,839,412

Owner Internal Costs: 5.00% \$91,971

Owner Contingency: 25.00% \$482,846

Lake Road CT 5 Dismantlement Opinion of Probable Cost: \$2,414,228

^{*}Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances = \$1,595,558

D	Task Name	Cost
1	Lake Road CTG 5 Dismantlement	\$1,595,561.08
2	Pre-Demolition Activities	\$242,211.32
3	Detailed Planning & Hire Owner's Engineer	\$69,627.52
4	Hire Demolition general Contractor	\$167,184.00
5	KCP&L Prepares Unit for Dismantlement	\$5,399.80
6	Demolition Contractor Mobilizes on Sit	\$0.00
7	KCP&L Overhead during Dismantlement	\$95,729.60
8	KCP&L Engineer	\$95,729.60
9	Demolition Contractor Overhead during Dismantlement	\$199,791.36
10	Demolition Contractor Project Manager	\$56,527.84
11	Demolition Contractor Safety Manager	\$50,331.36
12	Demolition Contractor Superintendent	\$92,932.16
13	Demolition Contractor Equipment Rental Cost	\$340,189.76
14	Equipment Rental	\$340,189.76
15	Demolition Contractor Consumables	\$339,400.16
16	Consumables	\$339,400.16
17	Scrap Crews	\$89,352.64
18	Crew to Handle Scrap Material(s)	\$89,352.64
19	Dismantlement	\$272,506.24
20	Electrical	\$107,481.60
21	Electrical Demolition of Equipment	\$107,481.60
22	Fuel Gas System	\$10,967.68
23	Remove all above grade fuel gas piping.	\$2,010.88
24	Gas Filter Skid	\$5,374.08
25	Remove all above grade fuel oil piping	\$3,582.72
26	Lube Oil System	\$17,913.60
27	Lube Oil Piping	\$5,374.08
28	Lube Oil Pumps	\$5,374.08
29	Lube Oil Tanks	\$7,165.44
30	Fire Protection	\$26,870.40
31	Fire Protection Piping	\$10,748.16
32	Firewater Tank	\$8,956.80
33	CO2 Storage Tank	\$7,165.44
34	Generator	\$7,165.44
35	Generator	\$7,165.44
36	Combustion Turbine	\$75,237.12
37	Inlet duct	\$8,956.80
38	Exhaust duct	\$12,539.52
39	Combustion Turbine	\$28,661.76
40	Combustion Turbine Foundation	\$16,122.24
41	Enclosure	\$8,956.80
42	Stack	\$26,870.40
43	Stack	\$26,870.40
44	Post Dismantlement Activities	\$16,380.00

Lake R	oad CTG 5 Dismantlement		
ID	Task Name	Cost	
45	Post Dismantlement Activities	\$16,380.00	
	Page 2		

)	Task Name	Duration	1st Quarter	
			Jan	Jan
1	Lake Road CTG 5 Dismantlement	319 days		
2	Pre-Demolition Activities	60 days		
3	Detailed Planning & Hire Owner's Engineer	2 mons		
4	Hire Demolition general Contractor	3 mons		
5	KCP&L Prepares Unit for Dismantlement	1 wk		I
6	Demolition Contractor Mobilizes on Sit	5 days		1
7	KCP&L Overhead during Dismantlement	94 days		-
8	KCP&L Engineer	94 days		
9	Demolition Contractor Overhead during Dismantlement	94 days		-
10	Demolition Contractor Project Manager	94 days		
11	Demolition Contractor Safety Manager	94 days		
12	Demolition Contractor Superintendent	94 days		
13	Demolition Contractor Equipment Rental Cost	94 days		-
14	Equipment Rental	94 days		
15	Demolition Contractor Consumables	94 days		
16	Consumables	94 days		
17	Scrap Crews	94 days		-
18	Crew to Handle Scrap Material(s)	94 days		
19	Dismantlement	94 days		
20	Electrical	60 days		
21	Electrical Demolition of Equipment	60 days		
22	Fuel Gas System	8 days		
23	Remove all above grade fuel gas piping.	3 days		
24	Gas Filter Skid	3 days		
25	Remove all above grade fuel oil piping	2 days		
26	Lube Oil System	10 days		
27	Lube Oil Piping	3 days		
28	Lube Oil Pumps	3 days		
29	Lube Oil Tanks	4 days		
30	Fire Protection	15 days		
31	Fire Protection Piping	6 days		

D	Task Name	Duration	1st Quarter		1st Quarter
			Jan	Jan	Jan
32	Firewater Tank	5 days		, j	
33	CO2 Storage Tank	4 days		<u> </u>	
34	Generator	4 days		-	
35	Generator	4 days		, in the second	
36	Combustion Turbine	42 days			▼
37	Inlet duct	5 days		F	
38	Exhaust duct	7 days		F	
39	Combustion Turbine	16 days			
40	Combustion Turbine Foundation	9 days			<u> </u>
41	Enclosure	5 days			ř
42	Stack	15 days			
43	Stack	15 days			†
44	Post Dismantlement Activities	10 days			
45	Post Dismantlement Activities	10 days			*



Lake Road CT 6 & 7 Retirement

Owner Costs

Pre-Retirement Activities \$69,498
Retirement Activities \$29,491
Post-Retirement Activities \$22,576

Owner Direct Total \$121,565

Owner Internal Costs 5.00% \$6,078

Owner Contingency: 25.00% \$31,911

Lake Road CT 6 & 7 Retirement Opinion of Probable Cost: \$159,554

ID	Task Name	Cost
1	Lake Road CTG 6 and 7 Retirement	\$121,565.68
2	Pre-Retirement Activities	\$69,498.64
3	Permitting Review	\$23,466.00
4	Develop Detailed Retirement Plan	\$20,368.00
5	Project Management During Retirement	\$25,664.64
6	Project Management During Retirement	\$25,664.64
7	Retirement Activities	\$29,491.04
8	Electrical	\$17,865.60
9	Medium and Low Voltage Drawout Switchgear	\$4,466.40
10	De-energize all buses at the source.	\$893.28
11	Open all circuit breakers.	\$893.28
12	Rack all circuit breakers into the fully withdrawn, disconnected position.	\$893.28
13	Verify that the closing/tripping springs are discharged.	\$893.28
14	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each breaker cubicle.	\$893.28
15	Motor Control Centers	\$4,466.40
16	De-energize all buses at the source.	\$893.28
17	Open all circuit breakers and disconnect switches.	\$1,786.56
10	Demons all frace in control circuits	¢1 706 F6

5	Project Management During Retirement	\$25,664.64
6	Project Management During Retirement	\$25,664.64
7	Retirement Activities	\$29,491.04
8	Electrical	\$17,865.60
9	Medium and Low Voltage Drawout Switchgear	\$4,466.40
10	De-energize all buses at the source.	\$893.28
11	Open all circuit breakers.	\$893.28
12	Rack all circuit breakers into the fully withdrawn, disconnected position.	\$893.28
13	Verify that the closing/tripping springs are discharged.	\$893.28
14	De-energize control power and auxiliary power circuits of each circuit	\$893.28
	breaker at the source and by opening control power circuit breakers or removing fuses in each breaker cubicle.	
15	Motor Control Centers	\$4,466.40
16	De-energize all buses at the source.	\$893.28
17	Open all circuit breakers and disconnect switches.	\$1,786.56
18	Remove all fuses in control circuits.	\$1,786.56
19	Low-voltage Switchboards and Panelboards	\$2,679.84
20	De-energize all buses at the source.	\$893.28
21	Open all circuit breakers and disconnect switches.	\$1,786.56
22	Motors	\$6,252.96
23	De-energize all primary power at the source.	\$893.28
24	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	\$893.28
25	Drain lube oil system (if applicable) and dispose of oil.	\$4,466.40
26	Fuel Oil System	\$3,026.16
27	Isolate Fuel Oil System	\$1,302.48
28	Drain and Vent Fuel Oil Piping	\$1,302.46
29	Lube Oil Cooling Water System	\$2,585.52
30	Open and Drain the Water Side of the Lube Oil Coolers	\$1,723.68
31	Open and Vent the Coolers and Expansion Tank	\$1,723.08
32	Lube Oil System	\$6,013.76
33	Empty and Remove from Site the Lubricating Oil	\$2,566.40
34	Drain Lubricating Oil Piping	\$2,585.52
35	Open and Vent Lubricating Oil Piping	\$861.84
36	Post Retirement Closure Activity	\$22,576.00
37	Post Retirement Closure Activity	\$22,576.00

)	Task Name	Duration			Quarter		l Quart		4th Qւ		1st Q			uarter
	Labo Bood CTC Count 7 Betimen and	02 -1	Mar	Apr	May Jur	ı Ju	ıl Au	g Sep	Oct	Nov Dec	Jan	Feb Ma	ar Apr	May Jur
1	Lake Road CTG 6 and 7 Retirement	92 days												Ψ
2	Pre-Retirement Activities	72 days										VCD81 D	roject Ma	11220r[3E
3	Permitting Review	20 days										KCPQLP	roject ivia	mager[259
4	Develop Detailed Retirement Plan	20 days												
5	Project Management During Retirement	32 days												
6	Project Management During Retirement	32 days												
7	Retirement Activities	32 days												
8	Electrical	20 days												
9	Medium and Low Voltage Drawout Switchgear	5 days												
10	De-energize all buses at the source.	1 day										<u>L</u>		
11	Open all circuit breakers.	1 day										Ь		
12	Rack all circuit breakers into the fully withdrawn, disconnected position.	1 day										h		
13	Verify that the closing/tripping springs are discharged.	1 day										, in the second		
14	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each breaker cubicle.	1 day										K		
15	Motor Control Centers	5 days												
16	De-energize all buses at the source.	1 day										, if		
17	Open all circuit breakers and disconnect switches.	2 days												
18	Remove all fuses in control circuits.	2 days										*		
19	Low-voltage Switchboards and Panelboards	3 days										•		
20	De-energize all buses at the source.	1 day										, ,	•	
21	Open all circuit breakers and disconnect switches.	2 days										ŀ		
22	Motors	7 days												

ID	Task Name	Duration		2nd	Quar	ter	3rd Q	uarter		4th Q	uarter	1st	Quarter	r	2nd Qu	ıarter	
			Mar		Ma			Aug	Sep				n Feb		1		
23	De-energize all primary power at the source.	1 day							·					Ь			
24	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	1 day												Ř			
25	Drain lube oil system (if applicable) and dispose of oil.	5 days												*			
26	Fuel Oil System	3 days												•			
27	Isolate Fuel Oil System	1 day															
28	Drain and Vent Fuel Oil Piping	2 days)			
29	Lube Oil Cooling Water System	3 days												•			
30	Open and Drain the Water Side of the Lube Oil Coolers	2 days															
31	Open and Vent the Coolers and Expansion Tank	1 day													ř		
32	Lube Oil System	6 days												ı			
33	Empty and Remove from Site the Lubricating Oil	2 days															
34	Drain Lubricating Oil Piping	3 days													4		
35	Open and Vent Lubricating Oil Piping	1 day													K		
36	Post Retirement Closure Activity	20 days														þ	
37	Post Retirement Closure Activity	20 days															

Lake Road CT 6 & 7 Dismantlement

Own	ωr	Costs
COVI		CO515

Pre-Dismantlement Activities \$191,883

Overhead During Dismantlement \$99,918

Post-Dismantlement Activities \$32,760

Owner Costs Total* \$324,561

Demolition General Contractor (DGC) Costs

 Site Management
 \$129,651

 Equipment Rental
 \$220,761

 Consummables
 \$220,249

 Scrap Crew(s)
 \$57,984

 Dismantlement
 \$160,911

Contractor Direct Cost* \$789,556

Contractor Allowances

DGC Insurance 2.00% \$15,791

Contingency/Profit 15.00% \$120,802

Performance Bond 2.00% \$18,523

Contractor Costs Total: \$944,672

Total: \$1,269,233

Owner Internal Costs: 5.00% \$63,462

Owner Contingency: 25.00% \$333,174

Lake Road CT 6 & 7 Dismantlement Opinion of Probable Cost: \$1,665,869

^{*}Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances = \$1,114,117

Lake Road CT 6 and 7 Dismantlement ID Cost Task Name Lake Road CT 6 and 7 Dismantlement \$1,114,119.36 1 2 \$191,883.12 **Pre-Demolition Activities** 3 \$69,627.52 **Detailed Planning** 4 Hire Demolition general Contractor \$111,456.00 5 \$10,799.60 KCP&L Prepares Unit for Dismantlement 6 Demolition Contractor Mobilizes on Site \$0.00 7 **KCP&L Overhead during Dismantlement** \$99,918.00 8 KCP&L Project Manager \$37,795.60 9 KCP&L Engineer \$62,122.40 10 **Demolition Contractor Overhead during Dismantlement** \$129,651.84 11 **Demolition Contractor Project Manager** \$36,682.96 12 **Demolition Contractor Safety Manager** \$32,661.84 13 **Demolition Contractor Superintendent** \$60,307.04 14 **Demolition Contractor Equipment Rental Cost** \$220,761.44 15 **Equipment Rental** \$220,761.44 16 **Demolition Contractor Consumables** \$220,249.04 17 Consumables \$220,249.04 18 \$57,984.16 **Scrap Crews** 19 Crew to Handle Scrap Material(s) \$57,984.16 20 Dismantlement \$160,911.76 21 **Electrical** \$53,740.80 22 **Electrical Demolition of Equipment** \$53,740.80 23 **Fuel Oil System** \$1,480.72 24 Remove all above grade fuel oil piping. \$1,480.72 25 **Lube Oil System** \$10,748.16 26 **Lube Oil Piping** \$1,791.36 27 Lube Oil Pumps \$3,582.72 \$5 374 08 28 **Lube Oil Tanks** 29 **Fire Protection** 30 Fire Protection Piping 31 CO2 Storage Tank 32 Generator

33

34

35

36

37

38

39

40

41

42

43

Stack

Combustion Turbine


Post Dismantlement Activities

Post Dismantlement Activities

Lube Oil Tanks	\$5,374.08
Fire Protection	\$10,748.16
Fire Protection Piping	\$3,582.72
CO2 Storage Tank	\$7,165.44
enerator	\$17,913.60
Generators	\$17,913.60
Combustion Turbine	\$62,697.60
Inlet ducts	\$7,165.44
Exhaust ducts	\$7,165.44
Combustion Turbines	\$17,913.60
Combustion Turbine Foundation	\$21,496.32
Combustion Turbine Enclosure Building	\$8,956.80
Stack	\$3,582.72
Stacks	\$3,582.72
t Dismantlement Activities	\$32,760.00
ost Dismantlement Activities	\$32,760.00
Page 1	

	Task Name	Duration	2012						2013 2014
1	Lake Dood CT C and 7 Dismonthers and	C22 dave	Qtr 1	Qtr	2 Qtr 3 Qtr 4	2 Qtr 3 Qtr 4 Qtr 1 Qtr 2 Qt	2 Qtr 3 Qtr 4 Qtr 1 Qtr 2 Qtr 3 Qtr 4	2 Qtr 3 Qtr 4 Qtr 1 Qtr 2 Qtr 3 Qtr 4 Qtr 1 Qtr 2 Q	2 Qtr 3 Qtr 4 Qtr 1 Qtr 2 Qtr 3 Qtr 4 Qtr 1 Qtr 2 Qtr 3 Qt
1	Lake Road CT 6 and 7 Dismantlement	633 days							
2	Pre-Demolition Activities	95 days							
3	Detailed Planning	2 mons							
4	Hire Demolition general Contractor	2 mons							
5	KCP&L Prepares Unit for Dismantlement	2 wks				•	•	•	•
5	Demolition Contractor Mobilizes on Site	5 days				۴	Ť	ή	ď
7	KCP&L Overhead during Dismantlement	61 days							
8	KCP&L Project Manager	61 days							
9	KCP&L Engineer	61 days							
10	Demolition Contractor Overhead during Dismantle	mer 61 days					-		
11	Demolition Contractor Project Manager	61 days							
12	Demolition Contractor Safety Manager	61 days							
13	Demolition Contractor Superintendent	61 days							
14	Demolition Contractor Equipment Rental Cost	61 days			ľ				—
15	Equipment Rental	61 days							
16	Demolition Contractor Consumables	61 days							
17	Consumables	61 days							
18	Scrap Crews	61 days			-				-
19	Crew to Handle Scrap Material(s)	61 days							
20	Dismantlement	61 days			—				
21	Electrical	30 days			—	-	-	-	-
22	Electrical Demolition of Equipment	30 days							
23	Fuel Oil System	2 days							
24	Remove all above grade fuel oil piping.	2 days			F				
25	Lube Oil System	6 days							
26	Lube Oil Piping	1 day			i F				
27	Lube Oil Pumps	2 days			P				
28	Lube Oil Tanks	3 days							*
29	Fire Protection	6 days			,				
30	Fire Protection Piping	2 days							
31	CO2 Storage Tank	4 days					<u>+</u>		_
32	Generator	10 days							

D	Task Name	Duration	2012		2013		2014	2015
			Qtr 1	Qtr 2 Qtr 3 Qtr 4	Qtr 1 Qtr 2	Qtr 3 Qtr 4	Qtr 1 Qtr 2 Qtr 3 Qt	r 4 Qtr 1 Qtr
33	Generators	10 days			T ₁			
34	Combustion Turbine	35 days						
35	Inlet ducts	4 days			K			
36	Exhaust ducts	4 days			F			
37	Combustion Turbines	10 days				ζ.		
38	Combustion Turbine Foundation	12 days				*		
39	Combustion Turbine Enclosure Building	5 days				K		
40	Stack	2 days						
41	Stacks	2 days				Ϋ́		
42	Post Dismantlement Activities	20 days						
43	Post Dismantlement Activities	20 days						



Lake Road Common Retirement

Owner Costs

Pre-Retirement Activities \$52,448
Retirement Activities \$588,014
Post-Retirement Activities \$26,224

Owner Direct Total \$666,686

Owner Internal Costs 5.00% \$33,334

Owner Contingency: 25.00% \$175,005

Lake Road Common Retirement Opinion of Probable Cost: \$875,025

Activities Required by Permit or Regulation

 Lake Road 5 Tank
 \$31,069

 Lake Road 6 Tank
 \$71,610

 Lake Road 7 Tank
 \$71,610

Activities Required by Permit or Regulation: \$174,289

	Task Name	Cost
1	Lake Road Common Retirement	\$666,686.48
2	Pre-Retirement Activities	\$52,448.80
3	Permitting Review	\$26,224.40
4	Develop Detailed Retirement Plan	\$26,224.40
5	Overheads	\$137,346.72
6	Retirement Overheads	\$120,133.28
7	Added Overhead Staff for Common Retirement	\$120,133.28
8	Common Removal Equipment Rental	\$17,213.44
9	Common Removal Equipment Rental	\$17,213.44
10	Retirement Activities	\$450,666.56
11	Administration Building	\$9,342.40
12	Secure Administration Building	\$9,342.40
13	Fuel Yard Office Building	\$5,605.44
14	Secure Fuel Yard Office Building	\$5,605.44
15	Butler Building	\$1,868.48
16	Secure Butler Building	\$1,868.48
17	Dozer Building	\$1,868.48
18	Secure Dozer Building	\$1,868.48
19	Laboratory	\$9,260.48
20	Secure Laboratory	\$9,260.48
21	Guard Shack	\$1,868.48
22	Secure Guard Shack	\$1,868.48
23	Gas Metering Station	\$6,866.80
24	Isolate Gas Metering Station at the Source	\$5,605.44
25	Vent Piping	\$1,261.36
26	Propane Tanks	\$1,261.36
27	Open and Vent Propane Tanks	\$1,261.36
28	Non-Potable/Fire Protection Water Tank	\$2,522.72
29	Drain and Vent the Non-Potable/Fire Protection Water Tank	\$2,522.72
30	Condensate Storage Tank	\$1,261.36
31	Drain and Vent the Condensate Storage Tank	\$1,261.36
32	Fuel Yard	\$26,690.80
33	Car Dumper	\$8,829.52
34	Empty Car Track Hoppers	\$1,261.36
35	Clean Car Dumper	\$3,784.08
36	Empty and Clean Belt Feeders 3A, 3B and 3C	\$3,784.08
37	West Yard Reclaim	\$15,338.56
38	Clean West Yard Reclaim Hoppers	\$2,522.72
39	Clean the West Yard Reclaim Hopper Vibrating Feeders	\$1,261.36
40	Clean the Frozen Coal Cracker	\$1,261.36
41	Boiler 4 and Boiler 5 Tripper	\$2,522.72
42	Clean the Boiler 4 and Boiler 5 Tripper	\$2,522.72
43	Coal Conveyors	\$50,454.40
44	Clean Conveyors - 5A, 5B, 6, 7, 8, 1, 2, and 3	\$25,227.20

)	Task Name	Cost
45	Wells	\$299,000.00
46	Close 13 Wells	\$299,000.00
47	900 Lb. Steam Header System	\$5,045.44
48	Open and Vent the 900 Lb. Steam Header System	\$2,522.72
49	Open and Vent the 200 Lb. and 3 Lb. Flash Tanks	\$2,522.72
50	200 Lb. Steam Header System	\$2,522.72
51	Open and Vent the 200 Lb. Steam Header System	\$2,522.72
52	Low Side Water Treatment	\$22,704.48
53	Open and Clean the Mixing Tanks	\$1,261.36
54	Open and Clean the 4 Lime Softeners	\$6,306.80
55	Open, Empty and Clean the Carbon Filters (11)	\$3,784.08
56	Open, Empty and Clean the Zeolite Filters (4)	\$3,784.08
57	Open and Vent the Low Side Deaerator	\$1,261.36
58	Open and Vent the Feedwater Storage Tanks (4)	\$1,261.36
59	Open and Vent the Desuperheater Storage Tank (1)	\$1,261.36
60	Flush the Piping	\$3,784.08
61	Low Side Feedwater System	\$2,522.72

Open and Vent BFP Suction and Discharge Piping

Open and Vent the Feedwater Heaters

Post Retirement Closure Activities

Post Retirement Closure Activities

62

63

64

65

\$1,261.36

\$1,261.36

\$26,224.40

\$26,224.40

)	Task Name	Duration	er	2nd Quarter	3rd Quarter	4th Quarter	1st Quarter	2nd Quarter	3rd Quart
1	Lake Road Common Retirement	142 days	Mar	Apr May Jun	Jul Aug Sep	Oct Nov Dec	Jan Feb Mai	r Apr May Jun	Jul Aug
2	Pre-Retirement Activities	40 days							
3	Permitting Review	20 days					KCP&L P	Project Manager	[25%],KCP&
4	Develop Detailed Retirement Plan	20 days						, ,	
5	Overheads	82 days	$\exists $,
6	Retirement Overheads	82 days							,
7	Added Overhead Staff for Common Retirement	82 days							
8	Common Removal Equipment Rental	82 days						_	ı
9	Common Removal Equipment Rental	82 days							
10	Retirement Activities	82 days							ı
11	Administration Building	5 days					•		
12	Secure Administration Building	5 days					*		
13	Fuel Yard Office Building	3 days							
14	Secure Fuel Yard Office Building	3 days					5		
15	Butler Building	1 day					—		
16	Secure Butler Building	1 day					ĥ		
17	Dozer Building	1 day					•		
18	Secure Dozer Building	1 day					Ť,		
19	Laboratory	4 days					•		
20	Secure Laboratory	4 days					Š		
21	Guard Shack	1 day					•	_	
22	Secure Guard Shack	1 day					h		
23	Gas Metering Station	4 days					•		
24	Isolate Gas Metering Station at the Source	3 days					0		
25	Vent Piping	1 day					Ì		
26	Propane Tanks	1 day					•		
27	Open and Vent Propane Tanks	1 day						Б	
28	Non-Potable/Fire Protection Water Tank	2 days					•		
29	Drain and Vent the Non-Potable/Fire Protection Water Tank	2 days						ř i	
30	Condensate Storage Tank	1 day					Ţ		

)	Task Name	Duration	er Man	2nd Quarter	3rd Quarter Jul Aug Sep	4th Quarter	1st Quarter	2nd Quarter	3rd Quarte
31	Drain and Vent the Condensate Storage Tanl	1 day	iviar	Apr May Jun	Jul Aug Sep	Oct Nov Dec	Jan Feb Iviar	Apr Iviay Jun	Jul Aug
32	Fuel Yard	13 days							
33	Car Dumper	7 days							
34	Empty Car Track Hoppers	1 day						†	
35	Clean Car Dumper	3 days						*	
36	Empty and Clean Belt Feeders 3A, 3B and	3 days						*	
37	West Yard Reclaim	4 days						•	
38	Clean West Yard Reclaim Hoppers	2 days						*	
39	Clean the West Yard Reclaim Hopper Vibrating Feeders	1 day						ř	
40	Clean the Frozen Coal Cracker	1 day						Γ,	
41	Boiler 4 and Boiler 5 Tripper	2 days							
42	Clean the Boiler 4 and Boiler 5 Tripper	2 days						ή,	
43	Coal Conveyors	20 days							
44	Clean Conveyors - 5A, 5B, 6, 7, 8, 1, 2, and 3	20 days							
45	Wells	2 days							
46	Close 13 Wells	2 days						Ĭ	
47	900 Lb. Steam Header System	4 days						•	
48	Open and Vent the 900 Lb. Steam Header System	2 days						7	
49	Open and Vent the 200 Lb. and 3 Lb. Flash Ta	2 days						5	
50	200 Lb. Steam Header System	2 days						•	
51	Open and Vent the 200 Lb. Steam Header System	2 days							
52	Low Side Water Treatment	18 days							
53	Open and Clean the Mixing Tanks	1 day						Ϋ́	
54	Open and Clean the 4 Lime Softeners	5 days							
55	Open, Empty and Clean the Carbon Filters (1	3 days						*	
56	Open, Empty and Clean the Zeolite Filters (4)	3 days						Š	
57	Open and Vent the Low Side Deaerator	1 day						Ϋ́	
58	Open and Vent the Feedwater Storage Tanks	1 day						K	

Lake F	load Common Retirement															
ID	Task Name	Duration	er	2nd	Quarter	3rd	Quarter	4th 0	Quarter	1st	Quarter	2nd	Quart	er	3rd	Quarte
			Mar	Apr	May Jun	Jul	Aug Sep	Oct	Nov Dec	Jan	Feb Mai	r Apr	May	Jun	Jul	Aug
59	Open and Vent the Desuperheater Storage Tank (1)	1 day												h		
60	Flush the Piping	3 days												5		
61	Low Side Feedwater System	2 days														
62	Open and Vent BFP Suction and Discharge P	i 1 day												h		
63	Open and Vent the Feedwater Heaters	1 day												Ь		
64	Post Retirement Closure Activities	20 days													—	
65	Post Retirement Closure Activities	20 days														

Lake Road Common Dismantlement

Owner Additional Costs

Pre-Dismantlement Activities \$0
Overhead During Dismantlement \$0

Owner Costs Total* \$0

Demolition General Contractor (DGC) Costs

Additional Site Management \$100,346
Equipment Rental \$489,213
Consummables \$732,959
Scrap Crew(s) \$727,292
Dismantlement \$532,207

Contractor Direct Cost* \$2,582,017

Contractor Allowances

DGC Insurance 2.00% \$51,640

Contingency/Profit 15.00% \$395,049

Performance Bond 2.00% \$60,574

Contractor Costs Total: \$3,089,280

Total: \$3,089,280

Owner Internal Costs: 5.00% \$154,464

Owner Contingency: 25.00% \$810,936

Lake Road Common Dismantlement Opinion of Probable Cost:

\$4,054,680

^{*}Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances = \$2,582,017


D	Task Name	Cost
1 I	ake Road Common Dismantlement	\$2,582,020.7
2	Overheads	\$2,049,812.8
3	Common Removal Overheads	\$100,346.9
4	Added Overhead Staff for Common Removals	\$100,346.9
5	Common Removal Equipment Rental	\$489,213.7
6	Common Removal Equipment Rental	\$489,213.7
7	Demolition Contractor Consummables	\$732,959.9
8	Consummables	\$732,959.9
9	Scrap Crew	\$727,292.1
10	Crew(s) to Handle Scrap Material	\$727,292.1
11	Dismantlement Activities	\$532,207.9
12	Administration Building	\$35,827.2
13	Administration Building	\$35,827.2
14	Fuel Yard Office Building	\$10,748.1
15	Remove Fuel Yard Office Building	\$10,748.1
16	Butler Building	\$7,165.4
17	Butler Building	\$7,165.4
18	Parking Lots and Plant Roads	\$39,409.9
19	Plant Roads and Parking Areas	\$35,827.2
20	Guard Shack	\$3,582.7
21	Dozer Building	\$7,165.4
22	Dozer Building	\$7,165.4
23	Laboratory	\$9,286.0
24	Laboratory	\$9,286.0
25	Fuel Equipment	\$11,607.6
26	Remove Propane Tanks and above ground piping	\$11,607.6
27	Remove Gas Metering Station and above ground piping	\$0.0
28	Fuel Yard	\$147,260.1
29	Remove Car Dumper	\$23,215.2
30	Remove West Yard Reclaim	\$18,572.1
31	Remove Boiler 4 and Boiler 5 Tripper	\$9,286.0
32	Conveyors	\$58,038.0
33	Remove Conveyors - 5A, 5B, 6, 7, 8, 1, 2, and 3	\$58,038.0
34	Remove Dust Collectors	\$2,321.5
35	Remove Miscellaneous Fuel Yard Equipment	\$35,827.2
36	Underground Circulating Water Piping between Condensers and Intake	\$39,409.9
37	Excavate Underground Circulating Water Piping	\$10,748.2
38	Collapse Underground Circulating Water Piping	\$7,165.4
39	Backfill and Compact Over Circulating Water Piping	\$21,496.3
40	Yard Fire Water Systems	\$10,748.1
41	Remove Hydrants and Fire Water System Piping Down to 3' Below Grade	\$10,748.1
42	Low Side Water Treatment	\$60,359.5
43	Remove Mixing Tanks	\$4,643.0

ID	Task Name	Cost
44	Remove 4 Lime Softeners	\$4,643.04
45	Remove 11 Carbon Filters	\$16,250.64
46	Remove 4 Zeolite Filters	\$6,964.56
47	Remove Deaerator	\$4,643.04
48	Remove 4 Feedwater Storage Tanks	\$9,286.08
49	Remove Desuperheater Storage Tanks	\$2,321.52
50	Remove interconnecting piping and equipment	\$11,607.60
51	Low Side Feedwater System	\$16,250.64
52	Remove BFP Suction and Discharge Pipe	\$2,321.52
53	Remove 3 Boiler Feed Pump/Motor Sets	\$9,286.08
54	Remove the Active and Retired Feedwater Heaters	\$2,321.52
55	Remove Low Side Sampling System	\$2,321.52
56	Boiler/Turbine Building	\$23,215.20
57	Remove the Common Boiler and Turbine Building	\$23,215.20
58	Water Storage Tanks	\$16,250.64
59	Remove the Non-Potable/Fire Protection Water Tank	\$11,607.60
60	Remove the Condensate Storage Tank	\$4,643.04
61	Steam Header Systems	\$13,929.12
62	Remove 900 Lb. Steam Header Piping and Equipment	\$11,607.60
63	Remove 200 Lb. Steam Header Piping and Equipment	\$2,321.52
64	Stacks	\$83,574.72
65	Remove #6 Stack to Grade	\$32,501.28
66	Remove #5 Stack to Grade	\$27,858.24
67	Remove #4 Stack to Grade	\$23,215.20
68	Final Site Grading and Drainage	\$0.00
69	Final Site Grading and Drainage	\$0.00

)	Task Name	Duration		2012						
		_	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr		
1	Lake Road Common Dismantlement	204 days						J		
2	Overheads	203 days		7				l		
3	Common Removal Overheads	203 days		Ť				ı		
4	Added Overhead Staff for Common Removals	203 days								
5	Common Removal Equipment Rental	203 days						l		
6	Common Removal Equipment Rental	203 days		-						
7	Demolition Contractor Consummables	203 days		1				l		
8	Consummables	203 days		•						
9	Scrap Crew	203 days						I		
10	Crew(s) to Handle Scrap Material	203 days		•						
11	Dismantlement Activities	203 days						1		
12	Administration Building	10 days		4	—					
13	Administration Building	10 days		4	Ъ					
14	Fuel Yard Office Building	3 days		l (•					
15	Remove Fuel Yard Office Building	3 days			Ϋ́					
16	Butler Building	2 days								
17	Butler Building	2 days			Ϋ́					
18	Parking Lots and Plant Roads	11 days								
19	Plant Roads and Parking Areas	10 days			ightharpoons					
20	Guard Shack	1 day			h					
21	Dozer Building	2 days								
22	Dozer Building	2 days			<u> </u>					
23	Laboratory	4 days								
24	Laboratory	4 days			*					
25	Fuel Equipment	7 days								
26	Remove Propane Tanks and above ground piping	5 days								
27	Remove Gas Metering Station and above ground piping	2 days			†					
28	Fuel Yard	58 days				—				
29	Remove Car Dumper	10 days			*					
30	Remove West Yard Reclaim	8 days								
31	Remove Boiler 4 and Boiler 5 Tripper	4 days			<u></u>					
32	Conveyors	25 days				-				

	Task Name	Duration		2012			2013
			Qtr 4	Qtr 1	Qtr 2	Qtr 3 Qtr 4	Qt
33	Remove Conveyors - 5A, 5B, 6, 7, 8, 1, 2, and 3	25 days					
34	Remove Dust Collectors	1 day				Ď	
35	Remove Miscellaneous Fuel Yard Equipment	10 days					
36	Underground Circulating Water Piping between Condensers and Intake and Cooling Towers	11 days					
37	Excavate Underground Circulating Water Piping	3 days					
38	Collapse Underground Circulating Water Piping	2 days				•	
39	Backfill and Compact Over Circulating Water Piping	6 days					
40	Yard Fire Water Systems	3 days				•	
41	Remove Hydrants and Fire Water System Piping Down to 3' Below Grade	3 days					
42	Low Side Water Treatment	26 days					
43	Remove Mixing Tanks	2 days				Ť,	
44	Remove 4 Lime Softeners	2 days				Ϋ́	
45	Remove 11 Carbon Filters	7 days					
46	Remove 4 Zeolite Filters	3 days				F	
47	Remove Deaerator	2 days				T	
48	Remove 4 Feedwater Storage Tanks	4 days				\overline{\cut_1}	
49	Remove Desuperheater Storage Tanks	1 day				\overline{F}	
50	Remove interconnecting piping and equipment	5 days				*	
51	Low Side Feedwater System	7 days				•	
52	Remove BFP Suction and Discharge Pipe	1 day				Ь	
53	Remove 3 Boiler Feed Pump/Motor Sets	4 days				\(\right\)	
54	Remove the Active and Retired Feedwater Heaters	1 day				i,	
55	Remove Low Side Sampling System	1 day				ή	
56	Boiler/Turbine Building	10 days					
57	Remove the Common Boiler and Turbine Building	10 days					
58	Water Storage Tanks	7 days				•	
59	Remove the Non-Potable/Fire Protection Water Tank	5 days				*	

D	Task Name	Duration		2012				2013
			Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1
60	Remove the Condensate Storage Tank	2 days					ή	
61	Steam Header Systems	6 days						
62	Remove 900 Lb. Steam Header Piping and Equipment	5 days					ξ	
63	Remove 200 Lb. Steam Header Piping and Equipment	1 day					Ϊ́	
64	Stacks	36 days					•	
65	Remove #6 Stack to Grade	14 days						
66	Remove #5 Stack to Grade	12 days						
67	Remove #4 Stack to Grade	10 days						
68	Final Site Grading and Drainage	1 day					•	
69	Final Site Grading and Drainage	1 day					1	



IATAN STATION

The Iatan Generating Station consists of two coal-fired power plants.

Iatan Unit 1 has an SPP-accredited unit rating of 705 MW and was placed in service in 1980. Unit 1 has a sub-critical Babcock & Wilcox boiler and a General Electric turbine. Missouri River water is used for condenser cooling. Iatan Unit 1 was originally commissioned with a dedicated chimney and an electrostatic precipitator for flue gas particulate removal. In 2009, Iatan Unit 1 was retrofitted with an SCR, baghouse, and wet scrubber. The original electrostatic precipitator and stack were abandoned in place and the flue gas was redirected to a common Iatan Units 1 and 2 chimney with a dedicated Unit 1 flue.

Iatan Unit 2 has an SPP-accredited unit rated of 881 MW and was placed in service in 2010. Unit 2 has a super-critical Alstom boiler and a Toshiba turbine. A cooling tower is used for condenser cooling with well water for cooling tower makeup. Iatan Unit 2 has an SCR, baghouse, and wet scrubber. The flue gas is discharged through a common Iatan Units 1 and 2 chimney with a dedicated Unit 2 flue.

The Iatan fuel yard has a rotary car dumper to unload unit trains of coal. The coal is stored in a common fuel yard. Fuel is reclaimed from the common fuel yard via a stacker reclaimer or a series of reclaim pits and transferred to Units 1 and 2 through a common conveyor system. Coal is transferred from the common conveyor system to dedicated unit conveyors (located near the final coal transfer points for each unit).

Both Iatan Units 1 and 2 have a fuel oil igniter system. Both units are supplied with fuel oil from a common fuel oil unloading and storage facility.

Both Units 1 and 2 have a wet scrubber that utilizes a common reagent preparation and gypsum handling facility. This facility includes a limestone unloading and storage area, a limestone slurry preparation system, a gypsum preparation system, and a gypsum stackout and storage system.

Both Units 1 and 2 beneficially use coal combustion products off site. Coal combustion products that are not beneficially used off site are disposed of in the on-site landfill.

The following are the major systems and equipment that were included in the retirement and dismantlement of each unit and the major systems and equipment that were considered common (additional details are listed in the attached retirement and dismantlement schedules included in this Appendix).

IATAN UNIT 1

- 1. Boiler, SCR, and boiler auxiliaries.
- 2. Turbine, heat balance equipment, and turbine auxiliaries.
- 3. Precipitator (currently retired in place).
- 4. Baghouse and wet scrubber.
- 5. Waste oil system.
- 6. Dedicated Unit 1 fuel handling equipment.
- 7. Dedicated Unit 1 fuel oil equipment.
- 8. Circulating water intake structure, circulating water piping, and circulating water equipment.

IATAN UNIT 2

- 1. Boiler, SCR, and boiler auxiliaries.
- 2. Turbine, heat balance equipment, and turbine auxiliaries.
- 3. Baghouse and wet scrubber.
- 4. Dedicated Unit 2 fuel handling equipment.
- 5. Dedicated Unit 2 fuel oil equipment.
- 6. Cooling tower and wells.

COMMON

- 1. Administration building.
- 2. Fuel yard office building.
- 3. Training building.
- 4. Warehouses.
- 5. Maintenance shops.
- 6. Common fuel handling equipment.
- 7. Sewage treatment.
- 8. Fuel oil storage and unloading.
- 9. Fire water systems.
- 10. Reagent preparation and gypsum handling.
- 11. Unit 1 stack (currently retired in place).
- 12. Units 1 and 2 common stack.
- 13. Landfill.
- 14. Clarifiers, clarifier storage tanks, and zero-liquid discharge equipment and auxiliaries.

UNIT 1

latan 1 Retirement

Owner Costs

Pre-Retirement Activities \$100,822
Retirement Activities \$661,769
Post-Retirement Activities \$26,564

Owner Direct Total \$789,155

Owner Internal Costs 5.00% \$39,458

Owner Contingency: 25.00% \$207,153

latan 1 Retirement Opinion of Probable Cost: \$1,035,765.41

Activities Required by Permit or Regulation

latan 1 Intake Removal\$613,077latan Unit 1 Ash Pond Closure\$36,357,000

Activities Required by Permit or Regulation: \$36,970,077

)	Task Name	Cost
1	latan 1 Retirement	\$789,156.31
2	Pre-Engineering	\$100,821.60
3	Permit review and engineering analysis, establish isolation points, and	\$0.00
	confirm fuel yard inventory has been reduced to zero tons.	
4	KCL&L Overhead Costs	\$115,245.60
5	KCP&L Retirement Manager	\$115,245.60
6	Equipment Rentals	\$39,070.50
7	Vacuum truck	\$39,070.50
8	Retirement	\$507,454.61
9	Electrical	\$18,911.68
10	Medium and Low Voltage Draw out Switchgear	\$2,679.84
11	De-energize all buses at the source.	\$446.64
12	Open all circuit breakers.	\$446.64
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	\$446.64
14	Verify that the closing/tripping springs are discharged.	\$446.64
15	De-energize control power and auxiliary power circuits of each circuit	\$893.28
	breaker at the source and by opening control power circuit breakers or	
	removing fuses in each breaker cubicle.	
16	Motor Control Centers	\$1,786.56
17	De-energize all buses at the source.	\$446.64
18	Open all circuit breakers and disconnect switches.	\$446.64
19	Remove all fuses in control circuits.	\$893.28
20	Low-voltage Switchboards and Panelboards	\$893.28
21	De-energize all buses at the source.	\$446.64
22	Open all circuit breakers and disconnect switches.	\$446.64
23	Oil-Filled Power Transformers	\$5,549.44
24	De-energize all transformer primaries and verify that the secondary is de-energized.	\$893.28
25	De-energize all low-voltage AC or DC power sources for space heaters,	\$893.28
	cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	
26	Drain and dispose of oil.	\$2,642.88
27	Clean up and dispose of oil on surface areas around the transformers on in containment pits.	
28	Dry-type Power Transformers	\$1,786.56
29	De-energize all transformer primaries and verify that the secondary is	\$893.28
	de-energized.	
30	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers	\$893.28
	or remove fuses at transformer end.	
31	Motors	\$6,216.00
32	De-energize all primary power at the source.	\$1,786.56

)	Task Name	Cost
33	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	\$1,786.56
34	Drian lube oil system (if applicable) and dispoe of oil.	\$2,642.88
35	Coal Handling	\$27,475.44
36	Empty all transfer hoppers.	\$1,704.56
37	Burn out coal silos.	\$1,685.44
38	Confirm all fuel lines, conveyors and trippers are clear of fuel.	\$1,685.44
39	Perform cleaning of the coal handling equipment to assure that all coal	\$22,400.00
	and coal dust has been removed from site.	
40	Fuel Oil and Igniter System	\$2,528.16
41	Drain fuel oil system	\$2,528.16
42	Waste Oil System	\$1,685.44
43	Drain all waste oil systems	\$1,685.44
44	Boiler Chemical Feed	\$1,685.44
45	Drain all chemical feed tanks.	\$1,685.44
46	Boiler	\$27,484.77
47	Open boiler doors.	\$880.96
48	Gas side - perform cleaning of the boiler and bottom ash system.	\$22,400.00
49	Drain boiler, drum, downcomers and headers.	\$842.72
50	Open drum doors.	\$880.96
51	Drain and clean the submerged flight conveyor system.	\$2,480.13
52	Stack and Ductwork	\$326,961.04
53	Open ductwork doors.	\$880.96
54	Perform extensive cleaning of the ductwork.	\$11,200.00
55	Place cap over stack opening to keep moisture out.	\$314,880.08
56	Condensate and Feedwater Piping	\$1,685.44
57	Drain water from the system.	\$842.72
58	Leave open vents and drains.	\$842.72
59	Feedwater heaters	\$2,528.16
60	Drain feedwater heaters	\$842.72
61	Leave open vents and drains.	\$1,685.44
62	Deaerator and Deaerator Storage Tank	\$1,685.44
63	Drain Deaerator and Storage	\$842.72
64	Leave open vents and drains.	\$842.72
65	Baghouse	\$17,351.92
66	Multiple cleaning cycles for filter bags.	\$2,528.16
67	Open all vent and drain lines on bag cleaning air and control air lines. Leave in open position or remove vent valves.	\$842.72
68	Remove all filter bags and cages.	\$880.96
69	Clear hoppers of all ash	\$2,805.44
70	Mechanically secure all compartment dampers and hopper outlet valves in open position.	
71	Disconnect ash transport piping and washdown baghouse hoppers and interior of casing.	\$1,421.84

D	Task Name	Cost
72	Install bird screens across hopper ash outlet and ash line flanges.	\$880.96
73	Padlock or tack weld all hopper doors shut. (note: if ash hopper doors are indoors, they could be removed and the opening covered with bird screens.)	\$880.96
74	If walk-in plenum, padlock or tack weld all outlet plenum doors and compartment ventilation dampers shut.	\$880.96
75	If top-door plenum, close and secure top doors and remove/disable door lift hoist.	\$1,723.68
76	If top-door plenum, establish natural ventilation or maintain HVAC fan to provide minimum air changes per hour in penthouse enclosure.	\$945.44
77	Pull electrical supply breakers on all electrical equipment except lighting and HVAC components that are to remain in service.	\$2,679.84
78	Wet FGD system	\$23,908.00
79	Multiple mist eliminator wash cycles. Remove ME's from absorber.	\$2,145.04
80	Drain and flush all slurry and reclaim water pumps and piping. Leave vent and drain valves open or remove. Install bird screens across drain openings.	\$1,723.68
81	Drain and wash out the reaction tank, reagent storage tank, recycle water tank, absorber blowdown tank, etc.	\$4,624.08
82	Leave all tank drain valves open or remove. Install bird screens across openings.	\$1,761.92
83	Drain all makeup and mist eliminator water pumps and piping. Leave vent and drain valves open or remove. Install bird screens across drain openings.	\$2,604.64
84	Mechanically secure all flue gas isolation dampers in open position or remove damper blades.	\$1,761.92
85	Remove solids from all inlet and outlet ductwork as necessary	\$2,240.00
86	Open all vent station air and control air lines. Leave in open position or remove vent valves	\$1,723.68
87	Padlock or tack weld all access doors to modules and ductwork shut.	\$1,762.24
88	Remove access doors to open-top tanks.	\$880.96
89	Pull electrical supply breakers on all electrical equipment except lighting and HVAC components that are to remain in service.	\$2,679.84
90	FGD Reagent Preparation-Limestone wet Scrubber	\$10,262.88
91	Remove limestone from day bins.	\$1,402.72
92	Removed cartridges/bags from bin vent filters	\$1,402.72
93	Padlock or tack weld all bin access doors shut. (note: if doors are indoors, they could be removed and the opening covered with bird screens.)	\$881.12
94	Remove bin discharge isolation valve and install bird screen.	\$440.48
95	Thoroughly wash and drain mills	\$1,402.72
96	Remove balls from any ball mills	\$1,120.00
97	Padlock or tack weld mill access doors closed.	\$881.12

	Task Name	Cost
98	Establish natural ventilation or maintain HVAC fan to provide minimum air	\$945.44
00	changes per hour in building.	44 706 56
99	Pull electrical supply breakers on all electrical equipment except lighting and HVAC components that are to remain in service.	\$1,786.56
100	FGD Byproduct Dewatering - Hydrocyclones and Vacuum Filters	\$7,287.12
101	Wash vacuum filter belt and remove all accumulated solids	\$2,240.00
102	Wash out vacuum receiver, remove pressure relief valve and access door.	\$1,421.84
	Install bird screens.	71,721.07
103	Establish natural ventilation or maintain HVAC fan to provide minimum air	\$945.44
	changes per hour in building.	ψ3 13.11
104	Pull electrical supply breakers on all electrical equipment except lighting	\$2,679.84
	and HVAC components that are to remain in service.	Ψ 2, 073.0-
L05	SCR	\$10,054.00
106	Vacuum fly ash from catalyst.	\$2,240.00
107	Remove catalyst of salvage or disposal.	\$2,881.92
108	Padlock or tack weld access doors shut.	\$880.96
109	Remove ammonia from storage tank for resale.	\$701.36
110	Wash out and drain storage tank and supply piping.	\$701.36
111	Vent storage tank and all piping. Leave vent and drain valves open or	\$861.84
	remove. Install bird screens.	7001.0-
112	Pull electrical supply breakers on all electrical equipment except lighting	\$1,786.56
	and HVAC components that are to remain in service.	γ1,700.3 (
113	Turbine(s) and Condenser	\$5,266.64
114	Drain hotwell and leave doors open.	\$861.84
115	Open main turbine doors.	\$880.96
116	Open bfp turbine doors.	\$880.96
117	Remove lube oil.	\$2,642.88
118	Generator	\$6,095.76
119	Verify that generator circuit breaker is open and racked out or that	\$446.64
	high-voltage disconnect switch on substation side of GSU transformer is	φ.1.010
	locked in the open position.	
120	Verify that generator field breaker or contactor (if applicable) is open.	\$446.64
121	De-energize power supplies to generator excitation system at the source.	\$446.64
122	De-energize AC and DC power supplies to generator and exciter space	\$446.64
	heaters, cooling equipment, controls, lighting, etc. at the source and open	ψ 1 10.0
	circuit breakers or remove fuses at the generator and exciter.	
123	Drain generator and exciter cooling water systems (if applicable).	\$861.84
124	Disconnect and remove hydrogen gas tanks and purge generator hydrogen	\$1,685.44
	system.	71,000.44
125	Disconnect and remove fire protection system gas/foam tanks and purge	\$1,761.92
123	fire protection system.	Ψ1,701.92
126	Circulation Water and Turbine Cooling Water System	\$3,409.12
		7J,7UJ.12

D	Task Name	Cost
128	Open water box doors.	\$880.96
129	Drain any circulating water chemical feed tanks.	\$842.72
130	Compressed Air System	\$2,721.28
131	Open vents and drains.	\$842.72
132	Remove desiccant from desiccant dryers.	\$1,878.56
133	Auxiliary Steam System	\$1,685.44
134	Drain water from system.	\$842.72
135	Remove aux boiler chemicals.	\$842.72
136	Auxiliary Cooling Water System	\$842.72
137	Drain water from system.	\$842.72
138	Condenser Air Extraction and Waterbox Priming System	\$842.72
139	Drain water from system.	\$842.72
140	Building Heating System	\$842.72
141	Drain water from system.	\$842.72
142	Battery System	\$4,253.28
143	De-energize all battery chargers from the source.	\$446.64
144	Open all AC and DC circuit breakers and/or fused switches on battery	\$446.64
	chargers and disconnect cables from batteries.	
145	Remove and dispose of battery electrolyte.	\$1,680.00
146	Remove and dispose of battery cells.	\$1,120.00
147	Clean up and dispose of electrolyte on surface areas around batteries.	\$560.00
148	Post Retirement Activities	\$26,564.00
149	Post Retirement Activities	\$26,564.00

	Task Name	Duration	1st Quarter		2nd Quarter	2nd Quarter 3rd Quarter	2nd Quarter 3rd Quarter 4th Quarter
1	latan 1 Retirement	292 days					
2	Pre-Engineering	66 days	↓	J			
3	Permit review and engineering analysis, establish isolation	66 days					
	points, and confirm fuel yard inventory has been reduced to zero tons.						
4	KCL&L Overhead Costs	186 days			-	—	V
5	KCP&L Retirement Manager	186 days					*
6	Equipment Rentals	186 days		Ţ	+	V	V
7	Vacuum truck	186 days			*		•
8	Retirement	186 days		•	+	-	
9	Electrical	22 days		-	-		
10	Medium and Low Voltage Draw out Switchgear	3 days					
11	De-energize all buses at the source.	0.5 days		h			
12	Open all circuit breakers.	0.5 days		ħ			
13	Rack all circuit breakers into the fully withdrawn,	0.5 days		<u> </u>			
	disconnected position.						
14	Verify that the closing/tripping springs are discharged.	0.5 days		h			
15	De-energize control power and auxiliary power circuits	1 day		Ť			
	of each circuit breaker at the source and by opening	,					
	control power circuit breakers or removing fuses in each						
	breaker cubicle.						
16	Motor Control Centers	2 days					
17	De-energize all buses at the source.	0.5 days		Ь			
18	Open all circuit breakers and disconnect switches.	0.5 days		Ъ			
19	Remove all fuses in control circuits.	1 day		Ĭ			
20	Low-voltage Switchboards and Panelboards	1 day		—			
21	De-energize all buses at the source.	0.5 days		Ь			
22	Open all circuit breakers and disconnect switches.	0.5 days		Ī			
23	Oil-Filled Power Transformers	7 days					
24	De-energize all transformer primaries and verify that the	1 day		P			
	secondary is de-energized.						

	Task Name	Duration	1st Quarter	2nd Quarter	3rd Quarter 4th Quar	ter 1st Quarter	2nd Quar
25	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	1 day		h			
26	Drain and dispose of oil.	3 days		<u></u>			
27	Clean up and dispose of oil on surface areas around the transformers on in containment pits.	2 days		M			
28	Dry-type Power Transformers	2 days					
29	De-energize all transformer primaries and verify that the secondary is de-energized.	e 1 day		h			
30	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	1 day		ľ			
31	Motors	7 days		-			
32	De-energize all primary power at the source.	2 days		h			
33	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	2 days		Ť			
34	Drian lube oil system (if applicable) and dispoe of oil.	3 days		7			
35	Coal Handling	25 days			 		
36	Empty all transfer hoppers.	1 day		I			
37	Burn out coal silos.	2 days		Ĥ			
38	Confirm all fuel lines, conveyors and trippers are clear of fuel.	2 days		Ì			
39	Perform cleaning of the coal handling equipment to assure that all coal and coal dust has been removed from site.	20 days					
40	Fuel Oil and Igniter System	3 days					
41	Drain fuel oil system	3 days			•		
42	Waste Oil System	2 days					
43	Drain all waste oil systems	2 days			ı *		
44	Boiler Chemical Feed	2 days					
45	Drain all chemical feed tanks.	2 days			1		
46	Boiler	27 days					

	Task Name	Duration	1st Quarter 2nd Quarter 3rd Quarter 4th Quarter 1st Quarter 2
47	Open boiler doors.	1 day	
48	Gas side - perform cleaning of the boiler and bottom ash system.	20 days	
49	Drain boiler, drum, downcomers and headers.	1 day	h h
50	Open drum doors.	1 day	
51	Drain and clean the submerged flight conveyor system.	5 days	*
52	Stack and Ductwork	12 days	▼
53	Open ductwork doors.	1 day	h
54	Perform extensive cleaning of the ductwork.	10 days	
55	Place cap over stack opening to keep moisture out.	1 day	T
56	Condensate and Feedwater Piping	2 days	
57	Drain water from the system.	1 day	h h
58	Leave open vents and drains.	1 day	Y
59	Feedwater heaters	3 days	
60	Drain feedwater heaters	1 day	h
61	Leave open vents and drains.	2 days	
62	Deaerator and Deaerator Storage Tank	2 days	
63	Drain Deaerator and Storage	1 day	η
64	Leave open vents and drains.	1 day	Y
65	Baghouse	16 days	
66	Multiple cleaning cycles for filter bags.	3 days	<u></u>
67	Open all vent and drain lines on bag cleaning air and control air lines. Leave in open position or remove vent valves.	1 day	
68	Remove all filter bags and cages.	1 day	
69	Clear hoppers of all ash	4 days	
70	Mechanically secure all compartment dampers and hopper outlet valves in open position.	1 day	
71	Disconnect ash transport piping and washdown baghouse hoppers and interior of casing.	1 day	
72	Install bird screens across hopper ash outlet and ash line flanges.	1 day	

)	Task Name	Duration	1st Quarter	2nd Quarter 3	rd Quarter 4th 0	Quarter	1st Quarter	2nd C
73	Padlock or tack weld all hopper doors shut. (note: if ash hopper doors are indoors, they could be removed and the opening covered with bird screens.)	1 day			ŀ			
74	If walk-in plenum, padlock or tack weld all outlet plenum doors and compartment ventilation dampers shut.	1 day			Ĥ			
75	If top-door plenum, close and secure top doors and remove/disable door lift hoist.	2 days			1			
76	If top-door plenum, establish natural ventilation or maintain HVAC fan to provide minimum air changes per hour in penthouse enclosure.	1 day						
77	Pull electrical supply breakers on all electrical equipment except lighting and HVAC components that are to remain ir service.	3 days			7			
78	Wet FGD system	19 days			•			
79	Multiple mist eliminator wash cycles. Remove ME's from absorber.	3 days						
80	Drain and flush all slurry and reclaim water pumps and piping. Leave vent and drain valves open or remove. Install bird screens across drain openings.	2 days						
81	Drain and wash out the reaction tank, reagent storage tank, recycle water tank, absorber blowdown tank, etc.	3 days						
82	Leave all tank drain valves open or remove. Install bird screens across openings.	2 days						
83	Drain all makeup and mist eliminator water pumps and piping. Leave vent and drain valves open or remove. Install bird screens across drain openings.	2 days						
84	Mechanically secure all flue gas isolation dampers in open position or remove damper blades.	2 days						
85	Remove solids from all inlet and outlet ductwork as necessary	2 days						
86	Open all vent station air and control air lines. Leave in open position or remove vent valves	2 days						
87	Padlock or tack weld all access doors to modules and ductwork shut.	2 days						

	Task Name	Duration	1st Quarter	2nd Quarter 3rd Quarte	4th Quarter	1st Quarter
88	Remove access doors to open-top tanks.	1 day				
89	, , ,	3 days				
	except lighting and HVAC components that are to remain in					
00	service.	0 -1				
90	FGD Reagent Preparation-Limestone wet Scrubber	9 days				
91	Remove limestone from day bins.	2 days				
92	Removed cartridges/bags from bin vent filters	2 days			•	
93	Padlock or tack weld all bin access doors shut. (note: if doors are indoors, they could be removed and the opening covered with bird screens.)	1 day				
94	Remove bin discharge isolation valve and install bird screen.	1 day			F	
95	Thoroughly wash and drain mills	2 days				
96	Remove balls from any ball mills	2 days				
97	Padlock or tack weld mill access doors closed.	1 day				
98	Establish natural ventilation or maintain HVAC fan to provide minimum air changes per hour in building.	1 day			I	
99	Pull electrical supply breakers on all electrical equipment except lighting and HVAC components that are to remain in service.	2 days			*	
100	FGD Byproduct Dewatering - Hydrocyclones and Vacuum Filters	5 days			•	
101	Wash vacuum filter belt and remove all accumulated solids	2 days			H	
102	Wash out vacuum receiver, remove pressure relief valve and access door. Install bird screens.	1 day			Ī	
103	Establish natural ventilation or maintain HVAC fan to provide minimum air changes per hour in building.	1 day			I	
104	Pull electrical supply breakers on all electrical equipment except lighting and HVAC components that are to remain in service.	3 days			7	
105	SCR	6 days			₩	* 1
106	Vacuum fly ash from catalyst.	4 days				儿
107	Remove catalyst of salvage or disposal.	4 days				

	Task Name	Duration	1st Quarter 2nd Quarter 3rd Quarter 4th Quarter 1st Quarter
108	Padlock or tack weld access doors shut.	1 day	
109	Remove ammonia from storage tank for resale.	1 day	P
110	Wash out and drain storage tank and supply piping.	1 day	Ť
111	Vent storage tank and all piping. Leave vent and drain valves open or remove. Install bird screens.	1 day	
112	Pull electrical supply breakers on all electrical equipment except lighting and HVAC components that are to remain in service.	2 days	
113	Turbine(s) and Condenser	6 days	•
114	Drain hotwell and leave doors open.	1 day	In In In In In In In In In In In In In I
115	Open main turbine doors.	1 day	, , , , , , , , , , , , , , , , , , ,
116	Open bfp turbine doors.	1 day	
117	Remove lube oil.	3 days	*
118	Generator	7 days	
119	Verify that generator circuit breaker is open and racked ou or that high-voltage disconnect switch on substation side of GSU transformer is locked in the open position.	t0.5 days	I,
120	Verify that generator field breaker or contactor (if applicable) is open.	0.5 days	F
121	De-energize power supplies to generator excitation system at the source.	0.5 days	F
122	De-energize AC and DC power supplies to generator and exciter space heaters, cooling equipment, controls, lighting, etc. at the source and open circuit breakers or remove fuses at the generator and exciter.	0.5 days	F
123	Drain generator and exciter cooling water systems (if applicable).	1 day	F)
124	Disconnect and remove hydrogen gas tanks and purge generator hydrogen system.	2 days	
125	Disconnect and remove fire protection system gas/foam tanks and purge fire protection system.	2 days	
126	Circulation Water and Turbine Cooling Water System	3 days	
127	Drain.	2 days	
128	Open water box doors.	1 day	ı İ

)	Task Name	Duration	1st Quarte	r 2nd Quarter	3rd Quarter	4th Quarter 1st Quarte	er 2nd C
129	Drain any circulating water chemical feed tanks.	1 day				ľ	
130	Compressed Air System	3 days					
131	Open vents and drains.	1 day				h	
132	Remove desiccant from desiccant dryers.	2 days					
133	Auxiliary Steam System	2 days					
134	Drain water from system.	1 day				h	
135	Remove aux boiler chemicals.	1 day				Ĭ	
136	Auxiliary Cooling Water System	1 day					
137	Drain water from system.	1 day				I	
138	Condenser Air Extraction and Waterbox Priming System	1 day				₩	
139	Drain water from system.	1 day				I	
140	Building Heating System	1 day				▼	
141	Drain water from system.	1 day				I	
142	Battery System	7 days					
143	De-energize all battery chargers from the source.	0.5 days				₽	
144	Open all AC and DC circuit breakers and/or fused switches on battery chargers and disconnect cables from batteries.	0.5 days				ř	
145	Remove and dispose of battery electrolyte.	3 days				†	
146	Remove and dispose of battery cells.	2 days				<u> </u>	
147	Clean up and dispose of electrolyte on surface areas around batteries.	1 day				Ĭ	
148	Post Retirement Activities	40 days					-
149	Post Retirement Activities	40 days					

latan 1 Dismantlement

Owner C	osts
---------	------

Pre-Dismantlement Activities \$892,760

Overhead During Dismantlement \$1,676,621

Post-Dismantlement Activities \$65,520

Owner Costs Total* \$2,634,901

Demolition General Contractor (DGC) Costs

 Site Management
 \$1,255,135

 Equipment Rental
 \$2,172,838

 Consummables
 \$2,371,947

 Scrap Crew(s)
 \$2,149,631

 Dismantlement
 \$5,143,375

Contractor Direct Cost* \$13,092,926

Contractor Allowances

DGC Insurance 2.00% \$261,859

Contingency/Profit 15.00% \$2,003,218

Performance Bond 2.00% \$307,160.04

Contractor Costs Total: \$15,665,162

Total: \$18,300,063

Owner Internal Costs: 5.00% \$915,003

Owner Contingency: 25.00% \$4,803,767

latan Unit 1 Dismantlement Opinion of Probable Cost: \$24,018,833

^{*}Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances = \$15,727,827

D	Task Name	Cost
1	latan Unit 1 Dismantlement	\$12,345,531.6
2	Pre-Demolition Activities	\$892,760.3
3	Detailed Planning & Hire Owner's Engineer	\$104,441.2
4	Detailed Site Characterization Study	\$610,335.4
5	Hire Demolition General Contractor	\$167,184.0
6	KCP&L Prepares Unit for Dismantlement	\$10,799.6
7	Demolition Contractor Mobilizes on Site	\$0.0
8	KCP&L Overhead during Dismantlement	\$1,676,621.5
9	KCP&L Project Manager	\$266,427.9
10	KCP&L Administrative Support	\$98,521.5
11	KCP&L Engineer	\$437,911.9
12	Owners Engineer Project Manager	\$130,720.0
13	Owners Engineer - Engineer	\$743,040.0
14	Demoliton Contractor Overhead during Dismantlement	\$913,939.1
15	Demolition Contractor Project Manager	\$258,584.7
16	Demolition Contractor Safety Manager	\$230,239.1
17	Demolition Contractor Superintendent	\$425,115.1
18	Demolition Contractor Equipment Rental Costs	\$1,556,187.0
19	Equipment Rental	\$1,556,187.0
20	Demolition Contractor Consummables	\$1,552,575.2
21	Consummables	\$1,552,575.2
22	Scrap Crew	\$1,540,569.6
23	Crew to Handle Scrap Material(s)	\$1,540,569.6
24	Dismantlement	\$4,147,358.8
25	Phase 1 Demolition	\$957,905.4
26	Phase 1 Electrical Demolition	\$342,149.7
27	Electrical Demolition of Phase 1 Equipment	\$342,149.7
28	Condensate System	\$105,690.2
29	Condensate Pumps	\$3,582.7
30	Condensate Transfer Pumps	\$1,791.3
31	Cycle Make-Up Pump	\$1,791.3
32	Steam Packing Exhauster and Blower	\$3,582.7
33	Low Pressure Heaters (except the condenser neck heat exchangers)	\$53,740.8
34	Deaerator	\$14,330.8
35	Deaerator Storage Tank	\$8,956.8
36	Condensate Piping	\$17,913.6
37	Boiler Feed System	\$67,816.9
38	Boiler Feed Pump Turbine and Exhaust	\$14,076.1
39	Boiler Feed Pump	\$17,913.6
40	High Pressure Heaters	\$35,827.2
41	Critical Piping	\$80,611.2
42	Main Steam Piping	\$26,870.4
43	Cold Reheat Piping	\$26,870.4

	Task Name	Cost
44	Hot Reheat Piping	\$26,870.
45	Extraction Steam System	\$17,913.
46	Piping	\$17,913.
47	Heater Drips	\$14,330.
48	Piping	\$14,330.
49	Auxiliary Steam	\$25,079.
50	Auxiliary Boilers and Auxiliary Skids	\$8,956.
51	Auxiliary Steam Piping	\$16,122.
52	Circulating Water (plant side)	\$8,956.
53	Waterboxes	\$8,956.
54	Bearing Cooling Water	\$30,453.
55	Bearing Cooling Water Pumps	\$3,582.
56	Bearing Cooling Water Heat Exchanger	\$8,956.
57	Bearing Cooling Water Piping	\$17,913.
58	Auxiliary Cooling Water	\$28,661.
59	Auxiliary Cooling Water Heat Exchanger	\$5,374.
60	Auxiliary Cooling Water Pumps	\$5,374.
61	Auxiliary Cooling Water Piping	\$17,913.
62	Service Water	\$8,956.
63	Service Water Piping	\$8,956.
64	Fuel Oil System (plant side)	\$41,201.
65	Igniter Fuel Oil Pumps	\$5,374
66	Igniter Fuel Oil and Atomizing Air Piping	\$8,956
67	Igniters	\$26,870.
68	Waste Oil System	\$12,539
69	Waste Oil Tank	\$3,582.
70	Waste Oil Transfer Pump	\$3,582
71	Waste Oil Piping	\$5,374.
72	Air Preheat System	\$10,236
73	Air Preheat Pumps	\$3,582
74	Air Preheat Piping	\$6,653.
75	Condenser Air Extraction System	\$10,748
76	Vacuum Pumps	\$7,165.
77	Extraction Piping	\$3,582.
78	Turbine Seals and Drains	\$12,539.
79	Piping	\$12,539.
80	Turbine Lube Oil System	\$20,363.
81	Turbine Lube Oil Tank	\$11,406.
82	Turbine Lube Oil Pumps	\$7,165.
83	Turbine Oil Mist Eliminator	\$1,791.
84	Generator Auxiliary Systems	\$32,244.
85	Hydrogen Cooler Skid and Piping	\$8,956.
86	Stator Cooling Water Skid and Piping	\$8,956.
87	Isophase Bus Duct	\$7,165.

D	Task Name	Cost
88	Exciter Heat Exchanger	\$3,582.72
89	EHC Coolers	\$3,582.72
90	Chemical Feed Systems	\$19,303.20
91	Tanks	\$8,555.04
92	Pumps	\$5,374.08
93	Piping	\$5,374.08
94	Sampling Systems	\$6,434.40
95	Field Mounted Heat Exchangers	\$3,582.72
96	Piping	\$2,851.68
97	Building Heating Systems	\$13,307.84
98	Steam Unit Heaters	\$9,505.60
99	Steam Piping	\$3,802.24
100	Compressed Air System	\$26,870.40
101	Air Compressors	\$7,165.44
102	Air Drying Equipment	\$5,374.08
103	Air Reciever Tanks	\$5,374.08
104	Compressed Air Piping	\$8,956.80
105	Miscellaneous Equipment	\$21,496.32
106	Miscellaneous Equipment (including Fire Protection)	\$21,496.32
107	Phase 2 Demolition	\$2,929,157.36
108	Precipitator	\$107,481.60
109	Remove Precipitator	\$107,481.60
110	Boiler Equipment	\$732,490.24
111	Fans	\$63,246.40
112	Pulverizers	\$71,654.40
113	Bottom Ash	\$16,451.52
114	Air Heater	\$200,632.32
115	Steam Drum	\$89,568.00
116	Coal Bunkers	\$71,654.40
117	Coal Feeders	\$46,575.36
118	Soot Blowers	\$50,895.36
119	Ductwork	\$100,316.16
120	Miscellaneous Other	\$21,496.32
121	Boiler Removal	\$401,264.64
122	Furnace	\$229,294.08
123	Back Pass	\$171,970.56
124	Boiler Steel Framing	\$723,709.44
125	Hanger Girders at Top	\$107,481.60
126	All Other Framing	\$336,775.68
127	Bracing and Girts	\$164,805.12
128	Columns	\$114,647.04
129	Boiler Foundations	\$128,977.92
130	Equipment Foundation Demolition to Grade	\$128,977.92

ID	Task Name	Cost
132	Remove HP Turbine	\$26,321.60
133	Remove IP Turbine	\$26,321.60
134	Remove LP Turbine	\$26,321.60
135	Remove Generator	\$52,643.20
136	Remove Condenser Neck Heat Exchanger	\$26,321.60
137	Remove Condenser	\$26,321.60
138	Remove Misc. Auxiliary Turbine Equipment	\$39,482.40
139	Turbine Pedestal Demolition to Grade	\$268,480.32
140	Top Slab and Beams	\$105,286.40
141	Columns	\$163,193.92
142	Remove Turbine Building	\$343,019.60
143	Siding and Rooding	\$108,682.80
144	All Framing Elevations	\$157,929.60
145	Bracing and Girts	\$52,643.20
146	Columns	\$23,764.00
147	Phase 3 Yard Demolition	\$260,296.00
148	Circulating Water Pipe (yard)	\$71,654.40
149	Excavate Circulating Water Pipe	\$17,913.60
150	Collapse Circulating Water Pipe	\$35,827.20
151	Backfill Circulating Water Pipe	\$17,913.60
152	Remove Ash Handling Equipment and Piping	\$35,827.20
153	Remove Fly-Ash Silo and Scale	\$26,870.40
154	Remove Ash Piping and Misc. Equipment	\$8,956.80
155	Remove Laydown Equipment and Warehoused Equipment	\$71,654.40
156	Remove Unit 1 Condensate Storage Tank and Pump	\$9,505.60
157	Remove Unit 1 Make-Up Water Storage Tank	\$17,913.60
158	Remove Unit 1 Water Treatment Equipment and Building	\$53,740.80
159	Post Dismantlement Activities	\$65,520.00
160	Post Dismantlement Activities	\$65,520.00

)	Task Name	Duration		2012		2013		2014		201
			H2	H1	H2	H1	H2	H1	H2	\perp
1	latan Unit 1 Dismantlement									
2	Pre-Demolition Activities	265 days		ψ						
3	Detailed Planning & Hire Owner's Engineer	3 mons								
4	Detailed Site Characterization Study	130 days				_				
5	Hire Demolition General Contractor	3 mons								
6	KCP&L Prepares Unit for Dismantlement	2 wks								
7	Demolition Contractor Mobilizes on Site	5 days								
8	KCP&L Overhead during Dismantlement	430 days				1			-	
9	KCP&L Project Manager	430 days								
10	KCP&L Administrative Support	430 days								
11	KCP&L Engineer	430 days								
12	Owners Engineer Project Manager	430 days								
13	Owners Engineer - Engineer	430 days								
14	Demoliton Contractor Overhead during Dismantlement	430 days				•			_	
15	Demolition Contractor Project Manager	430 days								
16	Demolition Contractor Safety Manager	430 days								
17	Demolition Contractor Superintendent	430 days								
18	Demolition Contractor Equipment Rental Costs	430 days				•			-	
19	Equipment Rental	430 days								
20	Demolition Contractor Consummables	430 days				•			-	
21	Consummables	430 days								
22	Scrap Crew	430 days							-	
23	Crew to Handle Scrap Material(s)	430 days								
24	Dismantlement	430 days?								
25	Phase 1 Demolition	191 days?								
26	Phase 1 Electrical Demolition	191 days								
27	Electrical Demolition of Phase 1 Equipment	191 days						1		
28	Condensate System	30 days								
29	Condensate Pumps	2 days				Ħ				
30	Condensate Transfer Pumps	1 day				H				
31	Cycle Make-Up Pump	1 day				H				
32	Steam Packing Exhauster and Blower	2 days				*				

)	Task Name	Duration	2012			2013		2014		
			H2	H1	H2	H1	H2	H1	H2	H1
33	Low Pressure Heaters (except the condenser neck heat exchangers)	30 days								
34	Deaerator	8 days				h				
35	Deaerator Storage Tank	5 days				K				
36	Condensate Piping	10 days								
37	Boiler Feed System	37 days								
38	Boiler Feed Pump Turbine and Exhaust	7 days				K				
39	Boiler Feed Pump	10 days				💍				
40	High Pressure Heaters	20 days								
41	Critical Piping	45 days					-			
42	Main Steam Piping	15 days					Cre	v 2 Operator,	Crew 2	Laborer[3
43	Cold Reheat Piping	15 days					T Cre	w 2 Operato	, <mark>Crew</mark> :	2 Laborer
44	Hot Reheat Piping	15 days					Cı	ew 2 Operato	r,Crew	2 Labore
45	Extraction Steam System	10 days				-				
46	Piping	10 days								
47	Heater Drips	8 days				•				
48	Piping	8 days				7				
49	Auxiliary Steam	14 days					-			
50	Auxiliary Boilers and Auxiliary Skids	5 days					∓ C	rew 2 Operat	o <mark>r,Crev</mark>	/ 2 Labore
51	Auxiliary Steam Piping	9 days						rew 2 Operat	or,Cre	v 2 Labor
52	Circulating Water (plant side)	5 days								
53	Waterboxes	5 days				H				
54	Bearing Cooling Water	17 days								
55	Bearing Cooling Water Pumps	2 days				H				
56	Bearing Cooling Water Heat Exchanger	5 days								
57	Bearing Cooling Water Piping	10 days				5				
58	Auxiliary Cooling Water	16 days								
59	Auxiliary Cooling Water Heat Exchanger	3 days				<u> </u>				
60	Auxiliary Cooling Water Pumps	3 days								
61	Auxiliary Cooling Water Piping	10 days								
62	Service Water	5 days								
63	Service Water Piping	5 days				K				

)	Task Name	Duration		2012		2013		2014		2015
			H2	H1	H2	H1	H2	H1	H2	H1
64	Fuel Oil System (plant side)	120 days								
65	Igniter Fuel Oil Pumps	3 days				<u> </u>				
66	Igniter Fuel Oil and Atomizing Air Piping	5 days					Cre	w 3 Operat	tor,¢rew	3 Laborer
67	Igniters	15 days								
68	Waste Oil System	7 days								
69	Waste Oil Tank	2 days					Ь			
70	Waste Oil Transfer Pump	2 days					, h			
71	Waste Oil Piping	3 days					ή			
72	Air Preheat System	9 days				•	,			
73	Air Preheat Pumps	2 days				Ŀ				
74	Air Preheat Piping	7 days								
75	Condenser Air Extraction System	6 days								
76	Vacuum Pumps	4 days								
77	Extraction Piping	2 days					h h			
78	Turbine Seals and Drains	7 days								
79	Piping	7 days				*				
80	Turbine Lube Oil System	17 days?								
81	Turbine Lube Oil Tank	12 days				*				
82	Turbine Lube Oil Pumps	4 days				K				
83	Turbine Oil Mist Eliminator	1 day?				i i				
84	Generator Auxiliary Systems	18 days								
85	Hydrogen Cooler Skid and Piping	5 days				片				
86	Stator Cooling Water Skid and Piping	5 days				K				
87	Isophase Bus Duct	4 days				7				
88	Exciter Heat Exchanger	2 days				l K				
89	EHC Coolers	2 days								
90	Chemical Feed Systems	15 days					•			
91	Tanks	9 days								
92	Pumps	3 days					5			
93	Piping	3 days								
94	Sampling Systems	5 days								
95	Field Mounted Heat Exchangers	2 days	-			l H				

)	Task Name	Duration		2012		2013		2014		2015
			H2	H1	H2	H1	H2	H1	H2	H1
96	Piping	3 days								
97	Building Heating Systems	14 days								
98	Steam Unit Heaters	10 days	-							
99	Steam Piping	4 days	-							
100	Compressed Air System	15 days								
101	Air Compressors	4 days				+7777				
102	Air Drying Equipment	3 days				<u> </u>				
103	Air Reciever Tanks	3 days				<u>H</u>				
104	Compressed Air Piping	5 days				P				
105	Miscellaneous Equipment	12 days				•				
106	Miscellaneous Equipment (including Fire Protection)	12 days					ካ			
107	Phase 2 Demolition	333 days								
108	Precipitator	30 days								
109	Remove Precipitator	30 days					ightharpoons			
110	Boiler Equipment	134 days								
111	Fans	20 days								
112	Pulverizers	20 days					T			
113	Bottom Ash	6 days								
114	Air Heater	56 days								
115	Steam Drum	25 days								
116	Coal Bunkers	20 days								
117	Coal Feeders	13 days								
118	Soot Blowers	16 days								
119	Ductwork	28 days								
120	Miscellaneous Other	6 days					T T			
121	Boiler Removal	56 days								
122	Furnace	32 days								
123	Back Pass	24 days								
124	Boiler Steel Framing	101 days							—	
125	Hanger Girders at Top	15 days						*		
126	All Other Framing	47 days								
127	Bracing and Girts	23 days								

	Task Name	Duration		2012		2013		2014		2015
			H2	H1	H2	H1	H2	H1	H2	H:
128	Columns	16 days								
129	Boiler Foundations	18 days								
130	Equipment Foundation Demolition to Grade	18 days							I	
131	Remove Turbine	333 days								
132	Remove HP Turbine	10 days					Ď			
133	Remove IP Turbine	10 days					<u></u>			
134	Remove LP Turbine	10 days					<u> </u>			
135	Remove Generator	20 days								
136	Remove Condenser Neck Heat Exchanger	10 days					<u></u>			
137	Remove Condenser	10 days					<u></u>			
138	Remove Misc. Auxiliary Turbine Equipment	15 days					-			
139	Turbine Pedestal Demolition to Grade	102 days								
140	Top Slab and Beams	40 days								
141	Columns	62 days								
142	Remove Turbine Building	146 days								
143	Siding and Rooding	41 days								
144	All Framing Elevations	60 days								
145	Bracing and Girts	20 days							*	
146	Columns	25 days								
147	Phase 3 Yard Demolition	150 days								
148	Circulating Water Pipe (yard)	40 days								
149	Excavate Circulating Water Pipe	10 days				K				
150	Collapse Circulating Water Pipe	20 days								
151	Backfill Circulating Water Pipe	10 days				5				
152	Remove Ash Handling Equipment and Piping	20 days								
153	Remove Fly-Ash Silo and Scale	15 days								
154	Remove Ash Piping and Misc. Equipment	5 days				Ķ				
155	Remove Laydown Equipment and Warehoused Equipment	40 days								
156	Remove Unit 1 Condensate Storage Tank and Pump	10 days								
157	Remove Unit 1 Make-Up Water Storage Tank	10 days					K			

latan 1	. Dismantlement									
ID	Task Name	Duration		2012		2013		2014		2015
			H2	H1	H2	H1	H2	H1	H2	H1
158	Remove Unit 1 Water Treatment Equipment and Building	30 days								
159	Post Dismantlement Activities	40 days							-	
160	Post Dismantlement Activities	40 days							*	

D	Task Name	Cost
1	latan Unit 1 AQCS Dismantlement	\$3,382,301.12
2	Common Removal Overheads	\$341,196.80
3	Added Overhead Staff for Common Removals	\$341,196.80
4	Scrap Crew	\$609,062.40
5	Crew(s) to Handle Scrap Material	\$609,062.40
6	Demolition Contractor Consummables	\$819,372.80
7	Consummables	\$819,372.80
8	Demolition Contractor Equipment Rental Costs	\$616,651.20
9	Equipment Rental	\$616,651.20
10	Dismantlement	\$996,017.92
11	Initial Structural	\$130,313.68
12	Remove SCR box & ductwork lagging & insulation	\$17,913.60
13	Remove SCR expansion joints	\$10,748.16
14	Remove ductwork lagging & insulation	\$7,952.40
15	Remove ductwork expansion joints	\$17,913.60
16	Remove ductwork access platforms & ladders	\$17,913.60
17	Remove FF lagging, insulation, wall panel, & roof panels	\$35,827.20
18	Remove ID fan lagging & insulation	\$7,165.4
19	Removal all HVAC equipment located on FGD Bldg roof	\$5,374.0
20	Remove FGD Bldg lagging, insulation, wall panel, & roof	\$9,505.60
21	General Electric	\$202,423.68
22	Remove breakers serving all FF equipment	\$895.68
23	Remove breakers serving all FGD equipment	\$1,791.30
24	Remove breakers serving all ID fan equipment	\$895.68
25	Remove breakers serving all SCR equipment	\$895.68
26	Remove breakers serving all comp air equipment	\$895.68
27	Remove all ductwork primary instrumentation, controls & assoc'd cables, and conduit	\$8,956.80
28	Remove all FGD primary instrumentation, controls & assoc'd cables, and conduit	\$26,870.4
29	Remove all FF primary instrumentation, controls & assoc'd cables, and conduit	\$17,913.60
30	Remove SCR primary instrumentation, controls, & assoc'd cable & conduit	\$8,956.8
31	Remove NH3 supply primary instrumentation, controls, & assoc'd cable & conduit	\$8,956.86
32	Remove wiring and conduit serving FGD equipment, HVAC, lighting and convenience outlets	\$35,827.2
33	Remove wiring and conduit serving FF equipment, HVAC, lighting and convenience outlets	\$17,913.6
34	Remove wiring and conduit serving the ID fans and assoc'd equipment	\$21,496.3
35	Remove wiring & conduit serving SCR vaporization & injection equipment	\$5,374.0

D	Task Name	Cost
36	Remove wiring & conduit serving compressed air equipment	\$5,374.08
37	Remove wiring & conduit serving comp air equipment	\$3,582.72
38	Remove electrial control cabinets & switchgear	\$17,913.60
39	Demolish electrical control room	\$17,913.60
40	FGD System	\$201,109.68
41	Remove ductwork between FGD module and chimney	\$7,952.40
42	Remove support steel and access platforms between FGD and	\$5,374.08
	chimney	
43	Remove FGD elevator	\$8,956.80
44	Remove all mechanical equipment, pumps, and motors and tanks in FGD Bldg	\$35,827.20
45	Remove oxi air blowers	\$895.68
46	Remove all FGD piping & valves other than recirc piping	\$26,870.40
47	Remove ox air lines	\$5,374.08
48	Remove FGD MEs panels	\$9,542.88
49	Remove FGD outlet duct and top cone	\$5,374.08
50	Remove FGD internal wash ME piping and ME supports	\$5,374.08
51	Remove FGD internal spray header piping	\$8,956.80
52	Remove FGD support steel, access provisions, stair tower, and recirc piping from top down	\$35,827.20
53	Remove FGD module walls	\$17,913.60
54	Remove FGD inlet duct	\$5,374.08
55	Remove FGD reaction tank walls and floor	\$17,913.60
56	Remove FGD Bldg trench floor grating	\$3,582.72
57	ID Fans	\$78,819.84
58	Remove ductwork between ID fan outlets and FGD module	\$12,539.52
59	Remove support steel and access platforms between ID fan outlets and FGD module	\$5,374.08
60	Remove ductwork between FF outlet and ID fan inlets	\$12,539.52
61	Remove support steel between FF outlet and ID fan inlets	\$5,374.08
62	Removed ID fan isolation dampers	\$14,330.88
63	Removed ID fan drive motor	\$7,165.44
64	Remove ID fan seal air system	\$7,165.44
65	Remove fan casing & rotor	\$14,330.88
66	Fabric Filters	\$309,905.28
67	Remove ductwork between air heater and FF	\$8,956.80
68	Remove ductwork structural steel between AH and FF	\$5,374.08
69	Remove FF penthouse hoists and trolleys	\$7,165.44
70	Remove FF hopper heaters, HVAC, lighting and convenience outlets	\$17,913.60
71	Remove FF ash handling piping	\$26,870.40
72	Remove compress air blower, dryers, and receivers, piping & valves	\$17,913.60
73	Remove FF penthouse roof panels supporting steel	\$17,913.60
74	Remove FF compartment roof hatches	\$5,374.08

ID	Task Name	Cost
75	Remove FF compartment pulse air piping	\$5,374.08
76	Remove FF compartment pulse air and compressed air supply piping	\$10,748.16
77	Remove FF outlet poppet damper operators	\$12,539.52
78	Remove FF bags & cages	\$25,079.04
79	Remove FF bag support sheets	\$25,079.04
80	Remove remaining FF roof	\$7,165.44
81	Remove FF outlet dampers	\$7,165.44
82	Remove ductwork between air heater and FF	\$8,956.80
83	Remove FF wall panels to hopper level	\$50,158.08
84	Remove ductwork structural steel between AH and FF	\$5,374.08
85	Remove FF stair tower(s)	\$17,913.60
86	Remove FF inlet dampers	\$7,165.44
87	Remove FF hoppers	\$12,539.52
88	Remove FF support steel	\$7,165.44
89	SCR and Ammonia Supply	\$73,445.76
90	Vacuum SCR catalyst	\$3,582.72
91	Remove SCR catalyst	\$16,122.24
92	Remove ammonia injection grid	\$3,582.72
93	Remove NH3 piping between storage & injection	\$3,582.72
94	Remove air horn air receiver & supply piping	\$3,582.72
95	Remove SCR guillotine dampers	\$7,165.44
96	Remove SCr muliti-louver dampers	\$3,582.72
97	Remove SCR box, internal supports, & assoc'd ductwork	\$26,870.40
98	Remove NH3 piping between storage & vaporizors	\$5,374.08
99	Site Preperation Work	\$0.00
100	<new task=""></new>	\$0.00

	Task Name	Duration	Qtr 2 Qtr 3 Qtr 4	2013	O+n 2 O+:-	2014
1	latan Unit 1 AQCS Dismantlement	594.5 days	Qtr 2 Qtr 3 Qtr 4	Qtr 1 Qtr 2	Qtr 3 Qtr 2	I Qtr I
2	Common Removal Overheads	340 days		—		
3	Added Overhead Staff for Common Removals	340 days				
4	Scrap Crew	340 days		—		
5	Crew(s) to Handle Scrap Material	340 days		—		
6	Demolition Contractor Consummables	340 days		—		
7	Consummables	340 days		—		
8	Demolition Contractor Equipment Rental Costs	340 days		—		
9	Equipment Rental	340 days				
10	Dismantlement	340.5 days				
11	Initial Structural	202.5 days				
12	Remove SCR box & ductwork lagging & insulation	10 days				
13	Remove SCR expansion joints	6 days				
14	Remove ductwork lagging & insulation	5 days				
15	Remove ductwork expansion joints	10 days			>	
16	Remove ductwork access platforms & ladders	10 days			ή,	
17	Remove FF lagging, insulation, wall panel, & roof panels	20 days				h
18	Remove ID fan lagging & insulation	4 days			l h	
19	Removal all HVAC equipment located on FGD Bldg roof	3 days				
20	Remove FGD Bldg lagging, insulation, wall panel, & roof	10 days				
21	General Electric	108 days			₩	
22	Remove breakers serving all FF equipment	0.5 days		H H		
23	Remove breakers serving all FGD equipment	1 day				
24	Remove breakers serving all ID fan equipment	0.5 days				
25	Remove breakers serving all SCR equipment	0.5 days		Electric	cal Crew - Op	erator,E
26	Remove breakers serving all comp air equipment	0.5 days		*		
27	Remove all ductwork primary instrumentation, controls & assoc'd cables, and of	5 days		<u> </u>		
28	Remove all FGD primary instrumentation, controls & assoc'd cables, and cond	ا 15 days				
29	Remove all FF primary instrumentation, controls & assoc'd cables, and condui	t 10 days				
30	Remove SCR primary instrumentation, controls, & assoc'd cable & conduit	5 days				
31	Remove NH3 supply primary instrumentation, controls, & assoc'd cable & cond	5 days		 		

	Task Name	Duration	0. 5	-				2013
32	Remove wiring and conduit serving FGD equipment, HVAC, lighting and convenience outlets	20 days	Qtr 2	Qtr 3 0	Qtr 3 Qtr 4 Qtr 1	Qtr 3 Qtr 4 Qtr 1 Qtr 2	Qtr 3 Qtr 4 Qtr 1 Qtr 2 Qtr 3	Qtr 3 Qtr 4 Qtr 1 Qtr 2 Qtr 3 Qtr
33	Remove wiring and conduit serving FF equipment, HVAC, lighting and convenience outlets	10 days						
34	Remove wiring and conduit serving the ID fans and assoc'd equipment	12 days						
35	Remove wiring & conduit serving SCR vaporization & injection equipment	3 days						
36	Remove wiring & conduit serving compressed air equipment	3 days						
37	Remove wiring & conduit serving comp air equipment	2 days						
38	Remove electrial control cabinets & switchgear	10 days						
39	Demolish electrical control room	10 days						
40	FGD System	98.5 days						
41	Remove ductwork between FGD module and chimney	5 days						
42	Remove support steel and access platforms between FGD and chimney	3 days						
43	Remove FGD elevator	5 days						
44	Remove all mechanical equipment, pumps, and motors and tanks in FGD Bldg							
45	Remove oxi air blowers	0.5 days						
46	Remove all FGD piping & valves other than recirc piping	15 days					🕌	
47	Remove ox air lines	3 days					*	#
48	Remove FGD MEs panels	6 days						
49	Remove FGD outlet duct and top cone	3 days						
50	Remove FGD internal wash ME piping and ME supports	3 days						
51	Remove FGD internal spray header piping	5 days						
52	Remove FGD support steel, access provisions, stair tower, and recirc piping from	20 days						
53	Remove FGD module walls	10 days					*	
54	Remove FGD inlet duct	3 days						
55	Remove FGD reaction tank walls and floor	10 days						
56	Remove FGD Bldg trench floor grating	2 days						
57	ID Fans	65 days						
58	Remove ductwork between ID fan outlets and FGD module	7 days						
59	Remove support steel and access platforms between ID fan outlets and FGD n							
60	Remove ductwork between FF outlet and ID fan inlets	7 days						
61	Remove support steel between FF outlet and ID fan inlets	3 days						
62	Removed ID fan isolation dampers	8 days						

	Task Name	Duration	
63	Removed ID fan drive motor	4 days	_
64	Remove ID fan seal air system	4 days	
65	Remove fan casing & rotor	8 days	
66	Fabric Filters	265.5 days	
67	Remove ductwork between air heater and FF	5 days	
68	Remove ductwork structural steel between AH and FF	3 days	
69	Remove FF penthouse hoists and trolleys	•	
	Remove FF hopper heaters, HVAC, lighting and convenience outlets	4 days	
70	Remove FF ash handling piping	10 days	
71		15 days	
72	Remove compress air blower, dryers, and receivers, piping & valves	10 days	
73	Remove FF penthouse roof panels supporting steel	10 days	
74	Remove FF compartment roof hatches	3 days	
75	Remove FF compartment pulse air piping	3 days	
76	Remove FF compartment pulse air and compressed air supply piping	6 days	
77	Remove FF outlet poppet damper operators	7 days	
78	Remove FF bags & cages	14 days	
79	Remove FF bag support sheets	14 days	
80	Remove remaining FF roof	4 days	
81	Remove FF outlet dampers	4 days	
82	Remove ductwork between air heater and FF	5 days	
83	Remove FF wall panels to hopper level	28 days	
84	Remove ductwork structural steel between AH and FF	3 days	
85	Remove FF stair tower(s)	10 days	
86	Remove FF inlet dampers	4 days	
87	Remove FF hoppers	7 days	
88	Remove FF support steel	4 days	
89	SCR and Ammonia Supply	38 days	
90	Vacuum SCR catalyst	2 days	
91	Remove SCR catalyst	9 days	
92	Remove ammonia injection grid	2 days	
93	Remove NH3 piping between storage & injection	2 days	
94	Remove air horn air receiver & supply piping	2 days	

latan 1	L AQCS Dismantlement										
ID	Task Name	Duration				2013				2014	
			Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2
95	Remove SCR guillotine dampers	4 days					H				
96	Remove SCr muliti-louver dampers	2 days					H				
97	Remove SCR box, internal supports, & assoc'd ductwork	15 days									
98	Remove NH3 piping between storage & vaporizors	3 days									
99	Site Preperation Work	1 day									
100	<new task=""></new>	1 day									

UNIT 2

latan 2 Retirement

Owner Costs

Pre-Retirement Activities \$100,822
Retirement Activities \$658,400
Post-Retirement Activities \$26,564

Owner Direct Total \$785,786

Owner Internal Costs 5.00% \$39,289

Owner Contingency: 25.00% \$206,269

latan 2 Retirement Opinion of Probable Cost: \$1,031,343.60

)	Task Name	Cost
1	latan 2 Retirement	\$785,786.45
2	Pre-Engineering	\$100,821.60
3	Permit review and engineering analysis, establish isolation points, and confirm fuel yard inventory has been reduced to zero tons.	\$0.00
4	KCL&L Overhead Costs	\$114,006.40
5	KCP&L Retirement Manager	\$114,006.40
6	Equipment Rentals	\$38,625.28
7	Vacuum truck	\$38,625.28
8	Retirement	\$505,769.17
9	Electrical	\$18,911.68
10	Medium and Low Voltage Draw out Switchgear	\$2,679.84
11	De-energize all buses at the source.	\$446.64
12	Open all circuit breakers.	\$446.64
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	\$446.64
14	Verify that the closing/tripping springs are discharged.	\$446.64
15	De-energize control power and auxiliary power circuits of each circuit	\$893.28
	breaker at the source and by opening control power circuit breakers or removing fuses in each breaker cubicle.	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,
16	Motor Control Centers	\$1,786.56
17	De-energize all buses at the source.	\$446.64
18	Open all circuit breakers and disconnect switches.	\$446.64
19	Remove all fuses in control circuits.	\$893.28
20	Low-voltage Switchboards and Panelboards	\$893.28
21	De-energize all buses at the source.	\$446.64
22	Open all circuit breakers and disconnect switches.	\$446.64
23	Oil-Filled Power Transformers	\$5,549.44
24	De-energize all transformer primaries and verify that the secondary is de-energized.	\$893.28
25	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	\$893.28
26	Drain and dispose of oil.	\$2,642.88
27	Clean up and dispose of oil on surface areas around the transformers on in containment pits.	\$1,120.00
28	Dry-type Power Transformers	\$1,786.56
29	De-energize all transformer primaries and verify that the secondary is de-energized.	\$893.28
30	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	\$893.28
31	Motors	\$6,216.00
32	De-energize all primary power at the source.	\$1,786.56

	Task Name	Cost
33	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	\$1,786.56
34	Drain lube oil system (if applicable) and dispose of oil.	\$2,642.88
35	Coal Handling	\$27,475.44
36	Empty all transfer hoppers.	\$1,704.56
37	Burn out coal silos.	\$1,685.44
38	Confirm all fuel lines, conveyors and trippers are clear of fuel.	\$1,685.44
39	Perform cleaning of the coal handling equipment to assure that all coal and coal dust has been removed from site.	\$22,400.00
40	Fuel Oil and Igniter System	\$2,528.16
41	Drain fuel oil system	\$2,528.16
42	Boiler Chemical Feed	\$1,685.44
43	Drain all chemical feed tanks.	\$1,685.44
44	Boiler	\$27,484.77
45	Open boiler doors.	\$880.96
46	Gas side - perform cleaning of the boiler and bottom ash system.	\$22,400.00
47	Drain boiler, drum, downcomers and headers.	\$842.72
48	Open drum doors.	\$880.96
49	Drain and clean the submerged flight conveyor system.	\$2,480.13
50	Stack and Ductwork	\$326,961.04
51	Open ductwork doors.	\$880.96
52	Perform extensive cleaning of the ductwork.	\$11,200.00
53	Place cap over stack opening to keep moisture out.	\$314,880.08
54	Condensate and Feedwater Piping	\$1,685.44
55	Drain water from the system.	\$842.72
56	Leave open vents and drains.	\$842.72
57	Feedwater heaters	\$2,528.16
58	Drain feedwater heaters	\$842.72
59	Leave open vents and drains.	\$1,685.44
60	Deaerator and Deaerator Storage Tank	\$1,685.44
61	Drain Deaerator and Storage	\$842.72
62	Leave open vents and drains.	\$842.72
63	Baghouse	\$17,351.92
64	Multiple cleaning cycles for filter bags.	\$2,528.16
65	Open all vent and drain lines on bag cleaning air and control air lines. Leave in open position or remove vent valves.	\$842.72
66	Remove all filter bags and cages.	\$880.96
67	Clear hoppers of all ash	\$2,805.44
68	Mechanically secure all compartment dampers and hopper outlet valves in open position.	\$880.96
69	Disconnect ash transport piping and washdown baghouse hoppers and interior of casing.	\$1,421.84
70	Install bird screens across hopper ash outlet and ash line flanges.	\$880.96

	Task Name	Cost
71	Padlock or tack weld all hopper doors shut. (note: if ash hopper doors are indoors, they could be removed and the opening covered with bird screens.)	\$880.96
72	If walk-in plenum, padlock or tack weld all outlet plenum doors and compartment ventilation dampers shut.	\$880.96
73	If top-door plenum, close and secure top doors and remove/disable door lift hoist.	\$1,723.68
74	If top-door plenum, establish natural ventilation or maintain HVAC fan to provide minimum air changes per hour in penthouse enclosure.	
75	Pull electrical supply breakers on all electrical equipment except lighting and HVAC components that are to remain in service.	\$2,679.84
76	Wet FGD system	\$23,908.00
77	Multiple mist eliminator wash cycles. Remove ME's from absorber.	\$2,145.04
78	Drain and flush all slurry and reclaim water pumps and piping. Leave vent and drain valves open or remove. Install bird screens across drain openings.	\$1,723.68
79	Drain and wash out the reaction tank, reagent storage tank, recycle water tank, absorber blowdown tank, etc.	\$4,624.08
80	Leave all tank drain valves open or remove. Install bird screens across openings.	\$1,761.92
81	Drain all makeup and mist eliminator water pumps and piping. Leave vent and drain valves open or remove. Install bird screens across drain openings.	\$2,604.64
82	Mechanically secure all flue gas isolation dampers in open position or remove damper blades.	\$1,761.92
83	Remove solids from all inlet and outlet ductwork as necessary	\$2,240.00
84	Open all vent station air and control air lines. Leave in open position or remove vent valves	\$1,723.68
85	Padlock or tack weld all access doors to modules and ductwork shut.	\$1,762.24
86	Remove access doors to open-top tanks.	\$880.96
87	Pull electrical supply breakers on all electrical equipment except lighting and HVAC components that are to remain in service.	\$2,679.84
88	FGD Reagent Preparation-Limestone wet Scrubber	\$10,262.88
89	Remove limestone from day bins.	\$1,402.72
90	Removed cartridges/bags from bin vent filters	\$1,402.72
91	Padlock or tack weld all bin access doors shut. (note: if doors are indoors, they could be removed and the opening covered with bird screens.)	\$881.12
92	Remove bin discharge isolation valve and install bird screen.	\$440.48
93	Thoroughly wash and drain mills	\$1,402.72
94	Remove balls from any ball mills	\$1,120.00
95	Padlock or tack weld mill access doors closed.	\$881.12
96	Establish natural ventilation or maintain HVAC fan to provide minimum air changes per hour in building.	\$945.44

)	Task Name	Cost			
97	Pull electrical supply breakers on all electrical equipment except lighting and HVAC components that are to remain in service.	\$1,786.56			
98	FGD Byproduct Dewatering - Hydrocyclones and Vacuum Filters	\$7,287.12			
99	Wash vacuum filter belt and remove all accumulated solids	\$2,240.00			
100	Wash out vacuum receiver, remove pressure relief valve and access door. Install bird screens.				
101					
102	Pull electrical supply breakers on all electrical equipment except lighting and HVAC components that are to remain in service.	\$2,679.84			
103	SCR	\$10,054.00			
104	Vacuum fly ash from catalyst.	\$2,240.00			
105	Remove catalyst of salvage or disposal.	\$2,881.92			
106	Padlock or tack weld access doors shut.	\$880.96			
107	Remove ammonia from storage tank for resale.	\$701.36			
108	Wash out and drain storage tank and supply piping.	\$701.36			
109					
110	Pull electrical supply breakers on all electrical equipment except lighting and HVAC components that are to remain in service.	\$1,786.56			
111	Turbine(s) and Condenser	\$5,266.64			
112	Drain hotwell and leave doors open.	\$861.84			
113	Open main turbine doors.	\$880.96			
114	Open bfp turbine doors.	\$880.96			
115	Remove lube oil.	\$2,642.88			
116	Generator	\$6,095.76			
117	Verify that generator circuit breaker is open and racked out or that high-voltage disconnect switch on substation side of GSU transformer is locked in the open position.	\$446.64			
118	Verify that generator field breaker or contactor (if applicable) is open.	\$446.64			
119	De-energize power supplies to generator excitation system at the source.	\$446.64			
120	De-energize AC and DC power supplies to generator and exciter space heaters, cooling equipment, controls, lighting, etc. at the source and open circuit breakers or remove fuses at the generator and exciter.	\$446.64			
121	Drain generator and exciter cooling water systems (if applicable).	\$861.84			
122	Disconnect and remove hydrogen gas tanks and purge generator hydrogen system.	\$1,685.44			
123	Disconnect and remove fire protection system gas/foam tanks and purge fire protection system.	\$1,761.92			
124	Circulation Water and Turbine Cooling Water System	\$3,409.12			
125	Drain.	\$1,685.44			
126	Open water box doors.	\$880.96			
127	Drain any circulating water chemical feed tanks.	\$842.72			

D	Task Name	Cost
128	Compressed Air System	\$2,721.28
129	Open vents and drains.	\$842.72
130	Remove desiccant from desiccant dryers.	\$1,878.56
131	Auxiliary Steam System	\$1,685.44
132	Drain water from system.	\$842.72
133	Remove aux boiler chemicals.	\$842.72
134	Auxiliary Cooling Water System	\$842.72
135	Drain water from system.	\$842.72
136	Condenser Air Extraction and Waterbox Priming System	\$842.72
137	Drain water from system.	\$842.72
138	Building Heating System	\$842.72
139	Drain water from system.	\$842.72
140	Battery System	\$4,253.28
141	De-energize all battery chargers from the source.	\$446.64
142	Open all AC and DC circuit breakers and/or fused switches on battery	\$446.64
	chargers and disconnect cables from batteries.	
143	Remove and dispose of battery electrolyte.	\$1,680.00
144	Remove and dispose of battery cells.	\$1,120.00
145	Clean up and dispose of electrolyte on surface areas around batteries.	\$560.00
146	Post Retirement Activities	\$26,564.00

147

Post Retirement Activities

\$26,564.00

	Task Name	Duration	1st Quarter	2nd Qu	2nd Quarter 3rd Quarter	2nd Quarter 3rd Quarter 4th Quarter
1	latan 2 Retirement	290 days	_			
2	Pre-Engineering	66 days		Ţ		
3	Permit review and engineering analysis, establish isolation	66 days				
	points, and confirm fuel yard inventory has been reduced to zero tons.					
4	KCL&L Overhead Costs	184 days		-	—	—
5	KCP&L Retirement Manager	184 days				*
6	Equipment Rentals	184 days				
7	Vacuum truck	184 days		1	—	*
8	Retirement	184 days		Į		
9	Electrical	22 days			—	
10	Medium and Low Voltage Draw out Switchgear	3 days	-			
11	De-energize all buses at the source.	0.5 days		Ь₩		
12	Open all circuit breakers.	0.5 days		Ϊ́		
13	Rack all circuit breakers into the fully withdrawn,	0.5 days		Ϊ́		
	disconnected position.					
14	Verify that the closing/tripping springs are discharged.	0.5 days		h		
15	De-energize control power and auxiliary power circuits	1 day		ľ		
	of each circuit breaker at the source and by opening					
	control power circuit breakers or removing fuses in each					
	breaker cubicle.					
16	Motor Control Centers	2 days	_			
17	De-energize all buses at the source.	0.5 days		Ъ		
18	Open all circuit breakers and disconnect switches.	0.5 days		<u>F</u>		
19	Remove all fuses in control circuits.	1 day		Ĭ		
20	Low-voltage Switchboards and Panelboards	1 day				
21	De-energize all buses at the source.	0.5 days		h		
22	Open all circuit breakers and disconnect switches.	0.5 days		I		
23	Oil-Filled Power Transformers	7 days				
24	De-energize all transformer primaries and verify that the	1 day		h		
	secondary is de-energized.					

	Task Name	Duration	1st Quarter	2nd Quarter	3rd Quarter 4tl	n Quarter	1st Quarter	2nd Qu
25	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	1 day		F				
26	Drain and dispose of oil.	3 days		4				
27	Clean up and dispose of oil on surface areas around the transformers on in containment pits.	2 days		ľ				
28	Dry-type Power Transformers	2 days						
29	De-energize all transformer primaries and verify that the secondary is de-energized.	1 day		h				
30	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	1 day		ř				
31	Motors	7 days		-				
32	De-energize all primary power at the source.	2 days		h				
33	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	2 days		Ť				
34	Drain lube oil system (if applicable) and dispose of oil.	3 days						
35	Coal Handling	25 days		-				
36	Empty all transfer hoppers.	1 day		J				
37	Burn out coal silos.	2 days		H				
38	Confirm all fuel lines, conveyors and trippers are clear of fuel.	2 days		İ				
39	Perform cleaning of the coal handling equipment to assure that all coal and coal dust has been removed from site.	20 days						
40	Fuel Oil and Igniter System	3 days						
41	Drain fuel oil system	3 days						
42	Boiler Chemical Feed	2 days						
43	Drain all chemical feed tanks.	2 days			ı *			
44	Boiler	27 days						
45	Open boiler doors.	1 day			ı†			

D	Task Name	Duration	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Quarter	2nd Quarte
46	Gas side - perform cleaning of the boiler and bottom ash system.	20 days						
47	Drain boiler, drum, downcomers and headers.	1 day			₽ *			
48	Open drum doors.	1 day			ř			
49	Drain and clean the submerged flight conveyor system.	5 days			7			
50	Stack and Ductwork	12 days				₽		
51	Open ductwork doors.	1 day			h			
52	Perform extensive cleaning of the ductwork.	10 days				<u> </u>		
53	Place cap over stack opening to keep moisture out.	1 day				ř		
54	Condensate and Feedwater Piping	2 days			Ţ			
55	Drain water from the system.	1 day				h		
56	Leave open vents and drains.	1 day				Ĭ		
57	Feedwater heaters	3 days						
58	Drain feedwater heaters	1 day				h		
59	Leave open vents and drains.	2 days				ř		
60	Deaerator and Deaerator Storage Tank	2 days						
61	Drain Deaerator and Storage	1 day				h		
62	Leave open vents and drains.	1 day				Ĭ		
63	Baghouse	16 days						
64	Multiple cleaning cycles for filter bags.	3 days						
65	Open all vent and drain lines on bag cleaning air and control air lines. Leave in open position or remove vent valves.	1 day				F		
66	Remove all filter bags and cages.	1 day				H		
67	Clear hoppers of all ash	4 days						
68	Mechanically secure all compartment dampers and hoppe outlet valves in open position.	r 1 day				P		
69	Disconnect ash transport piping and washdown baghouse hoppers and interior of casing.	1 day				F		
70	Install bird screens across hopper ash outlet and ash line flanges.	1 day				K		

	Task Name	Duration	1st Quarter 2nd Quarter 3rd Quarter 4th Quarter
71	Padlock or tack weld all hopper doors shut. (note: if ash hopper doors are indoors, they could be removed and the opening covered with bird screens.)	1 day	
72	If walk-in plenum, padlock or tack weld all outlet plenum doors and compartment ventilation dampers shut.	1 day	H
73	If top-door plenum, close and secure top doors and remove/disable door lift hoist.	2 days	
74	If top-door plenum, establish natural ventilation or maintain HVAC fan to provide minimum air changes per hour in penthouse enclosure.	1 day	
75	Pull electrical supply breakers on all electrical equipment except lighting and HVAC components that are to remain ir service.	3 days	
76	Wet FGD system	19 days	V-V
77	Multiple mist eliminator wash cycles. Remove ME's from absorber.	3 days	
78	Drain and flush all slurry and reclaim water pumps and piping. Leave vent and drain valves open or remove. Install bird screens across drain openings.	2 days	
79	Drain and wash out the reaction tank, reagent storage tank, recycle water tank, absorber blowdown tank, etc.	3 days	
80	Leave all tank drain valves open or remove. Install bird screens across openings.	2 days	
81	Drain all makeup and mist eliminator water pumps and piping. Leave vent and drain valves open or remove. Install bird screens across drain openings.	2 days	
82	Mechanically secure all flue gas isolation dampers in open position or remove damper blades.	2 days	
83	Remove solids from all inlet and outlet ductwork as necessary	2 days	
84	Open all vent station air and control air lines. Leave in open position or remove vent valves	2 days	
85	Padlock or tack weld all access doors to modules and ductwork shut.	2 days	

	Task Name	Duration	1st Quarter 2nd Quarter 3rd Quarter 4th Quarter 1st Quarter 2nd Qu
86	Remove access doors to open-top tanks.	1 day	
87	Pull electrical supply breakers on all electrical equipment except lighting and HVAC components that are to remain ir service.	3 days	
88	FGD Reagent Preparation-Limestone wet Scrubber	9 days	▼
89	Remove limestone from day bins.	2 days	h h
90	Removed cartridges/bags from bin vent filters	2 days	i
91	Padlock or tack weld all bin access doors shut. (note: if doors are indoors, they could be removed and the opening covered with bird screens.)	1 day	
92	Remove bin discharge isolation valve and install bird screen.	1 day	F
93	Thoroughly wash and drain mills	2 days	
94	Remove balls from any ball mills	2 days	H H
95	Padlock or tack weld mill access doors closed.	1 day	
96	Establish natural ventilation or maintain HVAC fan to provide minimum air changes per hour in building.	1 day	
97	Pull electrical supply breakers on all electrical equipment except lighting and HVAC components that are to remain ir service.	2 days	
98	FGD Byproduct Dewatering - Hydrocyclones and Vacuum Filters	5 days	
99	Wash vacuum filter belt and remove all accumulated solids	2 days	h h
.00	Wash out vacuum receiver, remove pressure relief valve and access door. Install bird screens.	1 day	
.01	Establish natural ventilation or maintain HVAC fan to provide minimum air changes per hour in building.	1 day	
.02	Pull electrical supply breakers on all electrical equipment except lighting and HVAC components that are to remain ir service.	3 days	
L03	SCR	6 days	
.04	Vacuum fly ash from catalyst.	4 days	
.05	Remove catalyst of salvage or disposal.	4 days	

	Task Name	Duration	1st Quarter 2nd Quarter 3rd Quarter 4th Quarter 1st Quarter
106	Padlock or tack weld access doors shut.	1 day	
107	Remove ammonia from storage tank for resale.	1 day	P
108	Wash out and drain storage tank and supply piping.	1 day	K I
109	Vent storage tank and all piping. Leave vent and drain valves open or remove. Install bird screens.	1 day	
110	Pull electrical supply breakers on all electrical equipment except lighting and HVAC components that are to remain in service.	2 days	
111	Turbine(s) and Condenser	6 days	•
112	Drain hotwell and leave doors open.	1 day	l γ γ
113	Open main turbine doors.	1 day	
114	Open bfp turbine doors.	1 day	Ĭ Ĭ
115	Remove lube oil.	3 days	T T
116	Generator	7 days	
117	Verify that generator circuit breaker is open and racked ou or that high-voltage disconnect switch on substation side of GSU transformer is locked in the open position.	t0.5 days	h h
118	Verify that generator field breaker or contactor (if applicable) is open.	0.5 days	, the state of the
119	De-energize power supplies to generator excitation system at the source.	0.5 days	F
120	De-energize AC and DC power supplies to generator and exciter space heaters, cooling equipment, controls, lighting, etc. at the source and open circuit breakers or remove fuses at the generator and exciter.	0.5 days	
121	Drain generator and exciter cooling water systems (if applicable).	1 day	
122	Disconnect and remove hydrogen gas tanks and purge generator hydrogen system.	2 days	
123	Disconnect and remove fire protection system gas/foam tanks and purge fire protection system.	2 days	
124	Circulation Water and Turbine Cooling Water System	3 days	
125	Drain.	2 days	h
126	Open water box doors.	1 day	The state of the s

)	Task Name	Duration	1st Quarter	2nd Quarter 3rd Quarter	4th Quarter 1st Quarter	2nd Quarte
127	Drain any circulating water chemical feed tanks.	1 day				
128	Compressed Air System	3 days				
129	Open vents and drains.	1 day			η	
130	Remove desiccant from desiccant dryers.	2 days			Ĭ	
131	Auxiliary Steam System	2 days				
132	Drain water from system.	1 day			h	
133	Remove aux boiler chemicals.	1 day			I T	
134	Auxiliary Cooling Water System	1 day				
135	Drain water from system.	1 day			I	
136	Condenser Air Extraction and Waterbox Priming System	1 day			₩	
137	Drain water from system.	1 day			I	
138	Building Heating System	1 day			•	
139	Drain water from system.	1 day			I	
140	Battery System	7 days				
141	De-energize all battery chargers from the source.	0.5 days			h	
142	Open all AC and DC circuit breakers and/or fused switches on battery chargers and disconnect cables from batteries.	0.5 days			ř	
143	Remove and dispose of battery electrolyte.	3 days			*	
144	Remove and dispose of battery cells.	2 days			†	
145	Clean up and dispose of electrolyte on surface areas around batteries.	1 day			i	
146	Post Retirement Activities	40 days			-	-
147	Post Retirement Activities	40 days			*	

latan 2 Dismantlement

Owner Additional Costs

Pre-Dismantlement Activities \$1,020,485

Overhead During Dismantlement \$1,916,492

Post-Dismantlement Activities \$70,596

Owner Costs Total* \$3,007,573

Demolition General Contractor (DGC) Costs

 Additional Site Management
 \$1,434,705

 Equipment Rental
 \$2,483,702

 Consummables
 \$2,711,297

 Scrap Crew(s)
 \$2,457,174

 Dismantlement*
 \$5,879,227

Contractor Direct Cost* \$14,966,105

Contractor Allowances

DGC Insurance 2.00% \$299,322

Contingency/Profit 15.00% \$2,289,814

Performance Bond 2.00% \$351,104.82

Contractor Costs Total: \$17,906,346


Total: \$20,913,919

Owner Internal Costs: 5.00% \$1,045,696

Owner Contingency: 25.00% \$5,489,904

latan Unit 2 Dismantlement Opinion of Probable Cost: \$27,449,519

^{*}Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances = \$17,973,678



latan Common Retirement

Owner Costs

Pre-Retirement Activities \$52,449
Retirement Activities \$365,473
Post-Retirement Activities \$32,080

Owner Direct Total \$450,002

Owner Internal Costs 5.00% \$22,500

Owner Contingency: 25.00% \$118,125

latan Common Retirement Opinion of Probable Cost: \$590,627.36

Activities Required by Permit or Regulation

Iatan Fuel Oil Tank Removal\$239,995Iatan Ash Landfill Closure, Phase 1\$1,470,192Iatan Ash Landfill Closure, Phase 2\$2,308,430Iatan Ash Landfill Post Closure, Phase 1 & 2\$2,024,220

Activities Required by Permit or Regulation: \$6,042,837

)	Task Name	Cost
1	latan Common Retirement	\$450,003.76
2	Pre-Retirement Activities	\$52,448.80
3	Permitting Review	\$26,224.40
4	Develop Detailed Retirement Plan	\$26,224.40
5	Overheads	\$102,172.56
6	Common Retirement Overheads	\$89,367.44
7	Added Overhead Staff for Common Retirement	\$89,367.44
8	Common Retirment Equipment Rental	\$12,805.12
9	Common Removal Equipment Rental	\$12,805.12
10	Retirement Activities	\$263,301.60
11	Administration Building	\$17,175.60
12	Secure Administration Building	\$17,175.60
13	Fuel Yard Office Building	\$10,305.36
14	Secure Fuel Yard Office Building	\$10,305.36
15	Training Building	\$10,305.36
16	Secure Training Building	\$10,305.36
17	Warehouse(s)	\$10,607.20
18	Secure Unit 1 Warehouse	\$3,736.96
19	Secure Unit 2 Warehouse	\$6,870.24
20	Maintenance Shop	\$25,951.20
21	Secure Maintenance Shop	\$25,951.20
22	Fuel Yard	\$131,234.64
23	Transfer Towers	\$80,527.44
24	Clean Transfer Tower 1	\$3,784.08
25	Clean Transfer Tower 2	\$3,784.08
26	Clean and Secure Crusher Building	\$6,306.80
27	Clean Stockout Conveyor Reclaim Pit	\$12,613.60
28	Conveyors	\$17,659.04
29	Clean Conveyor 2A, 4, 5B 6A, 6B, 7A and 7B	\$17,659.04
30	Car Dumper	\$8,829.52
31	Empty Car Dumper Hoppers	\$1,261.36
32	Clean Car Dumper	\$3,784.08
33	Secure Dumper Building	\$3,784.08
34	Remove Stacker/Reclaimer	\$19,173.20
35	Clean and Secure Stacker/Reclaimer	\$6,306.80
36	Unit 1 Reclaim	\$5,045.44
37	Clean Unit 1 Reclaim	\$2,522.72
38	Secure Unit 1 Reclaim Building	\$2,522.72
39	Sewage Treatment	\$4,202.72
40	Clean Sewage Treatment and Transfer Points	\$4,202.72
41	Fuel Oil Storage and Unloading	\$842.72
42	Remove Fuel Oil from Fuel Oil Storage and Vent	\$842.72
43	Yard Fire Water Systems	\$842.72
44	Drain Yard Fire Water System	\$842.72

latan Common Retirement

ID	Task Name	Cost
45	Reagent Prep and Gypsum Handling	\$29,365.20
46	Clean and Secure Limestone Unloading Facility	\$3,784.08
47	Clean and Secure Limestone Storage Facility	\$3,784.08
48	Clean Limestone Conveyor	\$3,859.92
49	Clean and Secure Limestone Prep Building	\$6,433.20
50	Clean Gypsum Stackout Conveyor	\$2,573.28
51	Clean and Secure PCM-1	\$2,573.28
52	Clean and Secure PCM-2	\$2,573.28
53	Clean and Secure the Vacuum Pump and Air Compressor Building	\$3,784.08
54	Water Pretreatment and ZLD	\$22,468.88
55	Drain and Clean Clarifiers	\$3,784.08
56	Drain and Clean ZLD System	\$7,568.16
57	Clean and Secure ZLD Building	\$8,593.92
58	Drain and Vent Storage Tanks	\$2,522.72
59	Post Retirement Closure Activities	\$32,080.80
60	Post Retirement Closure Activities	\$32,080.80

D	Task Name	Duration	er		1st Quarter		2nd Quarter				3rd Quar
			Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul
1	latan Common Retirement	131 days									7
2	Pre-Retirement Activities	40 days			—						
3	Permitting Review	20 days				ሷ					
4	Develop Detailed Retirement Plan	20 days			i)				
5	Overheads	61 days				•					
6	Common Retirement Overheads	61 days				-					
7	Added Overhead Staff for Common Retirement	61 days									
8	Common Retirment Equipment Rental	61 days									
9	Common Removal Equipment Rental	61 days									
10	Retirement Activities	61 days				-					
11	Administration Building	15 days				-					
12	Secure Administration Building	15 days									
13	Fuel Yard Office Building	9 days					-				
14	Secure Fuel Yard Office Building	9 days						h			
15	Training Building	9 days						-			
16	Secure Training Building	9 days									
17	Warehouse(s)	8 days									
18	Secure Unit 1 Warehouse	2 days									
19	Secure Unit 2 Warehouse	6 days									
20	Maintenance Shop	20 days									
21	Secure Maintenance Shop	20 days									
22	Fuel Yard	51 days									
23	Transfer Towers	21 days					-	,			
24	Clean Transfer Tower 1	3 days									
25	Clean Transfer Tower 2	3 days									
26	Clean and Secure Crusher Building	5 days					_				
27	Clean Stockout Conveyor Reclaim Pit	10 days)			
28	Conveyors	14 days					•				
29	Clean Conveyor 2A, 4, 5B 6A, 6B, 7A and 7B	14 days									
30	Car Dumper	7 days									
31	Empty Car Dumper Hoppers	1 day						ħ			
32	Clean Car Dumper	3 days						*			

Task Name		Duration	er		1st Quarter			2nd Quarter			3rd Quar
			Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul
33	Secure Dumper Building	3 days						I			
34	Remove Stacker/Reclaimer	5 days						<u> </u>			
35	Clean and Secure Stacker/Reclaimer	5 days							ካ		
36	Unit 1 Reclaim	4 days						Ţ			
37	Clean Unit 1 Reclaim	2 days							ή		
38	Secure Unit 1 Reclaim Building	2 days							T		
39	Sewage Treatment	4 days				•					
40	Clean Sewage Treatment and Transfer Points	4 days					ή				
41	Fuel Oil Storage and Unloading	1 day					—				
42	Remove Fuel Oil from Fuel Oil Storage and Vent	1 day					\mathcal{T}_{1}				
43	Yard Fire Water Systems	1 day									
44	Drain Yard Fire Water System	1 day					Ř				
45	Reagent Prep and Gypsum Handling	23 days									
46	Clean and Secure Limestone Unloading Facility	3 days					4				
47	Clean and Secure Limestone Storage Facility	3 days					Th				
48	Clean Limestone Conveyor	3 days									
49	Clean and Secure Limestone Prep Building	5 days)			
50	Clean Gypsum Stackout Conveyor	2 days									
51	Clean and Secure PCM-1	2 days						Š			
52	Clean and Secure PCM-2	2 days						T			
53	Clean and Secure the Vacuum Pump and Air	3 days						*			
	Compressor Building										
54	Water Pretreatment and ZLD	15 days						-			
55	Drain and Clean Clarifiers	3 days						T			
56	Drain and Clean ZLD System	6 days									
57	Clean and Secure ZLD Building	4 days									
58	Drain and Vent Storage Tanks	2 days									
59	Post Retirement Closure Activities	40 days									-
60	Post Retirement Closure Activities	40 days									

Iatan Common Dismantlement

Owner Additional Costs

Pre-Dismantlement Activities \$0
Overhead During Dismantlement \$0

Post-Dismantlement Activities

Owner Costs Total* \$0

Demolition General Contractor (DGC) Costs

 Additional Site Management
 \$86,011

 Equipment Rental
 \$419,326

 Consummables
 \$628,251

 Scrap Crew(s)
 \$623,393

 Dismantlement
 \$14,083,108

Contractor Direct Cost* \$15,840,089

Contractor Allowances

DGC Insurance 2.00% \$316,802

Contingency/Profit 15.00% \$2,423,534

Performance Bond 2.00% \$371,608.49

Contractor Costs Total: \$18,952,033

Total: \$18,952,033

Owner Internal Costs: 5.00% \$947,602

Owner Contingency: 25.00% \$4,974,909

latan Common Dismantlement Opinion of Probable Cost: \$24,874,543

^{*}Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances = \$15,840,089

)	Task Name	Cost
1	latan Common Dismantlement	\$15,840,077.07
2	Overheads	\$1,756,968.56
3	Common Removal Overheads	\$86,011.67
4	Added Overhead Staff for Common Removals	\$86,011.67
5	Common Removal Equipment Rental	\$419,326.08
6	Common Removal Equipment Rental	\$419,326.08
7	Scrap Crew	\$623,393.36
8	Crew(s) to Handle Scrap Material	\$623,393.36
9	Demolition Contractor Consummables	\$628,237.44
10	Consummables	\$628,237.44
11	Dismantlement Activities	\$14,083,108.51
12	Administration Building	\$35,827.20
13	Remove Administration Building	\$35,827.20
14	Fuel Yard Office Building	\$17,913.60
15	Remove Fuel Yard Office Building	\$17,913.60
16	Training Building	\$17,913.60
17	Remove Training Building	\$17,913.60
18	Parking Lots and Plant Roads	\$82,402.56
19	Plant Roads and Parking Areas	\$71,654.40
20	Guard Shack	\$10,748.16
21	Warehouse(s)	\$35,827.20
22	Remove Unit 1 Warehouse	\$17,913.60
23	Remove Unit 2 Warehouse	\$17,913.60
24	Maintenance Shop	\$23,215.20
25	Remove Maintenance Shop	\$23,215.20
26	Fuel Yard	\$752,371.20
27	Remove Transfer Towers	\$465,753.60
28	Transfer Tower 1	\$35,827.20
29	Transfer Tower 2	\$35,827.20
30	Crusher Building	\$71,654.40
31	Stockout Conveyor Reclaim Pit	\$89,568.00
32	Remove Conveyors	\$125,395.20
33	Conveyor 2A, 4, 5B 6A, 6B, 7A and 7B	\$125,395.20
34	Remove Car Dumper	\$89,568.00
35	Remove Underground Equipment	\$17,913.60
36	Remove Above Ground Equipment	\$35,827.20
37	Remove Building	\$17,913.60
38	Backfill Dumper Structure	\$17,913.60
39	Remove Stacker/Reclaimer	\$7,165.44
40	Remove Stacker/Reclaimer	\$3,582.72
41	Remove Unit 1 Reclaim	\$64,488.96
42	Remove Underground Equipment	\$17,913.60
43	Remove Above Ground Equipment	\$17,913.60
44	Remove Building	\$14,330.88

D	Task Name	Cost
45	Backfill Structure	\$14,330.88
46	Sewage Treatment	\$21,496.32
47	Remove Sewage Treatment Pumps and Miscellaneous Equipment	\$7,165.44
48	Remove Sewage Treatment Concrete Structures	\$14,330.88
49	Yard Fire Water Systems	\$35,827.20
50	Remove Hydrants and Fire Water System Piping Down to 3' Below Grade	\$35,827.20
51	Water Pretreatment Clarifiers and ZLD	\$121,812.48
52	Remove Clarifier Vessels	\$10,748.16
53	Remove Pump House	\$17,913.60
54	Remove Clarifier Water Storage Tanks	\$17,913.60
55	Remove Water Treatment Equipment	\$10,748.16
56	Remove Water Treatment Building	\$17,913.60
57	Remove ZLD Equipment	\$10,748.16
58	Remove ZLD Building	\$17,913.60
59	Remove Condensate Storage Tanks	\$17,913.60
60	Stacks	\$11,027,325.89
61	Remove Unit 1 Stack to Grade	\$4,198,401.00
62	Remove Common Stack to Grade	\$6,828,924.89
63	Reagent Prep and Gypsum Handling	\$336,775.68
64	Remove Limestone Unloading Facility	\$35,827.20
65	Remove Limestone Storage Facility	\$17,913.60
66	Remove Limestone Conveyor	\$17,913.60

\$143,308.80

\$17,913.60

\$7,165.44

\$7,165.44

\$71,654.40

\$17,913.60

\$1,574,400.38

\$1,574,400.38

67

68

69

70

71

72

73

74

Remove Limestone Prep Building

Remove PCM-1

Remove PCM-2


Remove Gypsum Stackout Conveyor

Remove Miscellaneous Equipment

Final Site Grading and Drainage

Final Site Grading and Drainage

Remove the Vacuum Pump and Air Compressor Building



	Task Name	Duration	2nd Quarter				3rd Qua	3rd Quarter			4th Quarter		
			Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	- 1	
33	Conveyor 2A, 4, 5B 6A, 6B, 7A and 7B	35 days											
34	Remove Car Dumper	25 days					_						
35	Remove Underground Equipment	5 days											
36	Remove Above Ground Equipment	10 days											
37	Remove Building	5 days											
38	Backfill Dumper Structure	5 days							ካ				
39	Remove Stacker/Reclaimer	1 day?						Ţ	-				
40	Remove Stacker/Reclaimer												
41	Remove Unit 1 Reclaim	18 days							4				
42	Remove Underground Equipment	5 days											
43	Remove Above Ground Equipment	5 days											
44	Remove Building	4 days							*				
45	Backfill Structure	4 days							¥				
46	Sewage Treatment	6 days											
47	Remove Sewage Treatment Pumps and Miscellaneous Equipment	2 days											
48	Remove Sewage Treatment Concrete Struc	tı 4 days				$\stackrel{\bigstar}{=}$							
49	Yard Fire Water Systems	10 days					•						
50	Remove Hydrants and Fire Water System Piping Down to 3' Below Grade	10 days											
51	Water Pretreatment Clarifiers and ZLD	34 days				Ţ							
52	Remove Clarifier Vessels	3 days											
53	Remove Pump House	5 days											
54	Remove Clarifier Water Storage Tanks	5 days					±						
55	Remove Water Treatment Equipment	3 days					*						
56	Remove Water Treatment Building	5 days						1					
57	Remove ZLD Equipment	3 days						5					
58	Remove ZLD Building	5 days											
59	Remove Condensate Storage Tanks	5 days						*					
60	Stacks	1 day?											
61	Remove Unit 1 Stack to Grade	1 day?											
62	Remove Common Stack to Grade	1 day?											

D	Task Name	Duration		2nd Qua	Quarter		3rd Quarter			4th Quarter		
			Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
63	Reagent Prep and Gypsum Handling	94 days										
64	Remove Limestone Unloading Facility	10 days							h			
65	Remove Limestone Storage Facility											
66	Remove Limestone Conveyor	5 days										
67	Remove Limestone Prep Building	40 days										
68	Remove Gypsum Stackout Conveyor	5 days										
69	Remove PCM-1	2 days									5	
70	Remove PCM-2	2 days										
71	Remove the Vacuum Pump and Air Compressor Building	20 days										
72	Remove Miscellaneous Equipment	5 days										
73	Final Site Grading and Drainage	1 day?										Ų
74	Final Site Grading and Drainage	1 day?										,

APPENDIX B

OPINIONS OF COSTS FOR SCRAP

OPINIONS OF SCRAP VALUES

The opinion of scrap value was based on a scrap value of:

1. Mixed Scrap: \$370.00/GT.

2. Insulated Cables: \$2.56/lb.

3. Motors: \$0.37/lb.

These scrap values were taken from www.scrapmonster.com. This website is an industry-

recognized source of scrap information that provides daily scrap pricing for the worldwide

scrap market.

Attached in the back of this Appendix is information that was developed from the

quantities used to build a 20-MW, coal-fired power plant (CFPP) located in the Midwest.

Per the attached spreadsheet:

1. 20-MW, CFPP Scrap Value: \$483,672.

The AACE International Capacity Factor Method (AACE) was used to estimate the scrap

value of the other coal-fired units. The capacity factor method is based on the following

calculation:

UnitA(scrap value)=CFPP(scrap value)*(CapacityUnitA/CapacityCFPP)^e

Where:

1. UnitA(scrap value) = Unit A Scrap Value.

CFPP(scrap value)= 20-MW, CFPP Scrap Value: \$483,672.

CapacityUnitA = Capacity of Unit A.

4. CapacityCFPP = 20 MW.

5. e = Proration Factor: 0.6 per the AACE guidelines.

Therefore, the scrap value of the other CFPPs is as follows:

SIBLEY UNIT 1

- 1. Capacity A = 51 MW.
- 2. Scrap Value = \$848,154.

SIBLEY UNIT 2

- 1. Capacity A = 51 MW.
- 2. Scrap Value = \$848,154.

SIBLEY UNIT 3

- 1. Capacity A = 363.8 MW.
- 2. Scrap Value = \$2,757,087.

LAKE ROAD 4/6

- 1. Capacity A = 99 MW.
- 2. Scrap Value = \$1,262,740.

The value of the common portion of these facilities was estimated at approximately 12-percent of the combined scrap values of the units on site.

Therefore:

- 1. Sibley Common: Scrap Value = \$1,564,200.
- 2. Lake Road Common: Scrap Value = \$248,964.

The scrap value of a 75-MW combustion turbine was calculated based on the following scrap weights:

- 1. Combustion Turbine: 250,000 lbs.
- 2. Generator: 280,000 lbs.
- 3. Total: 530,000 lbs.
- 4. Scrap Value of a 75-MW Combustion Turbine: (530,000 lbs/2,000 lbs/ton) * 370/GT = \$98,000.

The AACE method was used to estimate the scrap value of the GMO combustion turbines as described above.

SOUTH HARPER

- 1. Capacity A = 104.6 MW.
- 2. Number of CTs = Three.
- 3. Scrap Value = \$358,946.

GREENWOOD

- 1. Capacity A = 63.2 MW.
- 2. Number of CTs = Four.
- 3. Scrap Value = \$353,746.

CROSSROADS

- 1. Capacity A = 74.2 MW.
- 2. Number of CTs = Four.
- 3. Scrap Value = \$389,486.

KCI

- 1. Capacity A = 21 MW.
- 2. Number of CTs = Two.
- 3. Scrap Value = \$91,317.

NEVADA

- 1. Capacity A = 21 MW.
- 2. Number of CTs = One.
- 3. Scrap Value = \$45,397.

RALPH GREEN

- 1. Capacity A = 71.5 MW.
- 2. Number of CTs = One.
- 3. Scrap Value = \$95,230.

LAKE ROAD CT 5

- 1. Capacity A = 63 MW.
- 2. Number of CTs = One.
- 3. Scrap Value = \$88,266.

LAKE ROAD CTS 6 AND 7

- 1. Capacity A = 21 MW.
- 2. Number of CTs = Two.
- 3. Scrap Value = \$91,317.

The approximate weight of a 160-MW turbine is 342 tons. The AACE method was used to estimate the weight of the Lake Road turbines to determine scrap value.

LAKE ROAD STEAM TURBINE GENERATOR 1

- 1. Weight = 103 tons.
- 2. Scrap Value = \$38,162.

LAKE ROAD STEAM TURBINE GENERATOR 2

- 1. Weight = 118 tons.
- 2. Scrap Value = \$43,797.

LAKE ROAD STEAM TURBINE GENERATOR 3

- 1. Weight = 69 tons.
- 2. Scrap Value = \$25,661.

The approximate weight of the boiler that produces 220,000 lbs/hr of steam is 561 tons. The AACE method was used to estimate the weight of the Lake Road boilers to determine scrap value.

LAKE ROAD BOILER 1

- 1. Weight = 317 tons.
- 2. Scrap Value = \$117,312.

LAKE ROAD BOILER 2

- 1. Weight = 317 tons.
- 2. Scrap Value = \$117,312.

LAKE ROAD BOILER 3

- 1. Weight = 410 tons.
- 2. Scrap Value = \$151,376.

LAKE ROAD BOILER 4

- 1. Weight = 530 tons.
- 2. Scrap Value = \$196,024.

LAKE ROAD BOILER 5

- 1. Weight = 605 tons.
- 2. Scrap Value = \$224,107.

LAKE ROAD BOILER 8

- 1. Weight = 605 tons.
- 2. Scrap Value = \$224,107.

KCP&L-GMO Baghouse Weights

Baghouse Ductwork and Paneling Weights

		Length		
Member	Number	(foot)	lb/foot	weight (lb)
L2X2X1/4	4	6	3.19	76.56
C5X6.7	4	36	6.7	964.8
C6X8.2	4	25	8.2	820
L3X2X1/4	4	13	4.1	213.2
C5X6.7	2	45	6.7	603
C7X9.8	1	52	9.8	509.6
W10X26	1	30	26	780
L2 1/2X1 1/2 X 1/4	1	23	3.22	74.06
C5X6.7	1	60	6.7	402
W10X26	1	20	26	520
C5X6.7	1	2332	6.7	15624.4
C5X6.7	2	3424	6.7	45881.6
C4x5.4	2	440	5.4	4752
C5X6.7	1	990	6.7	6633
W10X26	1	1164	26	30264
				108,118 lbs
Assume plate adds 50% additional w	eight:			162,177 lbs
Weight of Ductwork:				270,296 lbs
Drawings of the baghouse structural Assume that the steel weighs approx				138,000 lbs
Total Estimated Scrap Weight of Bag	house:			408,000 lbs

Pipe Description	Length (ft)	Material Spec.	Equipment List #	Found on sheet:	Pipe Diameter	Unit Weight (lbs.)	Total Weight (lbs.)
8" Main Steam	112	P1	A01	8, 9, 18, 19	8	50.9	5700.8
4" Aux from Main to PRV	15	P1	A02	19	4	14.98	224.7
6" Steam from A2 to Desuperheating nozzle	8.5	P1	A03	19	6	28.57	242.845
3" Aux Steam	99	P1	A04	8, 9, 18, 19	3	10.25	1014.75
2" Aux Steam	13	P1	A05	8	2	5.02	65.26
	13	P1	AUS	0		3.02	03.20
1.5" Steam from A5 to Aux Oil Turbine Pump	58	P1	A06	8	1.5	3.63	210.54
1" Aux Steam from A5 to Starting Ejector	16.5	P1	A07	8	1	2.17	35.805
Auxillary steam PRV to							
flange past 260# safty	45	P2	A08	18	6	28.57	1285.65
valve							
A8 to 260# header	5	P5	A09	18	6	18.97	94.85
260# common header	25	P5	A11	18, 21	6	18.97	474.25
A11 to 150# safty valve	1	P5	A12	18	1	28.57	28.57
150# steam header		P5	A13	18	6	18.97	132.79
A13 to boiler burner	,	13	AIS	10	<u> </u>	10.57	132.73
header	10	P5	A14	18	6	18.97	189.7
A22 to building heating system	70	P5	A23	18	6	18.97	1327.9
A22 to intake structure	45	P5	A24	18, 21	3	18.97	853.65
heating system 10" Extraction No. 4 to	21	DE	DO1	11 12	10	40 F	050.5
Heater No. 1 8" Extraction No. 3 to	21	P5	B01	11, 13	10	40.5	850.5
Heater No. 2	135	P5	B02	11, 14, 16	8	28.6	3861
6" Extraction No. 2 to Heater No. 3	36	P5	B03	11, 13	6	18.97	682.92
6" Extraction (B3) to 8"	20	P5	B04	11	6	18.97	379.4
Extraction (B2)							
6" Extraction (B3) to Evaporator	96	P5	B05	11, 14, 16	6	18.97	1821.12
4" Extraction No. 1 to Heater No. 4	54	P5	B06	11, 14	4	10.79	582.66
4" Extraction (B6) to 8"	22	P5	B07	11, 14	4	10.79	237.38
Extraction (B2)				·			
4" Extraction (B6) to B5	11	P5	B08a	11	4	10.79	118.69
4" Extraction (B6) to B5	18	P5	B08b	11	6	18.97	341.46
8" Line from B2 to Back Pressure Valve	16	P5	C01	16	8	28.6	457.6
8" line from Evaporator to							
C1	8.5	P5	C02	16	8	28.6	243.1
Evaporator to Evaporator Feed Heater	7.5	P5	C03	16	8	28.6	214.5
8" Steam Exhaust	134	P5	C04a		8	28.6	3832.4
6" Disch. From Priming Eject	28.5	P5	C04b	8, 9	6	18.97	540.645
4" Exhaust from Aux Oil	45.5	P5	C05	8, 9	4	10.79	490.945
Pump B.F.P. Turbine Exhaust to	7	P5	C06	15	8		200.2
line B2 B.F. Pumps Disch. To and				15		28.6	ZUU.Z
including Header	153	P3	D01	11, 15, 18, 19, 20,	4	14.98	2291.94
Header to Heater No. 3 including bypass	25	Р3	D02	12	4	14.98	374.5
Heater No. 3 to Heater No. 4 including bypass	30	P3	D03	12	4	14.98	449.4
Heater No. 4 to Boiler							
stop check valve	30	P3	D04	14	4	14.98	449.4
Emergency feed from D1 to boiler stop check valve	30	Р3	D05	14	4	14.98	449.4

Pipe Description	Length (ft)	Material Spec.	Equipment List #	Found on sheet:	Pipe Diameter	Unit Weight (lbs.)	Total Weight (lbs.)
T.D.B.F. Pump recirculation to Htr. No. 2	64	P3	D06a	12, 16	1.25	3	192
T.D.B.F. Pump recirculation to Htr. No. 2	18	P3	D06b	12, 16	1	2.17	39.06
M.D.B.F. Pump recirculation to D6	5	Р3	D07	12	1	2.17	10.85
D1 to desuperheater in line A8	42	P3	D08	19	1	2.17	91.14
D8 to Chem Feed Tank	57	Р3	D09	11, 12, 15, 19	1.25	3	171
Chem Feed tank to boiler connection	28	Р3	D10	19	1	2.17	60.76
Hotwell to Condensate Pumps	2	P6	E01	13	6	18.97	37.94
Condensate pump to condensate cooler including bypass	35	P6	E02	11, 15	4	10.79	377.65
Condensate cooler to hyd. Cooler including bypass	16	P6	E03a	11	4	10.79	172.64
Condensate cooler to hyd. Cooler including bypass	35	P6	E03b	11	6	18.97	663.95
Hyd. Cooler to air ejector	15	P6	E04	11, 13	4	10.79	161.85
E3 to bearing water make- up	25	P6	E05a	11	2	3.65	91.25
E3 to bearing water make- up	14	P6	E05b	11	1.5	1.09	15.26
E5 to gland water storage	103	P6	E06	11, 16	1.5	1.09	112.27
Air ejector to Heater No. 1 including bypass	35	P6	E07	13	4	10.79	377.65
Recirculation line from E7 to condenser	20	P6	E08	13	2.5	5.79	115.8
bypass from E7 to lower surge tank	15	P6	E09	14	3	7.58	113.7
Heater No. 1 to Heater No. 2	62	P6	E10	14, 16	6	18.97	1176.14
Heater No. 1 to Drip Pump	18	P6	E11	15	2.5	5.79	104.22
Drip Pump to E10	9	P6	E12	14	2.5	5.79	52.11
Recirculation line from E12 to Heater No. 1	21	P6	E13	14	3	7.58	159.18
Drip Pump bypass from E11 to condenser.	6	P6	E14	15	3	7.58	45.48
Return line from lower surge tank to condenser	40	P6	E15	12, 14	3	7.58	303.2
Lower Surge Tank to transfer pump	5	P6	E16	14	4	10.79	53.95
Transfer pump to E10	18	P6	E17	12	3	7.58	136.44
Heater No. 2 to B.F. Pumps	74	P6	E18	12, 15, 16	1.25	3	222
Heater No. 2 overflow to lower surge tank	58	P6	E19	12, 15, 16	6	18.97	1100.26
Heater No. 2 drain to line E19	4.5	P6	E20	16	2	3.65	16.425
Line E19 to drain	25	P6	E21	14, 15	6	18.97	474.25
Lower surge tank overflow to line E21	10	P6	E22	14	3	7.58	75.8
Gland seal water tank to turbine	same as E6	same as E6	E23	same as E6	same as E6		n/a
Heater No. 1 bypass from line E29 to E14	10	P6	E24	15	2.5	5.79	57.9

KCP&L-GMO Pipe Weights (per Unit)

Pipe Description	Length (ft)	Material Spec.	Equipment List #	Found on sheet:	Pipe Diameter	Unit Weight (lbs.)	Total Weight (lbs.)
Condensate return header							
from lower surge tank No.	60	P6	E25	17	4	10.79	647.4
1 to lower surge tank No.	00	10	LZS	17	7	10.75	047.4
2							
Heater No. 4 drips to	13	P6	E26	13, 14	2.5	5.79	75.27
Heater No. 3		1 0	220	15, 14	2.5	3.73	7 3.27
Heater No. 3 bypass from	10	P6	E27	14	2.5	5.79	57.9
line E26 to line E28	10	1 0	L27	17	2.5	3.73	57.5
Heater No. 3 drips to	53	P6	E28	15, 16	4	10.79	571.87
Heater No. 2				13, 10	-	10.75	371.07
Line E28 to Heater No. 1	19	P6	E29	15	2.5	5.79	110.01
Boiler drum safety valve	63	P6	G01	22	8	28.6	1801.8
vents through roof		10	001	22	0	20.0	1001.0
superheater safety valve	61.5	P6	G02	22	6	18.97	1166.655
vent thru roof	01.5	10	GUZ		0	10.57	1100.055
Drip pan elbows to line F8		Р6	G03				0
Safety valve drains to line							
G3		Р6	G04				0
Condensate pump vents							
to condenser	21	Р6	G05	13, 15	4	10.79	226.59
Heater No.1 vent to							
condenser	15	Р6	G06	15	3	7.58	113.7
Drip Pump vent to Heater	_	_					_
No. 1	10	P6	G07	15	3	7.58	75.8
Blowdown tank vent thru					_		
roof	102	P6	G08	20	8	28.6	2917.2
Daria harada atau ada a	42	D.C	600	47	2	7.50	225.04
Drain header to ash sump	43	P6	G09	17	3	7.58	325.94
Evaporator drain to line	F.C.	D.C	640	47	2	7.50	424.40
G9	56	P6	G10	17	3	7.58	424.48
Evaporator Feed Heater	74	D.C	644	46 47	2	7.50	520.40
drain to line G10	71	P6	G11	16, 17	3	7.58	538.18
6" Air Suction	51	P6	K1 & K2	8, 9	6	18.97	967.47

Total Weight (per Unit): 47,554 lbs
Total Weight: 95,108 lbs

APPENDIX C

REFERENCE DOCUMENTS

REFERENCE DOCUMENTS

- 1. Decommissioning Handbook for Coal-Fired Power Plants, EPRI, Palo Alto, CA: 2004. (1011220)
- 2. Decommissioning Process for Fossil-Fueled Power Plants, EPRI, Palo Alto, CA: 2010. (1020652)
- 3. Association for the Advancement of Cost Estimating (AACE) International, *Skills and Knowledge of Cost Engineering*, 5th Edition, 2004.
- 4. Combustion Fossil Power, Fourth Edition, 1991.
- 5. Steam Its Generation and Use, 40th Edition, 1992.
- 6. Daniel International Corporation, La Cygne Station Unit 2, Weekly Progress Report No. 175, October 1, 1976.
- 7. Black & Veatch, Iatan Steam Generating Station Monthly Progress Report, November 1979.

APPENDIX D

ARO - SOURCE OF REQUIREMENT

Appendix D ARO - Source of Requirement

<u>Station</u>	Equipment	Source of Requirement
Greenwood	Fuel Oil Storage Tanks	Missouri Regulation 10 CSR 26-5.020 Release Reporting and Initial Release Response Measures
Nevada	Fuel Oil Storage Tank	Missouri Regulation 10 CSR 26-5.020 Release Reporting and Initial Release Response Measures
Ralph Green	Ash Pond Landfill Closure	Missouri Regulation 10 CSR 80-2.030
Sibley	Propane Storage Tanks	Missouri Regulation 10 CSR 20-15.020 Release Reporting and Initial Release Response Measures
	Common Pond	Missouri State Operating Permit MO-0004871, Missouri Regulation 10 CSR 80-2.030
	Landfill Stage A	Solid Waste Operating Permit #709505
	Units 1 & 2 River Intake	US Army Corps of Engineers Section 10 Permit - Rivers & Harbor Act of March 3, 1899
	Unit 3 River Intake	US Army Corps of Engineers Section 10 Permit - Rivers & Harbor Act of March 3, 1899
Lake Road	Boiler 5 Pond	Missouri State Operating Permit MO-0004898
	Turbine Generator 4 River Intake	US Army Corps of Engineers Section 10 Permit - Rivers & Harbor Act of March 3, 1899
	Boiler 5 Tank	Missouri Regulation 10 CSR 26-5.020 Release Reporting and Initial Release Response Measures
	Boiler 6 Tank	Missouri Regulation 10 CSR 26-5.020 Release Reporting and Initial Release Response Measures
	Boiler 7 Tank	Missouri Regulation 10 CSR 26-5.020 Release Reporting and Initial Release Response Measures
latan	latan Fuel Oil Tank Removal	Missouri Regulation 10 CSR 26-5.020 Release Reporting and Initial Release Response Measures
	latan Landfill Retirement	Solid Waste Operating Permit No. 0916501