

Exhibit No.: 37
Issue: Dismantlement Costs
Witness: Christopher "Chris" Robert Rogers
Type of Exhibit: Direct Testimony
Sponsoring Party: KCP&L Greater Missouri Operations Company
Case No.: ER-2016-0156
Date Testimony Prepared: February 23, 2016

FILED

MISSOURI PUBLIC SERVICE COMMISSION

SEP 22 2016

CASE NO.: ER-2016-0156

**Missouri Public
Service Commission**

DIRECT TESTIMONY

OF

CHRISTOPHER "CHRIS" ROBERT ROGERS

ON BEHALF OF

KCP&L GREATER MISSOURI OPERATIONS COMPANY

**Kansas City, Missouri
February 2016**

DIRECT TESTIMONY
OF
CHRISTOPHER “CHRIS” ROBERT ROGERS

Case No. ER-2016-0156

1 **Q: Please state your name and business address.**

2 A: My name is Christopher “Chris” Robert Rogers and my business address is Sega, Inc.,
3 16041 Foster Street, Overland Park, Kansas 66085.

4 **Q: On whose behalf are you testifying?**

5 A: I am testifying on behalf of KCP&L Greater Missouri Operations Company (“GMO” or
6 the “Company”).

7 **Q: What is the purpose of your testimony?**

8 A: The purpose of my testimony is to present and support the report attached to my
9 testimony as Schedule CRR-2 which separately addresses the near-term costs of
10 retirement and the potential future costs for dismantlement of GMO’s fossil-fueled
11 electric generating units. All costs are presented in 2015 dollars as if incurred over night.
12 No timeline for retirement or dismantlement was considered in this study. As further
13 described later, certain activities are required by permit or regulation to be performed
14 upon retirement of a unit and their resulting costs would be incurred immediately at
15 retirement.

16 **Q: Please describe your educational background, professional training and experience.**

17 A: Since graduating from Kansas State University with a Bachelor of Science in Mechanical
18 Engineering, I have practiced engineering, principally in the power industry, for more
19 than 40 years. During the first decade of my career, I performed design, construction

1 contracting, scheduling, and resident construction management services for new coal-
2 fired electric generating stations with a nationally-recognized architect/engineer firm in
3 Kansas City. During this interval I also completed a Master of Science in Civil
4 Engineering specializing in construction management from the University of Missouri-
5 Columbia.

6 From 1983 through 1986 I served as the Manager of Generating Facilities on the
7 staff of the Missouri Public Service Commission (“Commission” or “MPSC”) and
8 participated in several major rate cases, including the AmerenUE Callaway Nuclear Plant
9 and KCP&L Wolf Creek Nuclear Plant rate cases before the MPSC. Later while
10 employed as a consultant, I provided testimony on behalf of Aquila, Inc. in the South
11 Harper Generating Facility certification case before the MPSC. I have also testified
12 before the Hawaii Public Utilities Commission on behalf of the Hawaii State Consumer
13 Advocate.

14 I am currently an employee-owner and Vice President of Sega, Inc., (“Sega”) an
15 engineering and technical services firm located in Overland Park, Kansas. Among other
16 duties, I provide consulting and project management services for Sega’s electric power
17 generating clients. Since joining Sega in 1994, I have worked on many projects for
18 KCP&L and our other electric utility clients. Sega has provided engineering services for
19 numerous plant betterment and new capacity projects for KCP&L’s generation stations.

20 In 2012, I provided pre-filed testimony in support of KCP&L before the Kansas
21 Corporation Commission in Docket No. 12-KCPE-764-RTS regarding the near term
22 costs of retirement and the potential future costs for dismantlement of the Company’s

1 fossil-fueled electric generating units. In 2014, I also provided pre-filed testimony for
2 KCP&L before the MPSC in Case No. ER-2014-0370 on this issue.

3 **Q: Do you hold any professional licenses?**

4 A: Yes. I am a licensed professional engineer in the State of Missouri (License No. 21087)
5 and 12 other states. I also hold a Certificate of Record from the National Council of
6 Examiners for Engineering and Surveying (No. 19249).

7 **Q: Have you prepared an appendix that describes your training, licenses and power
8 industry experience?**

9 A: Yes. My professional qualifications are provided in Schedule CRR-1.

10 **Q: Have you previously testified in a proceeding before the MPSC or before any other
11 utility regulatory agency?**

12 A: Yes, I have previously testified before the MPSC, the Public Utility Commission of the
13 State of Hawaii and the Kansas Corporation Commission. The subject matter and
14 references for the cases in which I participated are provided at the back of Schedule
15 CRR-1.

16 **SUMMARY**

17 **Q: Would you briefly describe the retirement and dismantlement costs developed for
18 GMO's non-nuclear generating units?**

19 A: Sega was retained by GMO to study the cost of decommissioning GMO's non-nuclear
20 generating units. Decommissioning is the planned and orderly retirement of a generating
21 unit and the dismantlement and reclamation of the site. The term *decommissioning*
22 includes both retirement and dismantlement activities. Upon retirement from service, a
23 generating unit may either be rendered safe and stored almost indefinitely through on-

1 going maintenance and security measures or it can be dismantled completely and the site
2 reclaimed for other uses. Based upon Sega's experience in the electric generation
3 industry at large and our familiarity with GMO's generating fleet, Sega developed an
4 opinion of the probable costs for GMO to retire each of its fossil-fueled generating units.
5 Costs for dismantlement were also developed separately for each unit.

6 **Q: Please summarize retirement of an electric generating unit.**

7 **A:** Retirement, as used in this study, refers to the planned, orderly and safe shutdown and
8 removal from service of an electric generating unit, and assumes that the unit will not be
9 used for service again. No actions will be taken to preserve the unit or any of its
10 components for reuse. Retirement activities are specific to each unit and to the common
11 facilities at sites with multiple generating units. Common site facilities are presumed to
12 remain in service until the last unit on that site is retired.

13 Approximately three to six months before initiating retirement, a specific
14 retirement plan will be prepared for each unit that takes into account the requirements of
15 environmental permits and regulations for removing that unit from service. The
16 retirement plan will also provide for necessary safety and security measures during
17 retirement of the unit and for the time period from retirement until dismantlement.

18 First, the unit is rendered safe by de-energizing it and disconnecting it from
19 providing output to the electric grid. The switchyards at each unit will remain in service,
20 but isolated from the retired facility. Mechanical systems are de-energized as well. Fuel
21 unloading, handling and storage facilities will be cleaned out, as well as all liquids,
22 chemicals, coolants and reagents. Certain activities are required by specific unit permits
23 and/or state or federal regulations to be performed when the unit ceases operations.

1 These may include closure of ash landfills, removal of river water intakes, and/or
2 removal of fuel oil storage tanks. However, retirement activities do not include asbestos
3 and lead paint abatement measures that are typically handled as ongoing maintenance
4 expenses during the operating life of the unit and continuing if necessary after retirement.
5 More detail is provided on retirement activities in our report, which is Schedule CRR-2.

6 **Q: Please summarize dismantlement of an electric generating unit.**

7 A: Once the unit or facility has been retired and its dismantlement is scheduled, an engineer
8 will be retained to assist with environmental issues and technical details and develop a
9 detailed dismantlement plan. The unit or facility will be characterized and the boundaries
10 for demolition defined to set the scope of the work. A specialty demolition contractor
11 will be hired to perform dismantlement and salvage. Dismantlement as contemplated in
12 this study provides for the orderly removal of the unit's components to maximize safety
13 and scrap value while preventing damage to the surrounding facilities. The assumptions
14 for dismantlement for each of the units and facilities are provided in Schedule CRR-2.

15 **Q: Did you consider salvage value in reaching your opinion of probable dismantlement
16 costs for these units?**

17 A: Yes, the approximate scrap values for iron and steel and non-ferrous metals were tallied
18 for each unit or facility, based upon estimated quantities and averaged current-year scrap
19 prices. These scrap values were listed separately because the scrap metal prices vary
20 considerably, depending on industrial trends, international events and uncontrollable
21 circumstances at the time of the salvage transactions.

1 Q: What are the results of your study?

2 A: The opinion of the probable costs for retirement and dismantlement developed by Segal
3 for each of GMO's fossil-fueled units and the common facilities at each plant site are
4 provided below in Table 1. All costs shown are in 2015 dollars as if the activities were
5 performed in the current year and do not account for ownership percentages and
6 jurisdictional allocations. The development of these costs is described and supported by
7 the report in Schedule CRR-2.

8 In addition, Table 1 also contains a line item for retirement of common facilities
9 at the Jeffery Energy Center (JEC). Segal did not perform a study of the costs for
10 decommissioning the JEC. GMO owns a portion of the JEC, and Westar is the owner
11 and operator of this generating plant. As with the other GMO-owned plants, certain
12 activities are required by specific unit permits and/or state or federal regulations to be
13 performed when the unit ceases operations. In the case of the JEC this includes closure
14 of ash landfills. Since the costs for ash landfill closure are documented by Westar and
15 submitted annually to the Kansas Department of Health and Environment, these costs
16 were included in this Table 1. GMO will certainly have additional retirement costs when
17 JEC is retired, but such costs have not yet been determined.

18 As shown below in Table 1, there is a significant difference in cost between
19 retiring and dismantling a power plant. The costs to retire all of GMO's non-nuclear
20 generating units and the additional costs for the JEC ash landfill closure at retirement are
21 estimated to be approximately \$87.3 million. To dismantle all of GMO's non-nuclear
22 units, I estimate that it would cost an additional \$208.3 million, which does not include
23 JEC. Some components could be sold for scrap during dismantlement thereby recovering

1 an estimated \$38.5 million and bringing the estimated Net Terminal Value (cost to
2 dismantle less salvage) for all of GMO's fossil-fueled plants to \$169.9 million. This
3 amount does not include JEC.

Table 1 - Opinion of The Probable Costs for Decommissioning GMO's Electric Generating Units

(All cost values in 2015 dollars)

Name	Unit No.	Total Unit Capability ⁽¹⁾ MW	First Year In Service	Retirement			Dismantlement		
				Unit Retirement	Activities Required by Permit, Regulation ⁽²⁾ , or Agreement ⁽³⁾	Total Retirement	Dismantlement	Scrap Value ⁽⁴⁾	Net Terminal Cost
Sibley	1	49.8	1960	\$482,368		\$482,368	\$6,034,974	\$848,154	\$5,186,820
	2	47.1	1962	\$482,368		\$482,368	\$6,034,974	\$848,154	\$5,186,820
	3	364.1	1969	\$535,958		\$535,958	\$16,835,426	\$2,757,087	\$14,078,339
	Common			\$531,710	\$13,950,965	\$14,482,675	\$10,134,174	\$1,564,206	\$8,569,968
South Harper	1	101.2							
	2	102.1	2005	\$404,885		\$404,885	\$9,383,425	\$358,946	\$9,024,479
	3	100.0							
Greenwood	1	60.7	1975						
	2	61.7	1975						
	3	63.0	1977	\$413,021	\$471,333	\$884,354	\$11,063,645	\$353,736	\$10,709,909
	4	60.7	1979						
Crossroads	1	75.4							
	2	77.9							
	3	75.9	2002	\$400,303		\$400,303	\$11,249,327	\$389,486	\$10,859,841
	4	77.8							
KCI	1	0							
	2	0	1971	\$227,662		\$227,662	\$2,789,050	\$91,317	\$2,697,733
Nevada	1	17.7	1974	\$281,190	\$56,530	\$337,720	\$6,434,106	\$45,397	\$6,388,709
Ralph Green	3	70.9	1981	\$285,572	\$81,385	\$366,957	\$6,156,152	\$95,230	\$6,060,922
Lake Road	Boiler 1	N/A	1962	\$120,344		\$120,344	\$3,098,749	\$117,312	\$2,981,437
	Boiler 2	N/A	1962	\$120,344		\$120,344	\$3,098,749	\$117,312	\$2,981,437
	Boiler 3	N/A	1937	\$161,768		\$161,768	\$3,611,257	\$151,376	\$3,459,881
	Boiler 4	N/A	1951	\$138,357		\$138,357	\$4,045,457	\$196,024	\$3,849,433
	Boiler 5	N/A	1957	\$183,266	\$1,175,349	\$1,358,615	\$6,388,857	\$224,107	\$6,164,750
	Boiler 8	N/A	2006	\$105,550		\$105,550	\$2,250,354	\$224,107	\$2,026,247
	#4 / #6	96.3	1966	\$386,400	\$637,591	\$1,023,991	\$8,380,637	\$1,262,740	\$7,117,897
	Generator 1	9.4	1950	\$49,349		\$49,349	\$2,375,879	\$38,162	\$2,337,717
	Generator 2	19.0	1958	\$49,349		\$49,349	\$2,615,898	\$43,797	\$2,572,101
	Generator 3	6.6	1962	\$43,656		\$43,656	\$1,874,480	\$25,661	\$1,848,819
	CT 5	67.0	1974	\$209,711		\$209,711	\$2,414,288	\$88,266	\$2,326,022
	CT 6	21.0	1989						
	CT 7	20.5	1990	\$159,554		\$159,554	\$1,665,869	\$91,317	\$1,574,552
	Common			\$875,025	\$174,289	\$1,049,314	\$4,054,680	\$248,964	\$3,805,716
Iatan	1	712.9	1980	\$1,035,765	\$36,970,077	\$38,005,842	\$24,018,833	\$10,000,000	\$14,018,833
	2	881.5	2010	\$1,031,343		\$1,031,343	\$27,449,519	\$11,430,000	\$16,019,519
	Common			\$590,627	\$6,042,837	\$6,633,464	\$24,874,543	\$6,850,000	\$18,024,543
Jeffery Energy Center ⁽³⁾	1	718.0	1978						
	2	715.0	1980						
	3	722.0	1983						
	Common				\$18,426,409	\$18,426,409			
TOTALS		5,395	N/A	\$9,305,445	\$77,986,765	\$87,292,210	\$208,333,302	\$38,460,858	\$169,872,444

Notes

- (1) Current net SPP accredited unit capability, MW.
- (2) Activities required by permits and/or regulations that are to occur upon ceasing operations, including ash landfill closures, and river water intake.
- (3) GMO owns a percentage of Jeffery Energy Center. Westar is the controlling owner.
- (4) Current scrap values per averaged indices.

1 **Q: Are retirement costs optional for GMO?**

2 A: At present, GMO is not required to dismantle its plants upon retirement, and therefore, it
3 is not known when, or even if, the portion of the costs in my study related only to
4 dismantlement will be incurred. However, that is not the case for the costs of retiring the
5 generating units and common facilities. Retirement costs are the costs that will be
6 unavoidably incurred by the Company when the plant is shut-down, even if the closed
7 plant is never dismantled.

8 **Q: How have the results of your study been used in this case?**

9 A: It is my understanding that the retirement costs I have identified have been incorporated
10 into the depreciation study performed for GMO by Company witness, Mr. John Spanos.
11 It is also my understanding that Mr. Spanos has not included the dismantling costs from
12 my study in his depreciation study. By keeping the two categories of costs separate in
13 my study, I have facilitated Mr. Spanos' efforts in this regard, and I have provided
14 substantial evidence to the Commission clearly showing the distinction between the two
15 categories of costs.

16 **Q: Was the Schedule CRR-2 study prepared under your direction and supervision?**

17 A: Yes. I am the Officer-in-Charge at Sega for this study and participated in determining the
18 methodology and in the performance of the work with our team. I visited each of the
19 plant sites, provided oversight during preparation of the report, and reviewed the results
20 for reasonableness and appropriateness.

21 **Q: Does this conclude your testimony?**

22 A: Yes.

**BEFORE THE PUBLIC SERVICE COMMISSION
OF THE STATE OF MISSOURI**

In the Matter of KCP&L Greater Missouri Operations)
Company's Request for Authority to Implement)
A General Rate Increase for Electric Service) Case No. ER-2016-0156

AFFIDAVIT OF CHRISTOPHER R. ROGERS


STATE OF KANSAS)
) ss
COUNTY OF JOHNSON)

Christopher R. Rogers, being first duly sworn on his oath, states:


1. My name is Christopher R. Rogers. I am employed by Sega, Inc. I have been retained to serve as an expert witness to provide testimony on behalf of KCP&L Greater Missouri Operations Company.

2. Attached hereto and made a part hereof for all purposes is my Direct Testimony on behalf of KCP&L Greater Missouri Operations Company consisting of eight (8) pages, having been prepared in written form for introduction into evidence in the above-captioned docket.


3. I have knowledge of the matters set forth therein. I hereby swear and affirm that my answers contained in the attached testimony to the questions therein propounded, including any attachments thereto, are true and accurate to the best of my knowledge, information and belief.


Christopher R. Rogers

Subscribed and sworn before me this 5th day of February, 2016.


Notary Public

My commission expires: December 29, 2018



Chris R. Rogers, P.E.

POSITION Vice President, Sega Inc.

EDUCATION B.S.M.E., 1974
Kansas State University
Manhattan, Kansas

M.S.C.E. Civil Engineering – Construction Management, 1981
University of Missouri-Columbia
Columbia, Missouri

LICENSES Professional Engineer Licenses

- California
- Colorado
- Florida
- Hawaii
- Idaho
- Illinois
- Kansas
- Kentucky
- Michigan
- Missouri
- Montana
- North Carolina
- Utah
- NCEES Record Certificate

AFFILIATIONS American Society of Mechanical Engineers

EXPERIENCE SUMMARY

Mr. Rogers is a Vice President of Sega Inc. and a licensed professional engineer with 40 years of experience in the power industry. He leads the firm's corporate risk management activities and directs the firm's planning and studies practice. Mr. Rogers also provides project management and engineering services for Sega's electric power generating clients.

He has provided engineering and management services for many types of electric generating projects, including simple and combined cycle combustion turbine units, coal and waste coal-fired fluidized bed boiler plants, pulverized coal units, and biomass-fired plants. He has performed engineering and feasibility reviews for financing, construction monitoring, and performance testing of numerous generating facilities.

Mr. Rogers was the Manager of Generating Facilities in the Electric Department of the staff of the Missouri Public Service Commission from 1983 through 1986. He supervised the construction management audits in the rate cases for the Callaway Plant and Wolfcreek Nuclear Generating Station, had limited participation in the Grand Gulf Nuclear Station rate case, and performed other assignments concerning regulated generating facilities throughout the State of Missouri.

Chris R. Rogers, P.E.

During the first decade of his career, Mr. Rogers performed mechanical engineering design services for large utility-owned coal-fired central generating facilities while employed by a nationally recognized consulting engineering firm. He served on project design teams in the main office and as the chief mechanical resident engineer on a green-field, coal-fired power plant construction site.

SELECTED PROJECT EXPERIENCE

- **Kansas City Power & Light Company, Kansas City, Missouri** - Officer-in-charge of study for the 2016 Kansas City Power & Light – Greater Missouri Operations Company (GMO) Missouri rate case providing opinion of probable costs of retirement and dismantlement of 25 fossil-fueled generating units totaling approximately 1,720-MW of capacity, including six (6) coal-fired units, and fifteen (19) combustion turbines. Prepared direct testimony for filing with the Missouri Public Service Commission sponsoring Segal's report in Case No. ER-2014-_____.

Officer-in-charge of study for the 2014 Missouri rate case providing opinion of probable costs of retirement and dismantlement of 24 fossil-fueled generating units and 99 wind turbine generators totaling 5,306-MW of capacity, including eight (8) coal-fired units, one (1) combined-cycle plant, and fifteen (15) combustion turbines. Submitted pre-filed direct testimony before the Missouri Public Service Commission sponsoring Segal's report in Case No. ER-2014-0370.

Officer-in-charge of study for the 2014 Kansas rate case providing opinion of probable costs of retirement and dismantlement of 24 fossil-fueled generating units and 99 wind turbine generators totaling 5,306-MW of capacity, including eight (8) coal-fired units, one (1) combined-cycle plant, and fifteen (15) combustion turbines. Prepared direct testimony for filing with the Kansas Corporation Commission sponsoring Segal's report for Docket No. 15-KCPE-116-RTS.

Officer-in-charge of study for the 2012 Kansas rate case providing opinion of probable costs for retirement and dismantlement of 24 fossil-fueled generating units totaling 5,260-MW of capacity, including eight (8) coal-fired units, one (1) combined-cycle plant, and fifteen (15) combustion turbines. Provided pre-filed direct and rebuttal testimony before the Kansas Corporation Commission sponsoring Segal's report in Docket No. 12-KCPE-764-RTS.

- **Kansas City Power & Light Company, Kansas City, Missouri** - Officer-in-charge and project manager for 2014 power plant siting study to identify and evaluate multiple candidate sites for potential location of a new combined-cycle plants, simple-cycle peaking turbines, and reciprocating engine generating plants. Provided detailed report of findings to Kansas City Power & Light Company Resource Planning Department.

Chris R. Rogers, P.E.

Officer-in-charge and project manager for 2010 Great Plains Energy combined cycle plant siting study to identify and evaluate multiple candidate sites for potential location of new 600-MW class combined-cycle plant. Provided detailed report of findings to Kansas City Power & Light Company Resource Planning Department.

- **Kansas City Power & Light Company - GMO, Lake Road Generating Station, St. Joseph, Missouri** – Officer-in-charge and project manager for a study that assessed the feasibility of the KCP&L industrial steam generation and delivery system to serve its industrial steam customers.
- **Kansas City Power & Light - GMO (Formerly Aquila), South Harper Peaking Facility, Peculiar, Missouri** – 315-MW simple-cycle peaking plant. Project manager of Owner's Engineer for siting, permitting support, detailed installation design, balance of plant procurement, construction management services, commissioning, and documentation support. Sega's project manager and site manager.
- **Kansas City Power & Light, West Gardner and Osawatomie Generating Stations** – Two simple-cycle peaking projects. Sega, Inc's turnkey proposal manager for engineer-led EPC proposal for 400-MW of GE 7E gas turbine generator sets.
- **Independence Power & Light Department, Independence, Missouri** – Master plan study for a nominal 320-MW municipal utility. Project manager for five-year planning study including existing generation assessment, transmission system assessment, load forecast, alternative power supply analysis and economic evaluation.
- **State of Hawaii Division of Consumer Advocacy** – Investigated island-wide blackouts that occurred on Oahu and Maui after the earthquakes on October 15, 2006 and again on Oahu after lightning events on December 26, 2008. Officer-in-charge and project manager of team investigating causes of the outages, assessing utility outage recovery operations and identifying potential improvements to prevent or minimize future outages.
- **Utah Municipal Power Agency, Spanish Fork, Utah** – Officer-in-charge and project manager for due diligence assessment of a simple cycle 200-MW peaking plant consisting of five GE LM6000 combustion turbine generator sets.
- **Utah Municipal Power Agency, Spanish Fork, Utah** – Officer-in-Charge and Project manager for a study assessing the feasibility of potential sites and development of opinions of probable cost for installation of simple-cycle combustion turbines and reciprocating engine generating sets as a subcontractor to Sawvel and Associates of Findlay, Ohio.

Chris R. Rogers, P.E.

- **Kansas City Board of Public Utilities, Nearman Creek CT4, Kansas City, Kansas** – 85-MW simple-cycle peaking unit. Owner's Engineer (Sega, Inc.) site manager for commissioning, including checkout, performance testing, emissions testing and management of construction completion closeout activities.
- **Trigen – Kansas City Energy Corporation, Kansas City, Missouri** – Sega, Inc.'s project manager for feasibility study to repower a district heating plant with an 80-MW combustion turbine and heat recovery steam generator cogeneration project.
- **Conserve Energy System, Centralia, Illinois** – Sega, Inc.'s project manager on a technical feasibility study for a 215-MW coal-fired atmospheric circulating fluidized bed boiler steam electric generating plant.
- **Cargill, Inc., Blair, Nebraska** – Sega, Inc.'s project manager for feasibility study for an 100-MW net combustion turbine and heat recovery steam generator cogeneration project.
- **Independence Power & Light Department, Independence, Missouri** – Sega, Inc.'s project manager for major refurbishment program on six GE Frame 5 and one GE 7B-regenerative, oil and gas-fired gas turbines. Project included condition assessments, specifications, and contracting for renewal and upgrade components, unit controls replacement, remote digital controls addition, and major overhaul of each unit.
- **Somerset Generating Station, Somerset, Massachusetts** – Black & Veatch's project manager on independent engineering review, performing condition assessments for Montaup Electric Company's divestiture of a 40-MW net, oil-fired combustion turbine (2 x FT4) black start peaking unit, a 100-MW coal-fired power plant, a total of 16-MW of diesel generators (8 x 2-MW GM-EMD) and a 2-MW hydro electric plant.
- **Constellation Energy, Freehold, New Jersey** – Sega, Inc.'s project manager for review of project proforma and preparation of testimony before the New Jersey Board of Public Utilities concerning net present value of a 110-MW net, gas-fired combined cycle cogeneration project.
- **Cherokee County Cogeneration Project, Gaffney, South Carolina** – Sega, Inc.'s project manager for an 80-MW net, gas-fired combined cycle (GE 106FA) cogeneration project in Gaffney, South Carolina for Prudential Power Financing. Performed technical review of project during design, permitting, contracting, and financing. Conducted construction monitoring for lender. Also served as interim president of project development entity during lender's takeover of project and equity sale to FP&L.

Chris R. Rogers, P.E.

- **Independence Power and Light, Independence, Missouri** – Sega, Inc.'s project manager for study of 100-MW coal-fired steam electric unit, including conceptual design and estimating performance and cost for client's comparison to participation in Iatan II Project. Compiled and compared capital and operation and maintenance cost of alternative 100-MW coal-fired steam electric plants including pulverized coal and CFB plants, and natural gas-fired combined cycle and simple cycle units of the same size.
- **Florida State Correction Facility, Starke, Florida** – Bibb and Associates' project manager for independent review for potential equity investor, KLT Power, Inc. on a 23-MW, wood gasification and natural gas-fired, combined-cycle cogeneration project proposed near Starke, Florida.
- **Indeck-Oswego Energy Center, Oswego, New York** – Bibb and Associates' project manager on independent engineering review for BA Securities, Inc. regarding the power sales agreement during term of financing of 51-MW, gas-fired combined-cycle (GE6B) cogeneration project in Oswego, New York.
- **North Carolina EMC, Raleigh, North Carolina** – Bibb and Associates' project manager of the Owner's Engineer team that wrote specifications and evaluated EPC proposals for a 330-MW gas-fired combined-cycle project and 100-MW gas-fired simple-cycle project in North Carolina.
- **Indeck-Olean Energy Center, Olean, New York** – Bibb and Associates' project manager on independent engineering review for bank group consisting of Canadian Imperial Bank of Commerce, BOT Financial, Inc., Westpac Banking Corporation, and Toronto Dominion Bank. Project was a 79-MW, gas-fired combined-cycle (GE 6B) cogeneration project in Olean, New York. Scope included review of technical feasibility and economic viability of project for financing, construction progress monitoring and oversight of performance demonstration tests.
- **Orlando CoGen Limited, L.P, Orlando, Florida.** – Bibb and Associates' project manager for independent engineering review for senior lender, the Sumitomo Bank, Limited of a 120-MW gas-fired, single-shaft combined cycle (ABB11N1/VAX) cogeneration project in Orlando, Florida developed by Air Products and Chemicals, Inc. and Utilicorp United.
- **ACE Cogeneration Project, Trona, California** – Bibb and Associates' project manager for independent engineering assessment for equity investor, US West Capital, Inc., including design, permit status, operations and maintenance of an existing 96-MW, coal-fired CFB steam electric plant.

Chris R. Rogers, P.E.

- **Arroyo Cogeneration, Escondido, California** – Bibb and Associates' project manager for engineering review of project for development financing for Heller Financial, Inc, including alternate site selection program for a 49.9-MW, gas-fired, combined cycle (GE LM6000) cogeneration project.
- **Nestles Freehold Cogeneration Project, Freehold, New Jersey** – Bibb and Associates' project manager for independent engineering review for development financing by Heller Financial, Inc. of a proposed 110-MW, gas-fired, single-shaft combined cycle (ABB11N1/VAX) cogeneration project by Constellation Energy.
- **Intercontinental Energy, Bellingham, Massachusetts and Sayreville, New Jersey** – Bibb and Associates' project manager for independent engineering review for potential equity investor, American Energy Division of Potomac Capital Investment Corporation, for two 300-MW, gas-fired combined cycle (2 x W501D) cogeneration projects.
- **Sunnyside Cogeneration Project, Carbon County, Utah** – RW Beck and Associates' project manager for independent engineering review for senior lender, Swiss Bank Corporation, of the design and permitting review of a 50-MW waste coal-fired circulating fluidized bed boiler electric generating plant.
- **North Branch Power Project, Bayard, West Virginia** – RW Beck and Associates' project manager on independent engineering review for financing and construction monitoring for senior lender, Security Pacific Bank of a 80-MW waste coal-fired, circulating fluidized bed boiler project.
- **Unocal Geothermal, Monterey, California** – RW Beck and Associates' engineer, retained by Unocal to provide independent third-party oversight and monitoring of biennial performance tests by Pacific Gas and Electric Company at the Moss Landing Power Station (two 750-MW super-critical, gas and oil-fired steam electric generating units) related to geothermal steam pricing at Unocal's Geysers Geothermal projects.
- **St. Nicholas Power Project, Mahanoy Township, Pennsylvania** – RW Beck and Associates' project manager on independent engineering review for financing, construction monitoring and performance test monitoring for senior lender, Bank of New England for an 80-MW waste coal-fired steam electric plant.
- **Callaway Nuclear Generating Station, Fulton, Missouri** – Manager of Generating Facilities for the Missouri PSC staff, investigated and/or provided testimony concerning project construction management, in-service criteria, net electric capability, decommissioning funding, and in-service completion in rate case for an 1150-MW, PWR nuclear generating station.

Chris R. Rogers, P.E.

- **Wolf Creek Nuclear Generating Station, Burlington, Kansas** – Manager of Generating Facilities for the Missouri PSC staff, investigated and/or provided testimony concerning project construction management, in-service criteria and startup, related fossil-fuel plant retirements, related plant accreditations, depreciation, and net electric capability in rate case for an 1120-MW PWR nuclear generating station.
- **Grand Gulf Generating Station I, Grand Gulf, Mississippi** – Manager of Generating Facilities for the Missouri PSC staff, investigated and provided testimony concerning in-service criteria, in-service status, and overall project NRC inspection and licensing status for a 1250-MW BWR nuclear generating station.
- **Plains-Escalante Generating Station, Unit 1, Prewitt, New Mexico** – Burns & McDonnell's senior mechanical design engineer for mechanical equipment and systems, equipment procurement, construction contracting and coordination; and chief resident mechanical engineer during construction of a 220-MW pulverized coal power plant.
- **Basin Electric Power Cooperative, Inc., Laramie River Station, Wheatland, Wyoming** - Burns & McDonnell's mechanical design engineer for equipment and systems, equipment procurement, and construction contracting and CPM scheduler for coordination of construction completion of systems with sequenced system start-up program for three, 600-MW, pulverized coal-generating units for the Missouri Basin Joint Power Project Agency, lead by the Basin Electric Power Cooperative, Inc.

**TESTIMONY BEFORE THE
MISSOURI PUBLIC SERVICE COMMISSION**

<u>Issue Description</u>	<u>Exhibit No.</u>	<u>Transcript Vol. No.</u>	<u>Page Nos.</u>
AMEREN			
CASE NOS. EO-85-17 & ER-84-168 (on behalf of the MO PSC Staff)			
Phase I – Inservice Criteria	Direct Rebuttal Surrebuttal	A-7 A-12 A-14	7 492-83
Phase II – Net Electric Capability	Direct Surrebuttal	C-76 C-77	30 2852-2868
Phase III – Funding Decommissioning	Surrebuttal	C-38	28 2434-2440
Phase III – Inservice Review	Supplemental (1-28-85)	NA	NA NA
AMEREN			
CASE NO. ER-85-20 (on behalf of the MO PSC Staff)			
Status of Grand Gulf 1 and Waterford 3	Supplemental	12	4 118-181
KANSAS CITY POWER & LIGHT			
CASE NO. ER-85-128 & EO-85-185 (on behalf of the MO PSC Staff)			
Phase I – Inservice Criteria Startup	Affidavits Direct (filed 1/10/85)		NA NA
Phase IV – Fossil Plant Retirement Dates	Direct Surrebuttal	262 266	23 1798-1817
Phase IV – Depreciation – Wolf Creek	Rebuttal	259	
Phase IV – AWS Structural Steel Welding	Direct Surrebuttal	301 302	26 2294-2329
Phase IV – Net Electric Capability	Direct Surrebuttal	399 400	33 3682-3699
Phase IV – Accreditation Overview	Direct Surrebuttal Appendices (9/10/82)	262 436 263	23 7 1798-1817 4451-4483

Chris R. Rogers, P.E.

**TESTIMONY BEFORE THE
MISSOURI PUBLIC SERVICE COMMISSION (Cont'd)**

<u>Issue Description</u>	<u>Exhibit No.</u>	<u>Transcript Vol. No.</u>	<u>Page Nos.</u>	
AMEREN				
CASE NO. ER-85-265 (on behalf of the MO PSC Staff)				
Functionalization and Classification of Costs (Jurisdictional Allocations)	Surrebuttal	89	6	844-848
KANSAS CITY POWER & LIGHT (Formerly AQUIL INC.)				
CASE NO. EA-2006-0309 (on behalf of the Company)				
South Harper Peaking Facility Site Selection	Direct (filed 01/27/06)	N/A		N/A
KANSAS CITY POWER & LIGHT COMPANY, INC.				
CASE NO. ER-2014-0370 (on behalf of the Company)				
The Costs of Retirement and Dismantlement: Decommissioning KCP&L Fossil-Fueled Generating Units	Direct Testimony	131	N/A	N/A

**TESTIMONY BEFORE THE
PUBLIC UTILITIES COMMISSION
OF THE STATE OF HAWAII**

<u>Issue Description</u>	<u>Exhibit No.</u>	<u>Transcript Vol. No.</u>	<u>Page Nos.</u>
HAWAII ELECTRIC LIGHT COMPANY, INC.			
DOCKET NO. 99-207 (on behalf of Consumer Advocate)			
Keahole Projects or Facilities:	Direct Pre-filed CA-T-		288 – 301
1. Shop/Warehouse Building	12	II	301 – 309
2. Fire Protection System	Direct Examination	II	309 - 313
3. Water Treatment System	Commissioners' Exam		
4. Inclusion in Rate Base Amounts			

Chris R. Rogers, P.E.

HAWAII ELECTRIC COMPANY, INC.,
MAUI ELECTRIC COMPANY, LTD., AND
HAWAII ELECTRIC LIGHT COMPANY, INC.
DOCKET NO. 2006-0431 (on behalf of Consumer Advocate)

Consumer Advocates Statement of Position:	Filed August 24, 2007
Consumer Advocate's Supplement	Filed: September , 19, 2008

TESTIMONY BEFORE THE
KANSAS CORPORATION COMMISSION

<u>Issue Description</u>	<u>Exhibit No.</u>	<u>Transcript Vol. No.</u>	<u>Page Nos.</u>
--------------------------	--------------------	----------------------------	------------------

KANSAS CITY POWER & LIGHT COMPANY, INC.
DOCKET NO. 12-KCPE-764-RTS

The Costs of Retirement and Dismantlement: Decommissioning KCP&L Fossil-Fueled Generating Units	Pre-filed Direct Testimony Pre-filed Rebuttal Testimony
--	--

Kansas City Power & Light Co.



The Costs of Retirement and Dismantlement: *Decommissioning KCP&L-GMO's Generating Units*

Final, Rev. 1



Kansas City Power & Light Co.



The Costs of Retirement and Dismantlement: *Decommissioning KCP&L-GMO's Generating Units*

Final, Rev. 1

Sega, Inc. provides this report for the exclusive use and benefit of its Client and, without Sega, Inc.'s written consent, no one else may use or rely upon the contents of this report. Sega, Inc. makes no warranty, express or implied, regarding this report or its services.

TABLE OF CONTENTS

TABLE OF CONTENTS

	<u>Page</u>
CERTIFICATION	-ii-
SECTION 1 EXECUTIVE SUMMARY	1-1
1.1 Introduction	1-1
1.2 Description of Facilities	1-2
1.3 Approach.....	1-5
1.4 Results	1-6
SECTION 2 RETIREMENT	2-1
2.1 Introduction.....	2-1
2.2 Opinion of Probable Cost Basis	2-1
2.3 Retirement Activities	2-2
2.4 ARO Activities	2-4
SECTION 3 DISMANTLEMENT.....	3-1
3.1 Introduction.....	3-1
3.2 Opinion of Probable Cost Basis	3-1
3.3 Dismantlement Activities	3-2
3.4 Project Closure Activities.....	3-7
3.5 Scrap Metal Values	3-7
SECTION 4 APPENDICES	
A Opinions of Costs by Units	
Sibley	
South Harper	
Greenwood	
Crossroads	
KCI	
Nevada	
Ralph Green	
Lake Road	
Iatan	
B Opinions of Cost for Scrap	
C Reference Documents	
D ARO - Source of Requirement	

CERTIFICATION

I hereby certify that this document was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Missouri.



Christopher Robert Rogers
February 3, 2016

Christopher R. Rogers, P.E.
State of Missouri P.E. No. 021087

SECTION 1

EXECUTIVE SUMMARY

EXECUTIVE SUMMARY

1.1 INTRODUCTION

Kansas City Power & Light Company Greater Missouri Operations (GMO) Company retained Sega, Inc. (Sega) to provide an opinion of probable costs for retirement and dismantlement of its generating units. This report presents the results of Sega's study of the costs for decommissioning these facilities.

Decommissioning is comprised of two principal phases: *retirement* and *dismantlement*. *Retirement* is the shutdown or closure and removal from service of a generating unit or facility, and includes disconnection, de-energization, cleanout, and securing of the units to render them safe. *Retirement* triggers unavoidable costs for compliance with the mandatory provisions of the various plants' permits and with the specific requirements of State and Federal regulations for the closure of ash landfills, the removal and remediation of fuel-oil tanks, and the reclamation of river water intakes.

GMO is not required to dismantle its plants upon retirement, and therefore, it is not known when, or even if, dismantlement costs will be incurred. Often a unit may not be dismantled until sometime after it is retired, particularly if there are other operational generating units on the same site. *Dismantlement* is the orderly demolition of the unit in a controlled and safe manner so as to preserve the scrap value of reclaimed materials while appropriately protecting the workers and the environment. Scrap values are considered separately from dismantlement costs because scrap values have proven volatile over time. Scrap values in this report were developed from current average index prices, and were netted out against dismantlement costs to produce net terminal costs for each unit. All costs are provided in current day, 2015 dollars.

1.2 DESCRIPTION OF FACILITIES

The GMO generating facilities are located on eight sites and include 18 simple-cycle combustion turbines, four steam electric generating units, and a steam production facility utilizing six boilers that can be fired to generate electricity by supplying steam to three turbine generators or supplying steam to commercial customers. The major attributes of each unit are provided in Figure 1.1 and further described below.

Plant Name	Unit No.	Current Net SPP Accredited Capability, MW	First Year In Service	Fuel / Type
Sibley	1	51	1960	Coal/Steam
	2	51	1962	
	3	363.8	1969	
South Harper	1	104.5	2005	Natural Gas-Fired Combustion Turbines
	2	105.6	2005	
	3	103.8	2005	
Greenwood	1	62.5	1975	Distillate-Fired/ Natural Gas-Fired Combustion Turbines
	2	60.8	1975	
	3	65.8	1977	
	4	63.3	1979	
Crossroads	1	74.9	2002	Natural Gas-Fired Combustion Turbines
	2	72.9	2002	
	3	74.6	2002	
	4	74.4	2002	
KCI	1	0	1971	Natural Gas-Fired Combustion Turbines
	2	0	1971	
Nevada	1	20.8	1974	Distillate-Fired Combustion Turbine
Ralph Green	3	71.5	1981	Natural Gas-Fired Combustion Turbine
Lake Road	Boiler 1	N/A	1962	Distillate-Fired/ Natural Gas-Fired Boiler
	Boiler 2	N/A	1962	Distillate-Fired/ Natural Gas-Fired Boiler
	Boiler 3	N/A	1936	Natural Gas Fired Boiler
	Boiler 4	N/A	1951	Distillate-Fired/ Natural Gas-Fired Boiler
	Boiler 5	N/A	1959	Coal-Fired/Natural Gas- Fired Boiler
	Boiler 8	N/A	2006	Distillate-Fired/ Natural Gas-Fired Boiler
	#4/#6	99.0	1967	Coal-Fired/Natural Gas- Fired
	Generator 1	21.7	1951	Distillate-Fired/ Natural Gas-Fired Coal- Fired
	Generator 2	27.3	1957	Distillate-Fired/ Natural Gas-Fired Coal- Fired
	Generator 3	11.2	1962	Distillate-Fired/ Natural Gas-Fired Coal- Fired
	#5	63.0	1973	Distillate-Fired/ Natural Gas-Fired
	#6	21.0	1989	Distillate-Fired Combustion Turbine
	#7	21.7	1990	Distillate-Fired Combustion Turbine
Iatan	1	705	1980	Coal/Steam
	2	881	2010	Coal/Steam

Figure 1.1 - GMO Electric Generating Units

1.2.1 Facility Descriptions

Sibley Generating Station is a three-unit, coal-fired electric generating station located in Jackson County, near the town of Sibley, Missouri. Sibley Units 1 and 2 have sub-critical boilers, electrostatic precipitators (ESPs), and an SNCR. Sibley Unit 3 is a super-critical boiler, ESP, and an SCR.

South Harper Generating Station is a three-unit, natural gas-fired combustion turbine peaking plant in Cass County, near the town of Peculiar, Missouri.

Greenwood Generating Station is a four-unit distillate and natural gas-fired combustion turbine peaking plant in Jackson County, near the town of Greenwood, Missouri.

Crossroads Generating Station is a four-unit natural gas-fired combustion turbine peaking plant in Clarksdale, Mississippi.

KCI Generating Station is a two-unit, natural gas-fired combustion turbine peaking plant in Platte County, Missouri on the eastern edge of the Kansas City International Airport property.

Nevada Generating Station is a single-unit, distillate and natural gas-fired combustion turbine peaking plant located in Vernon County, near Nevada, Missouri.

Ralph Green Station is a single-unit, natural gas-fired combustion turbine peaking plant located in Cass County, in Pleasant Hill, Missouri.

Lake Road Generating Station is a multi-unit facility located in Buchanan County in St. Joseph, Missouri. Lake Road generates electricity from four steam turbine generators that receive steam from seven different boilers. These boilers burn either gas, distillate, or coal. These same boilers also produce steam that is sold to local steam customers. Lake Road also includes three combustion turbines that fire distillate (CTG 5, CTG 6, and CTG 7) or natural gas (CTG 5).

Iatan Generating Station is located in rural Platte County, near the town of Weston, Missouri. Unit 1 is a pulverized coal-fired, sub-critical steam electric plant with an SCR, baghouse, and wet scrubber. Unit 2 is a pulverized coal-fired, super-critical steam electric plant with an SCR, baghouse, and wet scrubber.

1.3 APPROACH

Sega met with representatives of GMO to gather information about the generating units and visited each of the plant sites (with the exception of the Crossroads facility). Discussions were held with certain plant staff, further documentation was obtained, and a walkdown of each unit was conducted. Sega utilized Microsoft® Project 2010 (MS Project) software with resource loading to develop and compile opinions of probable costs and schedules for the retirement of each unit. Costs were developed based on GMO's current labor rates and those of its present maintenance contractors. Site-specific retirement costs were developed using a bottom-up approach for each task.

The basis and limits for retiring or dismantling each unit were defined while visiting the plant sites. For instance, it was assumed that the switchyard and/or substation (as applicable) for each generator would remain in service following either retirement or dismantlement. In general, plant roads, fencing, and site grading were presumed to remain undisturbed unless otherwise specifically required to be removed. Closure of ash landfills, and the removal and remediation of river water intakes and fuel oil storage tanks were included in the retirement phase as required by applicable permits.

Dismantlement costs for Sibley Unit 3 was developed from the ground up. It was assumed that common facilities at each plant site, such as coal unloading, storage and handling systems, water treatment systems, ash handling systems, and office buildings, would remain in service until the last unit is retired. For multiple-unit sites, retirement and dismantlement costs were developed separately for the common plant facilities. For instance, applicable ash landfill closure costs for the units were included in the common plant category rather than for individual units.

The estimates of probable cost for “stack removal” and “final site grading and drainage” for the various sites were not developed using MS Project software. The “stack removal” costs for the various stacks were based on a budgetary estimate for the demolition of the existing Iatan Unit 1 stack. This estimate was scaled to estimate the demolition for the other stacks involved in this study. The “final site grading and drainage” estimate of probable cost was developed by Sega but was not developed in an MS Project schedule. Both of these activities are represented in the MS Project schedule in Appendix A for the applicable units as a onetime cost/use in the resource allocation section of the file; therefore, they appear as a one-day activity in the schedule with the estimated costs as a one-time expense.

1.4 RESULTS

The opinion of the probable costs for retirement and dismantlement developed by Sega for each of GMO’s units and the common facilities at each plant site are provided in Figure 1.2. All costs shown are in 2015 dollars. The costs are provided for the full ownership of these generating facilities. Fractional shares of ownership and jurisdictional allocations have not been taken into account in these costs. Ongoing expenses for the sites such as security, routine inspections, groundwater monitoring, etc., which would continue as long as the Company continues to own the sites, are not included in the decommissioning costs. Retirement costs are separately provided for each unit and for related common plant facilities. The costs of dismantlement and scrap values are provided for each unit and for common plant, as well as the final net terminal costs.

As shown in Figure 1.2, there is a significant difference between the costs of retiring and the costs of dismantling a power plant. In Sega’s opinion, the probable cost to dismantle all of GMO’s units is approximately \$208 million. Some materials could be sold for scrap, thereby recovering approximately \$38 million and bringing the estimated net terminal value for dismantling all of GMO’s plants to \$170 million, based upon the current averaged scrap indices.

However, were GMO to retire its generating units in place without dismantlement, Sega believes the cost would be approximately \$68.9 million.

Name	Unit No.	Retirement			Dismantlement		
		Unit Retirement	Activities Required by Permit Agreement or Regulation ⁽¹⁾	Total Retirement	Dismantlement	Scrap Value ⁽³⁾	Net Terminal Cost
Sibley	1	\$482,368		\$482,368	\$6,034,974	\$848,154	\$5,186,820
	2	\$482,368		\$482,368	\$6,034,974	\$848,154	\$5,186,820
	3	\$535,958		\$535,958	\$16,835,426	\$2,757,087	\$14,078,339
	Common	\$531,710	\$13,950,965	\$14,482,675	\$10,134,174	\$1,564,206	\$8,569,968
South Harper	1						
	2	\$404,885		\$404,885	\$9,383,425	\$358,946	\$9,024,479
	3						
Greenwood	1						
	2	\$413,021	\$471,333	\$884,354	\$11,063,645	\$353,746	\$10,709,899
	3						
	4						
Crossroads	1						
	2						
	3	\$400,303		\$400,303	\$11,249,327	\$389,486	\$10,859,841
	4						
KCI	1						
	2	\$227,662		\$227,662	\$2,789,050	\$91,317	\$2,697,733
Nevada	1	\$281,190	\$56,530	\$337,720	\$6,434,106	\$45,397	\$6,388,709
Ralph Green	3	\$285,572	\$81,385	\$366,957	\$6,156,152	\$95,230	\$6,060,922
Lake Road	Boiler 1	\$120,344		\$120,344	\$3,098,749	\$117,312	\$2,981,437
	Boiler 2	\$120,344		\$120,344	\$3,098,749	\$117,312	\$2,981,437
	Boiler 3	\$161,768		\$161,768	\$3,611,257	\$151,376	\$3,459,881
	Boiler 4	\$138,357		\$138,357	\$4,045,457	\$196,024	\$3,849,433
	Boiler 5	\$183,266	\$1,175,349	\$1,358,615	\$6,388,857	\$224,107	\$6,164,750
	Boiler 8	\$105,550		\$105,550	\$2,250,354	\$224,107	\$2,026,247
	#4 / #6	\$386,400	\$637,591	\$1,023,991	\$8,380,637	\$1,262,740	\$7,117,897
	Generator 1	\$49,349		\$49,349	\$2,375,879	\$38,162	\$2,337,717
	Generator 2	\$49,349		\$49,349	\$2,615,898	\$43,797	\$2,572,101
	Generator 3	\$43,656		\$43,656	\$1,874,480	\$25,661	\$1,848,819
	CT 5	\$209,711		\$209,711	\$2,414,288	\$88,266	\$2,326,022
	CT 6 & 7	\$159,554		\$159,554	\$1,665,869	\$91,317	\$1,574,552
	Common	\$875,025	\$174,289	\$1,049,314	\$4,054,680	\$248,964	\$3,805,716
Iatan	1	\$1,035,765	\$36,970,077	\$38,005,842	\$24,018,833	\$10,000,000	\$14,018,833
	2	\$1,031,343		\$1,031,343	\$27,449,519	\$11,430,000	\$16,019,519
	Common	\$590,627	\$6,042,837	\$6,633,464	\$24,874,543	\$6,850,000	\$18,024,543
		\$9,305,445	\$59,560,356	\$68,865,801	\$208,333,302	\$38,460,868	\$169,872,434

**Figure 1.2 - Probable Costs of Decommissioning
GMO Electric Generating Units⁽¹⁾**

- (1) All values in 2015 U.S. dollars.
- (2) Activities required by permits and/or regulations that are to occur upon ceasing operations, including ash landfill closures and river water intake structures.
- (3) Current scrap values per averaged indices.

SECTION 2

RETIREMENT

RETIREMENT

2.1 INTRODUCTION

Sega developed an opinion of probable cost to retire the GMO facilities previously listed in Figure 1.1 and further described in Appendix A. The opinion of probable cost is a buildup of estimated costs to perform the retirement activities to leave each facility in a safe state. A resource-loaded MS Project schedule was developed for the retirement of each facility. Each schedule includes the activity, duration of the activity, resources required for each activity, and the probable cost of each activity. The results for each facility are provided in Appendix A of this report.

The opinion of probable cost for the retirement of each coal-fired generating facility is broken down into the retirement of each unit (or boiler, turbine, and CTG in the case of Lake Road), plus the retirement of the common facilities. The common facilities will be retired when the last unit is retired at a site.

2.2 OPINION OF PROBABLE COST BASIS

Retirement activities will be performed by KCP&L bargaining unit personnel and managed by GMO. Man-hour costs for both management and bargaining unit personnel were provide by GMO. At the direction of GMO, the direct man-hour rate was multiplied by 1.4 to account for benefits and overhead loadings.

The estimates of probable cost to retire the combustion turbines are based on retiring all of the combustion turbines at a given site, not on an individual combustion turbine retirement basis. The only exception is at Lake Road. At Lake Road, CTG 5 is retired as a single unit and CTGs 6 and 7 are retired together per direction from the Lake Road plant staff.

A 5-percent "Owner Internal Costs" is included in the opinion of probable cost. This line item is included to cover the costs of various internal GMO departments that will charge to the project during the implementation of the retirement activities.

A 25-percent "Owner Contingency" is included in the opinion of probable cost. This level of contingency is consistent with Association for the Advancement of Cost Engineering (AACE-International) contingency level guidelines based on the engineering progress completed at the point when the cost estimate was developed.

2.3 RETIREMENT ACTIVITIES

Prior to starting the actual retirement activities, a retirement plan will be developed. This plan will address any laws, ordinances, regulations, and standards dictating how ash, slag, scrubber by-products, and any other waste stream is stored and/or removed from the plant site. An environmental assessment will be performed to develop a plan to address these issues and to assure that permits required to complete the retirement activities are in place. The retirement plan will also address plant safety during the time interval between plant retirement and eventual dismantlement. This plan should include the requirements for periodic inspections to assess the condition and integrity of the plant structures so that contractors can safely demolish the plant when so required. The costs to perform these activities are estimated in the "Pre-Retirement Activities" line item of each facility's opinion of probable cost.

The following activities and conditions are required to leave a generating facility (unit, common facilities, or entire plant, as may be applicable) in a safe state and are included in each facility's opinion of probable cost:

1. All equipment, tanks, vessels, containers, drums, headers, exchangers, and sumps will be drained and vented. Fuel oil, lubricating oil, liquid propane, bulk hydrogen, Halon, liquid ammonia, water treatment chemicals, lab chemicals, cleaning solutions, and Freon will be handled per plant procedures and plan permitting requirements. Man-ways, hand-holes, vents, and drains will be opened to ensure drainage. Drains will remain open.
2. The electrical sources will be isolated from the facility. The exact details of this scope of work will be determined during the pre-retirement activities phase. At a minimum, all electrical buses will be disconnected at the source. The medium- and low-voltage switchgear will be racked out by fully withdrawing the circuit breakers. Fuses will be removed, and circuit breakers and disconnect switches will be left in the open position. Motors

- will be disconnected at the source and motor lube oil will be drained (as applicable).
3. Fuel yard equipment will be cleaned and vacuumed to reduce or eliminate the hazards of fugitive coal dust.
 4. To the maximum extent possible, all drains will be emptied and vented. Low-point drains will remain open.
 5. Fuel gas piping and city/rural water piping will be cut and capped at the property line.
 6. Chimney Federal Aviation Agency (FAA) required lighting will be kept in service.
 7. Buildings will be "secured". The determination of the detailed activities required to leave a building in a secure state is included in the pre-retirement activities and will include isolating all power sources, draining potable water lines, draining and venting sewage lines, securing doors and windows, capping any means of egress for vermin, removing hazardous materials, and moving any relevant plant documentation to alternate off-site storage sites.
 8. Fuel oil and waste oil will be drained and removed.
 9. Boiler chemicals will be drained and removed.
 10. Boilers and HRSGs will be drained. The water and steam side will be vented. The gas side will be vacuumed to remove ash and slag. Drum doors and boiler doors will be left open. Bottom ash systems will be drained, cleaned, and vented.
 11. Ductwork will be vacuumed and left open.
 12. Condensate and feedwater piping will be drained and vented.
 13. Feedwater heaters will be drained and vented.
 14. Deaerator and deaerator storage tanks will be drained and vented.
 15. The turbine and condenser will be drained and vented.
 16. The generator will be electrically and mechanically isolated. The generator and exciter cooling water systems will be drained and vented. Hydrogen gas tanks and the generator hydrogen systems will be vented.
 17. Compressed air systems will be drained and vented. Desiccant will be removed from the compressed air dryer systems.

18. Circulating water systems and turbine cooling water systems will be drained and vented. Circulating water chemical feeds will be drained and vented.
19. Baghouses will be opened, cleaned, and vented. Filter bags and cages will be removed.
20. Wet Flue Gas Desulfurization (FGD) systems will be drained, opened, cleaned, and vented.
21. Dry FGD systems will be drained, opened, cleaned, and vented.
22. Re-agent preparation facilities will be drained, opened, cleaned, and vented.
23. SCRs will be opened, cleaned, and vented. Catalyst will be removed. Ammonia storage tanks will be emptied and vented.
24. The battery systems will have the battery electrolytes and battery cells removed and disposed.
25. Sewage treatment facilities will be drained, cleaned, and vented.
26. Oily drain tanks will be opened and pumped out.
27. CO₂ systems used for fire protection will be drained, opened, and vented.
28. Any other activities required by law, regulation or permit for a specific unit, common facility or plant site will be performed.

Once the site retirement activities are complete, several months of post-retirement activities will commence. These activities include determining the disposition of site documentation, assuring permits are in correct condition, developing plans to monitor the retired facility, accounting and environmental activities, and re-assigning personnel as required.

2.4 ARO ACTIVITIES

Asset Retirement Obligations (AROs) are a means that GMO utilizes to track the costs of activities that are required to be performed when one of its generating units ceases operation and is removed from service. These are activities that are required to be performed upon retirement according to permits, statutes, agreements, and regulations. For certain activities, such as ash landfill closures, GMO is required to periodically report

estimated cost updates to state environmental agencies (Kansas Department of Health and Environment and Missouri Department of Natural Resources). These agencies require GMO to periodically demonstrate the ability to fund these closure activities. This is because the costs for ash landfill closures and post-closure activities are significant.

Other activities, such as the removal of river water intakes, are stated requirements in the standard form permits issued by the United States Army Corp of Engineers. Also included in AROs are amounts for the abatement and removal of fuel oil storage tanks of the plants located in Missouri (Greenwood, Nevada, Lake Road, and Iatan Generating Stations).

While GMO accounts for asbestos abatement activities in AROs for the Greenwood, Nevada, and Sibley Generating Stations, these activities were excluded from the retirement and decommissioning costs. Asbestos abatement activities are ongoing at each of these sites during the life of the units, and will continue to be performed after retirement, but before dismantlement. Thus, asbestos abatement was not included in this decommissioning study.

Wherever KCP&L already had estimates and a basis for valuing the costs of such ARO closure activities, Segra reviewed and utilized these estimates, adjusting to 2015 present-day dollars. Where there was no prior estimate available, Segra developed an opinion of probable costs for their closure. Each of these costs is provided in Appendix A.

Appendix D is a table showing the source of the requirement that dictates each ARO activity.

SECTION 3

DISMANTLEMENT

DISMANTLEMENT

3.1 INTRODUCTION

Sega developed an opinion of probable cost to dismantle the GMO facilities that are listed in Appendix A. The opinion of probable cost is a buildup of estimated costs to perform the dismantlement activities to remove equipment and building superstructures down to grade-level foundations. Below-grade foundations, piping, and duct banks will be abandoned in place. A resource-loaded MS Project schedule was developed for the dismantlement of the facilities. Each schedule includes the activity, duration of the activity, resource required for each activity, and the probable cost of each activity. The results for each of the facilities are provided in Appendix A.

The opinion of probable cost for the dismantlement of each coal-fired generating facility is broken down into the dismantlement of each unit, plus the dismantlement of the common facilities. The common facilities will be dismantled when the last unit at the site is dismantled.

The estimate of probable cost to dismantle the combustion turbines are based on dismantling all of the combustion turbines at the site, not on an individual combustion turbine dismantlement basis with the exception of Lake Road. At Lake Road, CTG 5 is dismantled as a single unit and CTGs 6 and 7 are dismantled together per direction from the Lake Road plant staff.

3.2 OPINION OF PROBABLE COST BASIS

The project will be managed by GMO staff. GMO will hire an Owner's Engineer to assist with environmental issues and the technical dismantlement details. GMO will hire a Demolition General Contractor (DGC) to perform the complete dismantlement of each unit.

The opinion of probable cost is presented as the straight netting of the DGC's firm price cost, minus the current scrap value of the equipment and materials.

At the initiation of dismantlement, this study assumes that the unit or common facility has been previously retired as detailed in Section 2 - Retirement.

A resource-loaded MS-Project dismantlement schedule and an opinion of probable cost was developed for Iatan Unit 1, Sibley Unit 3, South Harper (all three units), Greenwood (all four units), Crossroads (all four units), KCI (both units), Nevada (one unit), Ralph Green (one unit), and Lake Road Boiler 1, Lake Road Boiler 2, Lake Road Boiler 3, Lake Road Boiler 4, Lake Road Boiler 5, Lake Road Boiler 8, Lake Road CTGs 6 and 7, Lake Road CTG 5, Lake Road T-G 1, Lake Road T-G 2, Lake Road T-G 3, and the common facilities at Iatan, Sibley, and Lake Road. The opinion of probable costs developed for Sibley Unit 3 was used to derive the dismantlement costs for Sibley 1, Sibley 2, and Lake Road 4/6 using the AACE International Capacity Factor Method. The cost for Iatan Unit 2 was derived from the cost to dismantle Iatan Unit 1 using the AACE International Capacity Factor method.

A 5-percent "Owner Internal Cost" is included in the opinion of probable cost. This line item is included to cover the costs of various internal GMO departments that will charge to the project during the implementation of the dismantlement activities.

A 25-percent "Owner Contingency" is included in the opinion of probable cost. This level of contingency is consistent with the AACE International contingency level based on the engineering progress completed at the point when the cost estimate is developed.

3.3 DISMANTLEMENT ACTIVITIES

The dismantlement of a facility is divided into pre-dismantlement activities, dismantlement activities, and project closure activities.

3.3.1 Pre-Dismantlement Activities

Pre-dismantlement activities consist of the detailed pre-planning of the dismantlement process. This pre-planning includes establishing the GMO project management team; hiring an Owner's Engineer; developing a detailed dismantlement scope of work, including how to address any environmental issues; developing a level 1 project schedule; and contracting with a DGC.

The GMO project management team will be responsible for the project execution and will consist of a full-time project manager, two full-time engineers, a full-time project administrative assistant, and a part-time procurement specialist. This team will have the authority to manage the dismantlement of the plant.

The Owner's Engineer will assist GMO with the technical aspects of executing the project. The Owner's Engineer will help establish the boundaries of demolition, provide environmental consulting, and develop the technical specifications for the DGC contract request for proposal. The Owner's Engineer will provide 1-1/2 full-time equivalent field engineers during the demolition phase of the project. The Owner's Engineer will also provide detailed design for equipment that requires modifications to keep other units or common facilities in operation during demolition and after the unit is dismantled.

The KCP&L project management team and the Owner's Engineer will review all existing permits to assure that any relevant existing permit requirements are met during demolition. This team will also get any additional required permits in place for demolition (outside of the normal permits that are the responsibility of the DGC).

Prior to dismantlement activities, a detailed site characterization study will be performed. This study involves a series of site investigations to determine potential subsurface environmental issues at the site, a description of the hydrological and hydrogeological conditions on the site, and a determination of potential waste streams generated during the demolition work. Based on the outcome of the site characterization study, reclamation, and remediation plans that address the environmental issues and site conditions will be

developed. The site characterization study and the development of the remediation plans can take up to six months to complete. The site characterization study will be performed by the Owner's Engineer.

The GMO project management team will identify the boundaries of dismantlement and the location of system and equipment isolation points between the unit to be demolished, common facilities, and units to remain.

The GMO project management team will be responsible for bidding and contracting with a qualified DGC.

Prior to the DGC mobilizing on site, the GMO project management team will confirm that the unit to be dismantled is ready to be turned over to the DGC.

3.3.2 Dismantlement Activities for a Coal-Fired Unit

The demolition contractor will be structured into several crews that will bring equipment and materials to the ground. A separate dedicated crew will be responsible for classifying the scrap by type and removing the scrap from the site.

The coal-fired units will be demolished in a phased and sequential manner to assure worker safety and to minimize any interferences with surrounding equipment. Please refer to the man-power loaded schedule and graphs in Appendix A for the details of each demolition phase.

3.3.2.1 *Phase 1 Demolition - Boiler and Turbine Equipment Removal*

Mechanical and electrical equipment and material inside the boiler and turbine building footprints will be removed. The goal of this phase is to remove the majority of the equipment in the boiler and turbine buildings leaving only the boiler, turbine, building, and support steel.

In this phase of the project, the switchyard is disconnected from the generating facility.

3.3.2.2 Phase 2 Demolition - Boiler and Turbine Removal

The boiler equipment will be removed at the start of this phase. Then, the boiler furnace and backpass will be removed from the bottom up (boilers are hung from the top of the boiler structure) and the structural steel is removed from the top down. Once the structural steel and all equipment are removed, the boiler equipment foundations will be demolished to existing grade.

In parallel with the above activities, the turbine, condenser neck heat exchangers, condenser, and miscellaneous turbine equipment will be removed. The turbine building and turbine pedestal is then demolished to grade.

3.3.2.3 Phase 3 Demolition - Precipitator and AQCS Dismantlement

If the unit has a precipitator, the precipitator will be removed similar to the process for removing the boiler. The precipitator internals will be removed from the bottom up and the precipitator structural steel will be removed from the top down. The precipitator foundation will be removed down to grade.

If the unit has a wet or dry scrubber and/or a baghouse, the dismantlement will start at the stack and work back towards the boiler to avoid dismantlement activities interferences.

3.3.2.4 Phase 4 Demolition - Yard Demolition

This phase removes equipment and materials external to the boiler and turbine areas. Underground piping, conduit, and duct banks will be abandoned in place with the exception of the circulating water pipe. The concrete reinforced circulating water pipes will be excavated, collapsed by crushing, and backfilled. Electrical man-holes will be collapsed by crushing and backfilled. Special care will be taken to assure that any materials left in the ground will not adversely impact site drainage.

3.3.2.5 *Phase 5 - Final Site Grading and Drainage*

Final grading and drainage includes a minimum amount of grading to assure that the site drainage facilities remain in place and includes final seeding of the site.

3.3.3 Dismantlement Activities for a Combustion Turbine Site

The demolition contractor will be structured into several crews that will bring equipment and materials to the ground. A separate dedicated crew will be responsible for classifying the scrap by type and removing the scrap from the site.

The combustion turbines, auxiliary equipment, and buildings will be demolished in a phased and sequential manner to assure worker safety and to minimize any interferences with surrounding equipment. Please refer to the man-power loaded schedule and graphs in Appendix A for the details of each demolition phase.

Final grading and drainage includes a minimum amount of grading to assure that the site drainage facilities remain in place and includes final seeding of the site.

3.3.4 Dismantlement Activities for Common Facilities

The demolition contractor will be structured into several crews that will bring equipment and materials to the ground. A separate dedicated crew will be responsible for classifying the scrap by type and removing the scrap from the site.

The common facilities dismantlement activities consist primarily of the removal of chimneys, fuel yard equipment, removal of site-specific common equipment, and the removal of facility buildings. The phasing of the common dismantlement processes are site specific and will be determined during the pre-dismantlement activity phase of the project.

Final grading and drainage includes a minimum amount of grading to assure that the site drainage facilities remain in place and includes final seeding of the site.

3.4 PROJECT CLOSURE ACTIVITIES

This phase of the project confirms that the remediation and reclamation of the site has been successfully complete and that all required “record” documentation needed by GMO is complete and on file.

3.5 SCRAP METAL VALUES

Scrap metal weights were developed for a 700-MW coal-fired unit based on the actual quantities and materials documented in the original construction documents. These scrap metal weights were applied to the other coal-fired units using the AACE International Capacity Factor Method.

Scrap metal weights for the combustion turbines, boilers, and turbine generators were based on weights for similar-sized equipment from previous Sega projects.

Please see Appendix B for the opinion of current average scrap values for each unit.

APPENDICES

APPENDIX A

OPINIONS OF COSTS BY UNITS

SIBLEY

SIBLEY STATION

The Sibley Generating Station consists of three coal-fired power plants.

Sibley Unit 1 has an SPP-accredited unit rating of 51 MW and was placed in service in 1960. Unit 1 has a sub-critical Babcock & Wilcox boiler and a Siemens turbine. River water is used for condenser cooling. Unit 1 has an electrostatic precipitator for particulate removal and an SNCR system for NO_x control.

Sibley Unit 2 has an SPP-accredited unit rating of 51 MW and was placed in service in 1962. Unit 2 has a sub-critical Babcock & Wilcox boiler and a General Electric turbine. River water is used for condenser cooling. Unit 2 has an electrostatic precipitator for particulate removal and an SNCR system for NO_x control.

Sibley Unit 3 has an SPP-accredited unit rating of 363.8 MW and was placed in service in 1969. Unit 3 has a super-critical Babcock & Wilcox boiler and a Siemens turbine. River water is used for condenser cooling. Unit 3 has an electrostatic precipitator for particulate removal and an SCR for NO_x control.

The Sibley common fuel yard has a bottom car dumper that can transfer fuel to either a bituminous fuel storage pile or a sub-bituminous fuel storage pile. The two different fuels can be blended prior to being transported to either the crusher house or to the blended pile. The blended pile has a reclaim system that can transport blended fuel to the crusher house. Crushed fuel is then transported to the Units 1, 2, and 3 silos. The fuel yard also has a tire chips storage and conveyor system that can transport tire chips to the Unit 3 silos.

All three Sibley units have a propane igniter system. The units are supplied with propane from common propane storage tanks and a common propane vaporizer.

All three units beneficially use coal combustion products off site. Coal combustion products that are not beneficially used off site are disposed of in the on-site solid waste landfill.

The following are the major systems and equipment that were included in the retirement and dismantlement of each unit and the major systems and equipment that were considered common (additional details are listed in the attached retirement and dismantlement schedules included in this Appendix).

SIBLEY UNIT 1

1. Boiler and boiler auxiliaries.
2. Turbine, heat balance equipment, and turbine auxiliaries.
3. Electrostatic precipitator.
4. Dedicated Unit 1 fuel handling equipment.
5. Dedicated Unit 1 propane equipment.
6. Dedicated Unit 1 SNCR process equipment.

SIBLEY UNIT 2

1. Boiler and boiler auxiliaries.
2. Turbine, heat balance equipment, and turbine auxiliaries.
3. Electrostatic precipitator.
4. Dedicated Unit 2 fuel handling equipment.
5. Dedicated Unit 2 propane equipment.
6. Dedicated Unit 2 SNCR process equipment.

SIBLEY UNIT 3

1. Boiler and boiler auxiliaries.
2. Turbine, heat balance equipment, and turbine auxiliaries.
3. Electrostatic precipitator.

4. Dedicated Unit 3 fuel handling equipment.
5. Dedicated Unit 3 propane equipment.
6. Dedicated Unit 3 SCR process equipment.

COMMON

1. Administration/Service building.
2. Fuel yard office building.
3. Temporary service building.
4. Warehouses.
5. Tractor shed and out building.
6. Water treatment and sewage treatment.
8. Common fuel handling equipment.
9. NO_x out ultra system
10. Fire water systems.
11. Stack.
12. Diesel generator.
13. Intake.

10/10/10

10/10/10

10/10/10

10/10/10

10/10/10

10/10/10

10/10/10

UNIT 1



Sibley Unit 1 Retirement

Owner Costs

Pre-Retirement Activities	\$100,821
Retirement Activities	\$240,134
Post-Retirement Activities	\$26,564

Owner Direct Total \$367,519

Owner Internal Costs 5.00% \$18,376

Owner Contingency: 25.00% \$96,474

Sibley Unit 1 Retirement Opinion of Probable Cost: \$482,368.69

Sibley Unit 1 Retirement Costs		
ID	Task Name	Cost
1	Sibley Unit 1 Retirement	\$367,519.09
2	Pre-Engineering	\$100,821.60
3	Permit review and engineering analysis, establish isolation points, and confirm	\$100,821.60
4	KCL&L Overhead Costs	\$83,646.00
5	KCP&L Retirement Manager	\$83,646.00
6	Equipment Rentals	\$28,339.20
7	Vacuum truck	\$28,339.20
8	Retirement	\$128,148.29
9	Electrical	\$18,911.68
10	Medium and Low Voltage Draw out Switchgear	\$2,679.84
11	De-energize all buses at the source.	\$446.64
12	Open all circuit breakers.	\$446.64
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	\$446.64
14	Verify that the closing/tripping springs are discharged.	\$446.64
15	De-energize control power and auxiliary power circuits of each circuit br	\$893.28
16	Motor Control Centers	\$1,786.56
17	De-energize all buses at the source.	\$446.64
18	Open all circuit breakers and disconnect switches.	\$446.64
19	Remove all fuses in control circuits.	\$893.28
20	Low-voltage Switchboards and Panelboards	\$893.28
21	De-energize all buses at the source.	\$446.64
22	Open all circuit breakers and disconnect switches.	\$446.64
23	Oil-Filled Power Transformers	\$5,549.44
24	De-energize all transformer primaries and verify that the secondary is de	\$893.28
25	De-energize all low-voltage AC or DC power sources for space heaters, cc	\$893.28
26	Drain and dispose of oil.	\$2,642.88
27	Clean up and dispose of oil on surface areas around the transformers on	\$1,120.00
28	Dry-type Power Transformers	\$1,786.56
29	De-energize all transformer primaries and verify that the secondary is de	\$893.28
30	De-energize all low-voltage AC or DC power sources for space heaters, cc	\$893.28
31	Motors	\$6,216.00
32	De-energize all primary power at the source.	\$1,786.56
33	De-energize all low-voltage power sources for space heaters or other au	\$1,786.56
34	Drain lube oil system (if applicable) and dispose of oil.	\$2,642.88
35	Coal Handling	\$29,248.24
36	isolate area K Unit 1 Silos.	\$8,522.80
37	Confirm all fuel lines and feedrs are clear of coal and coal dust.	\$1,685.44
38	Perform cleaning of the coal handling equipment to assure that all coal anc	\$19,040.00
39	Propane Igniter System	\$2,528.16
40	Isolate lines from source, open and vent.	\$2,528.16
41	Boiler Chemical Feed	\$1,685.44
42	Drain all chemical feed tanks.	\$1,685.44
43	Boiler	\$29,591.57
44	Open boiler doors.	\$880.96

Sibley Unit 1 Retirement Costs		
ID	Task Name	Cost
45	Gas side - perform cleaning of the boiler and bottom ash system.	\$16,800.00
46	Drain boiler, drums, downcomers and headers.	\$842.72
47	Open drum doors and blowdown tank doors.	\$880.96
48	Drain and vent the service water and ash sluice water systems	\$1,541.36
49	Clean bottom ash, economizer ash and fly ash system.	\$2,480.13
50	Open, flush with water and vent the SNCR/RRR piping	\$6,165.44
51	Precipitator	\$10,603.04
52	Multiple cleaning cycles for collection plates.	\$2,528.16
53	Clear hoppers of all ash	\$2,805.44
54	Disconnect transformers.	\$1,786.56
55	Mechanically secure all compartment dampers and hopper outlet valves in	\$720.48
56	Disconnect ash transport piping and washdown hoppers and interior of ca	\$1,000.48
57	Install bird screens across hopper ash outlet and ash line flanges.	\$880.96
58	Padlock or tack weld all hopper doors shut. (note: if ash hopper doors are i	\$880.96
59	Ductwork	\$6,480.96
60	Open ductwork doors.	\$880.96
61	Perform extensive cleaning of the ductwork.	\$5,600.00
62	Isolate ductwork at tie to ductwork common to Unit 2	\$0.00
63	Condensate and Feedwater Piping	\$2,528.16
64	Drain water from the system.	\$842.72
65	Leave open vents and drains.	\$842.72
66	Drain, open and vent condensate storage tanks	\$842.72
67	Feedwater heaters	\$2,528.16
68	Drain feedwater heaters	\$842.72
69	Leave open vents and drains.	\$1,685.44
70	Turbine and Condenser	\$4,385.68
71	Drain hotwell and leave doors open.	\$861.84
72	Open main turbine doors.	\$880.96
73	Remove lube oil.	\$2,642.88
74	Drain Gland Water Tank and Condensate Collection Tank	\$0.00
75	Generator	\$6,095.76
76	Verify that generator circuit breaker is open and racked out or that high-vo	\$446.64
77	Verify that generator field breaker or contactor (if applicable) is open.	\$446.64
78	De-energize power supplies to generator excitation system at the source.	\$446.64
79	De-energize AC and DC power supplies to generator and exciter space heat	\$446.64
80	Drain generator and exciter cooling water systems (if applicable).	\$861.84
81	Disconnect and remove hydrogen gas tanks and purge generator hydrogen	\$1,685.44
82	Disconnect and remove fire protection system gas/foam tanks and purge fi	\$1,761.92
83	Circulation Water and Turbine Cooling Water System	\$3,409.12
84	Drain.	\$1,685.44
85	Open water box doors.	\$880.96
86	Drain any circulating water chemical feed tanks.	\$842.72
87	Compressed Air System	\$842.72
88	Open vents and drains.	\$842.72

Sibley Unit 1 Retirement Costs

ID	Task Name	Cost
89	Auxiliary Steam System	\$2,528.16
90	Drain water from system.	\$842.72
91	Open and vent F.D. Fan Steam Coils	\$1,685.44
92	Bearing Cooling Water and Boiler Cooling Water System	\$842.72
93	Drain water from system and vent.	\$842.72
94	Condenser Air Extraction System	\$842.72
95	Drain water from system.	\$842.72
96	Building Heating System	\$842.72
97	Drain water from system.	\$842.72
98	Battery System	\$4,253.28
99	De-energize all battery chargers from the source.	\$446.64
100	Open all AC and DC circuit breakers and/or fused switches on battery charg	\$446.64
101	Remove and dispose of battery electrolyte.	\$1,680.00
102	Remove and dispose of battery cells.	\$1,120.00
103	Clean up and dispose of electrolyte on surface areas around batteries.	\$560.00
104	Post Retirement Activities	\$26,564.00
105	Post Retirement Activities	\$26,564.00

Sibley Unit 1 Retirement

ID	Task Name	Duration	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Quarter
1	Sibley Unit 1 Retirement	241 days					
2	Pre-Engineering	66 days					
3	Permit review and engineering analysis, establish isolation points, and confirm fuel yard inventory has been reduced to zero tons.	66 days					
4	KCL&L Overhead Costs	135 days					
5	KCP&L Retirement Manager	135 days					
6	Equipment Rentals	135 days					
7	Vacuum truck	135 days					
8	Retirement	135 days					
9	Electrical	22 days					
10	Medium and Low Voltage Draw out Switchgear	3 days					
11	De-energize all buses at the source.	0.5 days					
12	Open all circuit breakers.	0.5 days					
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	0.5 days					
14	Verify that the closing/tripping springs are discharged.	0.5 days					
15	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each breaker cubicle.	1 day					
16	Motor Control Centers	2 days					
17	De-energize all buses at the source.	0.5 days					
18	Open all circuit breakers and disconnect switches.	0.5 days					
19	Remove all fuses in control circuits.	1 day					
20	Low-voltage Switchboards and Panelboards	1 day					
21	De-energize all buses at the source.	0.5 days					
22	Open all circuit breakers and disconnect switches.	0.5 days					
23	Oil-Filled Power Transformers	7 days					
24	De-energize all transformer primaries and verify that the secondary is de-energized.	1 day					
25	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	1 day					
26	Drain and dispose of oil.	3 days					

Sibley Unit 1 Retirement							
ID	Task Name	Duration	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Quarter
27	Clean up and dispose of oil on surface areas around the transformers on in containment pits.	2 days					
28	Dry-type Power Transformers	2 days					
29	De-energize all transformer primaries and verify that the secondary is de-energized.	1 day					
30	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	1 day					
31	Motors	7 days					
32	De-energize all primary power at the source.	2 days					
33	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	2 days					
34	Drain lube oil system (if applicable) and dispose of oil.	3 days					
35	Coal Handling	24 days					
36	Isolate area K Unit 1 Silos.	5 days					
37	Confirm all fuel lines and feedrs are clear of coal and coal dust.	2 days					
38	Perform cleaning of the coal handling equipment to assure that all coal and coal dust has been removed from site.	17 days					
39	Propane Igniter System	3 days					
40	Isolate lines from source, open and vent.	3 days					
41	Boiler Chemical Feed	2 days					
42	Drain all chemical feed tanks.	2 days					
43	Boiler	28 days					
44	Open boiler doors.	1 day					
45	Gas side - perform cleaning of the boiler and bottom ash system.	15 days					
46	Drain boiler, drums, downcomers and headers.	1 day					
47	Open drum doors and blowdown tank doors.	1 day					
48	Drain and vent the service water and ash sluice water systems	1 day					
49	Clean bottom ash, economizer ash and fly ash system.	5 days					
50	Open, flush with water and vent the SNCR/RRI piping	4 days					
51	Precipitator	13 days					
52	Multiple cleaning cycles for collection plates.	3 days					



Sibley Unit 1 Retirement

ID	Task Name	Duration	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Quarter
53	Clear hoppers of all ash	4 days					
54	Disconnect transformers.	2 days					
55	Mechanically secure all compartment dampers and hopper outlet valves in open position.	1 day					
56	Disconnect ash transport piping and washdown hoppers and interior of casing.	1 day					
57	Install bird screens across hopper ash outlet and ash line flanges.	1 day					
58	Padlock or tack weld all hopper doors shut. (note: if ash hopper doors are indoors, they could be removed and the opening covered with bird screens.)	1 day					
59	Ductwork	7 days					
60	Open ductwork doors.	1 day					
61	Perform extensive cleaning of the ductwork.	5 days					
62	Isolate ductwork at tie to ductwork common to Unit 2	1 day					
63	Condensate and Feedwater Piping	3 days					
64	Drain water from the system.	1 day					
65	Leave open vents and drains.	1 day					
66	Drain, open and vent condensate storage tanks	1 day					
67	Feedwater heaters	3 days					
68	Drain feedwater heaters	1 day					
69	Leave open vents and drains.	2 days					
70	Turbine and Condenser	6 days					
71	Drain hotwell and leave doors open.	1 day					
72	Open main turbine doors.	1 day					
73	Remove lube oil.	3 days					
74	Drain Gland Water Tank and Condensate Collection Tank	1 day					
75	Generator	7 days					
76	Verify that generator circuit breaker is open and racked out or that high-voltage disconnect switch on substation side of GSU transformer is locked in the open position.	0.5 days					
77	Verify that generator field breaker or contactor (if applicable) is open	0.5 days					
78	De-energize power supplies to generator excitation system at the source.	0.5 days					



Sibley Unit 1 Retirement

ID	Task Name	Duration	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Quarter
79	De-energize AC and DC power supplies to generator and exciter space heaters, cooling equipment, controls, lighting, etc. at the source and open circuit breakers or remove fuses at the generator	0.5 days					
80	Drain generator and exciter cooling water systems (if applicable).	1 day					
81	Disconnect and remove hydrogen gas tanks and purge generator hydrogen system.	2 days					
82	Disconnect and remove fire protection system gas/foam tanks and purge fire protection system.	2 days					
83	Circulation Water and Turbine Cooling Water System	3 days					
84	Drain.	2 days					
85	Open water box doors.	1 day					
86	Drain any circulating water chemical feed tanks.	1 day					
87	Compressed Air System	1 day					
88	Open vents and drains.	1 day					
89	Auxiliary Steam System	3 days					
90	Drain water from system.	1 day					
91	Open and vent F.D. Fan Steam Coils	2 days					
92	Bearing Cooling Water and Boiler Cooling Water System	1 day					
93	Drain water from system and vent.	1 day					
94	Condenser Air Extraction System	1 day					
95	Drain water from system.	1 day					
96	Building Heating System	1 day					
97	Drain water from system.	1 day					
98	Battery System	7 days					
99	De-energize all battery chargers from the source.	0.5 days					
100	Open all AC and DC circuit breakers and/or fused switches on battery chargers and disconnect cables from batteries.	0.5 days					
101	Remove and dispose of battery electrolyte.	3 days					
102	Remove and dispose of battery cells.	2 days					
103	Clean up and dispose of electrolyte on surface areas around batteries	1 day					
104	Post Retirement Activities	40 days					
105	Post Retirement Activities	40 days					

Sibley Unit 1 Dismantlement

Owner Costs

Pre-Dismantlement Activities		\$892,760	
Overhead During Dismantlement		\$492,984	
Post-Dismantlement Activities		\$49,140	
Owner Costs Total*			\$1,434,884

Demolition General Contractor (DGC) Costs

Site Management		\$268,729	
Equipment Rental		\$457,572	
Consummables		\$456,510	
Scrap Crew(s)		\$452,980	
Dismantlement		\$1,008,001	
Contractor Direct Cost*	\$2,643,792		

Contractor Allowances

DGC Insurance	2.00%	\$52,876	
Contingency/Profit	15.00%	\$404,500	
Performance Bond	2.00%	\$62,023.36	

Contractor Costs Total: \$3,163,191

Total: \$4,598,075

Owner Internal Costs: 5.00% \$229,904

Owner Contingency: 25.00% \$1,206,995

Sibley Unit 1 Dismantlement Opinion of Probable Cost: \$6,034,974

*Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances
= \$4,078,676

11/11/2020

11/11/2020

11/11/2020

11/11/2020

11/11/2020

UNIT 2

Sibley Unit 2 Retirement

Owner Costs

Pre-Retirement Activities	\$100,821
Retirement Activities	\$240,134
Post-Retirement Activities	\$26,564

Owner Direct Total \$367,519

Owner Internal Costs 5.00% \$18,376

Owner Contingency: 25.00% \$96,474

Sibley Unit 2 Retirement Opinion of Probable Cost: \$482,368.69

Sibley Unit 2 Retirement		
ID	Task Name	Cost
1	Sibley Unit 2 Retirement	\$367,519.09
2	Pre-Engineering	\$100,821.60
3	Permit review and engineering analysis, establish isolation points, and confirm	\$100,821.60
4	KCL&L Overhead Costs	\$83,646.00
5	KCP&L Retirement Manager	\$83,646.00
6	Equipment Rentals	\$28,339.20
7	Vacuum truck	\$28,339.20
8	Retirement	\$128,148.29
9	Electrical	\$18,911.68
10	Medium and Low Voltage Draw out Switchgear	\$2,679.84
11	De-energize all buses at the source.	\$446.64
12	Open all circuit breakers.	\$446.64
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	\$446.64
14	Verify that the closing/tripping springs are discharged.	\$446.64
15	De-energize control power and auxiliary power circuits of each circuit br	\$893.28
16	Motor Control Centers	\$1,786.56
17	De-energize all buses at the source.	\$446.64
18	Open all circuit breakers and disconnect switches.	\$446.64
19	Remove all fuses in control circuits.	\$893.28
20	Low-voltage Switchboards and Panelboards	\$893.28
21	De-energize all buses at the source.	\$446.64
22	Open all circuit breakers and disconnect switches.	\$446.64
23	Oil-Filled Power Transformers	\$5,549.44
24	De-energize all transformer primaries and verify that the secondary is de	\$893.28
25	De-energize all low-voltage AC or DC power sources for space heaters, c	\$893.28
26	Drain and dispose of oil.	\$2,642.88
27	Clean up and dispose of oil on surface areas around the transformers on	\$1,120.00
28	Dry-type Power Transformers	\$1,786.56
29	De-energize all transformer primaries and verify that the secondary is de	\$893.28
30	De-energize all low-voltage AC or DC power sources for space heaters, c	\$893.28
31	Motors	\$6,216.00
32	De-energize all primary power at the source.	\$1,786.56
33	De-energize all low-voltage power sources for space heaters or other au	\$1,786.56
34	Drain lube oil system (if applicable) and dispose of oil.	\$2,642.88
35	Coal Handling	\$29,248.24
36	Isolate area K Unit 1 Silos.	\$8,522.80
37	Confirm all fuel lines and feedrs are clear of coal and coal dust.	\$1,685.44
38	Perform cleaning of the coal handling equipment to assure that all coal anc	\$19,040.00
39	Propane Igniter System	\$2,528.16
40	Isolate lines from source, open and vent.	\$2,528.16
41	Boiler Chemical Feed	\$1,685.44
42	Drain all chemical feed tanks.	\$1,685.44
43	Boiler	\$29,591.57
44	Open boiler doors.	\$880.96

Sibley Unit 2 Retirement		
ID	Task Name	Cost
45	Gas side - perform cleaning of the boiler and bottom ash system.	\$16,800.00
46	Drain boiler, drums, downcomers and headers.	\$842.72
47	Open drum doors and blowdown tank doors.	\$880.96
48	Drain and vent the service water and ash sluice water systems	\$1,541.36
49	Clean bottom ash, economizer ash and fly ash system.	\$2,480.13
50	Open, flush with water and vent the SNCR/RRR piping	\$6,165.44
51	Precipitator	\$10,603.04
52	Multiple cleaning cycles for collection plates.	\$2,528.16
53	Clear hoppers of all ash	\$2,805.44
54	Disconnect transformers.	\$1,786.56
55	Mechanically secure all compartment dampers and hopper outlet valves in	\$720.48
56	Disconnect ash transport piping and washdown hoppers and interior of ca	\$1,000.48
57	Install bird screens across hopper ash outlet and ash line flanges.	\$880.96
58	Padlock or tack weld all hopper doors shut. (note: if ash hopper doors are i	\$880.96
59	Ductwork	\$6,480.96
60	Open ductwork doors.	\$880.96
61	Perform extensive cleaning of the ductwork.	\$5,600.00
62	Isolate ductwork at tie to ductwork common to Unit 2	\$0.00
63	Condensate and Feedwater Piping	\$2,528.16
64	Drain water from the system.	\$842.72
65	Leave open vents and drains.	\$842.72
66	Drain, open and vent condensate storage tanks	\$842.72
67	Feedwater heaters	\$2,528.16
68	Drain feedwater heaters	\$842.72
69	Leave open vents and drains.	\$1,685.44
70	Turbine and Condenser	\$4,385.68
71	Drain hotwell and leave doors open.	\$861.84
72	Open main turbine doors.	\$880.96
73	Remove lube oil.	\$2,642.88
74	Drain Gland Water Tank and Condensate Collection Tank	\$0.00
75	Generator	\$6,095.76
76	Verify that generator circuit breaker is open and racked out or that high-vo	\$446.64
77	Verify that generator field breaker or contactor (if applicable) is open.	\$446.64
78	De-energize power supplies to generator excitation system at the source.	\$446.64
79	De-energize AC and DC power supplies to generator and exciter space heat	\$446.64
80	Drain generator and exciter cooling water systems (if applicable).	\$861.84
81	Disconnect and remove hydrogen gas tanks and purge generator hydrogen	\$1,685.44
82	Disconnect and remove fire protection system gas/foam tanks and purge fi	\$1,761.92
83	Circulation Water and Turbine Cooling Water System	\$3,409.12
84	Drain.	\$1,685.44
85	Open water box doors.	\$880.96
86	Drain any circulating water chemical feed tanks.	\$842.72
87	Compressed Air System	\$842.72
88	Open vents and drains.	\$842.72

Sibley Unit 2 Retirement


ID	Task Name	Cost
89	Auxiliary Steam System	\$2,528.16
90	Drain water from system.	\$842.72
91	Open and vent F.D. Fan Steam Coils	\$1,685.44
92	Bearing Cooling Water and Boiler Cooling Water System	\$842.72
93	Drain water from system and vent.	\$842.72
94	Condenser Air Extraction System	\$842.72
95	Drain water from system.	\$842.72
96	Building Heating System	\$842.72
97	Drain water from system.	\$842.72
98	Battery System	\$4,253.28
99	De-energize all battery chargers from the source.	\$446.64
100	Open all AC and DC circuit breakers and/or fused switches on battery charg	\$446.64
101	Remove and dispose of battery electrolyte.	\$1,680.00
102	Remove and dispose of battery cells.	\$1,120.00
103	Clean up and dispose of electrolyte on surface areas around batteries.	\$560.00
104	Post Retirement Activities	\$26,564.00
105	Post Retirement Activities	\$26,564.00

Sibley Unit 2 Retirement

ID	Task Name	Duration	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Quarter
1	Sibley Unit 2 Retirement	241 days					
2	Pre-Engineering	66 days					
3	Permit review and engineering analysis, establish isolation points, and confirm fuel yard inventory has been reduced to zero tons.	66 days					
4	KCL&L Overhead Costs	135 days					
5	KCP&L Retirement Manager	135 days					
6	Equipment Rentals	135 days					
7	Vacuum truck	135 days					
8	Retirement	135 days					
9	Electrical	22 days					
10	Medium and Low Voltage Draw out Switchgear	3 days					
11	De-energize all buses at the source.	0.5 days					
12	Open all circuit breakers.	0.5 days					
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	0.5 days					
14	Verify that the closing/tripping springs are discharged.	0.5 days					
15	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each breaker cubicle.	1 day					
16	Motor Control Centers	2 days					
17	De-energize all buses at the source.	0.5 days					
18	Open all circuit breakers and disconnect switches.	0.5 days					
19	Remove all fuses in control circuits.	1 day					
20	Low-voltage Switchboards and Panelboards	1 day					
21	De-energize all buses at the source.	0.5 days					
22	Open all circuit breakers and disconnect switches.	0.5 days					
23	Oil-Filled Power Transformers	7 days					
24	De-energize all transformer primaries and verify that the secondary is de-energized.	1 day					
25	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	1 day					
26	Drain and dispose of oil.	3 days					

Sibley Unit 2 Retirement

ID	Task Name	Duration	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Quarter
27	Clean up and dispose of oil on surface areas around the transformers on in containment pits.	2 days					
28	Dry-type Power Transformers	2 days					
29	De-energize all transformer primaries and verify that the secondary is de-energized.	1 day					
30	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	1 day					
31	Motors	7 days					
32	De-energize all primary power at the source.	2 days					
33	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	2 days					
34	Drain lube oil system (if applicable) and dispose of oil.	3 days					
35	Coal Handling	24 days					
36	Isolate area K Unit 1 Silos.	5 days					
37	Confirm all fuel lines and feedrs are clear of coal and coal dust.	2 days					
38	Perform cleaning of the coal handling equipment to assure that all coal and coal dust has been removed from site.	17 days					
39	Propane Igniter System	3 days					
40	Isolate lines from source, open and vent.	3 days					
41	Boiler Chemical Feed	2 days					
42	Drain all chemical feed tanks.	2 days					
43	Boiler	28 days					
44	Open boiler doors.	1 day					
45	Gas side - perform cleaning of the boiler and bottom ash system.	15 days					
46	Drain boiler, drums, downcomers and headers.	1 day					
47	Open drum doors and blowdown tank doors.	1 day					
48	Drain and vent the service water and ash sluice water systems	1 day					
49	Clean bottom ash, economizer ash and fly ash system.	5 days					
50	Open, flush with water and vent the SNCR/RRI piping	4 days					
51	Precipitator	13 days					
52	Multiple cleaning cycles for collection plates.	3 days					




Sibley Unit 2 Retirement

ID	Task Name	Duration	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Quarter
53	Clear hoppers of all ash	4 days					
54	Disconnect transformers.	2 days					
55	Mechanically secure all compartment dampers and hopper outlet valves in open position.	1 day					
56	Disconnect ash transport piping and washdown hoppers and interior of casing.	1 day					
57	Install bird screens across hopper ash outlet and ash line flanges.	1 day					
58	Padlock or tack weld all hopper doors shut. (note: if ash hopper doors are indoors, they could be removed and the opening covered with bird screens.)	1 day					
59	Ductwork	7 days					
60	Open ductwork doors.	1 day					
61	Perform extensive cleaning of the ductwork.	5 days					
62	Isolate ductwork at tie to ductwork common to Unit 2	1 day					
63	Condensate and Feedwater Piping	3 days					
64	Drain water from the system.	1 day					
65	Leave open vents and drains.	1 day					
66	Drain, open and vent condensate storage tanks	1 day					
67	Feedwater heaters	3 days					
68	Drain feedwater heaters	1 day					
69	Leave open vents and drains.	2 days					
70	Turbine and Condenser	6 days					
71	Drain hotwell and leave doors open.	1 day					
72	Open main turbine doors.	1 day					
73	Remove lube oil.	3 days					
74	Drain Gland Water Tank and Condensate Collection Tank	1 day					
75	Generator	7 days					
76	Verify that generator circuit breaker is open and racked out or that high-voltage disconnect switch on substation side of GSU transformer is locked in the open position.	0.5 days					
77	Verify that generator field breaker or contactor (if applicable) is open	0.5 days					
78	De-energize power supplies to generator excitation system at the source.	0.5 days					



Sibley Unit 2 Retirement

ID	Task Name	Duration	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Quarter
79	De-energize AC and DC power supplies to generator and exciter space heaters, cooling equipment, controls, lighting, etc. at the source and open circuit breakers or remove fuses at the generator	0.5 days					
80	Drain generator and exciter cooling water systems (if applicable).	1 day					
81	Disconnect and remove hydrogen gas tanks and purge generator hydrogen system.	2 days					
82	Disconnect and remove fire protection system gas/foam tanks and purge fire protection system.	2 days					
83	Circulation Water and Turbine Cooling Water System	3 days					
84	Drain.	2 days					
85	Open water box doors.	1 day					
86	Drain any circulating water chemical feed tanks.	1 day					
87	Compressed Air System	1 day					
88	Open vents and drains.	1 day					
89	Auxiliary Steam System	3 days					
90	Drain water from system.	1 day					
91	Open and vent F.D. Fan Steam Coils	2 days					
92	Bearing Cooling Water and Boiler Cooling Water System	1 day					
93	Drain water from system and vent.	1 day					
94	Condenser Air Extraction System	1 day					
95	Drain water from system.	1 day					
96	Building Heating System	1 day					
97	Drain water from system.	1 day					
98	Battery System	7 days					
99	De-energize all battery chargers from the source.	0.5 days					
100	Open all AC and DC circuit breakers and/or fused switches on battery chargers and disconnect cables from batteries.	0.5 days					
101	Remove and dispose of battery electrolyte.	3 days					
102	Remove and dispose of battery cells.	2 days					
103	Clean up and dispose of electrolyte on surface areas around batteries	1 day					
104	Post Retirement Activities	40 days					
105	Post Retirement Activities	40 days					



Sibley Unit 2 Dismantlement

Owner Costs

Pre-Dismantlement Activities		\$892,760	
Overhead During Dismantlement		\$492,984	
Post-Dismantlement Activities		\$49,140	
Owner Costs Total*			\$1,434,884

Demolition General Contractor (DGC) Costs

Site Management		\$268,729	
Equipment Rental		\$457,572	
Consummables		\$456,510	
Scrap Crew(s)		\$452,980	
Dismantlement		\$1,008,001	
Contractor Direct Cost*	\$2,643,792		

Contractor Allowances

DGC Insurance	2.00%	\$52,876	
Contingency/Profit	15.00%	\$404,500	
Performance Bond	2.00%	\$62,023.36	

Contractor Costs Total: \$3,163,191

Total:			\$4,598,075
Owner Internal Costs:	5.00%		\$229,904
Owner Contingency:	25.00%		\$1,206,995
Sibley Unit 2 Dismantlement Opinion of Probable Cost:			\$6,034,974

*Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances
= \$4,078,676

UNIT 3

UNIT 3

UNIT 3

UNIT 3

UNIT 3

Sibley Unit 3 Retirement

Owner Costs

Pre-Retirement Activities	\$100,821
Retirement Activities	\$280,964
Post-Retirement Activities	\$26,564

Owner Direct Total \$408,349

Owner Internal Costs 5.00% \$20,417

Owner Contingency: 25.00% \$107,192

Sibley Unit 3 Retirement Opinion of Probable Cost: \$535,958.06

Sibley Unit 3 Retirement		
ID	Task Name	Cost
1	Sibley Unit 3 Retirement	\$408,350.61
2	Pre-Engineering	\$100,821.60
3	Permit review and engineering analysis, establish isolation points, and confirm fuel yard inventory has been reduced to zero tons.	\$100,821.60
4	KCL&L Overhead Costs	\$99,755.60
5	KCP&L Retirement Manager	\$99,755.60
6	Equipment Rentals	\$33,797.12
7	Vacuum truck	\$33,797.12
8	Retirement	\$147,412.29
9	Electrical	\$18,911.68
10	Medium and Low Voltage Draw out Switchgear	\$2,679.84
11	De-energize all buses at the source.	\$446.64
12	Open all circuit breakers.	\$446.64
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	\$446.64
14	Verify that the closing/tripping springs are discharged.	\$446.64
15	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each breaker cubicle.	\$893.28
16	Motor Control Centers	\$1,786.56
17	De-energize all buses at the source.	\$446.64
18	Open all circuit breakers and disconnect switches.	\$446.64
19	Remove all fuses in control circuits.	\$893.28
20	Low-voltage Switchboards and Panelboards	\$893.28
21	De-energize all buses at the source.	\$446.64
22	Open all circuit breakers and disconnect switches.	\$446.64
23	Oil-Filled Power Transformers	\$5,549.44
24	De-energize all transformer primaries and verify that the secondary is de-energized.	\$893.28
25	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	\$893.28
26	Drain and dispose of oil.	\$2,642.88
27	Clean up and dispose of oil on surface areas around the transformers on in containment pits.	\$1,120.00
28	Dry-type Power Transformers	\$1,786.56
29	De-energize all transformer primaries and verify that the secondary is de-energized.	\$893.28
30	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	\$893.28
31	Motors	\$6,216.00
32	De-energize all primary power at the source.	\$1,786.56

Sibley Unit 3 Retirement

ID	Task Name	Cost
33	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	\$1,786.56
34	Drain lube oil system (if applicable) and dispose of oil.	\$2,642.88
35	Coal Handling	\$25,790.00
36	Empty all silos in Area M.	\$1,704.56
37	Confirm conveyors are run out of fuel.	\$1,685.44
38	Perform cleaning of the coal handling equipment to assure that all coal and coal dust has been removed from area.	\$22,400.00
39	Propane Igniter System	\$2,528.16
40	Isolate lines from source, open and vent.	\$2,528.16
41	Boiler Chemical Feed	\$1,685.44
42	Drain all chemical feed tanks.	\$1,685.44
43	Condensate Polisher	\$4,529.12
44	Drain water from system.	\$842.72
45	Drain acid and caustic tanks.	\$1,685.44
46	Open tanks and vessels.	\$880.96
47	Remove resin.	\$1,120.00
48	Boiler	\$32,108.85
49	Open boiler doors.	\$880.96
50	Gas side - perform cleaning of the boiler and bottom ash system.	\$22,400.00
51	Drain boiler, drum, downcomers and headers.	\$842.72
52	Open drum doors.	\$880.96
53	Drain, vent and clean the fly ash, slag and transport water system	\$2,480.13
54	Drain and vent the steam coil air heaters and piping	\$1,541.36
55	Drain and vent the steam coil air heater drain tanks	\$1,541.36
56	Drain and vent boiler sampling system panel and piping	\$1,541.36
57	Precipitator	\$9,901.68
58	Multiple cleaning cycles for collection plates.	\$2,528.16
59	Clear hoppers of all ash	\$2,104.08
60	Disconnect transformers.	\$1,786.56
61	Mechanically secure all compartment dampers and hopper outlet valves in open position.	\$720.48
62	Disconnect ash transport piping and washdown hoppers and interior of casing.	\$1,000.48
63	Install bird screens across hopper ash outlet and ash line flanges.	\$880.96
64	Padlock or tack weld all hopper doors shut. (note: if ash hopper doors are indoors, they could be removed and the opening covered with bird screens.)	\$880.96
65	Ductwork	\$12,080.96
66	Open ductwork doors.	\$880.96
67	Perform extensive cleaning of the ductwork.	\$11,200.00
68	Isolate ductwork at tie to common ductwork.	\$0.00
69	Condensate and Feedwater Piping	\$1,685.44
70	Drain water from the system.	\$842.72

Sibley Unit 3 Retirement

ID	Task Name	Cost
71	Leave open vents and drains.	\$842.72
72	Feedwater heaters	\$3,370.88
73	Drain feedwater heaters	\$842.72
74	Leave open vents and drains.	\$1,685.44
75	Drain and vent the heater drain piping.	\$842.72
76	Deaerator and Deaerator Storage Tank	\$1,685.44
77	Drain Deaerator and Storage	\$842.72
78	Leave open vents and drains.	\$842.72
79	SCR	\$9,053.52
80	Vacuum fly ash from catalyst.	\$1,680.00
81	Remove catalyst of salvage or disposal.	\$2,441.44
82	Padlock or tack weld access doors shut.	\$880.96
83	Remove ammonia from storage tank for resale.	\$701.36
84	Wash out and drain storage tank and supply piping.	\$701.36
85	Vent storage tank and all piping. Leave vent and drain valves open or remove. Install bird screens.	\$861.84
86	Pull electrical supply breakers on all electrical equipment except lighting and HVAC components that are to remain in service.	\$1,786.56
87	Turbine(s) and Condenser	\$5,266.64
88	Drain hotwell and leave doors open.	\$861.84
89	Open main turbine doors.	\$880.96
90	Open bfp turbine doors.	\$880.96
91	Remove lube oil.	\$2,642.88
92	Generator	\$6,095.76
93	Verify that generator circuit breaker is open and racked out or that high-voltage disconnect switch on substation side of GSU transformer is locked in the open position.	\$446.64
94	Verify that generator field breaker or contactor (if applicable) is open.	\$446.64
95	De-energize power supplies to generator excitation system at the source.	\$446.64
96	De-energize AC and DC power supplies to generator and exciter space heaters, cooling equipment, controls, lighting, etc. at the source and open circuit breakers or remove fuses at the generator and exciter.	\$446.64
97	Drain generator and exciter cooling water systems (if applicable).	\$861.84
98	Disconnect and remove hydrogen gas tanks and purge generator hydrogen system.	\$1,685.44
99	Disconnect and remove fire protection system gas/foam tanks and purge fire protection system.	\$1,761.92
100	Circulation Water and Turbine Cooling Water System	\$3,409.12
101	Drain.	\$1,685.44
102	Open water box doors.	\$880.96
103	Drain any circulating water chemical feed tanks.	\$842.72

Sibley Unit 3 Retirement


ID	Task Name	Cost
104	Compressed Air System	\$842.72
105	Open vents and drains.	\$842.72
106	Auxiliary Steam System	\$842.72
107	Drain water from system.	\$842.72
108	Station Cooling Water System	\$1,685.44
109	Drain water from system.	\$842.72
110	Vent piping.	\$842.72
111	Condenser Air Extraction	\$842.72
112	Drain water from system.	\$842.72
113	Building Heating System	\$842.72
114	Drain water from system.	\$842.72
115	Battery System	\$4,253.28
116	De-energize all battery chargers from the source.	\$446.64
117	Open all AC and DC circuit breakers and/or fused switches on battery chargers and disconnect cables from batteries.	\$446.64
118	Remove and dispose of battery electrolyte.	\$1,680.00
119	Remove and dispose of battery cells.	\$1,120.00
120	Clean up and dispose of electrolyte on surface areas around batteries.	\$560.00
121	Post Retirement Activities	\$26,564.00
122	Post Retirement Activities	\$26,564.00

Sibley Unit 3 Retirement

ID	Task Name	Duration	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Quarter
1	Sibley Unit 3 Retirement	267 days					
2	Pre-Engineering	66 days					
3	Permit review and engineering analysis, establish isolation points, and confirm fuel yard inventory has been reduced to	66 days					
4	KCL&L Overhead Costs	161 days					
5	KCP&L Retirement Manager	161 days					
6	Equipment Rentals	161 days					
7	Vacuum truck	161 days					
8	Retirement	161 days					
9	Electrical	22 days					
10	Medium and Low Voltage Draw out Switchgear	3 days					
11	De-energize all buses at the source.	0.5 days					
12	Open all circuit breakers.	0.5 days					
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	0.5 days					
14	Verify that the closing/tripping springs are discharged.	0.5 days					
15	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each breaker cubicle.	1 day					
16	Motor Control Centers	2 days					
17	De-energize all buses at the source.	0.5 days					
18	Open all circuit breakers and disconnect switches.	0.5 days					
19	Remove all fuses in control circuits.	1 day					
20	Low-voltage Switchboards and Panelboards	1 day					
21	De-energize all buses at the source.	0.5 days					
22	Open all circuit breakers and disconnect switches.	0.5 days					
23	Oil-Filled Power Transformers	7 days					
24	De-energize all transformer primaries and verify that the secondary is de-energized.	1 day					


Sibley Unit 3 Retirement

ID	Task Name	Duration	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Quarter
25	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	1 day					
26	Drain and dispose of oil.	3 days					
27	Clean up and dispose of oil on surface areas around the transformers on in containment pits.	2 days					
28	Dry-type Power Transformers	2 days					
29	De-energize all transformer primaries and verify that the secondary is de-energized.	1 day					
30	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	1 day					
31	Motors	7 days					
32	De-energize all primary power at the source.	2 days					
33	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	2 days					
34	Drain lube oil system (if applicable) and dispose of oil.	3 days					
35	Coal Handling	23 days					
36	Empty all silos in Area M.	1 day					
37	Confirm conveyors are run out of fuel.	2 days					
38	Perform cleaning of the coal handling equipment to assure that all coal and coal dust has been removed from area.	20 days					
39	Propane Igniter System	3 days					
40	Isolate lines from source, open and vent.	3 days					
41	Boiler Chemical Feed	2 days					
42	Drain all chemical feed tanks.	2 days					
43	Condensate Polisher	6 days					
44	Drain water from system.	1 day					
45	Drain acid and caustic tanks.	2 days					
46	Open tanks and vessels.	1 day					
47	Remove resin.	2 days					
48	Boiler	30 days					



Sibley Unit 3 Retirement

ID	Task Name	Duration	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Quarter
49	Open boiler doors.	1 day					
50	Gas side - perform cleaning of the boiler and bottom ash system.	20 days					
51	Drain boiler, drum, downcomers and headers.	1 day					
52	Open drum doors.	1 day					
53	Drain, vent and clean the fly ash, slag and transport water system	5 days					
54	Drain and vent the steam coil air heaters and piping	1 day					
55	Drain and vent the steam coil air heater drain tanks	1 day					
56	Drain and vent boiler sampling system panel and piping	1 day					
57	Precipitator	12 days					
58	Multiple cleaning cycles for collection plates.	3 days					
59	Clear hoppers of all ash	3 days					
60	Disconnect transformers.	2 days					
61	Mechanically secure all compartment dampers and hoppers	1 day					
62	Disconnect ash transport piping and washdown hoppers and	1 day					
63	Install bird screens across hopper ash outlet and ash line fl.	1 day					
64	Padlock or tack weld all hopper doors shut. (note: if ash ho	1 day					
65	Ductwork	13 days					
66	Open ductwork doors.	1 day					
67	Perform extensive cleaning of the ductwork.	10 days					
68	Isolate ductwork at tie to common ductwork.	2 days					
69	Condensate and Feedwater Piping	2 days					
70	Drain water from the system.	1 day					
71	Leave open vents and drains.	1 day					
72	Feedwater heaters	4 days					
73	Drain feedwater heaters	1 day					
74	Leave open vents and drains.	2 days					
75	Drain and vent the heater drain piping.	1 day					
76	Deaerator and Deaerator Storage Tank	2 days					
77	Drain Deaerator and Storage	1 day					
78	Leave open vents and drains.	1 day					
79	SCR	12 days					



Sibley Unit 3 Retirement

ID	Task Name	Duration	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Quarter
80	Vacuum fly ash from catalyst.	3 days					
81	Remove catalyst of salvage or disposal.	3 days					
82	Padlock or tack weld access doors shut.	1 day					
83	Remove ammonia from storage tank for resale.	1 day					
84	Wash out and drain storage tank and supply piping.	1 day					
85	Vent storage tank and all piping. Leave vent and drain valves open or remove. Install bird screens.	1 day					
86	Pull electrical supply breakers on all electrical equipment except lighting and HVAC components that are to remain in service.	2 days					
87	Turbine(s) and Condenser	6 days					
88	Drain hotwell and leave doors open.	1 day					
89	Open main turbine doors.	1 day					
90	Open bfp turbine doors.	1 day					
91	Remove lube oil.	3 days					
92	Generator	7 days					
93	Verify that generator circuit breaker is open and racked out or that high-voltage disconnect switch on substation side of GSU transformer is locked in the open position.	0.5 days					
94	Verify that generator field breaker or contactor (if applicable) is open.	0.5 days					
95	De-energize power supplies to generator excitation system at the source.	0.5 days					
96	De-energize AC and DC power supplies to generator and exciter space heaters, cooling equipment, controls, lighting, etc. at the source and open circuit breakers or remove fuses at the generator and exciter.	0.5 days					
97	Drain generator and exciter cooling water systems (if applicable).	1 day					
98	Disconnect and remove hydrogen gas tanks and purge generator hydrogen system.	2 days					
99	Disconnect and remove fire protection system gas/foam tanks and purge fire protection system.	2 days					
100	Circulation Water and Turbine Cooling Water System	4 days					



Sibley Unit 3 Retirement

ID	Task Name	Duration	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Quarter
101	Drain.	2 days					
102	Open water box doors.	1 day					
103	Drain any circulating water chemical feed tanks.	1 day					
104	Compressed Air System	1 day					
105	Open vents and drains.	1 day					
106	Auxiliary Steam System	1 day					
107	Drain water from system.	1 day					
108	Station Cooling Water System	2 days					
109	Drain water from system.	1 day					
110	Vent piping.	1 day					
111	Condenser Air Extraction	1 day					
112	Drain water from system.	1 day					
113	Building Heating System	1 day					
114	Drain water from system.	1 day					
115	Battery System	7 days					
116	De-energize all battery chargers from the source.	0.5 days					
117	Open all AC and DC circuit breakers and/or fused switches on battery chargers and disconnect cables from batteries.	0.5 days					
118	Remove and dispose of battery electrolyte.	3 days					
119	Remove and dispose of battery cells.	2 days					
120	Clean up and dispose of electrolyte on surface areas around batteries.	1 day					
121	Post Retirement Activities	40 days					
122	Post Retirement Activities	40 days					

Sibley Unit 3 Dismantlement

Owner Costs

Pre-Dismantlement Activities		\$892,760	
Overhead During Dismantlement		\$1,602,538	
Post-Dismantlement Activities		\$49,140	
Owner Costs Total*			\$2,544,438

Demolition General Contractor (DGC) Costs

Site Management		\$873,555	
Equipment Rental		\$1,487,425	
Consummables		\$1,483,973	
Scrap Crew(s)		\$1,472,497	
Dismantlement		\$3,276,697	
Contractor Direct Cost*	\$8,594,147		

Contractor Allowances

DGC Insurance	2.00%	\$171,883	
Contingency/Profit	15.00%	\$1,314,904	
Performance Bond	2.00%	\$201,618.69	

Contractor Costs Total: \$10,282,553

Total: \$12,826,991

Owner Internal Costs: 5.00% \$641,350

Owner Contingency: 25.00% \$3,367,085

Sibley Unit 3 Dismantlement Opinion of Probable Cost: \$16,835,426

*Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances
= \$11,138,585

Sibley Unit 3 Dismantlement		
ID	Task Name	Cost
1	Sibley Unit 3 Dismantlement	\$11,138,588.64
2	Pre-Dismantlement Activities	\$892,760.32
3	Detailed Planning & Hire Owner's Engineer	\$104,441.28
4	Detailed Site Characterization Study	\$610,335.44
5	Hire Demolition General Contractor	\$167,184.00
6	KCP&L Prepares Unit for Dismantlement	\$10,799.60
7	Demolition Contractor Mobilizes on Site	\$0.00
8	KCP&L Overhead during Dismantlement	\$1,602,538.32
9	KCP&L Project Manager	\$254,655.60
10	KCP&L Administrative Support	\$94,168.32
11	KCP&L Engineer	\$418,562.40
12	Owners Engineer Project Manager	\$124,944.00
13	Owners Engineer - Engineer	\$710,208.00
14	Demolition Contractor Overhead during Dismantlement	\$873,555.84
15	Demolition Contractor Project Manager	\$247,158.96
16	Demolition Contractor Safety Manager	\$220,065.84
17	Demolition Contractor Superintendent	\$406,331.04
18	Demolition Contractor Equipment Rental Costs	\$1,487,425.44
19	Equipment Rental	\$1,487,425.44
20	Demolition Contractor Consumables	\$1,483,973.04
21	Consumables	\$1,483,973.04
22	Scrap Crew(s)	\$1,472,497.92
23	Crew to Handle Scrap Material(s)	\$1,472,497.92
24	Dismantlement Directs	\$3,276,697.76
25	Phase 1 Demolition	\$775,861.84
26	Electrical Demolition	\$342,149.76
27	Electrical Demolition Equipment	\$342,149.76
28	Condensate System	\$73,445.76
29	Condensate Pumps	\$3,582.72
30	Condensate Booster Pumps	\$1,791.36
31	Gland Steam Condenser	\$3,582.72
32	Low Pressure Heaters (except the condenser neck heat exchangers)	\$26,870.40
33	Deaerator	\$7,165.44
34	Deaerator Storage Tank	\$7,165.44
35	Condensate Piping	\$17,913.60
36	Polisher Vessels, Regen Vessels and Support Skids	\$5,374.08
37	Boiler Feed System	\$42,298.88
38	Boiler Feed Pump Turbines (2) and Exhaust	\$10,054.40
39	Boiler Feed Pumps - Turbine Driven	\$14,330.88
40	Start-up Boiler Feed Pump	\$0.00
41	High Pressure Heaters	\$17,913.60
42	Feedwater piping	\$0.00
43	Critical Piping	\$69,863.04

Sibley Unit 3 Dismantlement

ID	Task Name	Cost
44	Main Steam Piping	\$23,287.68
45	Cold Reheat Piping	\$23,287.68
46	Hot Reheat Piping	\$23,287.68
47	Extraction Steam System	\$17,913.60
48	Piping and Valves	\$17,913.60
49	Heater Drips	\$8,956.80
50	Heater Drip Pump	\$1,791.36
51	Piping	\$7,165.44
52	Auxiliary Steam	\$12,539.52
53	Auxiliary Steam Piping, Tanks and Misc. Equipment	\$12,539.52
54	Circulating Water (plant side)	\$5,374.08
55	Waterboxes	\$5,374.08
56	Station Cooling Water	\$16,122.24
57	Station Cooling Water Pumps	\$1,791.36
58	Station Cooling Water Heat Exchanger	\$3,582.72
59	Station Cooling Water Piping	\$10,748.16
60	Chemical Mixing Tank	\$0.00
61	Station Cooling Water Head Tank	\$0.00
62	Service Water	\$12,539.52
63	Service Water Piping	\$12,539.52
64	Propane System (plant side)	\$16,122.24
65	Propane Piping and Valves	\$7,165.44
66	Igniters	\$8,956.80
67	Air Preheat System	\$7,165.44
68	Steam Coil Air Heater Piping	\$3,582.72
69	Steam Coil Drain Pumps	\$1,791.36
70	Steam Coil Drain Tanks	\$1,791.36
71	Condenser Air Extraction System	\$12,539.52
72	Vacuum Pumps	\$7,165.44
73	Vacuum Priming Pump	\$1,791.36
74	Vacuum Pump Piping	\$3,582.72
75	Turbine Seals and Drains	\$7,165.44
76	Piping	\$7,165.44
77	Turbine Lube Oil System	\$20,564.40
78	Turbine Lube Oil Tank	\$9,816.24
79	Turbine Lube Oil Pumps	\$7,165.44
80	Turbine Oil Mist Eliminator	\$3,582.72
81	Generator Auxilliary Systems	\$25,079.04
82	Hydrogen Cooler Skid and Piping	\$5,374.08
83	Stator Cooling Water Skid and Piping	\$5,374.08
84	Isophase Bus Duct	\$7,165.44
85	Exciter Heat Exchanger	\$3,582.72
86	EHC Coolers	\$3,582.72
87	Chemical Feed Systems	\$14,330.88

Sibley Unit 3 Dismantlement		
ID	Task Name	Cost
88	Tanks	\$3,582.72
89	Pumps	\$5,374.08
90	Piping	\$5,374.08
91	Sampling Systems	\$10,017.12
92	Field Mounted Heat Exchangers	\$3,582.72
93	Piping	\$2,851.68
94	Sample Panel	\$3,582.72
95	Building Heating Systems	\$13,307.84
96	Steam Unit Heaters	\$9,505.60
97	Steam Piping	\$3,802.24
98	Compressed Air System	\$26,870.40
99	Air Compressors	\$7,165.44
100	Air Drying Equipment	\$5,374.08
101	Air Receiver Tanks	\$5,374.08
102	Compressed Air Piping	\$8,956.80
103	Miscellaneous Equipment	\$21,496.32
104	Miscellaneous Equipment (including Fire Protection)	\$21,496.32
105	Phase 2 Demolition	\$2,409,476.56
106	Precipitator	\$107,481.60
107	Remove Precipitator	\$107,481.60
108	Boiler Equipment	\$536,314.56
109	Fans	\$53,740.80
110	Bottom Ash	\$16,451.52
111	Air Heater	\$143,308.80
112	Steam Drum	\$71,654.40
113	Coal Bunkers	\$71,654.40
114	Soot Blowers	\$25,447.68
115	Ductwork	\$100,316.16
116	SCR	\$53,740.80
117	Boiler Removal	\$329,610.24
118	Furnace	\$179,136.00
119	Back Pass	\$150,474.24
120	Boiler Steel Framing	\$616,227.84
121	Hanger Girders at Top	\$107,481.60
122	All Other Framing	\$286,617.60
123	Bracing and Girts	\$143,308.80
124	Columns	\$78,819.84
125	Boiler Foundations	\$128,977.92
126	Equipment Foundation Demolition to Grade	\$128,977.92
127	Remove Turbine	\$690,864.40
128	Remove HP Turbine	\$26,321.60
129	Remove IP Turbine	\$26,321.60
130	Remove LP Turbine	\$26,321.60
131	Remove Generator	\$39,482.40

Sibley Unit 3 Dismantlement		
ID	Task Name	Cost
132	Remove Condenser Neck Heat Exchanger	\$13,160.80
133	Remove Condenser	\$26,321.60
134	Remove Misc. Auxiliary Turbine Equipment	\$39,482.40
135	Turbine Pedestal Demolition to Grade	\$197,412.00
136	Top Slab and Beams	\$78,964.80
137	Columns	\$118,447.20
138	Remove Turbine Building	\$296,040.40
139	Siding and Roofing	\$92,778.00
140	All Framing Elevations	\$131,608.00
141	Bracing and Girts	\$52,643.20
142	Columns	\$19,011.20
143	Phase 3 Demolition	\$91,359.36
144	Yard Demolition	\$91,359.36
145	Remove Ash Handling Equipment and Piping	\$62,697.60
146	Slag Tank	\$17,913.60
147	Hydrovayer Pumps	\$8,956.80
148	Slag Tank Pumps	\$3,582.72
149	Hydrovayer Fly Ash System	\$8,956.80
150	Vacuum Filter System	\$5,374.08
151	Remove Slag Transport System Piping and Misc. Equipment	\$17,913.60
152	Remove Fuel Yard Equipment	\$19,704.96
153	Remove Conveyor 10	\$8,956.80
154	Remove Conveyor 10A	\$3,582.72
155	Remove Conveyor 10AA	\$3,582.72
156	Remove Conveyor 10AB	\$3,582.72
157	Remove Condensate Storage Tanks (2)	\$8,956.80
158	Project Close-Out	\$49,140.00
159	Project Close-Out Activities	\$49,140.00

Sibley Unit 3 Dismantlement

ID	Task Name	Duration	2012		2013		2014		2015		2016
			H2	H1	H2	H1	H2	H1	H2	H1	H1
1	Sibley Unit 3 Dismantlement	706 days									
2	Pre-Dismantlement Activities	265 days									
3	Detailed Planning & Hire Owner's Engineer	3 mons									
4	Detailed Site Characterization Study	130 days									
5	Hire Demolition General Contractor	3 mons									
6	KCP&L Prepares Unit for Dismantlement	2 wks									
7	Demolition Contractor Mobilizes on Site	5 days									
8	KCP&L Overhead during Dismantlement	411 days									
9	KCP&L Project Manager	411 days									
10	KCP&L Administrative Support	411 days									
11	KCP&L Engineer	411 days									
12	Owners Engineer Project Manager	411 days									
13	Owners Engineer - Engineer	411 days									
14	Demolition Contractor Overhead during Dismantlement	411 days									
15	Demolition Contractor Project Manager	411 days									
16	Demolition Contractor Safety Manager	411 days									
17	Demolition Contractor Superintendent	411 days									
18	Demolition Contractor Equipment Rental Costs	411 days									
19	Equipment Rental	411 days									
20	Demolition Contractor Consumables	411 days									
21	Consumables	411 days									
22	Scrap Crew(s)	411 days									
23	Crew to Handle Scrap Material(s)	411 days									
24	Dismantlement Directs	411 days									
25	Phase 1 Demolition	191 days									
26	Electrical Demolition	191 days									
27	Electrical Demolition Equipment	191 days									
28	Condensate System	41 days									
29	Condensate Pumps	2 days									
30	Condensate Booster Pumps	1 day									
31	Gland Steam Condenser	2 days									

Sibley Unit 3 Dismantlement

ID	Task Name	Duration	2012		2013		2014		2015		2016	
			H2	H1	H2	H1	H2	H1	H2	H1	H1	
32	Low Pressure Heaters (except the condenser neck heat exchangers)	15 days										
33	Deaerator	4 days										
34	Deaerator Storage Tank	4 days										
35	Condensate Piping	10 days										
36	Polisher Vessels, Regen Vessels and Support Ski	3 days										
37	Boiler Feed System	30 days										
38	Boiler Feed Pump Turbines (2) and Exhaust	5 days										
39	Boiler Feed Pumps - Turbine Driven	8 days										
40	Start-up Boiler Feed Pump	2 days										
41	High Pressure Heaters	10 days										
42	Feedwater piping	5 days										
43	Critical Piping	39 days										
44	Main Steam Piping	13 days										
45	Cold Reheat Piping	13 days										
46	Hot Reheat Piping	13 days										
47	Extraction Steam System	10 days										
48	Piping and Valves	10 days										
49	Heater Drips	5 days										
50	Heater Drip Pump	1 day										
51	Piping	4 days										
52	Auxiliary Steam	7 days										
53	Auxiliary Steam Piping, Tanks and Misc. Equipm	7 days										
54	Circulating Water (plant side)	3 days										
55	Waterboxes	3 days										
56	Station Cooling Water	11 days										
57	Station Cooling Water Pumps	1 day										
58	Station Cooling Water Heat Exchanger	2 days										
59	Station Cooling Water Piping	6 days										
60	Chemical Mixing Tank	1 day										
61	Station Cooling Water Head Tank	1 day										
62	Service Water	7 days										

Sibley Unit 3 Dismantlement

ID	Task Name	Duration	2012			2013		2014		2015		2016
			H2	H1	H2	H1	H2	H1	H2	H1	H2	H1
63	Service Water Piping	7 days										
64	Propane System (plant side)	9 days										
65	Propane Piping and Valves	4 days										
66	Igniters	5 days										
67	Air Preheat System	4 days										
68	Steam Coil Air Heater Piping	2 days										
69	Steam Coil Drain Pumps	1 day										
70	Steam Coil Drain Tanks	1 day										
71	Condenser Air Extraction System	7 days										
72	Vacuum Pumps	4 days										
73	Vacuum Priming Pump	1 day										
74	Vacuum Pump Piping	2 days										
75	Turbine Seals and Drains	4 days										
76	Piping	4 days										
77	Turbine Lube Oil System	15 days										
78	Turbine Lube Oil Tank	9 days										
79	Turbine Lube Oil Pumps	4 days										
80	Turbine Oil Mist Eliminator	2 days										
81	Generator Auxiliary Systems	14 days										
82	Hydrogen Cooler Skid and Piping	3 days										
83	Stator Cooling Water Skid and Piping	3 days										
84	Isophase Bus Duct	4 days										
85	Exciter Heat Exchanger	2 days										
86	EHC Coolers	2 days										
87	Chemical Feed Systems	8 days										
88	Tanks	2 days										
89	Pumps	3 days										
90	Piping	3 days										
91	Sampling Systems	7 days										
92	Field Mounted Heat Exchangers	2 days										
93	Piping	3 days										
94	Sample Panel	2 days										

Sibley Unit 3 Dismantlement

ID	Task Name	Duration	2012		2013		2014		2015		2016
			H2	H1	H2	H1	H2	H1	H2	H1	H2
95	Building Heating Systems	14 days									
96	Steam Unit Heaters	10 days									
97	Steam Piping	4 days									
98	Compressed Air System	15 days									
99	Air Compressors	4 days									
100	Air Drying Equipment	3 days									
101	Air Reciever Tanks	3 days									
102	Compressed Air Piping	5 days									
103	Miscellaneous Equipment	12 days									
104	Miscellaneous Equipment (including Fire Protec	12 days									
105	Phase 2 Demolition	332 days									
106	Precipitator	30 days									
107	Remove Precipitator	30 days									
108	Boiler Equipment	152 days									
109	Fans	15 days									
110	Bottom Ash	6 days									
111	Air Heater	40 days									
112	Steam Drum	20 days									
113	Coal Bunkers	20 days									
114	Soot Blowers	8 days									
115	Ductwork	28 days									
116	SCR	15 days									
117	Boiler Removal	46 days									
118	Furnace	25 days									
119	Back Pass	21 days									
120	Boiler Steel Framing	86 days									
121	Hanger Girders at Top	15 days									
122	All Other Framing	40 days									
123	Bracing and Girts	20 days									
124	Columns	11 days									
125	Boiler Foundations	18 days									
126	Equipment Foundation Demolition to Grade	18 days									

Crew 1-2 Laborer[600%],Crew 1-2 Operat

Sibley Unit 3 Dismantlement

ID	Task Name	Duration	2012		2013		2014		2015		2016
			H2	H1	H2	H1	H2	H1	H2	H1	H1
127	Remove Turbine	275 days									
128	Remove HP Turbine	10 days									
129	Remove IP Turbine	10 days									
130	Remove LP Turbine	10 days									
131	Remove Generator	15 days									
132	Remove Condenser Neck Heat Exchanger	5 days									
133	Remove Condenser	10 days									
134	Remove Misc. Auxiliary Turbine Equipment	15 days									
135	Turbine Pedestal Demolition to Grade	75 days									
136	Top Slab and Beams	30 days									
137	Columns	45 days									
138	Remove Turbine Building	125 days									
139	Siding and Roofing	35 days									
140	All Framing Elevations	50 days									
141	Bracing and Girts	20 days									
142	Columns	20 days									
143	Phase 3 Demolition	46 days									
144	Yard Demolition	46 days									
145	Remove Ash Handling Equipment and Piping	30 days									
146	Slag Tank	10 days									
147	Hydrovayer Pumps	5 days									
148	Slag Tank Pumps	2 days									
149	Hydrovayer Fly Ash System	5 days									
150	Vacuum Filter System	3 days									
151	Remove Slag Transport System Piping and Misc. Equipment	10 days									
152	Remove Fuel Yard Equipment	11 days									
153	Remove Conveyor 10	5 days									
154	Remove Conveyor 10A	2 days									
155	Remove Conveyor 10AA	2 days									
156	Remove Conveyor 10AB	2 days									
157	Remove Condensate Storage Tanks (2)	5 days									

Yard Crew Operator, Yard Crew Laborer[300%]
 Yard Crew Operator, Yard Crew Laborer[300%]
 Yard Crew Operator, Yard Crew Laborer[300%]

Sibley Unit 3 Dismantlement

ID	Task Name	Duration	2012			2013		2014		2015		2016
			H2	H1	H2	H1	H2	H1	H2	H1	H2	H1
158	Project Close-Out	30 days										
159	Project Close-Out Activities	30 days										

--	--	--	--	--	--	--	--	--	--	--	--	--

... ..

... ..

... ..

... ..

COMMON

... ..

... ..

... ..

... ..

... ..

... ..

... ..

... ..

... ..

... ..

... ..

... ..

Sibley Common Retirement

Owner Costs

Pre-Retirement Activities	\$52,488
Retirement Activities	\$326,401
Post-Retirement Activities	\$26,224

Owner Direct Total \$405,113

Owner Internal Costs 5.00% \$20,256

Owner Contingency: 25.00% \$106,342

Sibley Common Retirement Opinion of Probable Cost: \$531,710.81

Activities Required by Permit or Regulation

Propane Storage Tanks	\$32,531
Units 1 & 2 River Intake	\$592,147
Unit 3 River Intake	\$592,147
Landfill Stage A	\$1,150,440
Sibley Landfill Post Closure	\$2,082,900
Sibley Ash Pond Closure	\$9,500,800

Activities Required by Permit or Regulation: \$13,950,965

Sibley Common Retirement		
ID	Task Name	Cost
1	Sibley Common Retirement	\$405,075.52
2	Pre-Retirement Activities	\$52,448.80
3	Permitting Review	\$26,224.40
4	Develop Detailed Retirement Plan	\$26,224.40
5	Overheads	\$170,845.92
6	Retirement Overheads	\$149,434.08
7	Added Overhead Staff for Common Retirement	\$149,434.08
8	Common Removal Equipment Rental	\$21,411.84
9	Common Removal Equipment Rental	\$21,411.84
10	Retirement Activities	\$155,556.40
11	Administration/Service Building	\$9,342.40
12	Secure Administration/Service Building	\$9,342.40
13	Fuel Yard Office Building	\$5,605.44
14	Secure Fuel Yard Office Building	\$5,605.44
15	Temporary Service Building	\$1,868.48
16	Secure Temporary Service Building	\$1,868.48
17	Warehouse	\$5,605.44
18	Secure Warehouse and Middle Warehouse	\$5,605.44
19	Tractor Shed	\$4,630.24
20	Secure Tractor Shed	\$4,630.24
21	Out Buildings	\$3,736.96
22	Secure the Insulators Shack and Hedrick Hall	\$3,736.96
23	Fuel Yard	\$72,354.40
24	Empty Rotary Car Dumper and Clean (Area A)	\$2,941.36
25	Empty Sample House and Clean (Area B)	\$3,784.08
26	Empty Transfer Hoppers and Clean Transfer House 1 (Area D)	\$3,784.08
27	Empty and Clean the Bituminous Stackout Reclaim (Area C)	\$3,784.08
28	Empty and Clean the Sub-Bituminous Stackout/Reclaim (Area E)	\$3,784.08
29	Empty Transfer Hoppers and Clean Transfer House 2 (Area F)	\$3,784.08
30	Empty Transfer Hoppers and Clean the New Crusher House (Area G)	\$3,784.08
31	Empty and Clean the Blended Stackout/Reclaim (Area H)	\$3,784.08
32	Empty and Clean the Old Crusher House (Area I)	\$3,784.08
33	Empty and Clean Silo E	\$2,941.36
34	Empty Transfer Hoppers and Clean Transfer House (Area J)	\$3,784.08
35	Conveyors	\$20,181.76
36	Clean Conveyors - 5, 5A, 6, 6A, 16, 17, 7W, 7E, 7, 18, 18S, 18N, 11, 15, 8, 10C, 9A, 9, 12, 12A, 13, 14, 14A, 3 and 3A	\$20,181.76
37	Remove Bags and Clean Dust Collectors	\$5,926.40
38	Clean and Secure Miscellaneous Fuel Yard Equipment and clean laydown yards	\$6,306.80
39	Nox Out Ultra System	\$17,861.28
40	Drain and clean Tank 1100, 1200 and 1300	\$3,784.08
41	Drain and clean the Solutionizing Tank	\$3,784.08

Sibley Common Retirement		
ID	Task Name	Cost
42	Drain and clean the equipment in the HFD Enclosure	\$3,859.92
43	Open, clean and vent the equipment and piping by the MDM building	\$6,433.20
44	Intake Structures and Intake Chemical Feed System	\$842.72
45	Remove Chemicals	\$842.72
46	Underground Circulating Water Piping	\$3,849.60
47	Drain the Underground Circulating Water Piping	\$3,849.60
48	Sewage Treatment	\$4,202.72
49	Clean the Sewage Treatment Facility	\$4,202.72
50	Water Treatment	\$21,443.12
51	Drain and clean clarifier	\$2,522.72
52	Empty, clean and vent gravity filters	\$2,522.72
53	Open and vent storage tanks	\$1,261.36
54	Empty, clean and vent carbon filters	\$3,784.08
55	Remove RO membranes and open membrane housings	\$1,261.36
56	Remove demineralizer resins, clean and vent vessels	\$5,045.44
57	Remove chemicals and flush storage tanks	\$2,522.72
58	Flush and vent all water treatment piping.	\$2,522.72
59	Fuel Storage	\$3,370.88
60	Remove propane from propane storage tanks and vent.	\$842.72
61	Vent propane piping and vaporizer.	\$842.72
62	Drain and vent the Diesel Fuel Tank	\$1,685.44
63	Unit 3 Diesel Generator	\$842.72
64	Drain and vent diesel generator tank	\$842.72
65	Post Retirement Closure Activities	\$26,224.40
66	Post Retirement Closure Activities	\$26,224.40

Sibley Common Retirement


ID	Task Name	Duration	1st Quarter			2nd Quarter			3rd Quarter		
			Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug
1	Sibley Common Retirement	162 days	[Gantt bar spanning Dec to Aug]								
2	Pre-Retirement Activities	40 days	[Gantt bar spanning Dec to Feb]								
3	Permitting Review	20 days	[Gantt bar spanning Dec to Jan]								
4	Develop Detailed Retirement Plan	20 days	[Gantt bar spanning Jan to Feb]								
5	Overheads	102 days	[Gantt bar spanning Feb to Mar]								
6	Retirement Overheads	102 days	[Gantt bar spanning Feb to Mar]								
7	Added Overhead Staff for Common Retirement	102 days	[Gantt bar spanning Feb to Mar]								
8	Common Removal Equipment Rental	102 days	[Gantt bar spanning Feb to Mar]								
9	Common Removal Equipment Rental	102 days	[Gantt bar spanning Feb to Mar]								
10	Retirement Activities	102 days	[Gantt bar spanning Feb to Mar]								
11	Administration/Service Building	5 days	[Gantt bar spanning Mar to Apr]								
12	Secure Administration/Service Building	5 days	[Gantt bar spanning Mar to Apr]								
13	Fuel Yard Office Building	3 days	[Gantt bar spanning Mar to Apr]								
14	Secure Fuel Yard Office Building	3 days	[Gantt bar spanning Mar to Apr]								
15	Temporary Service Building	1 day	[Gantt bar spanning Mar to Apr]								
16	Secure Temporary Service Building	1 day	[Gantt bar spanning Mar to Apr]								
17	Warehouse	3 days	[Gantt bar spanning Mar to Apr]								
18	Secure Warehouse and Middle Warehouse	3 days	[Gantt bar spanning Mar to Apr]								
19	Tractor Shed	2 days	[Gantt bar spanning Mar to Apr]								
20	Secure Tractor Shed	2 days	[Gantt bar spanning Mar to Apr]								
21	Out Buildings	2 days	[Gantt bar spanning Mar to Apr]								
22	Secure the Insulators Shack and Hedrick Hall	2 days	[Gantt bar spanning Mar to Apr]								
23	Fuel Yard	58 days	[Gantt bar spanning Apr to Jun]								
24	Empty Rotary Car Dumper and Clean (Area A)	3 days	[Gantt bar spanning Apr to May]								
25	Empty Sample House and Clean (Area B)	3 days	[Gantt bar spanning Apr to May]								
26	Empty Transfer Hoppers and Clean Transfer House 1 (Area D)	3 days	[Gantt bar spanning Apr to May]								
27	Empty and Clean the Bituminous Stackout Reclaim (Area C)	3 days	[Gantt bar spanning Apr to May]								
28	Empty and Clean the Sub-Bituminous Stackout/Reclaim (Area E)	3 days	[Gantt bar spanning Apr to May]								

Sibley Common Retirement

ID	Task Name	Duration	1st Quarter			2nd Quarter			3rd Quarter			
			Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	
29	Empty Transfer Hoppers and Clean Transfer House 2 (Area F)	3 days										
30	Empty Transfer Hoppers and Clean the New Crusher House (Area G)	3 days										
31	Empty and Clean the Blended Stackout/Reclaim (Area H)	3 days										
32	Empty and Clean the Old Crusher House (Area I)	3 days										
33	Empty and Clean Silo E	3 days										
34	Empty Transfer Hoppers and Clean Transfer House (Area J)	3 days										
35	Conveyors	16 days										
36	Clean Conveyors - 5, 5A, 6, 6A, 16, 17, 7W, 7E, 7, 18, 18S, 18N, 11, 15, 8, 10C, 9A, 9, 12, 12A, 13, 14, 14A, 3 and 3A	16 days										
37	Remove Bags and Clean Dust Collectors	4 days										
38	Clean and Secure Miscellaneous Fuel Yard Equipment and clean laydown yards	5 days										
39	Nox Out Ultra System	14 days										
40	Drain and clean Tank 1100, 1200 and 1300	3 days										
41	Drain and clean the Solutionizing Tank	3 days										
42	Drain and clean the equipment in the HFD Enclosure	3 days										
43	Open, clean and vent the equipment and piping by the MDM building	5 days										
44	Intake Structures and Intake Chemical Feed System	1 day										
45	Remove Chemicals	1 day										
46	Underground Circulating Water Piping	3 days										
47	Drain the Underground Circulating Water Piping	3 days										
48	Sewage Treatment	4 days										
49	Clean the Sewage Treatment Facility	4 days										
50	Water Treatment	17 days										

Sibley Common Retirement

ID	Task Name	Duration	1st Quarter			2nd Quarter			3rd Quarter		
			Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug
51	Drain and clean clarifier	2 days									
52	Empty, clean and vent gravity filters	2 days									
53	Open and vent storage tanks	1 day									
54	Empty, clean and vent carbon filters	3 days									
55	Remove RO membranes and open membrane housings	1 day									
56	Remove demineralizer resins, clean and vent vessels	4 days									
57	Remove chemicals and flush storage tanks	2 days									
58	Flush and vent all water treatment piping.	2 days									
59	Fuel Storage	4 days									
60	Remove propane from propane storage tanks and vent.	1 day									
61	Vent propane piping and vaporizer.	1 day									
62	Drain and vent the Diesel Fuel Tank	2 days									
63	Unit 3 Diesel Generator	1 day									
64	Drain and vent diesel generator tank	1 day									
65	Post Retirement Closure Activities	20 days									
66	Post Retirement Closure Activities	20 days									



Sibley Common Dismantlement

Owner Additional Costs

Pre-Dismantlement Activities		\$0
Overhead During Dismantlement		\$0

Owner Costs Total* \$0

Demolition General Contractor (DGC) Costs

Additional Site Management		\$123,085
Equipment Rental		\$600,070
Consummables		\$899,049
Scrap Crew(s)		\$892,097
Dismantlement		\$3,939,133
Contractor Direct Cost*	\$6,453,434	

Contractor Allowances

DGC Insurance	2.00%	\$129,069
Contingency/Profit	15.00%	\$987,375
Performance Bond	2.00%	\$151,398

Contractor Costs Total: \$7,721,276

Total: \$7,721,276

Owner Internal Costs: 5.00% \$386,064

Owner Contingency: 25.00% \$2,026,835

Sibley Common Dismantlement Opinion of Probable Cost: \$10,134,174

*Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances
= \$6,453,434

Sibley Common Dismantlement

ID	Task Name	Cost
1	Sibley Common Dismantlement	\$6,453,436.08
2	Overheads	\$2,514,302.40
3	Common Removal Overheads	\$123,085.68
4	Added Overhead Staff for Common Removals	\$123,085.68
5	Common Removal Equipment Rental	\$600,070.08
6	Common Removal Equipment Rental	\$600,070.08
7	Demolition Contractor Consummables	\$899,049.36
8	Consummables	\$899,049.36
9	Scrap Crew	\$892,097.28
10	Crew(s) to Handle Scrap Material	\$892,097.28
11	Dismantlement Activities	\$3,939,133.68
12	Administration/Service Building	\$53,740.80
13	Remove Administration/Service Building	\$53,740.80
14	Fuel Yard Office Building	\$17,913.60
15	Remove Fuel Yard Office Building	\$17,913.60
16	Temporary Service Building	\$7,165.44
17	Remove Temporary Service Building	\$7,165.44
18	Parking Lots and Plant Roads	\$64,488.96
19	Plant Roads and Parking Areas	\$53,740.80
20	Guard Shack	\$10,748.16
21	Warehouse(s)	\$35,827.20
22	Remove Main Warehouse	\$21,496.32
23	Remove Middle Warehouse	\$14,330.88
24	Tractor Shed	\$14,330.88
25	Remove Tractor Shed	\$14,330.88
26	Out Buildings	\$11,607.60
27	Remove Insulators Shack	\$4,643.04
28	Remove Hedrick Hall	\$6,964.56
29	Fuel Equipment	\$25,536.72
30	Remove Propane Tanks and above ground piping	\$11,607.60
31	Remove Vaporizer	\$9,286.08
32	Remove Diesel Generator Tank	\$4,643.04
33	Fuel Yard	\$302,143.44
34	Remove Rotary Car Dumper	\$23,215.20
35	Remove Sample House	\$23,215.20
36	Remove Transfer Hoppers	\$11,607.60
37	Remove Bituminous Stackout Reclaim	\$16,250.64
38	Remove Sub-Bituminous Stackout/Reclaim	\$16,250.64
39	Remove Transfer House 2	\$13,929.12
40	Remove New Crusher House	\$34,822.80
41	Remove the Blended Stackout/Reclaim	\$16,250.64
42	Remove Old Crusher House	\$27,858.24
43	Remove Transfer House	\$13,929.12
44	Conveyors	\$46,430.40

Sibley Common Dismantlement


ID	Task Name	Cost
45	Remove Conveyors - 5, 5A, 6, 6A, 16, 17, 7W, 7E, 7, 18, 18S, 18N ,1	\$46,430.40
46	Remove Dust Collectors	\$4,643.04
47	Remove Miscellaneous Fuel Yard Equipment	\$53,740.80
48	Nox Out Ultra System	\$18,572.16
49	Remove Tank 1100, 1200 and 1300	\$4,643.04
50	Remove Solutionizing Tank	\$4,643.04
51	Remove HFD Enclosure	\$6,964.56
52	Remove miscellaneous piping and steel.	\$2,321.52
53	Underground Circulating Water Piping	\$53,740.80
54	Excavate Underground Circulating Water Piping	\$17,913.60
55	Collapse Underground Circulating Water Piping	\$10,748.16
56	Backfill and Compact Over Circulating Water Piping	\$25,079.04
57	Sewage Treatment	\$21,496.32
58	Remove Sewage Treatment Pumps and Miscellaneous Equipment	\$7,165.44
59	Remove Sewage Treatment Concrete Structures	\$14,330.88
60	Yard Fire Water Systems	\$21,496.32
61	Remove Hydrants and Fire Water System Piping Down to 3' Below Grade	\$21,496.32
62	Water Treatment	\$46,430.40
63	Remove clarifier	\$4,643.04
64	Remove gravity filters	\$4,643.04
65	Remove storage tanks	\$9,286.08
66	Remove carbon filters	\$4,643.04
67	Remove RO skids	\$4,643.04
68	Remove demineralizer vessels	\$6,964.56
69	Remove regeneration equipment	\$6,964.56
70	Remove miscellaneous piping and support equipment	\$4,643.04
71	Unit 3 Diesel Generator	\$4,643.04
72	Remove Unit 3 Diesel Generator	\$4,643.04
73	Common Stack	\$3,240,000.00
74	Remove Common Stack to Grade	\$3,240,000.00
75	Final Site Grading and Drainage	\$0.00
76	Final Site Grading and Drainage	\$0.00

Sibley Common Dismantlement

ID	Task Name	Duration	2012				2013		
			Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2
1	Sibley Common Dismantlement	250 days							
2	Overheads	249 days							
3	Common Removal Overheads	249 days							
4	Added Overhead Staff for Common Removals	249 days							
5	Common Removal Equipment Rental	249 days							
6	Common Removal Equipment Rental	249 days							
7	Demolition Contractor Consummables	249 days							
8	Consummables	249 days							
9	Scrap Crew	249 days							
10	Crew(s) to Handle Scrap Material	249 days							
11	Dismantlement Activities	249 days							
12	Administration/Service Building	15 days							
13	Remove Administration/Service Building	15 days							
14	Fuel Yard Office Building	5 days							
15	Remove Fuel Yard Office Building	5 days							
16	Temporary Service Building	2 days							
17	Remove Temporary Service Building	2 days							
18	Parking Lots and Plant Roads	18 days							
19	Plant Roads and Parking Areas	15 days							
20	Guard Shack	3 days							
21	Warehouse(s)	10 days							
22	Remove Main Warehouse	6 days							
23	Remove Middle Warehouse	4 days							
24	Tractor Shed	4 days							
25	Remove Tractor Shed	4 days							
26	Out Buildings	5 days							
27	Remove Insulators Shack	2 days							
28	Remove Hedrick Hall	3 days							
29	Fuel Equipment	11 days							
30	Remove Propane Tanks and above ground piping	5 days							
31	Remove Vaporizer	4 days							
32	Remove Diesel Generator Tank	2 days							

Sibley Common Dismantlement

ID	Task Name	Duration	2012				2013	
			Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1
33	Fuel Yard	122 days						
34	Remove Rotary Car Dumper	10 days						
35	Remove Sample House	10 days						
36	Remove Transfer Hoppers	5 days						
37	Remove Bituminous Stackout Reclaim	7 days						
38	Remove Sub-Bituminous Stackout/Reclaim	7 days						
39	Remove Transfer House 2	6 days						
40	Remove New Crusher House	15 days						
41	Remove the Blended Stackout/Reclaim	7 days						
42	Remove Old Crusher House	12 days						
43	Remove Transfer House	6 days						
44	Conveyors	20 days						
45	Remove Conveyors - 5, 5A, 6, 6A, 16, 17, 7W, 7E, 7, 18, 18S, 18N, 11, 15, 8, 10C, 9A, 9, 12, 12A, 13, 14, 14A, 3 and 3A	20 days						
46	Remove Dust Collectors	2 days						
47	Remove Miscellaneous Fuel Yard Equipment	15 days						
48	Nox Out Ultra System	8 days						
49	Remove Tank 1100, 1200 and 1300	2 days						
50	Remove Solutionizing Tank	2 days						
51	Remove HFD Enclosure	3 days						
52	Remove miscellaneous piping and steel.	1 day						
53	Underground Circulating Water Piping	15 days						
54	Excavate Underground Circulating Water Piping	5 days						
55	Collapse Underground Circulating Water Piping	3 days						
56	Backfill and Compact Over Circulating Water Piping	7 days						
57	Sewage Treatment	6 days						
58	Remove Sewage Treatment Pumps and Miscellaneous Equipment	2 days						



Sibley Common Dismantlement

ID	Task Name	Duration	2012				2013			
			Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	
59	Remove Sewage Treatment Concrete Structures	4 days								
60	Yard Fire Water Systems	6 days								
61	Remove Hydrants and Fire Water System Piping Down to 3' Below Grade	6 days								
62	Water Treatment	20 days								
63	Remove clarifier	2 days								
64	Remove gravity filters	2 days								
65	Remove storage tanks	4 days								
66	Remove carbon filters	2 days								
67	Remove RO skids	2 days								
68	Remove demineralizer vessels	3 days								
69	Remove regeneration equipment	3 days								
70	Remove miscellaneous piping and support equipment	2 days								
71	Unit 3 Diesel Generator	2 days								
72	Remove Unit 3 Diesel Generator	2 days								
73	Common Stack	1 day								
74	Remove Common Stack to Grade	1 day								
75	Final Site Grading and Drainage	1 day								
76	Final Site Grading and Drainage	1 day								

SOUTH HARPER

SOUTH HARPER STATION

The South Harper Generating Station consists of three natural gas-fired combustion turbine generator sets.

Combined, these combustion turbines have an SPP-accredited unit rating of 313.9 MW. South Harper was placed into service in 2005. Each unit is comprised of a Siemens Model 504D5A combustion turbine with a generator step-up transformer and auxiliary power transformer.

The following are the major systems and equipment that were included in the retirement and dismantlement of the South Harper Generating Station.

1. Combustion turbine generator sets and auxiliaries.
2. Generation step-up and auxiliary transformers.
3. Outdoor switchgear.
4. Exhaust stacks.
5. Administration building.
6. Natural gas filtering skid.
7. Flammable material storage building.
8. Service/Instrument air compressors.
9. Waste water tank.

South Harper Retirement

Owner Costs

Pre-Retirement Activities	\$43,834
Retirement Activities	\$219,498
Post-Retirement Activities	\$45,152

Owner Direct Total \$308,484

Owner Internal Costs 5.00% \$15,424

Owner Contingency: 25.00% \$80,977

South Harper Retirement Opinion of Probable Cost: \$404,885.25


South Harper Retirement		
ID	Task Name	Cost
1	South Harper Retirement	\$308,484.94
2	Pre-Retirement Activities	\$43,834.00
3	Permitting Review	\$23,466.00
4	Develop Detailed Retirement Plan	\$20,368.00
5	Retirement	\$219,498.94
6	Project Management During Retirement	\$98,648.46
7	Project Management During Retirement	\$98,648.46
8	Retirement Activities	\$119,567.28
9	Electrical	\$44,664.00
10	Medium and Low Voltage Drawout Switchgear	\$12,505.92
11	De-energize all buses at the source.	\$2,679.84
12	Open all circuit breakers.	\$2,679.84
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	\$2,679.84
14	Verify that the closing/tripping springs are discharged.	\$2,679.84
15	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each breaker cubicle.	\$1,786.56
16	Motor Control Centers	\$6,252.96
17	De-energize all buses at the source.	\$893.28
18	Open all circuit breakers and disconnect switches.	\$2,679.84
19	Remove all fuses in control circuits.	\$2,679.84
20	Low-voltage Switchboards and Panelboards	\$5,359.68
21	De-energize all buses at the source.	\$2,679.84
22	Open all circuit breakers and disconnect switches.	\$2,679.84
23	Oil-Filled Power Transformers	\$9,826.08
24	De-energize all buses at the source.	\$2,679.84
25	Open all circuit breakers and disconnect switches.	\$1,786.56
26	De-energize all buses at the source.	\$2,679.84
27	Open all circuit breakers and disconnect switches.	\$2,679.84
28	Dry-type Power Transformers	\$4,466.40
29	De-energize all transformer primaries and verify that the secondary is de-energized.	\$2,679.84
30	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	\$1,786.56
31	Motors	\$6,252.96
32	De-energize all primary power at the source.	\$1,786.56
33	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	\$1,786.56
34	Drain lube oil system (if applicable) and dispose of oil.	\$2,679.84
35	Administration Building	\$9,342.40
36	Secure the Administration Building	\$9,342.40

South Harper Retirement

ID	Task Name	Cost
37	Flammable Material Storage Building	\$5,605.44
38	Secure the Flammable Material Storage Building	\$5,605.44
39	Fuel Gas System	\$10,783.04
40	Isolate Fuel Gas System	\$3,907.44
41	Vent Fuel Gas Piping and Equipment	\$2,528.16
42	Open and Vent Knock-Out Drum	\$861.84
43	Drain, Open and Vent the Drain Tank	\$861.84
44	Empty the Coalescing Filter	\$1,761.92
45	Open and Vent Equipment on the CT Gas Valve Module	\$861.84
46	Lube Oil Cooling Water System	\$7,756.56
47	Open and Drain the Water Side of the Lube Oil Coolers	\$5,171.04
48	Open and Vent the Coolers and Expansion Tank	\$2,585.52
49	Oily Drain Tank	\$3,954.00
50	Open and Pump Out the Oily Drain Tank	\$3,954.00
51	Wash Water Skid	\$5,171.04
52	Open and Drain the Detergent Tank	\$1,723.68
53	Open and Drain the Demineralized Water Tank	\$1,723.68
54	Empty the Demineralized Water Tank	\$1,723.68
55	Compressed Air	\$3,447.36
56	Empty Dessiccant Air Dryers and Vent	\$1,723.68
57	Open and Vent the Air Receiver	\$1,723.68
58	Miscellaneous Piping	\$7,756.56
59	Open and Vent the Exhaust Frame Cooling Piping	\$2,585.52
60	Open and Vent the CT Air Processing Piping	\$0.00
61	Open and Vent the Inlet Air Heating Piping	\$2,585.52
62	Open and Vent the CT Air Processing Piping	\$2,585.52
63	Fire Protection Piping	\$6,856.48
64	Empty the CO2 Storage Tank	\$5,132.80
65	Open and Vent the Fire Protection Piping	\$1,723.68
66	Lube Oil System	\$11,587.04
67	Empty and Remove from Site the Lubricating Oil	\$6,416.00
68	Drain Lubricating Oil Piping	\$3,447.36
69	Open and Vent Lubricating Oil Piping	\$1,723.68
70	Potable Water	\$2,643.36
71	Disconnect Potable Water at Property Boundary	\$2,643.36
72	Waste Water Tank	\$1,283.20
73	Open, Drain and Vent Waste Water Tank	\$1,283.20
74	Post Retirement Closure Activity	\$45,152.00
75	Post Retirement Closure Activity	\$45,152.00

South Harper Retirement

ID	Task Name	Duration	3rd Quarter			4th Quarter			1st Quarter			2nd Quarter			3rd Qu	
			Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	
1	South Harper Retirement	204 days														
2	Pre-Retirement Activities	40 days														
3	Permitting Review	20 days														
4	Develop Detailed Retirement Plan	20 days														
5	Retirement	124 days														
6	Project Management During Retirement	123 days														
7	Project Management During Retirement	123 days														
8	Retirement Activities	123 days														
9	Electrical	50 days														
10	Medium and Low Voltage Drawout Switchgear	14 days														
11	De-energize all buses at the source.	3 days														
12	Open all circuit breakers.	3 days														
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	3 days														
14	Verify that the closing/tripping springs are discharged.	3 days														
15	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each	2 days														
16	Motor Control Centers	7 days														
17	De-energize all buses at the source.	1 day														
18	Open all circuit breakers and disconnect switches.	3 days														
19	Remove all fuses in control circuits.	3 days														
20	Low-voltage Switchboards and Panelboards	6 days														
21	De-energize all buses at the source.	3 days														
22	Open all circuit breakers and disconnect switches.	3 days														
23	Oil-Filled Power Transformers	11 days														
24	De-energize all buses at the source.	3 days														
25	Open all circuit breakers and disconnect switches.	2 days														




South Harper Retirement

ID	Task Name	Duration	3rd Quarter			4th Quarter			1st Quarter			2nd Quarter			3rd Qu	
			Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	
26	De-energize all buses at the source.	3 days														
27	Open all circuit breakers and disconnect switches.	3 days														
28	Dry-type Power Transformers	5 days														
29	De-energize all transformer primaries and verify that the secondary is de-energized.	3 days														
30	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses	2 days														
31	Motors	7 days														
32	De-energize all primary power at the source.	2 days														
33	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	2 days														
34	Drain lube oil system (if applicable) and dispose of oil.	3 days														
35	Administration Building	5 days														
36	Secure the Administration Building	5 days														
37	Flammable Material Storage Building	3 days														
38	Secure the Flammable Material Storage Building	3 days														
39	Fuel Gas System	11 days														
40	Isolate Fuel Gas System	3 days														
41	Vent Fuel Gas Piping and Equipment	3 days														
42	Open and Vent Knock-Out Drum	1 day														
43	Drain, Open and Vent the Drain Tank	1 day														
44	Empty the Coalescing Filter	2 days														
45	Open and Vent Equipment on the CT Gas Valve Module	1 day														
46	Lube Oil Cooling Water System	9 days														
47	Open and Drain the Water Side of the Lube Oil Coolers	6 days														

South Harper Retirement

ID	Task Name	Duration	3rd Quarter			4th Quarter			1st Quarter			2nd Quarter			3rd Qu					
			Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul					
48	Open and Vent the Coolers and Expansion Ta	3 days																		
49	Oily Drain Tank	3 days																		
50	Open and Pump Out the Oily Drain Tank	3 days																		
51	Wash Water Skid	6 days																		
52	Open and Drain the Detergent Tank	2 days																		
53	Open and Drain the Demineralized Water Tar	2 days																		
54	Empty the Demineralized Water Tank	2 days																		
55	Compressed Air	4 days																		
56	Empty Dessiccant Air Dryers and Vent	2 days																		
57	Open and Vent the Air Reciever	2 days																		
58	Miscellaneous Piping	17 days																		
59	Open and Vent the Exhaust Frame Cooling Pip	3 days																		
60	Open and Vent the CT Air Processing Piping	8 days																		
61	Open and Vent the Inlet Air Heating Piping	3 days																		
62	Open and Vent the CT Air Processing Piping	3 days																		
63	Fire Protection Piping	6 days																		
64	Empty the CO2 Storage Tank	4 days																		
65	Open and Vent the Fire Protection Piping	2 days																		
66	Lube Oil System	9 days																		
67	Empty and Remove from Site the Lubricating	5 days																		
68	Drain Lubricating Oil Piping	4 days																		
69	Open and Vent Lubricating Oil Piping	2 days																		
70	Potable Water	3 days																		
71	Disconnect Potable Water at Property Bound	3 days																		
72	Waste Water Tank	1 day																		
73	Open, Drain and Vent Waste Water Tank	1 day																		
74	Post Retirement Closure Activity	40 days																		
75	Post Retirement Closure Activity	40 days																		



South Harper Dismantlement

Owner Costs

Pre-Dismantlement Activities		\$892,760	
Overhead During Dismantlement		\$1,493,362	
Post-Dismantlement Activities		\$49,140	
Owner Costs Total*			\$2,435,262

Demolition General Contractor (DGC) Costs

Site Management		\$814,043	
Equipment Rental		\$1,386,092	
Consummables		\$138,875	
Scrap Crew(s)		\$364,064	
Dismantlement		\$1,236,894	
Contractor Direct Cost*		\$3,939,968	

Contractor Allowances

DGC Insurance	2.00%	\$78,799	
Contingency/Profit	15.00%	\$602,815	
Performance Bond	2.00%	\$92,431.65	

Contractor Costs Total: \$4,714,014

Total: \$7,149,276

Owner Internal Costs: 5.00% \$357,464

Owner Contingency: 25.00% \$1,876,685

South Harper Dismantlement Opinion of Probable Cost: \$9,383,425

*Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances
= \$6,375,230

South Harper Dismantlement		
ID	Task Name	Cost
1	South Harper CT Dismantlement	\$6,375,218.40
2	Pre-Demolition Activities	\$892,760.32
3	Detailed Planning & Hire Owner's Engineer	\$104,441.28
4	Detailed Site Characterization Study	\$610,335.44
5	Hire Demolition general Contractor	\$167,184.00
6	KCP&L Prepares Unit for Dismantlement	\$10,799.60
7	Demolition Contractor Mobilizes on Site	\$0.00
8	KCP&L Overhead during Dismantlement	\$1,493,362.96
9	KCP&L Project Manager	\$237,306.80
10	KCP&L Administrative Support	\$87,752.96
11	KCP&L Engineer	\$390,047.20
12	Owners Engineer Project Manager	\$116,432.00
13	Owners Engineer - Engineer	\$661,824.00
14	Demolition Contractor Overhead during Dismantlement	\$814,043.52
15	Demolition Contractor Project Manager	\$230,320.88
16	Demolition Contractor Safety Manager	\$205,073.52
17	Demolition Contractor Superintendent	\$378,649.12
18	Demolition Contractor Equipment Rental Cost	\$1,386,092.32
19	Equipment Rental	\$1,386,092.32
20	Demolition Contractor Consumables	\$138,860.48
21	Consumables	\$138,860.48
22	Scrap Crews	\$364,064.48
23	Crew to Handle Scrap Material(s)	\$364,064.48
24	Dismantlement	\$1,236,894.32
25	Electrical	\$197,049.60
26	Electrical Demolition of Equipment	\$197,049.60
27	Fuel Gas System	\$21,113.20
28	Remove all above grade fuel gas piping.	\$6,782.32
29	Gas Filter Skid	\$14,330.88
30	Lube Oil System	\$53,740.80
31	Lube Oil Piping	\$14,330.88
32	Lube Oil Pumps	\$17,913.60
33	Lube Oil Tanks	\$21,496.32
34	Compressed Air System	\$21,496.32
35	Compressed Air Piping	\$10,748.16
36	Compressors	\$5,374.08
37	Air Receiver	\$3,582.72
38	Dryer	\$1,791.36
39	Fire Protection	\$26,870.40
40	Fire Protection Piping	\$19,704.96
41	CO2 Storage Tank	\$7,165.44
42	Wash Water Skid	\$10,748.16
43	Detergent Tank	\$10,748.16
44	Miscellaneous Piping	\$62,697.60

South Harper Dismantlement


ID	Task Name	Cost
45	Exhaust Frame Cooling Piping	\$17,913.60
46	CT Air Processing Piping	\$21,496.32
47	Inlet Air Heating Piping	\$23,287.68
48	Generator	\$0.00
49	Generators	\$0.00
50	Combustion Turbine	\$263,329.92
51	Inlet Heaters	\$17,913.60
52	Inlet ducts	\$26,870.40
53	Exhaust ducts	\$35,827.20
54	Combustion Turbines	\$62,697.60
55	Combustion Turbine Foundations	\$66,280.32
56	Enclosures	\$53,740.80
57	CEMS	\$42,992.64
58	CEMS Building	\$21,496.32
59	CEMS Building Foundation	\$21,496.32
60	Stack	\$80,611.20
61	Stacks	\$80,611.20
62	Buildings	\$23,287.68
63	Remove Administration Building	\$17,913.60
64	Remove Flammable Material Storage Building	\$5,374.08
65	Waste Water Tank	\$8,956.80
66	Remove Waste Water Tank	\$8,956.80
67	Site Prep	\$424,000.00
68	Final Grading and Drainage	\$424,000.00
69	Post Dismantlement Activities	\$49,140.00
70	Post Dismantlement Activities	\$49,140.00

South Harper Dismantlement

ID	Task Name	Duration	2014				2015				2016			
			Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	
1	South Harper CT Dismantlement	678 days												
2	Pre-Demolition Activities	265 days												
3	Detailed Planning & Hire Owner's Engineer	3 mons												
4	Detailed Site Characterization Study	130 days												
5	Hire Demolition general Contractor	3 mons												
6	KCP&L Prepares Unit for Dismantlement	2 wks												
7	Demolition Contractor Mobilizes on Site	5 days												
8	KCP&L Overhead during Dismantlement	383 days												
9	KCP&L Project Manager	383 days												
10	KCP&L Administrative Support	383 days												
11	KCP&L Engineer	383 days												
12	Owners Engineer Project Manager	383 days												
13	Owners Engineer - Engineer	383 days												
14	Demolition Contractor Overhead during Dismantlement	383 days												
15	Demolition Contractor Project Manager	383 days												
16	Demolition Contractor Safety Manager	383 days												
17	Demolition Contractor Superintendent	383 days												
18	Demolition Contractor Equipment Rental Cost	383 days												
19	Equipment Rental	383 days												
20	Demolition Contractor Consumables	383 days												
21	Consumables	383 days												
22	Scrap Crews	383 days												
23	Crew to Handle Scrap Material(s)	383 days												
24	Dismantlement	383 days												
25	Electrical	110 days												
26	Electrical Demolition of Equipment	110 days												
27	Fuel Gas System	20 days												
28	Remove all above grade fuel gas piping.	12 days												
29	Gas Filter Skid	8 days												
30	Lube Oil System	30 days												
31	Lube Oil Piping	8 days												
32	Lube Oil Pumps	10 days												


South Harper Dismantlement

ID	Task Name	Duration	2014				2015				2016			
			Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2			
33	Lube Oil Tanks	12 days												
34	Compressed Air System	12 days												
35	Compressed Air Piping	6 days												
36	Compressors	3 days												
37	Air Receiver	2 days												
38	Dryer	1 day												
39	Fire Protection	15 days												
40	Fire Protection Piping	11 days												
41	CO2 Storage Tank	4 days												
42	Wash Water Skid	6 days												
43	Detergent Tank	6 days												
44	Miscellaneous Piping	35 days												
45	Exhaust Frame Cooling Piping	10 days												
46	CT Air Processing Piping	12 days												
47	Inlet Air Heating Piping	13 days												
48	Generator	29 days												
49	Generators	29 days												
50	Combustion Turbine	147 days												
51	Inlet Heaters	10 days												
52	Inlet ducts	15 days												
53	Exhaust ducts	20 days												
54	Combustion Turbines	35 days												
55	Combustion Turbine Foundations	37 days												
56	Enclosures	30 days												
57	CEMS	24 days												
58	CEMS Building	12 days												
59	CEMS Building Foundation	12 days												
60	Stack	45 days												
61	Stacks	45 days												
62	Buildings	13 days												
63	Remove Administration Building	10 days												
64	Remove Flammable Material Storage Building	3 days												



South Harper Dismantlement

ID	Task Name	Duration	2014				2015				2016			
			Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	
65	Waste Water Tank	5 days												
66	Remove Waste Water Tank	5 days												
67	Site Prep	20 days												
68	Final Grading and Drainage	20 days												
69	Post Dismantlement Activities	30 days												
70	Post Dismantlement Activities	30 days												



GREENWOOD

GREENWOOD STATION

The Greenwood Generating Station consists of four natural gas-fired and distillate-fired combustion turbine generator sets.

Combined, these combustion turbines have an SPP-accredited unit rating of 252.7 MW. Greenwood Units 1 and 2 were placed in service in 1975. Greenwood Unit 3 was placed in service in 1977. Greenwood Unit 4 was placed in service in 1979. Each unit is comprised of a GE Model MA7001B combustion turbine with a generator step-up transformer and auxiliary power transformer.

The following are the major systems and equipment that were included in the retirement and dismantlement of the Greenwood Generating Station.

1. Combustion turbine generator sets and auxiliaries.
2. Generation step-up and auxiliary transformers.
3. Outdoor switchgear.
4. Exhaust stacks.
5. Administration building.
6. Combustion turbine building.
7. Natural gas filtering skid.
8. Water treatment.
9. Service/Instrument air compressors.
10. Diesel generator.
11. Fuel oil storage and transfer equipment.

Greenwood Retirement

Owner Costs

Pre-Retirement Activities	\$43,834
Retirement Activities	\$225,697
Post-Retirement Activities	\$45,152

Owner Direct Total \$314,683

Owner Internal Costs 5.00% \$15,734

Owner Contingency: 25.00% \$82,604

Greenwood Retirement Opinion of Probable Cost: \$413,021.44

Activities Required by Permit or Regulation

Greenwood Storage Tank	\$157,111
Greenwood Storage Tank (2)	\$157,111
Greenwood Storage Tank (3)	\$157,111

Activities Required by Permit or Regulation: \$471,333

Greenwood Retirement		
ID	Task Name	Cost
1	Greenwood Retirement	\$314,683.28
2	Pre-Retirement Activities	\$43,834.00
3	Permitting Review	\$23,466.00
4	Develop Detailed Retirement Plan	\$20,368.00
5	Retirement	\$225,697.28
6	Project Management During Retirement	\$105,866.64
7	Project Management During Retirement	\$105,866.64
8	Retirement Activities	\$119,830.64
9	Electrical	\$44,664.00
10	Medium and Low Voltage Drawout Switchgear	\$12,505.92
11	De-energize all buses at the source.	\$2,679.84
12	Open all circuit breakers.	\$2,679.84
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	\$2,679.84
14	Verify that the closing/tripping springs are discharged.	\$2,679.84
15	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each breaker cubicle.	\$1,786.56
16	Motor Control Centers	\$6,252.96
17	De-energize all buses at the source.	\$893.28
18	Open all circuit breakers and disconnect switches.	\$1,786.56
19	Remove all fuses in control circuits.	\$3,573.12
20	Low-voltage Switchboards and Panelboards	\$5,359.68
21	De-energize all buses at the source.	\$2,679.84
22	Open all circuit breakers and disconnect switches.	\$2,679.84
23	Oil-Filled Power Transformers	\$9,826.08
24	De-energize all buses at the source.	\$2,679.84
25	Open all circuit breakers and disconnect switches.	\$1,786.56
26	De-energize all buses at the source.	\$2,679.84
27	Open all circuit breakers and disconnect switches.	\$2,679.84
28	Dry-type Power Transformers	\$4,466.40
29	De-energize all transformer primaries and verify that the secondary is de-energized.	\$2,679.84
30	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	\$1,786.56
31	Motors	\$6,252.96
32	De-energize all primary power at the source.	\$1,786.56
33	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	\$1,786.56
34	Drain lube oil system (if applicable) and dispose of oil.	\$2,679.84
35	Administration Building	\$7,473.92

Greenwood Retirement

ID	Task Name	Cost
36	Secure the Administration Building/Maintenance Shop	\$7,473.92
37	Combustion Turbine Buildings	\$0.00
38	Secure the Combustion Turbine Buildings	\$0.00
39	Fuel Gas System	\$10,783.04
40	Isolate Fuel Gas System	\$3,907.44
41	Vent Fuel Gas Piping and Equipment	\$2,528.16
42	Open and Vent Knock-Out Drum	\$861.84
43	Drain, Open and Vent the Drain Tank	\$861.84
44	Empty the Coalescing Filter	\$1,761.92
45	Open and Vent Equipment on the CT Gas Valve Module	\$861.84
46	Lube Oil Cooling Water System	\$7,756.56
47	Open and Drain the Water Side of the Lube Oil Coolers	\$5,171.04
48	Open and Vent the Coolers and Expansion Tank	\$2,585.52
49	Oily Drain Tank	\$3,954.00
50	Open and Pump Out the Oily Drain Tank	\$3,954.00
51	Wash Water Skid	\$5,171.04
52	Open and Drain the Detergent Tank	\$1,723.68
53	Open and Drain the Demineralized Water Tank	\$1,723.68
54	Empty the Demineralized Water Tank	\$1,723.68
55	Compressed Air	\$3,447.36
56	Empty Dessiccant Air Dryers and Vent	\$1,723.68
57	Open and Vent the Air Receiver	\$1,723.68
58	Miscellaneous Piping	\$7,756.56
59	Open and Vent the Exhaust Frame Cooling Piping	\$2,585.52
60	Open and Vent the CT Air Processing Piping	\$0.00
61	Open and Vent the Inlet Air Heating Piping	\$2,585.52
62	Open and Vent the CT Air Processing Piping	\$2,585.52
63	Fire Protection Piping	\$6,856.48
64	Empty the CO2 Storage Tank	\$5,132.80
65	Open and Vent the Fire Protection Piping	\$1,723.68
66	Lube Oil System	\$11,587.04
67	Empty and Remove from Site the Lubricating Oil	\$6,416.00
68	Drain Lubricating Oil Piping	\$3,447.36
69	Open and Vent Lubricating Oil Piping	\$1,723.68
70	Fuel Oil Storage and Unloading	\$861.84
71	Remove Fuel Oil from Fuel Oil Storage and Vent	\$861.84
72	Water Treatment	\$7,756.56
73	Drain All Tanks and Vessels	\$1,723.68
74	Remove Resin from Vessels	\$2,585.52
75	Remove Chemicals	\$2,585.52
76	Open and Vent Vessels	\$861.84
77	Diesel Generator	\$0.00
78	Empty and Vent Diesel Generator F.O. Tank	\$0.00
79	Potable Water	\$1,762.24

Greenwood Retirement

ID	Task Name	Cost
80	Disconnect Potable Water at Property Boundary	\$1,762.24
81	Post Retirement Closure Activity	\$45,152.00
82	Post Retirement Closure Activity	\$45,152.00

Greenwood Retirement

ID	Task Name	Duration	1st Quarter			2nd Quarter			3rd Quarter			4th Quarter			1st Quarter			2nd Quarter			3rd Quarter					
			Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep			
1	Greenwood Retirement	212 days	[Gantt bar spanning from Oct to Jul]																							
2	Pre-Retirement Activities	40 days	[Gantt bar spanning from Oct to Nov]																							
3	Permitting Review	20 days	[Gantt bar spanning from Oct to Nov]																							
4	Develop Detailed Retirement Plan	20 days	[Gantt bar spanning from Oct to Nov]																							
5	Retirement	132 days	[Gantt bar spanning from Dec to Jun]																							
6	Project Management During Retirement	132 days	[Gantt bar spanning from Dec to Jun]																							
7	Project Management During Retirement	132 days	[Gantt bar spanning from Dec to Jun]																							
8	Retirement Activities	132 days	[Gantt bar spanning from Dec to Jun]																							
9	Electrical	50 days	[Gantt bar spanning from Dec to Feb]																							
10	Medium and Low Voltage Drawout Switchgear	14 days	[Gantt bar spanning from Dec to Jan]																							
11	De-energize all buses at the source.	3 days	[Gantt bar spanning from Dec to Jan]																							
12	Open all circuit breakers.	3 days	[Gantt bar spanning from Dec to Jan]																							
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	3 days	[Gantt bar spanning from Dec to Jan]																							
14	Verify that the closing/tripping springs are discharged.	3 days	[Gantt bar spanning from Dec to Jan]																							
15	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each	2 days	[Gantt bar spanning from Dec to Jan]																							
16	Motor Control Centers	7 days	[Gantt bar spanning from Dec to Jan]																							
17	De-energize all buses at the source.	1 day	[Gantt bar spanning from Dec to Jan]																							
18	Open all circuit breakers and disconnect switches.	2 days	[Gantt bar spanning from Dec to Jan]																							
19	Remove all fuses in control circuits.	4 days	[Gantt bar spanning from Dec to Jan]																							
20	Low-voltage Switchboards and Panelboards	6 days	[Gantt bar spanning from Dec to Jan]																							
21	De-energize all buses at the source.	3 days	[Gantt bar spanning from Dec to Jan]																							
22	Open all circuit breakers and disconnect switches.	3 days	[Gantt bar spanning from Dec to Jan]																							
23	Oil-Filled Power Transformers	11 days	[Gantt bar spanning from Dec to Jan]																							
24	De-energize all buses at the source.	3 days	[Gantt bar spanning from Dec to Jan]																							
25	Open all circuit breakers and disconnect switches.	2 days	[Gantt bar spanning from Dec to Jan]																							

Greenwood Retirement

ID	Task Name	Duration	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Quarter	2nd Quarter	3rd Quarter											
			Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	
26	De-energize all buses at the source.	3 days																		
27	Open all circuit breakers and disconnect switches.	3 days																		
28	Dry-type Power Transformers	5 days																		
29	De-energize all transformer primaries and verify that the secondary is de-energized.	3 days																		
30	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses	2 days																		
31	Motors	7 days																		
32	De-energize all primary power at the source.	2 days																		
33	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	2 days																		
34	Drain lube oil system (if applicable) and dispose of oil.	3 days																		
35	Administration Building	4 days																		
36	Secure the Administration Building/Maintenance Shop	4 days																		
37	Combustion Turbine Buildings	3 days																		
38	Secure the Combustion Turbine Buildings	3 days																		
39	Fuel Gas System	11 days																		
40	Isolate Fuel Gas System	3 days																		
41	Vent Fuel Gas Piping and Equipment	3 days																		
42	Open and Vent Knock-Out Drum	1 day																		
43	Drain, Open and Vent the Drain Tank	1 day																		
44	Empty the Coalescing Filter	2 days																		
45	Open and Vent Equipment on the CT Gas Valve Module	1 day																		
46	Lube Oil Cooling Water System	9 days																		

Greenwood Retirement

ID	Task Name	Duration	1st Quarter			2nd Quarter			3rd Quarter			4th Quarter					
			Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec			
78	Empty and Vent Diesel Generator F.O. Tank	1 day															
79	Potable Water	2 days															
80	Disconnect Potable Water at Property Bound	2 days															
81	Post Retirement Closure Activity	40 days															
82	Post Retirement Closure Activity	40 days															

Greenwood Dismantlement

Owner Costs

Pre-Dismantlement Activities		\$892,760	
Overhead During Dismantlement		\$1,477,766	
Post-Dismantlement Activities		\$49,140	
Owner Costs Total*			\$2,419,666

Demolition General Contractor (DGC) Costs

Site Management		\$805,541	
Equipment Rental		\$1,371,616	
Consummables		\$1,368,432	
Scrap Crew(s)		\$360,262	
Dismantlement		\$1,117,115	
Contractor Direct Cost*	\$5,022,966		

Contractor Allowances

DGC Insurance	2.00%	\$100,459	
Contingency/Profit	15.00%	\$768,514	
Performance Bond	2.00%	\$117,838.78	

Contractor Costs Total: \$6,009,778

Total:			\$8,429,444
Owner Internal Costs:	5.00%		\$421,472
Owner Contingency:	25.00%		\$2,212,729
Greenwood Dismantlement Opinion of Probable Cost:			\$11,063,645

*Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances
= \$7,442,632

Greenwood Dismantlement		
ID	Task Name	Cost
1	Greenwood Dismantlement	\$7,442,635.44
2	Pre-Demolition Activities	\$892,760.32
3	Detailed Planning & Hire Owner's Engineer	\$104,441.28
4	Detailed Site Characterization Study	\$610,335.44
5	Hire Demolition general Contractor	\$167,184.00
6	KCP&L Prepares Unit for Dismantlement	\$10,799.60
7	Demolition Contractor Mobilizes on Site	\$0.00
8	KCP&L Overhead during Dismantlement	\$1,477,766.48
9	KCP&L Project Manager	\$234,828.40
10	KCP&L Administrative Support	\$86,836.48
11	KCP&L Engineer	\$385,973.60
12	Owners Engineer Project Manager	\$115,216.00
13	Owners Engineer - Engineer	\$654,912.00
14	Demolition Contractor Overhead during Dismantlement	\$805,541.76
15	Demolition Contractor Project Manager	\$227,915.44
16	Demolition Contractor Safety Manager	\$202,931.76
17	Demolition Contractor Superintendent	\$374,694.56
18	Demolition Contractor Equipment Rental Cost	\$1,371,616.16
19	Equipment Rental	\$1,371,616.16
20	Demolition Contractor Consumables	\$1,368,432.56
21	Consumables	\$1,368,432.56
22	Scrap Crews	\$360,262.24
23	Crew to Handle Scrap Material(s)	\$360,262.24
24	Dismantlement	\$1,117,115.92
25	Electrical	\$197,049.60
26	Electrical Demolition of Equipment	\$197,049.60
27	Fuel Gas System	\$17,932.24
28	Remove all above grade fuel gas piping.	\$3,601.36
29	Gas Filter Skid	\$14,330.88
30	Fueil Oil System	\$17,913.60
31	Remove above grade fuel oil piping	\$12,539.52
32	Remove fuel oil forwarding equipment	\$5,374.08
33	Remove fuel oil forwarding building	\$0.00
34	Demineralizer	\$17,913.60
35	Remove demineralizer vessels	\$3,582.72
36	Remove acid and caustic tanks	\$7,165.44
37	Remove hot water tank	\$3,582.72
38	Remove misc. demineralizer piping.	\$3,582.72
39	Lube Oil System	\$53,740.80
40	Lube Oil Piping	\$14,330.88
41	Lube Oil Pumps	\$17,913.60
42	Lube Oil Tanks	\$21,496.32
43	Compressed Air System	\$21,496.32
44	Compressed Air Piping	\$10,748.16

Greenwood Dismantlement


ID	Task Name	Cost
45	Compressors	\$5,374.08
46	Air Receiver	\$3,582.72
47	Dryer	\$1,791.36
48	Fire Protection	\$26,870.40
49	Fire Protection Piping	\$19,704.96
50	CO2 Storage Tank	\$7,165.44
51	Wash Water Skid	\$10,748.16
52	Detergent Tank	\$10,748.16
53	Miscellaneous Piping	\$62,697.60
54	Exhaust Frame Cooling Piping	\$17,913.60
55	CT Air Processing Piping	\$21,496.32
56	Inlet Air Heating Piping	\$23,287.68
57	Generator	\$51,949.44
58	Generators	\$51,949.44
59	Combustion Turbine	\$263,329.92
60	Inlet Heaters	\$17,913.60
61	Inlet ducts	\$26,870.40
62	Exhaust ducts	\$35,827.20
63	Combustion Turbines	\$62,697.60
64	Combustion Turbine Foundations	\$66,280.32
65	Enclosures	\$53,740.80
66	Diesel Generator	\$3,582.72
67	Remove diesel generator	\$3,582.72
68	CEMS	\$42,992.64
69	CEMS Building	\$21,496.32
70	CEMS Building Foundation	\$21,496.32
71	Stack	\$80,611.20
72	Stacks	\$80,611.20
73	Buildings	\$23,287.68
74	Remove Administration/Maintenance Building	\$17,913.60
75	Remove CT Buildings including gantry crane	\$5,374.08
76	Site Prep	\$225,000.00
77	Final Grading and Drainage	\$225,000.00
78	Post Dismantlement Activities	\$49,140.00
79	Post Dismantlement Activities	\$49,140.00

Greenwood Dismantlement

ID	Task Name	Duration	2014				2015				2016	
			Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	
1	Greenwood Dismantlement	674 days										
2	Pre-Demolition Activities	265 days										
3	Detailed Planning & Hire Owner's Engineer	3 mons										
4	Detailed Site Characterization Study	130 days										
5	Hire Demolition general Contractor	3 mons										
6	KCP&L Prepares Unit for Dismantlement	2 wks										
7	Demolition Contractor Mobilizes on Site	5 days										
8	KCP&L Overhead during Dismantlement	379 days										
9	KCP&L Project Manager	379 days										
10	KCP&L Administrative Support	379 days										
11	KCP&L Engineer	379 days										
12	Owners Engineer Project Manager	379 days										
13	Owners Engineer - Engineer	379 days										
14	Demolition Contractor Overhead during Dismantlement	379 days										
15	Demolition Contractor Project Manager	379 days										
16	Demolition Contractor Safety Manager	379 days										
17	Demolition Contractor Superintendent	379 days										
18	Demolition Contractor Equipment Rental Cost	379 days										
19	Equipment Rental	379 days										
20	Demolition Contractor Consumables	379 days										
21	Consumables	379 days										
22	Scrap Crews	379 days										
23	Crew to Handle Scrap Material(s)	379 days										
24	Dismantlement	379 days										
25	Electrical	110 days										
26	Electrical Demolition of Equipment	110 days										
27	Fuel Gas System	14 days										
28	Remove all above grade fuel gas piping.	6 days										
29	Gas Filter Skid	8 days										
30	Fueil Oil System	13 days										
31	Remove above grade fuel oil piping	7 days										
32	Remove fuel oil forwarding equipment	3 days										


Greenwood Dismantlement

ID	Task Name	Duration	2014				2015				2016			
			Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2			
33	Remove fuel oil forwarding building	3 days												
34	Demineralizer	10 days												
35	Remove demineralizer vessels	2 days												
36	Remove acid and caustic tanks	4 days												
37	Remove hot water tank	2 days												
38	Remove misc. demineralizer piping.	2 days												
39	Lube Oil System	30 days												
40	Lube Oil Piping	8 days												
41	Lube Oil Pumps	10 days												
42	Lube Oil Tanks	12 days												
43	Compressed Air System	12 days												
44	Compressed Air Piping	6 days												
45	Compressors	3 days												
46	Air Receiver	2 days												
47	Dryer	1 day												
48	Fire Protection	15 days												
49	Fire Protection Piping	11 days												
50	CO2 Storage Tank	4 days												
51	Wash Water Skid	6 days												
52	Detergent Tank	6 days												
53	Miscellaneous Piping	35 days												
54	Exhaust Frame Cooling Piping	10 days												
55	CT Air Processing Piping	12 days												
56	Inlet Air Heating Piping	13 days												
57	Generator	29 days												
58	Generators	29 days												
59	Combustion Turbine	147 days												
60	Inlet Heaters	10 days												
61	Inlet ducts	15 days												
62	Exhaust ducts	20 days												
63	Combustion Turbines	35 days												
64	Combustion Turbine Foundations	37 days												



Greenwood Dismantlement

ID	Task Name	Duration	2014				2015				2016			
			Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2			
65	Enclosures	30 days												
66	Diesel Generator	2 days												
67	Remove diesel generator	2 days												
68	CEMS	24 days												
69	CEMS Building	12 days												
70	CEMS Building Foundation	12 days												
71	Stack	45 days												
72	Stacks	45 days												
73	Buildings	13 days												
74	Remove Administration/Maintenance Building	10 days												
75	Remove CT Buildings including gantry crane	3 days												
76	Site Prep	20 days												
77	Final Grading and Drainage	20 days												
78	Post Dismantlement Activities	30 days												
79	Post Dismantlement Activities	30 days												



CROSSROADS

CROSSROADS STATION

The Crossroads Generating Station consists of four natural gas-fired combustion turbine generator sets.

Combined, these combustion turbines have an SPP-accredited unit rating of 276.8 MW. Crossroads was placed into service in 2002. Each unit is comprised of a GE Model MS7001EA combustion turbine with a generator step-up transformer and auxiliary power transformer.

The following are the major systems and equipment that were included in the retirement and dismantlement of the Crossroads Generating Station.

1. Combustion turbine generator sets and auxiliaries.
2. Generation step-up and auxiliary transformers.
3. Outdoor switchgear.
4. Exhaust stacks.
5. Maintenance building.
6. Natural gas filtering skid.
7. Service/Instrument air compressors.

Crossroads Retirement

Owner Costs

Pre-Retirement Activities	\$43,834
Retirement Activities	\$215,997
Post-Retirement Activities	\$45,162

Owner Direct Total \$304,993

Owner Internal Costs 5.00% \$15,250

Owner Contingency: 25.00% \$80,061

Crossroads Retirement Opinion of Probable Cost: \$400,303.31


Crossroads Retirement		
ID	Task Name	Cost
1	Crossroads Retirement	\$304,983.84
2	Pre-Retirement Activities	\$43,834.00
3	Permitting Review	\$23,466.00
4	Develop Detailed Retirement Plan	\$20,368.00
5	Retirement	\$215,997.84
6	Project Management During Retirement	\$99,450.48
7	Project Management During Retirement	\$99,450.48
8	Retirement Activities	\$116,547.36
9	Electrical	\$44,664.00
10	Medium and Low Voltage Drawout Switchgear	\$12,505.92
11	De-energize all buses at the source.	\$2,679.84
12	Open all circuit breakers.	\$2,679.84
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	\$2,679.84
14	Verify that the closing/tripping springs are discharged.	\$2,679.84
15	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each breaker cubicle.	\$1,786.56
16	Motor Control Centers	\$6,252.96
17	De-energize all buses at the source.	\$893.28
18	Open all circuit breakers and disconnect switches.	\$2,679.84
19	Remove all fuses in control circuits.	\$2,679.84
20	Low-voltage Switchboards and Panelboards	\$5,359.68
21	De-energize all buses at the source.	\$2,679.84
22	Open all circuit breakers and disconnect switches.	\$2,679.84
23	Oil-Filled Power Transformers	\$9,826.08
24	De-energize all buses at the source.	\$2,679.84
25	Open all circuit breakers and disconnect switches.	\$1,786.56
26	De-energize all buses at the source.	\$2,679.84
27	Open all circuit breakers and disconnect switches.	\$2,679.84
28	Dry-type Power Transformers	\$4,466.40
29	De-energize all transformer primaries and verify that the secondary is de-energized.	\$2,679.84
30	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	\$1,786.56
31	Motors	\$6,252.96
32	De-energize all primary power at the source.	\$1,786.56
33	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	\$1,786.56
34	Drain lube oil system (if applicable) and dispose of oil.	\$2,679.84
35	Maintenance Building	\$9,342.40

Crossroads Retirement

ID	Task Name	Cost
36	Secure the Maintenance Building	\$9,342.40
37	Fuel Gas System	\$10,783.04
38	Isolate Fuel Gas System	\$3,907.44
39	Vent Fuel Gas Piping and Equipment	\$2,528.16
40	Open and Vent Knock-Out Drum	\$861.84
41	Drain, Open and Vent the Drain Tank	\$861.84
42	Empty the Coalescing Filter	\$1,761.92
43	Open and Vent Equipment on the CT Gas Valve Module	\$861.84
44	Lube Oil Cooling Water System	\$7,756.56
45	Open and Drain the Water Side of the Lube Oil Coolers	\$5,171.04
46	Open and Vent the Coolers and Expansion Tank	\$2,585.52
47	Oily Drain Tank	\$3,954.00
48	Open and Pump Out the Oily Drain Tank	\$3,954.00
49	Wash Water Skid	\$5,171.04
50	Open and Drain the Detergent Tank	\$1,723.68
51	Open and Drain the Demineralized Water Tank	\$1,723.68
52	Empty the Demineralized Water Tank	\$1,723.68
53	Compressed Air	\$3,447.36
54	Empty Dessiccant Air Dryers and Vent	\$1,723.68
55	Open and Vent the Air Reciever	\$1,723.68
56	Miscellaneous Piping	\$10,342.08
57	Open and Vent the Exhaust Frame Cooling Piping	\$3,447.36
58	Open and Vent the CT Air Processing Piping	\$0.00
59	Open and Vent the Inlet Air Heating Piping	\$3,447.36
60	Open and Vent the CT Air Processing Piping	\$3,447.36
61	Fire Protection Piping	\$6,856.48
62	Empty the CO2 Storage Tank	\$5,132.80
63	Open and Vent the Fire Protection Piping	\$1,723.68
64	Lube Oil System	\$11,587.04
65	Empty and Remove from Site the Lubricating Oil	\$6,416.00
66	Drain Lubricating Oil Piping	\$3,447.36
67	Open and Vent Lubricating Oil Piping	\$1,723.68
68	Potable Water	\$2,643.36
69	Disconnect Potable Water at Property Boundary	\$2,643.36
70	Post Retirement Closure Activity	\$45,152.00
71	Post Retirement Closure Activity	\$45,152.00

Crossroads Retirement

ID	Task Name	Duration	2nd Quarter			3rd Quarter			4th Quarter			1st Quarter			2nd Quarter			3rd Q
			Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul
1	Crossroads Retirement	204 days																
2	Pre-Retirement Activities	40 days																
3	Permitting Review	20 days																
4	Develop Detailed Retirement Plan	20 days																
5	Retirement	124 days																
6	Project Management During Retirement	124 days																
7	Project Management During Retirement	124 days																
8	Retirement Activities	124 days																
9	Electrical	50 days																
10	Medium and Low Voltage Drawout Switchgear	14 days																
11	De-energize all buses at the source.	3 days																
12	Open all circuit breakers.	3 days																
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	3 days																
14	Verify that the closing/tripping springs are discharged.	3 days																
15	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each	2 days																
16	Motor Control Centers	7 days																
17	De-energize all buses at the source.	1 day																
18	Open all circuit breakers and disconnect switches.	3 days																
19	Remove all fuses in control circuits.	3 days																
20	Low-voltage Switchboards and Panelboards	6 days																
21	De-energize all buses at the source.	3 days																
22	Open all circuit breakers and disconnect switches.	3 days																
23	Oil-Filled Power Transformers	11 days																
24	De-energize all buses at the source.	3 days																
25	Open all circuit breakers and disconnect switches.	2 days																




Crossroads Retirement

ID	Task Name	Duration	2nd Quarter			3rd Quarter			4th Quarter			1st Quarter			2nd Quarter			3rd Q
			Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul
26	De-energize all buses at the source.	3 days										▶						
27	Open all circuit breakers and disconnect switches.	3 days										▶						
28	Dry-type Power Transformers	5 days											▶					
29	De-energize all transformer primaries and verify that the secondary is de-energized.	3 days										▶						
30	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses	2 days										▶						
31	Motors	7 days											▶					
32	De-energize all primary power at the source.	2 days											▶					
33	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	2 days											▶					
34	Drain lube oil system (if applicable) and dispose of oil.	3 days												▶				
35	Maintenance Building	5 days													▶			
36	Secure the Maintenance Building	5 days														▶		
37	Fuel Gas System	11 days															▶	
38	Isolate Fuel Gas System	3 days															▶	
39	Vent Fuel Gas Piping and Equipment	3 days															▶	
40	Open and Vent Knock-Out Drum	1 day															▶	
41	Drain, Open and Vent the Drain Tank	1 day															▶	
42	Empty the Coalescing Filter	2 days															▶	
43	Open and Vent Equipment on the CT Gas Valve Module	1 day															▶	
44	Lube Oil Cooling Water System	9 days															▶	
45	Open and Drain the Water Side of the Lube Oil Coolers	6 days															▶	
46	Open and Vent the Coolers and Expansion Tank	3 days															▶	
47	Oily Drain Tank	3 days															▶	

Crossroads Retirement

ID	Task Name	Duration	2nd Quarter			3rd Quarter			4th Quarter			1st Quarter			2nd Quarter			3rd Q		
			Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul		
48	Open and Pump Out the Oily Drain Tank	3 days																		
49	Wash Water Skid	6 days																		
50	Open and Drain the Detergent Tank	2 days																		
51	Open and Drain the Demineralized Water Tank	2 days																		
52	Empty the Demineralized Water Tank	2 days																		
53	Compressed Air	4 days																		
54	Empty Dessiccant Air Dryers and Vent	2 days																		
55	Open and Vent the Air Reciever	2 days																		
56	Miscelleaneous Piping	21 days																		
57	Open and Vent the Exhaust Frame Cooling Pip	4 days																		
58	Open and Vent the CT Air Processing Piping	9 days																		
59	Open and Vent the Inlet Air Heating Piping	4 days																		
60	Open and Vent the CT Air Processing Piping	4 days																		
61	Fire Protection Piping	6 days																		
62	Empty the CO2 Storage Tank	4 days																		
63	Open and Vent the Fire Protection Piping	2 days																		
64	Lube Oil System	9 days																		
65	Empty and Remove from Site the Lubricating	5 days																		
66	Drain Lubricating Oil Piping	4 days																		
67	Open and Vent Lubricating Oil Piping	2 days																		
68	Potable Water	3 days																		
69	Disconnect Potable Water at Property Bound	3 days																		
70	Post Retirement Closure Activity	40 days																		
71	Post Retirement Closure Activity	40 days																		



Crossroads Dismantlement

Owner Costs

Pre-Dismantlement Activities		\$887,360	
Overhead During Dismantlement		\$1,551,849	
Post-Dismantlement Activities		\$49,140	
Owner Costs Total*			\$2,488,349

Demolition General Contractor (DGC) Costs

Site Management		\$845,925	
Equipment Rental		\$1,440,377	
Consummables		\$1,437,034	
Scrap Crew(s)		\$378,322	
Dismantlement		\$982,145	
Contractor Direct Cost*	\$5,083,803		

Contractor Allowances

DGC Insurance	2.00%	\$101,676	
Contingency/Profit	15.00%	\$777,822	
Performance Bond	2.00%	\$119,266.02	

Contractor Costs Total: \$6,082,567

Total: \$8,570,916

Owner Internal Costs: 5.00% \$428,546

Owner Contingency: 25.00% \$2,249,865

Crossroads Dismantlement Opinion of Probable Cost: \$11,249,327

*Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances
 = \$7,572,152

Crossroads Dismantlement		
ID	Task Name	Cost
1	Crossroads Dismantlement	\$7,572,156.16
2	Pre-Demolition Activities	\$887,360.52
3	Detailed Planning & Hire Owner's Engineer	\$104,441.28
4	Detailed Site Characterization Study	\$610,335.44
5	Hire Demolition general Contractor	\$167,184.00
6	KCP&L Prepares Unit for Dismantlement	\$5,399.80
7	Demolition Contractor Mobilizes on Site	\$0.00
8	KCP&L Overhead during Dismantlement	\$1,551,849.76
9	KCP&L Project Manager	\$246,600.80
10	KCP&L Administrative Support	\$91,189.76
11	KCP&L Engineer	\$405,323.20
12	Owners Engineer Project Manager	\$120,992.00
13	Owners Engineer - Engineer	\$687,744.00
14	Demolition Contractor Overhead during Dismantlement	\$845,925.12
15	Demolition Contractor Project Manager	\$239,341.28
16	Demolition Contractor Safety Manager	\$213,105.12
17	Demolition Contractor Superintendent	\$393,478.72
18	Demolition Contractor Equipment Rental Cost	\$1,440,377.92
19	Equipment Rental	\$1,440,377.92
20	Demolition Contractor Consumables	\$1,437,034.72
21	Consumables	\$1,437,034.72
22	Scrap Crews	\$378,322.88
23	Crew to Handle Scrap Material(s)	\$378,322.88
24	Dismantlement	\$982,145.24
25	Electrical	\$197,049.60
26	Electrical Demolition of Equipment	\$197,049.60
27	Fuel Gas System	\$21,113.20
28	Remove all above grade fuel gas piping.	\$6,782.32
29	Gas Filter Skid	\$14,330.88
30	Lube Oil System	\$53,740.80
31	Lube Oil Piping	\$14,330.88
32	Lube Oil Pumps	\$17,913.60
33	Lube Oil Tanks	\$21,496.32
34	Compressed Air System	\$21,496.32
35	Compressed Air Piping	\$10,748.16
36	Compressors	\$5,374.08
37	Air Receiver	\$3,582.72
38	Dryer	\$1,791.36
39	Fire Protection	\$26,870.40
40	Fire Protection Piping	\$19,704.96
41	CO2 Storage Tank	\$7,165.44
42	Wash Water Skid	\$10,748.16
43	Detergent Tank	\$10,748.16
44	Miscellaneous Piping	\$62,697.60

Crossroads Dismantlement

ID	Task Name	Cost
45	Exhaust Frame Cooling Piping	\$17,913.60
46	CT Air Processing Piping	\$21,496.32
47	Inlet Air Heating Piping	\$23,287.68
48	Generator	\$0.00
49	Generators	\$0.00
50	Combustion Turbine	\$263,329.92
51	Inlet Heaters	\$17,913.60
52	Inlet ducts	\$26,870.40
53	Exhaust ducts	\$35,827.20
54	Combustion Turbines	\$62,697.60
55	Combustion Turbine Foundations	\$66,280.32
56	Enclosures	\$53,740.80
57	CEMS	\$42,992.64
58	CEMS Building	\$21,496.32
59	CEMS Building Foundation	\$21,496.32
60	Stack	\$80,611.20
61	Stacks	\$80,611.20
62	Buildings	\$17,913.60
63	Remove Maintenance Building	\$17,913.60
64	Waste Water Tank	\$8,956.80
65	Remove Waste Water Tank	\$8,956.80
66	Site Prep	\$174,625.00
67	Final Grading and Drainage	\$174,625.00
68	Post Dismantlement Activities	\$49,140.00
69	Post Dismantlement Activities	\$49,140.00

Crossroads Dismantlement


ID	Task Name	Duration	2014				2015				2016		
			Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2		
1	Crossroads Dismantlement	688 days											
2	Pre-Demolition Activities	260 days											
3	Detailed Planning & Hire Owner's Engineer	3 mons											
4	Detailed Site Characterization Study	130 days											
5	Hire Demolition general Contractor	3 mons											
6	KCP&L Prepares Unit for Dismantlement	1 wk											
7	Demolition Contractor Mobilizes on Site	5 days											
8	KCP&L Overhead during Dismantlement	398 days											
9	KCP&L Project Manager	398 days											
10	KCP&L Administrative Support	398 days											
11	KCP&L Engineer	398 days											
12	Owners Engineer Project Manager	398 days											
13	Owners Engineer - Engineer	398 days											
14	Demolition Contractor Overhead during Dismantlement	398 days											
15	Demolition Contractor Project Manager	398 days											
16	Demolition Contractor Safety Manager	398 days											
17	Demolition Contractor Superintendent	398 days											
18	Demolition Contractor Equipment Rental Cost	398 days											
19	Equipment Rental	398 days											
20	Demolition Contractor Consumables	398 days											
21	Consumables	398 days											
22	Scrap Crews	398 days											
23	Crew to Handle Scrap Material(s)	398 days											
24	Dismantlement	398 days											
25	Electrical	110 days											
26	Electrical Demolition of Equipment	110 days											
27	Fuel Gas System	20 days											
28	Remove all above grade fuel gas piping.	12 days											
29	Gas Filter Skid	8 days											
30	Lube Oil System	30 days											
31	Lube Oil Piping	8 days											
32	Lube Oil Pumps	10 days											

Crossroads Dismantlement

ID	Task Name	Duration	2014				2015				2016			
			Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2			
33	Lube Oil Tanks	12 days												
34	Compressed Air System	12 days												
35	Compressed Air Piping	6 days												
36	Compressors	3 days												
37	Air Receiver	2 days												
38	Dryer	1 day												
39	Fire Protection	15 days												
40	Fire Protection Piping	11 days												
41	CO2 Storage Tank	4 days												
42	Wash Water Skid	6 days												
43	Detergent Tank	6 days												
44	Miscellaneous Piping	35 days												
45	Exhaust Frame Cooling Piping	10 days												
46	CT Air Processing Piping	12 days												
47	Inlet Air Heating Piping	13 days												
48	Generator	29 days												
49	Generators	29 days												
50	Combustion Turbine	147 days												
51	Inlet Heaters	10 days												
52	Inlet ducts	15 days												
53	Exhaust ducts	20 days												
54	Combustion Turbines	35 days												
55	Combustion Turbine Foundations	37 days												
56	Enclosures	30 days												
57	CEMS	24 days												
58	CEMS Building	12 days												
59	CEMS Building Foundation	12 days												
60	Stack	45 days												
61	Stacks	45 days												
62	Buildings	10 days												
63	Remove Maintenance Building	10 days												
64	Waste Water Tank	5 days												

Crossroads Dismantlement

ID	Task Name	Duration	2014				2015				2016				
			Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2
65	Remove Waste Water Tank	5 days													
66	Site Prep	20 days													
67	Final Grading and Drainage	20 days													
68	Post Dismantlement Activities	30 days													
69	Post Dismantlement Activities	30 days													



KCI

KCI STATION

The KCI Generating Station consists of two natural gas-fired combustion turbine generator sets.

Combined, these combustion turbines have an SPP-accredited unit rating of 0 MW. KCI was placed into service in 1971. Each unit is comprised of a Pratt & Whitney GG4A-7 combustion turbine with a generator step-up transformer and auxiliary power transformer.

The following are the major systems and equipment that were included in the retirement and dismantlement of the KCI Generating Station.

1. Combustion turbine generator sets and auxiliaries.
2. Generation step-up and auxiliary transformers.
3. Outdoor switchgear.
4. Exhaust stacks.
5. Control Room/Maintenance building.
6. Gas compressor building and equipment.
7. Black-start generator.
8. Service/Instrument air compressors.
9. Glycol cooling towers.
10. Fire protection systems.

KCI Retirement

Owner Costs

Pre-Retirement Activities	\$43,834
Retirement Activities	\$112,691
Post-Retirement Activities	\$16,932

Owner Direct Total \$173,457

Owner Internal Costs 5.00% \$8,673

Owner Contingency: 25.00% \$45,532

KCI Retirement Opinion of Probable Cost: \$227,662.31

KCI Retirement		
ID	Task Name	Cost
1	KCI Retirement	\$173,457.84
2	Pre-Retirement Activities	\$43,834.00
3	Permitting Review	\$23,466.00
4	Develop Detailed Retirement Plan	\$20,368.00
5	Retirement	\$112,691.84
6	Project Management During Retirement	\$48,121.20
7	Project Management During Retirement	\$48,121.20
8	Retirement Activities	\$64,570.64
9	Electrical	\$19,652.16
10	Medium and Low Voltage Drawout Switchgear	\$5,359.68
11	De-energize all buses at the source.	\$893.28
12	Open all circuit breakers.	\$1,786.56
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	\$893.28
14	Verify that the closing/tripping springs are discharged.	\$893.28
15	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each breaker cubicle.	\$893.28
16	Motor Control Centers	\$2,679.84
17	De-energize all buses at the source.	\$893.28
18	Open all circuit breakers and disconnect switches.	\$893.28
19	Remove all fuses in control circuits.	\$893.28
20	Low-voltage Switchboards and Panelboards	\$1,786.56
21	De-energize all buses at the source.	\$893.28
22	Open all circuit breakers and disconnect switches.	\$893.28
23	Oil-Filled Power Transformers	\$4,466.40
24	De-energize all buses at the source.	\$893.28
25	Open all circuit breakers and disconnect switches.	\$1,786.56
26	De-energize all buses at the source.	\$893.28
27	Open all circuit breakers and disconnect switches.	\$893.28
28	Dry-type Power Transformers	\$1,786.56
29	De-energize all transformer primaries and verify that the secondary is de-energized.	\$893.28
30	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	\$893.28
31	Motors	\$3,573.12
32	De-energize all primary power at the source.	\$893.28
33	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	\$893.28
34	Drain lube oil system (if applicable) and dispose of oil.	\$1,786.56
35	Enclosure Building	\$3,736.96


KCI Retirement		
ID	Task Name	Cost
36	Secure the Enclosure Building	\$3,736.96
37	Gas Compressor Building	\$1,868.48
38	Secure the Gas Compressor Building	\$1,868.48
39	Shop Building	\$3,736.96
40	Secure the Shop Building	\$3,736.96
41	Cooling Towers	\$5,209.92
42	Drain Cooling Tower	\$3,907.44
43	Drain Cooling Tower Chemical Storage Tanks	\$1,302.48
44	Fuel Gas System	\$5,612.00
45	Isolate Fuel Gas System	\$3,907.44
46	Vent Fuel Gas Piping and Equipment	\$842.72
47	Open and Vent Equipment on the CT Gas Valve Module	\$861.84
48	Lube Oil Cooling Water System	\$2,585.52
49	Open and Drain the Glycol Side of the Lube Oil Coolers	\$1,723.68
50	Open and Vent the Coolers and Expansion Tank	\$861.84
51	Sump	\$3,954.00
52	Open and Pump Out the Sump	\$3,954.00
53	Miscellaneous Piping	\$2,585.52
54	Open and Vent Miscellaneous Piping	\$2,585.52
55	Fire Protection Piping	\$3,428.24
56	Empty the CO2 Storage Tank	\$2,566.40
57	Open and Vent the Fire Protection Piping	\$861.84
58	Lube Oil System	\$5,151.92
59	Empty and Remove from Site the Lubricating Oil	\$2,566.40
60	Drain Lubricating Oil Piping	\$1,723.68
61	Open and Vent Lubricating Oil Piping	\$861.84
62	Service Piping	\$5,286.72
63	Disconnect Potable Water at Property Boundary	\$2,643.36
64	Disconnect Compressed Air at Property Boundary	\$2,643.36
65	Black Start Engine	\$1,762.24
66	Vent Fuel Gas Piping to Black Start Engine	\$881.12
67	Post Retirement Closure Activity	\$16,932.00
68	Post Retirement Closure Activity	\$16,932.00

KCI Retirement			2nd Quarter			3rd Quarter			4th Quarter			1st Quarter		
ID	Task Name	Duration	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar
1	KCI Retirement	115 days												
2	Pre-Retirement Activities	40 days												
3	Permitting Review	20 days												
4	Develop Detailed Retirement Plan	20 days												
5	Retirement	60 days												
6	Project Management During Retirement	60 days												
7	Project Management During Retirement	60 days												
8	Retirement Activities	60 days												
9	Electrical	22 days												
10	Medium and Low Voltage Drawout Switches	6 days												
11	De-energize all buses at the source.	1 day												
12	Open all circuit breakers.	2 days												
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	1 day												
14	Verify that the closing/tripping springs are discharged.	1 day												
15	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each	1 day												
16	Motor Control Centers	3 days												
17	De-energize all buses at the source.	1 day												
18	Open all circuit breakers and disconnect switches.	1 day												
19	Remove all fuses in control circuits.	1 day												
20	Low-voltage Switchboards and Panelboards	2 days												
21	De-energize all buses at the source.	1 day												
22	Open all circuit breakers and disconnect switches.	1 day												
23	Oil-Filled Power Transformers	5 days												
24	De-energize all buses at the source.	1 day												
25	Open all circuit breakers and disconnect switches.	2 days												

KCI Retirement

ID	Task Name	Duration	2nd Quarter			3rd Quarter			4th Quarter			1st Quarter			
			Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	
26	De-energize all buses at the source.	1 day													
27	Open all circuit breakers and disconnect switches.	1 day													
28	Dry-type Power Transformers	2 days													
29	De-energize all transformer primaries and verify that the secondary is de-energized.	1 day													
30	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses	1 day													
31	Motors	4 days													
32	De-energize all primary power at the source.	1 day													
33	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	1 day													
34	Drain lube oil system (if applicable) and dispose of oil.	2 days													
35	Enclosure Building	2 days													
36	Secure the Enclosure Building	2 days													
37	Gas Compressor Building	1 day													
38	Secure the Gas Compressor Building	1 day													
39	Shop Building	2 days													
40	Secure the Shop Building	2 days													
41	Cooling Towers	4 days													
42	Drain Cooling Tower	3 days													
43	Drain Cooling Tower Chemical Storage Tanks	1 day													
44	Fuel Gas System	5 days													
45	Isolate Fuel Gas System	3 days													
46	Vent Fuel Gas Piping and Equipment	1 day													
47	Open and Vent Equipment on the CT Gas Valve Module	1 day													
48	Lube Oil Cooling Water System	3 days													

KCI Retirement															
ID	Task Name	Duration	2nd Quarter			3rd Quarter			4th Quarter			1st Quarter			
			Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	
49	Open and Drain the Glycol Side of the Lube Oil Coolers	2 days													
50	Open and Vent the Coolers and Expansion Tank	1 day													
51	Sump	3 days													
52	Open and Pump Out the Sump	3 days													
53	Miscellaneous Piping	3 days													
54	Open and Vent Miscellaneous Piping	3 days													
55	Fire Protection Piping	3 days													
56	Empty the CO2 Storage Tank	2 days													
57	Open and Vent the Fire Protection Piping	1 day													
58	Lube Oil System	5 days													
59	Empty and Remove from Site the Lubricating Oil	2 days													
60	Drain Lubricating Oil Piping	2 days													
61	Open and Vent Lubricating Oil Piping	1 day													
62	Service Piping	6 days													
63	Disconnect Potable Water at Property Boundary	3 days													
64	Disconnect Compressed Air at Property Boundary	3 days													
65	Black Start Engine	1 day													
66	Vent Fuel Gas Piping to Black Start Engine	1 day													
67	Post Retirement Closure Activity	15 days													
68	Post Retirement Closure Activity	15 days													



KCI Dismantlement

Owner Costs

Pre-Dismantlement Activities		\$473,576	
Overhead During Dismantlement		\$279,378	
Post-Dismantlement Activities		\$32,760	
Owner Costs Total*			\$785,714

Demolition General Contractor (DGC) Costs

Site Management		\$176,411	
Equipment Rental		\$300,380	
Consumables		\$299,683	
Scrap Crew(s)		\$78,896	
Dismantlement		\$263,996	

Contractor Direct Cost* \$1,119,366

Contractor Allowances

DGC Insurance	2.00%	\$22,387	
Contingency/Profit	15.00%	\$171,263	
Performance Bond	2.00%	\$26,260.33	

Contractor Costs Total: \$1,339,277

Total:			\$2,124,991
Owner Internal Costs:	5.00%		\$106,250
Owner Contingency:	25.00%		\$557,810
KCI Dismantlement Opinion of Probable Cost:			\$2,789,050

*Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances
= \$1,905,080

KCI Dismantlement		
ID	Task Name	Cost
1	KCI Dismantlement	\$1,905,082.52
2	Pre-Demolition Activities	\$473,576.40
3	Detailed Planning & Hire Owner's Engineer	\$69,627.52
4	Detailed Site Characterization Study	\$281,693.28
5	Hire Demolition general Contractor	\$111,456.00
6	KCP&L Prepares Unit for Dismantlement	\$10,799.60
7	Demolition Contractor Mobilizes on Site	\$0.00
8	KCP&L Overhead during Dismantlement	\$279,378.00
9	KCP&L Project Manager	\$51,426.80
10	KCP&L Engineer	\$84,527.20
11	Owners Engineer - Engineer	\$143,424.00
12	Demolition Contractor Overhead during Dismantlement	\$176,411.52
13	Demolition Contractor Project Manager	\$49,912.88
14	Demolition Contractor Safety Manager	\$44,441.52
15	Demolition Contractor Superintendent	\$82,057.12
16	Demolition Contractor Equipment Rental Cost	\$300,380.32
17	Equipment Rental	\$300,380.32
18	Demolition Contractor Consumables	\$299,683.12
19	Consumables	\$299,683.12
20	Scrap Crews	\$78,896.48
21	Crew to Handle Scrap Material(s)	\$78,896.48
22	Dismantlement	\$263,996.68
23	Electrical	\$53,740.80
24	Electrical Demolition of Equipment	\$53,740.80
25	Shop Building	\$7,165.44
26	Remove the Shop Building	\$7,165.44
27	Fuel Gas System	\$10,437.52
28	Remove all above grade fuel gas piping.	\$1,480.72
29	Remove Gas Compressor Equipment	\$5,374.08
30	Remove Gas Compressor Building	\$3,582.72
31	Lube Oil System	\$10,748.16
32	Lube Oil Piping	\$1,791.36
33	Lube Oil Pumps	\$3,582.72
34	Lube Oil Tanks	\$5,374.08
35	Compressed Air System	\$1,791.36
36	Remove Above Ground Compressed Air Piping	\$1,791.36
37	Fire Protection	\$10,748.16
38	Fire Protection Piping	\$3,582.72
39	CO2 Storage Tank	\$7,165.44
40	Miscellaneous Piping	\$10,748.16
41	Remove Miscellaneous Piping	\$8,956.80
42	Remove Above Ground Service Water Piping	\$1,791.36
43	Generator	\$17,913.60
44	Generators	\$17,913.60

KCI Dismantlement

ID	Task Name	Cost
45	Combustion Turbine	\$62,697.60
46	Inlet ducts	\$7,165.44
47	Exhaust ducts	\$7,165.44
48	Combustion Turbines	\$17,913.60
49	Combustion Turbine Foundation	\$21,496.32
50	Combustion Turbine Enclosure Building	\$8,956.80
51	Cooling Towers	\$10,748.16
52	Remove Cooling Towers	\$10,748.16
53	Stack	\$3,582.72
54	Stacks	\$3,582.72
55	Site Prep	\$63,675.00
56	Final Grading and Drainage	\$63,675.00
57	Post Dismantlement Activities	\$32,760.00
58	Post Dismantlement Activities	\$32,760.00

KCI Dismantlement

ID	Task Name	Duration	2013				2014				2015			
			Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	
1	KCI Dismantlement	633 days												
2	Pre-Demolition Activities	155 days												
3	Detailed Planning & Hire Owner's Engineer	2 mons												
4	Detailed Site Characterization Study	60 days												
5	Hire Demolition general Contractor	2 mons												
6	KCP&L Prepares Unit for Dismantlement	2 wks												
7	Demolition Contractor Mobilizes on Site	5 days												
8	KCP&L Overhead during Dismantlement	83 days												
9	KCP&L Project Manager	83 days												
10	KCP&L Engineer	83 days												
11	Owners Engineer - Engineer	83 days												
12	Demolition Contractor Overhead during Dismantlement	83 days												
13	Demolition Contractor Project Manager	83 days												
14	Demolition Contractor Safety Manager	83 days												
15	Demolition Contractor Superintendent	83 days												
16	Demolition Contractor Equipment Rental Cost	83 days												
17	Equipment Rental	83 days												
18	Demolition Contractor Consumables	83 days												
19	Consumables	83 days												
20	Scrap Crews	83 days												
21	Crew to Handle Scrap Material(s)	83 days												
22	Dismantlement	83 days												
23	Electrical	30 days												
24	Electrical Demolition of Equipment	30 days												
25	Shop Building	4 days												
26	Remove the Shop Building	4 days												
27	Fuel Gas System	7 days												
28	Remove all above grade fuel gas piping.	2 days												
29	Remove Gas Compressor Equipment	3 days												
30	Remove Gas Compressor Building	2 days												
31	Lube Oil System	6 days												
32	Lube Oil Piping	1 day												

KCI Dismantlement

ID	Task Name	Duration	2013				2014				2015				
			Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2		
33	Lube Oil Pumps	2 days													
34	Lube Oil Tanks	3 days													
35	Compressed Air System	1 day													
36	Remove Above Ground Compressed Air Piping	1 day													
37	Fire Protection	6 days													
38	Fire Protection Piping	2 days													
39	CO2 Storage Tank	4 days													
40	Miscellaneous Piping	6 days													
41	Remove Miscellaneous Piping	5 days													
42	Remove Above Ground Service Water Piping	1 day													
43	Generator	10 days													
44	Generators	10 days													
45	Combustion Turbine	35 days													
46	Inlet ducts	4 days													
47	Exhaust ducts	4 days													
48	Combustion Turbines	10 days													
49	Combustion Turbine Foundation	12 days													
50	Combustion Turbine Enclosure Building	5 days													
51	Cooling Towers	6 days													
52	Remove Cooling Towers	6 days													
53	Stack	2 days													
54	Stacks	2 days													
55	Site Prep	1 day													
56	Final Grading and Drainage	1 day													
57	Post Dismantlement Activities	20 days													
58	Post Dismantlement Activities	20 days													

NEVADA UNIT 1

NEVADA STATION

The Nevada Generating Station consists of a single distillate-fired combustion turbine generator set.

Nevada has an SPP-accredited unit rating of 20.8 MW. Nevada was placed into service in 1974. The unit is comprised of a GE Model MS5001P combustion turbine with a generator step-up transformer and auxiliary power transformer.

The following are the major systems and equipment that were included in the retirement and dismantlement of the Nevada Generating Station.

1. Combustion turbine generator sets and auxiliaries.
2. Generation step-up and auxiliary transformers.
3. Outdoor switchgear.
4. Exhaust stacks.
5. Maintenance building.
6. Fuel oil transfer equipment.
7. Service/Instrument air compressors.
8. Fuel oil storage.

Nevada Retirement

Owner Costs

Pre-Retirement Activities	\$43,834
Retirement Activities	\$125,254
Post-Retirement Activities	\$45,152

Owner Direct Total \$214,240

Owner Internal Costs 5.00% \$10,712

Owner Contingency: 25.00% \$56,238

Nevada Retirement Opinion of Probable Cost: \$281,190.00

Activities Required by Permit or Regulation

Nevada Storage Tank \$56,530

Activities Required by Permit or Regulation: \$56,530

Nevada Retirement		
ID	Task Name	Cost
1	Nevada Retirement	\$214,240.42
2	Pre-Retirement Activities	\$43,834.00
3	Permitting Review	\$23,466.00
4	Develop Detailed Retirement Plan	\$20,368.00
5	Retirement	\$125,254.42
6	Project Management During Retirement	\$55,339.38
7	Project Management During Retirement	\$55,339.38
8	Retirement Activities	\$69,915.04
9	Electrical	\$27,691.68
10	Medium and Low Voltage Drawout Switchgear	\$5,359.68
11	De-energize all buses at the source.	\$893.28
12	Open all circuit breakers.	\$893.28
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	\$893.28
14	Verify that the closing/tripping springs are discharged.	\$1,786.56
15	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each breaker cubicle.	\$893.28
16	Motor Control Centers	\$2,679.84
17	De-energize all buses at the source.	\$893.28
18	Open all circuit breakers and disconnect switches.	\$893.28
19	Remove all fuses in control circuits.	\$893.28
20	Low-voltage Switchboards and Panelboards	\$1,786.56
21	De-energize all buses at the source.	\$893.28
22	Open all circuit breakers and disconnect switches.	\$893.28
23	Oil-Filled Power Transformers	\$7,146.24
24	De-energize all buses at the source.	\$893.28
25	Open all circuit breakers and disconnect switches.	\$893.28
26	De-energize all buses at the source.	\$893.28
27	Open all circuit breakers and disconnect switches.	\$4,466.40
28	Dry-type Power Transformers	\$4,466.40
29	De-energize all transformer primaries and verify that the secondary is de-energized.	\$893.28
30	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	\$3,573.12
31	Motors	\$6,252.96
32	De-energize all primary power at the source.	\$893.28
33	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	\$893.28
34	Drain lube oil system (if applicable) and dispose of oil.	\$4,466.40
35	Maintenance Building	\$3,736.96
36	Secure the Maintenance Building	\$3,736.96
37	Fuel Oil System	\$5,631.12


Nevada Retirement

ID	Task Name	Cost
38	Isolate Fuel Oil System	\$3,907.44
39	Drain and Vent Fuel Oil Piping	\$1,723.68
40	Lube Oil Cooling Water System	\$2,585.52
41	Open and Drain the Water Side of the Lube Oil Coolers	\$1,723.68
42	Open and Vent the Coolers and Expansion Tank	\$861.84
43	Oily Drain Tank	\$3,954.00
44	Open and Pump Out the Oily Drain Tank	\$3,954.00
45	Compressed Air	\$2,585.52
46	Empty Dessiccant Air Dryers and Vent	\$861.84
47	Open and Vent the Air Reciever	\$1,723.68
48	Miscelleaneous Piping	\$5,171.04
49	Open and Vent the Exhaust Frame Cooling Piping	\$861.84
50	Open and Vent the Inlet Air Heating Piping	\$861.84
51	Open & Vent the CT Air Process Piping	\$861.84
52	Open and Vent the CT Air Processing Piping	\$2,585.52
53	Fire Protection Piping	\$3,428.24
54	Empty the CO2 Storage Tank	\$2,566.40
55	Open and Vent the Fire Protection Piping	\$861.84
56	Lube Oil System	\$8,580.16
57	Empty and Remove from Site the Lubricating Oil	\$5,132.80
58	Drain Lubricating Oil Piping	\$1,723.68
59	Open and Vent Lubricating Oil Piping	\$1,723.68
60	Potable Water	\$2,643.36
61	Disconnect Potable Water at Property Boundary	\$2,643.36
62	Waste Water	\$3,907.44
63	Disconnect Waste Water at Property Boundary	\$3,907.44
64	Post Retirement Closure Activity	\$45,152.00
65	Post Retirement Closure Activity	\$45,152.00

Nevada Retirement			4th Quarter				1st Quarter			2nd Quarter		
ID	Task Name	Duration	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr		
1	Nevada Retirement	149 days	[Gantt bar spanning from Sep to Apr]									
2	Pre-Retirement Activities	40 days	[Gantt bar spanning from Sep to Oct]									
3	Permitting Review	20 days	[Gantt bar spanning from Oct to Nov]									
4	Develop Detailed Retirement Plan	20 days	[Gantt bar spanning from Oct to Nov]									
5	Retirement	69 days	[Gantt bar spanning from Nov to Feb]									
6	Project Management During Retirement	69 days	[Gantt bar spanning from Nov to Feb]									
7	Project Management During Retirement	69 days	[Gantt bar spanning from Nov to Feb]									
8	Retirement Activities	69 days	[Gantt bar spanning from Nov to Feb]									
9	Electrical	31 days	[Gantt bar spanning from Nov to Dec]									
10	Medium and Low Voltage Drawout Switchgear	6 days	[Gantt bar spanning from Nov to Dec]									
11	De-energize all buses at the source.	1 day	[Gantt bar spanning from Nov to Nov]									
12	Open all circuit breakers.	1 day	[Gantt bar spanning from Nov to Nov]									
13	Rack all circuit breakers into the fully withdrawn, disconnected	1 day	[Gantt bar spanning from Nov to Nov]									
14	Verify that the closing/tripping springs are discharged.	2 days	[Gantt bar spanning from Nov to Dec]									
15	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each	1 day	[Gantt bar spanning from Nov to Nov]									
16	Motor Control Centers	3 days	[Gantt bar spanning from Dec to Dec]									
17	De-energize all buses at the source.	1 day	[Gantt bar spanning from Dec to Dec]									
18	Open all circuit breakers and disconnect switches.	1 day	[Gantt bar spanning from Dec to Dec]									
19	Remove all fuses in control circuits.	1 day	[Gantt bar spanning from Dec to Dec]									
20	Low-voltage Switchboards and Panelboards	2 days	[Gantt bar spanning from Dec to Dec]									
21	De-energize all buses at the source.	1 day	[Gantt bar spanning from Dec to Dec]									
22	Open all circuit breakers and disconnect switches.	1 day	[Gantt bar spanning from Dec to Dec]									
23	Oil-Filled Power Transformers	8 days	[Gantt bar spanning from Dec to Jan]									


Nevada Retirement

ID	Task Name	Duration	4th Quarter			1st Quarter			2nd Quarter
			Sep	Oct	Nov	Dec	Jan	Feb	Mar
24	De-energize all buses at the source.	1 day							
25	Open all circuit breakers and disconnect switches.	1 day							
26	De-energize all buses at the source.	1 day							
27	Open all circuit breakers and disconnect switches.	5 days							
28	Dry-type Power Transformers	5 days							
29	De-energize all transformer primaries and verify that the secondary is de-energized.	1 day							
30	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	4 days							
31	Motors	7 days							
32	De-energize all primary power at the source.	1 day							
33	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	1 day							
34	Drain lube oil system (if applicable) and dispose of oil.	5 days							
35	Maintenance Building	2 days							
36	Secure the Maintenance Building	2 days							
37	Fuel Oil System	5 days							
38	Isolate Fuel Oil System	3 days							
39	Drain and Vent Fuel Oil Piping	2 days							
40	Lube Oil Cooling Water System	3 days							
41	Open and Drain the Water Side of the Lube Oil Coolers	2 days							
42	Open and Vent the Coolers and Expansion Tank	1 day							



Nevada Retirement

ID	Task Name	Duration	4th Quarter			1st Quarter			2nd Quarter		
			Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	
43	Oily Drain Tank	3 days									
44	Open and Pump Out the Oily Drain Tank	3 days									
45	Compressed Air	3 days									
46	Empty Dessiccant Air Dryers and Vent	1 day									
47	Open and Vent the Air Reciever	2 days									
48	Miscellaneous Piping	5 days									
49	Open and Vent the Exhaust Frame Cooling Piping	1 day									
50	Open and Vent the Inlet Air Heating Piping	1 day									
51	Open & Vent the CT Air Process Piping	1 day									
52	Open and Vent the CT Air Processing Piping	3 days									
53	Fire Protection Piping	3 days									
54	Empty the CO2 Storage Tank	2 days									
55	Open and Vent the Fire Protection Piping	1 day									
56	Lube Oil System	8 days									
57	Empty and Remove from Site the Lubricating Oil	4 days									
58	Drain Lubricating Oil Piping	2 days									
59	Open and Vent Lubricating Oil Piping	2 days									
60	Potable Water	3 days									
61	Disconnect Potable Water at Property Boundary	3 days									
62	Waste Water	3 days									
63	Disconnect Waste Water at Property Boundary	3 days									
64	Post Retirement Closure Activity	40 days									
65	Post Retirement Closure Activity	40 days									



Nevada Dismantlement

Owner Costs

Pre-Dismantlement Activities		\$892,760	
Overhead During Dismantlement		\$799,319	
Post-Dismantlement Activities		\$65,520	
Owner Costs Total*			\$1,757,599

Demolition General Contractor (DGC) Costs

Site Management		\$435,715	
Equipment Rental		\$741,903	
Consummables		\$740,181	
Scrap Crew(s)		\$194,864	
Dismantlement		\$515,571	

Contractor Direct Cost* \$2,628,234

Contractor Allowances

DGC Insurance	2.00%	\$52,565	
Contingency/Profit	15.00%	\$402,120	
Performance Bond	2.00%	\$61,658.37	

Contractor Costs Total: \$3,144,577

Total: \$4,902,176

Owner Internal Costs: 5.00% \$245,109

Owner Contingency: 25.00% \$1,286,821

Nevada Dismantlement Opinion of Probable Cost: \$6,434,106

*Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances
= \$4,385,833

Nevada Dismantlement		
ID	Task Name	Cost
1	Nevada CT Dismantlement	\$4,385,836.20
2	Pre-Demolition Activities	\$892,760.32
3	Detailed Planning & Hire Owner's Engineer	\$104,441.28
4	Detailed Site Characterization Study	\$610,335.44
5	Hire Demolition general Contractor	\$167,184.00
6	KCP&L Prepares Unit for Dismantlement	\$10,799.60
7	Demolition Contractor Mobilizes on Sit	\$0.00
8	KCP&L Overhead during Dismantlement	\$799,319.60
9	KCP&L Project Manager	\$127,018.00
10	KCP&L Administrative Support	\$46,969.60
11	KCP&L Engineer	\$208,772.00
12	Owners Engineer Project Manager	\$62,320.00
13	Owners Engineer - Engineer	\$354,240.00
14	Demolition Contractor Overhead during Dismantlement	\$435,715.20
15	Demolition Contractor Project Manager	\$123,278.80
16	Demolition Contractor Safety Manager	\$109,765.20
17	Demolition Contractor Superintendent	\$202,671.20
18	Demolition Contractor Equipment Rental Cost	\$741,903.20
19	Equipment Rental	\$741,903.20
20	Demolition Contractor Consumables	\$740,181.20
21	Consumables	\$740,181.20
22	Scrap Crews	\$194,864.80
23	Crew to Handle Scrap Material(s)	\$194,864.80
24	Dismantlement	\$515,571.88
25	Electrical	\$107,481.60
26	Electrical Demolition of Equipment	\$107,481.60
27	Fuel Oil System	\$8,445.28
28	Remove Above Ground Fuel Oil Piping	\$3,071.20
29	Fuel Skids	\$5,374.08
30	Lube Oil System	\$17,913.60
31	Lube Oil Piping	\$5,374.08
32	Lube Oil Pumps	\$5,374.08
33	Lube Oil Tanks	\$7,165.44
34	Fire Protection	\$26,870.40
35	Fire Protection Piping	\$10,748.16
36	Firewater Tank	\$8,956.80
37	CO2 Storage Tank	\$7,165.44
38	Miscellaneous Piping	\$25,079.04
39	Exhaust Frame Cooling Piping	\$7,165.44
40	CT Air Processing Piping	\$8,956.80
41	Inlet Air Heating Piping	\$8,956.80
42	Generator	\$10,748.16
43	Generator	\$10,748.16
44	Combustion Turbine	\$93,150.72

Nevada Dismantlement

ID	Task Name	Cost
45	Inlet Heater	\$5,374.08
46	Inlet duct	\$10,748.16
47	Exhaust duct	\$14,330.88
48	Combustion Turbine	\$28,661.76
49	Combustion Turbine Foundation	\$16,122.24
50	Enclosure	\$17,913.60
51	CEMS	\$14,330.88
52	CEMS Building	\$7,165.44
53	CEMS Building Foundation	\$7,165.44
54	Stack	\$26,870.40
55	Stacks	\$26,870.40
56	Site Buildings	\$8,956.80
57	Remove Site Buildings	\$8,956.80
58	Site Prep	\$175,725.00
59	Final Grading and Drainage	\$175,725.00
60	Post Dismantlement Activities	\$65,520.00
61	Post Dismantlement Activities	\$65,520.00

Nevada Dismantlement

ID	Task Name	Duration	1st Quarter	
			Jan	Jan
1	Nevada CT Dismantlement	944 days	[Gantt bar spanning from start to end of 1st Quarter]	
2	Pre-Demolition Activities	130 days	[Gantt bar starting at beginning of 1st Quarter]	
3	Detailed Planning & Hire Owner's Engineer	3 mons	[Gantt bar]	
4	Detailed Site Characterization Study	130 days	[Gantt bar]	
5	Hire Demolition general Contractor	3 mons	[Gantt bar]	
6	KCP&L Prepares Unit for Dismantlement	2 wks	[Gantt bar]	
7	Demolition Contractor Mobilizes on Sit	5 days	[Gantt bar]	
8	KCP&L Overhead during Dismantlement	205 days	[Gantt bar]	
9	KCP&L Project Manager	205 days	[Gantt bar]	
10	KCP&L Administrative Support	205 days	[Gantt bar]	
11	KCP&L Engineer	205 days	[Gantt bar]	
12	Owners Engineer Project Manager	205 days	[Gantt bar]	
13	Owners Engineer - Engineer	205 days	[Gantt bar]	
14	Demolition Contractor Overhead during Dismantlement	205 days	[Gantt bar]	
15	Demolition Contractor Project Manager	205 days	[Gantt bar]	
16	Demolition Contractor Safety Manager	205 days	[Gantt bar]	
17	Demolition Contractor Superintendent	205 days	[Gantt bar]	
18	Demolition Contractor Equipment Rental Cost	205 days	[Gantt bar]	
19	Equipment Rental	205 days	[Gantt bar]	
20	Demolition Contractor Consumables	205 days	[Gantt bar]	
21	Consumables	205 days	[Gantt bar]	
22	Scrap Crews	205 days	[Gantt bar]	
23	Crew to Handle Scrap Material(s)	205 days	[Gantt bar]	
24	Dismantlement	205 days	[Gantt bar]	
25	Electrical	60 days	[Gantt bar]	
26	Electrical Demolition of Equipment	60 days	[Gantt bar]	
27	Fuel Oil System	8 days	[Gantt bar]	
28	Remove Above Ground Fuel Oil Piping	5 days	[Gantt bar]	
29	Fuel Skids	3 days	[Gantt bar]	
30	Lube Oil System	10 days	[Gantt bar]	
31	Lube Oil Piping	3 days	[Gantt bar]	

Nevada Dismantlement

ID	Task Name	Duration	1st Quarter	
			Jan	Jan
32	Lube Oil Pumps	3 days		
33	Lube Oil Tanks	4 days		
34	Fire Protection	15 days		
35	Fire Protection Piping	6 days		
36	Firewater Tank	5 days		
37	CO2 Storage Tank	4 days		
38	Miscellaneous Piping	14 days		
39	Exhaust Frame Cooling Piping	4 days		
40	CT Air Processing Piping	5 days		
41	Inlet Air Heating Piping	5 days		
42	Generator	6 days		
43	Generator	6 days		
44	Combustion Turbine	52 days		
45	Inlet Heater	3 days		
46	Inlet duct	6 days		
47	Exhaust duct	8 days		
48	Combustion Turbine	16 days		
49	Combustion Turbine Foundation	9 days		
50	Enclosure	10 days		
51	CEMS	8 days		
52	CEMS Building	4 days		
53	CEMS Building Foundation	4 days		
54	Stack	15 days		
55	Stacks	15 days		
56	Site Buildings	5 days		
57	Remove Site Buildings	5 days		
58	Site Prep	65 days		
59	Final Grading and Drainage	65 days		
60	Post Dismantlement Activities	40 days		
61	Post Dismantlement Activities	40 days		

RALPH GREEN UNIT 3

RALPH GREEN STATION

The Ralph Green Generating Station consists of a single gas-fired combustion turbine generator set.

Ralph Green has an SPP-accredited unit rating of 71.5 MW and was placed into service in 1981. The unit is comprised of a GE Model MS7001E combustion turbine with a generator step-up transformer and auxiliary power transformer.

The following are the major systems and equipment that were included in the retirement and dismantlement of the Ralph Green Generating Station.

1. Combustion turbine generator sets and auxiliaries.
2. Generation step-up and auxiliary transformers.
3. Outdoor switchgear.
4. Exhaust stack.
5. Administrative/Maintenance building.
6. Water treatment equipment.
7. Service/Instrument air compressors.
8. Demineralized water tank.

Ralph Green Retirement

Owner Costs

Pre-Retirement Activities	\$43,834
Retirement Activities	\$128,593
Post-Retirement Activities	\$45,152

Owner Direct Total \$217,579

Owner Internal Costs 5.00% \$10,879

Owner Contingency: 25.00% \$57,114

Ralph Green Retirement Opinion of Probable Cost: \$285,572.44

Activities Required by Permit or Regulation

Ash Pond Landfill Closure \$81,385

Activities Required by Permit or Regulation: \$81,385

Ralph Green Retirement		
ID	Task Name	Cost
1	Ralph Green Retirement	\$217,579.72
2	Pre-Retirement Activities	\$43,834.00
3	Permitting Review	\$23,466.00
4	Develop Detailed Retirement Plan	\$20,368.00
5	Retirement	\$128,593.72
6	Project Management During Retirement	\$56,141.40
7	Project Management During Retirement	\$56,141.40
8	Retirement Activities	\$72,452.32
9	Electrical	\$19,652.16
10	Medium and Low Voltage Drawout Switchgear	\$5,359.68
11	De-energize all buses at the source.	\$893.28
12	Open all circuit breakers.	\$893.28
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	\$893.28
14	Verify that the closing/tripping springs are discharged.	\$1,786.56
15	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each breaker cubicle.	\$893.28
16	Motor Control Centers	\$2,679.84
17	De-energize all buses at the source.	\$893.28
18	Open all circuit breakers and disconnect switches.	\$893.28
19	Remove all fuses in control circuits.	\$893.28
20	Low-voltage Switchboards and Panelboards	\$1,786.56
21	De-energize all buses at the source.	\$893.28
22	Open all circuit breakers and disconnect switches.	\$893.28
23	Oil-Filled Power Transformers	\$3,573.12
24	De-energize all buses at the source.	\$893.28
25	Open all circuit breakers and disconnect switches.	\$893.28
26	De-energize all buses at the source.	\$893.28
27	Open all circuit breakers and disconnect switches.	\$893.28
28	Dry-type Power Transformers	\$1,786.56
29	De-energize all transformer primaries and verify that the secondary is de-energized.	\$893.28
30	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	\$893.28
31	Motors	\$4,466.40
32	De-energize all primary power at the source.	\$893.28
33	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	\$893.28
34	Drain lube oil system (if applicable) and dispose of oil.	\$2,679.84
35	Administration/Maintenance Building	\$7,235.60
36	Secure Administration/Maintenance Building	\$7,235.60
37	Fuel Gas System	\$10,783.04

Ralph Green Retirement

ID	Task Name	Cost
38	Isolate Fuel Gas System	\$3,907.44
39	Vent Fuel Gas Piping and Equipment	\$2,528.16
40	Open and Vent Knock-Out Drum	\$861.84
41	Drain, Open and Vent the Drain Tank	\$861.84
42	Empty the Coalescing Filter	\$1,761.92
43	Open and Vent Equipment on the CT Gas Valve Module	\$861.84
44	Lube Oil Cooling Water System	\$2,585.52
45	Open and Drain the Water Side of the Lube Oil Coolers	\$1,723.68
46	Open and Vent the Coolers and Expansion Tank	\$861.84
47	Oily Drain Tank	\$3,954.00
48	Open and Pump Out the Oily Drain Tank	\$3,954.00
49	Wash Water Skid	\$2,585.52
50	Open and Drain the Detergent Tank	\$861.84
51	Open and Drain the Demineralized Water Tank	\$861.84
52	Empty the Demineralized Water Tank	\$861.84
53	Compressed Air	\$1,723.68
54	Empty Dessiccant Air Dryers and Vent	\$861.84
55	Open and Vent the Air Reciever	\$861.84
56	Miscelleaneous Piping	\$3,447.36
57	Open and Vent the Exhaust Frame Cooling Piping	\$861.84
58	Open and Vent the CT Air Processing Piping	\$861.84
59	Open and Vent the Inlet Air Heating Piping	\$861.84
60	Open and Vent the CT Air Processing Piping	\$861.84
61	Fire Protection Piping	\$3,428.24
62	Empty the CO2 Storage Tank	\$2,566.40
63	Open and Vent the Fire Protection Piping	\$861.84
64	Lube Oil System	\$7,718.32
65	Empty and Remove from Site the Lubricating Oil	\$5,132.80
66	Drain Lubricating Oil Piping	\$1,723.68
67	Open and Vent Lubricating Oil Piping	\$861.84
68	Water Treatment	\$9,338.88
69	Drain All Tanks and Vessels	\$1,723.68
70	Remove Resin from Vessels	\$2,585.52
71	Remove Chemicals	\$2,585.52
72	Open and Vent Vessels	\$861.84
73	Open and Vent the 2 Water Storage Tanks	\$861.84
74	Clean Neutralization Basin	\$720.48
75	Post Retirement Closure Activity	\$45,152.00
76	Post Retirement Closure Activity	\$45,152.00

Ralph Green Retirement

ID	Task Name	Duration	2012				2013			
			Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4
1	Ralph Green Retirement	150 days								
2	Pre-Retirement Activities	40 days								
3	Permitting Review	20 days								
4	Develop Detailed Retirement Plan	20 days								
5	Retirement	70 days								
6	Project Management During Retirement	70 days								
7	Project Management During Retirement	70 days								
8	Retirement Activities	70 days								
9	Electrical	22 days								
10	Medium and Low Voltage Drawout Switchgear	6 days								
11	De-energize all buses at the source.	1 day								
12	Open all circuit breakers.	1 day								
13	Rack all circuit breakers into the fully withdrawn, disconnected	1 day								
14	Verify that the closing/tripping springs are discharged.	2 days								
15	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each	1 day								
16	Motor Control Centers	3 days								
17	De-energize all buses at the source.	1 day								
18	Open all circuit breakers and disconnect switches.	1 day								
19	Remove all fuses in control circuits.	1 day								
20	Low-voltage Switchboards and Panelboards	2 days								
21	De-energize all buses at the source.	1 day								
22	Open all circuit breakers and disconnect switches.	1 day								
23	Oil-Filled Power Transformers	4 days								

Ralph Green Retirement

ID	Task Name	Duration	2012				2013					
			Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4		
24	De-energize all buses at the source.	1 day										
25	Open all circuit breakers and disconnect switches.	1 day										
26	De-energize all buses at the source.	1 day										
27	Open all circuit breakers and disconnect switches.	1 day										
28	Dry-type Power Transformers	2 days										
29	De-energize all transformer primaries and verify that the secondary is de-energized.	1 day										
30	De-energize all low-voltage AC or DC power sources for space heaters, cooling equipment, controls, etc. at the source and open circuit breakers or remove fuses at transformer end.	1 day										
31	Motors	5 days										
32	De-energize all primary power at the source.	1 day										
33	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	1 day										
34	Drain lube oil system (if applicable) and dispose of oil.	3 days										
35	Administration/Maintenance Building	5 days										
36	Secure Administration/Maintenance Bu	5 days										
37	Fuel Gas System	11 days										
38	Isolate Fuel Gas System	3 days										
39	Vent Fuel Gas Piping and Equipment	3 days										
40	Open and Vent Knock-Out Drum	1 day										
41	Drain, Open and Vent the Drain Tank	1 day										
42	Empty the Coalescing Filter	2 days										
43	Open and Vent Equipment on the CT Gas Valve Module	1 day										




Ralph Green Retirement

ID	Task Name	Duration	2012				2013				
			Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	
44	Lube Oil Cooling Water System	3 days									
45	Open and Drain the Water Side of the Lube Oil Coolers	2 days									
46	Open and Vent the Coolers and Expansion Tank	1 day									
47	Oily Drain Tank	3 days									
48	Open and Pump Out the Oily Drain Tank	3 days									
49	Wash Water Skid	3 days									
50	Open and Drain the Detergent Tank	1 day									
51	Open and Drain the Demineralized Water Tank	1 day									
52	Empty the Demineralized Water Tank	1 day									
53	Compressed Air	2 days									
54	Empty Dessiccant Air Dryers and Vent	1 day									
55	Open and Vent the Air Receiver	1 day									
56	Miscellaneous Piping	4 days									
57	Open and Vent the Exhaust Frame Cooling Piping	1 day									
58	Open and Vent the CT Air Processing Piping	1 day									
59	Open and Vent the Inlet Air Heating Piping	1 day									
60	Open and Vent the CT Air Processing Piping	1 day									
61	Fire Protection Piping	3 days									
62	Empty the CO2 Storage Tank	2 days									
63	Open and Vent the Fire Protection Piping	1 day									
64	Lube Oil System	6 days									
65	Empty and Remove from Site the Lubricating Oil	4 days									
66	Drain Lubricating Oil Piping	2 days									
67	Open and Vent Lubricating Oil Piping	1 day									
68	Water Treatment	11 days									



Ralph Green Retirement

ID	Task Name	Duration	2012				2013				
			Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	
69	Drain All Tanks and Vessels	2 days									
70	Remove Resin from Vessels	3 days									
71	Remove Chemicals	3 days									
72	Open and Vent Vessels	1 day									
73	Open and Vent the 2 Water Storage Tanks	1 day									
74	Clean Neutralization Basin	1 day									
75	Post Retirement Closure Activity	40 days									
76	Post Retirement Closure Activity	40 days									



Ralph Green Dismantlement

Owner Costs

Pre-Dismantlement Activities		\$892,760	
Overhead During Dismantlement		\$748,631	
Post-Dismantlement Activities		\$32,760	
Owner Costs Total*			\$1,674,151

Demolition General Contractor (DGC) Costs

Site Management		\$408,084	
Equipment Rental		\$694,855	
Consummables		\$693,242	
Scrap Crew(s)		\$182,507	
Dismantlement		\$542,291	
Contractor Direct Cost*	\$2,520,979		

Contractor Allowances

DGC Insurance	2.00%	\$50,420	
Contingency/Profit	15.00%	\$385,710	
Performance Bond	2.00%	\$59,142.17	

Contractor Costs Total: \$3,016,251

Total:			\$4,690,402
Owner Internal Costs:	5.00%		\$234,520
Owner Contingency:	25.00%		\$1,231,230
Ralph Green Dismantlement Opinion of Probable Cost:			\$6,156,152

*Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances
= \$4,195,130

Ralph Green Dismantlement

ID	Task Name	Cost
1	Ralph Green Dismantlement	\$4,195,133.68
2	Pre-Demolition Activities	\$892,760.32
3	Detailed Planning & Hire Owner's Engineer	\$104,441.28
4	Detailed Site Characterization Study	\$610,335.44
5	Hire Demolition general Contractor	\$167,184.00
6	KCP&L Prepares Unit for Dismantlement	\$10,799.60
7	Demolition Contractor Mobilizes on Sit	\$0.00
8	KCP&L Overhead during Dismantlement	\$748,631.04
9	KCP&L Project Manager	\$118,963.20
10	KCP&L Administrative Support	\$43,991.04
11	KCP&L Engineer	\$195,532.80
12	Owners Engineer Project Manager	\$58,368.00
13	Owners Engineer - Engineer	\$331,776.00
14	Demolition Contractor Overhead during Dismantlement	\$408,084.48
15	Demolition Contractor Project Manager	\$115,461.12
16	Demolition Contractor Safety Manager	\$102,804.48
17	Demolition Contractor Superintendent	\$189,818.88
18	Demolition Contractor Equipment Rental Cost	\$694,855.68
19	Equipment Rental	\$694,855.68
20	Demolition Contractor Consumables	\$693,242.88
21	Consumables	\$693,242.88
22	Scrap Crews	\$182,507.52
23	Crew to Handle Scrap Material(s)	\$182,507.52
24	Dismantlement	\$542,291.76
25	Electrical	\$107,481.60
26	Electrical Demolition of Equipment	\$107,481.60
27	Buildings	\$17,913.60
28	Remove Administration/Maintenance Building	\$17,913.60
29	Fuel Gas System	\$8,445.28
30	Remove all above grade fuel gas piping.	\$3,071.20
31	Gas Filter Skid	\$5,374.08
32	Lube Oil System	\$17,913.60
33	Lube Oil Piping	\$5,374.08
34	Lube Oil Pumps	\$5,374.08
35	Lube Oil Tanks	\$7,165.44
36	Compressed Air System	\$23,287.68
37	Compressed Air Piping	\$5,374.08
38	Compressors	\$8,956.80
39	Air Receiver	\$3,582.72
40	Dryer	\$5,374.08
41	Fire Protection	\$26,870.40
42	Fire Protection Piping	\$10,748.16
43	Firewater Tank	\$8,956.80
44	CO2 Storage Tank	\$7,165.44

Ralph Green Dismantlement


ID	Task Name	Cost
45	Wash Water Skid	\$14,330.88
46	Detergent Tank	\$7,165.44
47	Demineralized Water Tank	\$7,165.44
48	Miscellaneous Piping	\$25,079.04
49	Exhaust Frame Cooling Piping	\$7,165.44
50	CT Air Processing Piping	\$8,956.80
51	Inlet Air Heating Piping	\$8,956.80
52	Generator	\$0.00
53	Generator	\$0.00
54	Combustion Turbine	\$93,150.72
55	Inlet Heater	\$5,374.08
56	Inlet duct	\$10,748.16
57	Exhaust duct	\$14,330.88
58	Combustion Turbine	\$28,661.76
59	Combustion Turbine Foundation	\$16,122.24
60	Enclosure	\$17,913.60
61	CEMS	\$14,330.88
62	CEMS Building	\$7,165.44
63	CEMS Building Foundation	\$7,165.44
64	Stack	\$26,870.40
65	Stack	\$26,870.40
66	Demineralizer	\$23,287.68
67	Remove demineralizer vessels	\$3,582.72
68	Remove acid and caustic tanks	\$7,165.44
69	Remove hot water tank	\$3,582.72
70	Remove misc. demineralizer piping.	\$3,582.72
71	Remove 2 Demin. Water Storage Tanks	\$5,374.08
72	Site Prep	\$143,330.00
73	Final Grading and Drainage	\$143,330.00
74	Post Dismantlement Activities	\$32,760.00
75	Post Dismantlement Activities	\$32,760.00

Ralph Green Dismantlement

ID	Task Name	Duration	1st Quarter		1st Quarter	
			Jan	Jan	Jan	Jan
1	Ralph Green Dismantlement	319 days				
2	Pre-Demolition Activities	130 days				
3	Detailed Planning & Hire Owner's Engineer	3 mons				
4	Detailed Site Characterization Study	130 days				
5	Hire Demolition general Contractor	3 mons				
6	KCP&L Prepares Unit for Dismantlement	2 wks				
7	Demolition Contractor Mobilizes on Sit	5 days				
8	KCP&L Overhead during Dismantlement	192 days				
9	KCP&L Project Manager	192 days				
10	KCP&L Administrative Support	192 days				
11	KCP&L Engineer	192 days				
12	Owners Engineer Project Manager	192 days				
13	Owners Engineer - Engineer	192 days				
14	Demolition Contractor Overhead during Dismantlement	192 days				
15	Demolition Contractor Project Manager	192 days				
16	Demolition Contractor Safety Manager	192 days				
17	Demolition Contractor Superintendent	192 days				
18	Demolition Contractor Equipment Rental Cost	192 days				
19	Equipment Rental	192 days				
20	Demolition Contractor Consumables	192 days				
21	Consumables	192 days				
22	Scrap Crews	192 days				
23	Crew to Handle Scrap Material(s)	192 days				
24	Dismantlement	192 days				
25	Electrical	60 days				
26	Electrical Demolition of Equipment	60 days				
27	Buildings	10 days				
28	Remove Administration/Maintenance Building	10 days				
29	Fuel Gas System	8 days				
30	Remove all above grade fuel gas piping.	5 days				
31	Gas Filter Skid	3 days				

Ralph Green Dismantlement

ID	Task Name	Duration	1st Quarter		1st Quarter	
			Jan	Jan	Jan	Jan
32	Lube Oil System	10 days				
33	Lube Oil Piping	3 days				
34	Lube Oil Pumps	3 days				
35	Lube Oil Tanks	4 days				
36	Compressed Air System	13 days				
37	Compressed Air Piping	3 days				
38	Compressors	5 days				
39	Air Receiver	2 days				
40	Dryer	3 days				
41	Fire Protection	15 days				
42	Fire Protection Piping	6 days				
43	Firewater Tank	5 days				
44	CO2 Storage Tank	4 days				
45	Wash Water Skid	8 days				
46	Detergent Tank	4 days				
47	Demineralized Water Tank	4 days				
48	Miscellaneous Piping	14 days				
49	Exhaust Frame Cooling Piping	4 days				
50	CT Air Processing Piping	5 days				
51	Inlet Air Heating Piping	5 days				
52	Generator	6 days				
53	Generator	6 days				
54	Combustion Turbine	52 days				
55	Inlet Heater	3 days				
56	Inlet duct	6 days				
57	Exhaust duct	8 days				
58	Combustion Turbine	16 days				
59	Combustion Turbine Foundation	9 days				
60	Enclosure	10 days				
61	CEMS	8 days				
62	CEMS Building	4 days				
63	CEMS Building Foundation	4 days				



Ralph Green Dismantlement

ID	Task Name	Duration	1st Quarter		1st Quarter	
			Jan	Jan	Jan	Jan
64	Stack	15 days				
65	Stack	15 days				
66	Demineralizer	13 days				
67	Remove demineralizer vessels	2 days				
68	Remove acid and caustic tanks	4 days				
69	Remove hot water tank	2 days				
70	Remove misc. demineralizer piping.	2 days				
71	Remove 2 Demin. Water Storage Tanks	3 days				
72	Site Prep	20 days				
73	Final Grading and Drainage	20 days				
74	Post Dismantlement Activities	20 days				
75	Post Dismantlement Activities	20 days				

LAKE ROAD

LAKE ROAD STATION

The Lake Road Generating Station is a multi-unit facility that generates electricity from four steam turbine generators that receive steam from seven different boilers. These boilers burn either gas, distillate, or coal. These same boilers also produce steam that is sold to local steam customers. Lake Road also includes three combustion turbines that fire distillate (CTGs 5, 6, and 7) or natural gas (CTG 5).

Lake Road Boilers 1 and 2 are both package boilers rated at 85,000 lb/hr each. These boilers fire either natural gas or distillate and were placed into service in 1962.

Lake Road Boiler 3 is rated at 130,000 lb/hr, fires natural gas, and was placed into service in 1936.

Lake Road Boiler 4 is rated at 200,000 lb/hr, fires either natural gas or distillate, and was placed into service in 1951.

Lake Road Boiler 5 is rated at 250,000 lb/hr, fires either natural gas or coal, and was placed into service in 1959. This boiler has a precipitator for particulate control.

Lake Road Boiler 8 is rated at 250,000 lb/hr, fires either natural gas or distillate, and was placed into service in 2006.

Lake Road 4/6 has an SPP-accredited unit rating of 99 MW and was placed into service in 1967. This unit can fire either coal (using cyclone burners) or natural gas and has an electrostatic precipitator for particulate removal. River water is used for condenser cooling.

Lake Road Turbine Generator 1 has an SPP-accredited rating of 21.7 MW and was placed into service in 1951. This unit has a condensing turbine that uses a three-cell cooling tower for heat rejection.

Lake Road Turbine Generator 2 has an SPP-accredited rating of 27.3 MW and was placed into service in 1957. This unit has a condensing turbine that uses a four-cell cooling tower for heat rejection.

Lake Road Turbine Generator 3 has an SPP-accredited rating of 11.2 MW and was placed into service in 1962.

Lake Road Combustion Turbine (CT) 5 has an SPP-accredited rating of 63 MW and was placed into service in 1973. Lake Road CT 5 is comprised of a Westinghouse Model 501B combustion turbine set with a generator step-up transformer and auxiliary power transformer.

Lake Road Combustion Turbines 6 and 7 have an SPP-accredited rating of 42.7 MW and was placed into service in 1989 and 1990, respectively. Lake Road CTs 6 and 7 are comprised of P&W Model GG4A-7 combustion turbine set with a generator step-up transformer and auxiliary power transformer.

The Lake Road fuel yard has a main car unloading facility, a fuel storage and reclaim system, and a coal crusher facility that supplies coal to the units that can fire coal.

A detailed listing of the different equipment and systems included in each unit described above can be found in the attached retirement and dismantlement schedules included in this Appendix. The following is a detailed listing of the systems and equipment that are considered common to the Lake Road facilities.

COMMON

1. Administration building.
2. Fuel yard office building.
3. Butler building.
4. Dozer building.

5. Laboratory.
6. Guard shack.
4. Warehouses.
5. Non-Potable/Fire protection water tank.
6. Wells and low side water treatment.
8. Common fuel handling equipment.
9. 900 lb and 200 lb steam header system.
10. Fire water systems.
11. Stacks.
13. Low side feedwater system.

BOILER 1

Lake Road Boiler 1 Retirement

Owner Costs

Pre-Retirement Activities	\$25,969
Retirement Activities	\$52,440
Post-Retirement Activities	\$13,282

Owner Direct Total \$91,691

Owner Internal Costs 5.00% \$4,585

Owner Contingency: 25.00% \$24,069

Lake Road Boiler 1 Retirement Opinion of Probable Cost: \$120,344

Lake Road Boiler 1 Retirement

ID	Task Name	Cost
1	Lake Road Boiler 1 Retirement	\$91,691.28
2	Pre-Engineering	\$25,969.20
3	Permit review and engineering analysis and establish isolation points.	\$25,969.20
4	KCL&L Overhead Costs	\$17,348.80
5	KCP&L Retirement Manager	\$17,348.80
6	Equipment Rentals	\$5,877.76
7	Vacuum truck	\$5,877.76
8	Retirement	\$29,213.52
9	Electrical	\$10,037.04
10	Medium and Low Voltage Draw out Switchgear	\$2,679.84
11	De-energize all buses at the source.	\$446.64
12	Open all circuit breakers.	\$446.64
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	\$446.64
14	Verify that the closing/tripping springs are discharged.	\$446.64
15	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each breaker cubicle.	\$893.28
16	Motor Control Centers	\$1,786.56
17	De-energize all buses at the source.	\$446.64
18	Open all circuit breakers and disconnect switches.	\$446.64
19	Remove all fuses in control circuits.	\$893.28
20	Low-voltage Switchboards and Panelboards	\$893.28
21	De-energize all buses at the source.	\$446.64
22	Open all circuit breakers and disconnect switches.	\$446.64
23	Motors	\$4,677.36
24	De-energize all primary power at the source.	\$446.64
25	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	\$446.64
26	Drain lube oil system (if applicable) and dispose of oil.	\$3,784.08
27	Fuel Systems	\$3,784.08
28	Isolate gas lines from source, open and vent.	\$1,261.36
29	Isolate fuel oil lines from source, drain, open and vent.	\$2,522.72
30	Boiler Chemical Feed	\$1,261.36
31	Drain all chemical feed tanks.	\$1,261.36
32	Boiler	\$7,084.64
33	Open boiler doors.	\$880.96
34	Gas side - perform cleaning of the boiler and bottom ash system.	\$4,480.00
35	Drain boiler, drum, downcomers and headers.	\$842.72
36	Open drum doors.	\$880.96
37	Ductwork	\$5,360.96
38	Open ductwork doors.	\$880.96
39	Perform extensive cleaning of the ductwork.	\$4,480.00
40	Feedwater Piping	\$842.72

Lake Road Boiler 1 Retirement


ID	Task Name	Cost
41	Drain water from the system.	\$421.36
42	Leave open vents and drains.	\$421.36
43	Compressed Air System	\$842.72
44	Open vents and drains.	\$842.72
45	Post Retirement Activities	\$13,282.00
46	Post Retirement Activities	\$13,282.00

Lake Road Boiler 1 Retirement

ID	Task Name	Duration	4th Quarter	1st Quarter	2nd Quarter	3rd Quarter
1	Lake Road Boiler 1 Retirement	65 days				
2	Pre-Engineering	17 days				
3	Permit review and engineering analysis and establish isolation points.	17 days				
4	KCL&L Overhead Costs	28 days				
5	KCP&L Retirement Manager	28 days				
6	Equipment Rentals	28 days				
7	Vacuum truck	28 days				
8	Retirement	28 days				
9	Electrical	10 days				
10	Medium and Low Voltage Draw out Switchgear	3 days				
11	De-energize all buses at the source.	0.5 days				
12	Open all circuit breakers.	0.5 days				
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	0.5 days				
14	Verify that the closing/tripping springs are discharged.	0.5 days				
15	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each breaker cubicle.	1 day				
16	Motor Control Centers	2 days				
17	De-energize all buses at the source.	0.5 days				
18	Open all circuit breakers and disconnect switches.	0.5 days				
19	Remove all fuses in control circuits.	1 day				
20	Low-voltage Switchboards and Panelboards	1 day				
21	De-energize all buses at the source.	0.5 days				
22	Open all circuit breakers and disconnect switches.	0.5 days				
23	Motors	4 days				
24	De-energize all primary power at the source.	0.5 days				
25	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	0.5 days				
26	Drain lube oil system (if applicable) and dispose of oil.	3 days				

Lake Road Boiler 1 Retirement

ID	Task Name	Duration	4th Quarter	1st Quarter	2nd Quarter	3rd Quarter
27	Fuel Systems	3 days				
28	Isolate gas lines from source, open and vent.	1 day				
29	Isolate fuel oil lines from source, drain, open and vent.	2 days				
30	Boiler Chemical Feed	1 day				
31	Drain all chemical feed tanks.	1 day				
32	Boiler	7 days				
33	Open boiler doors.	1 day				
34	Gas side - perform cleaning of the boiler and bottom ash system.	4 days				
35	Drain boiler, drum, downcomers and headers.	1 day				
36	Open drum doors.	1 day				
37	Ductwork	5 days				
38	Open ductwork doors.	1 day				
39	Perform extensive cleaning of the ductwork.	4 days				
40	Feedwater Piping	1 day				
41	Drain water from the system.	0.5 days				
42	Leave open vents and drains.	0.5 days				
43	Compressed Air System	1 day				
44	Open vents and drains.	1 day				
45	Post Retirement Activities	20 days				
46	Post Retirement Activities	20 days				



Lake Road Boiler 1 Dismantlement

Owner Costs

Pre-Dismantlement Activities		\$412,728	
Overhead During Dismantlement		\$86,564	
Post-Dismantlement Activities		\$16,380	
Owner Costs Total*			\$515,672

Demolition General Contractor (DGC) Costs

Site Management		\$129,546	
Equipment Rental		\$307,618	
Consummables		\$306,904	
Scrap Crew(s)		\$304,531	
Dismantlement		\$493,684	
Contractor Direct Cost*	\$1,542,283		

Contractor Allowances

DGC Insurance	2.00%	\$30,846	
Contingency/Profit	15.00%	\$235,969	
Performance Bond	2.00%	\$36,181.96	

Contractor Costs Total: \$1,845,280

Total: \$2,360,952

Owner Internal Costs: 5.00% \$118,048

Owner Contingency: 25.00% \$619,750

Lake Road Boiler 1 Dismantlement Opinion of Probable Cost: \$3,098,749

*Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances
= \$2,057,955

Lake Road Boiler 1 Dismantlement		
ID	Task Name	Cost
1	Lake Road Boiler 1 Dismantlement	\$2,057,957.12
2	Pre-Dismantlement Activities	\$412,728.00
3	Detailed Characterization Study	\$234,744.40
4	Hire Demolition General Contractor	\$167,184.00
5	KCP&L Prepares Unit for Dismantlement	\$10,799.60
6	Demolition Contractor Mobilizes on Site	\$0.00
7	KCP&L Overhead during Dismantlement	\$86,564.00
8	KCP&L Engineer	\$86,564.00
9	Demolition Contractor Overhead during Dismantlement	\$129,546.80
10	Demolition Contractor Safety Manager	\$45,512.40
11	Demolition Contractor Superintendent	\$84,034.40
12	Demolition Contractor Equipment Rental Costs	\$307,618.40
13	Equipment Rental	\$307,618.40
14	Demolition Contractor Consumables	\$306,904.40
15	Consumables	\$306,904.40
16	Scrap Crew(s)	\$304,531.20
17	Crew to Handle Scrap Material(s)	\$304,531.20
18	Dismantlement Directs	\$493,684.32
19	Phase 1 Demolition	\$493,684.32
20	Electrical Demolition	\$71,654.40
21	Electrical Demolition Equipment	\$71,654.40
22	Critical Piping	\$3,582.72
23	Main Steam Piping	\$3,582.72
24	Fuel Systems (plant side)	\$7,165.44
25	Gas Piping and Valves	\$1,791.36
26	Fuel Oil Piping and Valves	\$1,791.36
27	Igniters	\$3,582.72
28	Chemical Feed Systems	\$5,374.08
29	Tanks	\$1,791.36
30	Pumps	\$1,791.36
31	Piping	\$1,791.36
32	Sampling Systems	\$10,017.12
33	Field Mounted Heat Exchangers	\$3,582.72
34	Piping	\$2,851.68
35	Sample Panel	\$3,582.72
36	Miscellaneous Equipment	\$8,956.80
37	Miscellaneous Equipment (including Fire Protection)	\$8,956.80
38	Boiler Equipment	\$71,654.40
39	Fans	\$17,913.60
40	Drums	\$17,913.60
41	Ductwork	\$35,827.20
42	Boiler Removal	\$143,308.80
43	Furnace	\$143,308.80
44	Boiler Steel Framing	\$100,316.16

Lake Road Boiler 1 Dismantlement

ID	Task Name	Cost
45	Framing	\$35,827.20
46	Bracing and Girts	\$35,827.20
47	Columns	\$28,661.76
48	Boiler Foundations	\$71,654.40
49	Equipment Foundation Demolition to Grade	\$71,654.40
50	Project Close-Out	\$16,380.00
51	Project Close-Out Activities	\$16,380.00

Lake Road Boiler 1 Dismantlement

ID	Task Name	Duration	2012				2013
			H2	H1	H2	H1	
1	Lake Road Boiler 1 Dismantlement	220 days					
2	Pre-Dismantlement Activities	125 days					
3	Detailed Characterization Study	50 days					
4	Hire Demolition General Contractor	3 mons					
5	KCP&L Prepares Unit for Dismantlement	2 wks					
6	Demolition Contractor Mobilizes on Site	5 days					
7	KCP&L Overhead during Dismantlement	85 days					
8	KCP&L Engineer	85 days					
9	Demolition Contractor Overhead during Dismantlement	85 days					
10	Demolition Contractor Safety Manager	85 days					
11	Demolition Contractor Superintendent	85 days					
12	Demolition Contractor Equipment Rental Costs	85 days					
13	Equipment Rental	85 days					
14	Demolition Contractor Consumables	85 days					
15	Consumables	85 days					
16	Scrap Crew(s)	85 days					
17	Crew to Handle Scrap Material(s)	85 days					
18	Dismantlement Directs	85 days					
19	Phase 1 Demolition	85 days					
20	Electrical Demolition	40 days					
21	Electrical Demolition Equipment	40 days					
22	Critical Piping	2 days					
23	Main Steam Piping	2 days					
24	Fuel Systems (plant side)	4 days					
25	Gas Piping and Valves	1 day					
26	Fuel Oil Piping and Valves	1 day					
27	Igniters	2 days					
28	Chemical Feed Systems	3 days					
29	Tanks	1 day					
30	Pumps	1 day					
31	Piping	1 day					
32	Sampling Systems	7 days					

Lake Road Boiler 1 Dismantlement

ID	Task Name	Duration	2012		2013	
			H2	H1	H2	H1
33	Field Mounted Heat Exchangers	2 days				
34	Piping	3 days				
35	Sample Panel	2 days				
36	Miscellaneous Equipment	5 days				
37	Miscellaneous Equipment (including Fire Protec	5 days				
38	Boiler Equipment	20 days				
39	Fans	5 days				
40	Drums	5 days				
41	Ductwork	10 days				
42	Boiler Removal	20 days				
43	Furnace	20 days				
44	Boiler Steel Framing	14 days				
45	Framing	5 days				
46	Bracing and Girts	5 days				
47	Columns	4 days				
48	Boiler Foundations	10 days				
49	Equipment Foundation Demolition to Grade	10 days				
50	Project Close-Out	10 days				
51	Project Close-Out Activities	10 days				

BOILER 2

Lake Road Boiler 2 Retirement

Owner Costs

Pre-Retirement Activities	\$25,969
Retirement Activities	\$52,440
Post-Retirement Activities	\$13,282

Owner Direct Total \$91,691

Owner Internal Costs 5.00% \$4,585

Owner Contingency: 25.00% \$24,069

Lake Road Boiler 2 Retirement Opinion of Probable Cost: \$120,344

Lake Road Boiler 2 Retirement


ID	Task Name	Cost
1	Lake Road Boiler 2 Retirement	\$91,691.28
2	Pre-Engineering	\$25,969.20
3	Permit review and engineering analysis and establish isolation points.	\$25,969.20
4	KCL&L Overhead Costs	\$17,348.80
5	KCP&L Retirement Manager	\$17,348.80
6	Equipment Rentals	\$5,877.76
7	Vacuum truck	\$5,877.76
8	Retirement	\$29,213.52
9	Electrical	\$10,037.04
10	Medium and Low Voltage Draw out Switchgear	\$2,679.84
11	De-energize all buses at the source.	\$446.64
12	Open all circuit breakers.	\$446.64
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	\$446.64
14	Verify that the closing/tripping springs are discharged.	\$446.64
15	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each breaker cubicle.	\$893.28
16	Motor Control Centers	\$1,786.56
17	De-energize all buses at the source.	\$446.64
18	Open all circuit breakers and disconnect switches.	\$446.64
19	Remove all fuses in control circuits.	\$893.28
20	Low-voltage Switchboards and Panelboards	\$893.28
21	De-energize all buses at the source.	\$446.64
22	Open all circuit breakers and disconnect switches.	\$446.64
23	Motors	\$4,677.36
24	De-energize all primary power at the source.	\$446.64
25	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	\$446.64
26	Drain lube oil system (if applicable) and dispose of oil.	\$3,784.08
27	Fuel Systems	\$3,784.08
28	Isolate gas lines from source, open and vent.	\$1,261.36
29	Isolate fuel oil lines from source, drain, open and vent.	\$2,522.72
30	Boiler Chemical Feed	\$1,261.36
31	Drain all chemical feed tanks.	\$1,261.36
32	Boiler	\$7,084.64
33	Open boiler doors.	\$880.96
34	Gas side - perform cleaning of the boiler and bottom ash system.	\$4,480.00
35	Drain boiler, drum, downcomers and headers.	\$842.72
36	Open drum doors.	\$880.96
37	Ductwork	\$5,360.96
38	Open ductwork doors.	\$880.96
39	Perform extensive cleaning of the ductwork.	\$4,480.00
40	Feedwater Piping	\$842.72

Lake Road Boiler 2 Retirement

ID	Task Name	Cost
41	Drain water from the system.	\$421.36
42	Leave open vents and drains.	\$421.36
43	Compressed Air System	\$842.72
44	Open vents and drains.	\$842.72
45	Post Retirement Activities	\$13,282.00
46	Post Retirement Activities	\$13,282.00

Lake Road Boiler 2 Retirement

ID	Task Name	Duration	4th Quarter	1st Quarter	2nd Quarter	3rd Quarter
1	Lake Road Boiler 2 Retirement	65 days				
2	Pre-Engineering	17 days				
3	Permit review and engineering analysis and establish isolation points.	17 days				
4	KCL&L Overhead Costs	28 days				
5	KCP&L Retirement Manager	28 days				
6	Equipment Rentals	28 days				
7	Vacuum truck	28 days				
8	Retirement	28 days				
9	Electrical	10 days				
10	Medium and Low Voltage Draw out Switchgear	3 days				
11	De-energize all buses at the source.	0.5 days				
12	Open all circuit breakers.	0.5 days				
13	Rack all circuit breakers into the fully withdrawn, disconnected position.	0.5 days				
14	Verify that the closing/tripping springs are discharged.	0.5 days				
15	De-energize control power and auxiliary power circuits of each circuit breaker at the source and by opening control power circuit breakers or removing fuses in each breaker cubicle.	1 day				
16	Motor Control Centers	2 days				
17	De-energize all buses at the source.	0.5 days				
18	Open all circuit breakers and disconnect switches.	0.5 days				
19	Remove all fuses in control circuits.	1 day				
20	Low-voltage Switchboards and Panelboards	1 day				
21	De-energize all buses at the source.	0.5 days				
22	Open all circuit breakers and disconnect switches.	0.5 days				
23	Motors	4 days				
24	De-energize all primary power at the source.	0.5 days				
25	De-energize all low-voltage power sources for space heaters or other auxiliary equipment at the source.	0.5 days				
26	Drain lube oil system (if applicable) and dispose of oil.	3 days				



Lake Road Boiler 2 Retirement

ID	Task Name	Duration	4th Quarter	1st Quarter	2nd Quarter	3rd Quarter	
27	Fuel Systems	3 days					
28	Isolate gas lines from source, open and vent.	1 day					
29	Isolate fuel oil lines from source, drain, open and vent.	2 days					
30	Boiler Chemical Feed	1 day					
31	Drain all chemical feed tanks.	1 day					
32	Boiler	7 days					
33	Open boiler doors.	1 day					
34	Gas side - perform cleaning of the boiler and bottom ash system.	4 days					
35	Drain boiler, drum, downcomers and headers.	1 day					
36	Open drum doors.	1 day					
37	Ductwork	5 days					
38	Open ductwork doors.	1 day					
39	Perform extensive cleaning of the ductwork.	4 days					
40	Feedwater Piping	1 day					
41	Drain water from the system.	0.5 days					
42	Leave open vents and drains.	0.5 days					
43	Compressed Air System	1 day					
44	Open vents and drains.	1 day					
45	Post Retirement Activities	20 days					
46	Post Retirement Activities	20 days					

Lake Road Boiler 2 Dismantlement

Owner Costs

Pre-Dismantlement Activities		\$412,728	
Overhead During Dismantlement		\$86,564	
Post-Dismantlement Activities		\$16,380	
Owner Costs Total*			\$515,672

Demolition General Contractor (DGC) Costs

Site Management		\$129,546	
Equipment Rental		\$307,618	
Consummables		\$306,904	
Scrap Crew(s)		\$304,531	
Dismantlement		\$493,684	
Contractor Direct Cost*	\$1,542,283		

Contractor Allowances

DGC Insurance	2.00%	\$30,846	
Contingency/Profit	15.00%	\$235,969	
Performance Bond	2.00%	\$36,181.96	

Contractor Costs Total: \$1,845,280

Total: \$2,360,952

Owner Internal Costs: 5.00% \$118,048

Owner Contingency: 25.00% \$619,750

Lake Road Boiler 2 Dismantlement Opinion of Probable Cost: \$3,098,749

*Owner Costs Total + Contractor Direct Costs = Manpower Loaded Schedule Total w/o Contractor Allowances
= \$2,057,955