

**DECOMMISSIONING COST ANALYSIS**  
**for the**  
**WOLF CREEK GENERATING STATION**



*prepared for the*

**Wolf Creek Nuclear Operating Corporation**


*prepared by*

**TLG Services, Inc.**  
**Bridgewater, Connecticut**

**August 2005**

**APPROVALS**

**Project Manager**

  
\_\_\_\_\_  
William A. Cloutier, Jr.

08/26/05

Date


**Project Engineer**

  
\_\_\_\_\_  
Thomas J. Garrett

08/29/05

Date


**Technical Manager**

  
\_\_\_\_\_  
Geoffrey M. Griffiths

08/29/05

Date

**Quality Assurance Manager**

  
\_\_\_\_\_  
Thomas L. Williamson

8/29/05

Date

## **TABLE OF CONTENTS**

<b><u>SECTION</u></b>	<b><u>PAGE</u></b>
EXECUTIVE SUMMARY .....	vii-xiv
1. INTRODUCTION .....	1-1
1.1 Objectives of Study .....	1-1
1.2 Site Description.....	1-2
1.3 Regulatory Guidance .....	1-2
1.3.1 Nuclear Waste Policy Act.....	1-4
1.3.2 Low-Level Radioactive Waste Acts .....	1-6
1.3.3 Radiological Criteria for License Termination.....	1-6
2. DECOMMISSIONING ALTERNATIVES .....	2-1
2.1 DECON.....	2-1
2.1.1 Period 1 - Preparations .....	2-2
2.1.2 Period 2 - Decommissioning Operations.....	2-4
2.1.3 Period 3 - Site Restoration .....	2-7
2.2 SAFSTOR .....	2-8
2.2.1 Period 1 - Preparations .....	2-9
2.2.2 Period 2 - Dormancy.....	2-10
2.2.3 Periods 3 and 4 - Delayed Decommissioning.....	2-11
2.2.4 Period 5 - Site Restoration .....	2-12
3. COST ESTIMATE.....	3-1
3.1 Basis of Estimate .....	3-1
3.2 Methodology .....	3-1
3.3 Financial Components of the Cost Model .....	3-3
3.3.1 Contingency .....	3-3
3.3.2 Financial Risk.....	3-5
3.4 Site-Specific Considerations.....	3-7
3.4.1 Spent Fuel Management.....	3-7
3.4.2 Reactor Vessel and Internal Components .....	3-9
3.4.3 Primary System Components.....	3-10
3.4.4 Main Turbine and Condenser.....	3-11
3.4.5 Transportation Methods .....	3-11
3.4.6 Low-Level Radioactive Waste Disposal .....	3-12
3.4.7 Site Conditions Following Decommissioning .....	3-13

**TABLE OF CONTENTS**  
(continued)

<b><u>SECTION</u></b>	<b><u>PAGE</u></b>
3.5 Assumptions.....	3-13
3.5.1 Estimating Basis .....	3-13
3.5.2 Labor Costs .....	3-14
3.5.3 Design Conditions.....	3-14
3.5.4 General.....	3-15
3.6 Cost Estimate Summary .....	3-17
4. SCHEDULE ESTIMATE .....	4-1
4.1 Schedule Estimate Assumptions .....	4-1
4.2 Project Schedule.....	4-2
5. RADIOACTIVE WASTES .....	5-1
6. RESULTS .....	6-1
7. REFERENCES.....	7-1

**TABLES**

Summary of Decommissioning Cost Elements, DECON .....	xiii
Summary of Decommissioning Cost Elements, SAFSTOR.....	xiv
3.1 Schedule of DECON Expenditures.....	3-19
3.1a Schedule of DECON Expenditures, License Termination .....	3-20
3.1b Schedule of DECON Expenditures, Spent Fuel Management.....	3-21
3.1c Schedule of DECON Expenditures, Site Restoration.....	3-22
3.2 Schedule of SAFSTOR Expenditures .....	3-23
3.2a Schedule of SAFSTOR Expenditures, License Termination.....	3-25
3.2b Schedule of SAFSTOR Expenditures, Spent Fuel Management .....	3-27
3.2c Schedule of SAFSTOR Expenditures, Site Restoration .....	3-29
5.1 Decommissioning Waste Summary, DECON .....	5-3
5.2 Decommissioning Waste Summary, SAFSTOR.....	5-4
6.1 Summary of Decommissioning Cost Elements, DECON .....	6-4
6.2 Summary of Decommissioning Cost Elements, SAFSTOR.....	6-5

**TABLE OF CONTENTS**  
(continued)

<b><u>SECTION</u></b>	<b><u>PAGE</u></b>
-----------------------	--------------------

**FIGURES**

4.1	Activity Schedule .....	4-3
4.2	Decommissioning Timelines .....	4-4

**APPENDICES**

A.	Unit Cost Factor Development.....	A-1
B.	Unit Cost Factor Listing.....	B-1
C.	Detailed Cost Analysis, DECON.....	C-1
D.	Detailed Cost Analysis, SAFSTOR .....	D-1

**REVISION LOG**

<b>No.</b>	<b>CRA No.</b>	<b>Date</b>	<b>Item Revised</b>	<b>Reason for Revision</b>
0		08-29-05		Original Issue

## **EXECUTIVE SUMMARY**

This report presents estimates of the cost to decommission the Wolf Creek Generating Station (Wolf Creek) for the selected decommissioning scenarios following the scheduled cessation of plant operations. The analysis relies upon site-specific, technical information from an evaluation prepared in 2002,<sup>[1]</sup> updated to reflect current assumptions pertaining to the disposition of the nuclear unit and relevant industry experience in undertaking such projects. The current estimates are designed to provide the Wolf Creek Nuclear Operating Corporation (WCNOC) and its owners with sufficient information to assess its financial obligations, as they pertain to the eventual decommissioning of the nuclear unit.

The currently projected cost to decommission the station, assuming the DECON alternative, is estimated at \$517.6 million, as reported in 2005 dollars. An estimate for a SAFSTOR alternative is also provided. The estimates are based on numerous fundamental assumptions, including regulatory requirements, project contingencies, low-level radioactive waste disposal practices, high-level radioactive waste management options, and site restoration requirements. The estimates incorporate a minimum cooling period of approximately 5½ years for the spent fuel that resides in the storage pool when operations cease. During this period, it is assumed the Department of Energy (DOE) will complete the transfer of the residual spent fuel inventory to a DOE repository. The estimates also include the dismantling of non-essential structures and limited restoration of the site.

### **Alternatives and Regulations**

The Nuclear Regulatory Commission (NRC or Commission) provided initial decommissioning requirements in its rule adopted on June 27, 1988.<sup>[2]</sup> In this rule, the NRC set forth financial criteria for decommissioning licensed nuclear power facilities. The regulations addressed planning needs, timing, funding methods, and environmental review requirements for decommissioning. The rule also defined three decommissioning alternatives as being acceptable to the NRC: DECON, SAFSTOR, and ENTOMB.

---

<sup>1</sup> "Decommissioning Cost Analysis for the Wolf Creek Generating Station," Document No. W11-1442-002, Rev. 0, TLG Services, Inc., August 2002.

<sup>2</sup> U.S. Code of Federal Regulations, Title 10, Parts 30, 40, 50, 51, 70 and 72 "General Requirements for Decommissioning Nuclear Facilities," Nuclear Regulatory Commission, Federal Register Volume 53, Number 123 (p 24018 et seq.), June 27, 1988.

DECON is defined as "the alternative in which the equipment, structures, and portions of a facility and site containing radioactive contaminants are removed or decontaminated to a level that permits the property to be released for unrestricted use shortly after cessation of operations."<sup>[3]</sup>

SAFSTOR is defined as "the alternative in which the nuclear facility is placed and maintained in a condition that allows the nuclear facility to be safely stored and subsequently decontaminated (deferred decontamination) to levels that permit release for unrestricted use."<sup>[4]</sup> Decommissioning is to be completed within 60 years, although longer time periods will be considered when necessary to protect public health and safety.

ENTOMB is defined as "the alternative in which radioactive contaminants are encased in a structurally long-lived material, such as concrete; the entombed structure is appropriately maintained and continued surveillance is carried out until the radioactive material decays to a level permitting unrestricted release of the property."<sup>[5]</sup> As with the SAFSTOR alternative, decommissioning is currently required to be completed within 60 years.

The 60-year restriction has limited the practicality for the ENTOMB alternative at commercial reactors that generate significant amounts of long-lived radioactive material. In 1997, the Commission directed its staff to re-evaluate this alternative and identify the technical requirements and regulatory actions that would be necessary for entombment to become a viable option. The resulting evaluation provided several recommendations, however, rulemaking has been deferred pending the completion of additional research studies, *e.g.*, on engineered barriers.

In 1996, the NRC published revisions to the general requirements for decommissioning nuclear power plants to clarify ambiguities and codify procedures and terminology as a means of enhancing efficiency and uniformity in the decommissioning process.<sup>[6]</sup> The amendments allow for greater public participation and better define the transition process from operations to decommissioning.

---

<sup>3</sup> Ibid. Page FR24022, Column 3.

<sup>4</sup> Ibid.

<sup>5</sup> Ibid. Page FR24023, Column 2.

<sup>6</sup> U.S. Code of Federal Regulations, Title 10, Parts 2, 50, and 51, "Decommissioning of Nuclear Power Reactors," Nuclear Regulatory Commission, Federal Register Volume 61, (p 39278 et seq.), July 29, 1996.



Regulatory Guide 1.184, issued in July 2000, further described the methods and procedures acceptable to the NRC staff for implementing the requirements of the 1996 revised rule relating to the initial activities and major phases of the decommissioning process. The costs and schedules presented in this analysis follow the general guidance and processes described in the amended regulations. The format and content of the estimates are also consistent with the recommendations of Regulatory Guide 1.202, issued in February 2005.<sup>[7]</sup>

### Methodology

The methodology used to develop the estimates described within this document follows the basic approach originally presented in the cost estimating guidelines<sup>[8]</sup> developed by the Atomic Industrial Forum (now Nuclear Energy Institute). This reference describes a unit factor method for determining decommissioning activity costs. The unit factors used in this analysis incorporate site-specific costs and the latest available information on worker productivity in decommissioning.

An activity duration critical path is used to determine the total decommissioning program schedule. The schedule is relied upon in calculating the carrying costs, which include program management, administration, field engineering, equipment rental, and support services such as quality control and security. This systematic approach for assembling decommissioning estimates ensures a high degree of confidence in the reliability of the resulting cost.

### Contingency

Consistent with cost estimating practice, contingencies are applied to the decontamination and dismantling costs developed as "specific provision for unforeseeable elements of cost within the defined project scope, particularly important where previous experience relating estimates and actual costs has shown that unforeseeable events which will increase costs are likely to occur."<sup>[9]</sup> The cost elements in the estimates are based on ideal conditions; therefore, the types of unforeseeable events that are almost certain to occur in decommissioning, based on industry experience, are addressed through a percentage contingency applied on a

---

<sup>7</sup> "Standard Format and Content of Decommissioning Cost Estimates of Decommissioning Cost Estimates for Nuclear Power Reactors," Regulatory Guide 1.202, U.S. Nuclear Regulatory Commission, February 2005.

<sup>8</sup> T.S. LaGuardia et al., "Guidelines for Producing Commercial Nuclear Power Plant Decommissioning Cost Estimates," AIF/NESP-036, May 1986.

<sup>9</sup> Project and Cost Engineers' Handbook, Second Edition, American Association of Cost Engineers, Marcel Dekker, Inc., New York, New York, p. 239.

line-item basis. This contingency factor is a nearly universal element in all large-scale construction and demolition projects. It should be noted that contingency, as used in this analysis, does not account for price escalation and inflation in the cost of decommissioning over the remaining operating life of the station.

The use and role of contingency within decommissioning estimates is not a safety factor issue. Safety factors provide additional security and address situations that may never occur. Contingency funds, by contrast, are expected to be fully expended throughout the program. Inclusion of contingency is necessary to provide assurance that sufficient funding will be available to accomplish the intended tasks.

### Low-Level Radioactive Waste Disposal

The contaminated and activated material generated in the decontamination and dismantling of a commercial nuclear reactor is classified as low-level (radioactive) waste, although not all of the material is suitable for “shallow-land” disposal. With the passage of the “Low-Level Radioactive Waste Policy Act” in 1980,<sup>[10]</sup> and its Amendments of 1985,<sup>[11]</sup> the states became ultimately responsible for the disposition of low-level radioactive waste generated within their own borders.

WCNOC is currently able to access the disposal facility in Barnwell, South Carolina. However, in June 2000, South Carolina formally joined with Connecticut and New Jersey to form the Atlantic Compact. The legislation provides for South Carolina to gradually limit access to the Barnwell facility, with only Atlantic Compact members having access to the facility after mid-year 2008. Despite the closing of one of the two currently accessible commercial disposal sites, it is reasonable to assume that additional disposal capacity will be available to support reactor decommissioning, particularly for the isolation of the more highly radioactive material that is not suitable for disposal elsewhere. However, for estimating purposes, and as a proxy for future disposal facilities, waste disposal costs are estimated using available pricing schedules for the currently operating facilities, *i.e.*, at Barnwell and the Envirocare facility in Utah.

### High-Level Radioactive Waste Management

Congress passed the “Nuclear Waste Policy Act”<sup>[12]</sup> (NWPA) in 1982, assigning the responsibility to the DOE for disposal of the spent nuclear fuel created by the

---

<sup>10</sup> “Low-Level Radioactive Waste Policy Act of 1980,” Public Law 96-573, 1980.

<sup>11</sup> “Low-Level Radioactive Waste Policy Amendments Act of 1985,” Public Law 99-240, 1986.

<sup>12</sup> “Nuclear Waste Policy Act of 1982 and Amendments,” U.S. Department of Energy’s Office of Civilian Radioactive Management, 1982.

commercial nuclear generating plants. Two permanent disposal facilities were envisioned, as well as an interim storage facility. To recover the cost, the legislation created a Nuclear Waste Fund through which money is collected from the sale of electricity generated by the power plants. The NWPA, along with the individual disposal contracts with the utilities, specified that the DOE was to begin accepting spent fuel by January 31, 1998.

Since the original legislation, the DOE has announced several delays in the program schedule. By January 1998, the DOE had failed to initiate the disposal of spent nuclear fuel and high level waste, as required by the NWPA and the utility contracts. As a result, utilities have initiated legal action against the DOE. While legal actions continue, the DOE has no plans to receive spent fuel prior to completing the construction of its geologic repository.

Operation of DOE's yet-to-be constructed repository is contingent upon the review and approval of the facility's license application by the NRC, the successful resolution of pending litigation, and the development of a national transportation system. In 2005, the DOE stated that operations at the repository would not begin before 2012. The DOE has no plans for receiving spent fuel from commercial nuclear plant sites prior to this date and startup operations may be phased in, creating additional delays. However, for estimating purposes, WCNOG has assumed that the high-level waste repository, or some interim storage facility, will be fully operational prior to the scheduled cessation of plant operations in 2025.

The NRC requires that licensees establish a program to manage and provide funding for the caretaking of all irradiated fuel at the reactor site until title of the fuel is transferred to the DOE.<sup>[13]</sup> For estimating purposes, WCNOG has assumed that all spent fuel will be removed to the DOE high-level waste repository within 5½ years after shutdown. Interim storage of the fuel, until the DOE has completed the transfer, will be in the pool located in the fuel building. The pool will be isolated, allowing WCNOG to proceed with decommissioning (or safe-storage preparations) in the shortest time possible.

At shutdown, the spent fuel pool is expected to be at capacity. Over the next 5½ years the assemblies will be packaged into multipurpose canisters for transfer to the final repository. It is assumed that the 5½ years also provides the necessary cooling period for the final core to meet DOE's transport system requirements for decay heat.

---

<sup>13</sup> "Domestic Licensing of Production and Utilization Facilities," U.S. Code of Federal Regulations, Title 10, Part 50.54 (bb).

### Site Restoration

The efficient removal of the contaminated materials at the site may result in damage to many of the site structures. Blasting, coring, drilling, and the other decontamination activities will substantially damage power block structures, potentially weakening the footings and structural supports. Prompt demolition once the license is terminated is clearly the most appropriate and cost-effective option. It is unreasonable to anticipate that these structures would be repaired and preserved after the radiological contamination is removed. The cost to dismantle site structures with a work force already mobilized is more efficient and less costly than if the process were deferred. Experience at shutdown generating stations has shown that plant facilities quickly degrade without maintenance, adding additional expense and creating potential hazards to the public and the demolition work force. Consequently, this analysis assumes that non-essential site structures within the restricted access area are removed to a nominal depth of three feet below the local grade level wherever possible. The site is then backfilled, graded and stabilized.

### Summary

The costs to decommission Wolf Creek are evaluated for both the DECON and SAFSTOR decommissioning alternatives. Regardless of the timing of the decommissioning activities, the estimates assume the eventual removal of all the contaminated and activated plant components and structural materials, such that the facility operator may then have unrestricted use of the site with no further requirement for an operating license. Decommissioning will be accomplished within the 60-year period required by current NRC regulations.

The scenarios analyzed for the purpose of generating the estimates are described in Section 2. The assumptions are presented in Section 3, along with schedules of annual expenditures. The major cost contributors are identified in Section 6, with detailed activity costs, waste volumes, and associated manpower requirements delineated in Appendices C and D. Cost summaries for the two scenarios are provided at the end of this section for the major cost components.

**SUMMARY OF DECOMMISSIONING COST ELEMENTS  
DECON**

(thousands of 2005 dollars)

<b>Cost Element</b>	<b>Total</b>
Decontamination	12,139
Removal	89,518
Packaging	12,276
Transportation	7,780
Waste Disposal	77,162
Off-site Waste Processing	24,006
Program Management <sup>[1]</sup>	219,348
Spent Fuel Pool Isolation	9,900
Spent Fuel Related	25,236
Insurance and Regulatory Fees	7,236
Energy	9,173
Characterization and Licensing Surveys	8,153
Property Taxes	9,711
Miscellaneous Equipment / Site Services	5,963
Total <sup>[2]</sup>	517,601
NRC License Termination	436,860
Spent Fuel Management <sup>[3]</sup>	25,236
Site Restoration	55,506
Total <sup>[2]</sup>	517,601

<sup>[1]</sup> Includes engineering and security

<sup>[2]</sup> Columns may not add due to rounding

<sup>[3]</sup> Includes spent fuel loading/packaging costs

**SUMMARY OF DECOMMISSIONING COST ELEMENTS  
SAFSTOR**  
(thousands of 2005 dollars)

<b>Cost Element</b>	<b>Total</b>
Decontamination	9,863
Removal	89,768
Packaging	10,162
Transportation	5,556
Waste Disposal	50,514
Off-site Waste Processing	27,928
Program Management <sup>[1]</sup>	325,335
Spent Fuel Pool Isolation	9,900
Spent Fuel Related	25,236
Insurance and Regulatory Fees	45,165
Energy	18,818
Characterization and Licensing Surveys	9,561
Property Taxes	16,548
Miscellaneous Equipment / Site Services	19,119
Total <sup>[2]</sup>	663,474
 NRC License Termination	 559,577
Spent Fuel Management <sup>[3]</sup>	48,599
Site Restoration	55,297
Total <sup>[2]</sup>	663,474

<sup>[1]</sup> Includes engineering and security

<sup>[2]</sup> Columns may not add due to rounding

<sup>[3]</sup> Includes fuel loading/packaging costs

## **1. INTRODUCTION**

This report presents estimates of the costs to decommission the Wolf Creek Generating Station (Wolf Creek) following a scheduled cessation of plant operations. The supporting analysis was designed to provide the Wolf Creek Nuclear Operating Corporation (WCNOC), the plant's operator, and its owners: Kansas Gas and Electric Company, a wholly owned subsidiary of Westar Energy, Inc. (Westar), Kansas City Power & Light Company (KCPL), and Kansas Electric Power Cooperative, Inc. (KEPCo), with sufficient information to assess their financial obligations, as they pertain to the eventual decommissioning of the nuclear station. It is not a detailed engineering document, but a financial analysis prepared in advance of the detailed engineering that will be required to carry out the decommissioning.

### **1.1 OBJECTIVES OF STUDY**

The objectives of this study are to prepare comprehensive estimates of the costs to decommission Wolf Creek, to provide a sequence or schedule for the associated activities, and to develop waste stream projections from the decontamination and dismantling activities.

An operating license was issued for Wolf Creek in June of 1985. For the purposes of this study, the final shutdown date (license expiration) is projected to be March of 2025, based upon a 40 year operating life. This date was used as input to scheduling the decommissioning activities.

We understand that for ratemaking purposes, the Kansas Corporation has directed the three owner companies to assume that Wolf Creek will continue to operate for an additional twenty years, and that the Missouri Public Service Commission has taken steps in that direction for Kansas City Power & Light Company in Missouri. We also understand that WCNOC is preparing an application to the NRC to renew the Wolf Creek operating license for an additional twenty years. Based on WCNOC's announced September 2006 application filing date and an approximate two year time period for the NRC to process the application, one could speculate that WCNOC might receive permission to extend its operating license in late 2008. Nevertheless, for purposes of this study, it is appropriate to retain the 2025 decommissioning date until such time as WCNOC actually receives a license extension.

## **1.2 SITE DESCRIPTION**

The Wolf Creek site is located approximately 3.5 miles northeast of the town of Burlington, in Coffey County, Kansas, approximately 75 miles southwest of Kansas City, Kansas. The site is on the east side of a man-made lake formed by impounding Wolf Creek. The station is an 1,170 MWe (nominal) pressurized water reactor with supporting facilities.

Westinghouse Electric Company designed the Nuclear Steam Supply System (NSSS). The system consists of a pressurized water reactor with four independent primary coolant loops, each of which contains a reactor coolant pump and a steam generator. An electrically heated pressurizer and connecting piping complete the system. The NSSS is rated at a thermal power level of 3,579 MWt (3,565 MWt reactor core plus 14 MWt for reactor coolant pumps), with a corresponding turbine-generator gross output of 1,214 MWe. The system is housed within a containment structure, a pre-stressed, post-tensioned concrete structure with cylindrical wall, a hemispherical dome, and a flat foundation slab. The wall and dome form a pre-stressed post-tensioned system. The inside surface of the structure is covered with a carbon steel liner, providing a leak tight membrane.

A power conversion system converts heat produced in the reactor to electrical energy. This system converts the thermal energy of the steam into mechanical shaft power and then into electrical energy. The turbine-generator is a tandem-compound, six-flow, four element, 1800-rpm unit. The unit consists of one high pressure and three low-pressure turbine elements driving a directly coupled generator. The turbine is operated in a closed feedwater cycle that condenses the steam; the feedwater is returned to the steam generators. Heat rejected in the main condensers is removed by the circulating water system.

The circulating water system supplies cooling water to the main condenser, condensing the steam exhausted from the turbine. A large cooling lake provides the heat sink required for removal of waste heat in the power plant's thermal cycle.

## **1.3 REGULATORY GUIDANCE**

The Nuclear Regulatory Commission (NRC or Commission) provided initial decommissioning requirements in its rule "General Requirements for



Decommissioning Nuclear Facilities," issued in June 1988.<sup>[1]</sup>\* This rule set forth financial criteria for decommissioning licensed nuclear power facilities. The regulation addressed decommissioning planning needs, timing, funding methods, and environmental review requirements. The intent of the rule was to ensure that decommissioning would be accomplished in a safe and timely manner and that adequate funds would be available for this purpose. Subsequent to the rule, the NRC issued Regulatory Guide 1.159, "Assuring the Availability of Funds for Decommissioning Nuclear Reactors,"<sup>[2]</sup> which provided additional guidance to the licensees of nuclear facilities on the financial methods acceptable to the NRC staff for complying with the requirements of the rule. The regulatory guide addressed the funding requirements and provided guidance on the content and form of the financial assurance mechanisms indicated in the rule.

The rule defined three decommissioning alternatives as being acceptable to the NRC: DECON, SAFSTOR, and ENTOMB. The DECON alternative assumes that any contaminated or activated portion of the plant's systems, structures and facilities are removed or decontaminated to levels that permit the site to be released for unrestricted use shortly after the cessation of plant operations. The rule also placed limits on the time allowed to complete the decommissioning process. For SAFSTOR, the process is restricted in overall duration to 60 years, unless it can be shown that a longer duration is necessary to protect public health and safety. The guidelines for ENTOMB are similar, providing the NRC with both sufficient leverage and flexibility to ensure that these deferred options are only used in situations where it is reasonable and consistent with the definition of decommissioning. At the conclusion of a 60-year dormancy period (or longer for ENTOMB if the NRC approves such a case), the site would still require significant remediation to meet the unrestricted release limits for license termination.

The ENTOMB alternative has not been viewed as a viable option for power reactors due to the significant time required to isolate the long-lived radionuclides for decay to permissible levels. However, with rulemaking permitting the controlled release of a site,<sup>[3]</sup> the NRC has re-evaluated this alternative. The resulting feasibility study, based upon an assessment by Pacific Northwest National Laboratory, concluded that the method did have conditional merit for some, if not most reactors. However, the staff also found that additional rulemaking would be needed before this option could be treated as a generic alternative. The NRC had considered rulemaking to alter

---

\* Annotated references for citations in Sections 1-6 are provided in Section 7.

the 60-year time for completing decommissioning and to clarify the use of engineered barriers for reactor entombments.<sup>[4]</sup> However, the NRC's staff has recommended that rulemaking be deferred, based upon several factors, *e.g.*, no licensee has committed to pursuing the entombment option, the unresolved issues associated with the disposition of greater-than-Class C material (GTCC), and the NRC's current priorities, at least until after the additional research studies are complete. The Commission concurred with the staff's recommendation.

In 1996, the NRC published revisions to the general requirements for decommissioning nuclear power plants.<sup>[5]</sup> When the decommissioning regulations were adopted in 1988, it was assumed that the majority of licensees would decommission at the end of the facility's operating licensed life. Since that time, several licensees permanently and prematurely ceased operations. Exemptions from certain operating requirements were required once the reactor was defueled to facilitate the decommissioning. Each case was handled individually, without clearly defined generic requirements. The NRC amended the decommissioning regulations in 1996 to clarify ambiguities and codify procedures and terminology as a means of enhancing efficiency and uniformity in the decommissioning process. The amendments allow for greater public participation and better define the transition process from operations to decommissioning.

Under the revised regulations, licensees will submit written certification to the NRC within 30 days after the decision to cease operations. Certification will also be required once the fuel is permanently removed from the reactor vessel. Submittal of these notices will entitle the licensee to a fee reduction and eliminate the obligation to follow certain requirements needed only during operation of the reactor. Within two years of submitting notice of permanent cessation of operations, the licensee is required to submit a Post-Shutdown Decommissioning Activities Report (PSDAR) to the NRC. The PSDAR describes the planned decommissioning activities, the associated sequence and schedule, and an estimate of expected costs. Prior to completing decommissioning, the licensee is required to submit an application to the NRC to terminate the license, which will include a license termination plan (LTP).

### **1.3.1 Nuclear Waste Policy Act**

Congress passed the Nuclear Waste Policy Act<sup>[6]</sup> (NWPA) in 1982, assigning the responsibility for disposal of the spent nuclear fuel

created by the commercial nuclear generating plants to the U.S. Department of Energy (DOE). Two permanent disposal facilities and an interim storage facility were envisioned. To recover the cost, the legislation created a Nuclear Waste Fund through which money is collected from the sale of electricity generated by the power plants. The NWPA, along with the individual disposal contracts with the utilities, specified that the DOE was to begin accepting spent fuel by January 31, 1998.

After pursuing a national site selection process, the NWPA was amended in 1987 to designate Yucca Mountain, Nevada, as the only site to be evaluated for geologic disposal of high-level waste. Also in 1987, the DOE announced a five-year delay (1998 to 2003) in the opening date for the repository. Two years later, in 1989, an additional seven-year delay was announced, primarily due to problems in obtaining the permits necessary from the state of Nevada to perform the required characterization of the site. In 2005, the DOE stated that operations at the repository would not begin before 2012 due to delays in the license application.

The NRC requires that licensees establish a program to manage and provide funding for the management of all irradiated fuel at the reactor until title of the fuel is transferred to the Secretary of Energy, pursuant to Title 10 of the Code of Federal Regulations (10 CFR), §50.54 (bb).<sup>[7]</sup> This funding requirement is fulfilled through inclusion of certain high-level waste cost elements in the decommissioning estimates, as identified in Section 3.

For estimating purposes, WCNOG has assumed that all spent fuel will be removed to a DOE high-level waste repository within 5½ years after shutdown. Interim storage of the fuel, until the DOE has completed the transfer, will be in the storage pool located in the fuel building. The pool will be isolated, allowing WCNOG to proceed with decommissioning (or safe-storage preparations) in the shortest time possible.

At shutdown, the spent fuel pool is expected to be at capacity. Over the next 5½ years the assemblies will be packaged into multipurpose canisters for transfer to the final repository. It is assumed that the 5½ years also provides the necessary cooling period for the final core to meet DOE's transport system requirements for decay heat.

### **1.3.2 Low-Level Radioactive Waste Acts**

The contaminated and activated material generated in the decontamination and dismantling of a commercial nuclear reactor is classified as low-level (radioactive) waste, although not all of the material is suitable for “shallow-land” disposal. Congress passed the “Low-Level Radioactive Waste Policy Act” in 1980,<sup>[8]</sup> declaring the states as being ultimately responsible for the disposition of low-level radioactive waste generated within their own borders. The federal law encouraged the formation of regional groups or compacts to implement this objective safely, efficiently, and economically, and set a target date of 1986 for implementation. After little progress, the “Low-Level Radioactive Waste Policy Amendments Act of 1985,”<sup>[9]</sup> extended the implementation schedule, with specific milestones and stiff sanctions for non-compliance. Subsequent court rulings have substantially diluted those sanctions. To date, no new compact facilities have been successfully sited, licensed and constructed.

WCNOC is currently able to access the disposal facility in Barnwell, South Carolina. However, in June 2000, South Carolina formally joined with Connecticut and New Jersey to form the Atlantic Compact. The legislation provides for South Carolina to gradually limit access to the Barnwell facility, with only Atlantic Compact members having access to the facility after mid-year 2008. Despite the closing of one of the two currently accessible commercial disposal sites, it is reasonable to assume that additional disposal capacity will be available to support reactor decommissioning, particularly for the isolation of the more highly radioactive material that is not suitable for disposal elsewhere.

For estimating purposes, and as a proxy for future disposal facilities, waste disposal costs are generated using pricing for the currently operating Envirocare facility in Clive, Utah. Since Envirocare does not have a license to dispose of more highly radioactive waste (Class B and C), pricing for the Barnwell facility is also used.

### **1.3.3 Radiological Criteria for License Termination**

In 1997, the NRC published Subpart E, “Radiological Criteria for License Termination,”<sup>[10]</sup> amending 10 CFR Part 20. This subpart provides radiological criteria for releasing a facility for unrestricted use. The regulation states that the site can be released for unrestricted

use if radioactivity levels are such that the average member of a critical group would not receive a Total Effective Dose Equivalent (TEDE) in excess of 25 millirem per year, and provided that residual radioactivity has been reduced to levels that are As Low As Reasonably Achievable (ALARA). The decommissioning estimates assume that the Wolf Creek site will be remediated to a residual level consistent with the NRC-prescribed level.

It should be noted that the NRC and the Environmental Protection Agency (EPA) differ on the amount of residual radioactivity considered acceptable in site remediation. The EPA has two limits that apply to radioactive materials. An EPA limit of 15 millirem per year is derived from criteria established by the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA or Superfund).<sup>[11]</sup> An additional and separate limit of 4 millirem per year, as defined in 40 CFR §141.16, is applied to drinking water.<sup>[12]</sup>

On October 9, 2002, the NRC signed an agreement with the EPA on the radiological decommissioning and decontamination of NRC-licensed sites. The Memorandum of Understanding (MOU)<sup>[13]</sup> provides that EPA will defer exercise of authority under CERCLA for the majority of facilities decommissioned under NRC authority. The MOU also includes provisions for NRC and EPA consultation for certain sites when, at the time of license termination, (1) groundwater contamination exceeds EPA-permitted levels; (2) NRC contemplates restricted release of the site; and/or (3) residual radioactive soil concentrations exceed levels defined in the MOU.

The MOU does not impose any new requirements on NRC licensees and should reduce the involvement of the EPA with NRC licensees who are decommissioning. Most sites are expected to meet the NRC criteria for unrestricted use, and the NRC believes that only a few sites will have groundwater or soil contamination in excess of the levels specified in the MOU that trigger consultation with the EPA. However, if there are other hazardous materials on the site, the EPA may be involved in the cleanup. As such, the possibility of dual regulation remains for certain licensees. The present study does not include any costs for this occurrence.

## **2. DECOMMISSIONING ALTERNATIVES**

Detailed cost estimates were developed to decommission the Wolf Creek nuclear unit for the approved decommissioning alternatives: DECON and SAFSTOR. Although the alternatives differ with respect to technique, process, cost, and schedule, they attain the same result: the ultimate release of the site for unrestricted use.

The following sections describe the basic activities associated with each alternative. Although detailed procedures for each activity identified are not provided, and the actual sequence of work may vary, the activity descriptions provide a basis not only for estimating but also for the expected scope of work, *i.e.*, engineering and planning at the time of decommissioning.

The conceptual approach that the NRC has described in its regulations divides decommissioning into three phases. The initial phase commences with the effective date of permanent cessation of operations and involves the transition of both plant and licensee from reactor operations (*i.e.*, power production) to facility de-activation and closure. During the first phase, notification is to be provided to the NRC certifying the permanent cessation of operations and the removal of fuel from the reactor vessel. The licensee is then prohibited from reactor operation.

The second phase encompasses activities during the storage period or during major decommissioning activities, or a combination of the two. The third phase pertains to the activities involved in license termination. The decommissioning estimates developed for Wolf Creek are also divided into phases or periods; however, demarcation of the phases is based upon major milestones within the project or significant changes in the projected expenditures.

### **2.1 DECON**

The DECON alternative, as defined by the NRC, is "the alternative in which the equipment, structures, and portions of a facility and site containing radioactive contaminants are removed or decontaminated to a level that permits the property to be released for unrestricted use shortly after cessation of operations." This study does not address the cost to dispose of the spent fuel residing at the site; such costs are funded through a surcharge on electrical generation. However, the study does estimate the costs incurred with transferring the fuel from the pool to a DOE transport cask.

### **2.1.1 Period 1 - Preparations**

In anticipation of the cessation of plant operations, detailed preparations are undertaken to provide a smooth transition from plant operations to site decommissioning. Through implementation of a staffing transition plan, the organization required to manage the intended decommissioning activities is assembled from available plant staff and outside resources. Preparations include the planning for permanent defueling of the reactor, revision of technical specifications applicable to the operating conditions and requirements, a characterization of the facility and major components, and the development of the PSDAR.

#### **Engineering and Planning**

The PSDAR, required within two years of the notice to cease operations, provides a description of the licensee's planned decommissioning activities, a timetable, and the associated financial requirements of the intended decommissioning program. Upon receipt of the PSDAR, the NRC will make the document available to the public for comment in a local hearing to be held in the vicinity of the reactor site. Ninety days following submittal and NRC receipt of the PSDAR, the licensee may begin to perform major decommissioning activities under a modified 10 CFR §50.59 procedure, *i.e.*, without specific NRC approval. Major activities are defined as any activity that results in permanent removal of major radioactive components, permanently modifies the structure of the containment, or results in dismantling components (for shipment) containing GTCC, as defined by 10 CFR §61. Major components are further defined as comprising the reactor vessel and internals, large bore reactor coolant system piping, and other large components that are radioactive. The NRC includes the following additional criteria for use of the §50.59 process in decommissioning. The proposed activity must not:

- foreclose release of the site for possible unrestricted use,
- significantly increase decommissioning costs,
- cause any significant environmental impact, or
- violate the terms of the licensee's existing license.

Existing operational technical specifications are reviewed and modified to reflect plant conditions and the safety concerns associated with permanent cessation of operations. The environmental impact associated with the planned decommissioning activities is also considered. Typically,

a licensee will not be allowed to proceed if the consequences of a particular decommissioning activity are greater than that bounded by previously evaluated environmental assessments or impact statements. In this instance, the licensee would have to submit a license amendment for the specific activity and update the environmental report.

The decommissioning program outlined in the PSDAR will be designed to accomplish the required tasks within the ALARA guidelines (as defined in 10 CFR §20) for protection of personnel from exposure to radiation hazards. It will also address the continued protection of the health and safety of the public and the environment during the dismantling activity. Consequently, with the development of the PSDAR, activity specifications, cost-benefit and safety analyses, work packages and procedures, would be assembled to support the proposed decontamination and dismantling activities.

#### Site Preparations

Following final plant shutdown, and in preparation for actual decommissioning activities, the following activities are initiated:

- Characterization of the site and surrounding environs. This includes radiation surveys of work areas, major components (including the reactor vessel and its internals), internal piping, and primary shield cores.
- Isolation of the spent fuel storage pool and fuel handling systems, such that decommissioning operations can commence on the balance of the plant. The pool will remain operational for approximately 5½ years following the cessation of operations before the inventory resident at shutdown can be transferred to the DOE.
- Specification of transport and disposal requirements for activated materials and/or hazardous materials, including shielding and waste stabilization.
- Development of procedures for occupational exposure control, control and release of liquid and gaseous effluent, processing of radwaste (including dry-active waste, resins, filter media, metallic and non-metallic components generated in decommissioning), site security and emergency programs, and industrial safety.



### **2.1.2 Period 2 - Decommissioning Operations**

This period includes the physical decommissioning activities associated with the removal and disposal of contaminated and activated components and structures, including the successful termination of the 10 CFR §50 operating license. Significant decommissioning activities in this phase include:

- Construction of temporary facilities and/or modification of existing facilities to support dismantling activities. This may include a centralized processing area to facilitate equipment removal and component preparations for off-site disposal.
- Reconfiguration and modification of site structures and facilities as needed to support decommissioning operations. This may include the upgrading of roads (on- and off-site) to facilitate hauling and transport. Modifications may be required to the containment structure to facilitate access of large/heavy equipment. Modifications may also be required to the refueling area of the building to support the segmentation of the reactor vessel internals and component extraction.
- Design and fabrication of temporary and permanent shielding to support removal and transportation activities, construction of contamination control envelopes, and the procurement of specialty tooling.
- Procurement (lease or purchase) of shipping canisters, cask liners, and industrial packages for the disposition of low-level radioactive waste.
- Decontamination of components and piping systems as required to control (minimize) worker exposure.
- Removal of piping and components no longer essential to support decommissioning operations.
- Removal of control rod drive housings and the head service structure from the reactor vessel head. Segmentation of the vessel closure head.

- Removal and segmentation of the upper internals assemblies. Segmentation will maximize the loading of the shielded transport casks, *i.e.*, by weight and activity. The operations are conducted under water using remotely operated tooling and contamination controls.
- Disassembly and segmentation of the remaining reactor internals, including the core shroud and lower core support assembly. Some material is expected to exceed Class C disposal requirements. As such, the segments will be packaged in modified fuel storage canisters for geologic disposal.
- Segmentation of the reactor vessel. A shielded platform is installed for segmentation as cutting operations are performed in-air using remotely operated equipment within a contamination control envelope. The water level is maintained just below the cut to minimize the working area dose rates. Segments are transferred in-air to containers that are stored under water, for example, in an isolated area of the refueling canal.
- Removal of the activated portions of the concrete biological shield and accessible contaminated concrete surfaces. If dictated by the steam generator and pressurizer removal scenarios, those portions of the associated cubicles necessary for access and component extraction are removed.
- Removal of the steam generators and pressurizer for material recovery and controlled disposal. The generators will be moved to an on-site processing center, the steam domes removed and the internal components segregated for recycling. The lower shell and tube bundle will be packaged for direct disposal. These components can serve as their own burial containers provided that all penetrations are properly sealed and the internal contaminants are stabilized, *e.g.*, with grout. Steel shielding will be added, as necessary, to those external areas of the package to meet transportation limits and regulations. The pressurizer is disposed of intact.

At least two years prior to the anticipated date of license termination, an LTP is required. Submitted as a supplement to the Final Safety Analysis Report (FSAR) or its equivalent, the plan must include: a site characterization, description of the remaining dismantling activities,

plans for site remediation, procedures for the final radiation survey, designation of the end use of the site, an updated cost estimate to complete the decommissioning, and any associated environmental concerns. The NRC will notice the receipt of the plan, make the plan available for public comment, and schedule a local hearing. LTP approval will be subject to any conditions and limitations as deemed appropriate by the Commission. The licensee may then commence with the final remediation of site facilities and services, including:

- Removal of remaining plant systems and associated components as they become nonessential to the decommissioning program or worker health and safety (e.g., waste collection and treatment systems, electrical power and ventilation systems).
- Removal of the steel liners from refueling canal, disposing of the activated and contaminated sections as radioactive waste. Removal of any activated/ contaminated concrete.
- Surveys of the decontaminated areas of the containment structure.
- Remediation and removal of the contaminated equipment and material from the auxiliary and fuel buildings and any other contaminated facility. Radiation and contamination controls will be utilized until residual levels indicate that the structures and equipment can be released for unrestricted access and conventional demolition. This activity may necessitate the dismantling and disposition of most of the systems and components (both clean and contaminated) located within these buildings. This activity facilitates surface decontamination and subsequent verification surveys required prior to obtaining release for demolition.
- Routing of material removed in the decontamination and dismantling to a central processing area. Material certified to be free of contamination is released for unrestricted disposition, e.g., as scrap, recycle, or general disposal. Contaminated material is characterized and segregated for additional off-site processing (disassembly, chemical cleaning, volume reduction, and waste treatment), and/or packaged for controlled disposal at a low-level radioactive waste disposal facility.

Incorporated into the LTP is the Final Survey Plan. This plan identifies the radiological surveys to be performed once the decontamination activities are completed and is developed using the guidance provided in the “Multi-Agency Radiation Survey and Site Investigation Manual (MARSSIM).”<sup>[14]</sup> This document incorporates the statistical approaches to survey design and data interpretation used by the EPA. It also identifies state-of-the-art, commercially available instrumentation and procedures for conducting radiological surveys. Use of this guidance ensures that the surveys are conducted in a manner that provides a high degree of confidence that applicable NRC criteria are satisfied. Once the survey is complete, the results are provided to the NRC in a format that can be verified. The NRC then reviews and evaluates the information, performs an independent confirmation of radiological site conditions, and makes a determination on final termination of the license.

The NRC will terminate the operating license if it determines that site remediation has been performed in accordance with the LTP, and that the terminal radiation survey and associated documentation demonstrate that the facility is suitable for release.

### **2.1.3 Period 3 - Site Restoration**

Following completion of decommissioning operations, site restoration activities will begin. Efficient removal of the contaminated materials and verification that residual radionuclide concentrations are below the NRC limits will result in substantial damage to many of the structures. Although performed in a controlled, safe manner, blasting, coring, drilling, scarification (surface removal), and the other decontamination activities will substantially degrade power block structures including the reactor, auxiliary, fuel and radwaste buildings. Under certain circumstances, verifying that subsurface radionuclide concentrations meet NRC site release requirements will require removal of grade slabs and lower floors, potentially weakening footings and structural supports. This removal activity will be necessary for those facilities and plant areas where historical records, when available, indicate the potential for radionuclides having been present in the soil, where system failures have been recorded, or where it is required to confirm that subsurface process and drain lines were not breached over the operating life of the station.

Prompt dismantling of site structures is clearly the most appropriate and cost-effective option. It is unreasonable to anticipate that these structures would be repaired and preserved after the radiological contamination is removed. The cost to dismantle site structures with a work force already mobilized on site is more efficient than if the process were deferred. Site facilities quickly degrade without maintenance, adding additional expense and creating potential hazards to the public as well as to future workers. Abandonment creates a breeding ground for vermin infestation as well as other biological hazards.

This cost study presumes that non-essential structures and site facilities are dismantled as a continuation of the decommissioning activity. Foundations and exterior walls are removed to a nominal depth of three feet below grade. The three-foot depth allows for the placement of gravel for drainage, as well as topsoil, so that vegetation can be established for erosion control. Site areas affected by the dismantling activities are restored and the plant area graded as required to prevent ponding and inhibit the refloating of subsurface materials.

Non-contaminated concrete rubble produced by demolition activities is processed to remove reinforcing steel and miscellaneous embedments. The processed material is then used on site to backfill foundation voids. Excess non-contaminated materials are trucked to an off-site area for disposal as construction debris.

## **2.2 SAFSTOR**

The NRC defines SAFSTOR as "the alternative in which the nuclear facility is placed and maintained in a condition that allows the nuclear facility to be safely stored and subsequently decontaminated (deferred decontamination) to levels that permit release for unrestricted use." The facility is left intact (during the dormancy period), with structures maintained in a sound condition. Systems that are not required to support the spent fuel pool or site surveillance and security are drained, de-energized, and secured. Minimal cleaning/removal of loose contamination and/or fixation and sealing of remaining contamination is performed. Access to contaminated areas is secured to provide controlled access for inspection and maintenance.

The engineering and planning requirements are similar to those for the DECON alternative, although a shorter time period is expected for these activities due to the more limited work scope. Site preparations are also similar to those for the DECON alternative. However, with the exception of the required radiation surveys and site characterizations, the mobilization and preparation of site facilities is less extensive.

#### **2.2.1 Period 1 - Preparations**

Preparations for long-term storage include the planning for permanent defueling of the reactor, revision of technical specifications appropriate to the operating conditions and requirements, a characterization of the facility and major components, and the development of the PSDAR.

The process of placing the plant in safe-storage includes, but is not limited to, the following activities:

- Isolation of the spent fuel storage services and fuel handling systems so that safe-storage operations may commence on the balance of the plant. This activity may be carried out by plant personnel in accordance with existing operating technical specifications. Activities are scheduled around the fuel handling systems to the greatest extent possible.
- Transfer of the spent fuel from the storage pool to DOE transport casks, following the minimum required cooling period in the spent fuel pool.
- Draining and de-energizing of the non-contaminated systems not required to support continued site operations or maintenance.
- Disposing of contaminated filter elements and resin beds not required for processing wastes from layup activities for future operations.
- Draining of the reactor vessel, with the internals left in place and the vessel head secured.
- Draining and de-energizing non-essential, contaminated systems with decontamination as required for future maintenance and inspection.

- Preparing lighting and alarm systems whose continued use is required; de-energizing portions of fire protection, electric power, and HVAC systems whose continued use is not required.
- Cleaning of the loose surface contamination from building access pathways.
- Performing an interim radiation survey of plant, posting warning signs where appropriate.
- Erecting physical barriers and/or securing all access to radioactive or contaminated areas, except as required for inspection and maintenance.
- Installing security and surveillance monitoring equipment and relocating security fence around secured structures, as required.

#### **2.2.2 Period 2 - Dormancy**

The second phase identified by the NRC in its rule addresses licensed activities during a storage period and is applicable to the dormancy phases of the deferred decommissioning alternatives. Dormancy activities include a 24-hour security force, preventive and corrective maintenance on security systems, area lighting, general building maintenance, heating and ventilation of buildings, routine radiological inspections of contaminated structures, maintenance of structural integrity, and a site environmental and radiation monitoring program. Resident maintenance personnel perform equipment maintenance, inspection activities, routine services to maintain safe conditions, adequate lighting, heating, and ventilation, and periodic preventive maintenance on essential site services.

An environmental surveillance program is carried out during the dormancy period to ensure that releases of radioactive material to the environment are prevented and/or detected and controlled. Appropriate emergency procedures are established and initiated for potential releases that exceed prescribed limits. The environmental surveillance program constitutes an abbreviated version of the program in effect during normal plant operations.

Security during the dormancy period is conducted primarily to prevent unauthorized entry and to protect the public from the consequences of its own actions. The security fence, sensors, alarms, and other surveillance equipment provide security. Fire and radiation alarms are also monitored and maintained.

Consistent with the DECON scenario, the spent fuel storage pool is emptied within 5½ years of the cessation of operations. Once emptied, the pool is secured for storage and decommissioned along with the power block structures in Period 4.

After an optional period of storage (such that license termination is accomplished within 60 years of final shutdown), it is required that the licensee submit an application to terminate the license, along with an LTP (described in Section 2.1.2), thereby initiating the third phase.

### **2.2.3 Periods 3 and 4 - Delayed Decommissioning**

Prior to the commencement of decommissioning operations, preparations are undertaken to reactivate site services and prepare for decommissioning. Preparations include engineering and planning, a detailed site characterization, and the assembly of a decommissioning management organization. Final planning for activities and the writing of activity specifications and detailed procedures are also initiated at this time.

Much of the work in developing a termination plan is relevant to the development of the detailed engineering plans and procedures. The activities associated with this phase and the follow-on decontamination and dismantling processes are detailed in Sections 2.1.1 and 2.1.2. The primary difference between the sequences anticipated for the DECON and this deferred scenario is the absence, in the latter, of any constraint on the availability of the fuel building for decommissioning.

Variations in the length of the dormancy period are expected to have little effect upon the quantities of radioactive wastes generated from system and structure removal operations. Given the levels of radioactivity and spectrum of radionuclides expected from thirty to forty years of plant operation, no plant process system identified as being contaminated upon final shutdown will become releasable due to the decay period alone, *i.e.*, there is no significant reduction in the waste



generated from the decommissioning activities. However, due to the lower activity levels, a greater percentage of the waste volume can be designated for off-site processing and recovery.

The delay in decommissioning also yields lower working area radiation levels. As such, the estimate for this delayed scenario incorporates reduced ALARA controls for the SAFSTOR's lower occupational exposure potential.

Although the initial radiation levels due to  $^{60}\text{Co}$  will decrease during the dormancy period, the internal components of the reactor vessel will still exhibit sufficiently high radiation dose rates to require remote sectioning under water due to the presence of long-lived radionuclides such as  $^{94}\text{Nb}$ ,  $^{59}\text{Ni}$ , and  $^{63}\text{Ni}$ . Therefore, the dismantling procedures described for the DECON alternative would still be employed during this scenario. Portions of the biological shield will still be radioactive due to the presence of activated trace elements with long half-lives ( $^{152}\text{Eu}$  and  $^{154}\text{Eu}$ ). Decontamination will require controlled removal and disposal. It is assumed that radioactive corrosion products on inner surfaces of piping and components will not have decayed to levels that will permit unrestricted use or allow conventional removal. These systems and components will be surveyed as they are removed and disposed of in accordance with the existing radioactive release criteria.

#### **2.2.4 Period 5 - Site Restoration**

Following completion of decommissioning operations, site-restoration activities can begin. Dismantling, as a continuation of the decommissioning process, is clearly the most appropriate and cost-effective option, as described in Section 2.1.3. The basis for the dismantling cost in this scenario is consistent with that described for DECON, presuming the removal of structures and site facilities to a nominal depth of three feet below grade and the limited restoration of the site.

### **3. COST ESTIMATE**

The cost estimates prepared for decommissioning Wolf Creek consider the unique features of the site, including the NSSS, power generation systems, support services, site buildings, and ancillary facilities. The basis of the estimates, including the sources of information relied upon, the estimating methodology employed, site-specific considerations, and other pertinent assumptions, is described in this section.

#### **3.1 BASIS OF ESTIMATE**

The estimates were developed using the site-specific, technical information from the 2002 analysis.<sup>[15]</sup> This information was reviewed for the current analysis and updated as deemed appropriate. The site-specific considerations and assumptions used in the previous evaluation were also revisited. Modifications were incorporated where new information was available or experience from ongoing decommissioning programs provided viable alternatives or improved processes.

#### **3.2 METHODOLOGY**

The methodology used to develop the estimates follows the basic approach originally presented in the AIF/NESP-036 study report, "Guidelines for Producing Commercial Nuclear Power Plant Decommissioning Cost Estimates,"<sup>[16]</sup> and the DOE "Decommissioning Handbook."<sup>[17]</sup> These documents present a unit factor method for estimating decommissioning activity costs, which simplifies the estimating calculations. Unit factors for concrete removal (\$/cubic yard), steel removal (\$/ton), and cutting costs (\$/inch) are developed using local labor rates. The activity-dependent costs are estimated with the item quantities (cubic yards and tons), developed from plant drawings and inventory documents. Removal rates and material costs for the conventional disposition of components and structures rely upon information available in the industry publication, "Building Construction Cost Data," published by R.S. Means.<sup>[18]</sup>

This analysis reflects lessons learned from TLG's involvement in the Shippingport Station Decommissioning Project, completed in 1989, as well as the decommissioning of the Cintichem reactor, hot cells, and associated facilities, completed in 1997. In addition, the planning and engineering for the Pathfinder, Shoreham, Rancho Seco, Trojan, Yankee Rowe, Big Rock Point, Maine Yankee, Humboldt Bay-3, Oyster Creek, Connecticut Yankee, and San

Onofre-1 nuclear units have provided additional insight into the process, the regulatory aspects, and the technical challenges of decommissioning commercial nuclear units.

The unit factor method provides a demonstrable basis for establishing reliable cost estimates. The detail provided in the unit factors, including activity duration, labor costs (by craft), and equipment and consumable costs, ensures that essential elements have not been omitted. Appendix A presents the detailed development of a typical unit factor. Appendix B provides the values contained within one set of factors developed for this analysis.

### Work Difficulty Factors

TLG has historically applied work difficulty adjustment factors (WDFs) to account for the inefficiencies in working in a power plant environment. WDFs are assigned to each unique set of unit factors, commensurate with the inefficiencies associated with working in confined, hazardous environments. The ranges used for the WDFs are as follows:

- |                                 |            |
|---------------------------------|------------|
| • Access Factor                 | 10% to 20% |
| • Respiratory Protection Factor | 10% to 50% |
| • Radiation/ALARA Factor        | 10% to 40% |
| • Protective Clothing Factor    | 10% to 30% |
| • Work Break Factor             | 8.33%      |

The factors and their associated range of values were developed in conjunction with the AIF/NESP-036 study. The application of the factors is discussed in more detail in that publication.

### Scheduling Program Durations

The unit factors, adjusted by the WDFs as described above, are applied against the inventory of materials to be removed in the radiologically controlled areas. The resulting man-hours, or crew-hours, are used in the development of the decommissioning program schedule, using resource loading and event sequencing considerations. The scheduling of conventional removal and dismantling activities is based upon productivity information available from the "Building Construction Cost Data" publication.

An activity duration critical path is used to determine the total decommissioning program schedule. The schedule is relied upon in calculating

the carrying costs, which include program management, administration, field engineering, equipment rental, and support services such as quality control and security. This systematic approach for assembling decommissioning estimates ensures a high degree of confidence in the reliability of the resulting costs.

### **3.3 FINANCIAL COMPONENTS OF THE COST MODEL**

TLG's proprietary decommissioning cost model, DECCER, produces a number of distinct cost elements. These direct expenditures, however, do not comprise the total cost to accomplish the project goal, *i.e.*, license termination and site restoration.

Inherent in any cost estimate that does not rely on historical data is the inability to specify the precise source of costs imposed by factors such as tool breakage, accidents, illnesses, weather delays, and labor stoppages. In the DECCER cost model, contingency fulfills this role. Contingency is added to each line item to account for costs that are difficult or impossible to develop analytically. Such costs are historically inevitable over the duration of a job of this magnitude; therefore, this cost analysis includes funds to cover these types of expenses.

#### **3.3.1 Contingency**

The activity- and period-dependent costs are combined to develop the total decommissioning cost. A contingency is then applied on a line-item basis, using one or more of the contingency types listed in the AIF/NESP-036 study. "Contingencies" are defined in the American Association of Cost Engineers "Project and Cost Engineers' Handbook"<sup>[19]</sup> as "specific provision for unforeseeable elements of cost within the defined project scope; particularly important where previous experience relating estimates and actual costs has shown that unforeseeable events which will increase costs are likely to occur." The cost elements in this analysis are based upon ideal conditions and maximum efficiency; therefore, consistent with industry practice, contingency is included. In the AIF/NESP-036 study, the types of unforeseeable events that are likely to occur in decommissioning are discussed and guidelines are provided for percentage contingency in each category. It should be noted that contingency, as used in this analysis, does not account for price escalation and inflation in the cost of decommissioning over the remaining operating life of the station.

The use and role of contingency within decommissioning estimates is not a “safety factor issue.” Safety factors provide additional security and address situations that may never occur. Contingency funds are expected to be fully expended throughout the program. They also provide assurance that sufficient funding is available to accomplish the intended tasks. An estimate without contingency, or from which contingency has been removed, can disrupt the orderly progression of events and jeopardize a successful conclusion to the decommissioning process.

For example, the most technologically challenging task in decommissioning a commercial nuclear station is the disposition of the reactor vessel and internal components, now highly radioactive after a lifetime of exposure to core activity. The disposition of these components forms the basis of the critical path (schedule) for decommissioning operations. Cost and schedule are interdependent, and any deviation in schedule has a significant impact on cost for performing a specific activity.

Disposition of the reactor vessel internals involves the underwater cutting of complex components that are highly radioactive. Costs are based upon optimum segmentation, handling, and packaging scenarios. The schedule is primarily dependent upon the turnaround time for the heavily shielded shipping casks, including preparation, loading, and decontamination of the containers for transport. The number of casks required is a function of the pieces generated in the segmentation activity, a value calculated on optimum performance of the tooling employed in cutting the various subassemblies. The expected optimization, however, may not be achieved, resulting in delays and additional program costs. For this reason, contingency must be included to mitigate the consequences of the expected inefficiencies inherent in this complex activity, along with related concerns associated with the operation of highly specialized tooling, field conditions, and water clarity.

Contingency funds are an integral part of the total cost to complete the decommissioning process. Exclusion of this component puts at risk a successful completion of the intended tasks and, potentially, subsequent related activities. For this study, TLG examined the major activity-related problems (decontamination, segmentation, equipment handling, packaging, transport, and waste disposal) that necessitate a

contingency. Individual activity contingencies ranged from 10% to 75%, depending on the degree of difficulty judged to be appropriate from TLG's actual decommissioning experience. The contingency values used in this study are as follows:

Decontamination	50%
Contaminated Component Removal	25%
Contaminated Component Packaging	10%
Contaminated Component Transport	15%
Low-Level Radioactive Waste Disposal	25%
Reactor Segmentation	75%
NSSS Component Removal	25%
Reactor Waste Packaging	25%
Reactor Waste Transport	25%
Reactor Vessel Component Disposal	50%
GTCC Disposal	15%
Non-Radioactive Component Removal	15%
Heavy Equipment and Tooling	15%
Supplies	25%
Engineering	15%
Energy	15%
Characterization and Termination Surveys	30%
Construction	15%
Taxes and Fees	10%
Insurance	10%
Staffing	15%

The contingency values are applied to the appropriate components of the estimates on a line item basis. A composite value is then reported at the end of each detailed estimate (as provided in Appendix C and D). For example, the composite contingency value reported for the DECON alternative in Appendix C is approximately 19.0%.

### **3.3.2 Financial Risk**

In addition to the routine uncertainties addressed by contingency, another cost element that is sometimes necessary to consider when bounding decommissioning costs relates to uncertainty, or risk.

Examples can include changes in work scope, pricing, job performance, and other variations that could conceivably, but not necessarily, occur. Consideration is sometimes necessary to generate a level of confidence in the estimate, within a range of probabilities. TLG considers these types of costs under the broad term “financial risk.” Included within the category of financial risk are:

- Transition activities and costs: ancillary expenses associated with eliminating 50% to 80% of the site labor force shortly after the cessation of plant operations, added cost for worker separation packages throughout the decommissioning program, national or company-mandated retraining, and retention incentives for key personnel.
- Delays in approval of the decommissioning plan due to intervention, public participation in local community meetings, legal challenges, and national and local hearings.
- Changes in the project work scope from the baseline estimate, involving the discovery of unexpected levels of contaminants, contamination in places not previously expected, contaminated soil previously undiscovered (either radioactive or hazardous material contamination), variations in plant inventory or configuration not indicated by the as-built drawings.
- Regulatory changes, *e.g.*, affecting worker health and safety, site release criteria, waste transportation, and disposal.
- Policy decisions altering national commitments, *e.g.*, in the ability to accommodate certain waste forms for disposition, or in the timetable for such, *e.g.*, the start and rate of acceptance of spent fuel by the DOE.
- Pricing changes for basic inputs, such as labor, energy, materials, and burial. Some of these inputs may vary slightly, *e.g.* -10% to +20%; burial could vary from -50% to +200% or more.

It has been TLG’s experience that the results of a risk analysis, when compared with the base case estimate for decommissioning, indicate that the chances of the base decommissioning estimate’s being too high is a low probability, and the chances that the estimate is too low is a

higher probability. This is mostly due to the pricing uncertainty for low-level radioactive waste burial, and to a lesser extent due to schedule increases from changes in plant conditions and to pricing variations in the cost of labor (both craft and staff). This cost study, however, does not add any additional costs to the estimate for financial risk, since there is insufficient historical data from which to project future liabilities. Consequently, the areas of uncertainty or risk are revisited periodically and addressed through repeated revisions or updates of the base estimates.

### **3.4 SITE-SPECIFIC CONSIDERATIONS**

There are a number of site-specific considerations that affect the method for dismantling and removal of equipment from the site and the degree of restoration required. The cost impact of the considerations identified below is included in this cost study.

#### **3.4.1 Spent Fuel Management**

The cost to dispose the spent fuel generated from plant operations is not reflected within the estimates to decommission Wolf Creek. Ultimate disposition of the spent fuel is within the province of the DOE's Waste Management System, as defined by the Nuclear Waste Policy Act. As such, the disposal cost is financed by a 1 mill/kWhr surcharge paid into the DOE's waste fund during operations. However, the NRC requires licensees to establish a program to manage and provide funding for the management of all irradiated fuel at the reactor until title of the fuel is transferred to the Secretary of Energy. This funding requirement is fulfilled through inclusion of certain high-level waste cost elements within the estimates, as described below.

For estimating purposes, WCNOG has assumed that all spent fuel will be removed to the DOE high-level waste repository within 5½ years after shutdown. Interim storage of the fuel, until the DOE has completed the transfer, will be in the spent fuel pool located in the fuel building on the Wolf Creek site. This will allow WCNOG to proceed with decommissioning (or safe-storage) operations in the shortest time possible. A delay in the startup of the repository, or a decrease in the spent fuel acceptance rate, will correspondingly prolong the transfer process and result in the fuel remaining at the Wolf Creek site longer.



At shutdown, the spent fuel pool is expected to be at capacity. Over the next 5½ years the assemblies will be packaged into multipurpose canisters for transfer to the final repository. It is assumed that the 5½ years also provides the necessary cooling period for the final core to meet DOE's transport system requirements for decay heat. Once the pool is emptied, the spent fuel storage and handling facilities are available for decommissioning. Operation and maintenance costs for the spent fuel pool are included within the estimate as well as the costs for transferal of spent fuel to the DOE.

#### Canister Loading and Transfer

A cost of \$200,000 is used for the labor to load/transport the spent fuel from the pool to a DOE transport vehicle (assuming the DOE casks are multi-purpose canister designs within a storage or transportation overpack).

#### Operations and Maintenance

An annual cost (excluding labor) of approximately \$941,000 is used for operation and maintenance of the spent fuel pool. Pool operations are expected to continue approximately 5½ years after the cessation of operations.

#### GTCC

The dismantling of the reactor internals will generate radioactive waste considered unsuitable for shallow land disposal, *i.e.*, low-level radioactive waste with concentrations of radionuclides that exceed the limits established by the Commission for Class C radioactive waste (GTCC). The Low-Level Radioactive Waste Policy Amendments Act of 1985 assigned the Federal Government the responsibility for the disposal of this material. The Act also stated that the beneficiaries of the activities resulting in the generation of such radioactive waste bear all reasonable costs of disposing of such waste. However, to date, the Federal Government has not identified a cost for disposing of GTCC or a schedule for acceptance. As such, the estimates to decommission the Wolf Creek reactor include an allowance for the disposition of GTCC material.

For purposes of this study, GTCC is packaged in the same canisters used to transport spent fuel. Disposal costs are based upon a cost equivalent to that envisioned for the spent fuel. It is not anticipated that the DOE would accept this waste prior to completing the transfer of spent fuel. Therefore, until such time as the DOE is ready to accept GTCC waste, it is reasonable to assume that this material would remain in storage with the spent fuel in the storage pool at the Wolf Creek site (for the DECON alternative). In the SAFSTOR scenario, the GTCC material is generated after the fuel has been removed. As such, the GTCC is assumed to be disposed of as it is generated during reactor vessel segmentation operations.

#### **3.4.2 Reactor Vessel and Internal Components**

The NSSS (reactor vessel and reactor coolant system components) will be decontaminated using chemical agents prior to the start of cutting operations (for DECON alternative only). A decontamination factor (average reduction) of 10 is assumed for the process.

The reactor pressure vessel and internal components are segmented for disposal in shielded, reusable transportation casks. Segmentation is performed in the refueling canal, where a turntable and remote cutter are installed. The vessel is segmented in place, using a mast-mounted cutter supported off the lower head and directed from a shielded work platform installed overhead in the reactor cavity. Transportation cask specifications and transportation regulations dictate the segmentation and packaging methodology.

Intact disposal of the reactor vessel and internal components can provide savings in cost and worker exposure by eliminating the complex segmentation requirements, isolation of the GTCC material, and transport/storage of the resulting waste packages. Portland General Electric (PGE) was able to dispose of the Trojan reactor as an intact package. However, its location on the Columbia River simplified the transportation analysis since:

- the reactor package could be secured to the transport vehicle for the entire journey, *i.e.*, the package was not lifted during transport,

- there were no man-made or natural terrain features between the plant site and the disposal location that could produce a large drop, and
- transport speeds were very low, limited by the overland transport vehicle and the river barge.

As a member of the Northwest Compact, PGE had a site available for disposal of the package - the US Ecology facility in Washington State. The characteristics of this arid site proved favorable in demonstrating compliance with land disposal regulations.

It is not known whether this option will be available when the Wolf Creek unit ceases operation. Future viability of this option will depend upon the ultimate location of the disposal site, as well as the disposal site licensee's ability to accept highly radioactive packages and effectively isolate them from the environment. Consequently, the study assumes the reactor vessel will require segmentation, as a bounding condition.

### **3.4.3 Primary System Components**

The following discussion deals with the removal and disposition of the steam generators, but the techniques involved are also applicable to other large components, such as heat exchangers, component coolers, and the pressurizer. The steam generators' size and weight, as well as their location within the reactor building, will ultimately determine the removal strategy.

A trolley crane is set up for the removal of the generators. It can also be used to move portions of the steam generator cubicle walls and floor slabs from the reactor building to a location where they can be decontaminated and transported to the material handling area. Interferences within the work area, such as grating, piping, and other components are removed to create sufficient laydown space for processing these large components.

The generators are rigged for removal, disconnected from the surrounding piping and supports, and maneuvered into the open area where they are lowered onto a dolly. Each generator is rotated into the horizontal position for extraction from the containment and placed

onto a multi-wheeled vehicle for transport to an on-site processing and storage area.

The generators are disassembled on-site with the steam dome and lightly contaminated subassemblies designated for off-site recycling. The more highly contaminated tube sheet and tube bundle are packaged for direct disposal. The interior volume is filled with low-density cellular concrete for stabilization of the internal contamination.

Disposal costs are based upon the displaced volume of the units. Each component is then loaded onto a rail car for transport to the disposal facility.

Reactor coolant piping is cut from the reactor vessel once the water level in the vessel (used for personnel shielding during dismantling and cutting operations in and around the vessel) is dropped below the nozzle zone. The piping is boxed and transported by shielded van. The reactor coolant pumps and motors are lifted out intact, packaged, and transported for processing and/or disposal.

#### **3.4.4 Main Turbine and Condenser**

The main turbine is dismantled using conventional maintenance procedures. The turbine rotors and shafts are removed to a laydown area. The lower turbine casings are removed from their anchors by controlled demolition. The main condensers are also disassembled and moved to a laydown area. Material is then prepared for transportation to an off-site recycling facility where it is surveyed and designated for either decontamination or volume reduction, conventional disposal, or controlled disposal. Components are packaged and readied for transport in accordance with the intended disposition.

#### **3.4.5 Transportation Methods**

Contaminated piping, components, and structural material other than the highly activated reactor vessel and internal components will qualify as LSA-I, II or III or Surface Contaminated Object, SCO-I or II, as described in Title 49.<sup>[20]</sup> The contaminated material will be packaged in Industrial Packages (IP-1, IP-2, or IP-3, as defined in subpart 173.411) for transport unless demonstrated to qualify as their own shipping containers. The reactor vessel and internal components are expected to

be transported in accordance with §71, as Type B. It is conceivable that the reactor, due to its limited specific activity, could qualify as LSA II or III. However, the high radiation levels on the outer surface would require that additional shielding be incorporated within the packaging so as to attenuate the dose to levels acceptable for transport.

Transport of the highly activated metal, produced in the segmentation of the reactor vessel and internal components, will be by shielded truck cask. Cask shipments may exceed 95,000 pounds, including vessel segment(s), supplementary shielding, cask tie-downs, and tractor-trailer. The maximum level of activity per shipment assumed permissible was based upon the license limits of the available shielded transport casks. The segmentation scheme for the vessel and internal segments is designed to meet these limits.

The transport of large intact components, *e.g.*, large heat exchangers and other oversized components, will be by a combination of truck, rail, and/or multi-wheeled transporter.

Transportation costs for material requiring controlled disposal are based upon the mileage to the Envirocare facility in Clive, Utah. Memphis, Tennessee, is used as the destination for off-site processing. Transportation costs are estimated using published tariffs from Tri-State Motor Transit.<sup>[21]</sup>

#### **3.4.6 Low-Level Radioactive Waste Disposal**

To the greatest extent practical, metallic material generated in the decontamination and dismantling processes is treated to reduce the total volume requiring controlled disposal. The treated material, meeting the regulatory and/or site release criterion, is released as scrap, requiring no further cost consideration. Conditioning and recovery of the waste stream is performed off site at a licensed processing center.

The Envirocare facility is used as a proxy for the future disposal of decommissioning waste. Since Envirocare does not have a license for Class B or C material, the Barnwell rates are also used, as appropriate. Surcharges are added for the highly activated components, *e.g.*, generated in the segmentation of the reactor vessel.

### **3.4.7 Site Conditions Following Decommissioning**

The NRC will terminate (or amend) the site license if it determines that site remediation has been performed in accordance with the license termination plan, and that the terminal radiation survey and associated documentation demonstrate that the facility is suitable for release. The NRC's involvement in the decommissioning process will end at this point. Local building codes and state environmental regulations will dictate the next step in the decommissioning process, as well as the owners' own future plans for the site.

Non-essential structures or buildings severely damaged in the decontamination process are removed to a nominal depth of three feet below grade. Concrete rubble generated from demolition activities is processed and made available as clean fill for the power block foundations. Excess construction debris is trucked off site as an alternative to onsite disposal. The excavations will be regraded such that the power block area will have a final contour consistent with adjacent surroundings. The existing electrical switchyard and access roads will remain in support of the electrical transmission and distribution system. Other structures that will remain are the main dam, cooling lake, makeup water discharge structure (west side of lake), makeup water screen house (located below the John Redmond Dam) and associated underground piping, and the Eisenhower Learning Center.

The estimates do not assume the remediation of any significant volume of contaminated soil. This assumption may be affected by continued plant operations and/or future regulatory actions, such as the development of site-specific release criteria.

## **3.5 ASSUMPTIONS**

The following are the major assumptions made in the development of the estimates for decommissioning the site.

### **3.5.1 Estimating Basis**

The study follows the principles of ALARA through the use of work duration adjustment factors. These factors address the impact of activities such as radiological protection instruction, mock-up training, and the use of respiratory protection and protective clothing. The

factors lengthen a task's duration, increasing costs and lengthening the overall schedule. ALARA planning is considered in the costs for engineering and planning, and in the development of activity specifications and detailed procedures. Changes to worker exposure limits may impact the decommissioning cost and project schedule.

### **3.5.2 Labor Costs**

WCNOC will manage the decontamination and dismantling of the station in addition to maintaining site security, radiological health and safety, quality assurance and overall site administration during the decommissioning. Personnel costs are based upon average salary information provided by WCNOC. Overhead costs are included for site and corporate support, reduced commensurate with the staffing of the project.

WCNOC will hire a Decommissioning Operations Contractor (DOC) to manage the decommissioning. Contract personnel will provide engineering services, *e.g.*, for preparing the activity specifications, work procedures, activation, and structural analyses, under the direction of WCNOC.

The craft labor required to decontaminate and dismantle the nuclear unit is acquired through standard site contracting practices. The current cost of labor at the site is used as an estimating basis.

Security, while reduced from operating levels, is maintained throughout the decommissioning for access control, material control, and to safeguard the spent fuel.

### **3.5.3 Design Conditions**

Any fuel cladding failure that occurred during the lifetime of the plant is assumed to have released fission products at sufficiently low levels that the buildup of quantities of long-lived isotopes (*e.g.*, <sup>137</sup>Cs, <sup>90</sup>Sr, or transuranics) has been prevented from reaching levels exceeding those that permit the major NSSS components to be shipped under current transportation regulations and disposal requirements.

The curie contents of the vessel and internals at final shutdown are derived from those listed in NUREG/CR-3474.<sup>[22]</sup> Actual estimates are

derived from the curie/gram values contained therein and adjusted for the different mass of the Wolf Creek components, projected operating life, and different periods of decay. Additional short-lived isotopes were derived from CR-0130<sup>[23]</sup> and CR-0672,<sup>[24]</sup> and benchmarked to the long-lived values from CR-3474.

The control elements are disposed of along with the spent fuel, *i.e.*, there is no additional cost provided for their disposal.

Activation of the containment building structure is confined to the biological shield. More extensive activation (at very low levels) of the interior structures within containment has been detected at several reactors and the owners have elected to dispose of the affected material at a controlled facility rather than reuse the material as fill on site or send it to a landfill. The ultimate disposition of the material removed from the containment building will depend upon the site release criteria selected, as well as the designated end use for the site.

#### **3.5.4 General**

##### **Transition Activities**

Existing warehouses are cleared of non-essential material and remain for use by WCNOG and its subcontractors. The plant's operating staff performs the following activities at no additional cost or credit to the project during the transition period. The disposal of operating wastes and any associated legacy wastes during this initial period is not considered a decommissioning expense.

- Drain and collect fuel oils, lubricating oils, and transformer oils for recycle and/or sale.
- Drain and collect acids, caustics, and other chemical stores for recycle and/or sale.
- Process operating waste inventories.

##### **Scrap and Salvage**

The existing plant equipment is considered obsolete and suitable for scrap as deadweight quantities only. WCNOG will make economically



reasonable efforts to salvage equipment following final plant shutdown. However, dismantling techniques assumed by TLG for equipment in this analysis are not consistent with removal techniques required for salvage (resale) of equipment. Experience has indicated that some buyers wanted equipment stripped down to very specific requirements before they would consider purchase. This required expensive rework after the equipment had been removed from its installed location. Since placing a salvage value on this machinery and equipment would be speculative, and the value would be small in comparison to the overall decommissioning expenses, this analysis does not attempt to quantify the value that an owner may realize based upon those efforts.

It is assumed, for purposes of this analysis, that any value received from the sale of scrap generated in the dismantling process would be more than offset by the on-site processing costs. The dismantling techniques assumed in the decommissioning estimates do not include the additional cost for size reduction and preparation to meet “furnace ready” conditions. For example, the recovery of copper from electrical cabling may require the removal and disposition of any contaminated insulation, an added expense. With a volatile market, the potential profit margin in scrap recovery is highly speculative, regardless of the ability to free release this material. This assumption is an implicit recognition of scrap value in the disposal of clean metallic waste at no additional cost to the project.

Furniture, tools, mobile equipment such as forklifts, trucks, bulldozers, and other property is removed at no cost or credit to the decommissioning project. Disposition may include relocation to other facilities. Spare parts are also made available for alternative use.

### Energy

For estimating purposes, the plant is assumed to be de-energized, with the exception of those facilities associated with spent fuel storage. Replacement power costs are used to calculate the cost of energy consumed during decommissioning for tooling, lighting, ventilation, and essential services.

### Insurance

Costs for continuing coverage (nuclear liability and property insurance) following cessation of plant operations and during decommissioning are included and based upon current operating premiums. Reductions in premiums, throughout the decommissioning process, are based upon the guidance and the limits for coverage defined in the NRC's proposed rulemaking "Financial Protection Requirements for Permanently Shutdown Nuclear Power Reactors."<sup>[25]</sup> The NRC's financial protection requirements are based on various reactor (and spent fuel) configurations.

### Taxes

Property tax payments are included for the land and those facilities that will continue to be used to support the decommissioning project. As the facilities are abandoned, the taxes are reduced accordingly.

### Site Modifications

The perimeter fence and in-plant security barriers will be moved, as appropriate, to conform to the Site Security Plan in force during the various stages of the project.

## **3.6 COST ESTIMATE SUMMARY**

Schedules of expenditures are provided for each scenario in Tables 3.1 and 3.2. Four tables are provided for each decommissioning alternative delineating the total cost as well as the individual cost contributors of License Termination, Spent Fuel Management and Site Restoration. Decommissioning costs are reported in the year of projected expenditure; however, the values are provided in thousands of 2005 dollars. Costs are not inflated, escalated, or discounted over the period of expenditure. The annual expenditures are based upon the detailed activity costs reported in Appendix C and D, along with the timelines presented in Section 4.

As discussed in Section 3.4.2, it is not anticipated that the DOE would accept the GTCC waste prior to completing the transfer of spent fuel. Since the fuel is removed from the site well before decommissioning commences in the SAFSTOR scenario, the disposal of the GTCC is assumed to be concurrent with the disposal of the reactor vessel internals. While designated for disposal at the

geologic repository along with the spent fuel, GTCC waste is still classified as low-level radioactive waste and, as such, included as a “License Termination” expense.

**TABLE 3.1**  
**SCHEDULE OF DECON EXPENDITURES**  
(thousands, 2005 dollars)

Year	Labor	Equipment & Materials	Energy	Burial	Other <sup>[1]</sup>	Total
2025	31,518	2,813	1,265	29	4,126	39,750
2026	49,535	19,305	2,322	17,360	9,744	98,266
2027	43,971	18,596	1,481	35,342	17,654	117,045
2028	37,404	9,312	1,234	13,843	7,383	69,176
2029	35,668	7,006	1,170	8,531	4,842	57,217
2030	32,619	6,061	1,001	8,230	4,000	51,910
2031	23,390	2,728	426	2,776	1,227	30,547
2032	17,044	15,241	178	5	214	32,682
2033	10,079	10,749	97	0	84	21,009
	281,228	91,811	9,173	86,116	49,274	517,601

---

<sup>[1]</sup> Includes property taxes, insurance, fees, energy, and equipment/materials

**TABLE 3.1a  
SCHEDULE OF DECON EXPENDITURES  
LICENSE TERMINATION  
(thousands, 2005 dollars)**

Year	Labor	Equipment & Materials	Energy	Burial	Other	Total
2025	30,510	994	1,265	29	2,848	35,646
2026	47,625	16,955	2,322	17,360	8,117	92,379
2027	42,053	16,254	1,481	35,342	15,914	111,044
2028	35,745	7,048	1,234	13,843	5,770	63,641
2029	34,079	4,770	1,170	8,531	3,266	51,815
2030	31,522	4,516	1,001	8,230	2,912	48,180
2031	23,390	2,728	426	2,776	1,227	30,547
2032	3,113	278	43	5	98	3,536
2033	71	0	0	0	0	71
	248,108	53,543	8,941	86,116	40,152	436,860

**TABLE 3.1b  
SCHEDULE OF DECON EXPENDITURES  
SPENT FUEL MANAGEMENT**  
(thousands, 2005 dollars)

Year	Labor	Equipment & Materials	Energy	Burial	Other	Total
2025	606	1,819	0	0	1,278	3,703
2026	778	2,335	0	0	1,576	4,690
2027	765	2,294	0	0	1,576	4,634
2028	745	2,234	0	0	1,581	4,559
2029	737	2,212	0	0	1,576	4,525
2030	509	1,527	0	0	1,088	3,124
2031	0	0	0	0	0	0
2032	0	0	0	0	0	0
2033	0	0	0	0	0	0
	4,140	12,420	0	0	8,676	25,236

**TABLE 3.1c**  
**SCHEDULE OF DECON EXPENDITURES**  
**SITE RESTORATION**  
(thousands, 2005 dollars)

Year	Labor	Equipment & Materials	Energy	Burial	Other	Total
2025	401	0	0	0	0	401
2026	1,131	15	0	0	50	1,196
2027	1,154	49	0	0	164	1,366
2028	914	30	0	0	32	976
2029	852	25	0	0	0	877
2030	588	17	0	0	0	606
2031	0	0	0	0	0	0
2032	13,932	14,963	135	0	117	29,146
2033	10,008	10,749	97	0	84	20,937
	28,980	25,847	232	0	446	55,506

**TABLE 3.2**  
**SCHEDULE OF SAFSTOR EXPENDITURES**  
(thousands, 2005 dollars)

Year	Labor	Equipment & Materials	Energy	Burial	Other <sup>[1]</sup>	Total
2025	24,629	2,470	1,265	29	4,126	32,519
2026	28,933	11,308	1,177	2,363	5,233	49,014
2027	6,699	2,546	312	35	4,008	13,600
2028	6,718	2,553	313	35	4,019	13,637
2029	6,699	2,546	312	35	4,008	13,600
2030	5,191	1,838	264	35	3,032	10,360
2031	1,827	260	156	35	857	3,136
2032	1,832	261	156	35	859	3,144
2033	1,827	260	156	35	857	3,136
2034	1,827	260	156	35	857	3,136
2035	1,827	260	156	35	857	3,136
2036	1,832	261	156	35	859	3,144
2037	1,827	260	156	35	857	3,136
2038	1,827	260	156	35	857	3,136
2039	1,827	260	156	35	857	3,136
2040	1,832	261	156	35	859	3,144
2041	1,827	260	156	35	857	3,136
2042	1,827	260	156	35	857	3,136
2043	1,827	260	156	35	857	3,136
2044	1,832	261	156	35	859	3,144
2045	1,827	260	156	35	857	3,136
2046	1,827	260	156	35	857	3,136
2047	1,827	260	156	35	857	3,136
2048	1,832	261	156	35	859	3,144
2049	1,827	260	156	35	857	3,136
2050	1,827	260	156	35	857	3,136
2051	1,827	260	156	35	857	3,136
2052	1,832	261	156	35	859	3,144
2053	1,827	260	156	35	857	3,136
2054	1,827	260	156	35	857	3,136
2055	1,827	260	156	35	857	3,136
2056	1,832	261	156	35	859	3,144
2057	1,827	260	156	35	857	3,136
2058	1,827	260	156	35	857	3,136
2059	1,827	260	156	35	857	3,136
2060	1,832	261	156	35	859	3,144
2061	1,827	260	156	35	857	3,136



**TABLE 3.2 (continued)**  
**SCHEDULE OF SAFSTOR EXPENDITURES**  
(thousands, 2005 dollars)

Year	Labor	Equipment & Materials	Energy	Burial	Other <sup>(1)</sup>	Total
2062	1,827	260	156	35	857	3,136
2063	1,827	260	156	35	857	3,136
2064	1,832	261	156	35	859	3,144
2065	1,827	260	156	35	857	3,136
2066	1,827	260	156	35	857	3,136
2067	1,827	260	156	35	857	3,136
2068	1,832	261	156	35	859	3,144
2069	1,827	260	156	35	857	3,136
2070	1,827	260	156	35	857	3,136
2071	1,827	260	156	35	857	3,136
2072	1,832	261	156	35	859	3,144
2073	1,827	260	156	35	857	3,136
2074	1,827	260	156	35	857	3,136
2075	1,827	260	156	35	857	3,136
2076	1,832	261	156	35	859	3,144
2077	1,827	260	156	35	857	3,136
2078	1,827	260	156	35	857	3,136
2079	33,758	2,450	1,483	35	912	38,639
2080	35,119	11,106	1,529	15,434	8,910	72,098
2081	37,457	14,842	1,372	25,223	12,877	91,772
2082	30,169	4,254	1,170	7,622	1,777	44,991
2083	30,169	4,254	1,170	7,622	1,777	44,991
2084	24,963	2,966	672	3,215	1,035	32,852
2085	17,133	14,399	185	7	203	31,928
2086	10,967	11,696	106	0	91	22,860
	386,355	101,733	18,818	63,390	93,177	663,474

<sup>(1)</sup> Includes property taxes, insurance, fees, energy, and equipment/materials

**TABLE 3.2a**  
**SCHEDULE OF SAFSTOR EXPENDITURES**  
**LICENSE TERMINATION**  
(thousands, 2005 dollars)

Year	Labor	Equipment & Materials	Energy	Burial	Other	Total
2025	24,023	651	1,265	29	2,848	28,816
2026	26,952	9,148	1,129	2,363	3,174	42,765
2027	1,827	260	156	35	857	3,136
2028	1,832	261	156	35	859	3,144
2029	1,827	260	156	35	857	3,136
2030	1,827	260	156	35	857	3,136
2031	1,827	260	156	35	857	3,136
2032	1,832	261	156	35	859	3,144
2033	1,827	260	156	35	857	3,136
2034	1,827	260	156	35	857	3,136
2035	1,827	260	156	35	857	3,136
2036	1,832	261	156	35	859	3,144
2037	1,827	260	156	35	857	3,136
2038	1,827	260	156	35	857	3,136
2039	1,827	260	156	35	857	3,136
2040	1,832	261	156	35	859	3,144
2041	1,827	260	156	35	857	3,136
2042	1,827	260	156	35	857	3,136
2043	1,827	260	156	35	857	3,136
2044	1,832	261	156	35	859	3,144
2045	1,827	260	156	35	857	3,136
2046	1,827	260	156	35	857	3,136
2047	1,827	260	156	35	857	3,136
2048	1,832	261	156	35	859	3,144
2049	1,827	260	156	35	857	3,136
2050	1,827	260	156	35	857	3,136
2051	1,827	260	156	35	857	3,136
2052	1,832	261	156	35	859	3,144
2053	1,827	260	156	35	857	3,136
2054	1,827	260	156	35	857	3,136
2055	1,827	260	156	35	857	3,136
2056	1,832	261	156	35	859	3,144
2057	1,827	260	156	35	857	3,136
2058	1,827	260	156	35	857	3,136
2059	1,827	260	156	35	857	3,136
2060	1,832	261	156	35	859	3,144
2061	1,827	260	156	35	857	3,136

**TABLE 3.2a (continued)**  
**SCHEDULE OF SAFSTOR EXPENDITURES**  
**LICENSE TERMINATION**  
(thousands, 2005 dollars)

Year	Labor	Equipment & Materials	Energy	Burial	Other	Total
2062	1,827	260	156	35	857	3,136
2063	1,827	260	156	35	857	3,136
2064	1,832	261	156	35	859	3,144
2065	1,827	260	156	35	857	3,136
2066	1,827	260	156	35	857	3,136
2067	1,827	260	156	35	857	3,136
2068	1,832	261	156	35	859	3,144
2069	1,827	260	156	35	857	3,136
2070	1,827	260	156	35	857	3,136
2071	1,827	260	156	35	857	3,136
2072	1,832	261	156	35	859	3,144
2073	1,827	260	156	35	857	3,136
2074	1,827	260	156	35	857	3,136
2075	1,827	260	156	35	857	3,136
2076	1,832	261	156	35	859	3,144
2077	1,827	260	156	35	857	3,136
2078	1,827	260	156	35	857	3,136
2079	32,936	2,450	1,483	35	912	37,816
2080	34,033	11,078	1,529	15,434	8,904	70,977
2081	36,157	14,793	1,372	25,223	12,868	90,414
2082	29,401	4,231	1,170	7,622	1,777	44,200
2083	29,401	4,231	1,170	7,622	1,777	44,200
2084	24,641	2,957	672	3,215	1,035	32,521
2085	4,083	383	59	7	94	4,626
2086	78	0	0	0	0	78
	336,766	63,470	17,962	63,390	77,988	559,577

**TABLE 3.2b**  
**SCHEDULE OF SAFSTOR EXPENDITURES**  
**SPENT FUEL MANAGEMENT**  
(thousands, 2005 dollars)

Year	Labor	Equipment & Materials	Energy	Burial	Other	Total
2025	606	1,819	0	0	1,278	3,703
2026	1,981	2,160	48	0	2,059	6,249
2027	4,872	2,286	156	0	3,151	10,465
2028	4,886	2,292	156	0	3,159	10,493
2029	4,872	2,286	156	0	3,151	10,465
2030	3,364	1,578	108	0	2,175	7,225
2031	0	0	0	0	0	0
2032	0	0	0	0	0	0
2033	0	0	0	0	0	0
2034	0	0	0	0	0	0
2035	0	0	0	0	0	0
2036	0	0	0	0	0	0
2037	0	0	0	0	0	0
2038	0	0	0	0	0	0
2039	0	0	0	0	0	0
2040	0	0	0	0	0	0
2041	0	0	0	0	0	0
2042	0	0	0	0	0	0
2043	0	0	0	0	0	0
2044	0	0	0	0	0	0
2045	0	0	0	0	0	0
2046	0	0	0	0	0	0
2047	0	0	0	0	0	0
2048	0	0	0	0	0	0
2049	0	0	0	0	0	0
2050	0	0	0	0	0	0
2051	0	0	0	0	0	0
2052	0	0	0	0	0	0
2053	0	0	0	0	0	0
2054	0	0	0	0	0	0
2055	0	0	0	0	0	0
2056	0	0	0	0	0	0
2057	0	0	0	0	0	0
2058	0	0	0	0	0	0
2059	0	0	0	0	0	0
2060	0	0	0	0	0	0
2061	0	0	0	0	0	0

**TABLE 3.2b (continued)**  
**SCHEDULE OF SAFSTOR EXPENDITURES**  
**SPENT FUEL MANAGEMENT**  
(thousands, 2005 dollars)

Year	Labor	Equipment & Materials	Energy	Burial	Other	Total
2062	0	0	0	0	0	0
2063	0	0	0	0	0	0
2064	0	0	0	0	0	0
2065	0	0	0	0	0	0
2066	0	0	0	0	0	0
2067	0	0	0	0	0	0
2068	0	0	0	0	0	0
2069	0	0	0	0	0	0
2070	0	0	0	0	0	0
2071	0	0	0	0	0	0
2072	0	0	0	0	0	0
2073	0	0	0	0	0	0
2074	0	0	0	0	0	0
2075	0	0	0	0	0	0
2076	0	0	0	0	0	0
2077	0	0	0	0	0	0
2078	0	0	0	0	0	0
2079	0	0	0	0	0	0
2080	0	0	0	0	0	0
2081	0	0	0	0	0	0
2082	0	0	0	0	0	0
2083	0	0	0	0	0	0
2084	0	0	0	0	0	0
2085	0	0	0	0	0	0
2086	0	0	0	0	0	0
	20,582	12,420	624	0	14,974	48,599

**TABLE 3.2c**  
**SCHEDULE OF SAFSTOR EXPENDITURES**  
**SITE RESTORATION**  
(thousands, 2005 dollars)

Year	Labor	Equipment & Materials	Energy	Burial	Other	Total
2025	0	0	0	0	0	0
2026	0	0	0	0	0	0
2027	0	0	0	0	0	0
2028	0	0	0	0	0	0
2029	0	0	0	0	0	0
2030	0	0	0	0	0	0
2031	0	0	0	0	0	0
2032	0	0	0	0	0	0
2033	0	0	0	0	0	0
2034	0	0	0	0	0	0
2035	0	0	0	0	0	0
2036	0	0	0	0	0	0
2037	0	0	0	0	0	0
2038	0	0	0	0	0	0
2039	0	0	0	0	0	0
2040	0	0	0	0	0	0
2041	0	0	0	0	0	0
2042	0	0	0	0	0	0
2043	0	0	0	0	0	0
2044	0	0	0	0	0	0
2045	0	0	0	0	0	0
2046	0	0	0	0	0	0
2047	0	0	0	0	0	0
2048	0	0	0	0	0	0
2049	0	0	0	0	0	0
2050	0	0	0	0	0	0
2051	0	0	0	0	0	0
2052	0	0	0	0	0	0
2053	0	0	0	0	0	0
2054	0	0	0	0	0	0
2055	0	0	0	0	0	0
2056	0	0	0	0	0	0
2057	0	0	0	0	0	0
2058	0	0	0	0	0	0
2059	0	0	0	0	0	0
2060	0	0	0	0	0	0
2061	0	0	0	0	0	0

**TABLE 3.2c (continued)**  
**SCHEDULE OF SAFSTOR EXPENDITURES**  
**SITE RESTORATION**  
(thousands, 2005 dollars)

Year	Labor	Equipment & Materials	Energy	Burial	Other	Total
2062	0	0	0	0	0	0
2063	0	0	0	0	0	0
2064	0	0	0	0	0	0
2065	0	0	0	0	0	0
2066	0	0	0	0	0	0
2067	0	0	0	0	0	0
2068	0	0	0	0	0	0
2069	0	0	0	0	0	0
2070	0	0	0	0	0	0
2071	0	0	0	0	0	0
2072	0	0	0	0	0	0
2073	0	0	0	0	0	0
2074	0	0	0	0	0	0
2075	0	0	0	0	0	0
2076	0	0	0	0	0	0
2077	0	0	0	0	0	0
2078	0	0	0	0	0	0
2079	823	0	0	0	0	823
2080	1,087	28	0	0	6	1,121
2081	1,300	49	0	0	9	1,358
2082	768	22	0	0	0	790
2083	768	22	0	0	0	790
2084	322	9	0	0	0	331
2085	13,050	14,016	126	0	109	27,302
2086	10,890	11,696	106	0	91	22,782
	29,007	25,843	232	0	215	55,297

## **4. SCHEDULE ESTIMATE**

The schedules for the decommissioning scenarios considered in this study follow the sequences presented in the AIF/NESP-036 study, with minor changes to reflect recent experience and site-specific constraints. In addition, the scheduling has been revised to reflect the spent fuel management plan described in Section 3.4.1.

A schedule or sequence of activities for the DECON alternative is presented in Figure 4.1. The scheduling sequence assumes that fuel is removed from the spent fuel pool within 5½ years. The key activities listed in the schedule do not reflect a one-to-one correspondence with those activities in the cost tables, but reflect dividing some activities for clarity and combining others for convenience. The schedule was prepared using the "Microsoft Project Professional 2002" computer software.<sup>[26]</sup>

### **4.1 SCHEDULE ESTIMATE ASSUMPTIONS**

The schedule reflects the results of a precedence network developed for the site decommissioning activities, *i.e.*, a PERT (Program Evaluation and Review Technique) Software Package. The work activity durations used in the precedence network reflect the actual man-hour estimates from the cost table, adjusted by stretching certain activities over their slack range and shifting the start and end dates of others. The following assumptions were made in the development of the decommissioning schedule:

- The fuel building is isolated until such time that all spent fuel has been discharged from the spent fuel pool to the DOE. Decontamination and dismantling of the storage pool is initiated once the transfer of spent fuel is complete (DECON option).
- All work (except vessel and internals removal) is performed during an 8-hour workday, 5 days per week, with no overtime. There are eleven paid holidays per year.
- Reactor and internals removal activities are performed by using separate crews for different activities working on different shifts, with a corresponding backshift charge for the second shift.
- Multiple crews work parallel activities to the maximum extent possible, consistent with optimum efficiency, adequate access for cutting, removal



and laydown space, and with the stringent safety measures necessary during demolition of heavy components and structures.


- For plant systems removal, the systems with the longest removal durations in areas on the critical path are considered to determine the duration of the activity.

## **4.2 PROJECT SCHEDULE**

The period-dependent costs presented in the detailed cost tables are based upon the durations developed in the schedules for decommissioning. Durations are established between several milestones in each project period; these durations are used to establish a critical path for the entire project. In turn, the critical path duration for each period is used as the basis for determining the period-dependent costs. A second critical path is shown for the spent fuel storage period, which determines the release of the auxiliary building for final decontamination.

Project timelines are provided in Figures 4.2 and 4.3 with milestone dates based on a 2025 shutdown date. The fuel pool is emptied approximately 5½ years after shutdown. Deferred decommissioning in the SAFSTOR scenarios is assumed to commence so that the operating license is terminated within a 60-year period from the cessation of plant operations.


**FIGURE 4.1  
ACTIVITY SCHEDULE**




Milestone Summary task External Milestone   
 Critical Path Task Performed During Period Deadline

**FIGURE 4.2  
DECOMMISSIONING TIMELINES  
(not to scale)**

**DECON Alternative**



**SAFSTOR Alternative**



## **5. RADIOACTIVE WASTES**

The objectives of the decommissioning process are the removal of all radioactive material from the site that would restrict its future use and the termination of the NRC license(s). This currently requires the remediation of all radioactive material at the site in excess of applicable legal limits. Under the Atomic Energy Act,<sup>[27]</sup> the NRC is responsible for protecting the public from sources of ionizing radiation. Title 10 of the Code of Federal Regulations delineates the production, utilization, and disposal of radioactive materials and processes. In particular, §71 defines radioactive material as it pertains to transportation and §61 specifies its disposition.

Most of the materials being transported for controlled burial are categorized as Low Specific Activity (LSA) or Surface Contaminated Object (SCO) materials containing Type A quantities, as defined in 49 CFR §173-178. Shipping containers are required to be Industrial Packages (IP-1, IP-2 or IP-3, as defined in subpart 173.411). For this study, commercially available steel containers are presumed to be used for the disposal of piping, small components, and concrete. Larger components can serve as their own containers, with proper closure of all openings, access ways, and penetrations.

The volumes of radioactive waste generated during the various decommissioning activities at the site are shown on a line-item basis in Appendices C and D, and summarized in Tables 5.1 and 5.2. The quantified waste volume summaries shown in these tables are consistent with §61 classifications. The volumes are calculated based on the exterior dimensions for containerized material and on the displaced volume of components serving as their own waste containers.

The reactor vessel and internals are categorized as large quantity shipments and, accordingly, will be shipped in reusable, shielded truck casks with disposable liners. In calculating disposal costs, the burial fees are applied against the liner volume, as well as the special handling requirements of the payload. Packaging efficiencies are lower for the highly activated materials (greater than Type A quantity waste), where high concentrations of gamma-emitting radionuclides limit the capacity of the shipping canisters.

No process system containing/handling radioactive substances at shutdown is presumed to meet material release criteria by decay alone, *i.e.*, systems radioactive at shutdown will still be radioactive over the time period during which the decommissioning is accomplished, due to the presence of long-lived radionuclides.

While the dose rates decrease with time, radionuclides such as  $^{137}\text{Cs}$  will still control the disposition requirements.

The waste material generated in the decontamination and dismantling of the nuclear station is primarily generated during Period 2 of DECON and Period 4 of SAFSTOR. Material that is considered potentially contaminated when removed from the radiologically controlled area is sent to processing facilities in Tennessee for conditioning and disposal at a unit cost of \$2.15 per pound (excluding transportation). Heavily contaminated components and activated materials are routed for controlled disposal. The disposal volumes reported in the tables reflect the savings resulting from reprocessing and recycling.

For purposes of constructing the estimates, the cost for disposal at the Envirocare facility was used as a proxy for future disposal facilities. A rate of \$268 per cubic foot is used for containerized waste and other large components including the reactor coolant pump motors. Demolition debris including miscellaneous steel, metal siding, scaffolding, and structural steel is disposed of at a bulk rate of \$36.75 per cubic foot. A unit rate of \$70 per cubic foot is used for the disposal of dry active waste.

Since Envirocare is not currently able to receive the more highly radioactive components generated in the decontamination and dismantling of the reactor, disposal costs for the Class B and C material are based upon Barnwell rates. An average disposal rate of approximately \$484 per cubic foot (based upon a waste density of 85 pounds per cubic foot) is used for this material, with additional surcharges for activity, dose rate, and/or handling added as appropriate for the particular package.

**TABLE 5.1  
DECOMMISSIONING WASTE SUMMARY  
DECON**

	<b>Waste Class<sup>1</sup></b>	<b>Volume (cubic feet)</b>	<b>Weight (pounds)</b>
<hr/>			
Low-Level Radioactive Waste			
	A	101,461	9,078,672
	B	12,680	1,907,275
	C	861	105,570
Geologic Repository (Greater-than Class C)			
	>C	559	116,756
		<hr/>	<hr/>
Total <sup>2</sup>		115,560	11,208,273
Processed Waste (Off Site)			9,770,048
Scrap Metal			134,376,815

<sup>1</sup> Waste is classified according to the requirements as delineated in Title 10 CFR, Part 61.55

<sup>2</sup> Columns may not add due to rounding.

**TABLE 5.2  
DECOMMISSIONING WASTE SUMMARY  
SAFSTOR**

	<b>Waste Class<sup>1</sup></b>	<b>Volume (cubic feet)</b>	<b>Weight (pounds)</b>
<hr/>			
Low-Level Radioactive Waste			
	A	94,820	6,950,421
	B	5,662	653,035
	C	845	101,865
Geologic Repository (Greater-than Class C)			
	>C	559	116,756
Total <sup>2</sup>		<hr/> 101,885	<hr/> 7,822,077
Processed Waste (Off Site)			11,356,310
Scrap Metal			134,710,392

<sup>1</sup> Waste is classified according to the requirements as delineated in Title 10 CFR, Part 61.55

<sup>2</sup> Columns may not add due to rounding.

## **6. RESULTS**

The analysis to estimate the costs to decommission Wolf Creek relied upon the site-specific, technical information developed for a previous analysis prepared in 2002. While not an engineering study, the estimates provide WCNOG with sufficient information to assess their financial obligations, as they pertain to the eventual decommissioning of the nuclear station.

The estimates described in this report are based on numerous fundamental assumptions, including regulatory requirements, project contingencies, low-level radioactive waste disposal practices, high-level radioactive waste management options, and site restoration requirements. The decommissioning scenarios assume continued operation of the station's spent fuel pool for a minimum of 5½ years following the cessation of operations for continued cooling of the assemblies. Once sufficiently cooled, the assemblies will be transferred to a DOE transport cask for disposition.

The cost projected to promptly decommission (DECON) Wolf Creek is estimated to be \$517.6 million. The majority of this cost (approximately 84.4%) is associated with the physical decontamination and dismantling of the nuclear unit so that the operating license can be terminated. Another 4.9% is associated with the management and transfer of the spent fuel. The remaining 10.7% is for the demolition of the designated structures and limited restoration of the site.

The cost projected for deferred decommissioning (SAFSTOR) is estimated to be \$663.5 million. The majority of this cost (approximately 84.3%) is associated with placing the unit in storage, ongoing caretaking of the unit during dormancy, and the eventual physical decontamination and dismantling of the nuclear unit so that the operating license can be terminated. Another 7.3% is associated with the management, interim storage, and eventual transfer of the spent fuel. The remaining 8.3% is for the demolition of the designated structures and limited restoration of the site.

The primary cost contributors, identified in Tables 6.1 and 6.2, are either labor-related or associated with the management and disposition of the radioactive waste. Program management is the largest single contributor to the overall cost. The magnitude of the expense is a function of both the size of the organization required to manage the decommissioning, as well as the duration of the program. It is assumed, for purposes of this analysis, that WCNOG will oversee the decommissioning program, using a DOC to manage the decommissioning labor force



and the associated subcontractors. The size and composition of the management organization varies with the decommissioning phase and associated site activities. However, once the operating license is terminated, the staff is substantially reduced for the conventional demolition and restoration of the site.

As described in this report, the spent fuel pool will remain operational for a minimum of 5½ years following the cessation of operations. The pool will be isolated and an independent spent fuel island created. This will allow decommissioning operations to proceed in and around the pool area. Over the 5½-year period, the spent fuel will be packaged for loading into a DOE-provided transport cask.

The cost for waste disposal includes only those costs associated with the controlled disposition of the low-level radioactive waste generated from decontamination and dismantling activities, including plant equipment and components, structural material, filters, resins and dry-active waste. As described in Section 5, disposition of the low-level radioactive material required controlled disposal is at the Envirocare facility. Highly activated components, requiring additional isolation from the environment, are packaged for geologic disposal. The cost of geologic disposal is based upon a cost equivalent for spent fuel.

A significant portion of the metallic waste is designated for additional processing and treatment at an off-site facility. Processing reduces the volume of material requiring controlled disposal through such techniques and processes as survey and sorting, decontamination, and volume reduction. The material that cannot be unconditionally released is packaged for controlled disposal at one of the currently operating facilities. The cost identified in the summary tables for processing is all-inclusive, incorporating the ultimate disposition of the material.

Removal costs reflect the labor-intensive nature of the decommissioning process, as well as the management controls required to ensure a safe and successful program. Decontamination and packaging costs also have a large labor component that is based upon prevailing union wages. Non-radiological demolition is a natural extension of the decommissioning process. The methods employed in decontamination and dismantling are generally destructive and indiscriminate in inflicting collateral damage. With a work force mobilized to support decommissioning operations, non-radiological demolition can be an integrated activity and a logical expansion of the work being performed in the process of terminating the operating license. Prompt demolition reduces future liabilities and can be more cost effective than deferral, due to the deterioration of the facilities (and therefore the working conditions) with time.

The reported cost for transport includes the tariffs and surcharges associated with moving large components and/or overweight shielded casks overland, as well as the general expense, *e.g.*, labor and fuel, of transporting material to the destinations identified in this report. For purposes of this analysis, material is primarily moved overland by truck.

Decontamination is used to reduce the plant's radiation fields and minimize worker exposure. Slightly contaminated material or material located within a contaminated area is sent to an off-site processing center, *i.e.*, this analysis does not assume that contaminated plant components and equipment can be decontaminated for uncontrolled release in-situ. Centralized processing centers have proven to be a more economical means of handling the large volumes of material produced in the dismantling of a nuclear unit.

License termination survey costs are associated with the labor intensive and complex activity of verifying that contamination has been removed from the site to the levels specified by the regulating agency. This process involves a systematic survey of all remaining plant surface areas and surrounding environs, sampling, isotopic analysis, and documentation of the findings. The status of any plant components and materials not removed in the decommissioning process will also require confirmation and will add to the expense of surveying the facilities alone.

The remaining costs include allocations for heavy equipment and temporary services, as well as for other expenses such as regulatory fees and the premiums for nuclear insurance. While site operating costs are greatly reduced following the final cessation of plant operations, certain administrative functions do need to be maintained either at a basic functional or regulatory level.

**TABLE 6.1  
SUMMARY OF DECOMMISSIONING COST ELEMENTS  
DECON**

<b>Cost Element</b>	<b>Cost 2005\$ (thousands)</b>	<b>Percent of Total Costs</b>
Decontamination	12,139	2.3
Removal	89,518	17.3
Packaging	12,276	2.4
Transportation	7,780	1.5
Waste Disposal	77,162	14.9
Off-site Waste Processing	24,006	4.6
Program Management <sup>[1]</sup>	219,348	42.4
Spent Fuel Pool Isolation	9,900	1.9
Spent Fuel Related	25,236	4.9
Insurance and Regulatory Fees	7,236	1.4
Energy	9,173	1.8
Characterization and Licensing Surveys	8,153	1.6
Property Taxes	9,711	1.9
Miscellaneous Equipment / Site Services	5,963	1.2
<b>Total <sup>[2]</sup></b>	<b>517,601</b>	<b>100.0</b>
 NRC License Termination	 436,860	 84.4
Spent Fuel Management <sup>[3]</sup>	25,236	4.9
Site Restoration	55,506	10.7
<b>Total <sup>[2]</sup></b>	<b>517,601</b>	<b>100.0</b>

<sup>[1]</sup> Utility staffing includes engineering and security.

<sup>[2]</sup> Columns may not add due to rounding.

<sup>[3]</sup> Includes fuel loading/packaging costs

**TABLE 6.2  
SUMMARY OF DECOMMISSIONING COST ELEMENTS  
SAFSTOR**

<b>Cost Element</b>	<b>Cost 2005\$ (thousands)</b>	<b>Percent of Total Costs</b>
Decontamination	9,863	1.5
Removal	89,768	13.5
Packaging	10,162	1.5
Transportation	5,556	0.8
Waste Disposal	50,514	7.6
Off-site Waste Processing	27,928	4.2
Program Management <sup>[1]</sup>	325,335	49.0
Spent Fuel Pool Isolation	9,900	1.5
Spent Fuel Related	25,236	3.8
Insurance and Regulatory Fees	45,165	6.8
Energy	18,818	2.8
Characterization and Licensing Surveys	9,561	1.4
Property Taxes	16,548	2.5
Miscellaneous Equipment / Site Services	19,119	2.9
<b>Total <sup>[2]</sup></b>	<b>663,474</b>	<b>100.0</b>
 NRC License Termination	 559,577	 84.3
Spent Fuel Management <sup>[3]</sup>	48,599	7.3
Site Restoration	55,297	8.3
<b>Total <sup>[2]</sup></b>	<b>663,474</b>	<b>100.0</b>

<sup>[1]</sup> Utility staffing includes engineering and security.

<sup>[2]</sup> Columns may not add due to rounding.

<sup>[3]</sup> Includes fuel loading/packaging costs

## **7. REFERENCES**

1. U.S. Code of Federal Regulations, Title 10, Parts 30, 40, 50, 51, 70 and 72, "General Requirements for Decommissioning Nuclear Facilities," Nuclear Regulatory Commission, Federal Register Volume 53, Number 123 (p 24018 et seq.), June 27, 1988.
2. U.S. Nuclear Regulatory Commission, Regulatory Guide 1.159, "Assuring the Availability of Funds for Decommissioning Nuclear Reactors," October 2003.
3. U.S. Code of Federal Regulations, Title 10, Part 20, Subpart E, "Radiological Criteria for License Termination."
4. U.S. Code of Federal Regulations, Title 10, Parts 20 and 50, "Entombment Options for Power Reactors," Advanced Notice of Proposed Rulemaking, Federal Register Volume 66, Number 200, October 16, 2001.
5. U.S. Code of Federal Regulations, Title 10, Parts 2, 50 and 51, "Decommissioning of Nuclear Power Reactors," Nuclear Regulatory Commission, Federal Register Volume 61 (p 39278 et seq.), July 29, 1996.
6. "Nuclear Waste Policy Act of 1982 and Amendments," U.S. Department of Energy's Office of Civilian Radioactive Management, 1982.
7. U.S. Code of Federal Regulations, Title 10, Part 50, "Domestic Licensing of Production and Utilization Facilities," Subpart 54 (bb), "Conditions of Licenses."
8. "Low Level Radioactive Waste Policy Act," Public Law 96-573, 1980.
9. "Low-Level Radioactive Waste Policy Amendments Act of 1985," Public Law 99-240, January 15, 1986.
10. U.S. Code of Federal Regulations, Title 10, Part 20, Subpart E, "Radiological Criteria for License Termination," Federal Register, Volume 62, Number 139 (p 39058 et seq.), July 21, 1997.
11. "Establishment of Cleanup Levels for CERCLA Sites with Radioactive Contamination," EPA Memorandum OSWER No. 9200.4-18, August 22, 1997.

## **7. REFERENCES**

(continued)

12. U.S. Code of Federal Regulations, Title 40, Part 141.16, "Maximum contaminant levels for beta particle and photon radioactivity from man-made radionuclides in community water systems."
13. "Memorandum of Understanding Between the Environmental Protection Agency and the Nuclear Regulatory Commission: Consultation and Finality on Decommissioning and Decontamination of Contaminated Sites," OSWER 9295.8-06a, October 9, 2002.
14. "Multi-Agency Radiation Survey and Site Investigation Manual (MARSSIM)," NUREG/CR-1575, Rev. 1, EPA 402-R-97-016, Rev. 1, August 2000.
15. "Decommissioning Cost Analysis for the Wolf Creek Generating Station," Document No. W11-1442-002, Rev. 0, TLG Services, Inc., August 2002.
16. T.S. LaGuardia et al., "Guidelines for Producing Commercial Nuclear Power Plant Decommissioning Cost Estimates," AIF/NESP-036, May 1986.
17. W.J. Manion and T.S. LaGuardia, "Decommissioning Handbook," U.S. Department of Energy, DOE/EV/10128-1, November 1980.
18. "Building Construction Cost Data 2005," Robert Snow Means Company, Inc., Kingston, Massachusetts.
19. Project and Cost Engineers' Handbook, Second Edition, p. 239, American Association of Cost Engineers, Marcel Dekker, Inc., New York, New York, 1984.
20. U.S. Department of Transportation, Section 49 of the Code of Federal Regulations, "Transportation," Parts 173 through 178, 1996.
21. Tri-State Motor Transit Company, published tariffs, Interstate Commerce Commission (ICC), Docket No. MC-427719 Rules Tariff, March 2004, Radioactive Materials Tariff, January 2004.

**7. REFERENCES**  
(continued)

22. J.C. Evans et al., "Long-Lived Activation Products in Reactor Materials" NUREG/CR-3474, Pacific Northwest Laboratory for the Nuclear Regulatory Commission. August 1984.
23. R.I. Smith, G.J. Konzek, W.E. Kennedy, Jr., "Technology, Safety and Costs of Decommissioning a Reference Pressurized Water Reactor Power Station," NUREG/CR-0130 and addenda, Pacific Northwest Laboratory for the Nuclear Regulatory Commission. June 1978.
24. H.D. Oak, et al., "Technology, Safety and Costs of Decommissioning a Reference Boiling Water Reactor Power Station," NUREG/CR-0672 and addenda, Pacific Northwest Laboratory for the Nuclear Regulatory Commission. June 1980.
25. "Financial Protection Requirements for Permanently Shutdown Nuclear Power Reactors," 10 CFR Parts 50 and 140, Federal Register Notice, Vol. 62, No. 210, October 30, 1997.
26. "Microsoft Project Professional 2002," Microsoft Corporation, Redmond, WA.
27. "Atomic Energy Act of 1954," (68 Stat. 919).

**APPENDIX A**

**UNIT COST FACTOR DEVELOPMENT**



**APPENDIX A  
UNIT COST FACTOR DEVELOPMENT**

Example: Unit Factor for Removal of Contaminated Heat Exchanger < 3,000 lbs.

**1. SCOPE**

Heat exchangers weighing < 3,000 lbs. will be removed in one piece using a crane or small hoist. They will be disconnected from the inlet and outlet piping. The heat exchanger will be sent to the waste processing area.

**2. CALCULATIONS**

Act ID	Activity Description	Activity Duration (minutes)	Critical Duration (minutes)*
a	Remove insulation	60	(b)
b	Mount pipe cutters	60	60
c	Install contamination controls	20	(b)
d	Disconnect inlet and outlet lines	60	60
e	Cap openings	20	(d)
f	Rig for removal	30	30
g	Unbolt from mounts	30	30
h	Remove contamination controls	15	15
i	Remove, wrap, send to waste processing area	<u>60</u>	<u>60</u>
	Totals (Activity/Critical)	355	255

Duration adjustment(s):

+ Respiratory protection adjustment (50% of critical duration) 128

+ Radiation/ALARA adjustment (40% of critical duration) 102

Adjusted work duration 485

+ Protective clothing adjustment (30% of adjusted duration) 146

Productive work duration 631

+ Work break adjustment (8.33 % of productive duration) 53

Total work duration (minutes) 684

**\*\*\* Total duration = 11.400 hr \*\*\***

\* alpha designators indicate activities that can be performed in parallel

**APPENDIX A  
(continued)**

**3. LABOR REQUIRED**

Crew	Number	Duration (hours)	Rate (\$/hr)	Cost
<hr/>				
Laborers	3.00	11.400	\$15.24	\$521.21
Craftsmen	2.00	11.400	\$22.31	\$508.67
Foreman	1.00	11.400	\$23.71	\$270.29
General Foreman	0.25	11.400	\$26.04	\$74.21
Fire Watch	0.05	11.400	\$15.24	\$8.69
Health Physics Technician	1.00	11.400	\$44.54	<u>\$507.76</u>
Total labor cost				\$1,890.83

**4. EQUIPMENT & CONSUMABLES COSTS**

Equipment Costs	none
Consumables/Materials Costs	
-Blotting paper 50 @ \$0.47 sq ft {1}	\$23.50
-Plastic sheets/bags 50 @ \$0.11/sq ft {2}	\$5.50
-Gas torch consumables 1 @ \$8.18/hr x 1 hr {3}	<u>\$8.18</u>
Subtotal cost of equipment and materials	\$37.18
Overhead & profit on equipment and materials @ 15.30 %	<u>\$5.69</u>
Total costs, equipment & material	\$42.87

**TOTAL COST:**

<b>Removal of contaminated heat exchanger &lt;3000 pounds:</b>	<b>\$1,933.70</b>
Total labor cost:	\$1890.83
Total equipment/material costs:	\$42.87
Total craft labor man-hours required per unit:	83.220

**APPENDIX A  
(continued)**

**5. NOTES AND REFERENCES**

- Work difficulty factors were developed in conjunction with the Atomic Industrial Forum's (now NEI) program to standardize nuclear decommissioning cost estimates and are delineated in Volume 1, Chapter 5 of the "Guidelines for Producing Commercial Nuclear Power Plant Decommissioning Cost Estimates," AIF/NESP-036, May 1986.
- References for equipment & consumables costs:
  1. [www.mcmaster.com](http://www.mcmaster.com) online catalog
  2. R.S. Means (2005) Section 01540-800-0200, page 17
  3. R.S. Means (2005) Section 01590-400-6360, page 25
- Material and consumable costs were adjusted using the regional indices for Emporia, Kansas.

**APPENDIX B**

**UNIT COST FACTOR LISTING  
(DECON: Power Block Structures Only)**

**APPENDIX B**

**UNIT COST FACTOR LISTING  
(Power Block Structures Only)**

<b>Unit Cost Factor</b>	<b>Cost/Unit(\$)</b>
Removal of clean instrument and sampling tubing, \$/linear foot	0.17
Removal of clean pipe 0.25 to 2 inches diameter, \$/linear foot	1.84
Removal of clean pipe >2 to 4 inches diameter, \$/linear foot	2.68
Removal of clean pipe >4 to 8 inches diameter, \$/linear foot	5.33
Removal of clean pipe >8 to 14 inches diameter, \$/linear foot	10.15
Removal of clean pipe >14 to 20 inches diameter, \$/linear foot	13.24
Removal of clean pipe >20 to 36 inches diameter, \$/linear foot	19.47
Removal of clean pipe >36 inches diameter, \$/linear foot	23.11
Removal of clean valve >2 to 4 inches	35.31
Removal of clean valve >4 to 8 inches	53.29
Removal of clean valve >8 to 14 inches	101.46
Removal of clean valve >14 to 20 inches	132.42
Removal of clean valve >20 to 36 inches	194.68
Removal of clean valve >36 inches	231.10
Removal of clean pipe hanger for small bore piping	12.56
Removal of clean pipe hanger for large bore piping	42.86
Removal of clean pump, <300 pound	90.93
Removal of clean pump, 300-1000 pound	253.46
Removal of clean pump, 1000-10,000 pound	991.74
Removal of clean pump, >10,000 pound	1,921.56
Removal of clean pump motor, 300-1000 pound	105.27
Removal of clean pump motor, 1000-10,000 pound	411.10
Removal of clean pump motor, >10,000 pound	924.94
Removal of clean heat exchanger <3000 pound	535.12
Removal of clean heat exchanger >3000 pound	1,352.00

**APPENDIX B**

**UNIT COST FACTOR LISTING  
(Power Block Structures Only)**

<b>Unit Cost Factor</b>	<b>Cost/Unit(\$)</b>
Removal of clean feedwater heater/deaerator	3,793.04
Removal of clean moisture separator/reheater	7,773.64
Removal of clean tank, <300 gallons	116.84
Removal of clean tank, 300-3000 gallon	366.48
Removal of clean tank, >3000 gallons, \$/square foot surface area	3.12
Removal of clean electrical equipment, <300 pound	48.68
Removal of clean electrical equipment, 300-1000 pound	171.39
Removal of clean electrical equipment, 1000-10,000 pound	342.80
Removal of clean electrical equipment, >10,000 pound	821.50
Removal of clean electrical transformer < 30 tons	570.52
Removal of clean electrical transformer > 30 tons	1,643.00
Removal of clean standby diesel generator, <100 kW	582.74
Removal of clean standby diesel generator, 100 kW to 1 MW	1,300.71
Removal of clean standby diesel generator, >1 MW	2,692.71
Removal of clean electrical cable tray, \$/linear foot	4.62
Removal of clean electrical conduit, \$/linear foot	2.02
Removal of clean mechanical equipment, <300 pound	48.68
Removal of clean mechanical equipment, 300-1000 pound	171.39
Removal of clean mechanical equipment, 1000-10,000 pound	342.80
Removal of clean mechanical equipment, >10,000 pound	821.50
Removal of clean HVAC equipment, <300 pound	48.68
Removal of clean HVAC equipment, 300-1000 pound	171.39
Removal of clean HVAC equipment, 1000-10,000 pound	342.80
Removal of clean HVAC equipment, >10,000 pound	821.50
Removal of clean HVAC ductwork, \$/pound	0.18

**APPENDIX B**

**UNIT COST FACTOR LISTING  
(Power Block Structures Only)**

<b>Unit Cost Factor</b>	<b>Cost/Unit(\$)</b>
Removal of contaminated instrument and sampling tubing, \$/linear foot	0.78
Removal of contaminated pipe 0.25 to 2 inches diameter, \$/linear foot	10.91
Removal of contaminated pipe >2 to 4 inches diameter, \$/linear foot	17.58
Removal of contaminated pipe >4 to 8 inches diameter, \$/linear foot	28.63
Removal of contaminated pipe >8 to 14 inches diameter, \$/linear foot	54.29
Removal of contaminated pipe >14 to 20 inches diameter, \$/linear foot	65.15
Removal of contaminated pipe >20 to 36 inches diameter, \$/linear foot	89.42
Removal of contaminated pipe >36 inches diameter, \$/linear foot	105.26
Removal of contaminated valve >2 to 4 inches	223.89
Removal of contaminated valve >4 to 8 inches	258.81
Removal of contaminated valve >8 to 14 inches	509.45
Removal of contaminated valve >14 to 20 inches	648.08
Removal of contaminated valve >20 to 36 inches	860.78
Removal of contaminated valve >36 inches	1,019.15
Removal of contaminated pipe hanger for small bore piping	55.58
Removal of contaminated pipe hanger for large bore piping	165.97
Removal of contaminated pump, <300 pound	463.80
Removal of contaminated pump, 300-1000 pound	1,039.77
Removal of contaminated pump, 1000-10,000 pound	3,083.34
Removal of contaminated pump, >10,000 pound	7,498.13
Removal of contaminated pump motor, 300-1000 pound	455.35
Removal of contaminated pump motor, 1000-10,000 pound	1,265.94
Removal of contaminated pump motor, >10,000 pound	2,845.71
Removal of contaminated heat exchanger <3000 pound	1,933.70
Removal of contaminated heat exchanger >3000 pound	5,637.16

**APPENDIX B**

**UNIT COST FACTOR LISTING  
(Power Block Structures Only)**

<b>Unit Cost Factor</b>	<b>Cost/Unit(\$)</b>
Removal of contaminated tank, <300 gallons	779.10
Removal of contaminated tank, >300 gallons, \$/square foot	14.48
Removal of contaminated electrical equipment, <300 pound	353.65
Removal of contaminated electrical equipment, 300-1000 pound	825.63
Removal of contaminated electrical equipment, 1000-10,000 pound	1,588.47
Removal of contaminated electrical equipment, >10,000 pound	3,053.11
Removal of contaminated electrical cable tray, \$/linear foot	17.04
Removal of contaminated electrical conduit, \$/linear foot	7.88
Removal of contaminated mechanical equipment, <300 pound	391.09
Removal of contaminated mechanical equipment, 300-1000 pound	911.06
Removal of contaminated mechanical equipment, 1000-10,000 pound	1,752.46
Removal of contaminated mechanical equipment, >10,000 pound	3,053.11
Removal of contaminated HVAC equipment, <300 pound	391.09
Removal of contaminated HVAC equipment, 300-1000 pound	911.06
Removal of contaminated HVAC equipment, 1000-10,000 pound	1,752.46
Removal of contaminated HVAC equipment, >10,000 pound	3,053.11
Removal of contaminated HVAC ductwork, \$/pound	1.23
Removal/plasma arc cut of contaminated thin metal components, \$/linear in.	1.73
Additional decontamination of surface by washing, \$/square foot	3.78
Additional decontamination of surfaces by hydrolasing, \$/square foot	16.35
Decontamination rig hook up and flush, \$/ 250 foot length	3,326.32
Chemical flush of components/systems, \$/gallon	12.47
Removal of clean standard reinforced concrete, \$/cubic yard	67.30
Removal of grade slab concrete, \$/cubic yard	85.61
Removal of clean concrete floors, \$/cubic yard	189.10



**APPENDIX B**

**UNIT COST FACTOR LISTING  
(Power Block Structures Only)**

<b>Unit Cost Factor</b>	<b>Cost/Unit(\$)</b>
Removal of sections of clean concrete floors, \$/cubic yard	515.96
Removal of clean heavily rein concrete w/#9 rebar, \$/cubic yard	131.20
Removal of contaminated heavily rein concrete w/#9 rebar, \$/cubic yard	1,049.44
Removal of clean heavily rein concrete w/#18 rebar, \$/cubic yard	165.97
Removal of contaminated heavily rein concrete w/#18 rebar, \$/cubic yard	1,387.49
Removal heavily rein concrete w/#18 rebar & steel embedments, \$/cubic yard	230.30
Removal of below-grade suspended floors, \$/cubic yard	189.10
Removal of clean monolithic concrete structures, \$/cubic yard	417.72
Removal of contaminated monolithic concrete structures, \$/cubic yard	1,046.38
Removal of clean foundation concrete, \$/cubic yard	329.76
Removal of contaminated foundation concrete, \$/cubic yard	974.61
Explosive demolition of bulk concrete, \$/cubic yard	15.69
Removal of clean hollow masonry block wall, \$/cubic yard	44.57
Removal of contaminated hollow masonry block wall, \$/cubic yard	189.31
Removal of clean solid masonry block wall, \$/cubic yard	44.57
Removal of contaminated solid masonry block wall, \$/cubic yard	189.31
Backfill of below-grade voids, \$/cubic yard	14.25
Removal of subterranean tunnels/voids, \$/linear foot	51.76
Placement of concrete for below-grade voids, \$/cubic yard	99.73
Excavation of clean material, \$/cubic yard	1.76
Excavation of contaminated material, \$/cubic yard	24.32
Removal of clean concrete rubble (tipping fee included), \$/cubic yard	88.88
Removal of contaminated concrete rubble, \$/cubic yard	15.40
Removal of building by volume, \$/cubic foot	0.17
Removal of clean building metal siding, \$/square foot	0.51

**APPENDIX B**

**UNIT COST FACTOR LISTING  
(Power Block Structures Only)**

<b>Unit Cost Factor</b>	<b>Cost/Unit(\$)</b>
Removal of contaminated building metal siding, \$/square foot	2.36
Removal of standard asphalt roofing, \$/square foot	0.82
Removal of transite panels, \$/square foot	1.23
Scarifying contaminated concrete surfaces (drill & spall), \$/square foot	8.71
Scabbling contaminated concrete floors, \$/square foot	4.40
Scabbling contaminated concrete walls, \$/square foot	4.82
Scabbling contaminated ceilings, \$/square foot	43.37
Scabbling structural steel, \$/square foot	3.94
Removal of clean overhead crane/monorail < 10 ton capacity	243.65
Removal of contaminated overhead crane/monorail < 10 ton capacity	884.39
Removal of clean overhead crane/monorail >10-50 ton capacity	584.77
Removal of contaminated overhead crane/monorail >10-50 ton capacity	2,121.31
Removal of polar crane > 50 ton capacity	2,459.18
Removal of gantry crane > 50 ton capacity	10,268.70
Removal of structural steel, \$/pound	0.17
Removal of clean steel floor grating, \$/square foot	1.85
Removal of contaminated steel floor grating, \$/square foot	6.49
Removal of clean free standing steel liner, \$/square foot	4.68
Removal of contaminated free standing steel liner, \$/square foot	16.69
Removal of clean concrete-anchored steel liner, \$/square foot	2.34
Removal of contaminated concrete-anchored steel liner, \$/square foot	19.33
Placement of scaffolding in clean areas, \$/square foot	12.07
Placement of scaffolding in contaminated areas, \$/square foot	17.78
Landscaping with topsoil, \$/acre	17,546.86
Cost of CPC B-88 LSA box & preparation for use	1,292.17

**APPENDIX B**

**UNIT COST FACTOR LISTING  
(Power Block Structures Only)**

<b>Unit Cost Factor</b>	<b>Cost/Unit(\$)</b>
Cost of CPC B-25 LSA box & preparation for use	1,006.08
Cost of CPC B-12V 12 gauge LSA box & preparation for use	849.62
Cost of CPC B-144 LSA box & preparation for use	5,245.00
Cost of LSA drum & preparation for use	86.32
Cost of cask liner for CNSI 14 195 cask	9,394.94
Cost of cask liner for CNSI 8 120A cask (resins)	5,951.55
Cost of cask liner for CNSI 8 120A cask (filters)	5,951.55
Decontamination of surfaces with vacuuming, \$/square foot	0.32

**APPENDIX C**  
**DETAILED COST ANALYSIS**  
**DECON**

Table C  
Wolf Creek Generating Station  
DECON Decommissioning Cost Estimate  
(Thousands of 2005 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Costs	Total Contingency	Total Costs	NRC Lic. Term. Costs	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Burial Volumes				Burial / Processed Wt., Lbs.	Craft Manhours	Utility and Contractor Manhours
															Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTCC Cu. Feet			
PERIOD 1a - Shutdown through Transition																					
Period 1a Direct Decommissioning Activities																					
1a.1.1	Prepare preliminary decommissioning cost	-	-	-	-	-	-	124	19	142	142	-	-	-	-	-	-	-	-	-	1,300
1a.1.2	Notification of Cessation of Operations									a											
1a.1.3	Remove fuel & source material									n/a											
1a.1.4	Notification of Permanent Defueling									a											
1a.1.5	Deactivate plant systems & process waste									a											
1a.1.6	Prepare and submit PSDAR	-	-	-	-	-	-	190	29	219	219	-	-	-	-	-	-	-	-	-	2,000
1a.1.7	Review plant dwgs & specs.	-	-	-	-	-	-	438	66	503	503	-	-	-	-	-	-	-	-	-	4,600
1a.1.8	Perform detailed rad survey									a											
1a.1.9	Estimate by-product inventory	-	-	-	-	-	-	95	14	109	109	-	-	-	-	-	-	-	-	-	1,000
1a.1.10	End product description	-	-	-	-	-	-	95	14	109	109	-	-	-	-	-	-	-	-	-	1,000
1a.1.11	Detailed by-product inventory	-	-	-	-	-	-	124	19	142	142	-	-	-	-	-	-	-	-	-	1,300
1a.1.12	Define major work sequence	-	-	-	-	-	-	713	107	820	820	-	-	-	-	-	-	-	-	-	7,500
1a.1.13	Perform SER and EA	-	-	-	-	-	-	295	44	339	339	-	-	-	-	-	-	-	-	-	3,100
1a.1.14	Perform Site-Specific Cost Study	-	-	-	-	-	-	476	71	547	547	-	-	-	-	-	-	-	-	-	5,000
1a.1.15	Prepare/submit License Termination Plan	-	-	-	-	-	-	390	58	448	448	-	-	-	-	-	-	-	-	-	4,096
1a.1.16	Receive NRC approval of termination plan									a											
Activity Specifications																					
1a.1.17.1	Plant & temporary facilities	-	-	-	-	-	-	468	70	538	484	-	54	-	-	-	-	-	-	-	4,920
1a.1.17.2	Plant systems	-	-	-	-	-	-	396	59	456	410	-	46	-	-	-	-	-	-	-	4,167
1a.1.17.3	NSSS Decontamination Flush	-	-	-	-	-	-	48	7	55	55	-	-	-	-	-	-	-	-	-	500
1a.1.17.4	Reactor internals	-	-	-	-	-	-	675	101	777	777	-	-	-	-	-	-	-	-	-	7,100
1a.1.17.5	Reactor vessel	-	-	-	-	-	-	618	93	711	711	-	-	-	-	-	-	-	-	-	6,500
1a.1.17.6	Biological shield	-	-	-	-	-	-	48	7	55	55	-	-	-	-	-	-	-	-	-	500
1a.1.17.7	Steam generators	-	-	-	-	-	-	297	45	341	341	-	-	-	-	-	-	-	-	-	3,120
1a.1.17.8	Reinforced concrete	-	-	-	-	-	-	152	23	175	88	-	88	-	-	-	-	-	-	-	1,600
1a.1.17.9	Main Turbine	-	-	-	-	-	-	38	6	44	-	-	44	-	-	-	-	-	-	-	400
1a.1.17.10	Main Condensers	-	-	-	-	-	-	38	6	44	-	-	44	-	-	-	-	-	-	-	400
1a.1.17.11	Plant structures & buildings	-	-	-	-	-	-	297	45	341	171	-	171	-	-	-	-	-	-	-	3,120
1a.1.17.12	Waste management	-	-	-	-	-	-	438	66	503	503	-	-	-	-	-	-	-	-	-	4,600
1a.1.17.13	Facility & site closeout	-	-	-	-	-	-	86	13	98	49	-	49	-	-	-	-	-	-	-	900
1a.1.17	Total	-	-	-	-	-	-	3,598	540	4,138	3,643	-	494	-	-	-	-	-	-	-	37,827
Planning & Site Preparations																					
1a.1.18	Prepare dismantling sequence	-	-	-	-	-	-	228	34	263	263	-	-	-	-	-	-	-	-	-	2,400
1a.1.19	Plant prep. & temp. svces	-	-	-	-	-	-	2,419	363	2,782	2,782	-	-	-	-	-	-	-	-	-	-
1a.1.20	Design water clean-up system	-	-	-	-	-	-	133	20	153	153	-	-	-	-	-	-	-	-	-	1,400
1a.1.21	Rigging/Cont. Cntrl Envlp/s/tooling/etc.	-	-	-	-	-	-	2,048	307	2,355	2,355	-	-	-	-	-	-	-	-	-	-
1a.1.22	Procure casks/liners & containers	-	-	-	-	-	-	117	18	135	135	-	-	-	-	-	-	-	-	-	1,230
1a.1	Subtotal Period 1a Activity Costs	-	-	-	-	-	-	11,482	1,722	13,205	12,710	-	494	-	-	-	-	-	-	-	73,753
Period 1a Collateral Costs																					
1a.3.1	Spent Fuel Transfer to DOE	-	-	-	-	-	-	2,600	390	2,990	-	2,990	-	-	-	-	-	-	-	-	-
1a.3	Subtotal Period 1a Collateral Costs	-	-	-	-	-	-	2,600	390	2,990	-	2,990	-	-	-	-	-	-	-	-	-
Period 1a Period-Dependent Costs																					
1a.4.1	Insurance	-	-	-	-	-	-	1,438	144	1,582	1,582	-	-	-	-	-	-	-	-	-	-
1a.4.2	Property taxes	-	-	-	-	-	-	1,487	149	1,636	1,636	-	-	-	-	-	-	-	-	-	-
1a.4.3	Health physics supplies	-	256	-	-	-	-	-	64	320	320	-	-	-	-	-	-	-	-	-	-
1a.4.4	Heavy equipment rental	-	336	-	-	-	-	-	50	386	386	-	-	-	-	-	-	-	-	-	-
1a.4.5	Disposal of DAW generated	-	-	6	3	-	28	-	8	45	45	-	-	-	404	-	-	-	8,103	99	-
1a.4.6	Plant energy budget	-	-	-	-	-	-	1,356	203	1,559	1,559	-	-	-	-	-	-	-	-	-	-
1a.4.7	NRC Fees	-	-	-	-	-	-	265	27	292	292	-	-	-	-	-	-	-	-	-	-
1a.4.8	Emergency Planning Fees	-	-	-	-	-	-	450	45	495	-	495	-	-	-	-	-	-	-	-	-

**Table C**  
**Wolf Creek Generating Station**  
**DECON Decommissioning Cost Estimate**  
 (Thousands of 2005 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Costs	Total Contingency	Total Costs	NRC Lic. Term. Costs	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Burial Volumes				Burial / Processed Wt., Lbs.	Craft Manhours	Utility and Contractor Manhours
															Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTCC Cu. Feet			
Period 1a Period-Dependent Costs (continued)																					
1a.4.9	Spent Fuel Pool O&M	-	-	-	-	-	-	940	141	1,082	-	1,082	-	-	-	-	-	-	-	-	-
1a.4.10	Security Staff Cost	-	-	-	-	-	-	1,772	266	2,038	2,038	-	-	-	-	-	-	-	-	-	58,921
1a.4.11	Utility Staff Cost	-	-	-	-	-	-	20,337	3,051	23,388	23,388	-	-	-	-	-	-	-	-	-	438,000
1a.4	Subtotal Period 1a Period-Dependent Costs	-	592	6	3	-	28	28,046	4,147	32,822	31,245	1,576	-	-	404	-	-	-	8,103	99	496,921
1a.0	TOTAL PERIOD 1a COST	-	592	6	3	-	28	42,128	6,260	49,016	43,956	4,566	494	-	404	-	-	-	8,103	99	570,674
PERIOD 1b - Decommissioning Preparations																					
Period 1b Direct Decommissioning Activities																					
Detailed Work Procedures																					
1b.1.1.1	Plant systems	-	-	-	-	-	-	450	68	518	466	-	52	-	-	-	-	-	-	-	4,733
1b.1.1.2	NSSS Decontamination Flush	-	-	-	-	-	-	95	14	109	109	-	-	-	-	-	-	-	-	-	1,000
1b.1.1.3	Reactor internals	-	-	-	-	-	-	238	36	273	273	-	-	-	-	-	-	-	-	-	2,500
1b.1.1.4	Remaining buildings	-	-	-	-	-	-	128	19	148	37	-	111	-	-	-	-	-	-	-	1,350
1b.1.1.5	CRD cooling assembly	-	-	-	-	-	-	95	14	109	109	-	-	-	-	-	-	-	-	-	1,000
1b.1.1.6	CRD housings & ICI tubes	-	-	-	-	-	-	95	14	109	109	-	-	-	-	-	-	-	-	-	1,000
1b.1.1.7	Incore instrumentation	-	-	-	-	-	-	95	14	109	109	-	-	-	-	-	-	-	-	-	1,000
1b.1.1.8	Reactor vessel	-	-	-	-	-	-	345	52	397	397	-	-	-	-	-	-	-	-	-	3,630
1b.1.1.9	Facility closeout	-	-	-	-	-	-	114	17	131	66	-	66	-	-	-	-	-	-	-	1,200
1b.1.1.10	Missile shields	-	-	-	-	-	-	43	6	49	49	-	-	-	-	-	-	-	-	-	450
1b.1.1.11	Biological shield	-	-	-	-	-	-	114	17	131	131	-	-	-	-	-	-	-	-	-	1,200
1b.1.1.12	Steam generators	-	-	-	-	-	-	438	66	503	503	-	-	-	-	-	-	-	-	-	4,600
1b.1.1.13	Reinforced concrete	-	-	-	-	-	-	95	14	109	55	-	55	-	-	-	-	-	-	-	1,000
1b.1.1.14	Main Turbine	-	-	-	-	-	-	148	22	171	-	-	171	-	-	-	-	-	-	-	1,560
1b.1.1.15	Main Condensers	-	-	-	-	-	-	148	22	171	-	-	171	-	-	-	-	-	-	-	1,560
1b.1.1.16	Auxiliary building	-	-	-	-	-	-	260	39	299	269	-	30	-	-	-	-	-	-	-	2,730
1b.1.1.17	Reactor building	-	-	-	-	-	-	260	39	299	269	-	30	-	-	-	-	-	-	-	2,730
1b.1.1	Total	-	-	-	-	-	-	3,162	474	3,636	2,953	-	684	-	-	-	-	-	-	-	33,243
1b.1.2	Decon primary loop	1,092	-	-	-	-	-	-	546	1,639	1,639	-	-	-	-	-	-	-	-	1,067	-
1b.1	Subtotal Period 1b Activity Costs	1,092	-	-	-	-	-	3,162	1,021	5,275	4,591	-	684	-	-	-	-	-	-	1,067	33,243
Period 1b Additional Costs																					
1b.2.1	Spent Fuel Pool Isolation	-	-	-	-	-	-	8,609	1,291	9,900	9,900	-	-	-	-	-	-	-	-	-	-
1b.2.2	Site Characterization Survey	-	-	-	-	-	-	1,332	400	1,731	1,731	-	-	-	-	-	-	-	-	-	-
1b.2.3	Misc/Hazardous Waste	-	2	-	5	66	-	-	11	84	84	-	-	1,365	-	-	-	-	91,790	442	-
1b.2	Subtotal Period 1b Additional Costs	-	2	-	5	66	-	9,941	1,702	11,716	11,716	-	-	1,365	-	-	-	-	91,790	442	-
Period 1b Collateral Costs																					
1b.3.1	Decon equipment	729	-	-	-	-	-	-	109	838	838	-	-	-	-	-	-	-	-	-	-
1b.3.2	DOC staff relocation expenses	-	-	-	-	-	-	921	138	1,059	1,059	-	-	-	-	-	-	-	-	-	-
1b.3.3	Process liquid waste	57	-	460	690	-	5,131	-	1,461	7,798	7,798	-	-	-	-	5,381	-	-	890,864	197	-
1b.3.4	Small tool allowance	-	1	-	-	-	-	-	-	1	1	-	-	-	-	-	-	-	-	-	-
1b.3.5	Pipe cutting equipment	-	957	-	-	-	-	-	143	1,100	1,100	-	-	-	-	-	-	-	-	-	-
1b.3.6	Decon rig	1,243	-	-	-	-	-	-	186	1,430	1,430	-	-	-	-	-	-	-	-	-	-
1b.3.7	Spent Fuel Transfer to DOE	-	-	-	-	-	-	1,400	210	1,610	-	1,610	-	-	-	-	-	-	-	-	-
1b.3	Subtotal Period 1b Collateral Costs	2,029	957	460	690	-	5,131	2,321	2,248	13,836	12,226	1,610	-	-	-	5,381	-	-	890,864	197	-
Period 1b Period-Dependent Costs																					
1b.4.1	Decon supplies	22	-	-	-	-	-	-	6	28	28	-	-	-	-	-	-	-	-	-	-
1b.4.2	Insurance	-	-	-	-	-	-	725	72	797	797	-	-	-	-	-	-	-	-	-	-
1b.4.3	Property taxes	-	-	-	-	-	-	750	75	825	825	-	-	-	-	-	-	-	-	-	-
1b.4.4	Health physics supplies	-	135	-	-	-	-	-	34	169	169	-	-	-	-	-	-	-	-	-	-
1b.4.5	Heavy equipment rental	-	169	-	-	-	-	-	25	195	195	-	-	-	-	-	-	-	-	-	-

Table C  
Wolf Creek Generating Station  
DECON Decommissioning Cost Estimate  
(Thousands of 2005 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Costs	Total Contingency	Total Costs	NRC Lic. Term. Costs	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Burial Volumes				Burial / Processed Wt., Lbs.	Craft Manhours	Utility and Contractor Manhours
															Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTCC Cu. Feet			
Period 1b Period-Dependent Costs (continued)																					
1b.4.6	Disposal of DAW generated	-	-	3	1	-	15	-	4	24	24	-	-	-	220	-	-	-	4,416	54	-
1b.4.7	Plant energy budget	-	-	-	-	-	-	1,367	205	1,572	1,572	-	-	-	-	-	-	-	-	-	-
1b.4.8	NRC Fees	-	-	-	-	-	-	134	13	147	147	-	-	-	-	-	-	-	-	-	-
1b.4.9	Emergency Planning Fees	-	-	-	-	-	-	227	23	249	-	249	-	-	-	-	-	-	-	-	-
1b.4.10	Spent Fuel Pool O&M	-	-	-	-	-	-	474	71	545	-	545	-	-	-	-	-	-	-	-	-
1b.4.11	Security Staff Cost	-	-	-	-	-	-	893	134	1,027	1,027	-	-	-	-	-	-	-	-	-	29,703
1b.4.12	DOC Staff Cost	-	-	-	-	-	-	4,203	630	4,834	4,834	-	-	-	-	-	-	-	-	-	64,137
1b.4.13	Utility Staff Cost	-	-	-	-	-	-	10,300	1,545	11,845	11,845	-	-	-	-	-	-	-	-	-	221,851
1b.4	Subtotal Period 1b Period-Dependent Costs	22	304	3	1	-	15	19,073	2,838	22,258	21,464	795	-	-	220	-	-	-	4,416	54	315,691
1b.0	TOTAL PERIOD 1b COST	3,144	1,264	463	696	66	5,146	34,497	7,809	53,085	49,996	2,405	684	1,365	220	5,381	-	-	987,070	1,759	348,934
PERIOD 1 TOTALS		3,144	1,855	469	699	66	5,174	76,625	14,069	102,101	93,952	6,971	1,178	1,365	625	5,381	-	-	995,173	1,859	919,609
PERIOD 2a - Large Component Removal																					
Period 2a Direct Decommissioning Activities																					
Nuclear Steam Supply System Removal																					
2a.1.1.1	Reactor Coolant Piping	86	98	13	20	-	441	-	182	840	840	-	-	-	1,157	-	-	-	139,959	6,975	-
2a.1.1.2	Pressurizer Relief Tank	15	13	4	6	-	115	-	40	192	192	-	-	-	328	-	-	-	36,395	1,093	-
2a.1.1.3	Reactor Coolant Pumps & Motors	44	41	32	5	139	2,624	-	713	3,598	3,598	-	-	198	2,556	-	-	-	897,754	3,833	-
2a.1.1.4	Pressurizer	22	22	509	349	-	650	-	282	1,834	1,834	-	-	-	2,426	-	-	-	255,229	2,462	-
2a.1.1.5	Steam Generators	183	3,151	2,830	2,063	2,595	4,716	-	3,040	18,577	18,577	-	-	16,029	17,596	-	-	-	3,344,326	35,051	-
2a.1.1.6	CRDMs/ICIs/Service Structure Removal	73	62	123	36	-	342	-	155	793	793	-	-	-	4,534	-	-	-	108,572	4,963	-
2a.1.1.7	Reactor Vessel Internals	58	2,229	3,505	883	-	6,699	203	6,178	19,755	19,755	-	-	-	1,377	412	861	-	314,544	27,523	1,233
2a.1.1.8	Vessel & Internals GTCC Disposal	-	-	-	-	-	13,089	-	1,963	15,052	15,052	-	-	-	-	-	-	559	116,756	-	-
2a.1.1.9	Reactor Vessel	41	4,747	1,267	556	-	9,006	203	8,570	24,390	24,390	-	-	-	7,750	2,128	-	-	1,069,368	27,523	1,233
2a.1.1	Totals	521	10,364	8,283	3,918	2,734	37,681	407	21,124	85,032	85,032	-	-	16,227	37,724	2,541	861	559	6,282,903	109,423	2,466
Removal of Major Equipment																					
2a.1.2	Main Turbine/Generator	-	227	215	29	886	723	-	396	2,476	2,476	-	-	4,847	2,699	-	-	-	654,240	9,892	-
2a.1.3	Main Condensers	-	618	113	53	745	642	-	446	2,617	2,617	-	-	7,701	2,270	-	-	-	550,231	28,153	-
Cascading Costs from Clean Building Demolition																					
2a.1.4.1	Reactor	-	509	-	-	-	-	-	76	585	585	-	-	-	-	-	-	-	-	11,141	-
2a.1.4.2	Auxiliary	-	269	-	-	-	-	-	40	309	309	-	-	-	-	-	-	-	-	6,585	-
2a.1.4.3	Hot Machine Shop	-	0	-	-	-	-	-	-	1	1	-	-	-	-	-	-	-	-	16	-
2a.1.4.4	Radwaste	-	55	-	-	-	-	-	8	64	64	-	-	-	-	-	-	-	-	1,269	-
2a.1.4.5	Fuel Building	-	130	-	-	-	-	-	20	150	150	-	-	-	-	-	-	-	-	2,642	-
2a.1.4	Totals	-	964	-	-	-	-	-	145	1,108	1,108	-	-	-	-	-	-	-	-	21,652	-
Disposal of Plant Systems																					
2a.1.5.1	AB - Main Steam	-	107	-	-	-	-	-	16	123	-	-	123	-	-	-	-	-	-	5,833	-
2a.1.5.2	AB - Main Steam RCA	-	40	2	6	188	-	-	39	276	276	-	-	2,156	-	-	-	-	87,550	1,495	-
2a.1.5.3	AC - Main Turbine	-	105	-	-	-	-	-	16	121	-	-	121	-	-	-	-	-	-	5,641	-
2a.1.5.4	AD - Condensate	-	116	-	-	-	-	-	17	134	-	-	134	-	-	-	-	-	-	6,144	-
2a.1.5.5	AE - Feedwater	-	80	-	-	-	-	-	12	92	-	-	92	-	-	-	-	-	-	4,271	-
2a.1.5.6	AF - Feedwater Hter Extrction, Drn & Vnt	-	99	-	-	-	-	-	15	114	-	-	114	-	-	-	-	-	-	5,352	-
2a.1.5.7	AK - Condensate Demineralizer	-	36	-	-	-	-	-	5	42	-	-	42	-	-	-	-	-	-	1,944	-
2a.1.5.8	AL - Auxiliary Feedwater	-	16	-	-	-	-	-	2	18	-	-	18	-	-	-	-	-	-	852	-
2a.1.5.9	AQ - Condensate & Feedwater Chem Additn	-	9	-	-	-	-	-	1	10	-	-	10	-	-	-	-	-	-	468	-
2a.1.5.10	AX - Acid Feed	-	14	-	-	-	-	-	2	16	-	-	16	-	-	-	-	-	-	754	-
2a.1.5.11	Auxiliary Bldg Non-System Specific	-	58	3	4	41	56	-	36	198	198	-	-	474	199	-	-	-	37,110	2,300	-
2a.1.5.12	Auxiliary Bldg Non-System Specific RCA	-	348	9	22	666	-	-	191	1,236	1,236	-	-	7,629	-	-	-	-	309,812	13,468	-
2a.1.5.13	BL - Reactor Makeup Water	-	144	11	13	168	169	-	107	612	612	-	-	1,928	700	-	-	-	132,091	5,513	-
2a.1.5.14	BM - Steam Generator Blowdown	-	289	6	15	451	-	-	143	903	903	-	-	5,160	-	-	-	-	209,560	11,187	-

Table C  
Wolf Creek Generating Station  
DECON Decommissioning Cost Estimate  
(Thousands of 2005 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Costs	Total Contingency	Total Costs	NRC Lic. Term. Costs	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Burial Volumes				Burial / Processed Wt., Lbs.	Craft Manhours	Utility and Contractor Manhours
															Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTCC Cu. Feet			
Disposal of Plant Systems (continued)																					
2a.1.5.15	CA - Steam Seal	-	8	-	-	-	-	-	1	10	-	-	10	-	-	-	-	-	-	455	-
2a.1.5.16	CB - Main Turbine Lube Oil	-	24	-	-	-	-	-	4	27	-	-	27	-	-	-	-	-	-	1,207	-
2a.1.5.17	CC - Generator Hydrogen & CO2	-	4	-	-	-	-	-	1	4	-	-	4	-	-	-	-	-	-	198	-
2a.1.5.18	CD - Generator Seal Oil	-	5	-	-	-	-	-	1	6	-	-	6	-	-	-	-	-	-	287	-
2a.1.5.19	CE - Stator Cooling Water	-	5	-	-	-	-	-	1	5	-	-	5	-	-	-	-	-	-	241	-
2a.1.5.20	CF - Lube Oil Strg, Xfer & Purification	-	15	-	-	-	-	-	2	18	-	-	18	-	-	-	-	-	-	812	-
2a.1.5.21	CG - Condenser Air Removal	-	12	-	-	-	-	-	2	14	-	-	14	-	-	-	-	-	-	657	-
2a.1.5.22	CH - Main Turbine Control Oil	-	24	-	-	-	-	-	4	28	-	-	28	-	-	-	-	-	-	1,219	-
2a.1.5.23	CL - Chlorination	-	11	-	-	-	-	-	2	12	-	-	12	-	-	-	-	-	-	569	-
2a.1.5.24	CO - Carbon Dioxide	-	2	-	-	-	-	-	0	2	-	-	2	-	-	-	-	-	-	121	-
2a.1.5.25	CW - Circulating Water	-	144	-	-	-	-	-	22	165	-	-	165	-	-	-	-	-	-	7,858	-
2a.1.5.26	CZ - Caustic Acid	-	2	-	-	-	-	-	0	2	-	-	2	-	-	-	-	-	-	111	-
2a.1.5.27	DA - Circulating Water System	-	146	-	-	-	-	-	22	168	-	-	168	-	-	-	-	-	-	7,953	-
2a.1.5.28	DM - Equipment Drains	-	23	-	-	-	-	-	3	27	-	-	27	-	-	-	-	-	-	1,223	-
2a.1.5.29	DM - Equipment Drains RCA	-	76	18	45	1,349	-	-	230	1,716	1,716	-	-	15,445	-	-	-	-	627,223	2,835	-
2a.1.5.30	EG - Component Cooling Water RCA	-	358	16	41	1,236	-	-	283	1,935	1,935	-	-	14,161	-	-	-	-	575,071	13,276	-
2a.1.5.31	EJ - Residual Heat Removal	-	189	23	29	238	481	-	210	1,170	1,170	-	-	2,727	1,713	-	-	-	263,397	7,528	-
2a.1.5.32	EM - High Pressure Coolant Injection	-	147	7	9	110	129	-	88	491	491	-	-	1,260	458	-	-	-	92,199	5,549	-
2a.1.5.33	EN - Containment Spray	-	108	3	9	264	-	-	68	452	452	-	-	3,026	-	-	-	-	122,874	4,004	-
2a.1.5.34	FB - Auxiliary Steam	-	39	-	-	-	-	-	6	45	-	-	45	-	-	-	-	-	-	2,106	-
2a.1.5.35	FB - Auxiliary Steam RCA	-	42	1	2	71	-	-	22	138	138	-	-	816	-	-	-	-	33,148	1,492	-
2a.1.5.36	FC - Auxiliary Turbines	-	25	-	-	-	-	-	4	29	-	-	29	-	-	-	-	-	-	1,301	-
2a.1.5.37	FE - Auxiliary Steam Chemical Addition	-	2	-	-	-	-	-	0	2	-	-	2	-	-	-	-	-	-	105	-
2a.1.5.38	GE - Turbine Bldg HVAC	-	54	-	-	-	-	-	8	62	-	-	62	-	-	-	-	-	-	3,081	-
2a.1.5.39	GF - Miscellaneous Building HVAC	-	16	-	-	-	-	-	2	19	-	-	19	-	-	-	-	-	-	945	-
2a.1.5.40	GS - Containment Hydrogen Control	-	39	2	3	57	21	-	24	146	146	-	-	658	73	-	-	-	33,309	1,484	-
2a.1.5.41	HF - Secondary Liquid Waste	369	487	39	46	540	639	-	558	2,678	2,678	-	-	6,186	2,522	-	-	-	453,942	31,196	-
2a.1.5.42	HY - Hydrogen	-	4	-	-	-	-	-	1	5	-	-	5	-	-	-	-	-	-	223	-
2a.1.5.43	KH - Service Gas	-	12	-	-	-	-	-	2	14	-	-	14	-	-	-	-	-	-	644	-
2a.1.5.44	LE - Oily Waste	-	48	-	-	-	-	-	7	55	-	-	55	-	-	-	-	-	-	2,575	-
2a.1.5.45	LE - Oily Waste RCA	-	96	2	5	150	-	-	47	300	300	-	-	1,718	-	-	-	-	69,785	3,398	-
2a.1.5.46	NT - Nitrogen	-	3	-	-	-	-	-	0	3	-	-	3	-	-	-	-	-	-	149	-
2a.1.5.47	OX - Oxygen	-	3	-	-	-	-	-	0	4	-	-	4	-	-	-	-	-	-	171	-
2a.1.5.48	SW - Screen Wash	-	12	-	-	-	-	-	2	14	-	-	14	-	-	-	-	-	-	635	-
2a.1.5.49	Turbine Bldg Non-System Specific	-	298	-	-	-	-	-	45	343	-	-	343	-	-	-	-	-	-	15,405	-
2a.1.5.50	VH - Circ Water & Makeup Water Scrnhs	-	5	-	-	-	-	-	1	5	-	-	5	-	-	-	-	-	-	245	-
2a.1.5.51	VV - Misc Bldg HVAC	-	2	-	-	-	-	-	0	3	-	-	3	-	-	-	-	-	-	123	-
2a.1.5.52	WG - Gland Water & Motor Cooling Water	-	11	-	-	-	-	-	2	12	-	-	12	-	-	-	-	-	-	593	-
2a.1.5.53	WL - Cooling Lake Makeup & Blowdown	-	14	-	-	-	-	-	2	16	-	-	16	-	-	-	-	-	-	745	-
2a.1.5	Totals	369	3,977	143	249	5,531	1,495	-	2,278	14,041	12,252	-	1,790	63,344	5,666	-	-	-	3,047,070	187,939	-
2a.1.6	Scaffolding in support of decommissioning	-	775	14	5	117	2	-	214	1,127	1,127	-	-	1,206	60	-	-	-	60,307	36,541	-
2a.1	Subtotal Period 2a Activity Costs	890	16,925	8,768	4,254	10,012	40,543	407	24,603	106,401	104,611	-	1,790	93,325	48,420	2,541	861	559	10,594,750	393,600	2,466
Period 2a Additional Costs																					
2a.2.1	Curie Surcharge(Excluding RPV)	-	-	-	-	-	1,204	-	301	1,505	1,505	-	-	-	-	-	-	-	-	-	-
2a.2	Subtotal Period 2a Additional Costs	-	-	-	-	-	1,204	-	301	1,505	1,505	-	-	-	-	-	-	-	-	-	-
Period 2a Collateral Costs																					
2a.3.1	Process liquid waste	153	-	78	226	-	1,098	-	393	1,948	1,948	-	-	-	-	1,350	-	-	182,187	217	-
2a.3.2	Small tool allowance	-	166	-	-	-	-	-	25	191	172	-	19	-	-	-	-	-	-	-	-
2a.3.3	Spent Fuel Transfer to DOE	-	-	-	-	-	-	4,000	600	4,600	-	4,600	-	-	-	-	-	-	-	-	-
2a.3	Subtotal Period 2a Collateral Costs	153	166	78	226	-	1,098	4,000	1,018	6,739	2,120	4,600	19	-	-	1,350	-	-	182,187	217	-



Table C  
Wolf Creek Generating Station  
DECON Decommissioning Cost Estimate  
(Thousands of 2005 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Costs	Total Contingency	Total Costs	NRC Lic. Term. Costs	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Burial Volumes					Burial / Processed Wt., Lbs.	Craft Manhours	Utility and Contractor Manhours
															Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTCC Cu. Feet				
Period 2a Period-Dependent Costs																						
2a.4.1	Decon supplies	67	-	-	-	-	-	-	17	84	84	-	-	-	-	-	-	-	-	-	-	
2a.4.2	Insurance	-	-	-	-	-	-	718	72	790	790	-	-	-	-	-	-	-	-	-	-	
2a.4.3	Property taxes	-	-	-	-	-	-	2,237	224	2,460	2,214	-	246	-	-	-	-	-	-	-	-	
2a.4.4	Health physics supplies	-	1,767	-	-	-	-	-	442	2,209	2,209	-	-	-	-	-	-	-	-	-	-	
2a.4.5	Heavy equipment rental	-	2,459	-	-	-	-	-	369	2,827	2,827	-	-	-	-	-	-	-	-	-	-	
2a.4.6	Disposal of DAW generated	-	-	86	38	-	418	-	119	661	661	-	-	-	5,967	-	-	-	119,577	1,465	-	
2a.4.7	Plant energy budget	-	-	-	-	-	-	1,938	291	2,228	2,228	-	-	-	-	-	-	-	-	-	-	
2a.4.8	NRC Fees	-	-	-	-	-	-	493	49	542	542	-	-	-	-	-	-	-	-	-	-	
2a.4.9	Emergency Planning Fees	-	-	-	-	-	-	676	68	744	-	-	-	-	-	-	-	-	-	-	-	
2a.4.10	Spent Fuel Pool O&M	-	-	-	-	-	-	1,415	212	1,627	-	1,627	-	-	-	-	-	-	-	-	-	
2a.4.11	Security Staff Cost	-	-	-	-	-	-	3,326	499	3,825	3,825	-	-	-	-	-	-	-	-	-	110,584	
2a.4.12	DOC Staff Cost	-	-	-	-	-	-	15,140	2,271	17,411	17,411	-	-	-	-	-	-	-	-	-	238,423	
2a.4.13	Utility Staff Cost	-	-	-	-	-	-	22,604	3,391	25,995	25,995	-	-	-	-	-	-	-	-	-	465,866	
2a.4	Subtotal Period 2a Period-Dependent Costs	67	4,226	86	38	-	418	48,546	8,022	61,403	58,786	2,371	246	-	5,967	-	-	-	119,577	1,465	814,873	
2a.0	TOTAL PERIOD 2a COST	1,110	21,316	8,933	4,517	10,012	43,263	52,953	33,943	176,048	167,023	6,971	2,055	93,325	54,387	3,891	861	559	10,896,510	395,282	817,339	
PERIOD 2b - Site Decontamination																						
Period 2b Direct Decommissioning Activities																						
Disposal of Plant Systems																						
2b.1.1.1	AN - Demineralized Wtr Storage & xfer	-	29	-	-	-	-	-	4	33	-	-	33	-	-	-	-	-	-	1,548	-	
2b.1.1.2	AN - Demineralized Wtr Strg & xfer RCA	-	9	0	0	10	-	-	4	24	24	-	-	120	-	-	-	-	4,855	320	-	
2b.1.1.3	AP - Condensate Storage & Transfer	-	33	-	-	-	-	-	5	38	-	-	38	-	-	-	-	-	-	1,660	-	
2b.1.1.4	BB - Reactor Coolant	-	143	19	20	152	333	-	147	813	813	-	-	1,746	1,388	-	-	-	176,612	5,854	-	
2b.1.1.5	BG - Chemical & Volume Control	463	451	49	58	428	982	-	668	3,098	3,098	-	-	4,899	3,559	-	-	-	510,728	26,318	-	
2b.1.1.6	BN - Borated Refueling Water Storage	-	171	11	21	481	106	-	146	935	935	-	-	5,512	416	-	-	-	257,593	6,907	-	
2b.1.1.7	Control Bldg Non-System Specific	-	89	2	6	187	-	-	51	335	335	-	-	2,139	-	-	-	-	86,849	3,413	-	
2b.1.1.8	Control Bldg Non-System Specific Cln	-	713	-	-	-	-	-	107	820	-	-	820	-	-	-	-	-	-	29,076	-	
2b.1.1.9	DO - Diesel Oil	-	1	-	-	-	-	-	0	1	-	-	1	-	-	-	-	-	-	48	-	
2b.1.1.10	EA - Service Water	-	48	-	-	-	-	-	7	55	-	-	55	-	-	-	-	-	-	2,592	-	
2b.1.1.11	EB - Closed Cooling Water	-	24	-	-	-	-	-	4	27	-	-	27	-	-	-	-	-	-	1,267	-	
2b.1.1.12	EF - Essential Service Water	-	55	-	-	-	-	-	8	63	-	-	63	-	-	-	-	-	-	2,951	-	
2b.1.1.13	EF - Essential Service Water RCA	-	45	2	4	125	-	-	31	206	206	-	-	1,427	-	-	-	-	57,959	1,677	-	
2b.1.1.14	EP - Accumulator Safety Injection	-	81	5	7	137	56	-	56	343	343	-	-	1,568	208	-	-	-	81,536	3,095	-	
2b.1.1.15	FA - Auxiliary Steam Generator	-	9	-	-	-	-	-	1	11	-	-	11	-	-	-	-	-	-	521	-	
2b.1.1.16	FO - Fuel Oil	-	9	-	-	-	-	-	1	10	-	-	10	-	-	-	-	-	-	486	-	
2b.1.1.17	FP - Fire Protection	-	70	-	-	-	-	-	11	81	-	-	81	-	-	-	-	-	-	3,826	-	
2b.1.1.18	FP - Fire Protection RCA	-	101	5	13	392	-	-	86	598	598	-	-	4,492	-	-	-	-	182,411	3,540	-	
2b.1.1.19	GA - Plant Heating	-	35	-	-	-	-	-	5	41	-	-	41	-	-	-	-	-	-	1,912	-	
2b.1.1.20	GA - Plant Heating RCA	-	58	1	2	65	-	-	25	150	150	-	-	746	-	-	-	-	30,275	1,992	-	
2b.1.1.21	GB - Central Chilled Water	-	33	-	-	-	-	-	5	38	-	-	38	-	-	-	-	-	-	1,803	-	
2b.1.1.22	GB - Central Chilled Water RCA	-	13	0	1	16	-	-	6	36	36	-	-	187	-	-	-	-	7,591	463	-	
2b.1.1.23	GD - Esstl Srvc Wtr Pumphs Bldg HVAC	-	5	-	-	-	-	-	1	6	-	-	6	-	-	-	-	-	-	271	-	
2b.1.1.24	GH - Radwaste Building HVAC	-	109	3	8	212	20	-	65	417	417	-	-	2,425	69	-	-	-	104,668	3,457	-	
2b.1.1.25	GK - Control Building HVAC	-	65	-	-	-	-	-	10	75	-	-	75	-	-	-	-	-	-	3,900	-	
2b.1.1.26	GL - Auxiliary Building HVAC	-	274	7	17	442	45	-	150	936	936	-	-	5,064	161	-	-	-	220,066	8,499	-	
2b.1.1.27	GM - Diesel Generator Building HVAC	-	11	-	-	-	-	-	2	13	-	-	13	-	-	-	-	-	-	692	-	
2b.1.1.28	GN - Containment Cooling	-	284	13	27	642	128	-	205	1,300	1,300	-	-	7,354	454	-	-	-	339,357	9,408	-	
2b.1.1.29	GP - Containmnt Integratd Leak Rate Test	-	20	1	2	51	-	-	13	85	85	-	-	580	-	-	-	-	23,570	737	-	
2b.1.1.30	GR - Containment Atmospheric Control	-	10	2	3	95	8	-	19	137	137	-	-	1,086	29	-	-	-	46,679	397	-	
2b.1.1.31	GT - Containment Purge HVAC	-	68	3	7	170	34	-	52	335	335	-	-	1,948	120	-	-	-	89,887	2,254	-	
2b.1.1.32	HA - Gaseous Radwaste	-	180	11	14	243	133	-	118	698	698	-	-	2,782	486	-	-	-	155,095	6,638	-	
2b.1.1.33	HB - Liquid Radwaste	399	432	36	40	484	547	-	527	2,465	2,465	-	-	5,544	2,203	-	-	-	398,693	30,306	-	
2b.1.1.34	HC - Solid Radwaste	-	234	22	26	243	414	-	205	1,144	1,144	-	-	2,781	1,514	-	-	-	244,386	8,917	-	
2b.1.1.35	HD - Decontamination	-	53	3	4	86	34	-	36	215	215	-	-	983	125	-	-	-	50,772	2,021	-	

Table C  
Wolf Creek Generating Station  
DECON Decommissioning Cost Estimate  
(Thousands of 2005 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Costs	Total Contingency	Total Costs	NRC Lic. Term. Costs	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Burial Volumes				Burial / Processed Wt., Lbs.	Craft Manhours	Utility and Contractor Manhours
															Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTCC Cu. Feet			
Disposal of Plant Systems (continued)																					
2b.1.1.36	HE - Boron Recycle	202	245	18	20	227	281	-	272	1,266	1,266	-	-	2,600	1,111	-	-	-	194,922	16,116	-
2b.1.1.37	JE - Emergency Fuel Oil	-	25	-	-	-	-	-	4	29	-	-	29	-	-	-	-	-	-	1,260	-
2b.1.1.38	KA - Compressed Air and Instrument	-	114	-	-	-	-	-	17	131	-	-	131	-	-	-	-	-	-	6,089	-
2b.1.1.39	KB - Breathing Air	-	20	-	-	-	-	-	3	23	-	-	23	-	-	-	-	-	-	1,075	-
2b.1.1.40	KC - Fire Protection	-	138	-	-	-	-	-	21	159	-	-	159	-	-	-	-	-	-	7,516	-
2b.1.1.41	KC - Fire Protection RCA	-	176	7	17	519	-	-	125	844	844	-	-	5,944	-	-	-	-	241,384	6,276	-
2b.1.1.42	KD - Domestic Water	-	32	-	-	-	-	-	5	37	-	-	37	-	-	-	-	-	-	1,708	-
2b.1.1.43	KE - Fuel Hndlg & Strg Reactor Vssl Serv	-	9	2	3	58	31	-	20	123	123	-	-	661	111	-	-	-	36,859	379	-
2b.1.1.44	KJ - Standby Diesel Engine	-	131	-	-	-	-	-	20	151	-	-	151	-	-	-	-	-	-	6,749	-
2b.1.1.45	LA - Sanitary Drains	-	5	-	-	-	-	-	1	6	-	-	6	-	-	-	-	-	-	290	-
2b.1.1.46	LA - Sanitary Drains RCA	-	13	0	1	24	-	-	7	45	45	-	-	272	-	-	-	-	11,053	421	-
2b.1.1.47	LB - Roof Drains	-	24	-	-	-	-	-	4	27	-	-	27	-	-	-	-	-	-	1,276	-
2b.1.1.48	LB - Roof Drains RCA	-	73	2	6	187	-	-	47	315	315	-	-	2,139	-	-	-	-	86,858	2,627	-
2b.1.1.49	LC - Yard Drains	-	2	-	-	-	-	-	0	2	-	-	2	-	-	-	-	-	-	96	-
2b.1.1.50	LD - Chemical & Detergent Waste	37	56	2	3	44	42	-	50	235	235	-	-	504	150	-	-	-	33,812	3,282	-
2b.1.1.51	LF - Floor & Equipment Drains	-	717	50	61	326	1,142	-	528	2,824	2,824	-	-	3,739	4,073	-	-	-	514,287	27,432	-
2b.1.1.52	RM - Process Sampling & Analysis	-	70	4	4	58	48	-	39	222	222	-	-	661	169	-	-	-	42,010	2,765	-
2b.1.1.53	Radwaste Bldg Non-System Specific	-	93	4	6	62	99	-	59	324	324	-	-	705	351	-	-	-	60,095	3,676	-
2b.1.1.54	Radwaste Bldg Non-System Specific RCA	-	571	15	37	1,107	-	-	316	2,046	2,046	-	-	12,684	-	-	-	-	515,103	21,915	-
2b.1.1.55	Reactor Bldg Non-System Specific	-	46	2	2	24	37	-	25	135	135	-	-	269	131	-	-	-	22,692	1,766	-
2b.1.1.56	Reactor Bldg Non-System Specific RCA	-	280	5	14	416	-	-	135	850	850	-	-	4,768	-	-	-	-	193,612	10,423	-
2b.1.1.57	SJ - Nuclear Sampling	-	38	3	3	37	37	-	25	142	142	-	-	423	130	-	-	-	28,862	1,564	-
2b.1.1.58	ST - Sewage Treatment	-	44	-	-	-	-	-	7	50	-	-	50	-	-	-	-	-	-	2,316	-
2b.1.1.59	SZ - Service Air	-	35	-	-	-	-	-	5	40	-	-	40	-	-	-	-	-	-	1,892	-
2b.1.1.60	VA - I&C Shop HVAC	-	3	-	-	-	-	-	0	3	-	-	3	-	-	-	-	-	-	141	-
2b.1.1.61	VB - I&C Shop Computer Room HVAC	-	2	-	-	-	-	-	0	2	-	-	2	-	-	-	-	-	-	95	-
2b.1.1.62	VC - Health Physics Computer Room HVAC	-	4	-	-	-	-	-	1	5	-	-	5	-	-	-	-	-	-	202	-
2b.1.1.63	VJ - Shop Bldg Machine Shop Area Vent	-	1	-	-	-	-	-	0	1	-	-	1	-	-	-	-	-	-	51	-
2b.1.1.64	VL - Shop Building HVAC	-	2	-	-	-	-	-	0	2	-	-	2	-	-	-	-	-	-	92	-
2b.1.1.65	VS - Admin Bldg HVAC	-	5	-	-	-	-	-	1	5	-	-	5	-	-	-	-	-	-	238	-
2b.1.1.66	VT - Tech Support Building HVAC	-	2	-	-	-	-	-	0	2	-	-	2	-	-	-	-	-	-	79	-
2b.1.1.67	VW - Waste Water Treatment Ventilation	-	1	-	-	-	-	-	0	1	-	-	1	-	-	-	-	-	-	48	-
2b.1.1.68	WD - Domestic Water	-	16	-	-	-	-	-	2	18	-	-	18	-	-	-	-	-	-	870	-
2b.1.1.69	WM - Makeup Demineralizer	-	73	-	-	-	-	-	11	84	-	-	84	-	-	-	-	-	-	3,929	-
2b.1.1.70	WS - Plant Services Water	-	61	-	-	-	-	-	9	70	-	-	70	-	-	-	-	-	-	3,297	-
2b.1.1.71	WS - Plant Services Water RCA	-	20	2	5	160	-	-	30	218	218	-	-	1,838	-	-	-	-	74,625	778	-
2b.1.1.72	WT - Waste Water Treatment	-	14	-	-	-	-	-	2	16	-	-	16	-	-	-	-	-	-	769	-
2b.1.1.73	WZ - Radioactive Liquid Waste	-	24	2	3	11	51	-	21	112	112	-	-	120	182	-	-	-	21,219	883	-
2b.1.1.74	Yard Non-System Specific	-	12	-	-	-	-	-	2	13	-	-	13	-	-	-	-	-	-	603	-
2b.1.1	Totals	1,102	7,162	312	465	7,920	4,609	-	4,592	26,163	23,974	-	2,189	90,709	17,141	-	-	-	5,146,975	319,753	-
2b.1.2	Scaffolding in support of decommissioning	-	969	18	6	146	3	-	267	1,408	1,408	-	-	1,508	75	-	-	-	75,384	45,676	-
Decontamination of Site Buildings																					
2b.1.3.1	Reactor	624	556	90	121	520	1,135	-	840	3,887	3,887	-	-	5,955	7,651	-	-	-	964,729	44,609	-
2b.1.3.2	Auxiliary	333	227	39	55	180	121	-	293	1,249	1,249	-	-	2,058	3,314	-	-	-	411,534	19,948	-
2b.1.3.3	Communication Corridor - Contaminated	7	4	1	1	1	3	-	6	23	23	-	-	17	72	-	-	-	7,850	406	-
2b.1.3.4	Hot Machine Shop	9	5	1	1	-	3	-	7	26	26	-	-	-	89	-	-	-	8,892	492	-
2b.1.3.5	Radwaste	177	112	21	29	74	64	-	150	627	627	-	-	844	1,753	-	-	-	208,396	10,271	-
2b.1.3.6	Radwaste Drum Storage	20	12	2	3	6	7	-	16	66	66	-	-	66	196	-	-	-	22,226	1,122	-
2b.1.3.7	Radwaste Storage Building	51	26	6	8	-	19	-	38	148	148	-	-	-	515	-	-	-	51,480	2,696	-
2b.1.3	Totals	1,222	941	160	219	781	1,353	-	1,350	6,026	6,026	-	-	8,941	13,590	-	-	-	1,675,107	79,543	-
2b.1	Subtotal Period 2b Activity Costs	2,324	9,072	490	690	8,847	5,965	-	6,210	33,597	31,408	-	2,189	101,157	30,807	-	-	-	6,897,466	444,972	-

Table C  
Wolf Creek Generating Station  
DECON Decommissioning Cost Estimate  
(Thousands of 2005 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Costs	Total Contingency	Total Costs	NRC Lic. Term. Costs	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Burial Volumes				Burial / Processed Wt., Lbs.	Craft Manhours	Utility and Contractor Manhours
															Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTCC Cu. Feet			
Period 2b Collateral Costs																					
2b.3.1	Process liquid waste	177	-	202	421	-	2,475	-	791	4,066	4,066	-	-	-	-	2,837	-	-	424,204	288	-
2b.3.2	Small tool allowance	-	174	-	-	-	-	-	26	200	200	-	-	-	-	-	-	-	-	-	-
2b.3.3	Spent Fuel Transfer to DOE	-	-	-	-	-	-	6,400	960	7,360	-	7,360	-	-	-	-	-	-	-	-	-
2b.3	Subtotal Period 2b Collateral Costs	177	174	202	421	-	2,475	6,400	1,777	11,626	4,266	7,360	-	-	-	2,837	-	-	424,204	288	-
Period 2b Period-Dependent Costs																					
2b.4.1	Decon supplies	1,022	-	-	-	-	-	-	256	1,278	1,278	-	-	-	-	-	-	-	-	-	-
2b.4.2	Insurance	-	-	-	-	-	-	1,192	119	1,311	1,311	-	-	-	-	-	-	-	-	-	-
2b.4.3	Property taxes	-	-	-	-	-	-	3,711	371	4,082	4,082	-	-	-	-	-	-	-	-	-	-
2b.4.4	Health physics supplies	-	2,201	-	-	-	-	-	550	2,752	2,752	-	-	-	-	-	-	-	-	-	-
2b.4.5	Heavy equipment rental	-	4,105	-	-	-	-	-	616	4,721	4,721	-	-	-	-	-	-	-	-	-	-
2b.4.6	Disposal of DAW generated	-	-	94	42	-	455	-	129	720	720	-	-	-	6,499	-	-	-	130,241	1,596	-
2b.4.7	Plant energy budget	-	-	-	-	-	-	2,538	381	2,919	2,919	-	-	-	-	-	-	-	-	-	-
2b.4.8	NRC Fees	-	-	-	-	-	-	818	82	899	899	-	-	-	-	-	-	-	-	-	-
2b.4.9	Emergency Planning Fees	-	-	-	-	-	-	1,122	112	1,235	-	1,235	-	-	-	-	-	-	-	-	-
2b.4.10	Spent Fuel Pool O&M	-	-	-	-	-	-	2,347	352	2,699	-	2,699	-	-	-	-	-	-	-	-	-
2b.4.11	Radwaste Processing Equipment/Services	-	-	-	-	-	-	462	69	532	532	-	-	-	-	-	-	-	-	-	-
2b.4.12	Security Staff Cost	-	-	-	-	-	-	4,423	663	5,086	5,086	-	-	-	-	-	-	-	-	-	147,061
2b.4.13	DOC Staff Cost	-	-	-	-	-	-	24,198	3,630	27,828	27,828	-	-	-	-	-	-	-	-	-	380,017
2b.4.14	Utility Staff Cost	-	-	-	-	-	-	36,107	5,416	41,523	41,523	-	-	-	-	-	-	-	-	-	741,814
2b.4	Subtotal Period 2b Period-Dependent Costs	1,022	6,306	94	42	-	455	76,919	12,747	97,585	93,651	3,934	-	-	6,499	-	-	-	130,241	1,596	1,268,893
2b.0	TOTAL PERIOD 2b COST	3,523	15,552	786	1,153	8,847	8,895	83,319	20,734	142,808	129,325	11,294	2,189	101,157	37,306	2,837	-	-	7,451,911	446,855	1,268,893
PERIOD 2c - Decontamination Following Wet Fuel Storage																					
Period 2c Direct Decommissioning Activities																					
2c.1.1	Remove spent fuel racks	375	34	144	55	-	1,247	-	531	2,386	2,386	-	-	-	4,412	-	-	-	395,882	1,722	-
Disposal of Plant Systems																					
2c.1.2.1	EC - Fuel Pool Cooling & Cleanup	-	194	12	17	227	217	-	141	808	808	-	-	2,600	769	-	-	-	174,505	7,486	-
2c.1.2.2	Fuel Bldg Non-System Specific	-	25	1	2	15	24	-	15	81	81	-	-	170	85	-	-	-	14,545	959	-
2c.1.2.3	Fuel Bldg Non-System Specific RCA	-	154	4	9	279	-	-	82	529	529	-	-	3,200	-	-	-	-	129,974	5,858	-
2c.1.2.4	Fuel Building Fire Protection	-	78	3	8	257	-	-	60	407	407	-	-	2,941	-	-	-	-	119,444	2,771	-
2c.1.2.5	GG - Fuel Building HVAC	-	151	5	12	326	31	-	97	621	621	-	-	3,729	109	-	-	-	161,237	4,684	-
2c.1.2	Totals	-	602	25	49	1,104	272	-	394	2,446	2,446	-	-	12,641	963	-	-	-	599,704	21,759	-
Decontamination of Site Buildings																					
2c.1.3.1	Fuel Building	386	425	13	20	236	33	-	347	1,462	1,462	-	-	2,705	895	-	-	-	198,758	31,734	-
2c.1.3	Totals	386	425	13	20	236	33	-	347	1,462	1,462	-	-	2,705	895	-	-	-	198,758	31,734	-
2c.1.4	Scaffolding in support of decommissioning	-	194	4	1	29	1	-	53	282	282	-	-	302	15	-	-	-	15,077	9,135	-
2c.1	Subtotal Period 2c Activity Costs	762	1,255	186	125	1,369	1,553	-	1,325	6,575	6,575	-	-	15,647	6,286	-	-	-	1,209,420	64,349	-
Period 2c Collateral Costs																					
2c.3.1	Process liquid waste	79	-	29	102	-	471	-	175	856	856	-	-	-	-	571	-	-	72,022	112	-
2c.3.2	Small tool allowance	-	32	-	-	-	-	-	5	37	37	-	-	-	-	-	-	-	-	-	-
2c.3.3	Decommissioning Equipment Disposition	-	-	71	28	581	106	-	125	910	910	-	-	6,000	373	-	-	-	303,507	739	-
2c.3	Subtotal Period 2c Collateral Costs	79	32	100	130	581	577	-	305	1,803	1,803	-	-	6,000	373	571	-	-	375,528	852	-
Period 2c Period-Dependent Costs																					
2c.4.1	Decon supplies	145	-	-	-	-	-	-	36	181	181	-	-	-	-	-	-	-	-	-	-
2c.4.2	Insurance	-	-	-	-	-	-	322	32	354	354	-	-	-	-	-	-	-	-	-	-
2c.4.3	Property taxes	-	-	-	-	-	-	215	22	237	237	-	-	-	-	-	-	-	-	-	-
2c.4.4	Health physics supplies	-	401	-	-	-	-	-	100	502	502	-	-	-	-	-	-	-	-	-	-
2c.4.5	Heavy equipment rental	-	1,108	-	-	-	-	-	166	1,275	1,275	-	-	-	-	-	-	-	-	-	-

**Table C**  
**Wolf Creek Generating Station**  
**DECON Decommissioning Cost Estimate**  
**(Thousands of 2005 Dollars)**

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Costs	Total Contingency	Total Costs	NRC Lic. Term. Costs	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Burial Volumes				Burial / Processed Wt., Lbs.	Craft Manhours	Utility and Contractor Manhours	
															Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTCC Cu. Feet				
Period 2c Period-Dependent Costs (continued)																						
2c.4.6	Disposal of DAW generated	-	-	31	14	-	152	-	43	241	241	-	-	-	2,171	-	-	-	-	43,514	533	-
2c.4.7	Plant energy budget	-	-	-	-	-	-	366	55	420	420	-	-	-	-	-	-	-	-	-	-	-
2c.4.8	NRC Fees	-	-	-	-	-	-	221	22	243	243	-	-	-	-	-	-	-	-	-	-	-
2c.4.9	Radwaste Processing Equipment/Services	-	-	-	-	-	-	250	37	287	287	-	-	-	-	-	-	-	-	-	-	-
2c.4.10	Security Staff Cost	-	-	-	-	-	-	1,194	179	1,373	1,373	-	-	-	-	-	-	-	-	-	-	39,711
2c.4.11	DOC Staff Cost	-	-	-	-	-	-	4,519	678	5,197	5,197	-	-	-	-	-	-	-	-	-	-	70,286
2c.4.12	Utility Staff Cost	-	-	-	-	-	-	7,236	1,085	8,321	8,321	-	-	-	-	-	-	-	-	-	-	142,680
2c.4	Subtotal Period 2c Period-Dependent Costs	145	1,510	31	14	-	152	14,322	2,456	18,630	18,630	-	-	-	2,171	-	-	-	-	43,514	533	252,677
2c.0	TOTAL PERIOD 2c COST	985	2,797	318	269	1,950	2,282	14,322	4,087	27,009	27,009	-	-	21,647	8,831	571	-	-	1,628,463	65,734	252,677	
PERIOD 2e - License Termination																						
Period 2e Direct Decommissioning Activities																						
2e.1.1	ORISE confirmatory survey	-	-	-	-	-	-	121	36	157	157	-	-	-	-	-	-	-	-	-	-	
2e.1.2	Terminate license	-	-	-	-	-	-	-	-	a	-	-	-	-	-	-	-	-	-	-	-	
2e.1	Subtotal Period 2e Activity Costs	-	-	-	-	-	-	121	36	157	157	-	-	-	-	-	-	-	-	-	-	
Period 2e Additional Costs																						
2e.2.1	Final Site Survey	-	-	-	-	-	-	4,819	1,446	6,265	6,265	-	-	-	-	-	-	-	-	149,600	-	
2e.2	Subtotal Period 2e Additional Costs	-	-	-	-	-	-	4,819	1,446	6,265	6,265	-	-	-	-	-	-	-	-	149,600	-	
Period 2e Collateral Costs																						
2e.3.1	DOC staff relocation expenses	-	-	-	-	-	-	921	138	1,059	1,059	-	-	-	-	-	-	-	-	-	-	
2e.3	Subtotal Period 2e Collateral Costs	-	-	-	-	-	-	921	138	1,059	1,059	-	-	-	-	-	-	-	-	-	-	
Period 2e Period-Dependent Costs																						
2e.4.1	Insurance	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2e.4.2	Property taxes	-	-	-	-	-	-	246	25	271	271	-	-	-	-	-	-	-	-	-	-	
2e.4.3	Health physics supplies	-	723	-	-	-	-	-	181	903	903	-	-	-	-	-	-	-	-	-	-	
2e.4.4	Disposal of DAW generated	-	-	5	2	-	22	-	6	35	35	-	-	-	312	-	-	-	-	6,260	77	
2e.4.5	Plant energy budget	-	-	-	-	-	-	210	31	241	241	-	-	-	-	-	-	-	-	-	-	
2e.4.6	NRC Fees	-	-	-	-	-	-	253	25	278	278	-	-	-	-	-	-	-	-	-	-	
2e.4.7	Security Staff Cost	-	-	-	-	-	-	436	65	502	502	-	-	-	-	-	-	-	-	-	14,503	
2e.4.8	DOC Staff Cost	-	-	-	-	-	-	3,916	587	4,503	4,503	-	-	-	-	-	-	-	-	-	58,817	
2e.4.9	Utility Staff Cost	-	-	-	-	-	-	4,493	674	5,167	5,167	-	-	-	-	-	-	-	-	-	81,377	
2e.4	Subtotal Period 2e Period-Dependent Costs	-	723	5	2	-	22	9,554	1,595	11,900	11,900	-	-	-	312	-	-	-	-	6,260	77	154,697
2e.0	TOTAL PERIOD 2e COST	-	723	5	2	-	22	15,415	3,215	19,381	19,381	-	-	-	312	-	-	-	-	6,260	149,677	154,697
PERIOD 2 TOTALS		5,618	40,388	10,041	5,941	20,808	54,462	166,009	61,979	365,246	342,737	18,265	4,244	216,130	100,836	7,299	861	559	19,983,150	1,057,547	2,493,606	
PERIOD 3b - Site Restoration																						
Period 3b Direct Decommissioning Activities																						
Demolition of Remaining Site Buildings																						
3b.1.1.1	Reactor	-	2,889	-	-	-	-	-	433	3,322	-	-	3,322	-	-	-	-	-	-	63,255	-	
3b.1.1.2	Access Vaults	-	10	-	-	-	-	-	1	11	-	-	11	-	-	-	-	-	-	250	-	
3b.1.1.3	Administration	-	130	-	-	-	-	-	20	150	-	-	150	-	-	-	-	-	-	4,467	-	
3b.1.1.4	Auxiliary	-	2,418	-	-	-	-	-	363	2,781	-	-	2,781	-	-	-	-	-	-	59,266	-	
3b.1.1.5	Auxiliary Boiler	-	18	-	-	-	-	-	3	20	-	-	20	-	-	-	-	-	-	619	-	
3b.1.1.6	Chlorine Storage	-	11	-	-	-	-	-	2	12	-	-	12	-	-	-	-	-	-	332	-	
3b.1.1.7	Circ Water Pump Enclosure	-	3	-	-	-	-	-	0	4	-	-	4	-	-	-	-	-	-	164	-	
3b.1.1.8	Circ Water Travel Screen Enclosure	-	3	-	-	-	-	-	0	3	-	-	3	-	-	-	-	-	-	160	-	
3b.1.1.9	Circulating Water Discharge Structure	-	91	-	-	-	-	-	14	105	-	-	105	-	-	-	-	-	-	2,373	-	
3b.1.1.10	Circulating Water Intake & Screenhouse	-	90	-	-	-	-	-	13	103	-	-	103	-	-	-	-	-	-	2,059	-	

**Table C**  
**Wolf Creek Generating Station**  
**DECON Decommissioning Cost Estimate**  
 (Thousands of 2005 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Costs	Total Contingency	Total Costs	NRC Lic. Term. Costs	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Burial Volumes				Burial / Processed Wt., Lbs.	Craft Manhours	Utility and Contractor Manhours
															Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTCC Cu. Feet			
Demolition of Remaining Site Buildings (continued)																					
3b.1.1.11	Communication Corridor - Clean	-	805	-	-	-	-	-	121	925	-	-	925	-	-	-	-	-	-	21,919	-
3b.1.1.12	Communication Corridor - Contaminated	-	31	-	-	-	-	-	5	36	-	-	36	-	-	-	-	-	-	674	-
3b.1.1.13	Covered Walkways	-	7	-	-	-	-	-	1	8	-	-	8	-	-	-	-	-	-	272	-
3b.1.1.14	Diesel Generator	-	290	-	-	-	-	-	43	333	-	-	333	-	-	-	-	-	-	6,314	-
3b.1.1.15	E.S.W.S. Pumphouse	-	149	-	-	-	-	-	22	171	-	-	171	-	-	-	-	-	-	3,019	-
3b.1.1.16	ESWS Valve House	-	8	-	-	-	-	-	1	9	-	-	9	-	-	-	-	-	-	243	-
3b.1.1.17	GOB - Administration Building	-	173	-	-	-	-	-	26	199	-	-	199	-	-	-	-	-	-	5,819	-
3b.1.1.18	Hot Machine Shop	-	11	-	-	-	-	-	2	13	-	-	13	-	-	-	-	-	-	417	-
3b.1.1.19	M.M.O. Building	-	165	-	-	-	-	-	25	190	-	-	190	-	-	-	-	-	-	3,483	-
3b.1.1.20	Material Center West	-	66	-	-	-	-	-	10	76	-	-	76	-	-	-	-	-	-	2,512	-
3b.1.1.21	Misc Structures and Additions	-	48	-	-	-	-	-	7	55	-	-	55	-	-	-	-	-	-	1,523	-
3b.1.1.22	Miscellaneous Site Foundations	-	241	-	-	-	-	-	36	277	-	-	277	-	-	-	-	-	-	7,265	-
3b.1.1.23	Miscellaneous Site Structures	-	949	-	-	-	-	-	142	1,091	-	-	1,091	-	-	-	-	-	-	20,254	-
3b.1.1.24	New Covered Walkway	-	5	-	-	-	-	-	1	6	-	-	6	-	-	-	-	-	-	160	-
3b.1.1.25	Oil Separator and Waste Tank	-	2	-	-	-	-	-	0	2	-	-	2	-	-	-	-	-	-	48	-
3b.1.1.26	Radwaste	-	1,065	-	-	-	-	-	160	1,224	-	-	1,224	-	-	-	-	-	-	24,859	-
3b.1.1.27	Radwaste Drum Storage	-	138	-	-	-	-	-	21	159	-	-	159	-	-	-	-	-	-	3,840	-
3b.1.1.28	Radwaste Storage Building	-	65	-	-	-	-	-	10	75	-	-	75	-	-	-	-	-	-	2,323	-
3b.1.1.29	Security Additions - Main Gate North	-	69	-	-	-	-	-	10	80	-	-	80	-	-	-	-	-	-	2,248	-
3b.1.1.30	Security/Guardhouse	-	29	-	-	-	-	-	4	33	-	-	33	-	-	-	-	-	-	845	-
3b.1.1.31	Site Diesel Generator	-	2	-	-	-	-	-	0	3	-	-	3	-	-	-	-	-	-	61	-
3b.1.1.32	Support Complex	-	19	-	-	-	-	-	3	22	-	-	22	-	-	-	-	-	-	697	-
3b.1.1.33	Turbine Building	-	2,578	-	-	-	-	-	387	2,965	-	-	2,965	-	-	-	-	-	-	89,690	-
3b.1.1.34	Turbine Pedestal	-	605	-	-	-	-	-	91	695	-	-	695	-	-	-	-	-	-	10,928	-
3b.1.1.35	Waste Water Treatment	-	12	-	-	-	-	-	2	14	-	-	14	-	-	-	-	-	-	407	-
3b.1.1.36	Fuel Building	-	1,193	-	-	-	-	-	179	1,372	-	-	1,372	-	-	-	-	-	-	24,799	-
3b.1.1	Totals	-	14,387	-	-	-	-	-	2,158	16,545	-	-	16,545	-	-	-	-	-	-	367,560	-
Site Closeout Activities																					
3b.1.2	Remove Rubble	-	9,481	-	-	-	-	-	1,422	10,903	-	-	10,903	-	-	-	-	-	-	14,614	-
3b.1.3	Grade & landscape site	-	1,684	-	-	-	-	-	253	1,937	-	-	1,937	-	-	-	-	-	-	5,050	-
3b.1.4	Final report to NRC	-	-	-	-	-	-	148	22	171	171	-	-	-	-	-	-	-	-	-	1,560
3b.1	Subtotal Period 3b Activity Costs	-	25,552	-	-	-	-	148	3,855	29,555	171	-	29,385	-	-	-	-	-	-	387,224	1,560
Period 3b Additional Costs																					
3b.2.1	Circulating Water Intake Cofferdam	-	192	-	-	-	-	-	29	221	-	-	221	-	-	-	-	-	-	2,540	-
3b.2.2	E.S.W.S. Pumphouse Cofferdam	-	256	-	-	-	-	-	38	295	-	-	295	-	-	-	-	-	-	3,386	-
3b.2.3	Concrete Crushing	-	611	-	-	-	-	6	92	709	-	-	709	-	-	-	-	-	-	4,294	-
3b.2	Subtotal Period 3b Additional Costs	-	1,059	-	-	-	-	6	160	1,225	-	-	1,225	-	-	-	-	-	-	10,220	-
Period 3b Collateral Costs																					
3b.3.1	Small tool allowance	-	135	-	-	-	-	-	20	156	-	-	156	-	-	-	-	-	-	-	-
3b.3	Subtotal Period 3b Collateral Costs	-	135	-	-	-	-	-	20	156	-	-	156	-	-	-	-	-	-	-	-
Period 3b Period-Dependent Costs																					
3b.4.1	Insurance	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
3b.4.2	Property taxes	-	-	-	-	-	-	182	18	200	-	-	200	-	-	-	-	-	-	-	-
3b.4.3	Heavy equipment rental	-	3,356	-	-	-	-	-	503	3,860	-	-	3,860	-	-	-	-	-	-	-	-
3b.4.4	Plant energy budget	-	-	-	-	-	-	202	30	232	-	-	232	-	-	-	-	-	-	-	-
3b.4.5	Security Staff Cost	-	-	-	-	-	-	840	126	966	-	-	966	-	-	-	-	-	-	-	27,926
3b.4.6	DOC Staff Cost	-	-	-	-	-	-	8,041	1,206	9,247	-	-	9,247	-	-	-	-	-	-	-	122,563
3b.4.7	Utility Staff Cost	-	-	-	-	-	-	4,185	628	4,813	-	-	4,813	-	-	-	-	-	-	-	79,123
3b.4	Subtotal Period 3b Period-Dependent Costs	-	3,356	-	-	-	-	13,450	2,512	19,318	-	-	19,318	-	-	-	-	-	-	-	229,611
3b.0	TOTAL PERIOD 3b COST	-	30,103	-	-	-	-	13,604	6,547	50,254	171	-	50,084	-	-	-	-	-	-	397,444	231,171
PERIOD 3 TOTALS		-	30,103	-	-	-	-	13,604	6,547	50,254	171	-	50,084	-	-	-	-	-	-	397,444	231,171

Table C  
Wolf Creek Generating Station  
DECON Decommissioning Cost Estimate  
(Thousands of 2005 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Costs	Total Contingency	Total Costs	NRC Lic. Term. Costs	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Burial Volumes				Burial / Processed Wt., Lbs.	Craft Manhours	Utility and Contractor Manhours
															Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTCC Cu. Feet			
TOTAL COST TO DECOMMISSION		8,762	72,347	10,509	6,640	20,874	59,636	256,238	82,595	517,601	436,860	25,236	55,506	217,495	101,461	12,680	861	559	20,978,320	1,456,850	3,644,386

TOTAL COST TO DECOMMISSION WITH 18.99% CONTINGENCY:	\$517,601	thousands of 2005 dollars
TOTAL NRC LICENSE TERMINATION COST IS 84.4% OR:	\$436,860	thousands of 2005 dollars
SPENT FUEL MANAGEMENT COST IS 4.88% OR:	\$25,236	thousands of 2005 dollars
NON-NUCLEAR DEMOLITION COST IS 10.72% OR:	\$55,506	thousands of 2005 dollars
TOTAL LOW-LEVEL RADIOACTIVE WASTE BURIED (EXCLUDING GTCC):	115,002	cubic feet
TOTAL GREATER THAN CLASS C RADWASTE VOLUME GENERATED:	559	cubic feet
TOTAL SCRAP METAL REMOVED:	67,188	tons
TOTAL CRAFT LABOR REQUIREMENTS:	1,456,850	man-hours

End Notes:  
n/a - indicates that this activity not charged as decommissioning expense.  
a - indicates that this activity performed by decommissioning staff.  
0 - indicates that this value is less than 0.5 but is non-zero.  
a cell containing " - " indicates a zero value

**APPENDIX D**  
**DETAILED COST ANALYSIS**  
**SAFSTOR**

Table D  
Wolf Creek Generating Station  
SAFSTOR Decommissioning Cost Estimate  
(Thousands of 2005 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Costs	Total Contingency	Total Costs	NRC Lic. Term. Costs	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Burial Volumes				Burial / Processed Wt., Lbs.	Craft Manhours	Utility and Contractor Manhours
															Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTCC Cu. Feet			
PERIOD 1a - Shutdown through Transition																					
Period 1a Direct Decommissioning Activities																					
1a.1.1	SAFSTOR site characterization survey	-	-	-	-	-	-	350	105	455	455	-	-	-	-	-	-	-	-	-	-
1a.1.2	Prepare preliminary decommissioning cost	-	-	-	-	-	-	124	19	142	142	-	-	-	-	-	-	-	-	-	1,300
1a.1.3	Notification of Cessation of Operations									a											
1a.1.4	Remove fuel & source material									n/a											
1a.1.5	Notification of Permanent Defueling									a											
1a.1.6	Deactivate plant systems & process waste									a											
1a.1.7	Prepare and submit PSDAR	-	-	-	-	-	-	190	29	219	219	-	-	-	-	-	-	-	-	-	2,000
1a.1.8	Review plant dwgs & specs.	-	-	-	-	-	-	124	19	142	142	-	-	-	-	-	-	-	-	-	1,300
1a.1.9	Perform detailed rad survey									a											
1a.1.10	Estimate by-product inventory	-	-	-	-	-	-	95	14	109	109	-	-	-	-	-	-	-	-	-	1,000
1a.1.11	End product description	-	-	-	-	-	-	95	14	109	109	-	-	-	-	-	-	-	-	-	1,000
1a.1.12	Detailed by-product inventory	-	-	-	-	-	-	143	21	164	164	-	-	-	-	-	-	-	-	-	1,500
1a.1.13	Define major work sequence	-	-	-	-	-	-	95	14	109	109	-	-	-	-	-	-	-	-	-	1,000
1a.1.14	Perform SER and EA	-	-	-	-	-	-	295	44	339	339	-	-	-	-	-	-	-	-	-	3,100
1a.1.15	Perform Site-Specific Cost Study	-	-	-	-	-	-	476	71	547	547	-	-	-	-	-	-	-	-	-	5,000
Activity Specifications																					
1a.1.16.1	Prepare plant and facilities for SAFSTOR	-	-	-	-	-	-	468	70	538	538	-	-	-	-	-	-	-	-	-	4,920
1a.1.16.2	Plant systems	-	-	-	-	-	-	396	59	456	456	-	-	-	-	-	-	-	-	-	4,167
1a.1.16.3	Plant structures and buildings	-	-	-	-	-	-	297	45	341	341	-	-	-	-	-	-	-	-	-	3,120
1a.1.16.4	Waste management	-	-	-	-	-	-	190	29	219	219	-	-	-	-	-	-	-	-	-	2,000
1a.1.16.5	Facility and site dormancy	-	-	-	-	-	-	190	29	219	219	-	-	-	-	-	-	-	-	-	2,000
1a.1.16	Total	-	-	-	-	-	-	1,542	231	1,773	1,773	-	-	-	-	-	-	-	-	-	16,207
Detailed Work Procedures																					
1a.1.17.1	Plant systems	-	-	-	-	-	-	113	17	129	129	-	-	-	-	-	-	-	-	-	1,183
1a.1.17.2	Facility closeout & dormancy	-	-	-	-	-	-	114	17	131	131	-	-	-	-	-	-	-	-	-	1,200
1a.1.17	Total	-	-	-	-	-	-	227	34	261	261	-	-	-	-	-	-	-	-	-	2,383
1a.1.18	Procure vacuum drying system	-	-	-	-	-	-	10	1	11	11	-	-	-	-	-	-	-	-	-	100
1a.1.19	Drain/de-energize non-cont. systems									a											
1a.1.20	Drain & dry NSSS									a											
1a.1.21	Drain/de-energize contaminated systems									a											
1a.1.22	Decon/secure contaminated systems									a											
1a.1	Subtotal Period 1a Activity Costs	-	-	-	-	-	-	3,764	617	4,381	4,381	-	-	-	-	-	-	-	-	-	35,890
Period 1a Collateral Costs																					
1a.3.1	Spent Fuel Transfer to DOE	-	-	-	-	-	-	2,600	390	2,990	-	2,990	-	-	-	-	-	-	-	-	-
1a.3	Subtotal Period 1a Collateral Costs	-	-	-	-	-	-	2,600	390	2,990	-	2,990	-	-	-	-	-	-	-	-	-
Period 1a Period-Dependent Costs																					
1a.4.1	Insurance	-	-	-	-	-	-	1,438	144	1,582	1,582	-	-	-	-	-	-	-	-	-	-
1a.4.2	Property taxes	-	-	-	-	-	-	1,487	149	1,636	1,636	-	-	-	-	-	-	-	-	-	-
1a.4.3	Health physics supplies	-	256	-	-	-	-	-	64	320	320	-	-	-	-	-	-	-	-	-	-
1a.4.4	Heavy equipment rental	-	336	-	-	-	-	-	50	386	386	-	-	-	-	-	-	-	-	-	-
1a.4.5	Disposal of DAW generated	-	-	6	3	-	28	-	8	45	45	-	-	-	404	-	-	-	8,103	99	-
1a.4.6	Plant energy budget	-	-	-	-	-	-	1,356	203	1,559	1,559	-	-	-	-	-	-	-	-	-	-
1a.4.7	NRC Fees	-	-	-	-	-	-	265	27	292	292	-	-	-	-	-	-	-	-	-	-
1a.4.8	Emergency Planning Fees	-	-	-	-	-	-	450	45	495	-	495	-	-	-	-	-	-	-	-	-
1a.4.9	Spent Fuel Pool O&M	-	-	-	-	-	-	940	141	1,082	-	1,082	-	-	-	-	-	-	-	-	-
1a.4.10	Security Staff Cost	-	-	-	-	-	-	1,772	266	2,038	2,038	-	-	-	-	-	-	-	-	-	58,921
1a.4.11	Utility Staff Cost	-	-	-	-	-	-	20,256	3,038	23,295	23,295	-	-	-	-	-	-	-	-	-	435,914
1a.4	Subtotal Period 1a Period-Dependent Costs	-	592	6	3	-	28	27,965	4,135	32,728	31,152	1,576	-	-	404	-	-	-	8,103	99	494,836



Table D  
Wolf Creek Generating Station  
SAFSTOR Decommissioning Cost Estimate  
(Thousands of 2005 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Costs	Total Contingency	Total Costs	NRC Lic. Term. Costs	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Burial Volumes				Burial / Processed Wt., Lbs.	Craft Manhours	Utility and Contractor Manhours
															Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTCC Cu. Feet			
1a.0	TOTAL PERIOD 1a COST	-	592	6	3	-	28	34,329	5,142	40,100	35,534	4,566	-	-	404	-	-	-	8,103	99	530,726
PERIOD 1b - SAFSTOR Limited DECON Activities																					
Period 1b Direct Decommissioning Activities																					
Decontamination of Site Buildings																					
1b.1.1.1	Reactor	615	-	-	-	-	-	-	307	922	922	-	-	-	-	-	-	-	-	24,718	-
1b.1.1.2	Auxiliary	314	-	-	-	-	-	-	157	470	470	-	-	-	-	-	-	-	-	12,859	-
1b.1.1.3	Communication Corridor - Contaminated	7	-	-	-	-	-	-	3	10	10	-	-	-	-	-	-	-	-	284	-
1b.1.1.4	Hot Machine Shop	9	-	-	-	-	-	-	4	13	13	-	-	-	-	-	-	-	-	353	-
1b.1.1.5	Radwaste	167	-	-	-	-	-	-	83	250	250	-	-	-	-	-	-	-	-	6,847	-
1b.1.1.6	Radwaste Drum Storage	19	-	-	-	-	-	-	9	28	28	-	-	-	-	-	-	-	-	770	-
1b.1.1.7	Radwaste Storage Building	48	-	-	-	-	-	-	24	71	71	-	-	-	-	-	-	-	-	1,940	-
1b.1.1.8	Fuel Building	381	-	-	-	-	-	-	190	571	571	-	-	-	-	-	-	-	-	14,711	-
1b.1.1	Totals	1,558	-	-	-	-	-	-	779	2,337	2,337	-	-	-	-	-	-	-	-	62,483	-
1b.1	Subtotal Period 1b Activity Costs	1,558	-	-	-	-	-	-	779	2,337	2,337	-	-	-	-	-	-	-	-	62,483	-
Period 1b Collateral Costs																					
1b.3.1	Decon equipment	729	-	-	-	-	-	-	109	838	838	-	-	-	-	-	-	-	-	-	-
1b.3.2	Process liquid waste	158	-	54	194	-	842	-	324	1,573	1,573	-	-	-	-	1,088	-	-	137,165	214	-
1b.3.3	Small tool allowance	-	25	-	-	-	-	-	4	29	29	-	-	-	-	-	-	-	-	-	-
1b.3.4	Spent Fuel Transfer to DOE	-	-	-	-	-	-	600	90	690	-	690	-	-	-	-	-	-	-	-	-
1b.3	Subtotal Period 1b Collateral Costs	887	25	54	194	-	842	600	527	3,130	2,440	690	-	-	-	1,088	-	-	137,165	214	-
Period 1b Period-Dependent Costs																					
1b.4.1	Decon supplies	948	-	-	-	-	-	-	237	1,185	1,185	-	-	-	-	-	-	-	-	-	-
1b.4.2	Insurance	-	-	-	-	-	-	362	36	399	399	-	-	-	-	-	-	-	-	-	-
1b.4.3	Property taxes	-	-	-	-	-	-	375	37	412	412	-	-	-	-	-	-	-	-	-	-
1b.4.4	Health physics supplies	-	285	-	-	-	-	-	71	356	356	-	-	-	-	-	-	-	-	-	-
1b.4.5	Heavy equipment rental	-	85	-	-	-	-	-	13	97	97	-	-	-	-	-	-	-	-	-	-
1b.4.6	Disposal of DAW generated	-	-	11	5	-	55	-	16	87	87	-	-	-	786	-	-	-	15,756	193	-
1b.4.7	Plant energy budget	-	-	-	-	-	-	342	51	393	393	-	-	-	-	-	-	-	-	-	-
1b.4.8	NRC Fees	-	-	-	-	-	-	67	7	74	74	-	-	-	-	-	-	-	-	-	-
1b.4.9	Emergency Planning Fees	-	-	-	-	-	-	113	11	125	-	125	-	-	-	-	-	-	-	-	-
1b.4.10	Spent Fuel Pool O&M	-	-	-	-	-	-	237	36	273	-	273	-	-	-	-	-	-	-	-	-
1b.4.11	Security Staff Cost	-	-	-	-	-	-	447	67	514	514	-	-	-	-	-	-	-	-	-	14,851
1b.4.12	Utility Staff Cost	-	-	-	-	-	-	5,106	766	5,872	5,872	-	-	-	-	-	-	-	-	-	109,874
1b.4	Subtotal Period 1b Period-Dependent Costs	948	369	11	5	-	55	7,049	1,348	9,785	9,388	397	-	-	786	-	-	-	15,756	193	124,726
1b.0	TOTAL PERIOD 1b COST	3,393	394	66	199	-	897	7,649	2,654	15,253	14,165	1,087	-	-	786	1,088	-	-	152,920	62,890	124,726
PERIOD 1c - Preparations for SAFSTOR Dormancy																					
Period 1c Direct Decommissioning Activities																					
1c.1.1	Prepare support equipment for storage	-	320	-	-	-	-	-	48	368	368	-	-	-	-	-	-	-	-	3,000	-
1c.1.2	Install containment pressure equal. lines	-	16	-	-	-	-	-	2	18	18	-	-	-	-	-	-	-	-	700	-
1c.1.3	Interim survey prior to dormancy	-	-	-	-	-	-	733	220	953	953	-	-	-	-	-	-	-	-	15,488	-
1c.1.4	Secure building accesses	-	-	-	-	-	-	-	-	a	-	-	-	-	-	-	-	-	-	-	-
1c.1.5	Prepare & submit interim report	-	-	-	-	-	-	55	8	64	64	-	-	-	-	-	-	-	-	-	583
1c.1	Subtotal Period 1c Activity Costs	-	335	-	-	-	-	788	278	1,402	1,402	-	-	-	-	-	-	-	-	19,188	583
Period 1c Additional Costs																					
1c.2.1	Spent Fuel Pool Isolation	-	-	-	-	-	-	8,609	1,291	9,900	9,900	-	-	-	-	-	-	-	-	-	-
1c.2.2	Misc/Hazardous Waste	-	2	-	5	66	-	-	11	84	84	-	-	1,365	-	-	-	-	91,790	442	-

**Table D**  
**Wolf Creek Generating Station**  
**SAFSTOR Decommissioning Cost Estimate**  
 (Thousands of 2005 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Costs	Total Contingency	Total Costs	NRC Lic. Term. Costs	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Burial Volumes				Burial / Processed Wt., Lbs.	Craft Manhours	Utility and Contractor Manhours
															Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTCC Cu. Feet			
1c.2	Subtotal Period 1c Additional Costs	-	2	-	5	66	-	8,609	1,303	9,985	9,985	-	-	1,365	-	-	-	-	91,790	442	-
Period 1c Collateral Costs																					
1c.3.1	Process liquid waste	172	-	59	211	-	911	-	351	1,705	1,705	-	-	-	-	1,184	-	-	149,292	233	-
1c.3.2	Small tool allowance	-	1	-	-	-	-	-	0	2	2	-	-	-	-	-	-	-	-	-	-
1c.3.3	Spent Fuel Transfer to DOE	-	-	-	-	-	-	600	90	690	-	690	-	-	-	-	-	-	-	-	-
1c.3	Subtotal Period 1c Collateral Costs	172	1	59	211	-	911	600	442	2,397	1,707	690	-	-	-	1,184	-	-	149,292	233	-
Period 1c Period-Dependent Costs																					
1c.4.1	Insurance	-	-	-	-	-	-	362	36	399	399	-	-	-	-	-	-	-	-	-	-
1c.4.2	Property taxes	-	-	-	-	-	-	375	37	412	412	-	-	-	-	-	-	-	-	-	-
1c.4.3	Health physics supplies	-	134	-	-	-	-	-	34	168	168	-	-	-	-	-	-	-	-	-	-
1c.4.4	Heavy equipment rental	-	85	-	-	-	-	-	13	97	97	-	-	-	-	-	-	-	-	-	-
1c.4.5	Disposal of DAW generated	-	-	1	1	-	7	-	2	11	11	-	-	-	102	-	-	-	2,042	25	-
1c.4.6	Plant energy budget	-	-	-	-	-	-	342	51	393	393	-	-	-	-	-	-	-	-	-	-
1c.4.7	NRC Fees	-	-	-	-	-	-	67	7	74	74	-	-	-	-	-	-	-	-	-	-
1c.4.8	Emergency Planning Fees	-	-	-	-	-	-	113	11	125	-	125	-	-	-	-	-	-	-	-	-
1c.4.9	Spent Fuel Pool O&M	-	-	-	-	-	-	237	36	273	-	273	-	-	-	-	-	-	-	-	-
1c.4.10	Security Staff Cost	-	-	-	-	-	-	447	67	514	514	-	-	-	-	-	-	-	-	-	14,851
1c.4.11	Utility Staff Cost	-	-	-	-	-	-	5,008	751	5,760	5,760	-	-	-	-	-	-	-	-	-	107,771
1c.4	Subtotal Period 1c Period-Dependent Costs	-	219	1	1	-	7	6,951	1,045	8,224	7,827	397	-	-	102	-	-	-	2,042	25	122,623
1c.0	TOTAL PERIOD 1c COST	172	558	61	217	66	918	16,949	3,068	22,008	20,921	1,087	-	1,365	102	1,184	-	-	243,124	19,888	123,206
PERIOD 1 TOTALS		3,565	1,544	132	418	66	1,844	58,926	10,864	77,360	70,620	6,741	-	1,365	1,292	2,273	-	-	404,148	82,877	778,658
PERIOD 2a - SAFSTOR Dormancy with Wet Spent Fuel Storage																					
Period 2a Direct Decommissioning Activities																					
2a.1.1	Quarterly Inspection									a											
2a.1.2	Semi-annual environmental survey									a											
2a.1.3	Prepare reports									a											
2a.1.4	Bituminous roof replacement	-	-	-	-	-	-	272	41	313	313	-	-	-	-	-	-	-	-	-	-
2a.1.5	Maintenance supplies	-	-	-	-	-	-	503	126	629	629	-	-	-	-	-	-	-	-	-	-
2a.1	Subtotal Period 2a Activity Costs	-	-	-	-	-	-	775	166	941	941	-	-	-	-	-	-	-	-	-	-
Period 2a Collateral Costs																					
2a.3.1	Spent Fuel Transfer to DOE	-	-	-	-	-	-	10,600	1,590	12,190	-	12,190	-	-	-	-	-	-	-	-	-
2a.3	Subtotal Period 2a Collateral Costs	-	-	-	-	-	-	10,600	1,590	12,190	-	12,190	-	-	-	-	-	-	-	-	-
Period 2a Period-Dependent Costs																					
2a.4.1	Insurance	-	-	-	-	-	-	1,910	191	2,101	1,807	294	-	-	-	-	-	-	-	-	-
2a.4.2	Property taxes	-	-	-	-	-	-	5,948	595	6,543	539	6,004	-	-	-	-	-	-	-	-	-
2a.4.3	Health physics supplies	-	256	-	-	-	-	-	64	320	320	-	-	-	-	-	-	-	-	-	-
2a.4.4	Disposal of DAW generated	-	-	23	10	-	113	-	32	179	179	-	-	-	1,617	-	-	-	32,412	397	-
2a.4.5	Plant energy budget	-	-	-	-	-	-	1,085	163	1,248	624	624	-	-	-	-	-	-	-	-	-
2a.4.6	NRC Fees	-	-	-	-	-	-	936	94	1,030	1,030	-	-	-	-	-	-	-	-	-	-
2a.4.7	Emergency Planning Fees	-	-	-	-	-	-	1,799	180	1,979	-	1,979	-	-	-	-	-	-	-	-	-
2a.4.8	Spent Fuel Pool O&M	-	-	-	-	-	-	3,762	564	4,326	-	4,326	-	-	-	-	-	-	-	-	-
2a.4.9	Security Staff Cost	-	-	-	-	-	-	3,889	583	4,472	1,515	2,958	-	-	-	-	-	-	-	-	129,314
2a.4.10	Utility Staff Cost	-	-	-	-	-	-	16,584	2,488	19,072	5,588	13,484	-	-	-	-	-	-	-	-	342,057
2a.4	Subtotal Period 2a Period-Dependent Costs	-	256	23	10	-	113	35,913	4,954	41,270	11,601	29,668	-	-	1,617	-	-	-	32,412	397	471,371
2a.0	TOTAL PERIOD 2a COST	-	256	23	10	-	113	47,288	6,710	54,401	12,542	41,858	-	-	1,617	-	-	-	32,412	397	471,371

Table D  
Wolf Creek Generating Station  
SAFSTOR Decommissioning Cost Estimate  
(Thousands of 2005 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Costs	Total Contingency	Total Costs	NRC Lic. Term. Costs	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Burial Volumes				Burial / Processed Wt., Lbs.	Craft Manhours	Utility and Contractor Manhours
															Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTCC Cu. Feet			
PERIOD 2c - SAFSTOR Dormancy without Spent Fuel Storage																					
Period 2c Direct Decommissioning Activities																					
2c.1.1	Quarterly Inspection									a											
2c.1.2	Semi-annual environmental survey									a											
2c.1.3	Prepare reports									a											
2c.1.4	Bituminous roof replacement	-	-	-	-	-	-	3,290	493	3,783	3,783	-	-	-	-	-	-	-	-	-	-
2c.1.5	Maintenance supplies	-	-	-	-	-	-	6,084	1,521	7,604	7,604	-	-	-	-	-	-	-	-	-	-
2c.1	Subtotal Period 2c Activity Costs	-	-	-	-	-	-	9,373	2,014	11,388	11,388	-	-	-	-	-	-	-	-	-	-
Period 2c Period-Dependent Costs																					
2c.4.1	Insurance	-	-	-	-	-	-	19,877	1,988	21,865	21,865	-	-	-	-	-	-	-	-	-	-
2c.4.2	Property taxes	-	-	-	-	-	-	5,926	593	6,518	6,518	-	-	-	-	-	-	-	-	-	-
2c.4.3	Health physics supplies	-	3,099	-	-	-	-	-	775	3,874	3,874	-	-	-	-	-	-	-	-	-	-
2c.4.4	Disposal of DAW generated	-	-	283	125	-	1,370	-	390	2,168	2,168	-	-	-	19,570	-	-	-	392,163	4,805	-
2c.4.5	Plant energy budget	-	-	-	-	-	-	6,563	984	7,547	7,547	-	-	-	-	-	-	-	-	-	-
2c.4.6	NRC Fees	-	-	-	-	-	-	11,327	1,133	12,459	12,459	-	-	-	-	-	-	-	-	-	-
2c.4.7	Security Staff Cost	-	-	-	-	-	-	15,938	2,391	18,329	18,329	-	-	-	-	-	-	-	-	-	529,950
2c.4.8	Utility Staff Cost	-	-	-	-	-	-	58,789	8,818	67,607	67,607	-	-	-	-	-	-	-	-	-	1,287,021
2c.4	Subtotal Period 2c Period-Dependent Costs	-	3,099	283	125	-	1,370	118,419	17,071	140,367	140,367	-	-	-	19,570	-	-	-	392,163	4,805	1,816,971
2c.0	TOTAL PERIOD 2c COST	-	3,099	283	125	-	1,370	127,793	19,085	151,754	151,754	-	-	-	19,570	-	-	-	392,163	4,805	1,816,971
PERIOD 2 TOTALS		-	3,355	306	136	-	1,483	175,080	25,795	206,155	164,297	41,858	-	-	21,187	-	-	-	424,575	5,202	2,288,343
PERIOD 3a - Reactivate Site Following SAFSTOR Dormancy																					
Period 3a Direct Decommissioning Activities																					
3a.1.1	Prepare preliminary decommissioning cost	-	-	-	-	-	-	124	19	142	142	-	-	-	-	-	-	-	-	-	1,300
3a.1.2	Review plant dwgs & specs.	-	-	-	-	-	-	438	66	503	503	-	-	-	-	-	-	-	-	-	4,600
3a.1.3	Perform detailed rad survey									a											
3a.1.4	End product description	-	-	-	-	-	-	95	14	109	109	-	-	-	-	-	-	-	-	-	1,000
3a.1.5	Detailed by-product inventory	-	-	-	-	-	-	124	19	142	142	-	-	-	-	-	-	-	-	-	1,300
3a.1.6	Define major work sequence	-	-	-	-	-	-	713	107	820	820	-	-	-	-	-	-	-	-	-	7,500
3a.1.7	Perform SER and EA	-	-	-	-	-	-	295	44	339	339	-	-	-	-	-	-	-	-	-	3,100
3a.1.8	Perform Site-Specific Cost Study	-	-	-	-	-	-	476	71	547	547	-	-	-	-	-	-	-	-	-	5,000
3a.1.9	Prepare/submit License Termination Plan	-	-	-	-	-	-	390	58	448	448	-	-	-	-	-	-	-	-	-	4,096
3a.1.10	Receive NRC approval of termination plan									a											
Activity Specifications																					
3a.1.11.1	Re-activate plant & temporary facilities	-	-	-	-	-	-	701	105	806	726	-	81	-	-	-	-	-	-	-	7,370
3a.1.11.2	Plant systems	-	-	-	-	-	-	396	59	456	410	-	46	-	-	-	-	-	-	-	4,167
3a.1.11.3	Reactor internals	-	-	-	-	-	-	675	101	777	777	-	-	-	-	-	-	-	-	-	7,100
3a.1.11.4	Reactor vessel	-	-	-	-	-	-	618	93	711	711	-	-	-	-	-	-	-	-	-	6,500
3a.1.11.5	Biological shield	-	-	-	-	-	-	48	7	55	55	-	-	-	-	-	-	-	-	-	500
3a.1.11.6	Steam generators	-	-	-	-	-	-	297	45	341	341	-	-	-	-	-	-	-	-	-	3,120
3a.1.11.7	Reinforced concrete	-	-	-	-	-	-	152	23	175	88	-	88	-	-	-	-	-	-	-	1,600
3a.1.11.8	Main Turbine	-	-	-	-	-	-	38	6	44	-	-	44	-	-	-	-	-	-	-	400
3a.1.11.9	Main Condensers	-	-	-	-	-	-	38	6	44	-	-	44	-	-	-	-	-	-	-	400
3a.1.11.10	Plant structures & buildings	-	-	-	-	-	-	297	45	341	171	-	171	-	-	-	-	-	-	-	3,120
3a.1.11.11	Waste management	-	-	-	-	-	-	438	66	503	503	-	-	-	-	-	-	-	-	-	4,600
3a.1.11.12	Facility & site closeout	-	-	-	-	-	-	86	13	98	49	-	49	-	-	-	-	-	-	-	900
3a.1.11	Total	-	-	-	-	-	-	3,784	568	4,351	3,830	-	521	-	-	-	-	-	-	-	39,777

Table D  
Wolf Creek Generating Station  
SAFSTOR Decommissioning Cost Estimate  
(Thousands of 2005 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Costs	Total Contingency	Total Costs	NRC Lic. Term. Costs	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Burial Volumes				Burial / Processed Wt., Lbs.	Craft Manhours	Utility and Contractor Manhours
															Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTCC Cu. Feet			
Planning & Site Preparations																					
3a.1.12	Prepare dismantling sequence	-	-	-	-	-	-	228	34	263	263	-	-	-	-	-	-	-	-	-	2,400
3a.1.13	Plant prep. & temp. svces	-	-	-	-	-	-	2,419	363	2,782	2,782	-	-	-	-	-	-	-	-	-	-
3a.1.14	Design water clean-up system	-	-	-	-	-	-	133	20	153	153	-	-	-	-	-	-	-	-	-	1,400
3a.1.15	Rigging/Cont. Cntrl Envlp/s/tooling/etc.	-	-	-	-	-	-	2,048	307	2,355	2,355	-	-	-	-	-	-	-	-	-	-
3a.1.16	Procure casks/liners & containers	-	-	-	-	-	-	117	18	135	135	-	-	-	-	-	-	-	-	-	1,230
3a.1	Subtotal Period 3a Activity Costs	-	-	-	-	-	-	11,382	1,707	13,090	12,569	-	521	-	-	-	-	-	-	-	72,703
Period 3a Period-Dependent Costs																					
3a.4.1	Insurance	-	-	-	-	-	-	207	21	228	228	-	-	-	-	-	-	-	-	-	-
3a.4.2	Property taxes	-	-	-	-	-	-	62	6	68	68	-	-	-	-	-	-	-	-	-	-
3a.4.3	Health physics supplies	-	129	-	-	-	-	-	32	161	161	-	-	-	-	-	-	-	-	-	-
3a.4.4	Heavy equipment rental	-	169	-	-	-	-	-	25	195	195	-	-	-	-	-	-	-	-	-	-
3a.4.5	Disposal of DAW generated	-	-	3	1	-	14	-	4	23	23	-	-	-	204	-	-	-	4,085	50	-
3a.4.6	Plant energy budget	-	-	-	-	-	-	684	103	786	786	-	-	-	-	-	-	-	-	-	-
3a.4.7	NRC Fees	-	-	-	-	-	-	134	13	147	147	-	-	-	-	-	-	-	-	-	-
3a.4.8	Security Staff Cost	-	-	-	-	-	-	245	37	282	282	-	-	-	-	-	-	-	-	-	8,149
3a.4.9	Utility Staff Cost	-	-	-	-	-	-	6,594	989	7,583	7,583	-	-	-	-	-	-	-	-	-	135,897
3a.4	Subtotal Period 3a Period-Dependent Costs	-	298	3	1	-	14	7,925	1,230	9,472	9,472	-	-	-	204	-	-	-	4,085	50	144,046
3a.0	TOTAL PERIOD 3a COST	-	298	3	1	-	14	19,307	2,938	22,562	22,041	-	521	-	204	-	-	-	4,085	50	216,748
PERIOD 3b - Decommissioning Preparations																					
Period 3b Direct Decommissioning Activities																					
Detailed Work Procedures																					
3b.1.1.1	Plant systems	-	-	-	-	-	-	450	68	518	466	-	52	-	-	-	-	-	-	-	4,733
3b.1.1.2	Reactor internals	-	-	-	-	-	-	238	36	273	273	-	-	-	-	-	-	-	-	-	2,500
3b.1.1.3	Remaining buildings	-	-	-	-	-	-	128	19	148	37	-	111	-	-	-	-	-	-	-	1,350
3b.1.1.4	CRD cooling assembly	-	-	-	-	-	-	95	14	109	109	-	-	-	-	-	-	-	-	-	1,000
3b.1.1.5	CRD housings & ICI tubes	-	-	-	-	-	-	95	14	109	109	-	-	-	-	-	-	-	-	-	1,000
3b.1.1.6	Incore instrumentation	-	-	-	-	-	-	95	14	109	109	-	-	-	-	-	-	-	-	-	1,000
3b.1.1.7	Reactor vessel	-	-	-	-	-	-	345	52	397	397	-	-	-	-	-	-	-	-	-	3,630
3b.1.1.8	Facility closeout	-	-	-	-	-	-	114	17	131	66	-	66	-	-	-	-	-	-	-	1,200
3b.1.1.9	Missile shields	-	-	-	-	-	-	43	6	49	49	-	-	-	-	-	-	-	-	-	450
3b.1.1.10	Biological shield	-	-	-	-	-	-	114	17	131	131	-	-	-	-	-	-	-	-	-	1,200
3b.1.1.11	Steam generators	-	-	-	-	-	-	438	66	503	503	-	-	-	-	-	-	-	-	-	4,600
3b.1.1.12	Reinforced concrete	-	-	-	-	-	-	95	14	109	55	-	55	-	-	-	-	-	-	-	1,000
3b.1.1.13	Main Turbine	-	-	-	-	-	-	148	22	171	-	-	171	-	-	-	-	-	-	-	1,560
3b.1.1.14	Main Condensers	-	-	-	-	-	-	148	22	171	-	-	171	-	-	-	-	-	-	-	1,560
3b.1.1.15	Auxiliary building	-	-	-	-	-	-	260	39	299	269	-	30	-	-	-	-	-	-	-	2,730
3b.1.1.16	Reactor building	-	-	-	-	-	-	260	39	299	269	-	30	-	-	-	-	-	-	-	2,730
3b.1.1	Total	-	-	-	-	-	-	3,067	460	3,527	2,843	-	684	-	-	-	-	-	-	-	32,243
3b.1	Subtotal Period 3b Activity Costs	-	-	-	-	-	-	3,067	460	3,527	2,843	-	684	-	-	-	-	-	-	-	32,243
Period 3b Additional Costs																					
3b.2.1	Site Characterization Survey	-	-	-	-	-	-	1,332	400	1,731	1,731	-	-	-	-	-	-	-	-	-	-
3b.2	Subtotal Period 3b Additional Costs	-	-	-	-	-	-	1,332	400	1,731	1,731	-	-	-	-	-	-	-	-	-	-
Period 3b Collateral Costs																					
3b.3.1	Decon equipment	729	-	-	-	-	-	-	109	838	838	-	-	-	-	-	-	-	-	-	-
3b.3.2	DOC staff relocation expenses	-	-	-	-	-	-	921	138	1,059	1,059	-	-	-	-	-	-	-	-	-	-
3b.3.3	Pipe cutting equipment	-	957	-	-	-	-	-	143	1,100	1,100	-	-	-	-	-	-	-	-	-	-
3b.3	Subtotal Period 3b Collateral Costs	729	957	-	-	-	-	921	391	2,997	2,997	-	-	-	-	-	-	-	-	-	-

**Table D**  
**Wolf Creek Generating Station**  
**SAFSTOR Decommissioning Cost Estimate**  
 (Thousands of 2005 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Costs	Total Contingency	Total Costs	NRC Lic. Term. Costs	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Burial Volumes				Burial / Processed Wt., Lbs.	Craft Manhours	Utility and Contractor Manhours
															Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTCC Cu. Feet			
Period 3b Period-Dependent Costs																					
3b.4.1	Decon supplies	45	-	-	-	-	-	-	11	56	56	-	-	-	-	-	-	-	-	-	-
3b.4.2	Insurance	-	-	-	-	-	-	478	48	525	525	-	-	-	-	-	-	-	-	-	-
3b.4.3	Property taxes	-	-	-	-	-	-	122	12	135	135	-	-	-	-	-	-	-	-	-	-
3b.4.4	Health physics supplies	-	256	-	-	-	-	-	64	320	320	-	-	-	-	-	-	-	-	-	-
3b.4.5	Heavy equipment rental	-	336	-	-	-	-	-	50	386	386	-	-	-	-	-	-	-	-	-	-
3b.4.6	Disposal of DAW generated	-	-	6	3	-	28	-	8	45	45	-	-	-	404	-	-	-	8,103	99	-
3b.4.7	Plant energy budget	-	-	-	-	-	-	1,356	203	1,559	1,559	-	-	-	-	-	-	-	-	-	-
3b.4.8	NRC Fees	-	-	-	-	-	-	265	27	292	292	-	-	-	-	-	-	-	-	-	-
3b.4.9	Security Staff Cost	-	-	-	-	-	-	486	73	559	559	-	-	-	-	-	-	-	-	-	16,164
3b.4.10	DOC Staff Cost	-	-	-	-	-	-	7,566	1,135	8,701	8,701	-	-	-	-	-	-	-	-	-	114,714
3b.4.11	Utility Staff Cost	-	-	-	-	-	-	13,239	1,986	15,225	15,225	-	-	-	-	-	-	-	-	-	273,750
3b.4	Subtotal Period 3b Period-Dependent Costs	45	592	6	3	-	28	23,513	3,617	27,804	27,804	-	-	-	404	-	-	-	8,103	99	404,629
3b.0	TOTAL PERIOD 3b COST	773	1,548	6	3	-	28	28,833	4,868	36,058	35,375	-	684	-	404	-	-	-	8,103	99	436,872
PERIOD 3 TOTALS		773	1,847	9	4	-	43	48,140	7,805	58,620	57,415	-	1,205	-	608	-	-	-	12,188	149	653,620
PERIOD 4a - Large Component Removal																					
Period 4a Direct Decommissioning Activities																					
Nuclear Steam Supply System Removal																					
4a.1.1.1	Reactor Coolant Piping	17	87	13	11	138	220	-	109	595	595	-	-	579	579	-	-	-	134,210	3,867	-
4a.1.1.2	Pressurizer Relief Tank	3	11	4	3	39	57	-	25	143	143	-	-	164	164	-	-	-	36,395	581	-
4a.1.1.3	Reactor Coolant Pumps & Motors	9	36	32	36	1,035	1,312	-	505	2,964	2,964	-	-	1,476	1,278	-	-	-	897,754	2,252	-
4a.1.1.4	Pressurizer	4	22	509	349	-	650	-	274	1,808	1,808	-	-	-	2,426	-	-	-	255,229	1,814	-
4a.1.1.5	Steam Generators	37	3,151	2,830	2,063	2,595	4,716	-	2,967	18,358	18,358	-	-	16,029	17,596	-	-	-	3,344,326	29,555	-
4a.1.1.6	CRDMs/ICIs/Service Structure Removal	15	58	120	25	98	176	-	96	588	588	-	-	1,227	3,012	-	-	-	101,470	2,614	-
4a.1.1.7	Reactor Vessel Internals	21	1,825	2,921	376	-	3,463	138	3,956	12,700	12,700	-	-	-	1,841	250	845	-	311,424	17,640	838
4a.1.1.8	Vessel & Internals GTCC Disposal	-	-	-	-	-	13,089	-	1,963	15,052	15,052	-	-	-	-	-	559	-	116,756	-	-
4a.1.1.9	Reactor Vessel	-	4,343	730	228	-	5,824	138	6,430	17,695	17,695	-	-	-	7,720	2,859	-	-	1,075,513	17,640	838
4a.1.1	Totals	106	9,533	7,158	3,091	3,904	29,509	276	16,326	69,903	69,903	-	-	19,475	34,616	3,110	845	559	6,273,078	75,963	1,675
Removal of Major Equipment																					
4a.1.2	Main Turbine/Generator	-	191	146	31	932	-	-	207	1,507	1,507	-	-	5,103	-	-	-	-	433,718	8,330	-
4a.1.3	Main Condensers	-	534	91	26	784	-	-	264	1,698	1,698	-	-	8,106	-	-	-	-	364,767	24,132	-
Cascading Costs from Clean Building Demolition																					
4a.1.4.1	Reactor	-	509	-	-	-	-	-	76	585	585	-	-	-	-	-	-	-	-	11,141	-
4a.1.4.2	Auxiliary	-	269	-	-	-	-	-	40	309	309	-	-	-	-	-	-	-	-	6,585	-
4a.1.4.3	Hot Machine Shop	-	0	-	-	-	-	-	-	1	1	-	-	-	-	-	-	-	-	16	-
4a.1.4.4	Radwaste	-	55	-	-	-	-	-	8	64	64	-	-	-	-	-	-	-	-	1,269	-
4a.1.4.5	Fuel Building	-	130	-	-	-	-	-	20	150	150	-	-	-	-	-	-	-	-	2,642	-
4a.1.4	Totals	-	964	-	-	-	-	-	145	1,108	1,108	-	-	-	-	-	-	-	-	21,652	-
Disposal of Plant Systems																					
4a.1.5.1	AB - Main Steam	-	107	-	-	-	-	-	16	123	-	-	123	-	-	-	-	-	-	5,833	-
4a.1.5.2	AB - Main Steam RCA	-	40	2	6	188	-	-	39	276	276	-	-	2,156	-	-	-	-	87,550	1,495	-
4a.1.5.3	AC - Main Turbine	-	105	-	-	-	-	-	16	121	-	-	121	-	-	-	-	-	-	5,641	-
4a.1.5.4	AD - Condensate	-	116	-	-	-	-	-	17	134	-	-	134	-	-	-	-	-	-	6,144	-
4a.1.5.5	AE - Feedwater	-	80	-	-	-	-	-	12	92	-	-	92	-	-	-	-	-	-	4,271	-
4a.1.5.6	AF - Feedwater Hter Extrction, Drn & Vnt	-	99	-	-	-	-	-	15	114	-	-	114	-	-	-	-	-	-	5,352	-
4a.1.5.7	AK - Condensate Demineralizer	-	36	-	-	-	-	-	5	42	-	-	42	-	-	-	-	-	-	1,944	-
4a.1.5.8	AL - Auxiliary Feedwater	-	16	-	-	-	-	-	2	18	-	-	18	-	-	-	-	-	-	852	-
4a.1.5.9	AQ - Condensate & Feedwater Chem Additn	-	9	-	-	-	-	-	1	10	-	-	10	-	-	-	-	-	-	468	-
4a.1.5.10	AX - Acid Feed	-	14	-	-	-	-	-	2	16	-	-	16	-	-	-	-	-	-	754	-
4a.1.5.11	Auxiliary Bldg Non-System Specific	-	50	1	3	72	6	-	25	157	157	-	-	824	22	-	-	-	35,448	1,969	-

Table D  
Wolf Creek Generating Station  
SAFSTOR Decommissioning Cost Estimate  
(Thousands of 2005 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Costs	Total Contingency	Total Costs	NRC Lic. Term. Costs	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Burial Volumes				Burial / Processed Wt., Lbs.	Craft Manhours	Utility and Contractor Manhours
															Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTCC Cu. Feet			
Disposal of Plant Systems (continued)																					
4a.1.5.12	Auxiliary Bldg Non-System Specific RCA	-	348	9	22	666	-	-	191	1,236	1,236	-	-	7,629	-	-	-	-	309,812	13,468	-
4a.1.5.13	BL - Reactor Makeup Water	-	124	7	11	221	83	-	87	534	534	-	-	2,529	315	-	-	-	129,173	4,655	-
4a.1.5.14	BM - Steam Generator Blowdown	-	251	6	15	451	-	-	133	855	855	-	-	5,160	-	-	-	-	209,560	9,483	-
4a.1.5.15	CA - Steam Seal	-	8	-	-	-	-	-	1	10	-	-	10	-	-	-	-	-	-	455	-
4a.1.5.16	CB - Main Turbine Lube Oil	-	24	-	-	-	-	-	4	27	-	-	27	-	-	-	-	-	-	1,207	-
4a.1.5.17	CC - Generator Hydrogen & CO2	-	4	-	-	-	-	-	1	4	-	-	4	-	-	-	-	-	-	198	-
4a.1.5.18	CD - Generator Seal Oil	-	5	-	-	-	-	-	1	6	-	-	6	-	-	-	-	-	-	287	-
4a.1.5.19	CE - Stator Cooling Water	-	5	-	-	-	-	-	1	5	-	-	5	-	-	-	-	-	-	241	-
4a.1.5.20	CF - Lube Oil Strg, Xfer & Purification	-	15	-	-	-	-	-	2	18	-	-	18	-	-	-	-	-	-	812	-
4a.1.5.21	CG - Condenser Air Removal	-	12	-	-	-	-	-	2	14	-	-	14	-	-	-	-	-	-	657	-
4a.1.5.22	CH - Main Turbine Control Oil	-	24	-	-	-	-	-	4	28	-	-	28	-	-	-	-	-	-	1,219	-
4a.1.5.23	CL - Chlorination	-	11	-	-	-	-	-	2	12	-	-	12	-	-	-	-	-	-	569	-
4a.1.5.24	CO - Carbon Dioxide	-	2	-	-	-	-	-	0	2	-	-	2	-	-	-	-	-	-	121	-
4a.1.5.25	CW - Circulating Water	-	144	-	-	-	-	-	22	165	-	-	165	-	-	-	-	-	-	7,858	-
4a.1.5.26	CZ - Caustic Acid	-	2	-	-	-	-	-	0	2	-	-	2	-	-	-	-	-	-	111	-
4a.1.5.27	DA - Circulating Water System	-	146	-	-	-	-	-	22	168	-	-	168	-	-	-	-	-	-	7,953	-
4a.1.5.28	DM - Equipment Drains	-	23	-	-	-	-	-	3	27	-	-	27	-	-	-	-	-	-	1,223	-
4a.1.5.29	DM - Equipment Drains RCA	-	76	18	45	1,349	-	-	230	1,716	1,716	-	-	15,445	-	-	-	-	627,223	2,835	-
4a.1.5.30	EG - Component Cooling Water RCA	-	358	16	41	1,236	-	-	283	1,935	1,935	-	-	14,161	-	-	-	-	575,071	13,276	-
4a.1.5.31	EJ - Residual Heat Removal	-	165	14	23	389	233	-	163	987	987	-	-	4,461	825	-	-	-	254,981	6,414	-
4a.1.5.32	EM - High Pressure Coolant Injection	-	128	2	6	188	-	-	61	386	386	-	-	2,159	-	-	-	-	87,663	4,659	-
4a.1.5.33	EN - Containment Spray	-	108	3	9	264	-	-	68	452	452	-	-	3,026	-	-	-	-	122,874	4,004	-
4a.1.5.34	FB - Auxiliary Steam	-	39	-	-	-	-	-	6	45	-	-	45	-	-	-	-	-	-	2,106	-
4a.1.5.35	FB - Auxiliary Steam RCA	-	42	1	2	71	-	-	22	138	138	-	-	816	-	-	-	-	33,148	1,492	-
4a.1.5.36	FC - Auxiliary Turbines	-	25	-	-	-	-	-	4	29	-	-	29	-	-	-	-	-	-	1,301	-
4a.1.5.37	FE - Auxiliary Steam Chemical Addition	-	2	-	-	-	-	-	0	2	-	-	2	-	-	-	-	-	-	105	-
4a.1.5.38	GE - Turbine Bldg HVAC	-	54	-	-	-	-	-	8	62	-	-	62	-	-	-	-	-	-	3,081	-
4a.1.5.39	GF - Miscellaneous Building HVAC	-	16	-	-	-	-	-	2	19	-	-	19	-	-	-	-	-	-	945	-
4a.1.5.40	GS - Containment Hydrogen Control	-	34	1	2	70	-	-	19	127	127	-	-	801	-	-	-	-	32,539	1,265	-
4a.1.5.41	HF - Secondary Liquid Waste	-	422	24	38	736	317	-	303	1,841	1,841	-	-	8,431	1,173	-	-	-	442,934	16,162	-
4a.1.5.42	HY - Hydrogen	-	4	-	-	-	-	-	1	5	-	-	5	-	-	-	-	-	-	223	-
4a.1.5.43	KH - Service Gas	-	12	-	-	-	-	-	2	14	-	-	14	-	-	-	-	-	-	644	-
4a.1.5.44	LE - Oily Waste	-	48	-	-	-	-	-	7	55	-	-	55	-	-	-	-	-	-	2,575	-
4a.1.5.45	LE - Oily Waste RCA	-	96	2	5	150	-	-	47	300	300	-	-	1,718	-	-	-	-	69,785	3,398	-
4a.1.5.46	NT - Nitrogen	-	3	-	-	-	-	-	0	3	-	-	3	-	-	-	-	-	-	149	-
4a.1.5.47	OX - Oxygen	-	3	-	-	-	-	-	0	4	-	-	4	-	-	-	-	-	-	171	-
4a.1.5.48	SW - Screen Wash	-	12	-	-	-	-	-	2	14	-	-	14	-	-	-	-	-	-	635	-
4a.1.5.49	Turbine Bldg Non-System Specific	-	298	-	-	-	-	-	45	343	-	-	343	-	-	-	-	-	-	15,405	-
4a.1.5.50	VH - Circ Water & Makeup Water Scrnhs	-	5	-	-	-	-	-	1	5	-	-	5	-	-	-	-	-	-	245	-
4a.1.5.51	VV - Misc Bldg HVAC	-	2	-	-	-	-	-	0	3	-	-	3	-	-	-	-	-	-	123	-
4a.1.5.52	WG - Gland Water & Motor Cooling Water	-	11	-	-	-	-	-	2	12	-	-	12	-	-	-	-	-	-	593	-
4a.1.5.53	WL - Cooling Lake Makeup & Blowdown	-	14	-	-	-	-	-	2	16	-	-	16	-	-	-	-	-	-	745	-
4a.1.5	Totals	-	3,796	108	228	6,052	639	-	1,906	12,729	10,939	-	1,790	69,317	2,336	-	-	-	3,017,759	167,788	-
4a.1.6	Scaffolding in support of decommissioning	-	674	14	5	117	2	-	189	1,000	1,000	-	-	1,206	60	-	-	-	60,307	32,150	-
4a.1	Subtotal Period 4a Activity Costs	106	15,692	7,516	3,381	11,790	30,150	276	19,036	87,946	86,156	-	1,790	103,206	37,012	3,110	845	559	10,149,630	330,016	1,675
Period 4a Additional Costs																					
4a.2.1	Curie Surcharge(Excluding RPV)	-	-	-	-	-	171	-	43	214	214	-	-	-	-	-	-	-	-	-	-
4a.2	Subtotal Period 4a Additional Costs	-	-	-	-	-	171	-	43	214	214	-	-	-	-	-	-	-	-	-	-
Period 4a Collateral Costs																					
4a.3.1	Process liquid waste	4	-	4	13	-	116	-	34	171	171	-	-	-	-	76	-	-	9,604	15	-
4a.3.2	Small tool allowance	-	132	-	-	-	-	-	20	151	136	-	15	-	-	-	-	-	-	-	-
4a.3	Subtotal Period 4a Collateral Costs	4	132	4	13	-	116	-	53	323	308	-	15	-	-	76	-	-	9,604	15	-

Table D  
Wolf Creek Generating Station  
SAFSTOR Decommissioning Cost Estimate  
(Thousands of 2005 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Costs	Total Contingency	Total Costs	NRC Lic. Term. Costs	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Burial Volumes				Burial / Processed Wt., Lbs.	Craft Manhours	Utility and Contractor Manhours
															Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTCC Cu. Feet			
Period 4a Period-Dependent Costs																					
4a.4.1	Decon supplies	49	-	-	-	-	-	-	12	61	61	-	-	-	-	-	-	-	-	-	-
4a.4.2	Insurance	-	-	-	-	-	-	522	52	574	574	-	-	-	-	-	-	-	-	-	-
4a.4.3	Property taxes	-	-	-	-	-	-	134	13	147	133	-	15	-	-	-	-	-	-	-	-
4a.4.4	Health physics supplies	-	1,438	-	-	-	-	-	359	1,797	1,797	-	-	-	-	-	-	-	-	-	-
4a.4.5	Heavy equipment rental	-	1,787	-	-	-	-	-	268	2,055	2,055	-	-	-	-	-	-	-	-	-	-
4a.4.6	Disposal of DAW generated	-	-	66	29	-	319	-	91	504	504	-	-	-	4,551	-	-	-	91,190	1,117	-
4a.4.7	Plant energy budget	-	-	-	-	-	-	1,408	211	1,619	1,619	-	-	-	-	-	-	-	-	-	-
4a.4.8	NRC Fees	-	-	-	-	-	-	358	36	394	394	-	-	-	-	-	-	-	-	-	-
4a.4.9	Radwaste Processing Equipment/Services	-	-	-	-	-	-	405	61	466	466	-	-	-	-	-	-	-	-	-	-
4a.4.10	Security Staff Cost	-	-	-	-	-	-	2,057	309	2,366	2,366	-	-	-	-	-	-	-	-	-	68,400
4a.4.11	DOC Staff Cost	-	-	-	-	-	-	10,975	1,646	12,622	12,622	-	-	-	-	-	-	-	-	-	173,280
4a.4.12	Utility Staff Cost	-	-	-	-	-	-	14,653	2,198	16,851	16,851	-	-	-	-	-	-	-	-	-	306,660
4a.4	Subtotal Period 4a Period-Dependent Costs	49	3,225	66	29	-	319	30,513	5,257	39,457	39,442	-	15	-	4,551	-	-	-	91,190	1,117	548,340
4a.0	TOTAL PERIOD 4a COST	159	19,048	7,585	3,423	11,790	30,756	30,789	24,388	127,939	126,120	-	1,819	103,206	41,562	3,186	845	559	10,250,420	331,148	550,015
PERIOD 4b - Site Decontamination																					
Period 4b Direct Decommissioning Activities																					
4b.1.1	Remove spent fuel racks	327	34	144	55	-	1,247	-	506	2,313	2,313	-	-	-	4,412	-	-	-	395,882	1,722	-
Disposal of Plant Systems																					
4b.1.2.1	AN - Demineralized Wtr Storage & xfer	-	29	-	-	-	-	-	4	33	-	-	33	-	-	-	-	-	-	1,548	-
4b.1.2.2	AN - Demineralized Wtr Strg & xfer RCA	-	9	0	0	10	-	-	4	24	24	-	-	120	-	-	-	-	4,855	320	-
4b.1.2.3	AP - Condensate Storage & Transfer	-	33	-	-	-	-	-	5	38	-	-	38	-	-	-	-	-	-	1,660	-
4b.1.2.4	BB - Reactor Coolant	-	122	13	17	219	224	-	123	718	718	-	-	2,511	896	-	-	-	172,973	4,930	-
4b.1.2.5	BG - Chemical & Volume Control	-	391	32	46	712	516	-	344	2,040	2,040	-	-	8,155	1,842	-	-	-	494,889	14,656	-
4b.1.2.6	BN - Borated Refueling Water Storage	-	147	7	18	546	-	-	122	840	840	-	-	6,255	-	-	-	-	254,024	5,897	-
4b.1.2.7	Control Bldg Non-System Specific	-	89	2	6	187	-	-	51	335	335	-	-	2,139	-	-	-	-	86,849	3,413	-
4b.1.2.8	Control Bldg Non-System Specific Cln	-	713	-	-	-	-	-	107	820	-	-	820	-	-	-	-	-	-	29,076	-
4b.1.2.9	DO - Diesel Oil	-	1	-	-	-	-	-	0	1	-	-	1	-	-	-	-	-	-	48	-
4b.1.2.10	EA - Service Water	-	48	-	-	-	-	-	7	55	-	-	55	-	-	-	-	-	-	2,592	-
4b.1.2.11	EB - Closed Cooling Water	-	24	-	-	-	-	-	4	27	-	-	27	-	-	-	-	-	-	1,267	-
4b.1.2.12	EC - Fuel Pool Cooling & Cleanup	-	169	5	12	359	-	-	98	643	643	-	-	4,115	-	-	-	-	167,129	6,321	-
4b.1.2.13	EF - Essential Service Water	-	55	-	-	-	-	-	8	63	-	-	63	-	-	-	-	-	-	2,951	-
4b.1.2.14	EF - Essential Service Water RCA	-	45	2	4	125	-	-	31	206	206	-	-	1,427	-	-	-	-	57,959	1,677	-
4b.1.2.15	EP - Accumulator Safety Injection	-	71	2	6	171	-	-	44	294	294	-	-	1,958	-	-	-	-	79,502	2,626	-
4b.1.2.16	FA - Auxiliary Steam Generator	-	9	-	-	-	-	-	1	11	-	-	11	-	-	-	-	-	-	521	-
4b.1.2.17	FO - Fuel Oil	-	9	-	-	-	-	-	1	10	-	-	10	-	-	-	-	-	-	486	-
4b.1.2.18	FP - Fire Protection	-	70	-	-	-	-	-	11	81	-	-	81	-	-	-	-	-	-	3,826	-
4b.1.2.19	FP - Fire Protection RCA	-	101	5	13	392	-	-	86	598	598	-	-	4,492	-	-	-	-	182,411	3,540	-
4b.1.2.20	Fuel Bldg Non-System Specific	-	21	0	1	28	2	-	10	64	64	-	-	322	9	-	-	-	13,827	825	-
4b.1.2.21	Fuel Bldg Non-System Specific RCA	-	154	4	9	279	-	-	82	529	529	-	-	3,200	-	-	-	-	129,974	5,858	-
4b.1.2.22	Fuel Building Fire Protection	-	78	3	8	257	-	-	60	407	407	-	-	2,941	-	-	-	-	119,444	2,771	-
4b.1.2.23	GA - Plant Heating	-	35	-	-	-	-	-	5	41	-	-	41	-	-	-	-	-	-	1,912	-
4b.1.2.24	GA - Plant Heating RCA	-	58	1	2	65	-	-	25	150	150	-	-	746	-	-	-	-	30,275	1,992	-
4b.1.2.25	GB - Central Chilled Water	-	33	-	-	-	-	-	5	38	-	-	38	-	-	-	-	-	-	1,803	-
4b.1.2.26	GB - Central Chilled Water RCA	-	13	0	1	16	-	-	6	36	36	-	-	187	-	-	-	-	7,591	463	-
4b.1.2.27	GD - Esstl Srvc Wtr Pumphs Bldg HVAC	-	5	-	-	-	-	-	1	6	-	-	6	-	-	-	-	-	-	271	-
4b.1.2.28	GG - Fuel Building HVAC	-	133	4	11	344	-	-	87	580	580	-	-	3,945	-	-	-	-	160,195	4,030	-
4b.1.2.29	GH - Radwaste Building HVAC	-	96	3	7	224	-	-	59	389	389	-	-	2,561	-	-	-	-	104,012	2,973	-
4b.1.2.30	GK - Control Building HVAC	-	65	-	-	-	-	-	10	75	-	-	75	-	-	-	-	-	-	3,900	-
4b.1.2.31	GL - Auxiliary Building HVAC	-	242	6	16	470	-	-	134	867	867	-	-	5,381	-	-	-	-	218,514	7,310	-
4b.1.2.32	GM - Diesel Generator Building HVAC	-	11	-	-	-	-	-	2	13	-	-	13	-	-	-	-	-	-	692	-
4b.1.2.33	GN - Containment Cooling	-	250	9	24	720	-	-	175	1,178	1,178	-	-	8,250	-	-	-	-	335,052	8,054	-
4b.1.2.34	GP - Containmnt Integratd Leak Rate Test	-	20	1	2	51	-	-	13	85	85	-	-	580	-	-	-	-	23,570	737	-
4b.1.2.35	GR - Containment Atmospheric Control	-	8	1	3	100	-	-	18	130	130	-	-	1,143	-	-	-	-	46,407	340	-

Table D  
Wolf Creek Generating Station  
SAFSTOR Decommissioning Cost Estimate  
(Thousands of 2005 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site	LLRW	Other Costs	Total Contingency	Total Costs	NRC	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Burial Volumes				Burial /	Craft Manhours	Utility and
						Processing Costs	Disposal Costs				Lic. Term. Costs				Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTCC Cu. Feet	Processed Wt., Lbs.		Contractor Manhours
Disposal of Plant Systems (continued)																					
4b.1.2.36	GT - Containment Purge HVAC	-	60	2	6	191	-	-	45	304	304	-	-	2,185	-	-	-	-	88,746	1,932	-
4b.1.2.37	HA - Gaseous Radwaste	-	158	4	11	323	-	-	90	585	585	-	-	3,699	-	-	-	-	150,219	5,632	-
4b.1.2.38	HB - Liquid Radwaste	-	376	23	34	641	289	-	270	1,634	1,634	-	-	7,343	1,077	-	-	-	389,899	14,004	-
4b.1.2.39	HC - Solid Radwaste	-	204	15	22	348	241	-	168	999	999	-	-	3,986	864	-	-	-	238,526	7,543	-
4b.1.2.40	HD - Decontamination	-	46	1	4	107	-	-	28	185	185	-	-	1,220	-	-	-	-	49,558	1,717	-
4b.1.2.41	HE - Boron Recycle	-	213	12	17	302	158	-	142	844	844	-	-	3,460	583	-	-	-	190,724	7,930	-
4b.1.2.42	JE - Emergency Fuel Oil	-	25	-	-	-	-	-	4	29	-	-	29	-	-	-	-	-	-	1,260	-
4b.1.2.43	KA - Compressed Air and Instrument	-	114	-	-	-	-	-	17	131	-	-	131	-	-	-	-	-	-	6,089	-
4b.1.2.44	KB - Breathing Air	-	20	-	-	-	-	-	3	23	-	-	23	-	-	-	-	-	-	1,075	-
4b.1.2.45	KC - Fire Protection	-	138	-	-	-	-	-	21	159	-	-	159	-	-	-	-	-	-	7,516	-
4b.1.2.46	KC - Fire Protection RCA	-	176	7	17	519	-	-	125	844	844	-	-	5,944	-	-	-	-	241,384	6,276	-
4b.1.2.47	KD - Domestic Water	-	32	-	-	-	-	-	5	37	-	-	37	-	-	-	-	-	-	1,708	-
4b.1.2.48	KE - Fuel Hndlg & Strg Reactor Vssl Serv	-	8	1	3	77	-	-	14	102	102	-	-	882	-	-	-	-	35,813	323	-
4b.1.2.49	KJ - Standby Diesel Engine	-	131	-	-	-	-	-	20	151	-	-	151	-	-	-	-	-	-	6,749	-
4b.1.2.50	LA - Sanitary Drains	-	5	-	-	-	-	-	1	6	-	-	6	-	-	-	-	-	-	290	-
4b.1.2.51	LA - Sanitary Drains RCA	-	13	0	1	24	-	-	7	45	45	-	-	272	-	-	-	-	11,053	421	-
4b.1.2.52	LB - Roof Drains	-	24	-	-	-	-	-	4	27	-	-	27	-	-	-	-	-	-	1,276	-
4b.1.2.53	LB - Roof Drains RCA	-	73	2	6	187	-	-	47	315	315	-	-	2,139	-	-	-	-	86,858	2,627	-
4b.1.2.54	LC - Yard Drains	-	2	-	-	-	-	-	0	2	-	-	2	-	-	-	-	-	-	96	-
4b.1.2.55	LD - Chemical & Detergent Waste	-	49	1	2	70	-	-	23	144	144	-	-	797	-	-	-	-	32,369	1,828	-
4b.1.2.56	LF - Floor & Equipment Drains	-	625	36	51	581	723	-	436	2,453	2,453	-	-	6,660	2,567	-	-	-	500,138	23,235	-
4b.1.2.57	RM - Process Sampling & Analysis	-	60	1	3	86	-	-	29	179	179	-	-	990	-	-	-	-	40,200	2,335	-
4b.1.2.58	Radwaste Bldg Non-System Specific	-	81	2	4	116	10	-	41	254	254	-	-	1,329	35	-	-	-	57,135	3,158	-
4b.1.2.59	Radwaste Bldg Non-System Specific RCA	-	571	15	37	1,107	-	-	316	2,046	2,046	-	-	12,684	-	-	-	-	515,103	21,915	-
4b.1.2.60	Reactor Bldg Non-System Specific	-	40	1	2	44	4	-	18	108	108	-	-	502	13	-	-	-	21,587	1,521	-
4b.1.2.61	Reactor Bldg Non-System Specific RCA	-	280	5	14	416	-	-	135	850	850	-	-	4,768	-	-	-	-	193,612	10,423	-
4b.1.2.62	SJ - Nuclear Sampling	-	32	1	2	59	-	-	17	111	111	-	-	677	-	-	-	-	27,501	1,312	-
4b.1.2.63	ST - Sewage Treatment	-	44	-	-	-	-	-	7	50	-	-	50	-	-	-	-	-	-	2,316	-
4b.1.2.64	SZ - Service Air	-	35	-	-	-	-	-	5	40	-	-	40	-	-	-	-	-	-	1,892	-
4b.1.2.65	VA - I&C Shop HVAC	-	3	-	-	-	-	-	0	3	-	-	3	-	-	-	-	-	-	141	-
4b.1.2.66	VB - I&C Shop Computer Room HVAC	-	2	-	-	-	-	-	0	2	-	-	2	-	-	-	-	-	-	95	-
4b.1.2.67	VC - Health Physics Computer Room HVAC	-	4	-	-	-	-	-	1	5	-	-	5	-	-	-	-	-	-	202	-
4b.1.2.68	VJ - Shop Bldg Machine Shop Area Vent	-	1	-	-	-	-	-	0	1	-	-	1	-	-	-	-	-	-	51	-
4b.1.2.69	VL - Shop Building HVAC	-	2	-	-	-	-	-	0	2	-	-	2	-	-	-	-	-	-	92	-
4b.1.2.70	VS - Admin Bldg HVAC	-	5	-	-	-	-	-	1	5	-	-	5	-	-	-	-	-	-	238	-
4b.1.2.71	VT - Tech Support Building HVAC	-	2	-	-	-	-	-	0	2	-	-	2	-	-	-	-	-	-	79	-
4b.1.2.72	VW - Waste Water Treatment Ventilation	-	1	-	-	-	-	-	0	1	-	-	1	-	-	-	-	-	-	48	-
4b.1.2.73	WD - Domestic Water	-	16	-	-	-	-	-	2	18	-	-	18	-	-	-	-	-	-	870	-
4b.1.2.74	WM - Makeup Demineralizer	-	73	-	-	-	-	-	11	84	-	-	84	-	-	-	-	-	-	3,929	-
4b.1.2.75	WS - Plant Services Water	-	61	-	-	-	-	-	9	70	-	-	70	-	-	-	-	-	-	3,297	-
4b.1.2.76	WS - Plant Services Water RCA	-	20	2	5	160	-	-	30	218	218	-	-	1,838	-	-	-	-	74,625	778	-
4b.1.2.77	WT - Waste Water Treatment	-	14	-	-	-	-	-	2	16	-	-	16	-	-	-	-	-	-	769	-
4b.1.2.78	WZ - Radioactive Liquid Waste	-	21	2	2	22	33	-	17	97	97	-	-	247	118	-	-	-	20,604	761	-
4b.1.2.79	Yard Non-System Specific	-	12	-	-	-	-	-	2	13	-	-	13	-	-	-	-	-	-	603	-
4b.1.2	Totals	-	7,226	234	450	10,656	2,201	-	3,856	24,623	22,434	-	2,189	122,048	8,004	-	-	-	5,655,104	287,640	-
4b.1.3	Scaffolding in support of decommissioning	-	1,010	21	7	175	3	-	283	1,500	1,500	-	-	1,809	90	-	-	-	90,460	48,226	-
Decontamination of Site Buildings																					
4b.1.4.1	Reactor	536	444	84	112	520	1,113	-	761	3,571	3,571	-	-	5,955	7,058	-	-	-	905,431	37,131	-
4b.1.4.2	Auxiliary	281	125	21	31	180	61	-	221	920	920	-	-	2,058	1,696	-	-	-	249,762	14,927	-
4b.1.4.3	Communication Corridor - Contaminated	6	2	0	1	1	1	-	4	16	16	-	-	17	36	-	-	-	4,292	300	-
4b.1.4.4	Hot Machine Shop	8	2	0	1	-	2	-	5	18	18	-	-	-	44	-	-	-	4,446	360	-
4b.1.4.5	Radwaste	150	58	11	16	74	33	-	112	453	453	-	-	844	892	-	-	-	122,248	7,650	-
4b.1.4.6	Radwaste Drum Storage	17	6	1	2	6	4	-	12	47	47	-	-	66	99	-	-	-	12,548	833	-
4b.1.4.7	Radwaste Storage Building	43	11	3	4	-	10	-	27	98	98	-	-	-	257	-	-	-	25,740	1,970	-
4b.1.4.8	Fuel Building	329	349	9	14	236	18	-	294	1,249	1,249	-	-	2,705	479	-	-	-	157,196	26,693	-



**Table D**  
**Wolf Creek Generating Station**  
**SAFSTOR Decommissioning Cost Estimate**  
 (Thousands of 2005 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Costs	Total Contingency	Total Costs	NRC Lic. Term. Costs	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Burial Volumes					Burial / Processed Wt., Lbs.	Craft Manhours	Utility and Contractor Manhours
															Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTCC Cu. Feet				
4b.1.4	Totals	1,370	998	130	179	1,017	1,241	-	1,437	6,372	6,372	-	-	11,646	10,563	-	-	-	1,481,663	89,865	-	
4b.1	Subtotal Period 4b Activity Costs	1,697	9,269	529	691	11,848	4,692	-	6,082	34,808	32,619	-	2,189	135,503	23,070	-	-	-	7,623,109	427,452	-	
Period 4b Collateral Costs																						
4b.3.1	Process liquid waste	11	-	10	36	-	208	-	64	328	328	-	-	-	-	203	-	-	25,651	40	-	
4b.3.2	Small tool allowance	-	171	-	-	-	-	-	26	197	197	-	-	-	-	-	-	-	-	-	-	
4b.3.3	Decommissioning Equipment Disposition	-	-	71	28	581	106	-	125	910	910	-	-	6,000	373	-	-	-	303,507	739	-	
4b.3	Subtotal Period 4b Collateral Costs	11	171	82	64	581	313	-	214	1,435	1,435	-	-	6,000	373	203	-	-	329,158	779	-	
Period 4b Period-Dependent Costs																						
4b.4.1	Decon supplies	1,061	-	-	-	-	-	-	265	1,326	1,326	-	-	-	-	-	-	-	-	-	-	
4b.4.2	Insurance	-	-	-	-	-	-	1,323	132	1,455	1,455	-	-	-	-	-	-	-	-	-	-	
4b.4.3	Property taxes	-	-	-	-	-	-	339	34	373	373	-	-	-	-	-	-	-	-	-	-	
4b.4.4	Health physics supplies	-	2,212	-	-	-	-	-	553	2,765	2,765	-	-	-	-	-	-	-	-	-	-	
4b.4.5	Heavy equipment rental	-	4,556	-	-	-	-	-	683	5,239	5,239	-	-	-	-	-	-	-	-	-	-	
4b.4.6	Disposal of DAW generated	-	-	93	41	-	449	-	128	710	710	-	-	-	6,414	-	-	-	128,528	1,575	-	
4b.4.7	Plant energy budget	-	-	-	-	-	-	2,817	423	3,240	3,240	-	-	-	-	-	-	-	-	-	-	
4b.4.8	NRC Fees	-	-	-	-	-	-	907	91	998	998	-	-	-	-	-	-	-	-	-	-	
4b.4.9	Radwaste Processing Equipment/Services	-	-	-	-	-	-	1,026	154	1,180	1,180	-	-	-	-	-	-	-	-	-	-	
4b.4.10	Security Staff Cost	-	-	-	-	-	-	3,996	599	4,596	4,596	-	-	-	-	-	-	-	-	-	132,874	
4b.4.11	DOC Staff Cost	-	-	-	-	-	-	24,820	3,723	28,543	28,543	-	-	-	-	-	-	-	-	-	392,846	
4b.4.12	Utility Staff Cost	-	-	-	-	-	-	33,000	4,950	37,950	37,950	-	-	-	-	-	-	-	-	-	668,704	
4b.4	Subtotal Period 4b Period-Dependent Costs	1,061	6,768	93	41	-	449	68,229	11,735	88,375	88,375	-	-	-	6,414	-	-	-	128,528	1,575	1,194,424	
4b.0	TOTAL PERIOD 4b COST	2,768	16,207	704	796	12,429	5,454	68,229	18,031	124,618	122,429	-	2,189	141,503	29,857	203	-	-	8,080,795	429,806	1,194,424	
PERIOD 4e - License Termination																						
Period 4e Direct Decommissioning Activities																						
4e.1.1	ORISE confirmatory survey	-	-	-	-	-	-	121	36	157	157	-	-	-	-	-	-	-	-	-	-	
4e.1.2	Terminate license	-	-	-	-	-	-	-	-	a	-	-	-	-	-	-	-	-	-	-	-	
4e.1	Subtotal Period 4e Activity Costs	-	-	-	-	-	-	121	36	157	157	-	-	-	-	-	-	-	-	-	-	
Period 4e Additional Costs																						
4e.2.1	Final Site Survey	-	-	-	-	-	-	4,819	1,446	6,265	6,265	-	-	-	-	-	-	-	-	149,600	-	
4e.2	Subtotal Period 4e Additional Costs	-	-	-	-	-	-	4,819	1,446	6,265	6,265	-	-	-	-	-	-	-	-	149,600	-	
Period 4e Collateral Costs																						
4e.3.1	DOC staff relocation expenses	-	-	-	-	-	-	921	138	1,059	1,059	-	-	-	-	-	-	-	-	-	-	
4e.3	Subtotal Period 4e Collateral Costs	-	-	-	-	-	-	921	138	1,059	1,059	-	-	-	-	-	-	-	-	-	-	
Period 4e Period-Dependent Costs																						
4e.4.1	Insurance	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
4e.4.2	Property taxes	-	-	-	-	-	-	95	9	104	104	-	-	-	-	-	-	-	-	-	-	
4e.4.3	Health physics supplies	-	723	-	-	-	-	-	181	903	903	-	-	-	-	-	-	-	-	-	-	
4e.4.4	Disposal of DAW generated	-	-	5	2	-	22	-	6	35	35	-	-	-	312	-	-	-	6,260	77	-	
4e.4.5	Plant energy budget	-	-	-	-	-	-	210	31	241	241	-	-	-	-	-	-	-	-	-	-	
4e.4.6	NRC Fees	-	-	-	-	-	-	253	25	278	278	-	-	-	-	-	-	-	-	-	-	
4e.4.7	Security Staff Cost	-	-	-	-	-	-	436	65	502	502	-	-	-	-	-	-	-	-	-	14,503	
4e.4.8	DOC Staff Cost	-	-	-	-	-	-	3,916	587	4,503	4,503	-	-	-	-	-	-	-	-	-	58,817	
4e.4.9	Utility Staff Cost	-	-	-	-	-	-	3,895	584	4,480	4,480	-	-	-	-	-	-	-	-	-	74,529	
4e.4	Subtotal Period 4e Period-Dependent Costs	-	723	5	2	-	22	8,804	1,490	11,046	11,046	-	-	-	312	-	-	-	6,260	77	147,849	
4e.0	TOTAL PERIOD 4e COST	-	723	5	2	-	22	14,665	3,110	18,526	18,526	-	-	-	312	-	-	-	6,260	149,677	147,849	
PERIOD 4 TOTALS		2,927	35,978	8,293	4,221	24,219	36,232	113,683	45,530	271,083	267,075	-	4,009	244,709	71,732	3,389	845	559	18,337,480	910,630	1,892,288	

Table D  
Wolf Creek Generating Station  
SAFSTOR Decommissioning Cost Estimate  
(Thousands of 2005 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Costs	Total Contingency	Total Costs	NRC Lic. Term. Costs	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Burial Volumes				Burial / Processed Wt., Lbs.	Craft Manhours	Utility and Contractor Manhours
															Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTCC Cu. Feet			
PERIOD 5b - Site Restoration																					
Period 5b Direct Decommissioning Activities																					
Demolition of Remaining Site Buildings																					
5b.1.1.1	Reactor	-	2,889	-	-	-	-	-	433	3,322	-	-	3,322	-	-	-	-	-	-	63,255	-
5b.1.1.2	Access Vaults	-	10	-	-	-	-	-	1	11	-	-	11	-	-	-	-	-	-	250	-
5b.1.1.3	Administration	-	130	-	-	-	-	-	20	150	-	-	150	-	-	-	-	-	-	4,467	-
5b.1.1.4	Auxiliary	-	2,418	-	-	-	-	-	363	2,781	-	-	2,781	-	-	-	-	-	-	59,266	-
5b.1.1.5	Auxiliary Boiler	-	18	-	-	-	-	-	3	20	-	-	20	-	-	-	-	-	-	619	-
5b.1.1.6	Chlorine Storage	-	11	-	-	-	-	-	2	12	-	-	12	-	-	-	-	-	-	332	-
5b.1.1.7	Circ Water Pump Enclosure	-	3	-	-	-	-	-	0	4	-	-	4	-	-	-	-	-	-	164	-
5b.1.1.8	Circ Water Travel Screen Enclosure	-	3	-	-	-	-	-	0	3	-	-	3	-	-	-	-	-	-	160	-
5b.1.1.9	Circulating Water Discharge Structure	-	91	-	-	-	-	-	14	105	-	-	105	-	-	-	-	-	-	2,373	-
5b.1.1.10	Circulating Water Intake & Screenhouse	-	90	-	-	-	-	-	13	103	-	-	103	-	-	-	-	-	-	2,059	-
5b.1.1.11	Communication Corridor - Clean	-	805	-	-	-	-	-	121	925	-	-	925	-	-	-	-	-	-	21,919	-
5b.1.1.12	Communication Corridor - Contaminated	-	31	-	-	-	-	-	5	36	-	-	36	-	-	-	-	-	-	674	-
5b.1.1.13	Covered Walkways	-	7	-	-	-	-	-	1	8	-	-	8	-	-	-	-	-	-	272	-
5b.1.1.14	Diesel Generator	-	290	-	-	-	-	-	43	333	-	-	333	-	-	-	-	-	-	6,314	-
5b.1.1.15	E.S.W.S. Pumphouse	-	149	-	-	-	-	-	22	171	-	-	171	-	-	-	-	-	-	3,019	-
5b.1.1.16	ESWS Valve House	-	8	-	-	-	-	-	1	9	-	-	9	-	-	-	-	-	-	243	-
5b.1.1.17	GOB - Administration Building	-	173	-	-	-	-	-	26	199	-	-	199	-	-	-	-	-	-	5,819	-
5b.1.1.18	Hot Machine Shop	-	11	-	-	-	-	-	2	13	-	-	13	-	-	-	-	-	-	417	-
5b.1.1.19	M.M.O. Building	-	165	-	-	-	-	-	25	190	-	-	190	-	-	-	-	-	-	3,483	-
5b.1.1.20	Material Center West	-	66	-	-	-	-	-	10	76	-	-	76	-	-	-	-	-	-	2,512	-
5b.1.1.21	Misc Structures and Additions	-	48	-	-	-	-	-	7	55	-	-	55	-	-	-	-	-	-	1,523	-
5b.1.1.22	Miscellaneous Site Foundations	-	241	-	-	-	-	-	36	277	-	-	277	-	-	-	-	-	-	7,265	-
5b.1.1.23	Miscellaneous Site Structures	-	949	-	-	-	-	-	142	1,091	-	-	1,091	-	-	-	-	-	-	20,254	-
5b.1.1.24	New Covered Walkway	-	5	-	-	-	-	-	1	6	-	-	6	-	-	-	-	-	-	160	-
5b.1.1.25	Oil Separator and Waste Tank	-	2	-	-	-	-	-	0	2	-	-	2	-	-	-	-	-	-	48	-
5b.1.1.26	Radwaste	-	1,065	-	-	-	-	-	160	1,224	-	-	1,224	-	-	-	-	-	-	24,859	-
5b.1.1.27	Radwaste Drum Storage	-	138	-	-	-	-	-	21	159	-	-	159	-	-	-	-	-	-	3,840	-
5b.1.1.28	Radwaste Storage Building	-	65	-	-	-	-	-	10	75	-	-	75	-	-	-	-	-	-	2,323	-
5b.1.1.29	Security Additions - Main Gate North	-	69	-	-	-	-	-	10	80	-	-	80	-	-	-	-	-	-	2,248	-
5b.1.1.30	Security/Guardhouse	-	29	-	-	-	-	-	4	33	-	-	33	-	-	-	-	-	-	845	-
5b.1.1.31	Site Diesel Generator	-	2	-	-	-	-	-	0	3	-	-	3	-	-	-	-	-	-	61	-
5b.1.1.32	Support Complex	-	19	-	-	-	-	-	3	22	-	-	22	-	-	-	-	-	-	697	-
5b.1.1.33	Turbine Building	-	2,578	-	-	-	-	-	387	2,965	-	-	2,965	-	-	-	-	-	-	89,690	-
5b.1.1.34	Turbine Pedestal	-	605	-	-	-	-	-	91	695	-	-	695	-	-	-	-	-	-	10,928	-
5b.1.1.35	Waste Water Treatment	-	12	-	-	-	-	-	2	14	-	-	14	-	-	-	-	-	-	407	-
5b.1.1.36	Fuel Building	-	1,193	-	-	-	-	-	179	1,372	-	-	1,372	-	-	-	-	-	-	24,799	-
5b.1.1	Totals	-	14,387	-	-	-	-	-	2,158	16,545	-	-	16,545	-	-	-	-	-	-	367,560	-
Site Closeout Activities																					
5b.1.2	Remove Rubble	-	9,481	-	-	-	-	-	1,422	10,903	-	-	10,903	-	-	-	-	-	-	14,614	-
5b.1.3	Grade & landscape site	-	1,684	-	-	-	-	-	253	1,937	-	-	1,937	-	-	-	-	-	-	5,050	-
5b.1.4	Final report to NRC	-	-	-	-	-	-	148	22	171	171	-	-	-	-	-	-	-	-	-	1,560
5b.1	Subtotal Period 5b Activity Costs	-	25,552	-	-	-	-	148	3,855	29,555	171	-	29,385	-	-	-	-	-	-	387,224	1,560
Period 5b Additional Costs																					
5b.2.1	Circulating Water Intake Cofferdam	-	192	-	-	-	-	-	29	221	-	-	221	-	-	-	-	-	-	2,540	-
5b.2.2	E.S.W.S. Pumphouse Cofferdam	-	256	-	-	-	-	-	38	295	-	-	295	-	-	-	-	-	-	3,386	-
5b.2.3	Concrete Crushing	-	611	-	-	-	-	6	92	709	-	-	709	-	-	-	-	-	-	4,294	-
5b.2	Subtotal Period 5b Additional Costs	-	1,059	-	-	-	-	6	160	1,225	-	-	1,225	-	-	-	-	-	-	10,220	-
Period 5b Collateral Costs																					
5b.3.1	Small tool allowance	-	135	-	-	-	-	-	20	156	-	-	156	-	-	-	-	-	-	-	-
5b.3	Subtotal Period 5b Collateral Costs	-	135	-	-	-	-	-	20	156	-	-	156	-	-	-	-	-	-	-	-

Table D  
Wolf Creek Generating Station  
SAFSTOR Decommissioning Cost Estimate  
(Thousands of 2005 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Costs	Total Contingency	Total Costs	NRC Lic. Term. Costs	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Burial Volumes				Burial / Processed Wt., Lbs.	Craft Manhours	Utility and Contractor Manhours
															Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTCC Cu. Feet			
Period 5b Period-Dependent Costs																					
5b.4.1	Insurance	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
5b.4.2	Property taxes	-	-	-	-	-	-	182	18	200	-	-	200	-	-	-	-	-	-	-	-
5b.4.3	Heavy equipment rental	-	3,356	-	-	-	-	-	503	3,860	-	-	3,860	-	-	-	-	-	-	-	-
5b.4.4	Plant energy budget	-	-	-	-	-	-	202	30	232	-	-	232	-	-	-	-	-	-	-	-
5b.4.5	Security Staff Cost	-	-	-	-	-	-	840	126	966	-	-	966	-	-	-	-	-	-	-	27,926
5b.4.6	DOC Staff Cost	-	-	-	-	-	-	8,041	1,206	9,247	-	-	9,247	-	-	-	-	-	-	-	122,563
5b.4.7	Utility Staff Cost	-	-	-	-	-	-	4,185	628	4,813	-	-	4,813	-	-	-	-	-	-	-	79,123
5b.4	Subtotal Period 5b Period-Dependent Costs	-	3,356	-	-	-	-	13,450	2,512	19,318	-	-	19,318	-	-	-	-	-	-	-	229,611
5b.0	TOTAL PERIOD 5b COST	-	30,103	-	-	-	-	13,604	6,547	50,254	171	-	50,084	-	-	-	-	-	-	397,444	231,171
PERIOD 5 TOTALS		-	30,103	-	-	-	-	13,604	6,547	50,254	171	-	50,084	-	-	-	-	-	-	397,444	231,171
TOTAL COST TO DECOMMISSION		7,266	72,827	8,741	4,779	24,285	39,601	409,434	96,541	663,474	559,577	48,599	55,297	246,074	94,820	5,662	845	559	19,178,390	1,396,303	5,844,080

TOTAL COST TO DECOMMISSION WITH 17.03% CONTINGENCY:	\$663,474	thousands of 2005 dollars
TOTAL NRC LICENSE TERMINATION COST IS 84.34% OR:	\$559,577	thousands of 2005 dollars
SPENT FUEL MANAGEMENT COST IS 7.32% OR:	\$48,599	thousands of 2005 dollars
NON-NUCLEAR DEMOLITION COST IS 8.33% OR:	\$55,297	thousands of 2005 dollars
TOTAL LOW-LEVEL RADIOACTIVE WASTE BURIED (EXCLUDING GTCC):	101,327	cubic feet
TOTAL GREATER THAN CLASS C RADWASTE VOLUME GENERATED:	559	cubic feet
TOTAL SCRAP METAL REMOVED:	67,355	tons
TOTAL CRAFT LABOR REQUIREMENTS:	1,396,303	man-hours

End Notes:  
n/a - indicates that this activity not charged as decommissioning expense.  
a - indicates that this activity performed by decommissioning staff.  
0 - indicates that this value is less than 0.5 but is non-zero.  
a cell containing " - " indicates a zero value