

**Wolf Creek Generating Station
Decommissioning Cost Estimate
Update for September 1, 1996**

FILED

SEP - 3 1996

MISSOURI
PUBLIC SERVICE COMMISSION

**Jointly Prepared By
Wolf Creek Nuclear Operating Corporation
and Union Electric Company**

Table Of Contents

| <u>Section</u> | <u>Description</u> | <u>Page</u> |
|----------------|---|-------------|
| 1 | Executive Summary | 2 |
| 2 | Regulatory Requirements | 3 |
| 2.1 | U. S. Nuclear Regulatory Commission | |
| 2.2 | U. S. Department of Energy | |
| 3 | Physical Description | 4 |
| 3.1 | Site Description | |
| 3.2 | Plant Description | |
| 4 | Decommissioning Activities Description | 5 |
| 4.1 | DECON Option | |
| 4.2 | SAFSTOR Option | |
| 4.3 | ENTOMB Option | |
| 5 | 1993 Cost Estimate Methodology | 7 |
| 5.1 | Unit Cost Factors | |
| 5.2 | Schedule | |
| 6 | 1996 Cost Estimate Methodology | 8 |
| 6.1 | Inventory | |
| 6.2 | Escalation | |
| 6.3 | Other Changes | |
| 6.4 | Risk Assessment | |
| 7 | Description of Appendices Showing Results | 11 |
| 8 | References | 12 |

Appendices

| | | |
|---|--|--------|
| A | Line Item Report - DECON | 6 pp |
| B | Line Item Report - SAFSTOR | 7 pp |
| C | Line Item Report - ENTOMB | 8 pp |
| D | Input Variables and Ranges | 5 pp |
| E | "Decommissioning Cost Study for the Wolf Creek Generating Station," August 1993, by TLG Engineering, Inc. | 109 pp |

1 Executive Summary

The cost estimate to decommission Wolf Creek Generating Station is \$408,887,000 in 1996 dollars. Three decommissioning options were examined: DECON, SAFSTOR and ENTOMB. The least expensive alternative is DECON, which assumes decontaminating and decommissioning (D&D) immediately following the conclusion of power operations in 2025, when the operating license expires. For immediate D&D, work is anticipated to be completed by 2033.

This decommissioning cost estimate is based on a 1993 site specific study performed by TLG Engineering, Inc. (TLG) which estimated a decommissioning cost of \$369,790,000 in 1993 dollars. The Kansas Corporation Commission approved the 1993 TLG study on June 9, 1994, in its Order Accepting Stipulation and Agreement in Docket No. 188,904-U. The Missouri Public Service Commission approved the same study on June 14, 1994, in its Order Approving Cost Estimates and Funding Levels for Nuclear Decommissioning Costs in Case No. EO-94-80. A copy of the 1993 TLG study is attached as Appendix E to this report.

This update uses the same assumptions regarding decommissioning requirements, techniques, and cost estimate methodology (except with regard to certain work efficiency assumptions) as the earlier study, but takes into account physical changes made to the plant since 1993 as well as inflation. It also includes a risk assessment of the impact of input variability on total cost.

This cost estimate is based on current requirements and present day technology. Wolf Creek Nuclear Operating Corporation (WCNOC) and Union Electric Company follow technology and cost trends at plants being decommissioned, and believe the technologies assumed by TLG in 1993 remain current, in that there have been no significant advances in decommissioning related technologies during the past three years.

In addition to the removal of radioactive material, this study also assumes demolition of the remaining structures from the power plant site, thereby permitting return of the site for other use. This study is based on current Owner needs and assessment regarding potential future use of the Wolf Creek Generating Station site, and assumes the site will ultimately be released for unrestricted use following decommissioning. Future changes in site cleanup and restoration standards or company needs for use of the site may change this assumption. Future cost updates will re-evaluate the assumption of release of the site for unrestricted use.

2 Regulatory Requirements

2.1 U. S. Nuclear Regulatory Commission

The NRC provides decommissioning guidance in the rule "General Requirements for Decommissioning Nuclear Facilities" (10 CFR Parts 30, 40, 50, 51, 70, and 72). This rule defines three decommissioning alternatives acceptable to NRC: one immediate option (DECON) and two delayed options (SAFSTOR and ENTOMB). These are discussed in Section 4.

2.2 U. S. Department of Energy

This study assumes spent fuel generated over the operating life of the reactor is removed from the site five years following plant shutdown. This requirement to keep fuel on site for at least five years is established by the U. S. Department of Energy (DOE) to allow adequate cooling prior to their acceptance.

The cost for disposal of spent fuel is not included in this estimate, as fuel disposal cost is funded by DOE's 1 mill/kWh surcharge. However, the study does consider the constraints the presence of spent fuel on site may impose on other decommissioning activities.

3 Physical Description

3.1 Site Description

Wolf Creek Generating Station is owned by Kansas Gas and Electric Company, Kansas City Power & Light Company, and Kansas Electric Power Cooperative, Inc. (the Owners), and is located approximately 3.5 miles northeast of Burlington in Coffey County, Kansas, about 75 miles southwest of Kansas City, Kansas. The power plant site is on the east side of a man-made lake formed by impounding Wolf Creek.

3.2 Plant Description

Wolf Creek Generating Station utilizes a pressurized water reactor (PWR) with facilities necessary to support a nominal 1150 MW(e) nuclear power plant. It was designed by Bechtel Power Corporation and constructed by Daniel International Corporation under the SNUPPS (Standardized Nuclear Unit Power Plant System) program along with its sister unit Callaway Plant located in Missouri, and owned by Union Electric Company.

The Westinghouse Nuclear Steam Supply System (NSSS) consists of a PWR with four reactor coolant loops, each with a pump and steam generator. An electrically heated pressurizer and connecting piping completes the NSSS, all of which is housed within a carbon steel lined concrete containment structure.

Heat produced in the reactor is converted to electrical energy by the power conversion system. The turbine-generator is a General Electric 1800 RPM unit, consisting of one high pressure and three low pressure turbine elements driving a directly coupled generator. Heat rejected in the main condensers is removed by the circulating water system. Cooling for the condenser circulating water system is supplied by Wolf Creek Lake, with makeup water drawn from the Neosho River two miles west of the Lake.

4 Decommissioning Activities Description

Although the three options of DECON, SAFSTOR, and ENTOMB differ with respect to process, cost, and schedule, they attain the same result: removal of all radioactive materials from the site allowing its release for unrestricted alternative use.

For all three options addressed in this study, the site is cleared of all above-grade structures and site improvements (excluding the Switchyard, Sewage Treatment Pond, Main Dam, Lake, and facilities west of the Lake — the Learning Center, Make-up Water Screenhouse, Make-Up Water Discharge and Lake Access Facility), and the land returned to a state consistent with adjacent areas. The following sections describe the basic activities necessary for each option.

4.1 DECON Option

DECON consists of removal of fuel assemblies, source material, radioactive fission and corrosion products, and other radioactive materials immediately after cessation of power operations. The advantages of the DECON option are: less cost in current dollars than either of the two delayed options, avoidance of long-term maintenance and security of the site, and the fact that decommissioning can be performed by individuals familiar with the facility.

There are three periods associated with the DECON option:

- Period 1, Decommissioning Preparation: This includes engineering planning, writing specifications and procedures, characterizing the site radioactivity, and assembling a decommissioning management organization. The Owners will file an application for NRC license termination accompanied by a Decommissioning Plan (DP) describing the removal of radioactive components and material from Wolf Creek Generating Station.
- Period 2, Decommissioning Operations and License Termination: Dismantling may begin on receipt of a decommissioning order from NRC. This period consists of decontaminating, removing, packaging, shipping, and burying components, systems, and structures which are radioactively contaminated.
- Period 3, Site Restoration: Following NRC license termination, demolition of the remaining portions of the containment structure and interior portions of the reactor building takes place. The auxiliary, control, diesel generator, turbine and other site structures are demolished, and the site is released for unrestricted use.

4.2 SAFSTOR Option

SAFSTOR places the facility in protective storage once spent fuel and source material are removed, followed by radiation surveys, general decontamination, and removal of any remaining radwaste from power operations. Delayed decontamination and dismantling activities are initiated such that license termination is accomplished within the 60 year time period set by NRC. As with DECON, this study further assumes that the remainder of the plant and facilities are demolished and the site is released for unrestricted use.

The cost of SAFSTOR is increased by the cost of maintaining the facility in protective storage; however, SAFSTOR does have advantages over DECON, including: the dormancy period provides a period of decay for residual radioactive material, lowering occupational radiation exposure during dismantling; and potential savings in the cost of disposal for the waste volume generated during decommissioning operations.

4.3 ENTOMB Option

ENTOMB also consists of placing the facility into protective storage. Initial activities include: removing contaminated components, systems, and structures outside the designated entombment boundary, and sealing the remaining radioactivity within the reactor containment building. After dormancy and radiation planning surveys, dismantlement may begin. It consists of removal of the entombment structure and materials within it, processing and disposing of any remaining solid and liquid radioactive wastes, and release of the site for unrestricted use.

5 1993 Cost Estimate Methodology

Decommissioning technology is well established, and the tools and equipment necessary to dismantle Wolf Creek Generating Station completely are available and have been demonstrated. This decommissioning cost study provides an estimate under current requirements based on present day costs and available technology. As additional dismantling experience on large reactors becomes available, cost estimates will be modified to reflect that experience.

5.1 Unit Cost Factors

The original 1993 study (Appendix E to this report) was performed in accordance with the published study from the Atomic Industrial Forum/National Environmental Studies Project report AIF/NESP-036, "Guidelines for Producing Commercial Nuclear Power Plant Decommissioning Cost Estimates". Those guidelines were prepared under review of representatives from utilities, state regulatory commissions, architect/engineering firms, FERC, NRC, and the National Association of Regulatory Utility Commissioners. In this methodology, costs to remove a unit of plant equipment, components, and structures are developed and coupled with the plant specific inventory of equipment, components, and structures.

The 1993 site specific cost estimate was developed using plant drawings and inventory documents to estimate structural and system component quantities, and land area of the site released for unrestricted use. WCNO developed the plant component inventory as well as salary and craft labor rates for site administration, operations, construction and maintenance personnel for positions anticipated for decommissioning.

5.2 Schedule

The schedule for the decommissioning scenarios considered in the 1993 study follows the sequence presented in AIF/NESP-036. Durations were established between several milestones in each period and used to establish a critical path for the entire project. Period dependent costs presented in Appendices A, B, and C are based on durations identified in the schedule for each of the three options.

This study assumes that spent fuel will be stored in the fuel building for five years following final shutdown in 2025, in accordance with DOE requirements. Decommissioning activities in the fuel building would be limited until the final core load could be transferred to DOE for disposal. Decommissioning activities such as vessel segmentation, steam generator removal, reactor and auxiliary building system removal will be concurrent with spent fuel storage and shipment. The fuel building will be used for spent fuel storage until all spent fuel has been removed from the site.

6 1996 Cost Estimate Methodology

This decommissioning cost estimate update is based on the 1993 study performed by TLG for Wolf Creek Generating Station. This update embraces the methodology and key assumptions used in the earlier study, and makes adjustments to produce a current cost estimate. The 1996 update considers escalation and physical plant changes during the last three years, and also addresses ranges of variables.

Union Electric developed a computer model to mimic the results of the 1993 TLG study, using AIF/NESP-036 for technical guidance. The model was set up to handle changes in plant systems and structures inventory, changes in time dependent variables such as wages and service costs, and changes in other variables as appropriate.

6.1 Inventory

The original plant inventory was developed for the "Response to Missouri PSC Stipulation for Data Relevant to Estimating Decommissioning Costs for Callaway Plant and Wolf Creek Generating Station." In that response WCNOG and UE worked together to develop detailed quantities of components, systems, and structures for WCGS and Callaway Plant. Due to the SNUPPS design there were many common areas, and the same quantities were used for both plants. In other areas there were bona fide differences in inventories, and these were also addressed as part of the stipulation response.

Since that time there have been minor changes made to the plant and the site. These physical changes have been reviewed and the plant inventories updated as necessary. These changes are reflected in this 1996 decommissioning cost update, both as costs to actually remove the new items, and as additional overhead costs due to the slight extension of related work durations. The effect of these changes on the overall cost estimate was minimal.

6.2 Escalation

In some cases escalation since the 1993 study can be accurately quantified. Escalation of these variables is based on reliable in-house data, such as the cost of WCNOG labor. This information is readily available from payroll records, and escalation from year to year is a discrete value which may be calculated with confidence.

In other cases the escalation of variables is uncertain, but the nature of the uncertainty can be described with probability distributions. Appendix D shows the ranges used for several such escalation variables. For example, DOC Staff Labor is estimated to have escalated by anywhere from 9.8% to 10.7% between 1993 and 1996. Since WCNOG does not have actual cost data for this hypothetical DOC, data from the U. S. Bureau of Labor Statistics (BLS) were used. The BLS publication "Monthly Labor Review" provides cost indices for a number of occupation descriptions, but Decommissioning

Operations Contractor is not one of them, not surprisingly. However, two of the occupation descriptions closely approximate the function of the DOC, and were used to establish bounds on the range of probable escalation for DOC Staff Labor between 1993 and 1996.

The 1993 study was based on input data as of mid-year 1993 (except for certain WCNO wage data from late 1992). This 1996 update is for mid-year 1996, and input data are typically for the end of June.

6.3 Other Changes

This 1996 decommissioning cost update considers ranges of input variables, recognizing that there is a degree of uncertainty regarding the input. In order to minimize excessive conservatism the estimate used for decommissioning funding purposes is based on data in the middle of an expected range. The 1993 study conservatively used the high end of the range for work efficiency factors. This update uses mid-range values as the basis for the funding amount, but analyzes the effect of maximum and minimum input values on the bottom line cost estimate. The range of work efficiency factors used in this study are listed in Appendix D. Use of these improved worker efficiency factors reduces not only actual removal costs, but also overhead costs by shortening the project duration about five months. The decrease in respirator usage under the new 10CFR20 further validates the use of the improved respiratory protection adjustment to worker efficiency.

6.4 Risk Assessment

By using ranges of escalation for some input variables instead of estimated discrete values, WCNO and Union Electric were able to determine the distribution range of the overall decommissioning cost, including a minimum and maximum value. This approach allows enhanced confidence in the resulting bottom line total cost estimate.

In cases where the values of input variables are uncertain, the nature of their uncertainty can be described with probability distributions which give both the range of values the variable could take and the likelihood of occurrence of each value within the range. The risk assessment calculates a probability distribution of the decommissioning cost estimates, based on the uncertainty of the input variables. Two simple probability distributions used in this analysis:

- A uniform distribution specifies a probability between minimum and maximum values, where every value across the range has an equal likelihood of occurrence. This is used when only a range is known. It is the typical distribution assumed for cases where more than one BLS line item reasonably describes a decommissioning line item, such as DOC Staff Labor.
- A triangular distribution specifies a probability between minimum and maximum values, but there is a skew set by the most likely value. The probability of occurrence of the minimum and maximum values is zero. This is used for rough modeling when actual data are absent, as in the case of Radwaste Burial. In this case

we have reasonable minimum and maximum values based on one source, but other sources indicate a most likely value within that range. In this and other triangular distributions, the most likely value used in this study is the average of the minimum and maximum.

In all cases the output cost shown in Appendices A, B and C is the mean average value of the range. Ranges used for escalation and other variables are listed in Appendix D.

The resulting distribution of the total 1996 decommissioning cost estimate is a typical bell shaped curve, with a minimum, a maximum, and a most likely value. Out of consideration for intergenerational equity, WCNOG has based this cost estimate on the most likely value, since there is an equal probability that the actual cost will be higher or lower. The most likely values are shown in Appendices A, B and C.

7 Description of Appendices Showing Results

Appendix A addresses the decommissioning cost estimate under the DECON option. Appendices B and C address the decommissioning cost estimate under the SAFSTOR and ENTOMB options, respectively. Appendices A, B, and C list costs for specific line items, grouped by Period Total Costs, Activity Costs, Undistributed Costs, and Staff Costs as described below:

- Period Total Costs: Subtotals are provided for each of the periods in DECON, SAFSTOR, and ENTOMB.
- Activity Costs: These costs are associated with the physical labor of dismantling and disposing of the plant, and are dependent upon plant inventory. They typically include the cost to decontaminate, remove, pack, ship, and bury plant components, systems, and structures.
- Undistributed Costs: These are essentially overhead costs, and are dependent on project duration. They consist primarily of insurance, taxes, and energy.
- Staff Costs: These are the balance of overhead costs, and are also dependent on project duration. There are utility staff costs and contractor staff costs. Utility costs are for site security, health physics, quality assurance, and overall site administration during decommissioning and demolition. A Decommissioning Operations Contractor (DOC) will provide sufficient staff to plan and schedule preparatory demolition, and manage the demolition efforts. Demolition is performed by the DOC, or a demolition subcontractor who will provide adequate staff, labor, equipment, materials and overhead to complete the demolition.

The top of the columns indicate the following activities and categories: Decon, Remove, Pack, Ship, Bury, Other, Total, Contingency (2 columns), and Estimate.

- Decon: The NSSS will be chemically decontaminated prior to segmentation, thereby reducing its radioactive contamination by about 90%. Other systems that are decontaminated include Chemical and Volume Control, Liquid Radwaste, Secondary Liquid Waste, Chemical and Detergent Waste, and Containment Spray. Non-system specific items such as electrical conduit and cable trays may also be decontaminated.
- Remove: Radioactive and non-radioactive systems and components will be removed using a variety of methods including: torch cutting, remote plasma arc cutting, scarifying and scabbling, and controlled blasting. Structures will be removed to three feet below local grade and the terrain restored to the local grade level. The existing electrical switchyard will remain after Wolf Creek Generating Station decommissioning in support of the Owners' electrical transmission and distribution systems.

ALARA ("As Low As Reasonably Achievable") principles impact the removal cost through the use of work duration adjustment factors which include radiological protection instruction, mock-up training, the use of respiratory protection and personnel protective clothing. These items lengthen task duration, increasing cost

and schedule. ALARA planning is considered in the costs for engineering and planning, and in the development of activity specifications and detailed procedures.

- Pack: Cask specifications and U. S. Department of Transportation (DOT) regulations dictate details of segmentation and packaging methodology. Packages meet current physical and radiological limitations and regulations, and shipments are made in DOT approved truck casks. Most of the materials being transported for controlled burial will be categorized as Type A Low Specific Activity (LSA) radwaste. Commercially available steel containers will be used for piping, small components and concrete. Compactible radwaste, such as booties, glove liners, respirator filter cartridges, shipping containers, and HP survey materials are volume reduced and packaged. The steam generators will be removed sequentially and stored on-site in a temporary staging area, where they will be filled with grout prior to loading for shipment.
- Ship: Packaged radwaste will be moved by a combination of overland transporter and rail to a regional burial facility to be located within 700 miles of the plant site.
- Bury: The low level radwaste generated in decommissioning Wolf Creek Generating Station will be shipped to the future Central Interstate Regional Compact burial facility. The cost for disposal in that facility is based on information from currently operating facilities and projections for compact costs. The highly activated sections of the reactor vessel internals will be Greater Than Class C (GTCC), as defined in 10CFR61. This waste most likely will be disposed as high level waste in DOE's repository unless an alternative solution is approved by NRC. The cost of GTCC disposal, unlike that for the spent fuel, is not covered by DOE's 1 mill/kWh surcharge, and is estimated from spent fuel equivalent disposal costs.
- Other: This consists primarily of undistributed and staff costs.
- Total: This is the sum of Decon, Remove, Pack, Ship, Bury, and Other.
- Contingency: There are two columns for contingency: one as a per cent of the line item under Total, and one as the dollar value of contingency for that line item. Contingency is defined as a specific provision for unforeseeable elements of cost within the defined project scope. This is particularly important where previous experiences relating estimates and actual costs have shown that unforeseeable events which will increase costs are likely to occur. The cost elements in this estimate are based on ideal conditions, therefore contingency factors have been applied. Contingency is assigned on a line item basis for this estimate.
- Estimate: This is the sum of Total and Contingency.

8 References

1. T. S. LaGuardia et al., "Guidelines for Producing Commercial Nuclear Power Plant Decommissioning Cost Estimates", AIF/NESP-036, May 1986.
2. UE and Kansas City Power & Light Company, "Response to Missouri PSC Stipulation for Data Relevant to Estimating Decommissioning Costs for Callaway Plant and Wolf Creek Generating Station", February 1993 and "Data Unique to Wolf Creek Generating Station", February 1993.

APPENDIX A

DECOMMISSIONING COST ESTIMATE UPDATE — LINE ITEM REPORT

Wolf Creek Generating Station 1996 DECON Option (Immediate)

| Cost (\$Thousands) | Activity: | Decon | Remove | Pack | Ship | Bury | Other | Total | Contingency | Estimate | |
|--|---|-------|--------|-------|------|---------|----------|----------|-------------|----------|----------|
| Period 1: Activity Costs | | | | | | | \$2 854 | \$2 854 | 15% | \$428 | \$3 282 |
| | Prepare prelim decommissioning plan | | | | | | 143 | 143 | 15% | 21 | 165 |
| | Prepare proposed decommissioning plan | | | | | | 440 | 440 | 15% | 66 | 506 |
| | Review plant drawings and specs | | | | | | 506 | 506 | 15% | 76 | 582 |
| | Estimate by-product inventory | | | | | | 110 | 110 | 15% | 17 | 127 |
| | Submit for license amendment | | | | | | 176 | 176 | 15% | 26 | 203 |
| | End product description | | | | | | 110 | 110 | 15% | 17 | 127 |
| | Detailed by-product inventory | | | | | | 143 | 143 | 15% | 21 | 165 |
| | Define major work sequence | | | | | | 826 | 826 | 15% | 124 | 950 |
| | Perform safety analysis | | | | | | 341 | 341 | 15% | 51 | 393 |
| | Submit dismantling plan | | | | | | 57 | 57 | 15% | 9 | 66 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 1: Undistributed Costs | | \$73 | | \$253 | \$54 | \$1 058 | \$8 310 | \$9 748 | 15% | \$1 461 | \$11 209 |
| a | Decon equipment | | | | | | 206 | 206 | 15% | 31 | 237 |
| b | Decon supplies | | | | | | 149 | 149 | 25% | 37 | 187 |
| c | DOC staff relocation expenses | | | | | | 898 | 898 | 15% | 135 | 1 033 |
| d | Process liquid waste | 73 | | 37 | 47 | 220 | | 378 | 21% | 80 | 458 |
| e | Insurance | | | | | | 597 | 597 | 10% | 60 | 657 |
| f | Property taxes | | | | | | 1 616 | 1 616 | 10% | 162 | 1 777 |
| g | Health physics supplies | | | | | | 1 033 | 1 033 | 25% | 258 | 1 291 |
| h | Heavy equipment rental | | | | | | 113 | 113 | 15% | 17 | 130 |
| i | Disposal of DAW generated | | | 216 | 6 | 838 | | 1 060 | 14% | 148 | 1 209 |
| j | Plant energy budget | | | | | | 3 264 | 3 264 | 15% | 490 | 3 754 |
| k | NRC fees | | | | | | 122 | 122 | 10% | 12 | 134 |
| l | Emergency planning fees | | | | | | 311 | 311 | 10% | 31 | 342 |
| | Contingencies for a, c, d, h, i, j (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| | Contingencies for b, g | 50% | 15% | 10% | 15% | 15% | 25% | | | | |
| | Contingencies for e, f, k, l | 50% | 15% | 10% | 15% | 15% | 10% | | | | |
| Period 1: Staff Costs | | | | | | | \$39 403 | \$39 403 | 15% | \$5 910 | \$45 313 |
| | DOC staff cost | | | | | | 5 079 | 5 079 | 15% | 762 | 5 841 |
| | Utility staff cost | | | | | | 34 324 | 34 324 | 15% | 5 149 | 39 472 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 1: Total Costs | | \$73 | | \$253 | \$54 | \$1 058 | \$50 567 | \$52 005 | 15% | \$7 800 | \$59 804 |
| Period 2: Activity Specifications | | | | | | | \$4 110 | \$4 110 | 15% | \$617 | \$4 727 |
| | Plant & temporary facilities | | | | | | 542 | 542 | 15% | 81 | 623 |
| | Plant systems | | | | | | 459 | 459 | 15% | 69 | 528 |
| | Reactor internals | | | | | | 782 | 782 | 15% | 117 | 899 |
| | Reactor vessel | | | | | | 716 | 716 | 15% | 107 | 823 |
| | Biological shield | | | | | | 55 | 55 | 15% | 8 | 63 |
| | Steam generators | | | | | | 344 | 344 | 15% | 52 | 395 |
| | Reinforced concrete | | | | | | 176 | 176 | 15% | 26 | 203 |
| | Turbines & condensers | | | | | | 88 | 88 | 15% | 13 | 101 |
| | Plant structures & buildings | | | | | | 344 | 344 | 15% | 52 | 395 |
| | Waste management | | | | | | 506 | 506 | 15% | 76 | 582 |
| | Facility & site closeout | | | | | | 99 | 99 | 15% | 15 | 114 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 2: Planning & Site Preparations | | | | | | | \$3 573 | \$3 573 | 15% | \$536 | \$4 109 |
| | Prepare dismantling sequence | | | | | | 264 | 264 | 15% | 40 | 304 |
| | Plant preparation & temporary services | | | | | | 1 635 | 1 635 | 15% | 245 | 1 880 |
| | Design water clean-up system | | | | | | 154 | 154 | 15% | 23 | 177 |
| | Rigging/CCES/tooling/etc. | | | | | | 1 384 | 1 384 | 15% | 208 | 1 592 |
| | Procure casks/liners & containers | | | | | | 135 | 135 | 15% | 20 | 156 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |

DECOMMISSIONING COST ESTIMATE UPDATE — LINE ITEM REPORT

Wolf Creek Generating Station 1996 DECON Option (Immediate)

| Cost (\$Thousands) | Activity: | Decon | Remove | Pack | Ship | Bury | Other | Total | Contingency | Estimate | |
|---|--|---------|----------|---------|---------|----------|----------|----------|-------------|----------|----------|
| Period 2: Detailed Work Procedures | | | | | | | \$3 825 | \$3 825 | 15% | \$574 | \$4 399 |
| | Plant systems | | | | | | 521 | 521 | 15% | 78 | 599 |
| | Vessel head | | | | | | 275 | 275 | 15% | 41 | 317 |
| | Reactor internals | | | | | | 275 | 275 | 15% | 41 | 317 |
| | Remaining buildings | | | | | | 149 | 149 | 15% | 22 | 171 |
| | CRD cooling assembly | | | | | | 110 | 110 | 15% | 17 | 127 |
| | CRD housings & ICI tubes | | | | | | 110 | 110 | 15% | 17 | 127 |
| | Incore instrumentation | | | | | | 110 | 110 | 15% | 17 | 127 |
| | Reactor vessel | | | | | | 400 | 400 | 15% | 60 | 460 |
| | Facility closeout | | | | | | 132 | 132 | 15% | 20 | 152 |
| | Missile shields | | | | | | 50 | 50 | 15% | 7 | 57 |
| | Biological shield | | | | | | 132 | 132 | 15% | 20 | 152 |
| | Steam generators | | | | | | 506 | 506 | 15% | 76 | 582 |
| | Reinforced concrete | | | | | | 110 | 110 | 15% | 17 | 127 |
| | Turbines & condensers | | | | | | 344 | 344 | 15% | 52 | 395 |
| | Auxiliary building | | | | | | 301 | 301 | 15% | 45 | 346 |
| | Reactor building | | | | | | 301 | 301 | 15% | 45 | 346 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 2: Decon NSSS/Rack Removal | | \$735 | \$35 | \$87 | \$23 | \$1 039 | \$1 260 | \$3 179 | 23% | \$733 | \$3 913 |
| | Decon primary loop | 504 | | | | | | 504 | 50% | 252 | 757 |
| | Remove spent fuel racks | 231 | 35 | 87 | 23 | 1 039 | 1 260 | 2 675 | 18% | 481 | 3 156 |
| | Contingencies | 50% | 25% | 10% | 15% | 15% | 15% | | | | |
| Period 2: NSSS Removal | | \$519 | \$6 405 | \$865 | \$4 280 | \$38 945 | | \$51 013 | 21% | \$10 523 | \$61 536 |
| | Reactor vessel | 113 | 2 824 | 290 | 263 | 3 310 | | 6 799 | 41% | 2 809 | 9 608 |
| | Reactor vessel internals | 49 | 1 070 | 294 | 316 | 7 515 | | 9 245 | 23% | 2 107 | 11 352 |
| | Steam generators | 151 | 2 246 | 145 | 3 613 | 19 725 | | 25 880 | 16% | 4 152 | 30 032 |
| | Reactor coolant piping | 73 | 115 | 68 | 19 | 2 273 | | 2 548 | 16% | 416 | 2 963 |
| | Reactor coolant pumps & motors | 28 | 35 | 36 | 41 | 3 840 | | 3 980 | 15% | 609 | 4 589 |
| | Pressurizer | 27 | 24 | 4 | 10 | 1 408 | | 1 473 | 16% | 233 | 1 706 |
| | Pressurizer relief tank | 13 | 55 | 6 | 4 | 217 | | 295 | 18% | 54 | 349 |
| | CRDMs/ICIs/service structure removal | 65 | 36 | 22 | 15 | 656 | | 793 | 18% | 144 | 938 |
| | Contingencies for Reactor Vessel and Internals | 50% | 75% | 25% | 25% | 15% | 15% | | | | |
| | Contingencies for Others | 50% | 25% | 10% | 15% | 15% | 15% | | | | |
| Period 2: Disposal of Plant Systems | | \$1 351 | \$11 632 | \$2 507 | \$557 | \$20 233 | \$13 847 | \$50 128 | 17% | \$8 485 | \$58 613 |
| CP/WCGS Contam Components (System Specific) | | \$1 196 | \$5 510 | \$2 181 | \$459 | \$17 877 | \$11 068 | \$38 291 | 17% | \$6 604 | \$44 895 |
| | BB - Reactor Coolant (partial) | | 107 | 70 | 16 | 810 | 348 | 1 352 | 16% | 210 | 1 562 |
| | BG - Chemical & Volume Control | 386 | 471 | 189 | 48 | 2 362 | 966 | 4 423 | 19% | 836 | 5 259 |
| | BL - Reactor Makeup Water | | 140 | 34 | 9 | 244 | 238 | 665 | 17% | 112 | 777 |
| | BM - Steam Generator Blowdown | | 316 | 113 | 30 | 1 107 | 740 | 2 306 | 16% | 372 | 2 678 |
| | BN - Borated Refueling Water Storage | | 149 | 61 | 9 | 391 | 459 | 1 069 | 16% | 172 | 1 241 |
| | EC - Fuel Pool Cooling & Cleanup | | 229 | 78 | 18 | 714 | 518 | 1 558 | 16% | 253 | 1 810 |
| | EJ - Residual Heat Removal | | 204 | 84 | 18 | 881 | 489 | 1 676 | 16% | 268 | 1 944 |
| | EM - High Pressure Coolant Injection | | 161 | 62 | 17 | 570 | 413 | 1 224 | 16% | 197 | 1 420 |
| | EP - Accumulator Safety Injection | | 82 | 30 | 6 | 209 | 208 | 535 | 16% | 87 | 622 |
| | GG - Fuel Building HVAC | | 148 | 49 | 11 | 570 | 213 | 990 | 16% | 161 | 1 151 |
| | GH - Radwaste Building HVAC | | 103 | 30 | 7 | 322 | 151 | 613 | 16% | 101 | 714 |
| | GL - Auxiliary Building HVAC | | 268 | 50 | 12 | 319 | 367 | 1 017 | 17% | 177 | 1 193 |
| | GN - Containment Cooling | | 311 | 114 | 23 | 1 230 | 540 | 2 217 | 16% | 358 | 2 575 |
| | GR - Containment Atmospheric Control | | 6 | 25 | 4 | 414 | 33 | 482 | 15% | 72 | 554 |
| | GS - Containment Hydrogen Control | | 26 | 21 | 5 | 163 | 147 | 362 | 15% | 56 | 418 |
| | GT - Containment Purge HVAC | | 69 | 35 | 5 | 356 | 190 | 656 | 16% | 103 | 759 |
| | HA - Gaseous Radwaste | | 152 | 77 | 15 | 563 | 273 | 1 080 | 16% | 173 | 1 253 |
| | HB - Liquid Radwaste | 419 | 410 | 142 | 28 | 905 | 679 | 2 583 | 22% | 568 | 3 151 |
| | HC - Solid Radwaste | | 241 | 226 | 28 | 1 004 | 499 | 1 998 | 16% | 312 | 2 310 |
| | HD - Decontamination | | 40 | 51 | 6 | 147 | 151 | 396 | 15% | 61 | 457 |
| | HE - Boron Recycle | | 253 | 78 | 19 | 481 | 474 | 1 305 | 17% | 217 | 1 523 |
| | HF - Secondary Liquid Waste | 358 | 456 | 209 | 37 | 1 034 | 884 | 2 978 | 20% | 607 | 3 585 |
| | KE - Fuel Handling & Storage, RPV Service | | 6 | 9 | 5 | 292 | | 312 | 15% | 47 | 359 |
| | LD - Chemical & Detergent Waste | 34 | 69 | 21 | 5 | 137 | 147 | 412 | 19% | 80 | 492 |
| | LF - Floor & Equipment Drains | | 1 007 | 228 | 57 | 1 477 | 1 675 | 4 443 | 17% | 756 | 5 198 |
| | RM - Process Sampling & Analysis | | 56 | 45 | 13 | 709 | 215 | 1 038 | 15% | 159 | 1 197 |
| | SJ - Nuclear Sampling | | 31 | 50 | 6 | 466 | 50 | 603 | 15% | 91 | 694 |
| | Contingencies for Contaminated Systems | 50% | 25% | 10% | 15% | 15% | 15% | | | | |

DECOMMISSIONING COST ESTIMATE UPDATE — LINE ITEM REPORT

Wolf Creek Generating Station 1996 DECON Option (Immediate)

| Cost (\$Thousands) | Activity: | Decon | Remove | Pack | Ship | Bury | Other | Total | Contingency | Estimate | |
|--|---|--------------|----------------|--------------|-------------|----------------|----------------|----------------|-------------|--------------|----------------|
| <u>CP/WCGS Contam Comp (Non-Syst Specific)</u> | | | <u>\$672</u> | <u>\$327</u> | <u>\$99</u> | <u>\$2,355</u> | <u>\$2,779</u> | <u>\$6,232</u> | <u>16%</u> | <u>\$986</u> | <u>\$7,218</u> |
| | Auxiliary Building | | 237 | 112 | 35 | 844 | 995 | 2,223 | 16% | 352 | 2,574 |
| | Control Building | | 216 | 115 | 35 | 835 | 985 | 2,187 | 16% | 344 | 2,531 |
| | Fuel Building | | 34 | 16 | 5 | 130 | 153 | 339 | 16% | 53 | 392 |
| | Radwaste Building | | 102 | 50 | 15 | 341 | 403 | 910 | 16% | 144 | 1,054 |
| | Reactor Building | | 83 | 33 | 10 | 205 | 243 | 574 | 16% | 93 | 667 |
| | Contingencies for Contaminated Systems | 50% | 25% | 10% | 15% | 15% | 15% | | | | |
| <u>CP/WCGS Decon-able Comp (Non-Syst Spec)</u> | | <u>\$103</u> | <u>\$383</u> | | | | | <u>\$486</u> | <u>22%</u> | <u>\$109</u> | <u>\$595</u> |
| | Auxiliary Building | 37 | 141 | | | | | 178 | 22% | 40 | 217 |
| | Control Building | 37 | 129 | | | | | 166 | 23% | 38 | 204 |
| | Fuel Building | 4 | 17 | | | | | 21 | 22% | 5 | 26 |
| | Radwaste Building | 13 | 48 | | | | | 61 | 23% | 14 | 75 |
| | Reactor Building | 12 | 48 | | | | | 60 | 22% | 13 | 73 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| <u>CP/WCGS Clean Comp (Non-Syst Specific)</u> | | | <u>\$1,189</u> | | | | | <u>\$1,189</u> | <u>15%</u> | <u>\$178</u> | <u>\$1,367</u> |
| | Auxiliary Building | | 427 | | | | | 427 | 15% | 64 | 491 |
| | Control Building | | 400 | | | | | 400 | 15% | 60 | 460 |
| | Fuel Building | | 55 | | | | | 55 | 15% | 8 | 63 |
| | Radwaste Building | | 163 | | | | | 163 | 15% | 24 | 188 |
| | Reactor Building | | 144 | | | | | 144 | 15% | 22 | 165 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| <u>CP/WCGS Non-Contam Comp (Syst Specific)</u> | | <u>\$52</u> | <u>\$1,766</u> | | | | | <u>\$1,818</u> | <u>16%</u> | <u>\$291</u> | <u>\$2,109</u> |
| | AB - Main Steam | | 148 | | | | | 148 | 15% | 22 | 171 |
| | AC - Main Turbine | | 137 | | | | | 137 | 15% | 21 | 157 |
| | AD - Condensate | | 139 | | | | | 139 | 15% | 21 | 160 |
| | AE - Feedwater | | 94 | | | | | 94 | 15% | 14 | 109 |
| | AF - Feedwater Htr Extraction, Drains, Vents | | 142 | | | | | 142 | 15% | 21 | 163 |
| | AK - Condensate Demineralizer | | 49 | | | | | 49 | 15% | 7 | 56 |
| | AL - Auxiliary Feedwater | | 21 | | | | | 21 | 15% | 3 | 24 |
| | AP - Condensate Storage & Transfer | | 41 | | | | | 41 | 15% | 6 | 47 |
| | AQ - Condensate & Feedwater Chem Addition | | 13 | | | | | 13 | 15% | 2 | 15 |
| | CA - Steam Seal | | 13 | | | | | 13 | 15% | 2 | 15 |
| | CB - Main Turbine Lube Oil | | 28 | | | | | 28 | 15% | 4 | 33 |
| | CC - Generator Hydrogen & CO2 | | 5 | | | | | 5 | 15% | 1 | 6 |
| | CD - Generator Seal Oil | | 7 | | | | | 7 | 15% | 1 | 8 |
| | CE - Stator Cooling Water | | 6 | | | | | 6 | 15% | 1 | 7 |
| | CF - Lube Oil Storage, Transfer, Purification | | 22 | | | | | 22 | 15% | 3 | 25 |
| | CG - Condenser Air Removal | | 16 | | | | | 16 | 15% | 2 | 19 |
| | CH - Main Turbine Control Oil | | 30 | | | | | 30 | 15% | 5 | 35 |
| | EB - Closed Cooling Water | | 34 | | | | | 34 | 15% | 5 | 39 |
| | EG - Component Cooling Water | | 141 | | | | | 141 | 15% | 21 | 162 |
| | EN - Containment Spray | 52 | 42 | | | | | 93 | 34% | 32 | 126 |
| | FA - Auxiliary Steam Generator | | 16 | | | | | 16 | 15% | 2 | 18 |
| | FB - Auxiliary Steam | | 68 | | | | | 68 | 15% | 10 | 78 |
| | FC - Auxiliary Turbines | | 33 | | | | | 33 | 15% | 5 | 38 |
| | FE - Auxiliary Steam Chemical Addition | | 3 | | | | | 3 | 15% | 0 | 3 |
| | GA - Plant Heating | | 73 | | | | | 73 | 15% | 11 | 84 |
| | GB - Central Chilled Water | | 54 | | | | | 54 | 15% | 8 | 62 |
| | GK - Control Building HVAC | | 160 | | | | | 160 | 15% | 24 | 184 |
| | GM - Diesel Generator Building HVAC | | 29 | | | | | 29 | 15% | 4 | 33 |
| | GP - Containment Integrated Leak Rate Test | | 7 | | | | | 7 | 15% | 1 | 8 |
| | JE - Emergency Fuel Oil | | 32 | | | | | 32 | 15% | 5 | 37 |
| | KJ - Standby Diesel Engine | | 106 | | | | | 106 | 15% | 16 | 122 |
| | LB - Roof Drains | | 58 | | | | | 58 | 15% | 9 | 67 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |

DECOMMISSIONING COST ESTIMATE UPDATE — LINE ITEM REPORT

Wolf Creek Generating Station 1996 DECON Option (Immediate)

| Cost (\$Thousands) | Activity: | Decon | Remove | Pack | Ship | Bury | Other | Total | Contingency | Estimate | |
|--|---|---------|---------|-------|------|---------|---------|----------|-------------|----------|----------|
| WCGS Non-Contam Comp (System Specific) | | | \$2 112 | | | | | \$2 112 | 15% | \$317 | \$2 429 |
| | AN - Demineralized Water Storage & Transfe | | 43 | | | | | 43 | 15% | 6 | 50 |
| | AX - Acid Feed | | 22 | | | | | 22 | 15% | 3 | 25 |
| | CL - Chlorination | | 14 | | | | | 14 | 15% | 2 | 17 |
| | CO - Carbon Dioxide | | 4 | | | | | 4 | 15% | 1 | 5 |
| | CW - Circulating Water | | 199 | | | | | 199 | 15% | 30 | 229 |
| | CZ - Caustic Acid | | 3 | | | | | 3 | 15% | 0 | 4 |
| | DA - Circulating Water | | 205 | | | | | 205 | 15% | 31 | 236 |
| | DM - Equipment Drains | | 63 | | | | | 63 | 15% | 9 | 72 |
| | DO - Diesel Oil | | 1 | | | | | 1 | 15% | 0 | 1 |
| | EA - Service Water | | 66 | | | | | 66 | 15% | 10 | 76 |
| | EF - Essential Service Water | | 80 | | | | | 80 | 15% | 12 | 93 |
| | FO - Fuel Oil | | 15 | | | | | 15 | 15% | 2 | 17 |
| | FP - Fire Protection | | 159 | | | | | 159 | 15% | 24 | 182 |
| | GD - Essntl Svce Water Pmpse Bldg HVAC | | 9 | | | | | 9 | 15% | 1 | 11 |
| | GE - Turbine Building HVAC | | 111 | | | | | 111 | 15% | 17 | 128 |
| | GF - Miscellaneous Building HVAC | | 36 | | | | | 36 | 15% | 5 | 41 |
| | HY - Hydrogen | | 7 | | | | | 7 | 15% | 1 | 8 |
| | KA - Compressed Air & Instrument | | 169 | | | | | 169 | 15% | 25 | 195 |
| | KB - Breathing Air | | 28 | | | | | 28 | 15% | 4 | 32 |
| | KC - Fire Protection | | 290 | | | | | 290 | 15% | 44 | 334 |
| | KD - Domestic Water | | 48 | | | | | 48 | 15% | 7 | 56 |
| | KH - Service Gas | | 19 | | | | | 19 | 15% | 3 | 22 |
| | LA - Sanitary Drains | | 14 | | | | | 14 | 15% | 2 | 16 |
| | LC - Yard Drains | | 2 | | | | | 2 | 15% | 0 | 3 |
| | LE - Oily Waste | | 103 | | | | | 103 | 15% | 15 | 119 |
| | NT - Nitrogen | | 4 | | | | | 4 | 15% | 1 | 5 |
| | OX - Oxygen | | 4 | | | | | 4 | 15% | 1 | 5 |
| | ST - Sewage Treatment | | 25 | | | | | 25 | 15% | 4 | 29 |
| | SW - Screen Wash | | 16 | | | | | 16 | 15% | 2 | 18 |
| | SZ - Service Air | | 49 | | | | | 49 | 15% | 7 | 57 |
| | VA - I&C Shop HVAC | | 3 | | | | | 3 | 15% | 1 | 4 |
| | VB - I&C Shop Computer Room HVAC | | 2 | | | | | 2 | 15% | 0 | 3 |
| | VC - Health Physics Computer Room HVAC | | 5 | | | | | 5 | 15% | 1 | 6 |
| | VH - Circ Water & Makeup Water Scmhse Ve | | 6 | | | | | 6 | 15% | 1 | 7 |
| | VJ - Shop Bldg Machine Shop Area Ventilatio | | 1 | | | | | 1 | 15% | 0 | 1 |
| | VL - Shop Building HVAC | | 2 | | | | | 2 | 15% | 0 | 3 |
| | VS - Administration Building HVAC | | 6 | | | | | 6 | 15% | 1 | 7 |
| | VT - Technical Support Building HVAC | | 2 | | | | | 2 | 15% | 0 | 2 |
| | VV - Miscellaneous Building HVAC | | 3 | | | | | 3 | 15% | 0 | 4 |
| | VW - Waste Water Treatment Ventilation | | 1 | | | | | 1 | 15% | 0 | 1 |
| | WD - Domestic Water | | 28 | | | | | 28 | 15% | 4 | 33 |
| | WG - Gland Water & Motor Cooling Water | | 18 | | | | | 18 | 15% | 3 | 21 |
| | WL - Cooling Lake Makeup & Blowdown | | 17 | | | | | 17 | 15% | 3 | 20 |
| | WM - Makeup Demineralizer | | 97 | | | | | 97 | 15% | 15 | 112 |
| | WS - Plant Service Water | | 85 | | | | | 85 | 15% | 13 | 98 |
| | WT - Waste Water Treatment | | 18 | | | | | 18 | 15% | 3 | 21 |
| | WZ - Radioactive Liquid Waste | | 6 | | | | | 6 | 15% | 1 | 6 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 2: Erect Scaffolding for Syst Removal | | | \$917 | | | | | \$917 | 15% | \$138 | \$1 055 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 2: Decontamination of Site Bldgs | | \$2 004 | \$619 | \$291 | \$80 | \$7 771 | \$1 041 | \$11 805 | 21% | \$2 519 | \$14 325 |
| | Auxiliary Building | 463 | 25 | 63 | 17 | 1 925 | 144 | 2 636 | 21% | 557 | 3 193 |
| | • Aux Bldg — Hot Machine Shop | 18 | | 1 | 1 | 48 | | 68 | 24% | 16 | 84 |
| | • Aux Bldg — Balance | 446 | 25 | 62 | 17 | 1 876 | 144 | 2 569 | 21% | 541 | 3 109 |
| | Control Building | 9 | 0 | 1 | 1 | 40 | 1 | 53 | 21% | 11 | 64 |
| | Fuel Building | 412 | 262 | 45 | 14 | 730 | 300 | 1 762 | 25% | 432 | 2 195 |
| | Radwaste Building | 264 | 12 | 34 | 9 | 1 100 | 71 | 1 491 | 21% | 316 | 1 807 |
| | • Radw Bldg — Rad & Personnel Tunnel | 12 | | 1 | 1 | 26 | | 39 | 25% | 10 | 49 |
| | • Radw Bldg — Radwaste Drum Storage | 26 | 1 | 3 | 1 | 110 | 6 | 147 | 21% | 31 | 179 |
| | • Radw Bldg — Balance | 226 | 11 | 30 | 7 | 963 | 66 | 1 304 | 21% | 274 | 1 579 |
| | Reactor Building | 855 | 320 | 149 | 40 | 3 976 | 524 | 5 863 | 21% | 1 203 | 7 066 |
| | Contingencies for Contaminated Structures | 50% | 25% | 10% | 15% | 15% | 15% | | | | |

DECOMMISSIONING COST ESTIMATE UPDATE — LINE ITEM REPORT

Wolf Creek Generating Station 1996 DECON Option (Immediate)

| Cost (\$Thousands) | Activity: | Decon | Remove | Pack | Ship | Bury | Other | Total | Contingency | Estimate | |
|--|---------------------------|---------|----------|---------|---------|----------|-----------|-----------|-------------|----------|-----------|
| Period 2: License Termination Survey | | | | | | | \$329 | \$329 | 15% | \$49 | \$379 |
| Contingencies (standard) | | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 2: Activity Costs Subtotal | | \$4 609 | \$19 608 | \$3 750 | \$4 940 | \$67 988 | \$27 985 | \$128 880 | 19% | \$24 174 | \$153 054 |
| Period 2: Undistributed Costs | | \$375 | | \$1 470 | \$697 | \$8 612 | \$22 619 | \$33 774 | 16% | \$5 371 | \$39 145 |
| a | Decon equipment | | | | | | 206 | 206 | 15% | 31 | 237 |
| b | Decon supplies | | | | | | 546 | 546 | 25% | 137 | 683 |
| c | DOC staff relocation exp | | | | | | 898 | 898 | 15% | 135 | 1 033 |
| d | Process liquid radwaste | 375 | | 681 | 671 | 5 069 | | 6 796 | 16% | 1 117 | 7 913 |
| e | Insurance | | | | | | 1 023 | 1 023 | 10% | 102 | 1 126 |
| f | Property taxes | | | | | | 1 917 | 1 917 | 10% | 192 | 2 109 |
| g | Health physics supplies | | | | | | 3 777 | 3 777 | 25% | 944 | 4 722 |
| h | Heavy equipment rental | | | | | | 7 936 | 7 936 | 15% | 1 190 | 9 126 |
| i | Small tool allowance | | | | | | 374 | 374 | 15% | 56 | 430 |
| j | Pipe cutting equipment | | | | | | 640 | 640 | 15% | 96 | 736 |
| k | Decon rig | | | | | | 832 | 832 | 15% | 125 | 957 |
| l | Disposal of DAW generated | | | 790 | 26 | 3 543 | | 4 359 | 14% | 614 | 4 973 |
| m | Plant energy budget | | | | | | 3 699 | 3 699 | 15% | 555 | 4 254 |
| n | NRC fees | | | | | | 338 | 338 | 10% | 34 | 371 |
| o | Emergency planning fees | | | | | | 432 | 432 | 10% | 43 | 475 |
| Contingencies for a, c, d, h, i, j, k, l, m | | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Contingencies for Undistributed items b, g | | 50% | 15% | 10% | 15% | 15% | 25% | | | | |
| Contingencies for Undist items e, f, n, o | | 50% | 15% | 10% | 15% | 15% | 10% | | | | |
| Period 2: Staff Costs | | | | | | | \$74 307 | \$74 307 | 15% | \$11 146 | \$85 453 |
| DOC staff costs | | | | | | | 17 420 | 17 420 | 15% | 2 613 | 20 033 |
| Utility staff costs | | | | | | | 56 887 | 56 887 | 15% | 8 533 | 65 420 |
| Contingencies (standard) | | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 2: Total Costs | | \$4 984 | \$19 608 | \$5 220 | \$5 637 | \$76 600 | \$124 911 | \$236 961 | 17% | \$40 691 | \$277 651 |
| Period 3: Removal of Major Equipment | | | \$305 | | | | | \$305 | 15% | \$46 | \$351 |
| Main turbine/generator | | | 76 | | | | | 76 | 15% | 11 | 87 |
| Main condensers | | | 229 | | | | | 229 | 15% | 34 | 264 |
| Contingencies (standard) | | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 3: Demolition of Remaining Site Bldgs | | | \$35 066 | | | | | \$35 066 | 15% | \$5 260 | \$40 326 |
| CP/WCGS Demolition Quantities | | | \$29 185 | | | | | \$29 185 | 15% | \$4 378 | \$33 562 |
| Auxiliary Building | | | 8 467 | | | | | 8 467 | 15% | 1 270 | 9 737 |
| • Aux Bldg — Hot Machine Shop | | | 24 | | | | | 24 | 15% | 4 | 28 |
| • Aux Bldg — Balance | | | 8 442 | | | | | 8 442 | 15% | 1 266 | 9 709 |
| Control Building | | | 2 833 | | | | | 2 833 | 15% | 425 | 3 258 |
| • Ctrl Bldg — Communications Corridor | | | 368 | | | | | 368 | 15% | 55 | 423 |
| • Ctrl Bldg — Balance | | | 2 465 | | | | | 2 465 | 15% | 370 | 2 835 |
| Diesel Generator Building | | | 429 | | | | | 429 | 15% | 64 | 493 |
| Fuel Building | | | 2 747 | | | | | 2 747 | 15% | 412 | 3 159 |
| Radwaste Building | | | 3 375 | | | | | 3 375 | 15% | 506 | 3 881 |
| • Radw Bldg — Rad & Personnel Tunnel | | | 20 | | | | | 20 | 15% | 3 | 22 |
| • Radw Bldg — Radwaste Drum Storage | | | 455 | | | | | 455 | 15% | 68 | 523 |
| • Radw Bldg — Balance | | | 2 901 | | | | | 2 901 | 15% | 435 | 3 336 |
| Reactor Building | | | 5 148 | | | | | 5 148 | 15% | 772 | 5 921 |
| Turbine Building | | | 6 186 | | | | | 6 186 | 15% | 928 | 7 114 |
| • Turb Bldg — Auxiliary Boiler | | | 25 | | | | | 25 | 15% | 4 | 29 |
| • Turb Bldg — Balance | | | 6 160 | | | | | 6 160 | 15% | 924 | 7 084 |
| Contingencies (standard) | | 50% | 15% | 10% | 15% | 15% | 15% | | | | |

DECOMMISSIONING COST ESTIMATE UPDATE — LINE ITEM REPORT

Wolf Creek Generating Station 1996 DECON Option (Immediate)

| Cost (\$Thousands) | Activity: | Decon | Remove | Pack | Ship | Bury | Other | Total | Contingency | Estimate |
|---|---|---------|----------|---------|---------|----------|-----------|-----------|-------------|-----------|
| Wolf Creek G S Demolition Quantities | | | \$5 881 | | | | | \$5 881 | 15% | \$6 764 |
| | Access Vaults | | 40 | | | | | 40 | 15% | 46 |
| | Administration | | 228 | | | | | 228 | 15% | 262 |
| | Chlorine Storage | | 19 | | | | | 19 | 15% | 21 |
| | Circulating Water Discharge Structure | | 383 | | | | | 383 | 15% | 441 |
| | Circulating Water Intake & Screenhouse | | 893 | | | | | 893 | 15% | 1 027 |
| | Covered Walkways | | 13 | | | | | 13 | 15% | 14 |
| | Essential Service Water System Pumphouse | | 845 | | | | | 845 | 15% | 971 |
| | Essential Service Water System Valve House | | 13 | | | | | 13 | 15% | 15 |
| | MMO Building | | 163 | | | | | 163 | 15% | 187 |
| | Miscellaneous Site Foundations | | 408 | | | | | 408 | 15% | 469 |
| | Miscellaneous Site Structures (32 structures) | | 2 509 | | | | | 2 509 | 15% | 2 885 |
| | Oil Separator and Waste Tank | | 2 | | | | | 2 | 15% | 3 |
| | Security Building/Guardhouse | | 345 | | | | | 345 | 15% | 396 |
| | Site Security Diesel Generator | | 3 | | | | | 3 | 15% | 3 |
| | Waste Water Treatment | | 19 | | | | | 19 | 15% | 22 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | |
| Period 3: Site Closeout Activities | | | \$5 670 | | | | \$172 | \$5 841 | 15% | \$6 718 |
| | Remove rubble | | 4 150 | | | | | 4 150 | 15% | 4 773 |
| | Grade & landscape site | | 1 519 | | | | | 1 519 | 15% | 1 747 |
| | Final report to NRC | | | | | | 172 | 172 | 15% | 198 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | |
| Period 3: Activity Costs Subtotal | | | \$41 041 | | | | \$172 | \$41 213 | 15% | \$47 394 |
| Period 3: Undistributed Costs | | | | | | | \$3 915 | \$3 915 | 14% | \$531 |
| a | Insurance | | | | | | 180 | 180 | 10% | 198 |
| b | Property taxes | | | | | | 943 | 943 | 10% | 1 037 |
| c | Heavy equipment rental | | | | | | 2 354 | 2 354 | 15% | 2 708 |
| d | Small tool allowance | | | | | | 312 | 312 | 15% | 359 |
| e | Plant energy budget | | | | | | 126 | 126 | 15% | 145 |
| | Contingencies for a, b | 50% | 15% | 10% | 15% | 15% | 10% | | | |
| | Contingencies for c, d, e (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | |
| Period 3: Staff Costs | | | | | | | \$17 039 | \$17 039 | 15% | \$2 556 |
| | DOC staff costs | | | | | | 7 541 | 7 541 | 15% | 8 672 |
| | Utility staff costs | | | | | | 9 498 | 9 498 | 15% | 10 923 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | |
| Period 3: Total Costs | | | \$41 041 | | | | \$21 126 | \$62 167 | 15% | \$9 269 |
| Total Cost to Decommission | | \$5 057 | \$60 648 | \$5 473 | \$5 691 | \$77 657 | \$196 602 | \$351 128 | 16% | \$57 759 |
| | | | | | | | | | | \$408 887 |

Input Variables Summary

| | 1996 | 1993 | Cost Component | Chg from '93: | 1996 | Avg Annl |
|--|-------|-------|-------------------------------------|---------------|--------|----------|
| Indirect Personnel Overhead [%] | | | WCNOC Staff — Management Labor | | 11.3% | 3.6% |
| Utility O&B (All Labor) | 71.0% | 64.6% | WCNOC Staff — Contract Labor | | 12.3% | 3.9% |
| DOC O&B (Administrative) | 90.0% | 90.0% | DOC Staff Labor | | 10.3% | 3.3% |
| DOC O&B (General Labor) | 40.0% | 40.0% | Security Guards Labor | | 12.3% | 3.9% |
| | | | Craft Labor | | 9.1% | 2.9% |
| | | | Specialty Consultant Labor | | 10.1% | 3.3% |
| Subcontractor Overhead and Profit [%] | | | Transportation Costs | | 3.1% | 1.0% |
| On Decommissioning Labor | 21.0% | 21.0% | Material and Equipment | | 9.0% | 2.9% |
| On Demolition Labor | 13.0% | 13.0% | NRC Fees | | 4.8% | 1.6% |
| On Equipment and Materials | 14.2% | 14.2% | Emergency Planning Fees | | 17.9% | 5.6% |
| | | | Other | | 6.3% | 2.1% |
| Work Efficiencies [%] | | | Radwaste Burial | | 10.0% | 3.2% |
| Height Adjustment, 12' - 20' | 15.0% | 20.0% | Radwaste Off-Site Processing | | 72.4% | 19.9% |
| Respiratory Protection Adjustment | 37.5% | 50.0% | Primary Liability Insurance | | 12.1% | 3.9% |
| Radiation/ALARA Adjustment | 25.0% | 32.0% | Excess Property Insurance (NEIL II) | | -36.6% | -14.1% |
| Protective Clothing Adjustment | 22.5% | 30.0% | Property Taxes (initial rate) | | 44.0% | 12.9% |
| Work Break Adjustment | 8.3% | 8.3% | Electrical Energy | | -14.2% | -5.0% |
| | | | Oil | | 14.8% | 4.7% |
| | | | Total Cost Estimate | | 10.6% | 3.4% |

APPENDIX B

DECOMMISSIONING COST ESTIMATE UPDATE — LINE ITEM REPORT

Wolf Creek Generating Station 1996 SAFSTOR Option (Delayed)

| Cost (\$Thousands) | Activity: | Decon | Remove | Pack | Ship | Bury | Other | Total | Contingency | Estimate | |
|--|--|----------------|--------------|--------------|--------------|----------------|----------------|----------------|-------------|----------------|----------------|
| Period 1: Mothballing Activities | | | | | | | \$1 775 | \$1 775 | 15% | \$266 | \$2 041 |
| | Prepare prelim decommissioning plan | | | | | | 132 | 132 | 15% | 20 | 152 |
| | Prepare proposed decommissioning plan | | | | | | 344 | 344 | 15% | 52 | 395 |
| | Review plant drawings and specs | | | | | | 143 | 143 | 15% | 21 | 165 |
| | Estimate by-product inventory | | | | | | 110 | 110 | 15% | 17 | 127 |
| | Submit for possession-only license | | | | | | 110 | 110 | 15% | 17 | 127 |
| | End product description | | | | | | 110 | 110 | 15% | 17 | 127 |
| | Detailed by-product inventory | | | | | | 165 | 165 | 15% | 25 | 190 |
| | Define major work sequence | | | | | | 110 | 110 | 15% | 17 | 127 |
| | Perform safety analysis of operation | | | | | | 220 | 220 | 15% | 33 | 253 |
| | Perform safety analysis of end product | | | | | | 220 | 220 | 15% | 33 | 253 |
| | Submit dismantling plan | | | | | | 110 | 110 | 15% | 17 | 127 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 1: Activity Specifications | | | | | | | \$1 785 | \$1 785 | 15% | \$268 | \$2 052 |
| | Prepare plant & facilities for mothball ops | | | | | | 542 | 542 | 15% | 81 | 623 |
| | Plant systems | | | | | | 459 | 459 | 15% | 69 | 528 |
| | Plant structures & buildings | | | | | | 344 | 344 | 15% | 52 | 395 |
| | Waste management | | | | | | 220 | 220 | 15% | 33 | 253 |
| | Facility & site dormancy | | | | | | 220 | 220 | 15% | 33 | 253 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 1: Detailed Work Procedures | | | | | | | \$653 | \$653 | 15% | \$98 | \$751 |
| | Plant systems | | | | | | 521 | 521 | 15% | 78 | 599 |
| | Facility closeout & dormancy | | | | | | 132 | 132 | 15% | 20 | 152 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 1: Miscellaneous | | | | | | | \$11 | \$11 | 15% | \$2 | \$13 |
| | Procure vacuum drying system | | | | | | 11 | 11 | 15% | 2 | 13 |
| Period 1: Decontamination of Site Bldgs | | | | | | | \$1 700 | \$1 700 | 50% | \$850 | \$2 550 |
| | Auxiliary Building | 360 | | | | | 360 | 360 | 50% | 180 | 541 |
| | • Aux Bldg — Hot Machine Shop | 10 | | | | | 10 | 10 | 50% | 5 | 15 |
| | • Aux Bldg — Balance | 350 | | | | | 350 | 350 | 50% | 175 | 525 |
| | Control Building | 8 | | | | | 8 | 8 | 50% | 4 | 12 |
| | Fuel Building | 363 | | | | | 363 | 363 | 50% | 181 | 544 |
| | Radwaste Building | 208 | | | | | 208 | 208 | 50% | 104 | 312 |
| | • Radw Bldg — Rad & Personnel Tunnel | 3 | | | | | 3 | 3 | 50% | 2 | 5 |
| | • Radw Bldg — Radwaste Drum Storage | 21 | | | | | 21 | 21 | 50% | 11 | 32 |
| | • Radw Bldg — Balance | 184 | | | | | 184 | 184 | 50% | 92 | 275 |
| | Reactor | 761 | | | | | 761 | 761 | 50% | 381 | 1 142 |
| | Contingencies for Contaminated Structures | 50% | 25% | 10% | 15% | 15% | 15% | | | | |
| Period 1: Miscellaneous | | | | | | | \$393 | \$673 | 15% | \$101 | \$774 |
| | Prepare support equipment for storage | | 259 | | | | 259 | 259 | 15% | 39 | 298 |
| | Install containment pressure equalization line | | 21 | | | | 21 | 21 | 15% | 3 | 24 |
| | Interim survey prior to dormancy | | | | | | 329 | 329 | 15% | 49 | 379 |
| | Prepare and submit interim report | | | | | | 64 | 64 | 15% | 10 | 73 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Subtotal Period 1 Activity Costs | | \$1 700 | \$280 | | | | \$4 616 | \$6 596 | 24% | \$1 585 | \$8 181 |
| Period 1: Undistributed Costs | | \$288 | | \$371 | \$204 | \$1 716 | \$3 766 | \$6 345 | 18% | \$1 112 | \$7 457 |
| a | Decon equipment | | | | | | 213 | 213 | 15% | 32 | 245 |
| b | Decon supplies | | | | | | 154 | 154 | 25% | 39 | 193 |
| c | Process liquid waste | 288 | | 148 | 197 | 857 | | 1 490 | 21% | 317 | 1 808 |
| d | Insurance | | | | | | 250 | 250 | 10% | 25 | 275 |
| e | Property taxes | | | | | | 474 | 474 | 10% | 47 | 522 |
| f | Health physics supplies | | | | | | 1 067 | 1 067 | 25% | 267 | 1 334 |
| g | Small tool allowance | | | | | | 25 | 25 | 15% | 4 | 29 |
| h | Disposal of DAW generated | | | 223 | 7 | 858 | | 1 088 | 14% | 152 | 1 240 |
| i | Plant energy budget | | | | | | 1 421 | 1 421 | 15% | 213 | 1 634 |
| j | NRC fees | | | | | | 50 | 50 | 10% | 5 | 55 |
| k | Emergency planning fees | | | | | | 113 | 113 | 10% | 11 | 124 |
| | Contingencies for a, c, g, h, i (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| | Contingencies for b, f | 50% | 15% | 10% | 15% | 15% | 25% | | | | |
| | Contingencies for d, e, j, k | 50% | 15% | 10% | 15% | 15% | 10% | | | | |

DECOMMISSIONING COST ESTIMATE UPDATE — LINE ITEM REPORT

Wolf Creek Generating Station 1996 SAFSTOR Option (Delayed)

| Cost (\$Thousands) | Activity: | Decon | Remove | Pack | Ship | Bury | Other | Total | Contingency | Estimate | |
|--|--|----------------|--------------|--------------|--------------|----------------|------------------|------------------|-------------|-----------------|------------------|
| Period 1: Staff Costs | | | | | | | \$12 913 | \$12 913 | 15% | \$1 937 | \$14 850 |
| Utility staff cost | | | | | | | 12 913 | 12 913 | 15% | 1 937 | 14 850 |
| Contingencies (standard) | | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 1: Total Cost to Mothball | | \$1 989 | \$280 | \$371 | \$204 | \$1 716 | \$21 296 | \$25 854 | 18% | \$4 633 | \$30 487 |
| Period 2: Mothballed Annual Maintenance Cost | | | | \$1 | \$1 | \$44 | \$5 084 | \$5 131 | 15% | \$755 | \$5 887 |
| a | Health physics supplies | | | | | | 41 | 41 | 25% | 10 | 51 |
| b | Insurance | | | | | | 60 | 60 | 10% | 6 | 66 |
| c | Property taxes | | | | | | 480 | 480 | 10% | 48 | 528 |
| d | Disposal of contaminated solid waste | | | 1 | 1 | 44 | | 47 | 15% | 7 | 54 |
| e | Bituminous roof replacement | | | | | | 41 | 41 | 15% | 6 | 47 |
| f | Maintenance supplies | | | | | | 88 | 88 | 25% | 22 | 110 |
| g | Plant energy budget | | | | | | 194 | 194 | 15% | 29 | 223 |
| h | NRC Fees | | | | | | 11 | 11 | 15% | 2 | 13 |
| i | Emergency planning fees | | | | | | 8 | 8 | 15% | 1 | 9 |
| j | Site maintenance staff | | | | | | 4 161 | 4 161 | 15% | 624 | 4 785 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| | Contingencies for a, f | 50% | 15% | 10% | 15% | 15% | 25% | | | | |
| | Contingencies for b, c | 50% | 15% | 10% | 15% | 15% | 10% | | | | |
| Period 2: Maintenance Cost (55.1 yr dormancy) | | | | \$63 | \$63 | \$2 449 | \$280 145 | \$282 720 | 15% | \$41 626 | \$324 346 |
| Period 3: Activity Costs | | | | | | | \$1 984 | \$1 984 | 15% | \$298 | \$2 282 |
| | Review plant drawings and specifications | | | | | | 506 | 506 | 15% | 76 | 582 |
| | End product description | | | | | | 110 | 110 | 15% | 17 | 127 |
| | Detailed by-product inventory | | | | | | 143 | 143 | 15% | 21 | 165 |
| | Define major work sequence | | | | | | 826 | 826 | 15% | 124 | 950 |
| | Perform safety analysis | | | | | | 341 | 341 | 15% | 51 | 393 |
| | Submit dismantling plan | | | | | | 57 | 57 | 15% | 9 | 66 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 3: Undistributed Costs | | | | \$221 | \$7 | \$858 | \$5 591 | \$6 677 | 16% | \$1 039 | \$7 716 |
| a | DOC staff relocation expenses | | | | | | 952 | 952 | 15% | 143 | 1 095 |
| b | Insurance | | | | | | 375 | 375 | 10% | 38 | 413 |
| c | Property taxes | | | | | | 712 | 712 | 10% | 71 | 783 |
| d | Health physics supplies | | | | | | 1 067 | 1 067 | 25% | 267 | 1 334 |
| e | Heavy equipment rental | | | | | | 262 | 262 | 15% | 39 | 302 |
| f | Disposal of DAW generated | | | 221 | 7 | 858 | | 1 086 | 14% | 152 | 1 238 |
| g | Plant energy budget | | | | | | 2 148 | 2 148 | 15% | 322 | 2 471 |
| h | NRC fees | | | | | | 74 | 74 | 10% | 7 | 82 |
| | Contingencies for a, e, f, g (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| | Contingencies for item d | 50% | 15% | 10% | 15% | 15% | 25% | | | | |
| | Contingencies for items b, c, h | 50% | 15% | 10% | 15% | 15% | 10% | | | | |
| Period 3: Staff Costs | | | | | | | \$18 821 | \$18 821 | 15% | \$2 823 | \$21 644 |
| | DOC staff costs | | | | | | 4 802 | 4 802 | 15% | 720 | 5 523 |
| | Utility staff costs | | | | | | 14 019 | 14 019 | 15% | 2 103 | 16 122 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 3: Total Costs | | | | \$221 | \$7 | \$858 | \$26 396 | \$27 482 | 15% | \$4 160 | \$31 642 |
| Period 4: Activity Specifications | | | | | | | \$4 380 | \$4 380 | 15% | \$657 | \$5 037 |
| | Re-activate plant and temporary facilities | | | | | | 811 | 811 | 15% | 122 | 933 |
| | Plant systems | | | | | | 459 | 459 | 15% | 69 | 528 |
| | Reactor internals | | | | | | 782 | 782 | 15% | 117 | 899 |
| | Reactor vessel | | | | | | 716 | 716 | 15% | 107 | 823 |
| | Biological shield | | | | | | 55 | 55 | 15% | 8 | 63 |
| | Steam generators | | | | | | 344 | 344 | 15% | 52 | 395 |
| | Reinforced concrete | | | | | | 176 | 176 | 15% | 26 | 203 |
| | Turbine and condenser | | | | | | 88 | 88 | 15% | 13 | 101 |
| | Plant structures & buildings | | | | | | 344 | 344 | 15% | 52 | 395 |
| | Waste management | | | | | | 506 | 506 | 15% | 76 | 582 |
| | Facility & site closeout | | | | | | 99 | 99 | 15% | 15 | 114 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |

DECOMMISSIONING COST ESTIMATE UPDATE — LINE ITEM REPORT

Wolf Creek Generating Station 1996 SAFSTOR Option (Delayed)

| Cost (\$Thousands) | Activity: | Decon | Remove | Pack | Ship | Bury | Other | Total | Contingency | Estimate | |
|---|--|----------------|-----------------|----------------|----------------|-----------------|----------------|-----------------|-------------|-----------------|-----------------|
| Period 4: Planning and Site Preparations | | | | | | | \$3 573 | \$3 573 | 15% | \$536 | \$4 109 |
| | Prepare dismantling sequence | | | | | | 264 | 264 | 15% | 40 | 304 |
| | Plant prep. and temp. services | | | | | | 1 635 | 1 635 | 15% | 245 | 1 880 |
| | Design water clean-up system | | | | | | 154 | 154 | 15% | 23 | 177 |
| | Rigging/CCES/tooling/etc. | | | | | | 1 384 | 1 384 | 15% | 208 | 1 592 |
| | Procure casks/liners and containers | | | | | | 135 | 135 | 15% | 20 | 156 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 4: Detailed Work Procedures | | | | | | | \$3 825 | \$3 825 | 15% | \$574 | \$4 399 |
| | Plant systems | | | | | | 521 | 521 | 15% | 78 | 599 |
| | Vessel head | | | | | | 275 | 275 | 15% | 41 | 317 |
| | Reactor internals | | | | | | 275 | 275 | 15% | 41 | 317 |
| | Remaining buildings | | | | | | 149 | 149 | 15% | 22 | 171 |
| | CRD cooling assembly | | | | | | 110 | 110 | 15% | 17 | 127 |
| | CRD housings and ICI tubes | | | | | | 110 | 110 | 15% | 17 | 127 |
| | Incore instrumentation | | | | | | 110 | 110 | 15% | 17 | 127 |
| | Reactor vessel | | | | | | 400 | 400 | 15% | 60 | 460 |
| | Facility closeout | | | | | | 132 | 132 | 15% | 20 | 152 |
| | Missile shields | | | | | | 50 | 50 | 15% | 7 | 57 |
| | Biological shield | | | | | | 132 | 132 | 15% | 20 | 152 |
| | Steam generators | | | | | | 506 | 506 | 15% | 76 | 582 |
| | Reinforced concrete | | | | | | 110 | 110 | 15% | 17 | 127 |
| | Turbine and condensers | | | | | | 344 | 344 | 15% | 52 | 395 |
| | Auxiliary building | | | | | | 301 | 301 | 15% | 45 | 346 |
| | Reactor building | | | | | | 301 | 301 | 15% | 45 | 346 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 4: Rack Removal | | \$253 | \$44 | \$100 | \$28 | \$1 195 | \$924 | \$2 544 | 18% | \$469 | \$3 013 |
| | Remove spent fuel racks | 253 | 44 | 100 | 28 | 1 195 | 924 | 2 544 | 18% | 469 | 3 013 |
| | Contingencies | 50% | 25% | 10% | 15% | 15% | 15% | | | | |
| Period 4: NSSS Removal | | \$460 | \$6 879 | \$831 | \$4 365 | \$36 867 | | \$49 402 | 21% | \$10 308 | \$59 710 |
| a | Reactor coolant piping | 66 | 127 | 67 | 19 | 2 221 | | 2 499 | 16% | 407 | 2 907 |
| b | Pressurizer relief tank | 12 | 60 | 5 | 4 | 211 | | 292 | 18% | 54 | 346 |
| c | Reactor coolant pumps & motors | 25 | 38 | 35 | 43 | 3 753 | | 3 894 | 15% | 595 | 4 488 |
| d | Pressurizer | 24 | 29 | 4 | 11 | 1 376 | | 1 444 | 16% | 228 | 1 671 |
| e | Steam generators | 134 | 2 674 | 143 | 3 765 | 19 238 | | 25 953 | 16% | 4 200 | 30 154 |
| f | CRDMS/ICIS/service structure removal | 58 | 39 | 22 | 15 | 641 | | 774 | 18% | 139 | 913 |
| g | Reactor vessel internals | 41 | 1 058 | 270 | 237 | 6 666 | | 8 271 | 23% | 1 940 | 10 212 |
| h | Reactor vessel | 101 | 2 855 | 285 | 271 | 2 762 | | 6 274 | 44% | 2 745 | 9 019 |
| | Contingencies for reactor vessel & internals | 50% | 75% | 25% | 25% | 15% | 15% | | | | |
| | Contingencies for others | 50% | 25% | 10% | 15% | 15% | 25% | | | | |
| Period 4: Disposal of Plant Systems | | \$1 322 | \$12 718 | \$2 729 | \$654 | \$22 027 | \$9 684 | \$49 134 | 17% | \$8 422 | \$57 557 |
| CP/WCGS Contam Comp (System Specific) | | \$1 183 | \$6 470 | \$2 350 | \$531 | \$19 283 | \$7 618 | \$37 436 | 18% | \$6 559 | \$43 995 |
| | BB - Reactor Coolant | | 125 | 76 | 19 | 873 | 240 | 1 333 | 16% | 209 | 1 541 |
| | BG - Chemical & Volume Control | 387 | 553 | 203 | 56 | 2 548 | 665 | 4 411 | 19% | 842 | 5 254 |
| | BL - Reactor Makeup Water | | 165 | 37 | 11 | 263 | 164 | 640 | 17% | 111 | 750 |
| | BM - Steam Generator Blowdown | | 371 | 122 | 34 | 1 194 | 509 | 2 231 | 16% | 366 | 2 597 |
| | BN - Borated Refueling Water Storage | | 177 | 66 | 11 | 421 | 316 | 991 | 16% | 163 | 1 154 |
| | EC - Fuel Pool Cooling & Cleanup | | 271 | 83 | 21 | 770 | 357 | 1 503 | 17% | 248 | 1 751 |
| | EJ - Residual Heat Removal | | 241 | 90 | 21 | 951 | 337 | 1 640 | 16% | 266 | 1 906 |
| | EM - High Pressure Coolant Injection | | 189 | 68 | 20 | 615 | 285 | 1 176 | 16% | 192 | 1 368 |
| | EP - Accumulator Safety Injection | | 96 | 31 | 7 | 225 | 144 | 503 | 17% | 84 | 587 |
| | GG - Fuel Building HVAC | | 170 | 53 | 12 | 615 | 146 | 996 | 16% | 164 | 1 159 |
| | GH - Radwaste Building HVAC | | 119 | 33 | 8 | 348 | 104 | 612 | 17% | 102 | 714 |
| | GL - Auxiliary Building HVAC | | 309 | 55 | 14 | 344 | 253 | 974 | 18% | 174 | 1 149 |
| | GN - Containment Cooling | | 362 | 122 | 26 | 1 328 | 371 | 2 210 | 16% | 362 | 2 571 |
| | GR - Containment Atmospheric Control | | 7 | 26 | 5 | 447 | 23 | 508 | 15% | 76 | 584 |
| | GS - Containment Hydrogen Control | | 31 | 23 | 6 | 176 | 101 | 336 | 16% | 52 | 388 |
| | GT - Containment Purge HVAC | | 78 | 38 | 6 | 382 | 131 | 635 | 16% | 101 | 736 |
| | HA - Gaseous Radwaste | | 178 | 83 | 18 | 608 | 189 | 1 075 | 16% | 175 | 1 250 |
| | HB - Liquid Radwaste | 412 | 484 | 153 | 32 | 977 | 468 | 2 526 | 22% | 564 | 3 089 |
| | HC - Solid Radwaste | | 281 | 243 | 32 | 1 081 | 343 | 1 981 | 16% | 313 | 2 294 |

DECOMMISSIONING COST ESTIMATE UPDATE — LINE ITEM REPORT

Wolf Creek Generating Station 1996 SAFSTOR Option (Delayed)

| Cost (\$Thousands) | Activity: | Decon | Remove | Pack | Ship | Bury | Other | Total | Contingency | Estimate | |
|--|--|-------------|----------------|--------------|--------------|----------------|----------------|----------------|-------------|--------------|----------------|
| | HD - Decontamination | | 46 | 55 | 7 | 159 | 104 | 371 | 16% | 58 | 429 |
| | HE - Boron Recycle | | 299 | 83 | 21 | 520 | 326 | 1 250 | 17% | 213 | 1 463 |
| | HF - Secondary Liquid Waste | 352 | 538 | 225 | 43 | 1 116 | 609 | 2 883 | 21% | 598 | 3 481 |
| | KE - Fuel Handling & Storage, RPV Service | | 7 | 9 | 6 | 316 | | 338 | 15% | 51 | 389 |
| | LD - Chemical & Detergent Waste | 32 | 82 | 21 | 6 | 147 | 101 | 389 | 20% | 77 | 466 |
| | LF - Floor & Equipment Drains | | 1 193 | 246 | 65 | 1 593 | 1 152 | 4 249 | 18% | 744 | 4 993 |
| | RM - Process Sampling & Analysis | | 64 | 50 | 15 | 764 | 147 | 1 041 | 15% | 160 | 1 201 |
| | SJ - Nuclear Sampling | | 36 | 55 | 7 | 502 | 34 | 634 | 15% | 96 | 730 |
| | Contingencies for Contaminated Systems | 50% | 25% | 10% | 15% | 15% | 15% | | | | |
| CP/WCGS Contam Comp (Non-System Specific) | | | \$788 | \$379 | \$123 | \$2 744 | \$2 066 | \$6 101 | 16% | \$975 | \$7 076 |
| | Auxiliary Building | | 278 | 131 | 44 | 983 | 740 | 2 175 | 16% | 348 | 2 522 |
| | Control Building | | 255 | 135 | 44 | 973 | 732 | 2 138 | 16% | 339 | 2 477 |
| | Fuel Building | | 40 | 19 | 6 | 151 | 114 | 331 | 16% | 53 | 383 |
| | Radwaste Building | | 119 | 58 | 18 | 397 | 300 | 892 | 16% | 143 | 1 035 |
| | Reactor Building | | 96 | 37 | 12 | 240 | 181 | 565 | 16% | 93 | 658 |
| | Contingencies for Contaminated Systems | 50% | 25% | 10% | 15% | 15% | 15% | | | | |
| CP/WCGS Non-Contam Comp (Syst Specific) | | \$47 | \$1 772 | | | | | \$1 818 | 16% | \$289 | \$2 108 |
| | AB - Main Steam | | 148 | | | | | 148 | 15% | 22 | 170 |
| | AC - Main Turbine | | 139 | | | | | 139 | 15% | 21 | 160 |
| | AD - Condensate | | 141 | | | | | 141 | 15% | 21 | 162 |
| | AE - Feedwater | | 96 | | | | | 96 | 15% | 14 | 110 |
| | AF - Feedwater Htr Extraction, Drains, Vents | | 143 | | | | | 143 | 15% | 22 | 165 |
| | AK - Condensate Demineralizer | | 49 | | | | | 49 | 15% | 7 | 56 |
| | AL - Auxiliary Feedwater | | 21 | | | | | 21 | 15% | 3 | 24 |
| | AP - Condensate Storage & Transfer | | 41 | | | | | 41 | 15% | 6 | 48 |
| | AQ - Condensate & Feedwater Chem Addition | | 13 | | | | | 13 | 15% | 2 | 15 |
| | CA - Steam Seal | | 13 | | | | | 13 | 15% | 2 | 15 |
| | CB - Main Turbine Lube Oil | | 29 | | | | | 29 | 15% | 4 | 33 |
| | CC - Generator Hydrogen & CO2 | | 5 | | | | | 5 | 15% | 1 | 6 |
| | CD - Generator Seal Oil | | 7 | | | | | 7 | 15% | 1 | 9 |
| | CE - Stator Cooling Water | | 6 | | | | | 6 | 15% | 1 | 7 |
| | CF - Lube Oil Storage, Transfer, & Purificatio | | 22 | | | | | 22 | 15% | 3 | 26 |
| | CG - Condenser Air Removal | | 17 | | | | | 17 | 15% | 3 | 20 |
| | CH - Main Turbine Control Oil | | 31 | | | | | 31 | 15% | 5 | 35 |
| | EB - Closed Cooling Water | | 34 | | | | | 34 | 15% | 5 | 39 |
| | EG - Component Cooling Water | | 142 | | | | | 142 | 15% | 21 | 164 |
| | EN - Containment Spray | 47 | 42 | | | | | 89 | 33% | 30 | 119 |
| | FA - Auxiliary Steam Generator | | 7 | | | | | 7 | 15% | 1 | 9 |
| | FB - Auxiliary Steam | | 69 | | | | | 69 | 15% | 10 | 79 |
| | FC - Auxiliary Turbines | | 33 | | | | | 33 | 15% | 5 | 38 |
| | FE - Auxiliary Steam Chemical Addition | | 3 | | | | | 3 | 15% | 0 | 4 |
| | GA - Plant Heating | | 74 | | | | | 74 | 15% | 11 | 86 |
| | GB - Central Chilled Water | | 54 | | | | | 54 | 15% | 8 | 62 |
| | GK - Control Building HVAC | | 156 | | | | | 156 | 15% | 23 | 180 |
| | GM - Diesel Generator Building HVAC | | 29 | | | | | 29 | 15% | 4 | 33 |
| | GP - Containment Integrated Leak Rate Test | | 6 | | | | | 6 | 15% | 1 | 7 |
| | JE - Emergency Fuel Oil | | 33 | | | | | 33 | 15% | 5 | 38 |
| | KJ - Standby Diesel Engine | | 107 | | | | | 107 | 15% | 16 | 123 |
| | LB - Roof Drains | | 58 | | | | | 58 | 15% | 9 | 67 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| WCGS Non-Contam Comp (System Specific) | | | \$2 111 | | | | | \$2 111 | 15% | \$317 | \$2 427 |
| | AN - Demineralized Water Storage & Transfe | | 43 | | | | | 43 | 15% | 6 | 50 |
| | AX - Acid Feed | | 20 | | | | | 20 | 15% | 3 | 23 |
| | CL - Chlorination | | 15 | | | | | 15 | 15% | 2 | 17 |
| | CO - Carbon Dioxide | | 4 | | | | | 4 | 15% | 1 | 5 |
| | CW - Circulating Water | | 200 | | | | | 200 | 15% | 30 | 230 |
| | CZ - Caustic Acid | | 3 | | | | | 3 | 15% | 0 | 4 |
| | DA - Circulating Water | | 207 | | | | | 207 | 15% | 31 | 238 |
| | DM - Equipment Drains | | 63 | | | | | 63 | 15% | 9 | 73 |
| | DO - Diesel Oil | | 1 | | | | | 1 | 15% | 0 | 1 |
| | EA - Service Water | | 66 | | | | | 66 | 15% | 10 | 76 |
| | EF - Essential Service Water | | 81 | | | | | 81 | 15% | 12 | 93 |
| | FO - Fuel Oil | | 15 | | | | | 15 | 15% | 2 | 17 |

DECOMMISSIONING COST ESTIMATE UPDATE — LINE ITEM REPORT

Wolf Creek Generating Station 1996 SAFSTOR Option (Delayed)

| Cost (\$Thousands) | Activity: | Decon | Remove | Pack | Ship | Bury | Other | Total | Contingency | Estimate | |
|---|-----------|----------------|----------------|--------------|-------------|----------------|--------------|-----------------|-------------|----------------|-----------------|
| FP - Fire Protection | | | 160 | | | | | 160 | 15% | 24 | 184 |
| GD - Essntl Svce Water Pmhpse Bldg HVAC | | | 9 | | | | | 9 | 15% | 1 | 11 |
| GE - Turbine Building HVAC | | | 108 | | | | | 108 | 15% | 16 | 124 |
| GF - Miscellaneous Building HVAC | | | 35 | | | | | 35 | 15% | 5 | 40 |
| HY- Hydrogen | | | 6 | | | | | 6 | 15% | 1 | 7 |
| KA - Compressed Air & Instrument | | | 169 | | | | | 169 | 15% | 25 | 194 |
| KB - Breathing Air | | | 27 | | | | | 27 | 15% | 4 | 32 |
| KC - Fire Protection | | | 292 | | | | | 292 | 15% | 44 | 336 |
| KD - Domestic Water | | | 48 | | | | | 48 | 15% | 7 | 56 |
| KH - Service Gas | | | 19 | | | | | 19 | 15% | 3 | 22 |
| LA - Sanitary Drains | | | 14 | | | | | 14 | 15% | 2 | 16 |
| LC - Yard Drains | | | 2 | | | | | 2 | 15% | 0 | 2 |
| LE - Oily Waste | | | 103 | | | | | 103 | 15% | 15 | 119 |
| NT - Nitrogen | | | 4 | | | | | 4 | 15% | 1 | 5 |
| OX - Oxygen | | | 4 | | | | | 4 | 15% | 1 | 5 |
| ST - Sewage Treatment | | | 24 | | | | | 24 | 15% | 4 | 28 |
| SW - Screen Wash | | | 16 | | | | | 16 | 15% | 2 | 18 |
| SZ - Service Air | | | 50 | | | | | 50 | 15% | 7 | 57 |
| VA - I&C Shop HVAC | | | 3 | | | | | 3 | 15% | 0 | 4 |
| VB - I&C Shop Computer Room HVAC | | | 2 | | | | | 2 | 15% | 0 | 2 |
| VC - Health Physics Computer Room HVAC | | | 5 | | | | | 5 | 15% | 1 | 6 |
| VH - Circ Water & Makeup Water Scrnhse Ve | | | 6 | | | | | 6 | 15% | 1 | 7 |
| VJ - Shop Bldg Machine Shop Area Ventilatio | | | 1 | | | | | 1 | 15% | 0 | 1 |
| VL - Shop Building HVAC | | | 2 | | | | | 2 | 15% | 0 | 2 |
| VS - Administration Building HVAC | | | 5 | | | | | 5 | 15% | 1 | 6 |
| VT - Technical Support Building HVAC | | | 2 | | | | | 2 | 15% | 0 | 2 |
| VV - Miscellaneous Building HVAC | | | 3 | | | | | 3 | 15% | 0 | 4 |
| VW - Waste Water Treatment Ventilation | | | 1 | | | | | 1 | 15% | 0 | 1 |
| WD - Domestic Water | | | 26 | | | | | 26 | 15% | 4 | 30 |
| WG - Gland Water & Motor Cooling Water | | | 18 | | | | | 18 | 15% | 3 | 21 |
| WL - Cooling Lake Makeup & Blowdown | | | 18 | | | | | 18 | 15% | 3 | 21 |
| WM - Makeup Demineralizer | | | 97 | | | | | 97 | 15% | 15 | 112 |
| WS - Plant Service Water | | | 86 | | | | | 86 | 15% | 13 | 99 |
| WT - Waste Water Treatment | | | 18 | | | | | 18 | 15% | 3 | 21 |
| WZ - Radioactive Liquid Waste | | | 5 | | | | | 5 | 15% | 1 | 6 |
| Contingencies (standard) | | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| <u>CP/WCGS Decontaminable Comp (Non-SystSpec)</u> | | <u>\$92</u> | <u>\$388</u> | | | | | <u>\$480</u> | <u>22%</u> | <u>\$104</u> | <u>\$584</u> |
| Auxiliary Building | | 33 | 143 | | | | | 176 | 22% | 38 | 213 |
| Control Building | | 34 | 131 | | | | | 165 | 22% | 37 | 202 |
| Fuel Building | | 3 | 17 | | | | | 20 | 21% | 4 | 24 |
| Radwaste Building | | 12 | 49 | | | | | 60 | 22% | 13 | 73 |
| Reactor Building | | 11 | 49 | | | | | 59 | 21% | 13 | 72 |
| Contingencies (standard) | | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| <u>CP/WCGS Clean Comp (Non-Syst Specific)</u> | | | <u>\$1 189</u> | | | | | <u>\$1 189</u> | <u>15%</u> | <u>\$178</u> | <u>\$1 367</u> |
| Auxiliary Building | | | 428 | | | | | 428 | 15% | 64 | 492 |
| Control Building | | | 400 | | | | | 400 | 15% | 60 | 460 |
| Fuel Building | | | 55 | | | | | 55 | 15% | 8 | 63 |
| Radwaste Building | | | 162 | | | | | 162 | 15% | 24 | 186 |
| Reactor Building | | | 144 | | | | | 144 | 15% | 22 | 166 |
| Contingencies (standard) | | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| <u>Period 4: Erect Scaffolding for Syst Removal</u> | | | <u>\$917</u> | | | | | <u>\$917</u> | <u>15%</u> | <u>\$138</u> | <u>\$1 055</u> |
| Contingencies (standard) | | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| <u>Period 4: Decontamination of Site Bldgs</u> | | <u>\$1 922</u> | <u>\$688</u> | <u>\$295</u> | <u>\$88</u> | <u>\$7 907</u> | <u>\$675</u> | <u>\$11 575</u> | <u>21%</u> | <u>\$2 463</u> | <u>\$14 039</u> |
| Auxiliary Building | | 445 | 27 | 63 | 19 | 1 959 | 93 | 2 606 | 21% | 546 | 3 152 |
| • Aux Bldg — Hot Machine Shop | | 17 | | 1 | 1 | 49 | | 68 | 24% | 16 | 84 |
| • Aux Bldg — Balance | | 429 | 27 | 62 | 18 | 1 909 | 93 | 2 537 | 21% | 530 | 3 068 |
| Control Building | | 9 | 1 | 1 | 1 | 40 | 1 | 54 | 21% | 11 | 65 |
| Fuel Building | | 391 | 295 | 46 | 15 | 743 | 195 | 1 685 | 25% | 417 | 2 101 |
| Radwaste Building | | 254 | 13 | 35 | 10 | 1 119 | 46 | 1 477 | 21% | 310 | 1 788 |
| • Radw Bldg — Rad & Personnel Tunnel | | 10 | | 1 | 1 | 24 | | 36 | 25% | 9 | 45 |
| • Radw Bldg — Radwaste Drum Storage | | 26 | 1 | 3 | 1 | 112 | 3 | 147 | 21% | 31 | 178 |
| • Radw Bldg — Balance | | 218 | 12 | 30 | 8 | 984 | 43 | 1 295 | 21% | 270 | 1 565 |
| Reactor Building | | 823 | 351 | 151 | 44 | 4 045 | 340 | 5 754 | 20% | 1 179 | 6 933 |
| Contingencies for Contaminated Structures | | 50% | 25% | 10% | 15% | 15% | 15% | | | | |

DECOMMISSIONING COST ESTIMATE UPDATE — LINE ITEM REPORT

Wolf Creek Generating Station 1996 SAFSTOR Option (Delayed)

| Cost (\$Thousands) | Activity: | Decon | Remove | Pack | Ship | Bury | Other | Total | Contingency | Estimate | |
|---|-------------------------------|----------------|-----------------|----------------|----------------|-----------------|-----------------|------------------|-------------|-----------------|------------------|
| Period 4: License Termination Survey | | | | | | | \$329 | \$329 | 15% | \$49 | \$379 |
| Contingencies (standard) | | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Subtotal Period 4 Activity Costs | | \$3,957 | \$21,247 | \$3,956 | \$5,134 | \$67,995 | \$23,390 | \$125,679 | 19% | \$23,617 | \$149,296 |
| Period 4: Undistributed Costs | | \$335 | | \$810 | \$384 | \$4,549 | \$13,303 | \$19,381 | 16% | \$3,158 | \$22,538 |
| a | Decon equipment | | | | | | 199 | 199 | 15% | 30 | 229 |
| b | Decon supplies | | | | | | 345 | 345 | 25% | 86 | 431 |
| c | DOC staff relocation expenses | | | | | | 891 | 891 | 15% | 134 | 1,025 |
| d | Process liquid radwaste | 335 | | 316 | 365 | 2,173 | | 3,190 | 18% | 580 | 3,770 |
| e | Insurance | | | | | | 734 | 734 | 10% | 73 | 807 |
| f | Property taxes | | | | | | 1,031 | 1,031 | 10% | 103 | 1,134 |
| g | Health physics supplies | | | | | | 2,384 | 2,384 | 25% | 596 | 2,980 |
| h | Heavy equipment rental | | | | | | 4,058 | 4,058 | 15% | 609 | 4,666 |
| i | Small tool allowance | | | | | | 342 | 342 | 15% | 51 | 393 |
| j | Pipe cutting equipment | | | | | | 619 | 619 | 15% | 93 | 712 |
| k | Disposal of DAW generated | | | 494 | 19 | 2,376 | | 2,888 | 14% | 409 | 3,297 |
| l | Plant energy budget | | | | | | 2,478 | 2,478 | 15% | 372 | 2,850 |
| m | NRC fees | | | | | | 221 | 221 | 10% | 22 | 244 |
| Contingencies for a, c, d, h, i, j, l, m | | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Contingencies for items b, g | | 50% | 15% | 10% | 15% | 15% | 25% | | | | |
| Contingencies for items e, f, n | | 50% | 15% | 10% | 15% | 15% | 10% | | | | |
| Period 4: Staff Costs | | | | | | | \$43,648 | \$43,648 | 15% | \$6,547 | \$50,196 |
| DOC staff costs | | | | | | | 11,973 | 11,973 | 15% | 1,796 | 13,769 |
| Utility staff costs | | | | | | | 31,676 | 31,676 | 15% | 4,751 | 36,427 |
| Contingencies (standard) | | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 4: Total Costs | | \$4,292 | \$21,247 | \$4,765 | \$5,518 | \$72,545 | \$80,341 | \$188,708 | 18% | \$33,321 | \$222,029 |
| Period 5: Removal of Major Equipment | | | \$306 | | | | | \$306 | 15% | \$46 | \$352 |
| Main turbine/generator | | | 74 | | | | | 74 | 15% | 11 | 85 |
| Main condensers | | | 232 | | | | | 232 | 15% | 35 | 267 |
| Contingencies (standard) | | | 50% | 15% | 10% | 15% | 15% | | | | |
| Period 5: Demolition of Remaining Site Bldgs | | | \$35,065 | | | | | \$35,065 | 15% | \$5,260 | \$40,325 |
| CP/WCGS Demolition Quantities | | | \$29,184 | | | | | \$29,184 | 15% | \$4,378 | \$33,562 |
| Auxiliary Building | | | 8,441 | | | | | 8,441 | 15% | 1,266 | 9,708 |
| • Aux Bldg — Hot Machine Shop | | | 24 | | | | | 24 | 15% | 4 | 27 |
| • Aux Bldg — Balance | | | 8,418 | | | | | 8,418 | 15% | 1,263 | 9,680 |
| Control Building | | | 2,835 | | | | | 2,835 | 15% | 425 | 3,260 |
| • Ctrl Bldg — Communications Corridor | | | 372 | | | | | 372 | 15% | 56 | 428 |
| • Ctrl Bldg — Balance | | | 2,463 | | | | | 2,463 | 15% | 369 | 2,832 |
| Diesel Generator Building | | | 428 | | | | | 428 | 15% | 64 | 492 |
| Fuel Building | | | 2,766 | | | | | 2,766 | 15% | 415 | 3,181 |
| Radwaste Building | | | 3,370 | | | | | 3,370 | 15% | 505 | 3,875 |
| • Radw Bldg — Rad & Personnel Tunnel | | | 18 | | | | | 18 | 15% | 3 | 21 |
| • Radw Bldg — Radwaste Drum Storage | | | 453 | | | | | 453 | 15% | 68 | 521 |
| • Radw Bldg — Balance | | | 2,898 | | | | | 2,898 | 15% | 435 | 3,333 |
| Reactor Building | | | 5,182 | | | | | 5,182 | 15% | 777 | 5,960 |
| Turbine Building | | | 6,162 | | | | | 6,162 | 15% | 924 | 7,087 |
| • Turb Bldg — Auxiliary Boiler | | | 25 | | | | | 25 | 15% | 4 | 28 |
| • Turb Bldg — Balance | | | 6,138 | | | | | 6,138 | 15% | 921 | 7,058 |
| Contingencies (standard) | | | 50% | 15% | 10% | 15% | 15% | | | | |
| Wolf Creek G.S. Demolition Quantities | | | \$5,881 | | | | | \$5,881 | 15% | \$882 | \$6,763 |
| Access Vaults | | | 53 | | | | | 53 | 15% | 8 | 61 |
| Administration | | | 298 | | | | | 298 | 15% | 45 | 343 |
| Chlorine Storage | | | 24 | | | | | 24 | 15% | 4 | 28 |
| Circulating Water Discharge Structure | | | 500 | | | | | 500 | 15% | 75 | 575 |
| Circulating Water Intake & Screenhouse | | | 1,180 | | | | | 1,180 | 15% | 177 | 1,357 |
| Covered Walkways | | | 11 | | | | | 11 | 15% | 2 | 13 |
| Essential Service Water System Pumphouse | | | 1,113 | | | | | 1,113 | 15% | 167 | 1,280 |
| Essential Service Water System Valve House | | | 17 | | | | | 17 | 15% | 3 | 20 |

DECOMMISSIONING COST ESTIMATE UPDATE — LINE ITEM REPORT

Wolf Creek Generating Station 1996 SAFSTOR Option (Delayed)

| Cost (\$Thousands) | Activity: | Decon | Remove | Pack | Ship | Bury | Other | Total | Contingency | Estimate | |
|---|-----------|----------------|-----------------|----------------|----------------|-----------------|------------------|------------------|-------------|-----------------|------------------|
| MMO Building | | | 245 | | | | | 245 | 15% | 37 | 282 |
| Miscellaneous Site Foundations | | | 533 | | | | | 533 | 15% | 80 | 613 |
| Miscellaneous Site Structures (32 structures) | | | 1 424 | | | | | 1 424 | 15% | 214 | 1 637 |
| Oil Separator and Waste Tank | | | 3 | | | | | 3 | 15% | 0 | 3 |
| Security Building/Guardhouse | | | 452 | | | | | 452 | 15% | 68 | 519 |
| Site Security Diesel Generator | | | 4 | | | | | 4 | 15% | 1 | 5 |
| Waste Water Treatment | | | 24 | | | | | 24 | 15% | 4 | 28 |
| Contingencies (standard) | | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 5: Site Closeout Activities | | | \$5 671 | | | | \$170 | \$5 841 | 15% | \$876 | \$6 718 |
| Remove rubble | | | 4 151 | | | | | 4 151 | 15% | 623 | 4 774 |
| Grade & landscape site | | | 1 520 | | | | | 1 520 | 15% | 228 | 1 748 |
| Final report to NRC | | | | | | | 170 | 170 | 15% | 26 | 196 |
| Contingencies (standard) | | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 5: Activity Costs | | | \$41 042 | | | | \$170 | \$41 213 | 15% | \$6 182 | \$47 394 |
| Period 5: Undistributed Costs | | | | | | | \$3 946 | \$3 946 | 14% | \$551 | \$4 497 |
| a Insurance | | | | | | | 207 | 207 | 10% | 21 | 227 |
| b Property taxes | | | | | | | 620 | 620 | 10% | 62 | 682 |
| c Heavy equipment rental | | | | | | | 2 633 | 2 633 | 15% | 395 | 3 027 |
| d Small tool allowance | | | | | | | 343 | 343 | 15% | 52 | 395 |
| e Plant energy budget | | | | | | | 144 | 144 | 15% | 22 | 166 |
| Contingencies for a, b | | 50% | 15% | 10% | 15% | 15% | 10% | | | | |
| Contingencies for c, d, e (standard) | | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 5: Staff Costs | | | | | | | \$17 109 | \$17 109 | 15% | \$2 566 | \$19 675 |
| DOC staff costs | | | | | | | 7 715 | 7 715 | 15% | 1 157 | 8 873 |
| Utility staff costs | | | | | | | 9 394 | 9 394 | 15% | 1 409 | 10 803 |
| Contingencies (standard) | | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 5: Total Costs | | | \$41 042 | | | | \$21 226 | \$62 268 | 15% | \$9 299 | \$71 567 |
| Total Cost to Decommission | | \$6 281 | \$62 575 | \$5 420 | \$5 792 | \$77 575 | \$429 444 | \$587 088 | 16% | \$93 048 | \$680 136 |

Input Variables Summary

| | | | Cost Component | Chg from '93: | 1996 | Avg Annl |
|--|-------------|-------------|-------------------------------------|---------------|--------------|-------------|
| Indirect Personnel Overhead [%] | 1996 | 1993 | WCNOC Staff — Management Labor | | 11.3% | 3.6% |
| Utility O&B (All Labor) | 71.0% | 64.6% | WCNOC Staff — Contract Labor | | 12.3% | 3.9% |
| DOC O&B (Administrative) | 90.0% | 90.0% | DOC Staff Labor | | 10.3% | 3.3% |
| DOC O&B (General Labor) | 40.0% | 40.0% | Security Guards Labor | | 12.3% | 3.9% |
| | | | Craft Labor | | 9.1% | 2.9% |
| | | | Specialty Consultant Labor | | 10.1% | 3.3% |
| Subcontractor Overhead and Profit [%] | | | Transportation Costs | | 3.1% | 1.0% |
| On Decommissioning Labor | 21.0% | 21.0% | Material and Equipment | | 9.0% | 2.9% |
| On Demolition Labor | 13.0% | 13.0% | NRC Fees | | 4.8% | 1.6% |
| On Equipment and Materials | 14.2% | 14.2% | Emergency Planning Fees | | 17.9% | 5.6% |
| | | | Other | | 6.3% | 2.1% |
| | | | Radwaste Burial | | 10.0% | 3.2% |
| | | | Radwaste Off-Site Processing | | 72.4% | 19.9% |
| Work Efficiencies [%] | | | Primary Liability Insurance | | 12.1% | 3.9% |
| Height Adjustment, 12' - 20' | 15.0% | 20.0% | Excess Property Insurance (NEIL II) | | -36.6% | -14.1% |
| Respiratory Protection Adjustment | 37.5% | 50.0% | Property Taxes (initial rate) | | 44.0% | 12.9% |
| Radiation/ALARA Adjustment | 25.0% | 32.0% | Electrical Energy | | -14.2% | -5.0% |
| Protective Clothing Adjustment | 22.5% | 30.0% | Oil | | 14.8% | 4.7% |
| Work Break Adjustment | 8.3% | 8.3% | Total Cost Estimate | | 12.3% | 3.9% |

APPENDIX C

DECOMMISSIONING COST ESTIMATE UPDATE — LINE ITEM REPORT

Wolf Creek Generating Station 1996 ENTOMB Option (Delayed)

| Cost (\$Thousands) | Activity: | Decon | Remove | Pack | Ship | Bury | Other | Total | Contingency | Estimate | |
|---|--|--------------|-------------|--------------|-------------|----------------|-----------------|-----------------|-------------|-----------------|-----------------|
| Period 1: Activity Costs | | | | | | | \$2 347 | \$2 347 | 15% | \$352 | \$2 699 |
| | Prepare prelim decommissioning plan | | | | | | 143 | 143 | 15% | 21 | 165 |
| | Review plant drawings and specs | | | | | | 506 | 506 | 15% | 76 | 582 |
| | End product description | | | | | | 110 | 110 | 15% | 17 | 127 |
| | Detailed by-product inventory | | | | | | 143 | 143 | 15% | 21 | 165 |
| | Define major work sequence | | | | | | 826 | 826 | 15% | 124 | 950 |
| | Perform safety analysis of operation | | | | | | 220 | 220 | 15% | 33 | 253 |
| | Perform safety analysis | | | | | | 341 | 341 | 15% | 51 | 393 |
| | Submit dismantling plan | | | | | | 57 | 57 | 15% | 9 | 66 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 1: Undistributed Costs | | \$115 | | \$282 | \$86 | \$1 200 | \$12 618 | \$14 300 | 15% | \$2 097 | \$16 398 |
| a | Decon equipment | | | | | | 213 | 213 | 15% | 32 | 245 |
| b | Decon supplies | | | | | | 154 | 154 | 25% | 39 | 193 |
| c | DOC staff relocation expenses | | | | | | 952 | 952 | 15% | 143 | 1 095 |
| d | Process liquid waste | 115 | | 59 | 79 | 341 | | 594 | 21% | 126 | 720 |
| e | Insurance | | | | | | 1 104 | 1 104 | 10% | 110 | 1 214 |
| f | Property taxes | | | | | | 2 097 | 2 097 | 10% | 210 | 2 306 |
| g | Health physics supplies | | | | | | 1 067 | 1 067 | 25% | 267 | 1 334 |
| i | Disposal of DAW generated | | | 223 | 7 | 858 | | 1 088 | 14% | 152 | 1 240 |
| j | Plant energy budget | | | | | | 6 315 | 6 315 | 15% | 947 | 7 263 |
| k | NRC fees | | | | | | 219 | 219 | 10% | 22 | 240 |
| l | Emergency planning fees | | | | | | 498 | 498 | 10% | 50 | 548 |
| | Contingencies for a, c, d, i, j (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| | Contingencies for b, g | 50% | 15% | 10% | 15% | 15% | 25% | | | | |
| | Contingencies for e, k, l | 50% | 15% | 10% | 15% | 15% | 10% | | | | |
| Period 1: Staff Costs | | | | | | | \$62 294 | \$62 294 | 15% | \$9 344 | \$71 638 |
| | DOC staff cost | | | | | | 5 251 | 5 251 | 15% | 788 | 6 038 |
| | Utility staff cost | | | | | | 57 043 | 57 043 | 15% | 8 556 | 65 600 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 1: Total Costs | | \$115 | | \$282 | \$86 | \$1 200 | \$77 260 | \$78 942 | 15% | \$11 794 | \$90 735 |
| Period 2: Activity Specifications | | | | | | | \$2 126 | \$2 126 | 15% | \$319 | \$2 445 |
| | Prepare plant & facilities for entombment | | | | | | 542 | 542 | 15% | 81 | 623 |
| | Plant systems | | | | | | 459 | 459 | 15% | 69 | 528 |
| | Reinforced concrete | | | | | | 176 | 176 | 15% | 26 | 203 |
| | Plant structures & buildings | | | | | | 344 | 344 | 15% | 52 | 395 |
| | Waste management | | | | | | 506 | 506 | 15% | 76 | 582 |
| | Facility & site closeout | | | | | | 99 | 99 | 15% | 15 | 114 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 2: Detailed Work Procedures | | | | | | | \$1 053 | \$1 053 | 15% | \$158 | \$1 210 |
| | Plant systems | | | | | | 521 | 521 | 15% | 78 | 599 |
| | Entombment structures | | | | | | 99 | 99 | 15% | 15 | 114 |
| | Facility closeout & dormancy | | | | | | 132 | 132 | 15% | 20 | 152 |
| | Auxiliary building | | | | | | 301 | 301 | 15% | 45 | 346 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 2: Additional Work Procedures | | | | | | | \$66 | \$66 | 15% | \$10 | \$76 |
| | Prepare dismantling sequence | | | | | | 55 | 55 | 15% | 8 | 63 |
| | Procure vacuum drying system | | | | | | 11 | 11 | 15% | 2 | 13 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 2: Rack Removal | | \$268 | \$44 | \$101 | \$28 | \$1 195 | \$924 | \$2 560 | 19% | \$477 | \$3 037 |
| | Remove spent fuel racks | 268 | 44 | 101 | 28 | 1 195 | 924 | 2 560 | 19% | 477 | 3 037 |
| | Contingencies | 50% | 25% | 10% | 15% | 15% | 15% | | | | |

DECOMMISSIONING COST ESTIMATE UPDATE — LINE ITEM REPORT

Wolf Creek Generating Station 1996 ENTOMB Option (Delayed)

| Cost (\$Thousands) | Activity: | Decon | Remove | Pack | Ship | Bury | Other | Total | Contingency | Estimate |
|--|-----------|---------|---------|-------|----------|----------|----------|-------|-------------|----------|
| Period 2: Disposal of Plant Systems External to Entombment Barrier | | | | | | | | | | |
| CP/WCGS Contam Components (System Specific) | \$1 302 | \$6 894 | \$2 295 | \$512 | \$18 410 | \$7 378 | \$36 791 | 18% | \$6 549 | \$43 340 |
| BG - Chemical & Volume Control | 420 | 602 | 205 | 56 | 2 548 | 665 | 4 496 | 19% | 871 | 5 367 |
| BL - Reactor Makeup Water | | 180 | 37 | 11 | 263 | 164 | 655 | 17% | 114 | 770 |
| BM - Steam Generator Blowdown | | 405 | 123 | 34 | 1 194 | 509 | 2 266 | 17% | 374 | 2 640 |
| BN - Borated Refueling Water Storage | | 193 | 66 | 11 | 421 | 316 | 1 008 | 17% | 167 | 1 175 |
| EC - Fuel Pool Cooling & Cleanup | | 294 | 84 | 21 | 770 | 357 | 1 527 | 17% | 254 | 1 782 |
| EJ - Residual Heat Removal | | 262 | 91 | 21 | 951 | 337 | 1 663 | 16% | 271 | 1 934 |
| EM - High Pressure Coolant Injection | | 205 | 68 | 20 | 615 | 285 | 1 193 | 16% | 196 | 1 389 |
| EP - Accumulator Safety Injection | | 104 | 32 | 7 | 225 | 144 | 513 | 17% | 86 | 598 |
| GG - Fuel Building HVAC | | 183 | 53 | 12 | 615 | 146 | 1 009 | 17% | 167 | 1 176 |
| GH - Radwaste Building HVAC | | 128 | 33 | 8 | 348 | 104 | 622 | 17% | 104 | 726 |
| GL - Auxiliary Building HVAC | | 332 | 55 | 14 | 344 | 253 | 998 | 18% | 180 | 1 178 |
| GN - Containment Cooling | | 392 | 123 | 26 | 1 328 | 371 | 2 241 | 16% | 369 | 2 610 |
| GR - Containment Atmospheric Control | | 7 | 27 | 5 | 447 | 23 | 509 | 15% | 76 | 585 |
| GS - Containment Hydrogen Control | | 33 | 23 | 6 | 176 | 101 | 338 | 16% | 53 | 391 |
| GT - Containment Purge HVAC | | 85 | 38 | 6 | 382 | 131 | 642 | 16% | 103 | 745 |
| HA - Gaseous Radwaste | | 192 | 84 | 18 | 608 | 189 | 1 091 | 16% | 179 | 1 269 |
| HB - Liquid Radwaste | 456 | 525 | 154 | 32 | 977 | 468 | 2 611 | 23% | 596 | 3 207 |
| HC - Solid Radwaste | | 306 | 246 | 32 | 1 081 | 343 | 2 008 | 16% | 320 | 2 328 |
| HD - Decontamination | | 51 | 56 | 7 | 159 | 104 | 377 | 16% | 59 | 436 |
| HE - Boron Recycle | | 324 | 84 | 21 | 520 | 326 | 1 276 | 17% | 220 | 1 495 |
| HF - Secondary Liquid Waste | 389 | 585 | 227 | 43 | 1 116 | 609 | 2 968 | 21% | 629 | 3 597 |
| KE - Fuel Handling & Storage, RPV Service | | 7 | 9 | 6 | 316 | | 338 | 15% | 51 | 389 |
| LD - Chemical & Detergent Waste | 37 | 89 | 23 | 6 | 147 | 101 | 402 | 20% | 81 | 483 |
| LF - Floor & Equipment Drains | | 1 297 | 248 | 65 | 1 593 | 1 152 | 4 356 | 18% | 771 | 5 126 |
| RM - Process Sampling & Analysis | | 71 | 50 | 15 | 764 | 147 | 1 048 | 15% | 162 | 1 210 |
| SJ - Nuclear Sampling | | 39 | 55 | 7 | 502 | 34 | 637 | 15% | 97 | 734 |
| Contingencies for Contaminated Systems | 50% | 25% | 10% | 15% | 15% | 15% | | | | |
| CP/WCGS Contam Comp (Non-System Specific) | | | | | | | | | | |
| Auxiliary Building | | \$898 | \$384 | \$123 | \$2 744 | \$2 066 | \$6 216 | 16% | \$1 003 | \$7 219 |
| Control Building | | 317 | 132 | 44 | 983 | 740 | 2 215 | 16% | 357 | 2 572 |
| Fuel Building | | 290 | 136 | 44 | 973 | 732 | 2 174 | 16% | 348 | 2 522 |
| Radwaste Building | | 46 | 19 | 6 | 151 | 114 | 337 | 16% | 54 | 391 |
| Reactor Building | | 136 | 59 | 18 | 397 | 300 | 910 | 16% | 147 | 1 057 |
| Contingencies for Contaminated Systems | 50% | 110 | 38 | 12 | 240 | 181 | 581 | 17% | 96 | 677 |
| Period 2: Erect Scaffolding for Syst Removal | | | | | | | | | | |
| Contingencies (standard) | 50% | \$855 | 15% | 10% | 15% | 15% | \$855 | 15% | \$128 | \$984 |
| Period 2: Decon of Site Bldgs Ext Entomb Barrier | | | | | | | | | | |
| Auxiliary Building | \$1 180 | \$369 | \$147 | \$45 | \$3 861 | \$335 | \$5 937 | 22% | \$1 333 | \$7 270 |
| · Aux Bldg — Hot Machine Shop | 476 | 30 | 64 | 19 | 1 959 | 93 | 2 640 | 21% | 562 | 3 203 |
| · Aux Bldg — Balance | 18 | | 1 | 1 | 49 | | 69 | 24% | 17 | 86 |
| Control Building | 458 | 30 | 63 | 18 | 1 909 | 93 | 2 571 | 21% | 546 | 3 117 |
| Fuel Building | 10 | 1 | 1 | 1 | 40 | 1 | 55 | 22% | 12 | 67 |
| Radwaste Building | 423 | 323 | 46 | 15 | 743 | 195 | 1 745 | 25% | 440 | 2 185 |
| · Radw Bldg — Rad & Personnel Tunnel | 271 | 15 | 36 | 10 | 1 119 | 46 | 1 496 | 21% | 319 | 1 815 |
| · Radw Bldg — Radwaste Drum Storage | 10 | | 1 | 1 | 24 | | 36 | 25% | 9 | 45 |
| · Radw Bldg — Balance | 27 | 1 | 3 | 1 | 112 | 3 | 148 | 21% | 32 | 179 |
| Contingencies for Contaminated Structures | 234 | 13 | 31 | 8 | 984 | 43 | 1 313 | 21% | 279 | 1 591 |
| Period 2: Entombment Operations | | | | | | | | | | |
| Prepare support equipment for storage | \$620 | | | | | \$443 | \$1 063 | 15% | \$159 | \$1 223 |
| Isolate systems & components at entombment | 125 | | | | | | 125 | 15% | 19 | 144 |
| Construct entombment barriers | 56 | | | | | | 56 | 15% | 8 | 64 |
| Install containment pressure equalizer line | 419 | | | | | | 419 | 15% | 63 | 482 |
| Interim survey prior to dormancy | 20 | | | | | | 20 | 15% | 3 | 23 |
| Prepare and submit interim report | | | | | | 316 | 316 | 15% | 47 | 364 |
| Contingencies (standard) | | | | | | 127 | 127 | 15% | 19 | 146 |
| Period 2: Activity Costs Subtotal | | | | | | | | | | |
| | \$2 750 | \$9 681 | \$2 928 | \$707 | \$26 210 | \$14 391 | \$56 667 | 18% | \$10 137 | \$66 803 |

DECOMMISSIONING COST ESTIMATE UPDATE — LINE ITEM REPORT

Wolf Creek Generating Station 1996 ENTOMB Option (Delayed)

| Cost (\$Thousands) | Activity: | Decon | Remove | Pack | Ship | Bury | Other | Total | Contingency | Estimate | |
|--|---|----------------|----------------|----------------|----------------|-----------------|------------------|------------------|-------------|-----------------|------------------|
| Period 2: Undistributed Costs | | \$243 | | \$689 | \$314 | \$3 504 | \$9 304 | \$14 053 | 16% | \$2 314 | \$16 367 |
| a | Decon equipment | | | | | | 199 | 199 | 15% | 30 | 229 |
| b | Decon supplies | | | | | | 289 | 289 | 25% | 72 | 361 |
| c | DOC staff relocation expenses | | | | | | 891 | 891 | 15% | 134 | 1 025 |
| d | Process liquid radwaste | 243 | | 271 | 302 | 1 897 | | 2 712 | 18% | 478 | 3 190 |
| e | Insurance | | | | | | 468 | 468 | 10% | 47 | 515 |
| f | Property taxes | | | | | | 888 | 888 | 10% | 89 | 977 |
| g | Health physics supplies | | | | | | 1 997 | 1 997 | 25% | 499 | 2 497 |
| h | Heavy equipment rental | | | | | | 1 130 | 1 130 | 15% | 170 | 1 300 |
| i | Small tool allowance | | | | | | 167 | 167 | 15% | 25 | 192 |
| j | Pipe cutting equipment | | | | | | 619 | 619 | 15% | 93 | 712 |
| l | Disposal of DAW generated | | | 418 | 13 | 1 607 | | 2 037 | 14% | 285 | 2 322 |
| m | Plant energy budget | | | | | | 2 548 | 2 548 | 15% | 382 | 2 930 |
| n | NRC fees | | | | | | 46 | 46 | 10% | 5 | 51 |
| o | Emergency planning fees | | | | | | 61 | 61 | 10% | 6 | 67 |
| | Contingencies for a, c, d, h, i, j, k, l, m | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| | Contingencies for Undistributed items b, g | 50% | 15% | 10% | 15% | 15% | 25% | | | | |
| | Contingencies for Undist items e, f, n, o | 50% | 15% | 10% | 15% | 15% | 10% | | | | |
| Period 2: Staff Costs | | | | | | | \$38 664 | \$38 664 | 15% | \$5 800 | \$44 463 |
| | DOC staff costs | | | | | | 9 381 | 9 381 | 15% | 1 407 | 10 789 |
| | Utility staff costs | | | | | | 29 282 | 29 282 | 15% | 4 392 | 33 675 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 2: Total Costs | | \$2 992 | \$9 681 | \$3 616 | \$1 021 | \$29 714 | \$62 359 | \$109 384 | 17% | \$18 250 | \$127 634 |
| Period 3: Entombed Annual Maintenance Cost | | | | | | | \$2 412 | \$2 412 | 15% | \$362 | \$2 773 |
| | Health physics supplies | | | | | | 7 | 7 | 15% | 1 | 8 |
| | Insurance | | | | | | 51 | 51 | 15% | 8 | 58 |
| | Property taxes | | | | | | 444 | 444 | 15% | 67 | 511 |
| | Maintenance supplies | | | | | | 55 | 55 | 15% | 8 | 63 |
| | Plant energy budget | | | | | | 89 | 89 | 15% | 13 | 102 |
| | NRC Fees | | | | | | 9 | 9 | 15% | 1 | 11 |
| | Site maintenance staff | | | | | | 1 757 | 1 757 | 15% | 264 | 2 020 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 3: Entombed Maintenance Cost — 49.6 yr | | | | | | | \$119 617 | \$119 617 | 15% | \$17 943 | \$137 560 |
| Period 4: Entombment Dismantling Activity Costs | | | | | | | \$1 114 | \$1 114 | 15% | \$167 | \$1 281 |
| | Review plant drawings and specifications | | | | | | 143 | 143 | 15% | 21 | 165 |
| | Submit for possession-only license | | | | | | 110 | 110 | 15% | 17 | 127 |
| | End product description | | | | | | 35 | 35 | 15% | 5 | 41 |
| | Detailed by-product inventory | | | | | | 165 | 165 | 15% | 25 | 190 |
| | Define major work sequence | | | | | | 110 | 110 | 15% | 17 | 127 |
| | Perform safety analysis of operation | | | | | | 220 | 220 | 15% | 33 | 253 |
| | Perform safety analysis of end product | | | | | | 220 | 220 | 15% | 33 | 253 |
| | Submit dismantling plan | | | | | | 110 | 110 | 15% | 17 | 127 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 4: Undistributed Costs | | | | | | | \$4 196 | \$4 196 | 16% | \$675 | \$4 871 |
| a | DOC staff relocation expenses | | | | | | 891 | 891 | 15% | 134 | 1 025 |
| b | Insurance | | | | | | 351 | 351 | 10% | 35 | 386 |
| c | Property taxes | | | | | | 666 | 666 | 10% | 67 | 733 |
| d | Health physics supplies | | | | | | 999 | 999 | 25% | 250 | 1 248 |
| e | Heavy equipment rental | | | | | | 246 | 246 | 15% | 37 | 283 |
| f | Plant energy budget | | | | | | 973 | 973 | 15% | 146 | 1 119 |
| g | NRC fees | | | | | | 70 | 70 | 10% | 7 | 77 |
| | Contingencies (standard) for items a, e, f | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| | Contingencies for Undistributed items d | 50% | 15% | 10% | 15% | 15% | 25% | | | | |
| | Contingencies for Undistributed items b, c, g | 50% | 15% | 10% | 15% | 15% | 10% | | | | |
| Period 4: Staff Costs | | | | | | | \$18 821 | \$18 821 | 15% | \$2 823 | \$21 644 |
| | DOC staff costs | | | | | | 4 802 | 4 802 | 15% | 720 | 5 523 |
| | Utility staff costs | | | | | | 14 019 | 14 019 | 15% | 2 103 | 16 122 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 4: Total Costs | | | | | | | \$24 131 | \$24 131 | 15% | \$3 665 | \$27 796 |

DECOMMISSIONING COST ESTIMATE UPDATE — LINE ITEM REPORT

Wolf Creek Generating Station 1996 ENTOMB Option (Delayed)

| Cost (\$Thousands) | Activity: | Decon | Remove | Pack | Ship | Bury | Other | Total | Contingency | Estimate | |
|--|--|--------------|----------------|--------------|----------------|-----------------|----------------|-----------------|-------------|-----------------|-----------------|
| Period 5: Activity Specifications | | | | | | | \$4 380 | \$4 380 | 15% | \$657 | \$5 037 |
| | Re-activate plant and temporary facilities | | | | | | 811 | 811 | 15% | 122 | 933 |
| | Plant systems | | | | | | 459 | 459 | 15% | 69 | 528 |
| | Reactor internals | | | | | | 782 | 782 | 15% | 117 | 899 |
| | Reactor vessel | | | | | | 716 | 716 | 15% | 107 | 823 |
| | Biological shield | | | | | | 55 | 55 | 15% | 8 | 63 |
| | Steam generators | | | | | | 344 | 344 | 15% | 52 | 395 |
| | Reinforced concrete | | | | | | 176 | 176 | 15% | 26 | 203 |
| | Turbine & condenser | | | | | | 88 | 88 | 15% | 13 | 101 |
| | Plant structures & buildings | | | | | | 344 | 344 | 15% | 52 | 395 |
| | Waste management | | | | | | 506 | 506 | 15% | 76 | 582 |
| | Facility & site closeout | | | | | | 99 | 99 | 15% | 15 | 114 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 5: Planning & Site Preparations | | | | | | | \$3 573 | \$3 573 | 15% | \$536 | \$4 109 |
| | Prepare dismantling sequence | | | | | | 264 | 264 | 15% | 40 | 304 |
| | Plant preparation & temporary services | | | | | | 1 635 | 1 635 | 15% | 245 | 1 880 |
| | Design water clean-up system | | | | | | 154 | 154 | 15% | 23 | 177 |
| | Rigging/CCES/tooling/etc. | | | | | | 1 384 | 1 384 | 15% | 208 | 1 592 |
| | Procure casks/liners & containers | | | | | | 135 | 135 | 15% | 20 | 156 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 5: Detailed Work Procedures | | | | | | | \$3 524 | \$3 524 | 15% | \$529 | \$4 053 |
| | Plant systems | | | | | | 521 | 521 | 15% | 78 | 599 |
| | Vessel head | | | | | | 275 | 275 | 15% | 41 | 317 |
| | Reactor internals | | | | | | 275 | 275 | 15% | 41 | 317 |
| | Remaining buildings | | | | | | 149 | 149 | 15% | 22 | 171 |
| | CRD cooling assembly | | | | | | 110 | 110 | 15% | 17 | 127 |
| | CRD housings & ICI tubes | | | | | | 110 | 110 | 15% | 17 | 127 |
| | Incore instrumentation | | | | | | 110 | 110 | 15% | 17 | 127 |
| | Reactor vessel | | | | | | 400 | 400 | 15% | 60 | 460 |
| | Facility closeout | | | | | | 132 | 132 | 15% | 20 | 152 |
| | Missile shields | | | | | | 50 | 50 | 15% | 7 | 57 |
| | Biological shield | | | | | | 132 | 132 | 15% | 20 | 152 |
| | Steam generators | | | | | | 506 | 506 | 15% | 76 | 582 |
| | Reinforced concrete | | | | | | 110 | 110 | 15% | 17 | 127 |
| | Turbine & condensers | | | | | | 344 | 344 | 15% | 52 | 395 |
| | Reactor building | | | | | | 301 | 301 | 15% | 45 | 346 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 5: Nuclear Steam Supply System Removal | | \$460 | \$6 879 | \$831 | \$4 365 | \$36 867 | | \$49 402 | 21% | \$10 308 | \$59 710 |
| a | Reactor coolant piping | 66 | 127 | 67 | 19 | 2 221 | | 2 499 | 16% | 407 | 2 907 |
| b | Pressurizer relief tank | 12 | 60 | 5 | 4 | 211 | | 292 | 18% | 54 | 346 |
| c | Reactor coolant pumps & motors | 25 | 38 | 35 | 43 | 3 753 | | 3 894 | 15% | 595 | 4 488 |
| d | Pressurizer | 24 | 29 | 4 | 11 | 1 376 | | 1 444 | 16% | 228 | 1 671 |
| e | Steam generators | 134 | 2 674 | 143 | 3 765 | 19 238 | | 25 953 | 16% | 4 200 | 30 154 |
| f | CRDMS/ICIS/service structure removal | 58 | 39 | 22 | 15 | 641 | | 774 | 18% | 139 | 913 |
| g | Reactor vessel internals | 41 | 1 058 | 270 | 237 | 6 666 | | 8 271 | 23% | 1 940 | 10 212 |
| h | Reactor vessel | 101 | 2 855 | 285 | 271 | 2 762 | | 6 274 | 44% | 2 745 | 9 019 |
| | Contingencies for reactor vessel & internals | 50% | 75% | 25% | 25% | 15% | 15% | | | | |
| | Contingencies for others | 50% | 25% | 10% | 15% | 15% | 25% | | | | |
| Period 5: Disposal of Plant Systems | | \$191 | \$5 632 | \$76 | \$19 | \$873 | \$240 | \$7 031 | 16% | \$1 130 | \$8 161 |
| CP/WCGS Contam Comp. (Syst. Specific) | | \$52 | \$172 | \$76 | \$19 | \$873 | \$240 | \$1 432 | 17% | \$242 | \$1 674 |
| | BB - Reactor Coolant | | 125 | 76 | 19 | 873 | 240 | 1 333 | 16% | 209 | 1 541 |
| | EN - Containment Spray | 52 | 47 | | | | | 100 | 33% | 33 | 133 |
| | Contingencies | 50% | 25% | 10% | 15% | 15% | 15% | | | | |

DECOMMISSIONING COST ESTIMATE UPDATE — LINE ITEM REPORT

Wolf Creek Generating Station 1996 ENTOMB Option (Delayed)

| Cost (\$Thousands) | Activity: | Decon | Remove | Pack | Ship | Bury | Other | Total | Contingency | Estimate | |
|---|---|-------|---------|------|------|------|-------|---------|-------------|----------|---------|
| CP/WCGS Non-Contam Comp (Syst Specific) | | \$47 | \$1 772 | | | | | \$1 818 | 16% | \$289 | \$2 108 |
| | AB - Main Steam | | 148 | | | | | 148 | 15% | 22 | 170 |
| | AC - Main Turbine | | 139 | | | | | 139 | 15% | 21 | 160 |
| | AD - Condensate | | 141 | | | | | 141 | 15% | 21 | 162 |
| | AE - Feedwater | | 96 | | | | | 96 | 15% | 14 | 110 |
| | AF - Feedwater Htr Extraction, Drains, Vents | | 143 | | | | | 143 | 15% | 22 | 165 |
| | AK - Condensate Demineralizer | | 49 | | | | | 49 | 15% | 7 | 56 |
| | AL - Auxiliary Feedwater | | 21 | | | | | 21 | 15% | 3 | 24 |
| | AP - Condensate Storage & Transfer | | 41 | | | | | 41 | 15% | 6 | 48 |
| | AQ - Condensate & Feedwater Chem Addition | | 13 | | | | | 13 | 15% | 2 | 15 |
| | CA - Steam Seal | | 13 | | | | | 13 | 15% | 2 | 15 |
| | CB - Main Turbine Lube Oil | | 29 | | | | | 29 | 15% | 4 | 33 |
| | CC - Generator Hydrogen & CO2 | | 5 | | | | | 5 | 15% | 1 | 6 |
| | CD - Generator Seal Oil | | 7 | | | | | 7 | 15% | 1 | 9 |
| | CE - Stator Cooling Water | | 6 | | | | | 6 | 15% | 1 | 7 |
| | CF - Lube Oil Storage, Transfer, Purification | | 22 | | | | | 22 | 15% | 3 | 26 |
| | CG - Condenser Air Removal | | 17 | | | | | 17 | 15% | 3 | 20 |
| | CH - Main Turbine Control Oil | | 31 | | | | | 31 | 15% | 5 | 35 |
| | EB - Closed Cooling Water | | 34 | | | | | 34 | 15% | 5 | 39 |
| | EG - Component Cooling Water | | 142 | | | | | 142 | 15% | 21 | 164 |
| | EN - Containment Spray | 47 | 42 | | | | | 89 | 33% | 30 | 119 |
| | FA - Auxiliary Steam Generator | | 7 | | | | | 7 | 15% | 1 | 9 |
| | FB - Auxiliary Steam | | 69 | | | | | 69 | 15% | 10 | 79 |
| | FC - Auxiliary Turbines | | 33 | | | | | 33 | 15% | 5 | 38 |
| | FE - Auxiliary Steam Chemical Addition | | 3 | | | | | 3 | 15% | 0 | 4 |
| | GA - Plant Heating | | 74 | | | | | 74 | 15% | 11 | 86 |
| | GB - Central Chilled Water | | 54 | | | | | 54 | 15% | 8 | 62 |
| | GK - Control Building HVAC | | 156 | | | | | 156 | 15% | 23 | 180 |
| | GM - Diesel Generator Building HVAC | | 29 | | | | | 29 | 15% | 4 | 33 |
| | GP - Containment Integrated Leak Rate Test | | 6 | | | | | 6 | 15% | 1 | 7 |
| | JE - Emergency Fuel Oil | | 33 | | | | | 33 | 15% | 5 | 38 |
| | KJ - Standby Diesel Engine | | 107 | | | | | 107 | 15% | 16 | 123 |
| | LB - Roof Drains | | 58 | | | | | 58 | 15% | 9 | 67 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| WCGS Non-Contam Comp (System Specific) | | | \$2 111 | | | | | \$2 111 | 15% | \$317 | \$2 427 |
| | AN - Demineralized Water Storage & Transfe | | 43 | | | | | 43 | 15% | 6 | 50 |
| | AX - Acid Feed | | 20 | | | | | 20 | 15% | 3 | 23 |
| | CL - Chlorination | | 15 | | | | | 15 | 15% | 2 | 17 |
| | CO - Carbon Dioxide | | 4 | | | | | 4 | 15% | 1 | 5 |
| | CW - Circulating Water | | 200 | | | | | 200 | 15% | 30 | 230 |
| | CZ - Caustic Acid | | 3 | | | | | 3 | 15% | 0 | 4 |
| | DA - Circulating Water | | 207 | | | | | 207 | 15% | 31 | 238 |
| | DM - Equipment Drains | | 63 | | | | | 63 | 15% | 9 | 73 |
| | DO - Diesel Oil | | 1 | | | | | 1 | 15% | 0 | 1 |
| | EA - Service Water | | 66 | | | | | 66 | 15% | 10 | 76 |
| | EF - Essential Service Water | | 81 | | | | | 81 | 15% | 12 | 93 |
| | FO - Fuel Oil | | 15 | | | | | 15 | 15% | 2 | 17 |
| | FP - Fire Protection | | 160 | | | | | 160 | 15% | 24 | 184 |
| | GD - Essntl Svce Water Pmhpse Bldg HVAC | | 9 | | | | | 9 | 15% | 1 | 11 |
| | GE - Turbine Building HVAC | | 108 | | | | | 108 | 15% | 16 | 124 |
| | GF - Miscellaneous Building HVAC | | 35 | | | | | 35 | 15% | 5 | 40 |
| | HY - Hydrogen | | 6 | | | | | 6 | 15% | 1 | 7 |
| | KA - Compressed Air & Instrument | | 169 | | | | | 169 | 15% | 25 | 194 |
| | KB - Breathing Air | | 27 | | | | | 27 | 15% | 4 | 32 |
| | KC - Fire Protection | | 292 | | | | | 292 | 15% | 44 | 336 |
| | KD - Domestic Water | | 48 | | | | | 48 | 15% | 7 | 56 |
| | KH - Service Gas | | 19 | | | | | 19 | 15% | 3 | 22 |
| | LA - Sanitary Drains | | 14 | | | | | 14 | 15% | 2 | 16 |
| | LC - Yard Drains | | 2 | | | | | 2 | 15% | 0 | 2 |
| | LE - Oily Waste | | 103 | | | | | 103 | 15% | 15 | 119 |
| | NT - Nitrogen | | 4 | | | | | 4 | 15% | 1 | 5 |
| | OX - Oxygen | | 4 | | | | | 4 | 15% | 1 | 5 |
| | ST - Sewage Treatment | | 24 | | | | | 24 | 15% | 4 | 28 |
| | SW - Screen Wash | | 16 | | | | | 16 | 15% | 2 | 18 |
| | SZ - Service Air | | 50 | | | | | 50 | 15% | 7 | 57 |

DECOMMISSIONING COST ESTIMATE UPDATE — LINE ITEM REPORT

Wolf Creek Generating Station 1996 ENTOMB Option (Delayed)

| Cost (\$Thousands) | Activity: | Decon | Remove | Pack | Ship | Bury | Other | Total | Contingency | Estimate | |
|---|-----------|----------------|-----------------|----------------|----------------|-----------------|-----------------|-----------------|-------------|-----------------|-----------------|
| VA - I&C Shop HVAC | | | 3 | | | | | 3 | 15% | 0 | 4 |
| VB - I&C Shop Computer Room HVAC | | | 2 | | | | | 2 | 15% | 0 | 2 |
| VC - Health Physics Computer Room HVAC | | | 5 | | | | | 5 | 15% | 1 | 6 |
| VH - Circ Water & Makeup Water Scrubse Ve | | | 6 | | | | | 6 | 15% | 1 | 7 |
| VJ - Shop Bldg Machine Shop Area Ventilatio | | | 1 | | | | | 1 | 15% | 0 | 1 |
| VL - Shop Building HVAC | | | 2 | | | | | 2 | 15% | 0 | 2 |
| VS - Administration Building HVAC | | | 5 | | | | | 5 | 15% | 1 | 6 |
| VT - Technical Support Building HVAC | | | 2 | | | | | 2 | 15% | 0 | 2 |
| VV - Miscellaneous Building HVAC | | | 3 | | | | | 3 | 15% | 0 | 4 |
| VW - Waste Water Treatment Ventilation | | | 1 | | | | | 1 | 15% | 0 | 1 |
| WD - Domestic Water | | | 26 | | | | | 26 | 15% | 4 | 30 |
| WG - Gland Water & Motor Cooling Water | | | 18 | | | | | 18 | 15% | 3 | 21 |
| WL - Cooling Lake Makeup & Blowdown | | | 18 | | | | | 18 | 15% | 3 | 21 |
| WM - Makeup Demineralizer | | | 97 | | | | | 97 | 15% | 15 | 112 |
| WS - Plant Service Water | | | 86 | | | | | 86 | 15% | 13 | 99 |
| WT - Waste Water Treatment | | | 18 | | | | | 18 | 15% | 3 | 21 |
| WZ - Radioactive Liquid Waste | | | 5 | | | | | 5 | 15% | 1 | 6 |
| Contingencies (standard) | | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| CP/WCGS Decon-able Comp (Non-Syst Spec) | | \$92 | \$388 | | | | | \$480 | 22% | \$104 | \$584 |
| Auxiliary Building | | 33 | 143 | | | | | 176 | 22% | 38 | 213 |
| Control Building | | 34 | 131 | | | | | 165 | 22% | 37 | 202 |
| Fuel Building | | 3 | 17 | | | | | 20 | 21% | 4 | 24 |
| Radwaste Building | | 12 | 49 | | | | | 60 | 22% | 13 | 73 |
| Reactor Building | | 11 | 49 | | | | | 59 | 21% | 13 | 72 |
| Contingencies (standard) | | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| CP/WCGS Clean Comp (Non-Syst Specific) | | | \$1 189 | | | | | \$1 189 | 15% | \$178 | \$1 367 |
| Auxiliary Building | | | 428 | | | | | 428 | 15% | 64 | 492 |
| Control Building | | | 400 | | | | | 400 | 15% | 60 | 460 |
| Fuel Building | | | 55 | | | | | 55 | 15% | 8 | 63 |
| Radwaste Building | | | 162 | | | | | 162 | 15% | 24 | 186 |
| Reactor Building | | | 144 | | | | | 144 | 15% | 22 | 166 |
| Contingencies (standard) | | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 5: Erect Scaffolding for Syst Removal | | | \$62 | | | | | \$62 | 15% | \$9 | \$71 |
| Contingencies (standard) | | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 5: Decontamination of Site Buildings | | \$823 | \$351 | \$151 | \$44 | \$4 045 | \$340 | \$5 754 | 20% | \$1 179 | \$6 933 |
| Reactor Building | | 823 | 351 | 151 | 44 | 4 045 | 340 | 5 754 | 20% | 1 144 | 6 898 |
| Contingencies | | 50% | 25% | 10% | 15% | 15% | 15% | | | | |
| Period 5: License Termination Survey | | | | | | | \$329 | \$329 | 15% | \$49 | \$379 |
| Contingencies (standard) | | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 5: Total Activity Costs | | \$1 474 | \$12 924 | \$1 058 | \$4 427 | \$41 786 | \$12 386 | \$74 055 | 19% | \$14 397 | \$88 452 |
| Period 5: Undistributed Costs | | \$233 | | \$703 | \$180 | \$3 483 | \$14 087 | \$18 686 | 16% | \$3 055 | \$21 741 |
| a Decon equipment | | | | | | | 227 | 227 | 15% | 34 | 261 |
| b Decon supplies | | | | | | | 408 | 408 | 25% | 102 | 510 |
| c DOC staff relocation expenses | | | | | | | 1 015 | 1 015 | 15% | 152 | 1 167 |
| d Process liquid waste | | 233 | | 118 | 159 | 689 | | 1 199 | 21% | 255 | 1 454 |
| e Insurance | | | | | | | 870 | 870 | 10% | 87 | 956 |
| f Property taxes | | | | | | | 1 221 | 1 221 | 10% | 122 | 1 344 |
| g Health physics supplies | | | | | | | 2 825 | 2 825 | 25% | 706 | 3 531 |
| h Heavy equipment rental | | | | | | | 4 807 | 4 807 | 15% | 721 | 5 529 |
| i Small tool allowance | | | | | | | 221 | 221 | 15% | 33 | 254 |
| j Pipe cutting equipment | | | | | | | 705 | 705 | 15% | 106 | 811 |
| k Disposal of DAW generated | | | | 585 | 22 | 2 793 | | 3 400 | 14% | 481 | 3 881 |
| l Plant energy budget | | | | | | | 1 525 | 1 525 | 15% | 229 | 1 754 |
| m NRC fees | | | | | | | 263 | 263 | 10% | 26 | 289 |
| Contingencies (standard) for a c d e h i j k l | | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Contingencies for b, g | | 50% | 15% | 10% | 15% | 15% | 25% | | | | |
| Contingencies for e, f, m | | 50% | 15% | 10% | 15% | 15% | 10% | | | | |

DECOMMISSIONING COST ESTIMATE UPDATE — LINE ITEM REPORT

Wolf Creek Generating Station 1996 ENTOMB Option (Delayed)

| Cost (\$Thousands) | Activity: | Decon | Remove | Pack | Ship | Bury | Other | Total | Contingency | Estimate | |
|---|---|---------|----------|---------|---------|----------|----------|-----------|-------------|----------|-----------|
| Period 5: Staff Costs | | | | | | | \$48,399 | \$48,399 | 15% | \$7,260 | \$55,659 |
| | DOC staff costs | | | | | | 14,977 | 14,977 | 15% | 2,247 | 17,224 |
| | Utility staff costs | | | | | | 33,422 | 33,422 | 15% | 5,013 | 38,435 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 5: Total Cost | | \$1,707 | \$12,924 | \$1,761 | \$4,607 | \$45,268 | \$74,872 | \$141,140 | 18% | \$24,712 | \$165,851 |
| Period 6: Removal of Major Equipment | | | \$306 | | | | | \$306 | 15% | \$46 | \$352 |
| | Main turbine/generator | | 74 | | | | | 74 | 15% | 11 | 85 |
| | Main condensers | | 232 | | | | | 232 | 15% | 35 | 267 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 6: Demolition of Remaining Site Bldgs | | | \$35,065 | | | | | \$35,065 | 15% | \$5,260 | \$40,325 |
| CP/WCGS Demolition Quantities | | | \$29,184 | | | | | \$29,184 | 15% | \$4,378 | \$33,562 |
| | Auxiliary Building | | 8,441 | | | | | 8,441 | 15% | 1,266 | 9,708 |
| | • Aux Bldg — Hot Machine Shop | | 24 | | | | | 24 | 15% | 4 | 27 |
| | • Aux Bldg — Balance | | 8,418 | | | | | 8,418 | 15% | 1,263 | 9,680 |
| | Control Building | | 2,835 | | | | | 2,835 | 15% | 425 | 3,260 |
| | • Ctrl Bldg — Communications Corridor | | 372 | | | | | 372 | 15% | 56 | 428 |
| | • Ctrl Bldg — Balance | | 2,463 | | | | | 2,463 | 15% | 369 | 2,832 |
| | Diesel Generator Building | | 428 | | | | | 428 | 15% | 64 | 492 |
| | Fuel Building | | 2,766 | | | | | 2,766 | 15% | 415 | 3,181 |
| | Radwaste Building | | 3,370 | | | | | 3,370 | 15% | 505 | 3,875 |
| | • Radw Bldg — Rad & Personnel Tunnel | | 18 | | | | | 18 | 15% | 3 | 21 |
| | • Radw Bldg — Radwaste Drum Storage | | 453 | | | | | 453 | 15% | 68 | 521 |
| | • Radw Bldg — Balance | | 2,898 | | | | | 2,898 | 15% | 435 | 3,333 |
| | Reactor Building | | 5,182 | | | | | 5,182 | 15% | 777 | 5,960 |
| | Turbine Building | | 6,162 | | | | | 6,162 | 15% | 924 | 7,087 |
| | • Turb Bldg — Auxiliary Boiler | | 25 | | | | | 25 | 15% | 4 | 28 |
| | • Turb Bldg — Balance | | 6,138 | | | | | 6,138 | 15% | 921 | 7,058 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Wolf Creek G.S. Demolition Quantities | | | \$5,881 | | | | | \$5,881 | 15% | \$882 | \$6,763 |
| | Access Vaults | | 53 | | | | | 53 | 15% | 8 | 61 |
| | Administration | | 298 | | | | | 298 | 15% | 45 | 343 |
| | Chlorine Storage | | 24 | | | | | 24 | 15% | 4 | 28 |
| | Circulating Water Discharge Structure | | 500 | | | | | 500 | 15% | 75 | 575 |
| | Circulating Water Intake & Screenhouse | | 1,180 | | | | | 1,180 | 15% | 177 | 1,357 |
| | Covered Walkways | | 11 | | | | | 11 | 15% | 2 | 13 |
| | Essential Service Water System Pumphouse | | 1,113 | | | | | 1,113 | 15% | 167 | 1,280 |
| | Essential Service Water System Valve House | | 17 | | | | | 17 | 15% | 3 | 20 |
| | MMO Building | | 245 | | | | | 245 | 15% | 37 | 282 |
| | Miscellaneous Site Foundations | | 533 | | | | | 533 | 15% | 80 | 613 |
| | Miscellaneous Site Structures (32 structures) | | 1,424 | | | | | 1,424 | 15% | 214 | 1,637 |
| | Oil Separator and Waste Tank | | 3 | | | | | 3 | 15% | 0 | 3 |
| | Security Building/Guardhouse | | 452 | | | | | 452 | 15% | 68 | 519 |
| | Site Security Diesel Generator | | 4 | | | | | 4 | 15% | 1 | 5 |
| | Waste Water Treatment | | 24 | | | | | 24 | 15% | 4 | 28 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 6: Site Closeout Activities | | | \$5,671 | | | | \$170 | \$4,321 | 15% | \$648 | \$4,970 |
| | Remove rubble | | 4,151 | | | | | 4,151 | 15% | 623 | 4,774 |
| | Grade & landscape site | | 1,520 | | | | | | | | |
| | Final report to NRC | | | | | | 170 | 170 | 15% | 26 | 196 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 6: Activity Costs Subtotal | | | \$41,042 | | | | \$170 | \$39,692 | 15% | \$5,954 | \$45,646 |

DECOMMISSIONING COST ESTIMATE UPDATE — LINE ITEM REPORT

Wolf Creek Generating Station 1996 ENTOMB Option (Delayed)

| Cost (\$Thousands) | Activity: | Decon | Remove | Pack | Ship | Bury | Other | Total | Contingency | Estimate | |
|-------------------------------|--------------------------------------|---------|----------|---------|---------|----------|-----------|-----------|-------------|----------|-----------|
| Period 6: Undistributed Costs | | | | | | | \$3 938 | \$1 305 | 12% | \$155 | \$1 460 |
| a | Insurance | | | | | | 207 | 207 | 10% | 21 | 227 |
| b | Property taxes | | | | | | 620 | 620 | 10% | 62 | 682 |
| c | Heavy equipment rental | | | | | | 2 633 | | | | |
| d | Small tool allowance | | | | | | 343 | 343 | 15% | 52 | 395 |
| e | Plant energy budget | | | | | | 136 | 136 | 15% | 20 | 156 |
| | Contingencies for a, b | 50% | 15% | 10% | 15% | 15% | 10% | | | | |
| | Contingencies for c, d, e (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 6: Staff Costs | | | | | | | \$17 109 | \$17 109 | 15% | \$2 566 | \$19 675 |
| | DOC staff costs | | | | | | 7 715 | 7 715 | 15% | 1 157 | 8 873 |
| | Utility staff costs | | | | | | 9 394 | 9 394 | 15% | 1 409 | 10 803 |
| | Contingencies (standard) | 50% | 15% | 10% | 15% | 15% | 15% | | | | |
| Period 6: Total Costs | | | \$41 042 | | | | \$21 217 | \$58 107 | 15% | \$8 675 | \$66 782 |
| Total Cost to Decommission | | \$4 841 | \$64 007 | \$5 690 | \$5 747 | \$76 612 | \$381 595 | \$534 315 | 16% | \$85 517 | \$619 833 |

Input Variables Summary

| | | | Cost Component | Chg from '93: | 1996 | Avg Annl |
|--|-------|-------|-------------------------------------|---------------|--------|----------|
| Indirect Personnel Overhead [%] | | | WCNOC Staff — Management Labor | | 11.3% | 3.6% |
| | 1996 | 1993 | WCNOC Staff — Contract Labor | | 12.3% | 3.9% |
| Utility O&B (All Labor) | 71.0% | 64.6% | DOC Staff Labor | | 10.3% | 3.3% |
| DOC O&B (Administrative) | 90.0% | 90.0% | Security Guards Labor | | 12.3% | 3.9% |
| DOC O&B (General Labor) | 40.0% | 40.0% | Craft Labor | | 9.1% | 2.9% |
| Subcontractor Overhead and Profit [%] | | | Specialty Consultant Labor | | 10.1% | 3.3% |
| On Decommissioning Labor | 21.0% | 21.0% | Transportation Costs | | 3.1% | 1.0% |
| On Demolition Labor | 13.0% | 13.0% | Material and Equipment | | 9.0% | 2.9% |
| On Equipment and Materials | 14.2% | 14.2% | NRC Fees | | 4.8% | 1.6% |
| Work Efficiencies [%] | | | Emergency Planning Fees | | 17.9% | 5.6% |
| Height Adjustment, 12' - 20' | 15.0% | 20.0% | Other | | 6.3% | 2.1% |
| Respiratory Protection Adjustment | 37.5% | 50.0% | Radwaste Burial | | 10.0% | 3.2% |
| Radiation/ALARA Adjustment | 25.0% | 32.0% | Radwaste Off-Site Processing | | 72.4% | 19.9% |
| Protective Clothing Adjustment | 22.5% | 30.0% | Primary Liability Insurance | | 12.1% | 3.9% |
| Work Break Adjustment | 8.3% | 8.3% | Excess Property Insurance (NEIL II) | | -36.6% | -14.1% |
| | | | Property Taxes (initial rate) | | 44.0% | 12.9% |
| | | | Electrical Energy | | -14.2% | -5.0% |
| | | | Oil | | 14.8% | 4.7% |
| | | | Total Cost Estimate | | 11.3% | 3.6% |

APPENDIX D

Wolf Creek GS Decommissioning Cost Estimate

Input Variables and Ranges

September 1996


| Escalation Variables | Escalation Variables (Change From 1993 To 1996) | | | |
|-------------------------------|---|---------|------------|---------|
| | Actual | Minimum | MostLikely | Maximum |
| Utility Management Labor | 11.3% | | | |
| Utility Contract Labor | 12.3% | | | |
| DOC Staff Labor | | 9.8% | | 10.7% |
| Security Guard Labor | 12.3% | | | |
| Craft Labor | | 8.9% | | 9.3% |
| Specialty Consultant Labor | | 8.5% | | 11.7% |
| Transportation | | 0.090% | | 6.2% |
| Material and Equipment | | 7.0% | | 11.1% |
| NRC Fees | | -2.1% | | 11.8% |
| Emergency Planning Fees | | -8.9% | | 44.7% |
| Miscellaneous | | 6.2% | | 6.4% |
| Radwaste Burial | | -47.0% | 10.0% | 66.7% |
| Radwaste Processing | | 62.4% | 72.4% | 82.4% |
| Primary Liability Insurance | 12.1% | | | |
| Excess Property Insurance | -36.6% | | | |
| Property Taxes (initial rate) | 44.0% | | | |
| Electrical Energy | -14.2% | | | |
| Fuel Oil | | 4.8% | 14.8% | 24.8% |

| Indirect Personnel Overhead | Other Variables (Cost Adders) | | |
|-----------------------------|-------------------------------|------------|---------|
| | Minimum | MostLikely | Maximum |
| Utility O&B (All Labor) | 61.0% | 71.0% | 81.0% |
| DOC O&B (Administrative) | 80.0% | 90.0% | 100.0% |
| DOC O&B (General Labor) | 30.0% | 40.0% | 50.0% |

| Subcontractor Overhead and Profit | | | |
|-----------------------------------|-------|-------|-------|
| On Decommissioning Labor | 11.0% | 21.0% | 31.0% |
| On Demolition Labor | 3.0% | 13.0% | 23.0% |
| On Equipment and Materials | 4.2% | 14.2% | 24.2% |

| Work Efficiencies | | | |
|-----------------------------------|-------|------|-------|
| Height Adjustment, 12' - 20' | 10.0% | | 20.0% |
| Respiratory Protection Adjustment | 25.0% | | 50.0% |
| Radiation/ALARA Adjustment | 10.0% | | 40.0% |
| Protective Clothing Adjustment | 15.0% | | 30.0% |
| Work Break Adjustment | 0.0% | 8.3% | 16.7% |

Escalation Variables Summary Table — 1993 to 1996



Wolf Creek GS Decommissioning Cost Estimate

Input Variables and Ranges

September 1996

Escalation Variable

Source of Data or Basis of Change from 1993 to 1996 Cost Estimate

Utility Management Labor

| | |
|-------------|--------------------------------|
| Actual | in-house historical wages data |
| Minimum | - |
| Most Likely | - |
| Maximum | - |

Utility Contract Labor

| | |
|-------------|--------------------------------|
| Actual | in-house historical wages data |
| Minimum | - |
| Most Likely | - |
| Maximum | - |

DOC Staff Labor

| | |
|-------------|--|
| Actual | - |
| Minimum | Ref 1: Private industry workers, Professional specialty and technical occupations |
| Most Likely | - |
| Maximum | Ref 1: Private industry workers, Executive, administrative, and managerial occupations |

Security Guard Labor

| | |
|-------------|-----------------------------------|
| Actual | in-house historical contract data |
| Minimum | - |
| Most Likely | - |
| Maximum | - |

Craft Labor

| | |
|-------------|--|
| Actual | - |
| Minimum | Ref 2: Midwest (formerly North Central) |
| Most Likely | - |
| Maximum | Ref 1: Private industry workers, Blue collar workers - Handlers, equipment cleaners, helpers, and laborers |

Specialty Consultant Labor

| | |
|-------------|--|
| Actual | - |
| Minimum | lower limit of UE confidential in-house policy for consultants, based on Ref 3 |
| Most Likely | - |
| Maximum | upper limit of UE confidential in-house policy for consultants, based on Ref 3 |

Transportation

| | |
|-------------|---|
| Actual | - |
| Minimum | Ref 4: Railroads, line haul operations (code 4011) |
| Most Likely | - |
| Maximum | Ref 4: Trucking and courier services, except air (code 421) |

Material and Equipment

| | |
|-------------|---|
| Actual | - |
| Minimum | Ref 5: All commodities |
| Most Likely | - |
| Maximum | Ref 5: Chemical and allied products (code 06) |

NRC Fees

| | |
|-------------|--|
| Actual | - |
| Minimum | anticipated fees based on extrapolation of actual historical charges |
| Most Likely | - |
| Maximum | actual hourly rate charged for resident NRC inspector |

Wolf Creek GS Decommissioning Cost Estimate

Input Variables and Ranges

September 1996

Escalation Variable

Source of Data or Basis of Change from 1993 to 1996 Cost Estimate

Emergency Planning Fees

| | |
|-------------|--|
| Actual | - |
| Minimum | anticipated fees based on extrapolation of actual historical charges |
| Most Likely | - |
| Maximum | anticipated fees based on extrapolation of actual historical charges |

Miscellaneous

| | |
|-------------|---|
| Actual | - |
| Minimum | Ref 6: All commodities except farm products |
| Most Likely | - |
| Maximum | Ref 7: Total manufacturing |

Radwaste Burial

| | |
|-------------|---|
| Actual | - |
| Minimum | Ref 8: current low estimate for LLW compacts (\$160/ft ³) |
| Most Likely | current base fees for CNSI at Barnwell, South Carolina (\$330/ft ³) |
| Maximum | Ref 8: current high estimate for LLW compacts (\$500/ft ³) |

Radwaste Processing

| | |
|-------------|---|
| Actual | - |
| Minimum | most likely less 10% |
| Most Likely | Ref 8: current average for recycling (\$100/ft ³) |
| Maximum | most likely plus 10% |

Primary Liability Insurance

| | |
|-------------|-----------------------------------|
| Actual | current actual insurance premiums |
| Minimum | - |
| Most Likely | - |
| Maximum | - |

Excess Property Insurance

| | |
|-------------|-----------------------------------|
| Actual | current actual insurance premiums |
| Minimum | - |
| Most Likely | - |
| Maximum | - |

Property Taxes

| | |
|-------------|--|
| Actual | Owners' Tax Departments' estimate for decommissioning period |
| Minimum | - |
| Most Likely | - |
| Maximum | - |

Electrical Energy

| | |
|-------------|--|
| Actual | estimated current marginal replacement power costs with Wolf Creek offline |
| Minimum | - |
| Most Likely | - |
| Maximum | - |

Fuel Oil

| | |
|-------------|---------------------------|
| Actual | - |
| Minimum | most likely less 10% |
| Most Likely | based on 1996 actual cost |
| Maximum | most likely plus 10% |

Wolf Creek GS Decommissioning Cost Estimate

Input Variables and Ranges

September 1996

Indirect Personnel Overhead

Source of Data or Basis of Change from 1993 to 1996 Cost Estimate

Utility O&B (All Labor)

| | |
|-------------|-----------------------------|
| Actual | - |
| Minimum | most likely less 10% |
| Most Likely | based on Wolf Creek actuals |
| Maximum | most likely plus 10% |

DOC O&B (Administrative)

| | |
|-------------|--------------------------------------|
| Actual | - |
| Minimum | most likely less 10% |
| Most Likely | estimated in 1993 by TLG - no change |
| Maximum | most likely plus 10% |

DOC O&B (General Labor)

| | |
|-------------|--------------------------------------|
| Actual | - |
| Minimum | most likely less 10% |
| Most Likely | estimated in 1993 by TLG - no change |
| Maximum | most likely plus 10% |

Subcontractor Overhead and Profit

On Decommissioning Labor

| | |
|-------------|--------------------------------------|
| Actual | - |
| Minimum | most likely less 10% |
| Most Likely | estimated in 1993 by TLG - no change |
| Maximum | most likely plus 10% |

On Demolition Labor

| | |
|-------------|--------------------------------------|
| Actual | - |
| Minimum | most likely less 10% |
| Most Likely | estimated in 1993 by TLG - no change |
| Maximum | most likely plus 10% |

On Equipment and Materials

| | |
|-------------|--------------------------------------|
| Actual | - |
| Minimum | most likely less 10% |
| Most Likely | estimated in 1993 by TLG - no change |
| Maximum | most likely plus 10% |

Wolf Creek GS Decommissioning Cost Estimate

Input Variables and Ranges

September 1996

Work Efficiencies

Source of Data or Basis of Change from 1993 to 1996 Cost Estimate

Height Adjustment, 12' - 20'

| | |
|-------------|--------------------------|
| Actual | - |
| Minimum | AIF/NESP-036 lower limit |
| Most Likely | - |
| Maximum | AIF/NESP-036 upper limit |

Respiratory Protection Adjustment

| | |
|-------------|--------------------------|
| Actual | - |
| Minimum | AIF/NESP-036 lower limit |
| Most Likely | - |
| Maximum | AIF/NESP-036 upper limit |

Radiation/ALARA Adjustment

| | |
|-------------|--------------------------|
| Actual | - |
| Minimum | AIF/NESP-036 lower limit |
| Most Likely | - |
| Maximum | AIF/NESP-036 upper limit |

Protective Clothing Adjustment

| | |
|-------------|--------------------------|
| Actual | - |
| Minimum | AIF/NESP-036 lower limit |
| Most Likely | - |
| Maximum | AIF/NESP-036 upper limit |

Work Break Adjustment

| | |
|-------------|--|
| Actual | - |
| Minimum | most likely less 10% (or zero, whichever is higher) |
| Most Likely | AIF/NESP-036 figure |
| Maximum | most likely plus 10% (or double, whichever is lower) |

NOTE: TLG used the upper limit for these work efficiency adjustments in their 1993 study.

References

- | | |
|-------|--|
| Ref 1 | Monthly Labor Review, Table 21 - Employment Cost Index, Compensation, by occupation and industry group |
| Ref 2 | Monthly Labor Review, Table 24 - Employment Cost Index, Compensation, Workers, By Region |
| Ref 3 | Consumer Price Index, Table 6 - CPI for Urban Wage Earners and Clerical Workers (CPI-W): U. S. city average, by expenditure category and commodity and service group, All items. |
| Ref 4 | Producer Price Indexes, Table 5 |
| Ref 5 | Producer Price Indexes, Table 6 |
| Ref 6 | Producer Price Indexes, Table 8 |
| Ref 7 | Producer Price Indexes, Table 4 |
| Ref 8 | "Trends in Decommissioning Costs — A Five-Year Retrospective", a paper delivered by John Carlson, TLG Services, Inc. Tuesday afternoon, April 16, 1996 ANS Topical Meeting on D&D, Chicago, Illinois |

NOTE: June 1993 and June 1996 data are used for references 1 through 7.

APPENDIX E

DECOMMISSIONING COST STUDY

for the

**WOLF CREEK
GENERATING STATION**

Prepared for the

WOLF CREEK NUCLEAR OPERATING CORPORATION

August 1993

prepared by

TLG Engineering, Inc.

for

TLG Services, Inc.

Bridgewater, Connecticut

TABLE OF CONTENTS

| | PAGE |
|--|------|
| REVISION LOG | iii |
| EXECUTIVE SUMMARY | iv |
| 1. SUMMARY | 1-1 |
| 2. INTRODUCTION | 2-1 |
| 2.1 Objective of Study | 2-1 |
| 2.2 Site Description | 2-1 |
| 2.3 Regulatory Guidance | 2-2 |
| 3. DECOMMISSIONING ALTERNATIVES | 3-1 |
| 3.1 DECON | 3-1 |
| 3.1.1 Period 1: Preparations | |
| 3.1.2 Period 2: Decommissioning Operations and License Termination | |
| 3.1.3 Period 3: Site Restoration | |
| 3.2 SAFSTOR | 3-7 |
| 3.2.1 Period 1: SAFSTOR Operations | |
| 3.2.2 Period 2: SAFSTOR Dormancy | |
| 3.2.3 Period 3 - 5: Deferred Decommissioning | |
| 3.3 ENTOMB | 3-12 |
| 3.3.1 Period 1: Preparations | |
| 3.3.2 Period 2: Entombment Operations | |
| 3.3.3 Period 3: Dormancy | |
| 3.3.4 Period 4 - 6: Deferred Decommissioning | |
| 4. COST ESTIMATE | 4-1 |
| 4.1 Basis of Estimate | 4-1 |
| 4.2 Methodology | 4-3 |
| 4.3 Site-Specific Considerations | 4-5 |
| 4.3.1 Spent Fuel Disposition | |
| 4.3.2 Major Component Removal | |
| 4.3.3 Transportation Methods | |
| 4.3.4 Site Conditions at Facility Closeout | |
| 4.4 Assumptions | 4-7 |
| 4.5 Cost Estimate Summary | 4-11 |
| 4.6 Decommissioning vs. Site Restoration | 4-12 |

| | | |
|-----|-------------------------------------|-----|
| 5. | SCHEDULE ESTIMATE | 5-1 |
| 5.1 | Schedule Estimate Assumptions | 5-1 |
| 5.2 | Project Schedule | 5-2 |
| 5.3 | Spent Fuel Schedule Impact | 5-2 |
| 6. | RADIOACTIVE WASTE | 6-1 |
| 7. | OCCUPATIONAL EXPOSURE | 7-1 |
| 8. | RESULTS | 8-1 |
| 9. | REFERENCES | 9-1 |

APPENDICES

| | |
|---|------------------------------|
| A | Unit Cost Factor Development |
| B | Unit Cost Factor Listing |
| C | Detailed Cost Analysis |

TABLES & FIGURES

| | | |
|------------|--|------|
| Table 1.1 | Cost and Schedule Estimate Summary | 1-4 |
| Table 4.1a | Summary of Decommissioning Costs - DECON | 4-13 |
| Table 4.1b | Summary of Decommissioning Costs - SAFSTOR | 4-14 |
| Table 4.1c | Summary of Decommissioning Costs - ENTOMB | 4-15 |
| Table 6.1 | Radioactive Waste Burial Volumes for Decommissioning | 6-2 |
| Table 8.1 | Summary of Decommissioning Costs | 8-2 |
| Figure 5.1 | DECON Activity Schedule | 5-3 |
| Figure 5.2 | Decommissioning Timeline | 5-6 |

REVISION LOG

| Rev. | Date | Description | Approval |
|-------------|----------------|-----------------------|-----------------|
| 0 | 8-24-93 | Original Issue | WAC |

EXECUTIVE SUMMARY

A site-specific cost estimate was performed for the decommissioning of the Wolf Creek Generating Station (WCGS) by TLG Services, Inc., of Bridgewater, Connecticut (TLG). This study addressed the decommissioning options to DECON, SAFSTOR or ENTOMB. Using the DECON alternative, work is anticipated to be completed by 2033, and the total costs for decommissioning WCGS is anticipated to be \$369,789,856 in 1993 dollars. For the deferred alternatives, work is anticipated to be completed in 2087, with total expenditures of \$605,733,632 and \$556,846,208 for the SAFSTOR and ENTOMB scenarios, respectively.

This study provides cost estimates for decommissioning WCGS under current requirements and based upon present-day technology. Using drawings and inventory documents, TLG and Wolf Creek Nuclear Operating Corporation (WCNOC) estimated quantities and volumes of the equipment and material removed during decommissioning. A unit cost factor was then applied to the volumes and quantities to estimate the removal of "activity dependent" costs. The period dependent costs were then determined from a detailed critical path schedule based on the removal activities.

The estimates considered that the final core discharge of spent fuel would be stored in the Fuel Building for approximately five years, following final shutdown in 2025, in accordance with the U.S. Department of Energy's (DOEs) minimum cooling requirements for acceptance. Decommissioning activities within the Fuel Building would be limited until the final core load, as well as the remainder of the spent fuel generated during plant operations, could be transferred to DOE's Waste Management System for deep geologic disposal. This is assumed, for this study, to be accomplished approximately five years following the cessation of plant operations.

This study includes the following additional considerations:

Burial of low-level radioactive wastes at a Central Interstate regional facility within 700 miles of the plant site. Base rates were provided by WCNOC along with information from currently operating facilities on disposal fee schedules.

Low-level waste classified as "greater than class C" packaged for disposal with the high-level spent nuclear fuel at a cost comparable to that envisioned for spent fuel.

Contingency was included in the estimate to address the many uncertainties that exist in a project of this nature. The analysis, prepared on a line item basis, used a range of contingencies selected to reflect conditions and uncertainties likely to be present at the time of decommissioning.

In addition to estimated costs, the report includes program schedules, scrap projections and estimates of occupational radiation exposures and low-level radioactive waste volumes inherent in the proposed decommissioning scenarios.

1. SUMMARY

The Wolf Creek Generating Station (WCGS) is located approximately 3.5 miles northeast of the town of Burlington, in Coffey County, Kansas, approximately 75 miles southwest of Kansas City, Kansas. The station is comprised of a single pressurized water reactor with supporting facilities. WCGS was designed and constructed under the standardization program SNUPPS (Standardized Nuclear Unit Power Plant System). WCGS is owned by Kansas Gas and Electric Company, Kansas City Power & Light Company and Kansas Electric Power Cooperative, Inc. (Owners). The Owners formed a wholly-owned subsidiary corporation, Wolf Creek Nuclear Operating Corporation (WCNOC), to act as their agent in performing all functions related to the operation, maintenance, repair, decommissioning and decontamination of WCGS.

This study provides estimates associated with the decommissioning of the nuclear unit at WCGS, following the conclusion of its operation: cost; schedule; waste generation/disposition; and radiation exposure. The study considers the decommissioning methods of DECON, SAFSTOR and ENTOMB.

DECON of a power reactor consists of the removal of all fuel assemblies and source material, radioactive fission and corrosion products, and all other radioactive materials having activities above Regulatory Guide 1.86, NUREG 5512 and other applicable release limits shortly after the cessation of plant operations. The facility operator may then have unrestricted use of the site with no requirement for a Nuclear Regulatory Commission (NRC) license. DECON is described in the rule on decommissioning issued by the NRC, "General Requirements for Decommissioning Nuclear Facilities." In this study, the site is cleared of all above-grade structures and site improvements, and the land returned to a state consistent with adjacent areas.

There are advantages to the DECON alternative. The alternative is less costly, in 1993 dollars, than the scenarios involving extended delays in the station dismantling. (The ultimate cost for any alternative will depend upon future economic factors such as inflation and policy factors such as future NRC regulations and waste policy decisions and actions.) DECON eliminates a potential long-term safety hazard, and those individuals familiar with the nuclear facility will still be available to support the dismantling effort. DECON also relieves the utility of long term obligations and liability for continuing maintenance of the property.

SAFSTOR places and maintains the facility in protective storage once spent fuel and source material are removed. Concurrently, the plant staff conducts general plant decontamination activities, radiation surveys, and the processing and removal of any

radioactive waste materials remaining from operations. In addition, a possession-only license is obtained and the security, surveillance and maintenance plans for the delay period implemented. Delayed dismantling (decontamination) activities are initiated such that license termination is accomplished within the 60 year time period set by the NRC. As with the DECON alternative, this study further assumes that the remainder of the reactor facility is dismantled and site restoration is performed.

The cost of the SAFSTOR alternative is increased by the cost incurred in maintaining the station in protective storage. However, SAFSTOR does have other advantages over the DECON alternative. Primarily, the dormancy period provides a period of decay for the residual radioactive material, resulting in lower personnel radiation exposures during dismantling, than are incurred in the DECON alternative, and potential savings in the cost of disposal for the waste volume generated during decommissioning operations.

ENTOMB also consists of placing the facility into protective storage. Initial activities consist of removing from the site all contaminated components, systems and structures outside the designated entombment boundary and sealing the remaining radioactivity within an entombment structure (usually the massive, concrete central portion of the containment or reactor building). This structure provides for isolation of the entire radioactive inventory on the site during the delay period. Additional activities involve the securing of a possession-only license, and the implementation of security and surveillance plans for the delay period. Dismantling activities are initiated after the delay or dormancy period and consist of radiation surveys, removal of the entombment structure and materials within it, processing and disposing of any remaining solid and liquid radioactive wastes followed by the restoration and release of the site as described in the DECON alternative.

While the disposal cost of spent fuel assemblies generated during plant operation is not considered a decommissioning expense, the presence of those assemblies on-site does have a bearing on the cost to decommission. This study recognizes that the current wet spent fuel storage facilities at WCGS will be active approximately five years after operations cease. This duration is based upon the Department of Energy's (DOE) minimum criteria for fuel turnover and transfer to a federal repository.

This study provides cost estimates for decommissioning WCGS under current requirements based upon present-day costs and available technology. Cost and schedule estimates presented herein are based upon the complete removal of all components and structures within the property lines, as the station is presently configured, except as noted within the body of this report. The total cost associated with decommissioning WCGS is shown in Table 1.1. The costs shown in Table 1.1 are summaries taken from the detailed cost tables in Appendix C and the scheduling analysis described in Section 5.

TABLE 1.1
WCGS
COST AND SCHEDULE ESTIMATE SUMMARY

| | Cost, 93\$ (thousands) | Schedule (months) |
|--------------------------|-----------------------------------|------------------------------|
| DECON | | |
| Total | 369,790 | 99.2 |
| SAFSTOR | | |
| Preparations | 27,038 | 12.0 |
| 55 year maintenance cost | 284,644 | 661.4 |
| Delayed dismantling | <u>294,052</u> | <u>70.3</u> |
| Total | 605,734 | 743.6 |
| ENTOMB | | |
| Preparations | 194,612 | 77.0 |
| 50 year maintenance cost | 129,568 | 595.2 |
| Delayed dismantling | <u>232,666</u> | <u>71.4</u> |
| Total | 556,846 | 743.6 |

2. INTRODUCTION

This analysis is designed to provide WCNOG with the information needed to prepare financial planning documents required by the NRC as well as state and local regulators. It is not a detailed engineering document, but a cost estimate prepared in advance of the detailed engineering preparations which will be necessary to carry out the decommissioning of WCGS. The costs estimated in this study should be considered in light of this qualification.

2.1 OBJECTIVE OF STUDY

The objective of this study is to estimate cost, schedule, occupational exposure and waste volume generated to decommission WCGS including all supporting facilities.

This study considers the license expiration date as March 11, 2025, 40 years from the date of issuance of the facility's low power operating license.

2.2 SITE DESCRIPTION

WCGS is located approximately 3.5 miles northeast of the town of Burlington, in Coffey County, Kansas, approximately 75 miles southwest of Kansas City, Kansas. The site is on the east side of a man-made lake formed by impounding Wolf Creek. The station is an 1150 MWe (nominal) pressurized water reactor plant with supporting facilities. The WCGS was designed and constructed under the standardization program SNUPPS.

The Nuclear Steam Supply Steam System (NSSS) was designed by Westinghouse Electric Corporation. The NSSS consists of a pressurized water reactor with four independent primary coolant loops, each of which contains a reactor coolant pump and a steam generator. An electrically heated pressurizer and connecting piping complete the system. The NSSS is rated at a thermal power level of 3425 MWt (3411 MWt reactor core plus, 14 MWt for reactor coolant pumps) with a corresponding turbine-generator gross output of 1186 MWe. The system is housed within a containment structure, a pre-stressed, post-tensioned concrete structure with cylindrical wall, a hemispherical dome, and a flat foundation slab. The wall and dome form a pre-stressed post-tensioned system. The inside surface of the structure is covered with a carbon steel liner, providing a leaktight membrane.

Heat produced in the reactor is converted to electrical energy by the Power Conversion System. This system converts the thermal energy of the steam into mechanical shaft power and then into electrical energy. The turbine-generator at WCGS is a tandem-compound, six-flow, four element, 1800 rpm unit. The unit consists of one high pressure and three low pressure turbine elements driving a directly coupled generator. The turbine is operated in a closed feedwater cycle which condenses the steam; the feedwater is returned to the steam generators. Heat rejected in the main condensers is removed by the Circulating Water system.

The circulating water system supplies cooling water from the plant's cooling water source to the main condenser, condensing the steam exhausted from the turbine. A large cooling lake provides the heat sink required for removal of waste heat in the power plant's thermal cycle.

2.3 REGULATORY GUIDANCE

The NRC provides decommissioning guidance in the rule "General Requirements for Decommissioning Nuclear Facilities" (Ref. 1) in addition to that previously set forth in Regulatory Guide 1.86 (Ref. 2). This new rule defines three decommissioning alternatives acceptable to the NRC, i.e., DECON, SAFSTOR, and ENTOMB.

DECON is defined by the NRC as "the alternative in which the equipment, structures, and portions of a facility and site containing radioactive contaminants are removed or decontaminated to a level that permits the property to be released for unrestricted use shortly after cessation of operations."

SAFSTOR is defined as "the alternative in which the nuclear facility is placed and maintained in a condition that allows the nuclear facility to be safely stored and subsequently decontaminated (deferred decontamination) to levels that permit release for unrestricted use."

ENTOMB is defined as "the alternative in which radioactive contaminants are encased in a structurally long-lived material, such as concrete; the entombed structure is appropriately maintained and continued surveillance is carried out until the radioactive material decays to a level permitting unrestricted release of the property." However, this process (as with SAFSTOR) is restricted in overall duration to 60 years and therefore limited in application unless it can be shown that a longer duration is necessary to protect health and safety.

3. DECOMMISSIONING ALTERNATIVE DESCRIPTIONS

Three specific decommissioning alternatives were examined for the WCGS study: DECON, SAFSTOR and ENTOMB.

The dormancy durations selected for use in the SAFSTOR and ENTOMB alternatives was based upon the maximum allowable interval (60 years) between cessation of operations and termination of the site license(s). Although the alternatives differ with respect to technique, process, cost, and schedule, the three alternatives attain the same result: removal of all radioactive materials from the site and ultimate release of the site for unrestricted and/or alternative use.

The following sections describe the basic activities necessary for each alternative. Although detailed procedures for each activity required are not provided, and actual sequences of work may vary, these activity descriptions may provide a basis for detailed engineering planning and scheduling at the time of decommissioning.

3.1 DECON

This alternative deals with the immediate removal of all radioactive materials from the site after the cessation of operations. This study does not address the cost of the removal of spent fuel from the site because such costs are assumed to be covered through WCNOG's contract with DOE. However, the study does consider the constraints that the presence of spent fuel on site may impose on other decommissioning activities. In addition to the removal of radioactive material, this study also assumes the dismantling of the remaining structures from the site, thereby permitting return of WCGS for other use.

3.1.1 Period 1 - Preparations

Prior to the commencement of decommissioning operations, detailed preparations are undertaken to provide a smooth transition from plant operations to site decommissioning activities. These preparations include engineering planning, surveys of plant areas to determine contamination levels, activation analyses of the vessel and vessel internals, as well as the assembly of a decommissioning management organization. Final planning for activities and writing of activity specifications and detailed procedures also begin at this time. Period 1 ends upon receipt of a decommissioning order from the NRC.

3.1.1.1 Engineering and Planning

Prior to the commencement of decommissioning operations, WCNOG will file an application for license termination accompanied by a Decommissioning Plan (DP) with the NRC describing how it will remove all radioactive components and essentially all radioactive material from WCGS. This request for dismantling of the reactor and termination of the facility's license should include a detailed plan describing the organization and program that will be used during the decommissioning of the facility. The plan will accomplish the required tasks within the As-Low-As-Reasonably-Achievable (ALARA as defined in 10 CFR 20) guidelines for protection of personnel from exposure to radioactive and non-radioactive contaminants. It will also clearly describe how WCNOG will continue to protect the health and safety of the public and the environment during the dismantling activity.

Prior to the start of decommissioning operations, work begins on the documentation and planning necessary for both licensing change applications and for accomplishing the work required. The development of a decommissioning organization within the utility is essential to this planning. This development includes identifying the staff requirements and commitment of key personnel.

In preparation for a change in license, regulatory criteria applicable to decommissioning are reviewed. The existing technical specifications are reviewed and modified to reflect decommissioning requirements and to delete non-applicable operating specifications. A DP is prepared during this time.

In addition, a supplemental environmental report will be required by the NRC and all applicable records (i.e., as-built or revised drawings and specifications, operating records, and site-specific background data) will be needed.

Much of the work in the development of the DP is also relevant to the development of the detailed engineering plans and procedures. This work includes:

- * Site preparation plans for decommissioning activities;
- * Detailed procedures and sequences for removal of systems and components;

- * Procedures for sectioning and disposing of the reactor vessel and its internals;
- * Plans for decontamination of structures and systems;
- * Design/procurement and testing of tooling and equipment;
- * Identification/selection of specialty contractors;
- * Procedures for removal and disposal of radioactive materials; and
- * Sequential planning of activities to minimize conflicts with simultaneous activities.

3.1.1.2 Site Preparations

Following final plant shutdown and in preparation for actual decommissioning activities, the following activities are initiated.

- * Prepare site support and storage facilities as required.
- * This study assumes that the spent fuel and source material generated over the operating life of the reactor will be removed from the site within a five year period following plant shutdown. This duration is based upon the minimum turnover requirements as established by DOE for spent fuel acceptance. While the fuel remains on site, the existing spent fuel handling facilities will remain operational. This activity may be carried out by existing plant personnel in accordance with standard operating technical specifications. Decommissioning operations are assumed to proceed around the Fuel Building, in essence to divorce the spent fuel issue from the balance of the decommissioning program. Following the spent fuel storage and shipment period, the remaining Fuel Building and its associated systems will be decontaminated and removed in like fashion as the balance of the WCGS site.
- * Clean all plant areas of loose contamination and process all liquid and solid wastes.
- * Conduct radiation surveys of work area contamination and general dose levels; major component, piping, and structure

dose levels (including the reactor vessel and its internals); internal piping contamination levels; and activation profiles from primary shield core samples.

- * Calculate residual by-product material inventory for plant components, structures and systems, and normalize neutron flux profiles from operational survey data for development of packaging and shipping requirements and decommissioning safety requirements.
- * Determine shipping container requirements for activated materials and fabricate such containers.
- * Develop procedures for occupational exposure control, control and release of liquid and gaseous effluents, control of solid radwaste, site security and emergency programs, and industrial safety.

3.1.2 Period 2 - Decommissioning Operations and License Termination

The dismantling procedures may begin upon receipt of the dismantling order from the NRC. For the DECON alternative the decommissioning operations involve the following:

- * Construct temporary facilities and arrange existing storage facilities to support the dismantling activities. These may include: changing rooms and contaminated laundry facilities for increased work force, protected and open laydown areas to facilitate equipment removal and shipping operations and additional roads to facilitate hauling and transportation.
- * Design, procure, and install water cleanup system for removal of cutting residues and crud deposits from the reactor vessel.
- * Design and fabricate special shielding and contamination control envelopes, special tooling and remotely operated equipment. Modify the refueling cavity to support segmentation activities and prepare rigging for segmentation and removal of piping sections and components, including the reactor vessel and its internals.
- * Procure required shipping casks, liners, and Low Specific Activity (LSA) containers from suppliers.

- * Conduct decontamination of components and piping systems as required. Remove, package and dispose of piping and components as they are no longer required to support the decommissioning process.
- * Remove and section control rod drive housings and instrumentation tubes from reactor vessel head.
- * Reassemble reactor vessel head and flange (following flange separation from vessel) for shipment and burial as its own container.
- * Segment upper and lower core support structures and in-core instrumentation and package in shielded casks. These operations are performed underwater by remote cutting equipment within a contamination control envelope. Ship and bury packaged items which meet 10 CFR 61 Class "C" requirements or less.
- * Provide additional spent fuel casks to accommodate 10 CFR 61 "Greater Than Class C" (GTCC) reactor vessel internals materials and components.
- * Remove the reactor coolant piping and pumps and package the piping in standard LSA containers. The reactor coolant pumps are sealed with steel plate so as to serve as their own containers. Ship and bury piping and pumps.
- * Segment/section the reactor vessel and package into shielded containers. The operation is performed remotely in air using a contamination control envelope. Sections are placed in containers under water, e.g., in the refueling cavity. Ship and bury packaged items.
- * Remove systems and associated components as they become non-essential to the support of vessel disposition, other decommissioning operations or worker health (e.g., decommissioning waste processing systems, electrical systems, HVAC systems, water systems).
- * Remove activated portions of the concrete biological shield and all accessible contaminated concrete (excluding steam generator and pressurizer cubicles). If dictated by the steam generator and

pressurizer removal scenarios, remove those portions of the associated cubicles necessary for access and component extraction.

- * Remove steam generators and pressurizer for shipment and burial. Decontaminate exterior surfaces, as required, and seal-weld all openings in steam generators and pressurizer. These components can serve as their own burial containers provided that all penetrations are properly sealed.
- * Pump low-density concrete grout into the primary side of the steam generator to control movement of loose contamination during transport. Pump concrete grout into the secondary side of the steam generator at the lower shells to provide additional shielding for transport.
- * Decontaminate all remaining containment structure areas including steam generator and pressurizer cubicles.
- * Decontaminate the Auxiliary Building as well as all contaminated outlying structures and facilities. This activity may necessitate the dismantling and disposition of most of the systems and components (both clean and contaminated) located within these buildings so as to facilitate surface decontamination and subsequent verification surveys required prior to obtaining release for demolition.
- * Decontaminate Fuel Building with the conclusion of spent fuel transfer operations. Conduct final radiation survey to ensure that all radioactive materials have been removed from the Fuel Building. This survey may coincide with final NRC site inspection.
- * Following notification by WCNOG of completion of the decontamination and disposal of components and materials from the facility, the NRC regional staff conducts an on-site survey to verify that the acceptable residual activity and contamination levels are satisfied. When the requirements are satisfied, the NRC can terminate the license for the station.

3.1.3 Period 3 - Site Restoration

Following completion of the decommissioning operations, site restoration activities may begin. Building foundations and portions of structures three feet below grade and lower are abandoned in place. The clean fill from above-grade structures demolition can be used to backfill voids created by the demolition process. Excess fill is removed from the site. Site areas affected by the dismantling activities are cleaned up and the plant area graded and landscaped as required. These activities include:

- * Perform demolition of the remaining portions of the containment structure and interior portions of the reactor building. Internal floors and walls are removed from the lower levels upward, using controlled blasting techniques. Concrete rubble and clean fill produced by demolition activities is used on-site to backfill voids. Suitable materials can be used on site for fill; otherwise the rubble is trucked off-site for disposal as construction debris.
- * Remaining buildings are then removed using conventional demolition techniques for above ground structures, including the Turbine Building, Auxiliary Building, Control Building, Diesel Generator Building, and other site structures.
- * Prepare the final dismantling program report.

3.2 SAFSTOR

The SAFSTOR decommissioning alternative provides a condition that ensures public health and safety from radioactive material remaining at the site without the need for extensive modifications to the facility. During the SAFSTOR period the facility is left intact and all structures are maintained in a sound condition. Systems not required to be operational for support of the spent fuel pool and surveillance purposes during the dormancy period are drained, de-energized, and secured. Minimal cleaning/removal of loose contamination and/or fixation and sealing of remaining contamination are performed. Access to contaminated areas is secured to provide controlled access for inspection and maintenance.

The engineering and planning requirements are similar to those for the DECON alternative, although a shorter time period is expected for these activities. Site preparations are also similar to those for the DECON

alternative. However, with the exception of required radiation surveys, the mobilization and preparation of site facilities is less extensive.

3.2.1 Period 1 - SAFSTOR Operations

Prior to commencement of decommissioning operations, WCNOG will file a Decommissioning Plan (DP) with the NRC describing how it will remove all radioactive components and essentially all radioactivity from the WCGS site. This request for eventual dismantling of the reactor and termination of the facility's license includes a detailed plan describing the organization and program that will be used during the decommissioning of the facility. The plan will accomplish the required tasks within the ALARA guidelines for protection of personnel from exposure to radioactive and non-radioactive contaminants. It will also clearly describe how WCNOG will continue to protect the health and safety of the public and the environment during the dismantling activities.

Following approval of the DP by the NRC, the NRC issues an order authorizing implementation. The DP may then be implemented by WCNOG. The DP includes spent fuel disposition, partial decontamination, followed by a delay period before the remaining radioactive components are removed. The NRC may amend the operating license to permit "Possession Only" after final plant shutdown. This amended license would remain in effect until final decontamination of the site and its release is complete.

The "Possession Only" license permits ownership and possession of fuel, by-product material and reactor components, but does not permit operation of the reactor. This license status, though permitting significant relief from the technical specifications, still requires adequate surveillance, monitoring and reporting.

After plant shutdown, modified technical specifications are implemented. Spent fuel and in-core source materials are isolated in the spent fuel storage facilities awaiting ultimate disposal or until they can be transferred to another facility. These steps may be carried out by plant personnel in accordance with standard operating procedures. The residual inventories of liquid and solid wastes are processed and removed and plant radiation surveys initiated.

The decommissioning activities for the SAFSTOR alternative are as follows:

- * Drain/de-energize/secure all non-contaminated systems not required to support decommissioning operations.
- * Dispose of contaminated filter elements and resin beds not required for processing wastes from decontamination activities.
- * Drain reactor vessel; internals will remain in place.
- * Drain/de-energize/secure all contaminated systems. Decontaminate as required.
- * Prepare lighting and alarm systems whose continued use is required. De-energize and/or secure portions of fire protection, electric power, and HVAC systems whose continued use is not required.
- * Install containment building pressure equalization line. This line should be provided with an absolute filter.
- * Clean loose surface contamination from building access pathways.
- * Perform final radiation survey of plant; post warning signs as appropriate.
- * Erect physical barriers and/or secure all access to radioactive or contaminated areas, except as required for controlled access for inspection and maintenance.
- * Spent fuel shipments to the DOE will continue throughout Period 1 and the first few years of the "dormancy" period.
- * Install security and surveillance monitoring equipment and relocate security fence around secured structures as required.
- * Nonradioactive structures, located outside the secured area, may be demolished. However, this study assumes that demolition would be delayed until after license termination.

- * Sections of the site outside the controlled area may be graded and landscaped as required. Part of this site area may be released for unrestricted use or for restricted use, depending on the terms of the possession-only license.
- * Prepare final decommissioning program report for submittal to NRC.

3.2.2 Period 2 - SAFSTOR Dormancy

Activities required during the planned dormancy period, for the SAFSTOR alternative, include a 24 hour guard force, preventive and corrective maintenance on security systems, area lighting, general building maintenance, heating and ventilation of buildings, routine radiological inspections of contaminated buildings, maintenance of structural integrity, and an environmental and radiation monitoring program.

Maintenance and equipment inspection activities are provided by a utility maintenance staff. Their duty is to maintain the structures in a safe condition, provide adequate lighting, ventilation, and heating, and perform periodic preventative maintenance on essential equipment.

An environmental surveillance program is carried out during the dormancy period to ensure that releases of radioactive material to the environment are controlled. Such releases are identified and quantified. Appropriate emergency procedures are established and initiated for releases that exceed prescribed limits. The environmental surveillance program will be a abbreviated version of that carried out during normal plant operations.

Primary physical security is provided by the security fence which must be maintained in good condition for the duration of this period. Fire and radiation alarms will be monitored.

3.2.3 Periods 3 - 5 Deferred Decommissioning

Deferred decommissioning involves decontamination and dismantling processes similar to those described in the DECON alternative. SAFSTOR Period 3 activities would correspond to the DECON Period 1 Planning Phase, Period 4 to the Period 2 Decommissioning Operations Phase, and Period 5 to the Period 3 Site Restoration Phase. Section 3.1

of this report delineates the activities associated with each phase of the decommissioning process.

Although the initial radiation levels due to Co60 will decrease significantly during the dormancy period, the internal components of the reactor vessel will still have sufficiently high radiation dose rates to require remote sectioning under water due to the presence of long-lived radionuclides such as Nb94 and Ni59. Therefore, the dismantling procedures described for the DECON alternative would be employed. Portions of the concrete shield will still be radioactive because of the presence of activated trace elements with long half-lives (Eu152 and Eu154) and will require controlled removal, packaging, and burial procedures. It is assumed that radioactive corrosion products on inner surfaces of piping and components will not have decayed to levels that will permit unrestricted use or allow conventional removal. These systems and components are surveyed as they are removed with disposition dependent upon the existing release criteria. No system in this study designated as contaminated in the DECON alternative is assumed to be releasable after the dormancy; they are removed and disposed of as contaminated material.

Because this alternative provides a period of decay of the residual radioactivity, lower personnel radiation exposures are incurred than with the DECON alternative. Many of the dismantling activities may employ manual techniques rather than remote procedures. Thus, dismantling operations can be simplified.

Following the completion of the decontamination and removal of radioactive components and materials from the facility, the NRC regional staff conducts an on-site survey to verify that the acceptable activity and contamination level requirements are satisfied. When the requirements are satisfied, NRC can terminate the license and any further NRC jurisdiction over the facility.

Site restoration activities may now be performed, similar to those for DECON, for structures still remaining on site. The site is graded and landscaped as required. A final decommissioning program completion report is then prepared.

3.3 ENTOMB

This alternative deals with creation of an entombment structure within the Reactor Building. An entombment structure is constructed within the containment structure to serve as an additional barrier in preventing contact with the reactor vessel and internals, steam generators, reactor coolant pumps and piping, and pressurizer, and the refueling pool area. This structure uses the existing biological shield concrete where possible; new concrete is added as necessary to provide a sealed reinforced concrete barrier around the primary system, preventing personnel access. Feedwater and steam piping to and from the steam generators is isolated. All radioactive material exterior to this structure is either moved within the entombment structure, or removed and packaged for off-site disposal. The decontaminated structures and systems and all other site structures and systems remain as is until after the dormancy period. At this time all remaining radioactive material within the entombment structure is removed.

In addition to removal of radioactivity, this study also assumes the removal of all remaining structures from the site; thereby ending WCNO's liability and permitting release of the WCGS site for alternative use.

3.3.1 Period 1: Preparations

Prior to the start of the decommissioning process detailed preparations are undertaken to provide a smooth transition from operations to decommissioning. These preparations include engineering planning, surveys of plant areas to determine contamination levels, activation analyses of the vessel and vessel internals, as well as the assembly of a decommissioning management organization. Upon final shutdown, more detailed surveys and benchmarking of calculated estimates are performed to validate results. Final planning for activities and writing of activity specifications and detailed procedures also begin at this time.

3.3.1.1 Engineering and Planning

WCNO will file a DP with the NRC describing how it will remove all radioactive components and essentially all radioactivity from the WCGS site. This request for eventual dismantling of the reactor and termination of the facility operating license should include a detailed plan describing the organization and program that will be used during the decommissioning of the facility. The plan should address how the major activities will be accomplished with the least possible personnel

exposure to radioactive and non-radioactive contaminants. It should also clearly describe how WCNOG will continue to protect the health and safety of the public and the environment during the dismantling activity.

The DP will address spent fuel disposition, partial decontamination and a delay period (assumed to be approximately 60 years for this study) before the remaining radioactive components are removed. The NRC may amend the operating license to permit "Possession Only" after final shutdown. This would pertain until final decontamination of the site and its release.

The "Possession Only" license permits ownership and possession of spent fuel, by-product material and reactor components, but does not permit operation of the reactor. This license status, though permitting significant relief from the technical specifications, still requires adequate surveillance, monitoring and reporting.

The goal in this method of decommissioning is to confine the highly radioactive or contaminated components (e.g., the reactor vessel and its internals) within concrete structures integral with the primary containment and other designated portions of the reactor building. This alternative includes the removal and disposal of all fuel assemblies, solid and liquid wastes, and any remaining radioactive materials, components, and structural materials exterior to the entombment structure(s). The engineering and planning requirements for this alternative are similar to those described for the DECON alternative. However, the DP should include descriptions for monitoring the structures/facility and the environment, with associated reports, security requirements, and any other activities necessary during the dormancy period.

3.3.1.2 Site Preparations

Site preparations for ENTOMB include most of the activities previously described for the DECON alternative. However, because ENTOMB is not as extensive as DECON, plant support and storage facility requirements may be less.

After final plant shutdown, modified technical specifications are implemented. Spent fuel and in-core source materials are isolated in the spent fuel storage facilities awaiting ultimate disposal or until they

can be transferred to another facility. These steps may be carried out by plant personnel in accordance with standard operating procedures.

An entombment structure is constructed within the containment structure to serve as an additional barrier in preventing contact with the reactor vessel and internals, steam generators, reactor coolant pumps and piping, pressurizer, and the refueling pool area. This structure uses the existing concrete where possible; new concrete is added as necessary to provide a sealed reinforced concrete barrier around the NSSS, preventing access. Except for draining and drying the reactor coolant system, only minimal work is performed on any component(s) within the entombment boundary prior to the dormancy period, thereby significantly reducing the occupational radiation exposure. Upon beginning the delayed dismantling portion of decommissioning, occupational exposure is reduced due to radioactive decay of the radionuclides during the dormancy period.

Liquid and solid wastes are processed and removed and plant radiation surveys conducted. The actual entombment program begins upon receipt of the Dismantling (ENTOMB) Order from the NRC.

Following approval of the DP by the NRC, the NRC will issue an order authorizing implementation. The DP may then be implemented by WCNO.

3.3.2 Period 2: Entombment Operations

The activities necessary to accomplish the entombment requirements are as follows:

- * Drain/de-energize/secure non-contaminated systems not required to support decommissioning operations.
- * Convert the existing spent fuel storage facilities into a self contained wet fuel storage facility and isolate the Fuel Building from the power block such that decommissioning operations can commence. This activity may be carried out by existing plant personnel in accordance with standard operating technical specifications. Decommissioning operations are assumed to be scheduled around the Fuel Building to the greatest extent possible such that the overall project schedule is optimized.

- * Dispose of contaminated filter elements and resin beds not required for processing wastes from decontamination activities.
- * Drain reactor vessel, steam generators and pressurizer. Cut, cap, and seal weld all piping at the entombment boundary interface.
- * Drain/de-energize/secure contaminated systems. Decontaminate, as required, and remove portions of these systems located outside entombment boundary. Package, ship, and bury removed systems; isolate remaining systems, if required, at the entombment boundary. Certain components can be moved or stored within the entombment structure.
- * Prepare lighting and security alarm systems required for continued use. De-energize and/or secure sections of the fire protection, electric power, and HVAC systems not required for continued use.
- * Remove all large contaminated components external to the entombment boundary(s). Where feasible, these components are decontaminated (in situ if possible, and therefore not removed) and released; otherwise the components are boxed/packaged and shipped for disposal as low specific activity (LSA) waste.
- * Complete the entombment barrier(s) by capping and filling all openings and penetrations with concrete.
- * Structural surfaces exterior to the entombment barrier should be cleaned/decontaminated to unrestricted levels. Equipment and normal personnel access hatches located outside the entombment barrier boundary remain operational with controlled access.
- * An entombment structure pressure equalization line equipped with an absolute filter should be installed.
- * Decommission all other radioactive structures and remove all radioactive materials for shipping and burial. Alternatively, selected contaminated material and non-combustible wastes may be transferred to storage within the entombment structure. Decontaminated structures other than the Reactor Building may remain intact with accesses properly secured against unauthorized entry.

- * Drain and decontaminate spent fuel pool once all assemblies have been removed from the site or to another storage facility on-site. Decontaminate Fuel Building and secure access.
- * Install security and surveillance monitoring equipment and relocate security fence around structures containing radioactive material as required.
- * Perform final radiation survey of plant and post warning signs as appropriate.
- * Prepare interim decommissioning program report for submittal to NRC.

Sections of the site outside the controlled area may be graded and landscaped as required and released for unrestricted use. All other site structures may remain intact.

3.3.3 Period 3: Dormancy

Activities required during the planned dormancy period, for the ENTOMB alternative, include routine inspection, preventive and corrective maintenance on safety systems, maintenance of structural integrity, and an environmental and radiation monitoring program. Maintenance and equipment inspection activities may also be distributed over a quarterly period in such a manner that all portions of the plant are inspected and maintained within that period.

An environmental surveillance program is carried out during the dormancy period to ensure that releases of radioactivity to the environment are controlled. Such releases should be identified and quantified. Appropriate emergency procedures should be established and initiated for releases that exceed prescribed limits. The environmental surveillance program is generally a modified/abbreviated version of that carried on during normal plant operations.

Security during the dormancy period is primarily conducted to prevent unauthorized entry and to protect the public from the consequences of their own actions. Security detection and notification systems used during plant operations are augmented by the installation of audible alarms. Additionally, silent alarms may be installed to alert off-site security personnel to trespass and fire. It is assumed for purposes of

this study that employment of full time on-site security personnel is required once fuel has been removed from the site. These personnel can provide periodic site checks and prompt response to alarms. Liaison with local law enforcement agencies is maintained and their assistance requested as necessary.

Primary physical security by the security fence must be maintained in good condition for the duration of this period. The facility is secured; exterior doors will be locked and alarmed for intrusion. Fire and radiation alarms are monitored continuously by security personnel.

The utility will designate a representative who will be responsible for controlling authorized entry into, and movement within, the facility. Interior access doors are also under his control. In addition, he is responsible for plant maintenance, surveillance programs and for providing notification and administrative reports for security breaches and taking appropriate actions.

3.3.4 Periods 4-6: Deferred Decommissioning

At the end of the dormancy period for the ENTOMB alternative, remaining structures will be completely dismantled. Basically, the same dismantling operations as those described for the DECON alternative are performed. Because this alternative provides a period of decay for the residual radioactivity, lower personnel radiation exposures are incurred than in the DECON alternative. Many of the dismantling activities may employ manual techniques rather than remote procedures, thus dismantling operations can be simplified.

Although the initial contact dose levels due to Co60 would decay significantly during the dormancy period, the internal components of the reactor vessel will still have sufficiently high radiation dose rates to require remote sectioning under water due to the presence of long-lived radionuclides such as Nb94, Ni59, and Ni63. In addition, the reactor vessel is segmented remotely for ALARA reasons. Therefore, the procedures described for the DECON alternative are employed. Portions of the concrete biological shield will still be radioactive because of the presence of activated trace elements with long half-lives and will require controlled removal, packaging, and burial procedures. It is unlikely that radioactive corrosion products on inner surfaces of piping and components will have decayed to levels that will permit unrestricted release or allow conventional removal. These systems and components

will have to be removed under controlled conditions and their interiors surveyed to determine their disposition as either radioactive waste or releasable as unrestricted scrap material.

Following notification by WCNOG of completion of the decontamination and disposal of components and materials from the facility, the NRC regional staff will conduct an on-site survey to verify that the acceptable activity and contamination levels are satisfied. When the requirements are satisfied, NRC can terminate the license and any further NRC jurisdiction over the facility.

Site restoration activities may now be performed, as are those for DECON, for those structures still remaining on site. The site is then graded and landscaped. A final decommissioning program completion report is prepared and the site released for unrestricted use.

4. COST ESTIMATE

A site-specific cost estimate was prepared for WCGS to account for the unique features of the NSSS, electric power generation systems, site buildings and structures. The basis for the estimate (including the source of information), methodology, site specific considerations, assumptions and total costs, are described in this section.

4.1 BASIS OF ESTIMATE

A site-specific cost estimate was developed using WCGS drawings and the inventory documents provided by WCNOG. These drawings and documents were used to develop the general arrangement of the facility and to determine estimates of building concrete volumes, steel quantities, and land area of the site restored. WCNOG developed the plant component inventory in conjunction with a similar effort by the Union Electric Company for the Callaway Plant nuclear unit.

This cost estimate is based on averages, such that the cost shown for the project is a reasonable approximation of what is expected to occur. Individual cost elements will vary and as such, this estimate, while a useful tool for cost control, may not provide sufficient detail for actual management of the decommissioning project and is not intended to replace detailed engineering or cost-benefit analyses.

Listed below are the major factors considered as the basis of the cost estimates:

1. WCGS drawings, including architectural and civil, were provided by WCNOG. The inventory of structural material, developed from these drawings, is essentially the same as that previously reported in WCNOG's response to the Missouri PSC stipulation (Ref. 3) for data relevant to estimating decommissioning costs. As mentioned, WCNOG developed the plant component data base which was also provided in response to the Missouri PSC stipulation. This inventory was used by TLG, with minor modification, to generate the cost estimates presented within this study.
2. Employee salary and craft labor rates for site administration, operations, construction and maintenance personnel were provided by WCNOG for positions identified by TLG Engineering.

3. Engineering services for such items as writing activity specifications, detailed procedures, detailed activation analyses, structural modifications, etc. are assumed to be provided by a Decommissioning Operations Contractor (DOC).
4. Material and equipment costs for conventional demolition and/or construction activities are taken from R.S. Means Construction Cost Data (Ref. 4).
5. Rates for shipping radioactive wastes were provided by Tri-State Motor Transit in published tariffs for this cargo (Ref. 5).
6. Disposition of radioactive wastes is a major contributor to the cost to decommissioning. The availability of burial sites is of national concern, with regional compacts being formed to provide adequate burial space for operating and planned reactors. In this study, a Central Interstate Compact burial facility is assumed (for cost estimating) to be located within 700 miles of the plant site. The cost for disposal in this, as yet undeveloped, site is based upon information from currently operating facilities along with the fee and surcharge structure used to generate total disposal costs (Ref. 6).
7. Costs in this estimate are in 1993 dollars. This estimate excludes interest and escalation. No present-value economic analysis is included.
8. Site property taxes were provided by WCNOG for inclusion in the total decommissioning cost.
9. This study does not address the removal or disposal of spent fuel from the site. The costs for such activities are assumed to be covered by WCNOG's contract with DOE and funded by DOE's 1 mill/kwhr surcharge. However, this study does consider the constraints that the presence of spent fuel on site may impose on other decommissioning activities due to the inability to ship spent fuel cooled less than five years to the DOE repository. Consequently, the Fuel Building at WCGS will not be available for decommissioning until approximately five years after the final shutdown.
10. This study presumes that any and all dry cask spent fuel storage canisters used to supplement plant storage capacity during operations will have been removed from the site prior to shutdown of the station.
11. The WCNOG staffing requirements during decommissioning vary with the level of effort associated with the various phases of the on-site storage of spent fuel.

12. In Period 1 of SAFSTOR/Delayed Dismantling, it was assumed that the level of effort required to accomplish the activities called for additional labor from off-site personnel. It is these personnel that are costed and accounted for in Period 1. The utility personnel perform the remaining activities as indicated in the detailed cost table (Table C-2) by the designation "a".
13. This study follows the principles of ALARA through the use of work duration adjustment factors which incorporate such items as radiological protection instruction, mock-up training, the use of respiratory protection and personnel protective clothing. These items lengthen a task's duration, which increases the costs and lengthens the schedule. ALARA planning is considered in the costs for engineering and planning, and in the development of activity specifications and detailed procedures.
14. This study is performed in accordance with the published study from the Atomic Industrial Forum/National Environmental Studies Project report AIF/NESP-036, "Guidelines for Producing Commercial Nuclear Power Plant Decommissioning Cost Estimates" (Ref. 7). The contents of those guidelines were prepared under the review of a task force consisting of representatives from utilities, state regulatory commissions, architect/engineering firms, the Federal Energy Regulatory Commission, the NRC, and the National Association of Regulatory Utility Commissioners.

4.2 METHODOLOGY

The methodology used to develop the cost estimates follows the basic approach presented in the AIF/NESP-036 study report and the US DOE "Decommissioning Handbook" (Ref. 8). These references utilize a unit cost factor method for estimating decommissioning activity costs to simplify the estimating calculations. Unit cost factors for concrete removal (\$/cubic yard) steel removal (\$/ton) and cutting costs (\$/in) were developed from the labor and material cost information provided by WCNO. With the item quantity (cubic yards, tons, inches, etc.) developed from plant drawings and inventory documents, the activity-dependent costs are estimated.

The unit cost factors used in this study reflect the latest available information about worker productivity in decommissioning, including the Shippingport Station Decommissioning Project, completed in 1989.

The activity duration critical path was used to determine the total decommissioning program schedule. The program schedule is used to determine the period-dependent costs for program management,

administration, field engineering, equipment rental, quality assurance and security. WCNOG provided typical salary and hourly rates for personnel associated with period-dependent costs. The costs for conventional demolition of nonradioactive structures, materials, backfill, landscaping and equipment rental were obtained from the "Building Construction Cost Data" published by R. S. Means (Ref. 4). Examples of unit cost factor development are presented in the AIF "Guidelines" study (Ref. 7), one of which is reproduced in Appendix A. Appendix B lists specific factors developed for the WCGS analyses.

The unit cost factor method provides a demonstrable basis for establishing reliable cost estimates. The detail of activities for labor costs (by craft) and equipment, and consumables costs provide assurance that cost elements have not been omitted. These detailed unit cost factors coupled with the plant-specific inventory of piping, components and structures provide a high degree of confidence in the reliability of the cost estimates.

"Contingencies" are defined in the American Association of Cost Engineers' Cost Engineers' Notebook (Ref. 9) as "specific provision for unforeseeable elements of cost within the defined project scope; particularly important where previous experience relating estimates and actual costs has shown that unforeseeable events which will increase costs are likely to occur." The cost elements in this estimate are based upon ideal conditions, therefore a contingency factor has been applied. As with any major project, examples of items which could occur that have not been accounted for in this estimate are changes, the effects of craft labor strikes, bad weather halting or slowing down waste shipments to the burial grounds, equipment/tool breakage, changes in the anticipated plant shutdown conditions, etc. In the AIF/NESP-036 study, (Ref. 7), the types of unforeseeable events that are likely to occur in decommissioning are discussed and guidelines are provided for percentage contingency in each category. Application of contingency is assigned on a line item basis for this estimate.

In the past, most cost studies were similar in the weight or contribution of the individual cost components as compared to the total cost. As such, average contingencies were consistently calculated in the 23-27% range for a standard estimate, with 25% used as a typical value for decommissioning cost estimates by TLG as well as Battelle Pacific Northwest Laboratories, FERC and other regulating agencies. However, more recent cost estimates have deviated in composition from one utility, and in some instances from one nuclear unit, to the next. With extremes in the cost implications from issues such as the post-operational storage of spent fuel, and projections for low-level radioactive waste disposal, the distribution of cost components has shifted within current

estimates. As such, the same contingency analysis that calculated an average 25% value five years ago, can now yield a significantly different result.

4.3 SITE-SPECIFIC CONSIDERATIONS

There are a number of site-specific considerations that affect the method for dismantling and removal of equipment from the site and the degree of restoration required. The cost impact of these considerations identified below is included in this cost study.

4.3.1 Spent Fuel Disposition

The spent fuel bundles stored in the spent fuel pool will be transferred to the Department of Energy as per the existing contract between WCNO and DOE. This is currently assumed to be completed by 2030, approximately five years following final plant shutdown. The decommissioning scenario has been constructed to permit freedom of the project from the restraints imposed by continued spent fuel storage and shipment. Once the spent fuel assemblies from the final core discharge have been transferred/shipped to DOE, the spent fuel storage and handling facilities are released for decommissioning.

4.3.2 Major Component Removal

The reactor pressure vessel and reactor internal components are segmented for disposal and shipped in shielded casks. Segmentation and packaging of the reactor vessel internals is performed in the refueling cavity where a turntable and remote cutter will be installed. The vessel is segmented in place using a mast-mounted cutter supported off the lower head and directed from a shielded work platform installed overhead in the canal. Shipping cask specifications and United States Department of Transportation (US DOT) regulations will dictate segmentation and packaging methodology; all packages designated meet current physical and radiological limitations and regulations. All cask shipments are made in US DOT-approved, currently available, truck casks. The closure head is disposed of intact and is modified for shipment as its own container and shipped to the burial site with the steam generators, reactor coolant pumps and pressurizer.

Reactor coolant piping is cut from the reactor vessel once the water level in the vessel (used for personnel shielding during dismantling and cutting operations in and around the vessel) is dropped below the nozzle

zone. The piping is boxed and shipped by shielded van to the disposal site.

The steam generators are assumed to be removed as follows: an auxiliary trolley placed on the Reactor Building polar crane rail is used in conjunction with an elevated runway with a trolley outside the equipment hatch to extract the generators. The equipment hatch may be enlarged, or a secondary opening created, to accommodate removal of the generators. Once outside the containment structure, the generators are moved to a temporary staging area on-site. Concrete grout is pumped into the steam generators to control movement of radioactive contamination during transport, and for radiation shielding. Additional carbon steel shields will be welded onto the outer surface of the steam generator as required to meet transportation requirements. Impact limiters will be placed on the generator package to provide protection against possible accidents during rail transport. The generators and other large components will then be transferred to high-capacity railcars. These railcars transport the generators (and other NSSS components) to the regional burial site. This study assumes that the burial site has reasonable rail access for handling these high-capacity railcars.

The main turbine is dismantled using conventional maintenance procedures. The turbine rotors and shafts are removed to a clean laydown area for disposal. The lower turbine casings are removed from their anchors by controlled demolition. The main condensers are segmented and transported to the laydown area for disposal as scrap along with the lower turbine casings.

4.3.3 Transportation Methods

TLG assumed that the NSSS components are moved by a combination of overland transporter and rail to the regional burial facility. These payloads include the reactor vessel closure head package, reactor coolant pumps, the steam generators and the pressurizer unit. In this study it is assumed that the steam generator units are removed sequentially and stored on-site in a temporary staging area. The generators are then rigged for loading onto the transports.

4.3.4 Site Conditions at Facility Closeout

It is assumed that the site is restored by regrading to conform to the adjacent landscape. Sufficient topsoil is to be placed to permit new growth of native vegetation.

4.4 ASSUMPTIONS

The following are the major assumptions made in the development of the cost estimates for WCGS.

1. WCNOG will hire a Decommissioning Operations Contractor (DOC). The DOC will provide sufficient staff to perform the preparatory demolition planning and scheduling, and manage the demolition efforts. Site security, health physics, quality assurance and overall site administration during decommissioning and demolition is provided by WCNOG. The demolition work is performed by the DOC, or a demolition subcontractor who will provide adequate staff, labor, equipment, materials and overhead to complete the demolition.
2. Only existing site structures and those presently in the construction stage are considered in the dismantling cost. Tentative designs and future site improvements are not considered.
3. A regional burial facility was assumed to exist within 700 miles of the WCGS site. This location was taken as the final destination for all low-level radioactive waste shipments from WCGS. The cost of burial at this yet-to-be-developed site was based upon information supplied by WCNOG, and from existing low-level radioactive waste disposal sites' published rate schedules.
4. No plant process system identified as being contaminated upon final shutdown will become releasable due to the decay period, i.e., there is no significant reduction in waste volume in delaying decommissioning.
5. The decommissioning activities will be performed in accordance with the current regulations which are assumed to be in place at the time of dismantling.
6. Nuclear liability insurance provides coverage for damage or injuries due to radiation exposure from equipment, material, etc. used during decom-

missioning. Nuclear liability insurance is phased out upon final decontamination of the site. WCNOG provided nuclear liability as well as property insurance premiums.

7. The NSSS (reactor vessel and reactor coolant systems) are chemically decontaminated using one chemical flush and two water rinses prior to segmentation. Typically, a decontamination factor (DF) of 10 is expected (Ref. 10). The NSSS flush will only be performed for the DECON mode.
8. Reactor vessel and internals packages conditions:

Any fuel cladding failure that has occurred or may occur during the lifetime of the plant is assumed:

a) to have released fission products at sufficiently low levels that the buildup of quantities of long-lived isotopes (e.g. cesium-137, strontium-90, or transuranics) has been prevented from reaching levels exceeding those which permit the major NSSS components to be shipped as LSA waste and burial within the requirements of 10 CFR 61 or the regional burial ground; or

b) to have necessitated systematic decontamination during the operating life of the plant and therefore the radionuclide levels are acceptable for transport as LSA waste and burial within the requirements of 10 CFR 61.

The Control Element Assemblies (CEA) are integral to a number of the spent fuel assemblies. Separate disposal of the CEAs is therefore not required, and not considered a decommissioning expense.

The curie contents of the vessel and internals at final shutdown are derived from those listed in NUREG/CR-3474 (Ref. 11). Actual estimates are derived from the Ci/gram values in NUREG/CR-3474 and adjusted for the different mass of WCGS components, projected operating life, as well as for different periods of decay. Additional short-lived isotopes were derived from NUREG/CR-0130 (Ref. 10) and NUREG/CR-0672 (Ref. 12) and benchmarked to the long-lived values from NUREG/CR-3474.

9. The reactor vessel and internals disposal costs are based on remote segmentation in-place, packaging in casks with shielding, and shipping by truck to the burial ground. A maximum normal road weight limit of

80,000 pounds is assumed for all truck shipments including cask shipments. This includes vessel segment(s), supplementary shielding, cask tie-downs and tractor trailer. The maximum curies per shipment assumed permissible are based upon the license limits of available shielded shipping casks. The number and curie content of vessel segments are selected to meet these limits.

10. Overland transport costs for the steam generators are based upon information provided by Reliance Trucking of Phoenix, Arizona. This company has handled the overland transport and installation of NSSS components for several plants.
11. Whenever possible, steam generators are removed sequentially and stored on site until ready to be moved. This scenario will consolidate shipping and reduce mobilization costs for the heavy haul vehicles.
12. WCNOG provides for the electrical power to be brought on-site required to demolish the plant.
13. Scrap generated during decommissioning is not included as a salvage credit line item in this study for two reasons: (1) the scrap value merely offsets the associated site removal and scrap reprocessing costs, and (2) a relatively low value of scrap exists in the market. Scrap processing and site removal costs are not included in the estimate.

Decommissioning will take place sufficiently far in the future that all equipment will be worn, obsolete and suitable for scrap as deadweight quantities only. No equipment is salvageable as used equipment.

14. WCNOG removes all items of furniture, tools, mobile equipment such as forklifts, trucks, bulldozers, other similar mobile equipment and other such items of personal property owned by WCNOG that is easily removed without the use of special equipment. The costs for these activities are presumed to be covered by the WCNOG transition staff.
15. Existing warehouses will remain for use by the demolition contractor and its subcontractors, as well as WCNOG. The warehouses will be dismantled as they are no longer needed to support the decommissioning program.

16. All contaminated piping, components and structures other than the reactor vessel and internals are assumed to meet US DOT limits for LSA material.
17. The WCNO staff will perform the following:
 - * Fuel oil tanks will be emptied. Tanks are cleaned by flushing or steam cleaning as required prior to disposal.
 - * Acid and caustic tanks are emptied through normal usage.
 - * Excess acid or caustic removed to support disposal at the storage container is returned to the vendor at no credit or cost to the project.
 - * Lubricating and transformer oils are drained and removed from site by a waste disposal vendor.
18. All structures and site improvements will be removed to three foot below local grade and the local terrain restored to the local grade level. The intake and discharge conduits will be sealed.
19. The perimeter fence is moved as appropriate to conform with the Site Security Plan in force at the various stages in the project.
20. All road and parking area base material is removed. Road and parking areas with asphalt surfacing or concrete are broken up and the asphalt and concrete used for backfill on site if needed. All gravel road and parking areas remain in place and the area covered with fill.
21. This study estimates that there will be some radioactive waste generated which is greater than 10 CFR 61 Class C quantities, resulting from disposal of the highly activated sections of the reactor vessel internals. This waste will most likely be disposed of as High Level Waste in the DOE's deep geological repository unless an alternative solution is approved by the NRC. The cost of disposal, unlike that for the spent fuel, is not covered by DOE's 1 mill/kWhr surcharge, and has been estimated from spent fuel equivalent disposal costs.
22. The existing electrical switchyard will remain after WCGS decommissioning in support of the WCNO electrical transmission and distribution system.

23. WCGS is assumed to have no significant amount of asbestos or inventories of hazardous and toxic materials at the time of final shutdown.
24. To the greatest extent practical, non-compactible LLW is recovered through decontamination to reduce the total volume of radioactive material buried. The components and materials deemed suitable for recovery include mid-size and large piping, pumps, mid-size and large valves, plate and structural steel, and other metallic components that are easily surveyed and decontaminated. The recovery fractions assigned for these components range from 70% to 90%. Materials and components that are unlikely to be recovered include concrete, small bore piping, heat exchangers, and dry active waste (DAW). Recovery is not attempted for these components or materials due to the difficulty of surveying the material, or the unlikelihood of success in decontamination.

The recovered waste that meets radioactive material release limits is released as clean scrap, requiring no further cost consideration. Material that does not meet release limits will be shipped as LLRW to the regional site for controlled burial.

Compactible DAW, such as booties, glove liners, respirator filter cartridges, shipping containers, HP survey materials, etc. are assumed to be drummed and compacted to 10% of their original volume.

25. The number of cask shipments out of the containments is expected to average three over a two week period. Non-cask shipments are limited to three shipments per week.

4.5 COST ESTIMATE SUMMARY

Summaries of the decommissioning alternative costs with annual expenditures are provided in Tables 4.1a, b and c. These costs were taken from the detailed cost tables in Appendix C.

The detailed cost tables (Appendix C) show the detailed listing and costs of major activities for each decommissioning scenario. Note that "Decon" as used in the headings of these tables, refers to decontamination. It should be noted that "Total" as used in the heading of tables, is the sum of Decon, Remove, Pack, Ship and Bury as well as other miscellaneous items not listed (such as engineering and preparations). Staff relocation expenses are those costs

associated with moving DOC/WCNOB personnel to the site; either for per diem allowance or for moving expenses.

4.6 DECOMMISSIONING vs. SITE RESTORATION

The total projected station cost of decommissioning WCGS, for the DECON mode is \$369,789,856. Of these total costs, the majority is directly attributable to the engineering and planning and the actual disposition of the residual radioactive material at WCGS. It should be noted, however, that a direct accounting of only these costs is not entirely accurate in portraying the actual cost of "decommissioning" as defined by the NRC and consideration must also be given to the methods of executing the decontamination processes.

Nuclear power plants are designed to contain the radioactive material generated during the normal operation of the facility. Accordingly, radioactive and potentially radioactive systems are located in shielded labyrinths, tunnels and pipe chases. This inaccessibility, while essential during operation, serves to impede decommissioning activities. Consequently, disposition of these components requires that, in many situations, additional access (and working space) be developed. This access is achieved by dismantling structures and components along the intended path of egress and in the immediate working area. In most instances, this material is non-radioactive and therefore not normally perceived as a necessary constituent in facility decontamination. However, failure to establish adequate working room will increase the residence times for decontamination and dismantling activities resulting in increases in the incurred occupational exposure.

The cost associated with the removal of non-contaminated and other releasable materials in support of the decommissioning process are commonly referred to as cascading costs. Cascading costs are identified in evaluating the dismantling processes involved in decommissioning WCGS and included with the license termination costs delineated in Appendix C. Consequently, for the utility to meet the intent of the NRC's definition of decommissioning, ("...release of the property for unrestricted use and termination of license") a cost of \$307,315,744 would be required to terminate the facility's license(s), or approximately 83.11% of the total cost. This percentage of the total station projected costs for license termination at WCGS meets the NRC's minimum requirements for decommissioning as delineated in title 10 of the Code of Federal Regulations, Part 50.75. The remaining costs would be required for site restoration as described in Section 3.

TABLE 4.1a
SUMMARY OF DECON DECOMMISSIONING COSTS
(Thousands of 1993 Dollars)

| Year | Period 1 | Period 2 | Period 3 | Totals |
|------|--------------|---------------|--------------|---------------|
| 2025 | \$10,623,119 | \$0 | | \$10,623,119 |
| 2026 | \$16,102,992 | \$0 | | \$16,102,992 |
| 2027 | \$25,963,805 | \$11,757,513 | | \$37,721,318 |
| 2028 | \$0 | \$71,720,829 | | \$71,720,829 |
| 2029 | \$0 | \$69,058,013 | | \$69,058,013 |
| 2030 | \$0 | \$68,796,377 | | \$68,796,377 |
| 2031 | \$0 | \$33,926,980 | \$15,978,271 | \$49,905,251 |
| 2032 | \$0 | \$0 | \$31,611,066 | \$31,611,066 |
| 2033 | \$0 | \$0 | \$14,250,891 | \$14,250,891 |
| | \$52,689,916 | \$255,259,712 | \$61,840,228 | \$369,789,856 |

TABLE 4.1b
SUMMARY OF SAFSTOR DECOMMISSIONING COSTS
(Thousands of 1993 Dollars)

| Year | Period 1 | Period 2 | Period 3 | Period 4 | Period 5 | Totals |
|-------------------|--------------|---------------|--------------|---------------|--------------|---------------|
| 2025 | \$21,866,696 | | | | | \$21,866,696 |
| 2026 | \$5,171,178 | \$7,167,411 | | | | \$12,338,589 |
| 2027 | | \$8,838,193 | | | | \$8,838,193 |
| 2028 | | \$8,838,193 | | | | \$8,838,193 |
| 2029 | | \$8,838,193 | | | | \$8,838,193 |
| 2030 | | \$5,647,590 | | | | \$5,647,590 |
| 2031 | | \$4,873,976 | | | | \$4,873,976 |
| 2032 through 2070 | | \$238,985,058 | | | | \$238,985,058 |
| 2081 | | \$1,455,516 | \$12,613,065 | | | \$14,068,581 |
| 2082 | | | \$17,072,305 | \$17,195,806 | | \$34,268,112 |
| 2083 | | | | \$85,916,926 | | \$85,916,926 |
| 2084 | | | | \$83,712,154 | | \$83,712,154 |
| 2085 | | | | \$15,595,689 | \$25,552,595 | \$41,148,284 |
| 2086 | | | | | \$31,489,056 | \$31,489,056 |
| 2087 | | | | | \$4,904,033 | \$4,904,033 |
| | \$27,037,874 | \$284,644,128 | \$29,685,370 | \$202,420,576 | \$61,945,684 | \$605,733,632 |

TABLE 4.1c
SUMMARY OF ENTOMB DECOMMISSIONING COSTS
(Thousands of 1993 Dollars)

| Year | Period 1 | Period 2 | Period 3 | Period 4 | Period 5 | Period 6 | Totals |
|-------------------|--------------|---------------|---------------|--------------|---------------|--------------|---------------|
| 2025 | \$10,456,451 | | | | | | \$10,456,451 |
| 2026 | \$13,571,138 | | | | | | \$13,571,138 |
| 2027 | \$13,534,059 | | | | | | \$13,534,059 |
| 2028 | \$21,650,171 | | | | | | \$21,650,171 |
| 2029 | \$20,650,573 | \$22,573,791 | | | | | \$43,224,364 |
| 2030 | | \$57,375,052 | | | | | \$57,375,052 |
| 2031 | | \$34,801,261 | \$1,022,868 | | | | \$35,824,129 |
| 2032 through 2080 | | | \$128,015,880 | | | | \$128,015,880 |
| 2081 | | | \$529,316 | \$12,988,483 | | | \$13,517,799 |
| 2082 | | | | \$13,557,709 | \$17,515,936 | | \$31,073,645 |
| 2083 | | | | | \$59,135,123 | | \$59,135,123 |
| 2084 | | | | | \$56,925,121 | | \$56,925,121 |
| 2085 | | | | | \$10,605,228 | \$25,549,445 | \$36,154,673 |
| 2086 | | | | | | \$31,485,174 | \$31,485,174 |
| 2087 | | | | | | \$4,903,429 | \$4,903,429 |
| | \$79,862,392 | \$114,750,104 | \$129,568,064 | \$26,546,192 | \$144,181,408 | \$61,938,048 | \$556,846,208 |

5. SCHEDULE ESTIMATE

The schedule for the decommissioning scenarios considered in this study follow the sequence presented in the AIF/NESP-036 study (Ref. 7) with minor changes to reflect recent experience and revised estimates. In addition, the scheduling has been revised to reflect spent fuel turnover (to DOE) requirements at shutdown.

TLG has prepared a schedule for decommissioning WCGS. The assumptions supporting this schedule are listed in Section 5.1. Figure 5.1 presents the schedule of key activities for the DECON alternative. Note that the activities listed in the schedules do not reflect a one to one correspondence with the activities in the cost tables in Appendix C, but reflect dividing some activities for clarity and combining others for convenience. A legend defining the schedule nomenclature and depictions is also included. The schedule was prepared using the "Microsoft Project" computer software (Ref. 13).

5.1 SCHEDULE ESTIMATE ASSUMPTIONS

The schedule estimate reflects the results of a precedence network developed for WCGS decommissioning activities, i.e., a PERT (Programmed Evaluation and Review Technique). The durations used in the precedence network reflect the actual manhour estimates from the cost tables in Appendix C. The schedule output is then adjusted by stretching certain activities over their slack range; other activities were pushed to the end of their slack period. The following assumptions were made in the development of the schedule for WCGS.

1. All work except vessel and internals removal activities is performed during an 8-hour workday, 5 days per week with no overtime. There are eleven paid holidays per year.
2. The Fuel Building will continue to serve as spent fuel storage until such time that all spent fuel has been removed from the site.
3. Vessel and internals removal activities are performed by using separate crews for different activities working on different shifts, with a corresponding backshift charge for the second shift.
4. Multiple crews work parallel activities to the maximum extent possible consistent with optimum efficiency, adequate access for cutting, removal and laydown space, and with the stringent safety measures necessary during demolition of heavy components and structures.

5. For plant systems removal, the systems with the longest removal durations in areas on the critical path are considered to determine the duration of the activity.

5.2 PROJECT SCHEDULE

The period-dependent costs presented in the cost tables in Appendix C are based upon the durations developed in the schedule for the three decommissioning alternatives. Durations are established between several milestones in each project period; these durations are used to establish a critical path for the entire project. In turn, the critical path duration for each period was used as the basis for determining the total costs for these items.

Project timelines for the DECON, SAFSTOR and ENTOMB alternatives are included in this section as Figure 5.2. Milestone dates are based on a 40 year plant operating life.

5.3 SPENT FUEL SCHEDULE IMPACT

The decommissioning scenarios allows for approximately five years of wet fuel storage in the spent fuel pool. Other decommissioning activities such as vessel segmentation, steam generator removals, reactor and auxiliary building system removals, etc. are performed in parallel with the spent fuel storage and shipment.

**FIGURE 5.1
DECON ACTIVITY SCHEDULE**




FIGURE 5.1
DECON ACTIVITY SCHEDULE
 (continued)




FIGURE 5.1
DECON ACTIVITY SCHEDULE
 (continued)






FIGURE 5.2
DECOMMISSIONING TIME LINE
(not to scale)


DECON:



SAFSTOR:



ENTOMB:



6. RADIOACTIVE WASTES

The ultimate goal of the decommissioning program is the removal all material from the site which would restrict its future use. This requires the removal of all material from the site which is in excess of applicable legal limits for radioactive contamination.

Under the Atomic Energy Act, the NRC is responsible for protecting the public from sources of ionizing radiation. Title 10 of the Code of Federal Regulations delineates the production, utilization and disposal of radioactive materials and processes. In particular, 10 CFR, Part 61 of controls the burial of radioactive material; Part 72 defines radioactive material

The radioactive waste volume generated during the various decommissioning programs at WCGS are shown by line activity in the cost tables in Appendix C. Waste volumes shown in Table 6.1 are quantified consistent with 10 CFR 61 classifications. The waste volumes shown are calculated based on the gross container volume to be shipped and buried in the controlled burial ground.

Most of the materials being transported for controlled burial are categorized as LSA material containing Type A quantities as defined in 49 CFR 173-178 (Ref. 14). The containers must be strong tight packages. For this study, commercially available steel containers are presumed to be used for piping, small components and concrete.

The reactor vessel and internals are categorized as large quantity shipments and, accordingly, must be shipped in reusable shielded casks with disposable liners. In this case, the liner volume is taken as the waste volume. Radioactive Waste classified as 10 CFR 61 Greater than Class C (GTCC) is assumed to be disposed of in the same manner as the spent fuel, i.e., at DOE's ultimate repository.

The waste volume attributed to site decontamination is primarily generated during Period 2 of DECON, Period 4 of SAFSTOR and Period 5 of ENTOMB. The low-level radioactive waste generated as a result of the decommissioning of WCGS is destined for disposal at the future Central Interstates regional burial facility. For cost estimating purposes, this study uses a projection provided by WCNOC and from an existing burial facility's published rate schedule.

Table 6.1 displays waste volumes associated with the decommissioning. No process system containing or handling radioactive substances at shutdown is presumed releasable as non-contaminated scrap metal because of the presence of long-lived radionuclides.

TABLE 6.1
RADIOACTIVE WASTE BURIAL VOLUMES FOR DECOMMISSIONING

| | Waste Class ¹ | Volume (Cubic feet) |
|----------------|-----------------------------|------------------------|
| DECON | A | 188,591 |
| | B | 12,935 |
| | C | 476 |
| | >C | <u>221</u> |
| | Total | 202,223 |
| SAFSTOR | A | 195,371 |
| | B | 8,649 |
| | C | 476 |
| | >C | <u>221</u> |
| | Total | 204,717 |
| ENTOMB | A | 191,026 |
| | B | 8,315 |
| | C | 476 |
| | >C | <u>221</u> |
| | Total | 200,038 |

¹ Waste is classified according to the requirements as delineated in Title 10 of the Code of Federal Regulations, Part 61.55

7. OCCUPATIONAL EXPOSURE

Estimates of occupational radiation exposure were developed by TLG. These estimates are scoping in nature and are performed to provide an upper bound to the exposure estimates. This bounding calculation is a check to see if NRC dose limitations are not exceeded in the cost study. It should be noted that the radiation exposure rates used to calculate the exposures shown in Appendix C are based on optimum conditions; factors such as plant age, maintenance and operating history could cause the expected exposure rates at the time of decommissioning to vary significantly.

Radiation doses to decommissioning workers are calculated as the product of the estimated radiation zone work force requirements and the radiation exposure rates estimated for each decommissioning task. The decommissioning occupational exposure estimates are based on the following assumptions:

1. Occupational exposure estimates include only the craft labor necessary for decontamination, removal and packaging activities as well as all required health physics personnel exposures in support of these activities. Casual exposures to the plant staff are not included in this estimate.
2. Personnel exposure to radiation is minimized by utilizing shielding and remote handling techniques and avoiding higher radiation fields when personnel presence is not necessary.
3. Local exposure rates near items such as tanks and pipes are reduced by chemical decontamination prior to work in that area.
4. Careful prompt accounting of accumulated radiation exposure is maintained to rapidly identify tasks causing excessive dose accumulation by workers so that corrective action can be taken.
5. Cobalt-60 is the primary contributor to radiation exposure. The reduction in personnel exposure from area and components during the activities performed after the SAFSTOR/ENTOMB dormancy period is assumed to be that of the reduction in Cobalt-60.
6. Exposures as the result of spent fuel storage activities are expected to be minimal and therefore are not included.

Implementation of the DECON alternative yields the higher occupational radiation exposure because the work is performed sooner after shutdown, without the benefit of any extended decay time for the radionuclides on site. The SAFSTOR alternative yields a lower cumulative dose, primarily due to the decay during dormancy and because almost all of the dismantling operations are performed after the dormancy period. However, additional dose is incurred in the ENTOMB alternative from the activities associated with removing contaminated material outside the entombment boundary, yielding a total cumulative dose higher than the SAFSTOR alternative yet still lower than DECON.

Typical field experience relative to recent cost studies performed by TLG indicate that actual field exposures are significantly less than TLG projections. This may be due to ignoring the dose reduction impact of the ALARA factors costed into the study.

8. RESULTS

Decommissioning technology is well established and the tools and equipment necessary to dismantle WCGS completely are available and have been demonstrated. The projected costs to decommission the plant, presuming the use of the DECON alternative, including the five year operation of the spent fuel pool, is \$369,789,856. This projected cost includes shipment of wastes and dismantled materials to a regional disposal site and demolition of the remaining site structures. The estimate reflects the site-specific features of WCGS and the projected cost of radioactive waste shipping and burial costs. An analysis of the major activities contributing to the total cost is shown in Table 8.1.

The decommissioning and utility staffs along with the removal activity combine to represent the majority of the cost to decommission WCGS. This is a direct result of the labor-intensive nature of the decommissioning process. Burial is the next largest cost component reflecting the costs associated with the development of new regional waste disposal facilities. Transportation costs are most sensitive to increases in fuel costs and distances to existing or new burial facilities. Removal costs are dependent on the degree of remotely operated equipment available in the future and the associated higher cost of that equipment versus the savings in labor costs.

This study for WCGS provides an estimate for decommissioning the site under current requirements based on present day costs and available technology. As additional dismantling experience on large reactors becomes available, cost estimates must be modified to reflect this experience. In addition, there are costs associated with decommissioning activities that historically increase at rates significantly greater than inflationary trends. For example, the cost of radioactive waste burial has increased rapidly in the last few years. It is therefore appropriate that this cost estimate be reviewed periodically, and updated/revised as required.

TABLE 8.1
SUMMARY OF DECOMMISSIONING COSTS

| Work Category | Costs 93\$ (thousands) | Percent of Total Costs |
|------------------------|-----------------------------------|-----------------------------------|
| DECON | | |
| Decontamination | 6,957 | 1.88 |
| Removal | 68,487 | 18.52 |
| Packaging | 5,599 | 1.51 |
| Shipping | 6,392 | 1.73 |
| Burial (off-site) | 81,180 | 21.95 |
| Decommissioning Staffs | 137,406 | 37.16 |
| Other * | <u>63,769</u> | <u>17.24</u> |
| Subtotal | 369,790 | 100.00 |
| SAFSTOR | | |
| Decontamination | 8,353 | 1.38 |
| Removal | 67,782 | 11.19 |
| Packaging | 5,295 | 0.87 |
| Shipping | 6,106 | 1.01 |
| Burial (off-site) | 79,884 | 13.19 |
| Decommissioning Staffs | 329,107 | 54.33 |
| Other * | <u>109,207</u> | <u>18.03</u> |
| Subtotal | 605,734 | 100.00 |
| ENTOMB | | |
| Decontamination | 6,276 | 1.13 |
| Removal | 68,886 | 12.37 |
| Packaging | 5,471 | 0.98 |
| Shipping | 6,055 | 1.09 |
| Burial (off-site) | 78,177 | 14.04 |
| Decommissioning Staffs | 281,676 | 50.58 |
| Other * | <u>110,306</u> | <u>19.81</u> |
| Subtotal | 556,846 | 100.00 |

* Other includes: engineering & preparations, property lease payments, insurance, off-site LLW recycling costs and plant energy budget.

9. REFERENCES

1. U.S. Code of Federal Regulations, Title 10, Parts 30, 40, 50, 51, 70 and 72 "General Requirements for Decommissioning Nuclear Facilities", Nuclear Regulatory Commission, Federal Register Volume 53, Number 123 (p 24018+), June 27, 1988.
2. U.S. Nuclear Regulatory Commission Regulatory Guide 1.86, "Termination of Operating Licenses for Nuclear Reactors", June, 1974.
3. "Response to Missouri PSC Stipulation for Data Relevant to Estimating Decommissioning Costs for WCNGS and Wolf Creek Generating Station", February 1993.
4. "Building Construction Cost Data 1990", Robert Snow Means Company, Inc., Kingston, Massachusetts.
5. Tri-State Motor Transit Company, published tariffs, Interstate Commerce Commission (ICC) Docket No. MC-109397 and Supplements.
6. Chem-Nuclear Services, Inc., Low-Level Radioactive Waste Management Facility, Barnwell, SC.
7. T.S. LaGuardia et al., "Guidelines for Producing Commercial Nuclear Power Plant Decommissioning Cost Estimates", AIF/NESP-036, May 1986.
8. W.J. Manion and T.S. LaGuardia, "Decommissioning Handbook", U.S. Department of Energy, DOE/EV/10128-1, November, 1980.
9. Cost Engineers Notebook: American Association of Cost Engineers, AA-4.000, pg 3 of 22, Rev. 2 (January 1978) (Updated periodically).
10. R.I. Smith, G.J. Konzek, W.E. Kennedy, Jr., "Technology, Safety and Costs of Decommissioning a Reference Pressurized Water Reactor Power Station," NUREG/CR-0130 and addenda, Pacific Northwest Laboratory for the Nuclear Regulatory Commission. June 1978.
11. J.C. Evans et al., "Long-Lived Activation Products in Reactor Materials" NUREG/CR-3474, Pacific Northwest Laboratory for the Nuclear Regulatory Commission. August 1984.

12. H.D. Oak, et al., "Technology, Safety and Costs of Decommissioning a Reference Boiling Water Reactor Power Station," NUREG/CR-0672 and addenda, Pacific Northwest Laboratory for the Nuclear Regulatory Commission. June 1980.
13. "Microsoft Project for Windows," Version 3.0, Microsoft Corporation, Redmond, WA 1993.
14. U.S. Department of Transportation, Section 49 of the Code of Federal Regulations, "Transportation", Parts 173 through 178.

APPENDIX A
UNIT COST FACTOR DEVELOPMENT

APPENDIX A UNIT COST FACTOR DEVELOPMENT

Example: Unit Factor for Removal of Contaminated Heat Exchanger < 3000 lbs.

1. SCOPE

Heat exchangers weighing < 3,000 lb will be removed in one piece using a crane or small hoist. They will be disconnected from the inlet and outlet piping. The heat exchanger will be sent to the packing area.

2. CALCULATIONS

| Act ID | Activity Description | Activity Duration | Critical Duration |
|--|---|----------------------|----------------------|
| a | Remove Insulation | 60 | 60 |
| b | Mount pipe cutters | 45 | 45 |
| c | Install contamination controls | 20 | (b) |
| d | Disconnect inlet and outlet lines | 60 | 60 |
| e | Cap openings | 20 | (d) |
| f | Rig for removal | 30 | 30 |
| g | Unbolt from mounts | 30 | 30 |
| h | Remove contamination controls | 15 | 15 |
| i | Remove, wrap in plastic, send to packing area | <u>60</u> | <u>60</u> |
| Totals (Activity/Critical) | | 340 | 300 |
| Duration adjustment(s): | | | |
| + Respiratory protection adjustment (50% of critical duration) | | | 150 |
| + Radiation/ALARA adjustment (32% of critical duration) | | | <u>96</u> |
| Adjusted work duration | | | 546 |
| + Protective clothing adjustment (30% of adjusted duration) | | | <u>164</u> |
| Productive work duration | | | 710 |
| + Work break adjustment (8.33 % of productive duration) | | | <u>59</u> |
| Total work duration (mins) | | | 769 |

*** Total duration = 12.82 hr ***

3. LABOR REQUIRED

| Crew | Number | Duration (hr) | Rate (\$/hr) | Cost |
|----------------------------------|--------|------------------|-----------------|-----------------|
| Laborers | 3.00 | 12.82 | \$14.06 | \$540.62 |
| Craftsmen | 2.00 | 12.82 | \$22.10 | \$566.51 |
| Foreman | 1.00 | 12.82 | \$24.35 | \$312.09 |
| General Foreman | 0.25 | 12.82 | \$33.23 | <u>\$106.48</u> |
| Subtotal labor cost | | | | \$1,525.70 |
| Overhead & Profit on labor @ 21% | | | | <u>\$320.40</u> |
| Total labor cost | | | | \$1,846.10 |

4. EQUIPMENT & CONSUMABLES COSTS

| | |
|--|-------------------|
| Equipment Costs | none |
| Consumables/Materials Costs | |
| -Blotting paper 50 @ \$0.48 sq ft {2} | \$24.00 |
| -Plastic sheets/bags 50 @ \$0.06/sq ft {3} | \$3.00 |
| -Gas torch consumables 1 @ \$7.39/hr x 1 hr {1} | <u>\$7.39</u> |
| Subtotal cost of equipment and materials | \$34.39 |
| Overhead & profit on equipment and materials @ 14.25% | <u>\$4.90</u> |
| Total costs, equipment & material | \$39.29 |
| TOTAL COST Removal of contaminated heat exchanger <3000 pound: | \$1,885.39 |
| Total labor cost: | \$1,846.10 |
| Total equipment/material costs: | \$39.29 |
| Total adjusted exposure manhours incurred: | 52.83 |
| Total craft labor manhours required per unit: | 80.11 |

5. NOTES AND REFERENCES

1. Durations are shown in minutes. The integrated duration accounts for those activities that can be performed in conjunction with other activities, indicated by the alpha designator of the concurrent activity. This results in an overall decrease in the sequenced duration.
2. Work difficulty factors were developed in conjunction with the AIF program to standardize decommissioning cost studies and are delineated in the "Guidelines" study (Ref. 7, p. 64).
3. Adjusted for regional material costs for Wichita, Kansas:
4. References:
 1. R.S. Means (1992) Division 016 Section 420-6360 pg 19
 2. McMaster-Carr Ed. 94 pg 735
 3. R.S. Means (1992) Division 015 Section 602-0200 pg 12

APPENDIX B

**UNIT COST FACTOR LISTING
(Power Block Structures Only for DECON)**

APPENDIX B

UNIT COST FACTOR LISTING
(Power Block Structures Only for DECON)

| Unit Cost Factor | Cost/Unit(\$) |
|---|----------------------|
| Removal of clean instrument and sampling tubing, \$/linear foot | \$0.21 |
| Removal of clean pipe 0.25 to 2 inches diameter \$/linear foot | \$3.79 |
| Removal of clean pipe >2 to 4 inches diameter \$/linear foot | \$4.61 |
| Removal of clean pipe >4 to 8 inches diameter \$/linear foot | \$6.23 |
| Removal of clean pipe >8 to 14 inches diameter \$/linear foot | \$11.77 |
| Removal of clean pipe >14 to 20 inches diameter \$/linear foot | \$15.33 |
| Removal of clean pipe >20 to 36 inches diameter \$/linear foot | \$22.55 |
| Removal of clean pipe >36 inches diameter \$/linear foot | \$26.78 |
| Removal of clean valves >2 to 4 inches | \$46.07 |
| Removal of clean valves >4 to 8 inches | \$62.34 |
| Removal of clean valves >8 to 14 inches | \$106.33 |
| Removal of clean valves >14 to 20 inches | \$153.29 |
| Removal of clean valves >20 to 36 inches | \$225.49 |
| Removal of clean valves >36 inches | \$267.82 |
| Removal of clean pipe hangers for small bore piping | \$13.76 |
| Removal of clean pipe hangers for large bore piping | \$47.37 |
| Removal of clean pumps, <300 pound | \$105.55 |
| Removal of clean pumps, 300-1000 pound | \$266.61 |
| Removal of clean pumps, 1000-10,000 pound | \$1,107.01 |
| Removal of clean pumps, >10,000 pound | \$2,263.21 |
| Removal of clean turbine-driven pumps < 10,000 pounds | \$1,345.84 |
| Removal of clean turbine-driven pumps > 10,000 pounds | \$2,622.82 |
| Removal of clean PWR turbine-generator | \$73,648.02 |
| Removal of clean heat exchanger <3000 pound | \$555.77 |
| Removal of clean heat exchanger >3000 pound | \$1,594.11 |
| Removal of clean feedwater heater/deaerator | \$3,973.55 |

APPENDIX B

UNIT COST FACTOR LISTING
(Power Block Structures Only for DECON)
 (continued)

| Unit Cost Factor | Cost/Unit(\$) |
|--|----------------------|
| Removal of clean moisture separator/reheater | \$9131.48 |
| Removal of clean PWR main condenser | \$205,661.95 |
| Removal of clean tanks, <300 gallons | \$135.71 |
| Removal of clean tanks, 300-3000 gallons | \$427.16 |
| Removal of clean tanks, >3000 gallons, \$/square foot surface area | \$3.65 |
| Removal of clean electrical equipment, <300 pound | \$57.74 |
| Removal of clean electrical equipment, 300-1000 pound | \$203.80 |
| Removal of clean electrical equipment, 1000-10,000 pound | \$407.61 |
| Removal of clean electrical equipment, >10,000 pound | \$990.78 |
| Removal of clean electrical transformers < 30 tons | \$688.08 |
| Removal of clean electrical transformers > 30 tons | \$1,981.56 |
| Removal of clean standby diesel-generator, <100 kW | \$702.83 |
| Removal of clean standby diesel-generator, 100 kW to 1 MW | \$1,568.73 |
| Removal of clean standby diesel-generator, >1 MW | \$3,247.59 |
| Removal of clean electrical cable tray, \$/linear foot | \$5.38 |
| Removal of clean electrical conduit, \$/linear foot | \$2.35 |
| Removal of clean mechanical equipment, <300 pound | \$57.74 |
| Removal of clean mechanical equipment, 300-1000 pound | \$203.80 |
| Removal of clean mechanical equipment, 1000-10,000 pound | \$407.61 |
| Removal of clean mechanical equipment, >10,000 pound | \$990.78 |
| Removal of clean HVAC equipment, <300 pound | \$57.74 |
| Removal of clean HVAC equipment, 300-1000 pound | \$203.80 |
| Removal of clean HVAC equipment, 1000-10,000 pound | \$407.61 |
| Removal of clean HVAC equipment, >10,000 pound | \$990.78 |
| Removal of clean HVAC ductwork, \$/pound | \$0.43 |
| Removal/manual flame cut of clean thin metal components, \$/inch-cut | \$2.36 |
| Asbestos clean removal (pipe/components) | \$3.88 |

APPENDIX B

UNIT COST FACTOR LISTING
(Power Block Structures Only for DECON)
 (continued)

| Unit Cost Factor | Cost/Unit(\$) |
|--|----------------------|
| Removal of contaminated instrument and sampling tubing, \$/linear foot | \$0.34 |
| Removal of contaminated pipe 0.25 to 2 inches diameter \$/linear foot | \$13.39 |
| Removal of contaminated pipe >2 to 4 inches diameter \$/linear foot | \$34.85 |
| Removal of contaminated pipe >4 to 8 inches diameter \$/linear foot | \$43.10 |
| Removal of contaminated pipe >8 to 14 inches diameter \$/linear foot | \$76.20 |
| Removal of contaminated pipe >14 to 20 inches diameter \$/linear foot | \$91.45 |
| Removal of contaminated pipe >20 to 36 inches diameter \$/linear foot | \$127.34 |
| Removal of contaminated pipe >36 inches diameter \$/linear foot | \$150.44 |
| Removal of contaminated valves >2 to 4 inches | \$166.19 |
| Removal of contaminated valves >4 to 8 inches | \$206.60 |
| Removal of contaminated valves >8 to 14 inches | \$381.00 |
| Removal of contaminated valves >14 to 20 inches | \$512.54 |
| Removal of contaminated valves >20 to 36 inches | \$682.28 |
| Removal of contaminated valves >36 inches | \$752.21 |
| Removal of contaminated pipe hangers for small bore piping | \$30.91 |
| Removal of contaminated pipe hangers for large bore piping | \$111.40 |
| Removal of contaminated pumps, <300 pound | \$325.63 |
| Removal of contaminated pumps, 300-1000 pound | \$800.26 |
| Removal of contaminated pumps, 1000-10,000 pound | \$3,541.04 |
| Removal of contaminated pumps, >10,000 pound | \$7,556.83 |
| Removal of contaminated turbine-driven pumps < 10,000 pound | \$3,520.15 |
| Removal of contaminated turbine-driven pumps > 10,000 pound | \$7,425.00 |
| Removal of contaminated heat exchanger <3000 pound | \$1,885.39 |
| Removal of contaminated heat exchanger >3000 pound | \$4,872.75 |
| Removal of contaminated tanks, <300 gallons | \$582.64 |
| Removal of contaminated tanks, >300 gallons, \$/square foot | \$11.92 |
| Removal of contaminated electrical equipment, <300 pound | \$203.02 |

APPENDIX B

UNIT COST FACTOR LISTING
(Power Block Structures Only for DECON)
 (continued)

| Unit Cost Factor | Cost/Unit(\$) |
|--|----------------------|
| Removal of contaminated electrical equipment, 300-1000 pound | \$523.55 |
| Removal of contaminated electrical equipment, 1000-10,000 pound | \$979.10 |
| Removal of contaminated electrical equipment, >10,000 pound | \$2,142.85 |
| Removal of contaminated electrical cable tray, \$/linear foot | \$19.29 |
| Removal of contaminated electrical conduit, \$/linear foot | \$16.86 |
| Removal of contaminated mechanical equipment, <300 pound | \$203.02 |
| Removal of contaminated mechanical equipment, 300-1000 pound | \$523.55 |
| Removal of contaminated mechanical equipment, 1000-10,000 pound | \$979.10 |
| Removal of contaminated mechanical equipment, >10,000 pound | \$2,142.85 |
| Removal of contaminated HVAC equipment, <300 pound | \$203.02 |
| Removal of contaminated HVAC equipment, 300-1000 pound | \$523.55 |
| Removal of contaminated HVAC equipment, 1000-10,000 pound | \$979.10 |
| Removal of contaminated HVAC equipment, >10,000 pound | \$2,142.85 |
| Removal of contaminated HVAC ductwork, \$/pound | \$1.34 |
| Removal/plasma arc cut of contaminated thin metal components, \$/linear inch | \$1.44 |
| Surface decontamination of equipment, \$/square foot | \$3.88 |
| Surface decontamination of large components, \$/square foot | \$13.94 |
| Decontamination rig hook-up and flush | \$1,497.75 |
| Chemical flush of components/systems, \$/gallon | \$5.18 |
| Removal of standard reinforced concrete, \$/cubic yard | \$258.66 |
| Removal of grade slab concrete, \$/cubic yard | \$128.18 |
| Removal of clean concrete floors, \$/cubic yard | \$157.00 |
| Removal of sections of clean concrete floors, \$/cubic yard | \$477.97 |
| Removal of clean heavily rein concrete w/#9 rebar, \$/cubic yard | \$126.82 |
| Removal of contaminated heavily rein concrete w/#9 rebar, \$/cubic yard | \$962.88 |
| Removal of clean heavily rein concrete w/#18 rebar, \$/cubic yard | \$161.77 |

APPENDIX B

UNIT COST FACTOR LISTING
(Power Block Structures Only for DECON)
 (continued)

| Unit Cost Factor | Cost/Unit(\$) |
|---|----------------------|
| Removal of contaminated heavily rein concrete w/#18 rebar, \$/cubic yard | \$1,275.93 |
| Removal heavily rein concrete w/#18 rebar & steel embedments, \$/cubic yard | \$226.68 |
| Removal of below grade suspended floors, \$/square foot | \$157.00 |
| Removal of clean monolithic concrete structures, \$/cubic yard | \$428.07 |
| Removal of contaminated monolithic concrete structures, \$/cubic yard | \$959.51 |
| Removal of clean foundation concrete, \$/cubic yard | \$336.25 |
| Removal of contaminated foundation concrete, \$/cubic yard | \$893.15 |
| Explosive demolition of bulk concrete, \$/cubic yard | \$16.91 |
| Removal of clean hollow masonry block wall, \$/cubic yard | \$41.36 |
| Removal of contaminated hollow masonry block wall, \$/cubic yard | \$101.18 |
| Removal of clean solid masonry block wall, \$/cubic yard | \$41.36 |
| Removal of contaminated solid masonry block wall, \$/cubic yard | \$101.18 |
| Placement of concrete for below grade voids, \$/cubic yard | \$72.04 |
| Placement of entombment concrete, \$/cubic yard | \$235.36 |
| Removal of subterranean tunnels/voids, \$/linear foot | \$62.56 |
| Backfill of below grade voids, \$/cubic yard | \$13.50 |
| Excavation of clean material, \$/cubic yard | \$2.42 |
| Excavation of contaminated material, \$/cubic yard | \$5.82 |
| Excavation of submerged concrete rubble, \$/cubic yard | \$7.26 |
| Removal of clean concrete rubble, \$/cubic yard | \$42.29 |
| Removal of contaminated concrete rubble, \$/cubic yard | \$16.86 |
| Removal of building by volume, \$/cubic foot | \$0.15 |
| Removal of clean building metal siding, \$/square foot | \$0.67 |
| Removal of contaminated building metal siding, \$/square foot | \$1.67 |
| Removal of standard asphalt roofing, \$/square foot | \$0.90 |
| Removal of transite panels, \$/square foot | \$0.89 |
| Scarifying contaminated concrete surfaces (drill & spall) | \$6.18 |

APPENDIX B

UNIT COST FACTOR LISTING
(Power Block Structures Only for DECON)
 (continued)

| Unit Cost Factor | Cost/Unit(\$) |
|---|----------------------|
| Scabbling contaminated concrete floors \$/square foot | \$4.18 |
| Scabbling contaminated concrete walls \$/square foot | \$12.50 |
| Scabbling contaminated ceilings \$/square foot | \$41.66 |
| Scabbling structural steel \$/square foot | \$2.95 |
| Removal of clean overhead cranes/monorails < 10 ton capacity | \$273.93 |
| Removal of contaminated overhead cranes/monorails < 10 ton capacity | \$642.33 |
| Removal of clean overhead cranes/monorails >10 - 50 ton capacity | \$657.43 |
| Removal of contaminated overhead cranes/monorails >10 - 50 ton capacity | \$1,540.33 |
| Removal of polar cranes > 50 ton capacity, each | \$2,804.71 |
| Removal of gantry cranes > 50 ton capacity, each | \$10,332.19 |
| Removal of structural steel, \$/pound | \$0.17 |
| Removal of clean steel floor grating, \$/square foot | \$1.45 |
| Removal of contaminated steel floor grating, \$/square foot | \$3.66 |
| Removal of clean free-standing steel liner, \$/square foot | \$5.12 |
| Removal of contaminated free-standing steel liner, \$/square foot | \$12.67 |
| Removal of clean concrete anchored steel liner, \$/square foot | \$2.56 |
| Removal of contaminated concrete anchored steel liner, \$/square foot | \$14.83 |
| Placement of scaffolding in clean areas, \$/square foot | \$2.39 |
| Placement of scaffolding in contaminated areas, \$/square foot | \$3.84 |
| Landscaping with topsoil, \$/acre | \$14,512.75 |
| Landscaping w/o topsoil, \$/acre | \$1,747.55 |
| Cost of LSA box & preparation for use | \$1,024.65 |
| Cost of LSA drum & preparation for use | \$96.91 |
| Cost of cask liner for CNSI 14-195 cask | \$6,638.16 |
| Cost of cask liner for CNSI 8-120A cask (resins) | \$8,930.12 |
| Cost of cask liner for CNSI 8-120A cask (filters) | \$8,923.15 |
| Decontamination of surfaces with vacuuming, \$/square foot | \$0.62 |

APPENDIX C

DETAILED COST ANALYSIS

TABLE C-1
DECON COST ESTIMATE FOR WOLF CREEK GENERATING STATION
(THOUSANDS OF 1993 DOLLARS)

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Cntgcy | Total | LicTerm | Clean | A CF | B CF | C CF | >C CF | M-Hrs | M-Ren |
|---|-------|--------|------|------|------|-------|--------|-------|---------|-------|------|------|------|-------|-------|-------|
| PERIOD 1 | | | | | | | | | | | | | | | | |
| 1. Prepare preliminary decommissioning plan | | | | | | 130 | 20 | 150 | 150 | | | | | | | |
| 2. Prepare proposed decommissioning plan | | | | | | 400 | 60 | 460 | 460 | | | | | | | |
| 3. Remove fuel & source material | | | | | | | | n/a | | | | | | | | |
| 4. Decon plant & process waste | | | | | | | | a | | | | | | | | |
| 5. Review plant dwgs & specs. | | | | | | 460 | 69 | 529 | 529 | | | | | | | |
| 6. Perform detailed rad survey | | | | | | | | a | | | | | | | | |
| 7. Estimate by-product inventory | | | | | | 100 | 15 | 115 | 115 | | | | | | | |
| 8. Submit for license amendment | | | | | | 160 | 24 | 184 | 184 | | | | | | | |
| 9. End product description | | | | | | 100 | 15 | 115 | 115 | | | | | | | |
| 10. Detailed by-product inventory | | | | | | 130 | 20 | 150 | 150 | | | | | | | |
| 11. Define major work sequence | | | | | | 750 | 113 | 863 | 863 | | | | | | | |
| 12. Perform safety analysis | | | | | | 310 | 47 | 357 | 357 | | | | | | | |
| 13. Submit dismantling plan | | | | | | 52 | 8 | 60 | 60 | | | | | | | |
| 14. Receive license amendment | | | | | | | | a | | | | | | | | |
| 15. Receive dismantling order | | | | | | | | a | | | | | | | | |
| Subtotal Period 1 Activity Costs | | | | | | 2592 | 389 | 2981 | 2981 | | | | | | | |
| Period 1 Undistributed costs | | | | | | | | | | | | | | | | |
| 1. Decon equipment | | | | | | 189 | 28 | 217 | 217 | | | | | | | |
| 2. Decon supplies | | | | | | 137 | 34 | 171 | 171 | | | | | | | |
| 3. DOC staff relocation expenses | | | | | | 845 | 127 | 972 | 972 | | | | | | | |
| 4. Process liquid waste | 67 | | 34 | 46 | 200 | | 74 | 422 | 422 | | 458 | | | 119 | 3 | |
| 5. Insurance | | | | | | 587 | 59 | 645 | 645 | | | | | | | |
| 6. Property taxes | | | | | | 693 | 69 | 762 | 762 | | | | | | | |
| 7. Health physics supplies | | | | | | 947 | 237 | 1184 | 1184 | | | | | | | |
| 8. Heavy equipment rental | | | | | | 104 | 16 | 120 | 120 | | | | | | | |
| 9. Disposal of DAW generated | | | 198 | 6 | 762 | | 135 | 1101 | 1101 | 2473 | | | | 6725 | 17 | |

NOTES- "n/a" indicates that fuel handling, packaging, shipping, and disposal are charged to plant operations, not decommissioning

- "a" indicates that costs are included in the utility staff costs.
- Columns may not total due to rounding errors.

TABLE C-1 (continued)
DECON COST ESTIMATE FOR WOLF CREEK GENERATING STATION

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Cntgcy | Total | LIC | Term | Clean | A CF | B CF | C CF | D-C CF | M-Hfs | M-Rom |
|---|-----------|--------|------------|-----------|------------|--------------|-------------|--------------|--------------|------|-------------|------------|------|------|--------|-------------|-----------|
| Period 1 Undistributed Costs (continued) | | | | | | | | | | | | | | | | | |
| 10. Plant energy budget | | | | | | 3425 | 514 | 3939 | 3939 | | | | | | | | |
| 11. NRC Fees | | | | | | 116 | 12 | 128 | 128 | | | | | | | | |
| 12. Emergency Planning Fees | | | | | | 264 | 26 | 291 | 291 | | | | | | | | |
| Subtotal Undistributed Costs Period 1 | 67 | | 232 | 52 | 962 | 7308 | 1331 | 9952 | 9952 | | 2473 | 458 | | | | 6844 | 20 |
| Staff Costs | | | | | | | | | | | | | | | | | |
| DOC Staff Cost | | | | | | 4607 | 691 | 5298 | 5298 | | | | | | | | |
| Utility Staff Cost | | | | | | 29965 | 4495 | 34459 | 34459 | | | | | | | | |
| TOTAL PERIOD 1 COST | 67 | | 232 | 52 | 962 | 44471 | 6905 | 52690 | 52690 | | 2473 | 458 | | | | 6844 | 20 |
| PERIOD 2 | | | | | | | | | | | | | | | | | |
| Activity Specifications | | | | | | | | | | | | | | | | | |
| 16.1 Plant & temporary facilities | | | | | | 492 | 74 | 566 | 509 | 57 | | | | | | | |
| 16.2 Plant systems | | | | | | 417 | 63 | 479 | 431 | 48 | | | | | | | |
| 16.3 Reactor Internals | | | | | | 710 | 107 | 817 | 817 | | | | | | | | |
| 16.4 Reactor vessel | | | | | | 650 | 98 | 748 | 748 | | | | | | | | |
| 16.5 Biological shield | | | | | | 50 | 8 | 58 | 58 | | | | | | | | |
| 16.6 Steam generators | | | | | | 312 | 47 | 359 | 359 | | | | | | | | |
| 16.7 Reinforced concrete | | | | | | 160 | 24 | 184 | 92 | 92 | | | | | | | |
| 16.8 Turbine & condenser | | | | | | 80 | 12 | 92 | | 92 | | | | | | | |
| 16.9 Plant structures & buildings | | | | | | 312 | 47 | 359 | 179 | 179 | | | | | | | |
| 16.10 Waste management | | | | | | 460 | 69 | 529 | 529 | | | | | | | | |
| 16.11 Facility & site closeout | | | | | | 90 | 14 | 104 | 52 | 52 | | | | | | | |
| 16. Total | | | | | | 3733 | 560 | 4293 | 3773 | 520 | | | | | | | |
| Planning & Site Preparations | | | | | | | | | | | | | | | | | |
| 17. Prepare dismantling sequence | | | | | | 240 | 36 | 276 | 276 | | | | | | | | |
| 18. Plant prep. & temp. svcs | | | | | | 1485 | 223 | 1708 | 1708 | | | | | | | | |
| 19. Design water clean-up system | | | | | | 140 | 21 | 161 | 161 | | | | | | | | |
| 20. Rigging/CCEs/tooling/etc. | | | | | | 1257 | 189 | 1446 | 1446 | | | | | | | | |
| 21. Procure casks/liners & containers | | | | | | 123 | 18 | 141 | 141 | | | | | | | | |

TABLE C-1 (continued)
DECON COST ESTIMATE FOR WOLF CREEK GENERATING STATION

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Cntgcy | Total | LicTerm | Clean | A CF | B CF | C CF | >C CF | M-Hrs | M-Rom |
|--|-------|--------|------|------|-------|-------|--------|-------|---------|-------|------|------|------|--------|-------|-------|
| Detailed Work Procedures | | | | | | | | | | | | | | | | |
| 22.1 Plant systems | | | | | | 473 | 71 | 544 | 490 | 54 | | | | | | |
| 22.2 Vessel head | | | | | | 250 | 38 | 288 | 288 | | | | | | | |
| 22.3 Reactor Internals | | | | | | 250 | 38 | 288 | 288 | | | | | | | |
| 22.4 Remaining buildings | | | | | | 135 | 20 | 155 | 39 | 116 | | | | | | |
| 22.5 CRD cooling assembly | | | | | | 100 | 15 | 115 | 115 | | | | | | | |
| 22.6 CRD housings & ICI tubes | | | | | | 100 | 15 | 115 | 115 | | | | | | | |
| 22.7 Incore instrumentation | | | | | | 100 | 15 | 115 | 115 | | | | | | | |
| 22.8 Reactor vessel | | | | | | 363 | 54 | 417 | 417 | | | | | | | |
| 22.9 Facility closeout | | | | | | 120 | 18 | 138 | 69 | 69 | | | | | | |
| 22.10 Missile shields | | | | | | 45 | 7 | 52 | 52 | | | | | | | |
| 22.11 Biological shield | | | | | | 120 | 18 | 138 | 138 | | | | | | | |
| 22.12 Steam generators | | | | | | 460 | 69 | 529 | 529 | | | | | | | |
| 22.13 Reinforced concrete | | | | | | 100 | 15 | 115 | 58 | 58 | | | | | | |
| 22.14 Turbine & condensers | | | | | | 312 | 47 | 359 | | 359 | | | | | | |
| 22.15 Auxiliary building | | | | | | 273 | 41 | 314 | 283 | 31 | | | | | | |
| 22.16 Reactor building | | | | | | 273 | 41 | 314 | 283 | 31 | | | | | | |
| 22. Total | | | | | | 3474 | 521 | 3995 | 3276 | 719 | | | | | | |
| Decon NSSS/Rack Removal | | | | | | | | | | | | | | | | |
| 23. Decon primary loop | 463 | | | | | | 231 | 694 | 694 | | | | | 800 | 8 | |
| 24. Remove spent fuel racks | 212 | 35 | 80 | 22 | 945 | 731 | 378 | 2402 | 2402 | 3150 | | | | 8531 | 46 | |
| Nuclear Steam Supply System Removal | | | | | | | | | | | | | | | | |
| 25.1 Reactor Coolant Piping | 67 | 127 | 62 | 18 | 2066 | | 384 | 2725 | 2725 | 6485 | | | | 7987 | 176 | |
| 25.2 Pressurizer Relief Tank | 12 | 61 | 5 | 4 | 197 | | 52 | 330 | 330 | 621 | | | | 3007 | 74 | |
| 25.3 Reactor Coolant Pumps & Motors | 26 | 38 | 33 | 40 | 3491 | | 555 | 4183 | 4183 | 11312 | | | | 2862 | 65 | |
| 25.4 Pressurizer | 25 | 27 | 4 | 10 | 1280 | | 213 | 1558 | 1558 | 4147 | | | | 1933 | 38 | |
| 25.5 Steam Generators | 138 | 2487 | 133 | 3502 | 17932 | | 3919 | 28112 | 28112 | 58484 | | | | 99082 | 1258 | |
| 25.6 CRDMS/ ICIS/Service Structure Removal | 60 | 37 | 20 | 14 | 596 | | 133 | 861 | 861 | 1843 | | | | 3546 | 85 | |
| 25.7 Reactor vessel internals | 45 | 1066 | 269 | 302 | 6832 | | 1989 | 10503 | 10503 | 1441 | 801 | 476 | 221 | 13273 | 40 | |
| 25.8 Reactor vessel | 103 | 2689 | 265 | 252 | 3009 | | 2649 | 8967 | 8967 | 5540 | 2096 | | | 15731 | 43 | |
| 25. Totals | 475 | 6532 | 792 | 4141 | 35403 | | 9894 | 57238 | 57238 | 89873 | 2897 | 476 | 221 | 147420 | 1778 | |

TABLE C-1 (continued)
DECON COST ESTIMATE FOR WOLF CREEK GENERATING STATION

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Cntgcy | Total | LicTerm | Clean | A CF | B CF | C CF | >C CF | M-Hrs | M-Rm |
|--|-------|--------|------|------|------|-------|--------|-------|---------|-------|------|------|------|-------|-------|------|
| Disposal of Plant Systems | | | | | | | | | | | | | | | | |
| 26.1 AX - Acid Feed | | 19 | | | | | 3 | 22 | | 22 | | | | | 833 | |
| 26.2 Accumulator Safety Injection | | 88 | 27 | 6 | 190 | 121 | 72 | 504 | 504 | | 617 | | | | 3844 | 31 |
| 26.3 Auxiliary Bldg Non-System Specific Clean | | 404 | | | | | 61 | 465 | | 465 | | | | | 17709 | |
| 26.4 Auxiliary Bldg Non-System Specific Cont | | 247 | 103 | 34 | 767 | 577 | 279 | 2007 | 2007 | | 2488 | | | | 11246 | 14 |
| 26.5 Auxiliary Bldg Non-System Specific Decon | 34 | 135 | | | | | 37 | 206 | 51 | 155 | | | | | 7291 | |
| 26.6 Auxiliary Building HVAC | | 280 | 46 | 12 | 290 | 213 | 152 | 992 | 992 | | 940 | | | | 9618 | 13 |
| 26.7 Auxiliary Feedwater | | 20 | | | | | 3 | 23 | | 23 | | | | | 912 | |
| 26.8 Auxiliary Steam | | 65 | | | | | 10 | 75 | | 75 | | | | | 2948 | |
| 26.9 Auxiliary Steam Chemical Addition | | 3 | | | | | <1 | 3 | | 3 | | | | | 121 | |
| 26.10 Auxiliary Steam Generator | | 7 | | | | | 1 | 8 | | 8 | | | | | 321 | |
| 26.11 Auxiliary Turbines | | 31 | | | | | 5 | 36 | | 36 | | | | | 1358 | |
| 26.12 Borated Refueling Water Storage | | 163 | 56 | 9 | 355 | 266 | 141 | 990 | 990 | | 1152 | | | | 7142 | 23 |
| 26.13 Boron Recycle | | 273 | 71 | 18 | 438 | 275 | 185 | 1260 | 1260 | | 1422 | | | | 11754 | 126 |
| 26.14 CL - Chlorination | | 14 | | | | | 2 | 16 | | 16 | | | | | 607 | |
| 26.15 CW - Circulating Water | | 190 | | | | | 29 | 219 | | 219 | | | | | 8903 | |
| 26.16 CZ - Caustic Acid | | 3 | | | | | <1 | 3 | | 3 | | | | | 134 | |
| 26.17 Central Chilled Water | | 51 | | | | | 8 | 59 | | 59 | | | | | 2304 | |
| 26.18 Chemical & Detergent Waste | 31 | 75 | 19 | 5 | 124 | 85 | 68 | 406 | 406 | | 401 | | | | 4502 | 25 |
| 26.19 Chemical & Volume Control | 354 | 507 | 173 | 47 | 2147 | 560 | 734 | 4523 | 4523 | | 6968 | | | | 32065 | 177 |
| 26.20 Closed Cooling Water | | 32 | | | | | 5 | 37 | | 37 | | | | | 1443 | |
| 26.21 CO - Carbon Dioxide | | 4 | | | | | <1 | 5 | | 5 | | | | | 177 | |
| 26.22 Component Cooling Water | | 134 | | | | | 20 | 154 | | 154 | | | | | 6177 | |
| 26.23 Condensate | | 133 | | | | | 20 | 153 | | 153 | | | | | 5956 | |
| 26.24 Condensate & Feedwater Chemical Addition | | 12 | | | | | 2 | 14 | | 14 | | | | | 526 | |
| 26.25 Condensate Demineralizer | | 46 | | | | | 7 | 53 | | 53 | | | | | 2068 | |
| 26.26 Condensate Storage & Transfer | | 39 | | | | | 6 | 45 | | 45 | | | | | 1656 | |
| 26.27 Condenser Air Removal | | 16 | | | | | 2 | 18 | | 18 | | | | | 699 | |
| 26.28 Containment Atmospheric Control | | 6 | 23 | 4 | 377 | 19 | 64 | 492 | 492 | | 1222 | | | | 343 | <1 |
| 26.29 Containment Cooling | | 330 | 104 | 22 | 1119 | 313 | 311 | 2198 | 2198 | | 3631 | | | | 12706 | 16 |
| 26.30 Containment Hydrogen Control | | 28 | 19 | 5 | 148 | 85 | 45 | 330 | 330 | | 481 | | | | 1285 | <1 |
| 26.31 Containment Integrated Leak Rate Test | | 6 | | | | | <1 | 7 | | 7 | | | | | 287 | |
| 26.32 Containment Purge HVAC | | 72 | 32 | 5 | 322 | 110 | 87 | 629 | 629 | | 1046 | | | | 2724 | 3 |
| 26.33 Containment Spray | 47 | 40 | | | | | 29 | 116 | 70 | 46 | | | | | 3339 | |
| 26.34 Control Bldg Non-System Specific Clean | | 378 | | | | | 57 | 435 | | 435 | | | | | 16569 | |
| 26.35 Control Bldg Non-System Specific Cont | | 226 | 106 | 34 | 759 | 571 | 272 | 1968 | 1968 | | 2462 | | | | 10332 | 12 |
| 26.36 Control Bldg Non-System Specific Decon | 34 | 124 | | | | | 36 | 194 | 52 | 142 | | | | | 6802 | |

TABLE C-1 (continued)
DECON COST ESTIMATE FOR WOLF CREEK GENERATING STATION

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Cntgcy | Total | LicTerm | Clean | A CF | B CF | C CF | >C CF | M-HRS | M-Rm |
|--|-------|--------|------|------|------|-------|--------|-------|---------|-------|------|------|------|-------|-------|------|
| Disposal of Plant Systems (continued) | | | | | | | | | | | | | | | | |
| 26.37 Control Building HVAC | | 147 | | | | | 22 | 169 | | 169 | | | | | 6162 | |
| 26.38 DA - Circulating Water System | | 196 | | | | | 29 | 226 | | 226 | | | | | 9126 | |
| 26.39 DM - Equipment Drains | | 60 | | | | | 9 | 69 | | 69 | | | | | 2710 | |
| 26.40 DO - Diesel Oil | | 1 | | | | | <1 | 1 | | 1 | | | | | 47 | |
| 26.41 Decontamination | | 43 | 47 | 6 | 134 | 88 | 49 | 366 | 366 | | 435 | | | | 1945 | 5 |
| 26.42 Demineralized Water Storage & Transfer | | 41 | | | | | 6 | 47 | | 47 | | | | | 1819 | |
| 26.43 Diesel Generator Building HVAC | | 27 | | | | | 4 | 31 | | 31 | | | | | 1115 | |
| 26.44 EA - Service Water | | 63 | | | | | 10 | 73 | | 73 | | | | | 2928 | |
| 26.45 EF - Essential Service Water | | 77 | | | | | 12 | 89 | | 89 | | | | | 3541 | |
| 26.46 Emergency Fuel Oil | | 31 | | | | | 5 | 36 | | 36 | | | | | 1329 | |
| 26.47 FO - Fuel Oil | | 14 | | | | | 2 | 16 | | 16 | | | | | 625 | |
| 26.48 FP - Fire Protection | | 152 | | | | | 23 | 175 | | 175 | | | | | 7096 | |
| 26.49 Feedwater | | 90 | | | | | 14 | 104 | | 104 | | | | | 4105 | |
| 26.50 Feedwater Heater Extraction | | 135 | | | | | 20 | 155 | | 155 | | | | | 6164 | |
| 26.51 Floor & Equipment Drains | | 1093 | 209 | 55 | 1342 | 971 | 649 | 4320 | 4320 | | 4357 | | | | 46675 | 126 |
| 26.52 Fuel Bldg Non-System Specific Clean | | 52 | | | | | 8 | 60 | | 60 | | | | | 2293 | |
| 26.53 Fuel Bldg Non-System Specific Cont | | 36 | 15 | 5 | 118 | 89 | 42 | 306 | 306 | | 383 | | | | 1638 | 2 |
| 26.54 Fuel Bldg Non-System Specific Decon | 4 | 16 | | | | | 4 | 24 | 6 | 18 | | | | | 852 | |
| 26.55 Fuel Building HVAC | | 154 | 45 | 10 | 518 | 123 | 141 | 991 | 991 | | 1682 | | | | 5374 | 7 |
| 26.56 Fuel Handling & Storage Reactor Vessel | | 6 | 8 | 5 | 266 | | 43 | 329 | 329 | | 864 | | | | 292 | <1 |
| 26.57 Fuel Pool Cooling & Cleanup | | 248 | 71 | 18 | 649 | 301 | 214 | 1501 | 1501 | | 2106 | | | | 10872 | 29 |
| 26.58 GD - Esstl. Srvc. Wtr Pumps, Bldg HVAC | | 9 | | | | | 1 | 10 | | 10 | | | | | 365 | |
| 26.59 GE - Turbine Bldg HVAC | | 102 | | | | | 15 | 118 | | 118 | | | | | 4319 | |
| 26.60 GF - Miscellaneous Building HVAC | | 33 | | | | | 5 | 38 | | 38 | | | | | 1387 | |
| 26.61 Gaseous Radwaste | | 162 | 71 | 15 | 512 | 159 | 150 | 1069 | 1069 | | 1662 | | | | 7023 | 17 |
| 26.62 Generator Hydrogen Seal & CO2 | | 5 | | | | | <1 | 6 | | 6 | | | | | 210 | |
| 26.63 Generator Seal Oil | | 7 | | | | | 1 | 8 | | 8 | | | | | 296 | |
| 26.64 HY - Hydrogen | | 6 | | | | | <1 | 7 | | 7 | | | | | 277 | |
| 26.65 High Pressure Coolant Injection | | 173 | 57 | 17 | 518 | 240 | 165 | 1170 | 1170 | | 1682 | | | | 7576 | 37 |
| 26.66 KA - Compressed Air and Instrument | | 160 | | | | | 24 | 185 | | 185 | | | | | 7081 | |
| 26.67 KB - Breathing Air | | 26 | | | | | 4 | 30 | | 30 | | | | | 1182 | |
| 26.68 KC - Fire Protection | | 277 | | | | | 42 | 319 | | 319 | | | | | 12879 | |
| 26.69 KD - Domestic Water | | 46 | | | | | 7 | 52 | | 52 | | | | | 2023 | |
| 26.70 KH - Service Gas | | 18 | | | | | 3 | 21 | | 21 | | | | | 780 | |
| 26.71 LA - Sanitary Drains | | 13 | | | | | 2 | 15 | | 15 | | | | | 582 | |
| 26.72 LC - Yard Drains | | 2 | | | | | <1 | 3 | | 3 | | | | | 95 | |

TABLE C-1 (continued)
DECON COST ESTIMATE FOR WOLF CREEK GENERATING STATION

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Contgcy | Total | LicTerm | Clean | A CF | B CF | C CF | >C CF | M-Hrs | M-Ren |
|--|-------|--------|------|------|------|-------|---------|-------|---------|-------|------|------|------|-------|-------|-------|
| Disposal of Plant Systems (continued) | | | | | | | | | | | | | | | | |
| 26.73 LE - Oily waste | | 98 | | | | | 15 | 112 | | 112 | | | | | 4433 | |
| 26.74 Liquid Radwaste | 384 | 442 | 130 | 27 | 823 | 394 | 502 | 2702 | 2702 | | 2670 | | | | 32913 | 384 |
| 26.75 Lube Oil Storage, Transfer, & Purification | | 21 | | | | | 3 | 24 | | 24 | | | | | 925 | |
| 26.76 Main Steam | | 139 | | | | | 21 | 160 | | 160 | | | | | 6475 | |
| 26.77 Main Turbine | | 131 | | | | | 20 | 151 | | 151 | | | | | 5932 | |
| 26.78 Main Turbine Control Oil | | 29 | | | | | 4 | 33 | | 33 | | | | | 1211 | |
| 26.79 Main Turbine Lube Oil | | 27 | | | | | 4 | 31 | | 31 | | | | | 1164 | |
| 26.80 NT - Nitrogen | | 4 | | | | | <1 | 5 | | 5 | | | | | 186 | |
| 26.81 Nuclear Sampling | | 33 | 46 | 6 | 423 | 29 | 81 | 618 | 618 | | 1373 | | | | 1564 | 3 |
| 26.82 OX - Oxygen | | 4 | | | | | <1 | 5 | | 5 | | | | | 177 | |
| 26.83 Plant Heating | | 70 | | | | | 11 | 81 | | 81 | | | | | 3155 | |
| 26.84 Process Sampling & Analysis | | 60 | 42 | 13 | 644 | 124 | 136 | 1020 | 1020 | | 2090 | | | | 2650 | 4 |
| 26.85 Radwaste Bldg Non-System Specific Clean | | 153 | | | | | 23 | 176 | | 176 | | | | | 6704 | |
| 26.86 Radwaste Bldg Non-System Specific Cont | | 106 | 46 | 14 | 310 | 234 | 115 | 825 | 825 | | 1007 | | | | 4848 | 6 |
| 26.87 Radwaste Bldg Non-System Specific Decon | 12 | 46 | | | | | 13 | 70 | 18 | 53 | | | | | 2487 | |
| 26.88 Radwaste Building HVAC | | 108 | 28 | 7 | 293 | 88 | 88 | 611 | 611 | | 951 | | | | 3781 | 5 |
| 26.89 Reactor Bldg Non-System Specific Clean | | 136 | | | | | 20 | 157 | | 157 | | | | | 5982 | |
| 26.90 Reactor Bldg Non-System Specific Cont | | 86 | 30 | 9 | 187 | 141 | 75 | 527 | 527 | | 607 | | | | 3884 | 5 |
| 26.91 Reactor Bldg Non-System Specific Decon | 11 | 46 | | | | | 12 | 70 | 17 | 53 | | | | | 2474 | |
| 26.92 Reactor Coolant System | | 115 | 65 | 16 | 736 | 202 | 178 | 1313 | 1313 | | 2390 | | | | 5295 | 75 |
| 26.93 Reactor Makeup Water | | 152 | 31 | 9 | 222 | 138 | 96 | 647 | 647 | | 720 | | | | 6469 | 7 |
| 26.94 Residual Heat Removal | | 221 | 77 | 18 | 801 | 284 | 228 | 1628 | 1628 | | 2599 | | | | 9890 | 82 |
| 26.95 Roof Drains | | 55 | | | | | 8 | 63 | | 63 | | | | | 2529 | |
| 26.96 ST - Sewage Treatment | | 23 | | | | | 3 | 26 | | 26 | | | | | 1000 | |
| 26.97 SW - Screen Wash | | 15 | | | | | 2 | 17 | | 17 | | | | | 640 | |
| 26.98 SZ - Service Air | | 47 | | | | | 7 | 54 | | 54 | | | | | 2101 | |
| 26.99 Secondary Liquid Waste | 328 | 493 | 191 | 36 | 940 | 513 | 530 | 3030 | 3030 | | 3050 | | | | 33315 | 195 |
| 26.100 Solid Radwaste | | 258 | 207 | 27 | 911 | 289 | 269 | 1961 | 1961 | | 2955 | | | | 11609 | 58 |
| 26.101 Standby Diesel Engine | | 101 | | | | | 15 | 117 | | 117 | | | | | 4394 | |
| 26.102 Stator Cooling Water | | 6 | | | | | <1 | 7 | | 7 | | | | | 249 | |
| 26.103 Steam Generator Blowdown | | 341 | 104 | 29 | 1006 | 429 | 315 | 2225 | 2225 | | 3264 | | | | 14867 | 117 |
| 26.104 Steam Seal | | 12 | | | | | 2 | 14 | | 14 | | | | | 539 | |
| 26.105VA - I&C Shop HVAC | | 3 | | | | | <1 | 4 | | 4 | | | | | 141 | |
| 26.106VB - I&C Shop Computer Room HVAC | | 2 | | | | | <1 | 3 | | 3 | | | | | 95 | |
| 26.107VC - Health Physics Computer Room HVAC | | 5 | | | | | <1 | 5 | | 5 | | | | | 200 | |
| 26.108VH - Circ Water & Makeup Water Scrubs Vt | | 6 | | | | | <1 | 6 | | 6 | | | | | 245 | |

C-7

Document W11-25-002

TABLE C-1 (continued)
DECON COST ESTIMATE FOR WOLF CREEK GENERATING STATION

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Cntgcy | Total | LICTerm | Clean | A CF | B CF | C CF | >C CF | M-Hrs | M-Ren |
|--|-------|--------|------|------|-------|-------|--------|--------|---------|-------|--------|------|------|-------|--------|-------|
| Disposal of Plant Systems (continued) | | | | | | | | | | | | | | | | |
| 26.109VJ - Shop Bldg Machine Shop Area Vent | | 1 | | | | | <1 | 1 | | 1 | | | | | 51 | |
| 26.110VL - Shop Building HVAC | | 2 | | | | | <1 | 2 | | 2 | | | | | 92 | |
| 26.111VS - Admin. Bldg HVAC | | 5 | | | | | <1 | 6 | | 6 | | | | | 238 | |
| 26.112VT - Tech Support Building HVAC | | 2 | | | | | <1 | 2 | | 2 | | | | | 79 | |
| 26.113VV - Misc. Bldg. HVAC | | 3 | | | | | <1 | 3 | | 3 | | | | | 123 | |
| 26.114VW - Waste Water Treatment Ventilation | | 1 | | | | | <1 | 1 | | 1 | | | | | 48 | |
| 26.115WD - Domestic Water | | 25 | | | | | 4 | 28 | | 28 | | | | | 1089 | |
| 26.116WG - Gland Water & Motor Cooling Water | | 17 | | | | | 3 | 20 | | 20 | | | | | 781 | |
| 26.117WL - Cooling Lake Makeup & Blowdown | | 17 | | | | | 3 | 19 | | 19 | | | | | 754 | |
| 26.118WM - Makeup Demineralizer | | 92 | | | | | 14 | 105 | | 105 | | | | | 4108 | |
| 26.119WS - Plant Services Water | | 82 | | | | | 12 | 94 | | 94 | | | | | 3791 | |
| 26.120WT - Waste Water Treatment | | 17 | | | | | 3 | 19 | | 19 | | | | | 767 | |
| 26.121WZ - Radioactive Liquid Waste | | 5 | | | | | <1 | 6 | | 6 | | | | | 237 | |
| 26. Totals | 1238 | 11785 | 2298 | 542 | 18389 | 8031 | 7323 | 49606 | 43671 | 5936 | 59679 | | | | 556167 | 1605 |
| 27. Erect scaffolding for systems removal | | 918 | | | | | 138 | 1056 | 1056 | | | | | | 29008 | |
| Decontamination of Site Buildings | | | | | | | | | | | | | | | | |
| 28.1 Reactor | 784 | 344 | 136 | 39 | 3614 | 304 | 1085 | 6306 | 6306 | 11728 | | | | | 36369 | 136 |
| 28.2 Auxiliary | 409 | 27 | 56 | 16 | 1706 | 83 | 487 | 2784 | 2784 | 5536 | | | | | 14327 | 54 |
| 28.3 Communication Corridor - Contaminated | 9 | <1 | 1 | <1 | 36 | <1 | 10 | 58 | 58 | 118 | | | | | 315 | <1 |
| 28.4 Fuel Building | 378 | 289 | 41 | 13 | 664 | 174 | 393 | 1953 | 1953 | 2156 | | | | | 25593 | 56 |
| 28.5 Hot Machine Shop | 16 | | 1 | <1 | 44 | | 15 | 76 | 76 | 142 | | | | | 546 | 1 |
| 28.6 Radwaste | 218 | 12 | 29 | 8 | 900 | 38 | 257 | 1462 | 1462 | 2921 | | | | | 7625 | 57 |
| 28.7 Radwaste Drum Storage | 24 | 1 | 3 | <1 | 100 | 3 | 28 | 161 | 161 | 324 | | | | | 857 | 2 |
| 28. Totals | 1838 | 674 | 267 | 77 | 7064 | 604 | 2276 | 12800 | 12800 | 22926 | | | | | 85633 | 306 |
| 29. License termination survey | | | | | | 299 | 45 | 344 | 344 | | | | | | | |
| 30. Terminate license | | | | | | | | 8 | | | | | | | | |
| Subtotal Period 2 Activity Costs | 4226 | 19944 | 3437 | 4782 | 61801 | 20117 | 21853 | 136160 | 128986 | 7174 | 175628 | 2897 | 476 | 221 | 827559 | 3744 |

Document W11-25-002

TABLE C-1 (continued)
DECON COST ESTIMATE FOR WOLF CREEK GENERATING STATION

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Contgcy | Total | LicTerm | Clean A | CF | B CF | C CF | >C CF | M-Hrs | M-Ren |
|--|-------------|--------------|-------------|-------------|--------------|---------------|--------------|---------------|---------------|-------------|---------------|--------------|------------|------------|---------------|-------------|
| Period 2 Undistributed Costs | | | | | | | | | | | | | | | | |
| 1. Decon equipment | | | | | | 189 | 28 | 217 | 217 | | | | | | | |
| 2. Decon supplies | | | | | | 501 | 125 | 626 | 626 | | | | | | | |
| 3. DOC staff relocation expenses | | | | | | 845 | 127 | 972 | 972 | | | | | | | |
| 4. Process liquid waste | 344 | | 624 | 651 | 4608 | | 1023 | 7250 | 7250 | | | 9580 | | | 835 | 19 |
| 5. Insurance | | | | | | 1067 | 107 | 1173 | 1173 | | | | | | | |
| 6. Property taxes | | | | | | 1498 | 150 | 1648 | 1483 | 165 | | | | | | |
| 7. Health physics supplies | | | | | | 3464 | 866 | 4330 | 4330 | | | | | | | |
| 8. Heavy equipment rental | | | | | | 7277 | 1092 | 8369 | 7532 | 837 | | | | | | |
| 9. Small tool allowance | | | | | | 343 | 51 | 394 | 355 | 39 | | | | | | |
| 10. Pipe cutting equipment | | | | | | 587 | 88 | 675 | 675 | | | | | | | |
| 11. Decon rig | | | | | | 763 | 114 | 878 | 878 | | | | | | | |
| 12. Disposal of DAW generated | | | 724 | 25 | 3221 | | 559 | 4529 | 4529 | 10490 | | | | | 24597 | 61 |
| 13. Plant energy budget | | | | | | 4611 | 692 | 5303 | 4773 | 530 | | | | | | |
| 14. NRC Fees | | | | | | 322 | 32 | 354 | 354 | | | | | | | |
| 15. Emergency Planning Fees | | | | | | 366 | 37 | 402 | 402 | | | | | | | |
| Subtotal Undistributed Costs Period 2 | 344 | | 1348 | 676 | 7829 | 21832 | 5091 | 37120 | 35549 | 1571 | 10490 | 9580 | | | 25433 | 81 |
| Staff Costs | | | | | | | | | | | | | | | | |
| DOC Staff Cost | | | | | | 17260 | 2589 | 19849 | 19849 | | | | | | | |
| Utility Staff Cost | | | | | | 54026 | 8104 | 62130 | 62130 | | | | | | | |
| TOTAL PERIOD 2 | 4570 | 19944 | 4785 | 5458 | 69630 | 113235 | 37637 | 255260 | 246514 | 8746 | 186118 | 12477 | 476 | 221 | 852991 | 3825 |
| PERIOD 3 | | | | | | | | | | | | | | | | |
| Removal of Major Equipment | | | | | | | | | | | | | | | | |
| 31. Main Turbine/generator | | | 70 | | | | 10 | 80 | | 80 | | | | | 3082 | |
| 32. Main Condensers | | | 219 | | | | 33 | 252 | | 252 | | | | | 9282 | |

TABLE C-1 (continued)
DECON COST ESTIMATE FOR WOLF CREEK GENERATING STATION

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Cntgcy | Total | LicTerm | Clean A CF | B CF | C CF | >C CF | M-Hrs | M-Rm |
|---|-------|--------|------|------|------|-------|--------|-------|---------|------------|------|------|-------|--------|------|
| Demolition of Remaining Site Buildings | | | | | | | | | | | | | | | |
| 33.1 Reactor | 4823 | | | | | | 723 | 5546 | | 5546 | | | | 118164 | |
| 33.2 Access vaults | 37 | | | | | | 6 | 43 | | 43 | | | | 436 | |
| 33.3 Administration | 209 | | | | | | 31 | 241 | | 241 | | | | 4753 | |
| 33.4 Auxiliary | 7834 | | | | | | 1175 | 9009 | | 9009 | | | | 162497 | |
| 33.5 Auxiliary Boiler | 23 | | | | | | 3 | 26 | | 26 | | | | 672 | |
| 33.6 Chlorine Storage | 17 | | | | | | 3 | 19 | | 19 | | | | 376 | |
| 33.7 Circ. water discharge structure | 351 | | | | | | 53 | 403 | | 403 | | | | 4140 | |
| 33.8 Circulating water intake & screenhouse | 828 | | | | | | 124 | 952 | | 952 | | | | 5369 | |
| 33.9 Communication Corridor - Contaminated | 346 | | | | | | 52 | 398 | | 398 | | | | 8911 | |
| 33.10 Communication Corridor-Clean | 2292 | | | | | | 344 | 2635 | | 2635 | | | | 53284 | |
| 33.11 Covered walkways | 8 | | | | | | 1 | 10 | | 10 | | | | 322 | |
| 33.12 Diesel Generator | 398 | | | | | | 60 | 458 | | 458 | | | | 7888 | |
| 33.13 E.S.W.S. Pumphouse | 781 | | | | | | 117 | 898 | | 898 | | | | 5070 | |
| 33.14 ESWS Valve House | 12 | | | | | | 2 | 14 | | 14 | | | | 243 | |
| 33.15 Fuel Building | 2574 | | | | | | 386 | 2960 | | 2960 | | | | 63283 | |
| 33.16 Hot Machine shop | 22 | | | | | | 3 | 25 | | 25 | | | | 639 | |
| 33.17 M.W.O. Building | 172 | | | | | | 26 | 198 | | 198 | | | | 3483 | |
| 33.18 Misc. Site Foundations | 374 | | | | | | 56 | 431 | | 431 | | | | 7394 | |
| 33.19 Misc. Site Structures | 999 | | | | | | 150 | 1149 | | 1149 | | | | 20240 | |
| 33.20 Oil Separator and Waste Tank | 2 | | | | | | <1 | 3 | | 3 | | | | 48 | |
| 33.21 Radwaste | 2714 | | | | | | 407 | 3121 | | 3121 | | | | 58493 | |
| 33.22 Radwaste Drum Storage | 422 | | | | | | 63 | 485 | | 485 | | | | 12006 | |
| 33.23 Security/Guardhouse | 317 | | | | | | 47 | 364 | | 364 | | | | 4682 | |
| 33.24 Site Diesel Generator | 3 | | | | | | <1 | 3 | | 3 | | | | 60 | |
| 33.25 Turbine Building | 5712 | | | | | | 857 | 6569 | | 6569 | | | | 166045 | |
| 33.26 Waste Water Treatment | 17 | | | | | | 3 | 20 | | 20 | | | | 432 | |
| 33. Totals | 31285 | | | | | | 4693 | 35978 | | 35978 | | | | 708928 | |

C-10

Document W11-25-002

TABLE C-1 (continued)
DECON COST ESTIMATE FOR WOLF CREEK GENERATING STATION

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Cntgcy | Total | LicTerm | Clean | A CF | B CF | C CF | >C CF | M-Hrs | M-Rom |
|---------------------------------------|-------|--------|------|------|------|-------|--------|-------|---------|-------|------|------|------|-------|--------|-------|
| <hr/> | | | | | | | | | | | | | | | | |
| Site Closeout Activities | | | | | | | | | | | | | | | | |
| 34. Remove Rubble | | 3804 | | | | | 571 | 4374 | | 4374 | | | | | 12323 | |
| 35. Grade & landscape site | | 1393 | | | | | 209 | 1602 | | 1602 | | | | | 8028 | |
| 36. Final report to NRC | | | | | | 156 | 23 | 179 | 179 | | | | | | | |
| Subtotal Period 3 Activity Costs | | 36771 | | | | 156 | 5539 | 42466 | 179 | 42287 | | | | | 741643 | |
| Period 3 Undistributed Costs | | | | | | | | | | | | | | | | |
| 1. Insurance | | | | | | 172 | 17 | 189 | 189 | | | | | | | |
| 2. Property taxes | | | | | | 514 | 51 | 565 | | 565 | | | | | | |
| 3. Heavy equipment rental | | | | | | 2159 | 324 | 2483 | | 2483 | | | | | | |
| 4. Small tool allowance | | | | | | 286 | 43 | 329 | | 329 | | | | | | |
| 5. Plant energy budget | | | | | | 119 | 18 | 137 | | 137 | | | | | | |
| Subtotal Undistributed Costs Period 3 | | | | | | 3250 | 453 | 3704 | 189 | 3515 | | | | | | |
| Staff Costs | | | | | | | | | | | | | | | | |
| DOC Staff Cost | | | | | | 6145 | 922 | 7067 | | 7067 | | | | | | |
| Utility Staff Cost | | | | | | 7481 | 1122 | 8604 | 7743 | 860 | | | | | | |
| TOTAL PERIOD 3 | | 36771 | | | | 17033 | 8036 | 61840 | 8112 | 53728 | | | | | 741643 | |

C-11

TABLE C-1 (continued)
DECON COST ESTIMATE FOR WOLF CREEK GENERATING STATION

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Contgcy | Total | License | Term | Clean | A CF | B CF | C CF | +C CF | M-Hrs | M-Rm |
|---|-------|--------|------|------|-------|--------|---------------|--------|------------|-------|--------|-------|------|------|---------|-------|------|
| TOTAL COST TO DECOMMISSION | 4638 | 56716 | 5017 | 5510 | 70592 | 174739 | 52578 | 369790 | 307316 | 62474 | 188591 | 12935 | 476 | 221 | 1601479 | 3844 | |
| TOTAL COST TO DECOMMISSION WITH 16.58% CONTINGENCY: | | | | | | | \$369,789.856 | | | | | | | | | | |
| TOTAL NRC LICENSE TERMINATION COST IS 83.11% OR | | | | | | | \$307,315.744 | | | | | | | | | | |
| NON-NUCLEAR DEMOLITION COST IS 16.89% OR: | | | | | | | \$ 62,474.080 | | | | | | | | | | |
| TOTAL RADWASTE VOLUME BURIED: | | | | | | | 202.223 | | cubic foot | | | | | | | | |
| TOTAL SCRAP METAL REMOVED: | | | | | | | 41,775.9 | | tons | | | | | | | | |
| TOTAL CRAFT LABOR REQUIREMENTS: | | | | | | | 1,601,478.5 | | man-hours | | | | | | | | |
| TOTAL PERSONNEL RADIATION EXPOSURE: | | | | | | | 3,844.5 | | man-rem | | | | | | | | |
| TOTAL CRAFT LABOR COST WITH 22.51% CONTINGENCY: | | | | | | | \$ 43,652.808 | | | | | | | | | | |

C-12

Document W11-25-002

TABLE C-2
SAFSTOR COST ESTIMATE FOR WOLF CREEK GENERATING STATION
(THOUSANDS OF 1993 DOLLARS)

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Cntgcy | Total | LicTerm | Clean A CF | B CF | C CF | >C CF | M-Hrs | M-Rom |
|---|-------|--------|------|------|------|-------|--------|-------|---------|------------|------|------|-------|-------|-------|
| PERIOD 1: Mothballing Activities | | | | | | | | | | | | | | | |
| 1. Prepare preliminary decommissioning plan | | | | | | 120 | 18 | 138 | 138 | | | | | | |
| 2. Prepare proposed decommissioning plan | | | | | | 312 | 47 | 359 | 359 | | | | | | |
| 3. Remove fuel & source material | | | | | | | | n/a | | | | | | | |
| 4. Decon plant & process waste | | | | | | | | a | | | | | | | |
| 5. Review plant dwgs & specs. | | | | | | 130 | 20 | 150 | 150 | | | | | | |
| 6. Perform detailed rad survey | | | | | | | | a | | | | | | | |
| 7. Estimate by-product inventory | | | | | | 100 | 15 | 115 | 115 | | | | | | |
| 8. Submit for possession-only license | | | | | | 100 | 15 | 115 | 115 | | | | | | |
| 9. End product description | | | | | | 100 | 15 | 115 | 115 | | | | | | |
| 10. Detailed by-product inventory | | | | | | 150 | 23 | 173 | 173 | | | | | | |
| 11. Define major work sequence | | | | | | 100 | 15 | 115 | 115 | | | | | | |
| 12. Perform safety analysis of operation | | | | | | 200 | 30 | 230 | 230 | | | | | | |
| 13. Perform safety analysis of end product | | | | | | 200 | 30 | 230 | 230 | | | | | | |
| 14. Submit dismantling plan | | | | | | 100 | 15 | 115 | 115 | | | | | | |
| 15. Receive possession-only license | | | | | | | | a | | | | | | | |
| Activity Specifications | | | | | | | | | | | | | | | |
| 16.1 Prepare plant and facilities for mothbal | | | | | | 492 | 74 | 566 | 566 | | | | | | |
| 16.2 Plant systems | | | | | | 417 | 63 | 479 | 479 | | | | | | |
| 16.3 Plant structures and buildings | | | | | | 312 | 47 | 359 | 359 | | | | | | |
| 16.4 Waste management | | | | | | 200 | 30 | 230 | 230 | | | | | | |
| 16.5 Facility and site dormancy | | | | | | 200 | 30 | 230 | 230 | | | | | | |
| 16. Total | | | | | | 1621 | 243 | 1864 | 1864 | | | | | | |
| Detailed Work Procedures | | | | | | | | | | | | | | | |
| 17.1 Plant systems | | | | | | 473 | 71 | 544 | 544 | | | | | | |
| 17.2 Facility closeout & dormancy | | | | | | 120 | 18 | 138 | 138 | | | | | | |
| 17. Total | | | | | | 593 | 89 | 682 | 682 | | | | | | |

NOTES- "n/a" Indicates that fuel handling, packaging, shipping, and disposal are charged to plant operations, not decommissioning
 - "a" Indicates that costs are included in the utility staff costs.
 - Columns may not total due to rounding errors.

C-13

Document W11-25-002

TABLE C-2 (continued)
SAFSTOR COST ESTIMATE FOR WOLF CREEK GENERATING STATION

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Critcgy | Total | LICTERM | Clean | A CF | B CF | C CF | -C CF | M-HRS | M-ROB |
|--|-------|--------|------|------|------|-------|---------|-------|---------|-------|------|------|------|-------|-------|-------|
| Detailed Work Procedures (continued) | | | | | | | | | | | | | | | | |
| 18. Procure vacuum drying system | | | | | | 10 | 2 | 12 | 12 | | | | | | | |
| 19. Drain/de-energize non-cont. systems | | | | | | | | a | | | | | | | | |
| 20. Drain & dry NSSS | | | | | | | | a | | | | | | | | |
| 21. Drain/de-energize contaminated systems | | | | | | | | a | | | | | | | | |
| 22. Decon/secure contaminated systems | | | | | | | | a | | | | | | | | |
| Decontamination of Site Buildings | | | | | | | | | | | | | | | | |
| 23.1 Reactor | 680 | | | | | | 340 | 1019 | 1019 | | | | | | 22048 | |
| 23.2 Auxiliary | 313 | | | | | | 156 | 469 | 469 | | | | | | 9872 | |
| 23.3 Communication corridor - contaminated | 7 | | | | | | 3 | 10 | 10 | | | | | | 216 | |
| 23.4 Fuel Building | 324 | | | | | | 162 | 486 | 486 | | | | | | 11308 | |
| 23.5 Hot Machine Shop | 9 | | | | | | 4 | 13 | 13 | | | | | | 271 | |
| 23.6 Radwaste | 167 | | | | | | 83 | 250 | 250 | | | | | | 5257 | |
| 23.7 Radwaste Drum Storage | 19 | | | | | | 9 | 28 | 28 | | | | | | 591 | |
| 23. Totals | 1517 | | | | | | 758 | 2275 | 2275 | | | | | | 49565 | |
| 24. Prepare support equipment for storage | | 235 | | | | | 35 | 271 | 271 | | | | | | 3000 | 3 |
| 25. Install containment pressure equal. line | | 19 | | | | | 3 | 22 | 22 | | | | | | 700 | 2 |
| 26. Interim survey prior to dormancy | | | | | | 299 | 45 | 344 | 344 | | | | | | | |
| 27. Secure building accesses | | | | | | | | a | | | | | | | | |
| 28. Prepare & submit interim report | | | | | | 58 | 9 | 67 | 67 | | | | | | | |
| Subtotal Period 1 Activity Costs | 1517 | 254 | | | | 4193 | 1426 | 7390 | 7390 | | | | | | 53265 | 5 |
| Period 1 Undistributed Costs | | | | | | | | | | | | | | | | |
| 1. Decon equipment | | | | | | 189 | 28 | 217 | 217 | | | | | | | |
| 2. Decon supplies | | | | | | 137 | 34 | 171 | 171 | | | | | | | |
| 3. Process liquid waste | 256 | | 131 | 175 | 761 | | 282 | 1605 | 1605 | | | 1744 | | | 452 | 11 |
| 4. Insurance | | | | | | 222 | 22 | 244 | 244 | | | | | | | |
| 5. Property taxes | | | | | | 421 | 42 | 463 | 463 | | | | | | | |
| 6. Health physics supplies | | | | | | 947 | 237 | 1184 | 1184 | | | | | | | |
| 7. Small tool allowance | | | | | | 22 | 3 | 25 | 25 | | | | | | | |
| 8. Disposal of DAW generated | | | 198 | 6 | 762 | | 135 | 1101 | 1101 | | 2473 | | | | 6725 | 17 |

C-14

Document W11-25-002

TABLE C-2 (continued)
SAFSTOR COST ESTIMATE FOR WOLF CREEK GENERATING STATION

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Contgcy | Total | Licenses | Clean A CF | B CF | C CF | >C CF | M-Hrs | M-Rm |
|---|-------|--------|------|------|------|-------|---------|--------------|------------|------------|------|------|-------|-------|------|
| Period 1 Undistributed Costs (continued) | | | | | | | | | | | | | | | |
| 9. Plant energy budget | | | | | | 1261 | 189 | 1451 | 1451 | | | | | | |
| 10. NRC Fees | | | | | | 44 | 4 | 48 | 48 | | | | | | |
| 11. Emergency Planning Fees | | | | | | 100 | 10 | 110 | 110 | | | | | | |
| Subtotal Undistributed Costs Period 1 | 256 | | 329 | 181 | 1523 | 3342 | 987 | 6619 | 6619 | 2473 | 1744 | | | 7178 | 27 |
| Staff Costs | | | | | | | | | | | | | | | |
| DOC Staff Cost | | | | | | | | | | | | | | | |
| Utility Staff Cost | | | | | | 11330 | 1699 | 13029 | 13029 | | | | | | |
| TOTAL COST TO MOTHBALL | 1773 | 254 | 329 | 181 | 1523 | 18865 | 4112 | 27038 | 27038 | 2473 | 1744 | | | 60443 | 32 |
| TOTAL COST TO MOTHBALL WITH 17.94% CONTINGENCY: | | | | | | | | \$27,037,874 | | | | | | | |
| TOTAL MOTHBALLING RADWASTE VOLUME BURIED: | | | | | | | | 4,216 | cubic feet | | | | | | |
| TOTAL SCRAP REMOVED: | | | | | | | | 0.0 | tons | | | | | | |
| TOTAL CRAFT LABOR REQUIREMENTS: | | | | | | | | 60,442.6 | man-hours | | | | | | |
| TOTAL PERSONNEL RADIATION EXPOSURE: | | | | | | | | 32.1 | man-rem | | | | | | |
| TOTAL CRAFT LABOR COST WITH 17.94% CONTINGENCY: | | | | | | | | \$1,243,463 | | | | | | | |

C-15

Document W11-25-002

TABLE C-2 (continued)
SAFSTOR COST ESTIMATE FOR WOLF CREEK GENERATING STATION

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Cntgcy | Total | LicTerm | Clean | A CF | B CF | C CF | +C CF | M-Hrs | M-Rom |
|--|-------|--------|------|------|------|-------|--------|---------------|---------|-------|------|------|------|-------|-------|-------|
| PERIOD 2: Mothballed Annual Maintenance Cost | | | | | | | | | | | | | | | | |
| 1. Quarterly inspection | | | | | | | | \$ | | | | | | | | |
| 2. Semi-annual environmental survey | | | | | | | | \$ | | | | | | | | |
| 3. Prepare reports | | | | | | | | \$ | | | | | | | | |
| 4. Health physics supplies | | | | | | 36 | 9 | 45 | 45 | | | | | | | |
| 5. Insurance | | | | | | 53 | 5 | 58 | 58 | | | | | | | |
| 6. Property taxes | | | | | | 421 | 42 | 463 | 463 | | | | | | | |
| 7. Disposal of contaminated solid waste | 1 | <1 | | 39 | | | 6 | 47 | 47 | 128 | | | | | 35 | <1 |
| 8. Bituminous roof replacement | | | | | | 36 | 5 | 41 | 41 | | | | | | | |
| 9. Maintenance supplies | | | | | | 77 | 19 | 97 | 97 | | | | | | | |
| 10. Plant energy budget | | | | | | 170 | 26 | 196 | 196 | | | | | | | |
| 11. NRC Fees | | | | | | 10 | <1 | 11 | 11 | | | | | | | |
| 12. Emergency Planning Fees | | | | | | 7 | <1 | 8 | 8 | | | | | | | |
| 13. Site maintenance staff | | | | | | 3651 | 548 | 4199 | 4199 | | | | | | | |
| PERIOD 2 ANNUAL MAINTENANCE TOTALS | | | | | | | | | | | | | | | | |
| | 1 | <1 | | 39 | | 4462 | 662 | 5165 | 5165 | 128 | | | | | 35 | <1 |
| MAINTENANCE COST FOR 55.1125 YEARS DORMANCY: | | | | | | | | \$284,644,128 | | | | | | | | |
| PERIOD 3 | | | | | | | | | | | | | | | | |
| 1. Review plant dwgs & specs. | | | | | | 460 | 69 | 529 | 529 | | | | | | | |
| 2. Perform detailed rad survey | | | | | | | | n/a | | | | | | | | |
| 3. End product description | | | | | | 100 | 15 | 115 | 115 | | | | | | | |
| 4. Detailed by-product inventory | | | | | | 130 | 20 | 150 | 150 | | | | | | | |
| 5. Define major work sequence | | | | | | 750 | 113 | 863 | 863 | | | | | | | |
| 6. Perform safety analysis | | | | | | 310 | 47 | 357 | 357 | | | | | | | |
| 7. Submit dismantling plan | | | | | | 52 | 8 | 60 | 60 | | | | | | | |
| 8. Receive dismantling order | | | | | | | | a | | | | | | | | |
| Subtotal Period 3 Activity Costs | | | | | | 1802 | 270 | 2072 | 2072 | | | | | | | |

C-16

Document W11-25-002

TABLE C-2 (continued)
SAFSTOR COST ESTIMATE FOR WOLF CREEK GENERATING STATION

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Cntgcy | Total | LicTerm | Clean A CF | B CF | C CF | HC CF | M-Hrs | M-Rom |
|--|-------|--------|------|------|------|-------|--------|-------|---------|------------|------|------|-------|-------|-------|
| Period 3 Undistributed costs | | | | | | | | | | | | | | | |
| 1. DOC staff relocation expenses | | | | | | 845 | 127 | 972 | 972 | | | | | | |
| 2. Insurance | | | | | | 333 | 33 | 366 | 366 | | | | | | |
| 3. Property taxes | | | | | | 632 | 63 | 695 | 695 | | | | | | |
| 4. Health physics supplies | | | | | | 947 | 237 | 1184 | 1184 | | | | | | |
| 5. Heavy equipment rental | | | | | | 233 | 35 | 267 | 267 | | | | | | |
| 6. Disposal of DAW generated | | | 196 | 6 | 762 | | 135 | 1099 | 1099 | 2473 | | | | 6725 | 17 |
| 7. Plant energy budget | | | | | | 1907 | 286 | 2193 | 2193 | | | | | | |
| 8. NRC Fees | | | | | | 66 | 7 | 73 | 73 | | | | | | |
| Subtotal Undistributed costs Period 3 | | | 196 | 6 | 762 | 4962 | 922 | 6849 | 6849 | 2473 | | | | 6725 | 17 |
| Staff costs | | | | | | | | | | | | | | | |
| DOC Staff Cost | | | | | | 4607 | 691 | 5298 | 5298 | | | | | | |
| Utility Staff Cost | | | | | | 13449 | 2017 | 15466 | 15466 | | | | | | |
| TOTAL PERIOD 3 COST | | | 196 | 6 | 762 | 24820 | 3901 | 29685 | 29685 | 2473 | | | | 6725 | 17 |
| PERIOD 4 | | | | | | | | | | | | | | | |
| Activity Specifications | | | | | | | | | | | | | | | |
| 9.1 Re-activate plant & temporary facilities | | | | | | 737 | 111 | 848 | 763 | 85 | | | | | |
| 9.2 Plant systems | | | | | | 417 | 63 | 479 | 431 | 48 | | | | | |
| 9.3 Reactor Internals | | | | | | 710 | 107 | 817 | 817 | | | | | | |
| 9.4 Reactor vessel | | | | | | 650 | 98 | 748 | 748 | | | | | | |
| 9.5 Biological shield | | | | | | 50 | 8 | 58 | 58 | | | | | | |
| 9.6 Steam generators | | | | | | 312 | 47 | 359 | 359 | | | | | | |
| 9.7 Reinforced concrete | | | | | | 160 | 24 | 184 | 92 | 92 | | | | | |
| 9.8 Turbine & condenser | | | | | | 80 | 12 | 92 | | 92 | | | | | |
| 9.9 Plant structures & buildings | | | | | | 312 | 47 | 359 | 179 | 179 | | | | | |
| 9.10 Waste Management | | | | | | 460 | 69 | 529 | 529 | | | | | | |
| 9.11 Facility & site closeout | | | | | | 90 | 14 | 104 | 52 | 52 | | | | | |
| 9. Total | | | | | | 3978 | 597 | 4574 | 4026 | 548 | | | | | |

C-17

Document W11-25-002

TABLE C-2 (continued)
SAFSTOR COST ESTIMATE FOR WOLF CREEK GENERATING STATION

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Cntgcy | Total | LicTerm | Clean | A CF | B CF | C CF | -C CF | M-Hrs | M-Rm |
|---|-------|--------|------|------|------|-------|--------|-------|---------|-------|------|------|------|-------|-------|------|
| Planning & Site Preparations | | | | | | | | | | | | | | | | |
| 10. Prepare dismantling sequence | | | | | | 240 | 36 | 276 | 276 | | | | | | | |
| 11. Plant prep. & temp. svces | | | | | | 1485 | 223 | 1708 | 1708 | | | | | | | |
| 12. Design water clean-up system | | | | | | 140 | 21 | 161 | 161 | | | | | | | |
| 13. Rigging/CCEs/tooling/etc. | | | | | | 1257 | 189 | 1446 | 1446 | | | | | | | |
| 14. Procure casks/liners & containers | | | | | | 123 | 18 | 141 | 141 | | | | | | | |
| Detailed Work Procedures | | | | | | | | | | | | | | | | |
| 15.1 Plant systems | | | | | | 473 | 71 | 544 | 490 | 54 | | | | | | |
| 15.2 Vessel head | | | | | | 250 | 38 | 288 | 288 | | | | | | | |
| 15.3 Reactor Internals | | | | | | 250 | 38 | 288 | 288 | | | | | | | |
| 15.4 Remaining buildings | | | | | | 135 | 20 | 155 | 39 | 116 | | | | | | |
| 15.5 CRD cooling assembly | | | | | | 100 | 15 | 115 | 115 | | | | | | | |
| 15.6 CRD housings & ICI tubes | | | | | | 100 | 15 | 115 | 115 | | | | | | | |
| 15.7 Incore instrumentation | | | | | | 100 | 15 | 115 | 115 | | | | | | | |
| 15.8 Reactor vessel | | | | | | 363 | 54 | 417 | 417 | | | | | | | |
| 15.9 Facility closeout | | | | | | 120 | 18 | 138 | 69 | 69 | | | | | | |
| 15.10 Missile shields | | | | | | 45 | 7 | 52 | 52 | | | | | | | |
| 15.11 Biological shield | | | | | | 120 | 18 | 138 | 138 | | | | | | | |
| 15.12 Steam generators | | | | | | 460 | 69 | 529 | 529 | | | | | | | |
| 15.13 Reinforced concrete | | | | | | 100 | 15 | 115 | 58 | 58 | | | | | | |
| 15.14 Turbine & condensers | | | | | | 312 | 47 | 359 | | 359 | | | | | | |
| 15.15 Auxiliary building | | | | | | 273 | 41 | 314 | 283 | 31 | | | | | | |
| 15.16 Reactor building | | | | | | 273 | 41 | 314 | 283 | 31 | | | | | | |
| 15. Total | | | | | | 3474 | 521 | 3995 | 3276 | 719 | | | | | | |
| 16. Remove spent fuel racks | 200 | 35 | 79 | 22 | 945 | 731 | 371 | 2383 | 2383 | | 3150 | | | | 7874 | 42 |

C-18

Document W11-25-002

TABLE C-2 (continued)
SAFSTOR COST ESTIMATE FOR WOLF CREEK GENERATING STATION

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Cntgcy | Total | LicTerm | Clean | A CF | B CF | C CF | -C CF | M-Hrs | M-Rm |
|--|-------|--------|------|------|-------|-------|--------|-------|---------|-------|-------|------|------|-------|--------|------|
| Nuclear Steam Supply System Removal | | | | | | | | | | | | | | | | |
| 17.1 Reactor Coolant Piping | 61 | 118 | 62 | 18 | 2066 | | 379 | 2703 | 2703 | | 6485 | | | | 7280 | 26 |
| 17.2 Pressurizer Relief Tank | 11 | 56 | 5 | 4 | 196 | | 50 | 321 | 321 | | 621 | | | | 2731 | 2 |
| 17.3 Reactor Coolant Pumps & Motors | 23 | 35 | 33 | 40 | 3491 | | 553 | 4175 | 4175 | | 11312 | | | | 2633 | 2 |
| 17.4 Pressurizer | 22 | 27 | 4 | 10 | 1280 | | 212 | 1554 | 1554 | | 4147 | | | | 1852 | 1 |
| 17.5 Steam Generators | 125 | 2487 | 133 | 3502 | 17895 | | 3907 | 28050 | 28050 | | 58484 | | | | 98627 | 50 |
| 17.6 CRDMs/ ICIs/Service Structure Removal | 54 | 36 | 20 | 14 | 596 | | 130 | 851 | 851 | | 1843 | | | | 3308 | 2 |
| 17.7 Reactor Vessel Internals | 38 | 984 | 251 | 220 | 6201 | | 1805 | 9499 | 9499 | | 1834 | 393 | 476 | 221 | 11270 | 3 |
| 17.8 Reactor Vessel | 94 | 2656 | 265 | 252 | 2569 | | 2553 | 8389 | 8389 | | 5540 | 2096 | | | 15026 | 4 |
| 17. Totals | 429 | 6398 | 773 | 4059 | 34294 | | 9589 | 55542 | 55542 | | 90266 | 2489 | 476 | 221 | 142727 | 90 |
| Disposal of Plant Systems | | | | | | | | | | | | | | | | |
| 18.1 AX - Acid Feed | | 19 | | | | | 3 | 22 | | 22 | | | | | 833 | |
| 18.2 Accumulator Safety Injection | | 81 | 26 | 6 | 190 | 121 | 70 | 495 | 495 | | 617 | | | | 3503 | 28 |
| 18.3 Auxiliary Bldg Non-System Specific Clean | | 404 | | | | | 61 | 465 | | 465 | | | | | 17709 | |
| 18.4 Auxiliary Bldg Non-System Specific Cont | | 217 | 102 | 34 | 767 | 577 | 271 | 1968 | 1968 | | 2488 | | | | 9846 | 12 |
| 18.5 Auxiliary Bldg Non-System Specific Decon | 31 | 135 | | | | | 36 | 202 | 47 | 155 | | | | | 7182 | |
| 18.6 Auxiliary Building HVAC | | 260 | 46 | 12 | 290 | 213 | 147 | 967 | 967 | | 940 | | | | 8707 | 12 |
| 18.7 Auxiliary Feedwater | | 20 | | | | | 3 | 23 | | 23 | | | | | 912 | |
| 18.8 Auxiliary Steam | | 65 | | | | | 10 | 75 | | 75 | | | | | 2948 | |
| 18.9 Auxiliary Steam Chemical Addition | | 3 | | | | | <1 | 3 | | 3 | | | | | 121 | |
| 18.10 Auxiliary Steam Generator | | 7 | | | | | 1 | 8 | | 8 | | | | | 321 | |
| 18.11 Auxiliary Turbines | | 31 | | | | | 5 | 36 | | 36 | | | | | 1358 | |
| 18.12 Borated Refueling Water Storage | | 149 | 56 | 9 | 355 | 266 | 137 | 972 | 972 | | 1152 | | | | 6477 | 21 |
| 18.13 Boron Recycle | | 252 | 70 | 18 | 438 | 275 | 180 | 1232 | 1232 | | 1422 | | | | 10710 | 115 |
| 18.14 CL - Chlorination | | 14 | | | | | 2 | 16 | | 16 | | | | | 607 | |
| 18.15 CW - Circulating Water | | 190 | | | | | 29 | 219 | | 219 | | | | | 8903 | |
| 18.16 CZ - Caustic Acid | | 3 | | | | | <1 | 3 | | 3 | | | | | 134 | |
| 18.17 Central Chilled Water | | 51 | | | | | 8 | 59 | | 59 | | | | | 2304 | |
| 18.18 Chemical & Detergent Waste | 27 | 69 | 18 | 5 | 124 | 85 | 65 | 393 | 393 | | 401 | | | | 4051 | 23 |
| 18.19 Chemical & Volume Control | 326 | 466 | 171 | 47 | 2147 | 560 | 710 | 4429 | 4429 | | 6968 | | | | 28855 | 160 |
| 18.20 Closed Cooling Water | | 32 | | | | | 5 | 37 | | 37 | | | | | 1443 | |
| 18.21 Co - Carbon Dioxide | | 4 | | | | | <1 | 5 | | 5 | | | | | 177 | |
| 18.22 Component Cooling Water | | 134 | | | | | 20 | 154 | | 154 | | | | | 6177 | |
| 18.23 Condensate | | 133 | | | | | 20 | 153 | | 153 | | | | | 5956 | |
| 18.24 Condensate & Feedwater Chemical Addition | | 12 | | | | | 2 | 14 | | 14 | | | | | 526 | |
| 18.25 Condensate Demineralizer | | 46 | | | | | 7 | 53 | | 53 | | | | | 2068 | |

C-19

Document W11-25-002

TABLE C-2 (continued)
SAFSTOR COST ESTIMATE FOR WOLF CREEK GENERATING STATION

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Cntgcy | Total | LICTerm | Clean | A CF | B CF | C CF | >C CF | M-Hrs | M-Rm |
|--|-------|--------|------|------|------|-------|--------|-------|---------|-------|------|------|------|-------|-------|------|
| 18.26 Condensate Storage & Transfer | | 39 | | | | | 6 | 45 | | 45 | | | | | 1656 | |
| 18.27 Condenser Air Removal | | 16 | | | | | 2 | 18 | | 18 | | | | | 699 | |
| 18.28 Containment Atmospheric Control | | 6 | 22 | 4 | 377 | 19 | 64 | 491 | 491 | | 1222 | | | | 302 | <1 |
| 18.29 Containment Cooling | | 305 | 103 | 22 | 1119 | 313 | 305 | 2166 | 2166 | | 3631 | | | | 11519 | 14 |
| 18.30 Containment Hydrogen Control | | 26 | 19 | 5 | 148 | 85 | 44 | 327 | 327 | | 481 | | | | 1153 | <1 |
| 18.31 Containment Integrated Leak Rate Test | | 6 | | | | | <1 | 7 | | 7 | | | | | 287 | |
| 18.32 Containment Purge HVAC | | 66 | 32 | 5 | 322 | 110 | 85 | 622 | 622 | | 1046 | | | | 2469 | 3 |
| 18.33 Containment Spray | 44 | 40 | | | | | 28 | 112 | 67 | 46 | | | | | 3219 | |
| 18.34 Control Bldg Non-System Specific Clean | | 378 | | | | | 57 | 435 | | 435 | | | | | 16569 | |
| 18.35 Control Bldg Non-System Specific Cont | | 199 | 105 | 34 | 759 | 571 | 265 | 1933 | 1933 | | 2462 | | | | 9079 | 11 |
| 18.36 Control Bldg Non-System Specific Decon | 32 | 124 | | | | | 34 | 189 | 47 | 142 | | | | | 6691 | |
| 18.37 Control Building HVAC | | 147 | | | | | 22 | 169 | | 169 | | | | | 6162 | |
| 18.38 DA - Circulating Water System | | 196 | | | | | 29 | 226 | | 226 | | | | | 9126 | |
| 18.39 DM - Equipment Drains | | 60 | | | | | 9 | 69 | | 69 | | | | | 2710 | |
| 18.40 DO - Diesel Oil | | 1 | | | | | <1 | 1 | | 1 | | | | | 47 | |
| 18.41 Decontamination | | 39 | 46 | 6 | 134 | 88 | 49 | 361 | 361 | | 435 | | | | 1762 | 5 |
| 18.42 Demineralized Water Storage & Transfer | | 41 | | | | | 6 | 47 | | 47 | | | | | 1819 | |
| 18.43 Diesel Generator Building HVAC | | 27 | | | | | 4 | 31 | | 31 | | | | | 1115 | |
| 18.44 EA - Service Water | | 63 | | | | | 10 | 73 | | 73 | | | | | 2928 | |
| 18.45 EF - Essential Service Water | | 77 | | | | | 12 | 89 | | 89 | | | | | 3541 | |
| 18.46 Emergency Fuel Oil | | 31 | | | | | 5 | 36 | | 36 | | | | | 1329 | |
| 18.47 FO - Fuel Oil | | 14 | | | | | 2 | 16 | | 16 | | | | | 625 | |
| 18.48 FP - Fire Protection | | 152 | | | | | 23 | 175 | | 175 | | | | | 7096 | |
| 18.49 Feedwater | | 90 | | | | | 14 | 104 | | 104 | | | | | 4105 | |
| 18.50 Feedwater Heater Extraction | | 135 | | | | | 20 | 155 | | 155 | | | | | 6164 | |
| 18.51 Floor & Equipment Drains | | 1005 | 207 | 55 | 1342 | 971 | 627 | 4208 | 4208 | | 4357 | | | | 42514 | 116 |
| 18.52 Fuel Bldg Non-System Specific Clean | | 52 | | | | | 8 | 60 | | 60 | | | | | 2293 | |
| 18.53 Fuel Bldg Non-System Specific Cont | | 31 | 15 | 5 | 118 | 89 | 41 | 300 | 300 | | 383 | | | | 1429 | 2 |
| 18.54 Fuel Bldg Non-System Specific Decon | 3 | 16 | | | | | 4 | 24 | 5 | 18 | | | | | 840 | |
| 18.55 Fuel Building HVAC | | 143 | 45 | 10 | 518 | 123 | 138 | 977 | 977 | | 1682 | | | | 4864 | 7 |
| 18.56 Fuel Handling & Storage Reactor Vessel | | 6 | 8 | 5 | 266 | | 43 | 328 | 328 | | 864 | | | | 259 | <1 |
| 18.57 Fuel Pool Cooling & Cleanup | | 228 | 70 | 18 | 649 | 301 | 209 | 1475 | 1475 | | 2106 | | | | 9874 | 27 |
| 18.58 GD - Esstl. Srvc. Wtr Pumps, Bldg HVAC | | 9 | | | | | 1 | 10 | | 10 | | | | | 365 | |
| 18.59 GE - Turbine Bldg HVAC | | 102 | | | | | 15 | 118 | | 118 | | | | | 4319 | |
| 18.60 GF - Miscellaneous Building HVAC | | 33 | | | | | 5 | 38 | | 38 | | | | | 1387 | |
| 18.61 Gaseous Radwaste | | 150 | 70 | 15 | 512 | 159 | 147 | 1053 | 1053 | | 1662 | | | | 6409 | 15 |
| 18.62 Generator Hydrogen Seal & CO2 | | 5 | | | | | <1 | 6 | | 6 | | | | | 210 | |

C-20

Document W11-25-002

TABLE C-2 (continued)
SAFSTOR COST ESTIMATE FOR WOLF CREEK GENERATING STATION

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Chgcy | Total | LicTerm | Clean | A CF | B CF | C CF | >C CF | M-Hrs | M-Rom |
|--|-------|--------|------|------|------|-------|-------|-------|---------|-------|------|------|------|-------|-------|-------|
| Disposal of Plant Systems (continued) | | | | | | | | | | | | | | | | |
| 18.63 Generator Seal oil | | 7 | | | | | 1 | 8 | | 8 | | | | | 296 | |
| 18.64 HY - Hydrogen | | 6 | | | | | <1 | 7 | | 7 | | | | | 277 | |
| 18.65 High Pressure Coolant Injection | | 159 | 57 | 17 | 518 | 240 | 162 | 1152 | 1152 | | 1682 | | | | 6875 | 33 |
| 18.66 KA - Compressed Air and Instrument | | 160 | | | | | 24 | 185 | | 185 | | | | | 7081 | |
| 18.67 KB - Breathing Air | | 26 | | | | | 4 | 30 | | 30 | | | | | 1182 | |
| 18.68 KC - Fire Protection | | 277 | | | | | 42 | 319 | | 319 | | | | | 12879 | |
| 18.69 KD - Domestic Water | | 46 | | | | | 7 | 52 | | 52 | | | | | 2023 | |
| 18.70 KH - Service Gas | | 18 | | | | | 3 | 21 | | 21 | | | | | 780 | |
| 18.71 LA - Sanitary Drains | | 13 | | | | | 2 | 15 | | 15 | | | | | 582 | |
| 18.72 LC - Yard Drains | | 2 | | | | | <1 | 3 | | 3 | | | | | 95 | |
| 18.73 LE - Oily Waste | | 98 | | | | | 15 | 112 | | 112 | | | | | 4433 | |
| 18.74 Liquid Radwaste | 347 | 408 | 129 | 27 | 823 | 394 | 475 | 2603 | 2603 | | 2670 | | | | 29740 | 347 |
| 18.75 Lube Oil Storage, Transfer, & Purification | | 21 | | | | | 3 | 24 | | 24 | | | | | 925 | |
| 18.76 Main Steam | | 139 | | | | | 21 | 160 | | 160 | | | | | 6475 | |
| 18.77 Main Turbine | | 131 | | | | | 20 | 151 | | 151 | | | | | 5932 | |
| 18.78 Main Turbine Control Oil | | 29 | | | | | 4 | 33 | | 33 | | | | | 1211 | |
| 18.79 Main Turbine Lube Oil | | 27 | | | | | 4 | 31 | | 31 | | | | | 1164 | |
| 18.80 NT - Nitrogen | | 4 | | | | | <1 | 5 | | 5 | | | | | 186 | |
| 18.81 Nuclear Sampling | | 30 | 46 | 6 | 423 | 29 | 81 | 613 | 613 | | 1373 | | | | 1407 | 2 |
| 18.82 OX - Oxygen | | 4 | | | | | <1 | 5 | | 5 | | | | | 177 | |
| 18.83 Plant Heating | | 70 | | | | | 11 | 81 | | 81 | | | | | 3155 | |
| 18.84 Process Sampling & Analysis | | 54 | 42 | 13 | 644 | 124 | 135 | 1013 | 1013 | | 2090 | | | | 2399 | 4 |
| 18.85 Radwaste Bldg Non-System Specific Clean | | 153 | | | | | 23 | 176 | | 176 | | | | | 6704 | |
| 18.86 Radwaste Bldg Non-System Specific Cont | | 93 | 45 | 14 | 310 | 234 | 112 | 808 | 808 | | 1007 | | | | 4237 | 5 |
| 18.87 Radwaste Bldg Non-System Specific Decon | 11 | 46 | | | | | 12 | 69 | 16 | 53 | | | | | 2449 | |
| 18.88 Radwaste Building HVAC | | 100 | 28 | 7 | 293 | 88 | 86 | 601 | 601 | | 951 | | | | 3414 | 5 |
| 18.89 Reactor Bldg Non-System Specific Clean | | 136 | | | | | 20 | 157 | | 157 | | | | | 5982 | |
| 18.90 Reactor Bldg Non-System Specific Cont | | 75 | 29 | 9 | 187 | 141 | 72 | 513 | 513 | | 607 | | | | 3392 | 4 |
| 18.91 Reactor Bldg Non-System Specific Decon | 10 | 46 | | | | | 12 | 68 | 15 | 53 | | | | | 2438 | |
| 18.92 Reactor Coolant System | | 105 | 64 | 16 | 736 | 202 | 176 | 1299 | 1299 | | 2390 | | | | 4772 | 68 |
| 18.93 Reactor Makeup Water | | 139 | 31 | 9 | 222 | 138 | 93 | 631 | 631 | | 720 | | | | 5868 | 7 |
| 18.94 Residual Heat Removal | | 203 | 76 | 18 | 801 | 284 | 224 | 1604 | 1604 | | 2599 | | | | 8987 | 75 |
| 18.95 Roof Drains | | 55 | | | | | 8 | 63 | | 63 | | | | | 2529 | |
| 18.96 ST - Sewage Treatment | | 23 | | | | | 3 | 26 | | 26 | | | | | 1000 | |
| 18.97 SW - Screen Wash | | 15 | | | | | 2 | 17 | | 17 | | | | | 640 | |
| 18.98 SZ - Service Air | | 47 | | | | | 7 | 54 | | 54 | | | | | 2101 | |

C-21

Document W11-25-002

TABLE C-2 (continued)
SAFSTOR COST ESTIMATE FOR WOLF CREEK GENERATING STATION

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Cntgcy | Total | LicTerm | Clean | A CF | B CF | C CF | >C CF | M-Hrs | M-Rom |
|---|-------|--------|------|------|-------|-------|--------|-------|---------|-------|-------|------|------|-------|--------|-------|
| Disposal of Plant Systems (continued) | | | | | | | | | | | | | | | | |
| 18.99 Secondary Liquid Waste | 297 | 453 | 190 | 36 | 940 | 513 | 504 | 2932 | 2932 | | 3050 | | | | 30121 | 177 |
| 18.100Solid Radwaste | | 237 | 205 | 27 | 911 | 289 | 264 | 1933 | 1933 | | 2955 | | | | 10526 | 53 |
| 18.101Standby Diesel Engine | | 101 | | | | | 15 | 117 | | 117 | | | | | 4394 | |
| 18.102Stator Cooling Water | | 6 | | | | | <1 | 7 | | 7 | | | | | 249 | |
| 18.103Steam Generator Blowdown | | 313 | 103 | 29 | 1006 | 429 | 308 | 2189 | 2189 | | 3264 | | | | 13504 | 107 |
| 18.104Steam Seal | | 12 | | | | | 2 | 14 | | 14 | | | | | 539 | |
| 18.105VA - I&C Shop HVAC | | 3 | | | | | <1 | 4 | | 4 | | | | | 141 | |
| 18.106VB - I&C Shop Computer Room HVAC | | 2 | | | | | <1 | 3 | | 3 | | | | | 95 | |
| 18.107VC - Health Physics Computer Room HVAC | | 5 | | | | | <1 | 5 | | 5 | | | | | 200 | |
| 18.108VH - Circ Water & Makeup Water Scrns Vt | | 6 | | | | | <1 | 6 | | 6 | | | | | 245 | |
| 18.109VJ - Shop Bldg Machine Shop Area Vent | | 1 | | | | | <1 | 1 | | 1 | | | | | 51 | |
| 18.110VL - Shop Building HVAC | | 2 | | | | | <1 | 2 | | 2 | | | | | 92 | |
| 18.111VS - Admin. Bldg HVAC | | 5 | | | | | <1 | 6 | | 6 | | | | | 238 | |
| 18.112VT - Tech Support Building HVAC | | 2 | | | | | <1 | 2 | | 2 | | | | | 79 | |
| 18.113VV - Misc. Bldg. HVAC | | 3 | | | | | <1 | 3 | | 3 | | | | | 123 | |
| 18.114VW - Waste Water Treatment Ventilation | | 1 | | | | | <1 | 1 | | 1 | | | | | 48 | |
| 18.115WD - Domestic Water | | 25 | | | | | 4 | 28 | | 28 | | | | | 1089 | |
| 18.116WG - Gland Water & Motor Cooling Water | | 17 | | | | | 3 | 20 | | 20 | | | | | 781 | |
| 18.117WL - Cooling Lake Makeup & Blowdown | | 17 | | | | | 3 | 19 | | 19 | | | | | 754 | |
| 18.118WM - Makeup Demineralizer | | 92 | | | | | 14 | 105 | | 105 | | | | | 4108 | |
| 18.119WS - Plant Services Water | | 82 | | | | | 12 | 94 | | 94 | | | | | 3791 | |
| 18.120WT - Waste Water Treatment | | 17 | | | | | 3 | 19 | | 19 | | | | | 767 | |
| 18.121WZ - Radioactive Liquid Waste | | 5 | | | | | <1 | 6 | | 6 | | | | | 237 | |
| 18. Totals | 1129 | 11226 | 2277 | 542 | 18389 | 8031 | 7127 | 48721 | 42785 | 5936 | 59679 | | | | 524723 | 1455 |
| 19. Erect scaffolding for systems removal | | 918 | | | | | 138 | 1056 | 1056 | | | | | | 29008 | |
| Decontamination of Site Buildings | | | | | | | | | | | | | | | | |
| 20.1 -Reactor | 735 | 314 | 135 | 39 | 3614 | 304 | 1053 | 6194 | 6194 | | 11728 | | | | 33325 | 124 |
| 20.2 Auxiliary | 383 | 24 | 55 | 16 | 1706 | 83 | 474 | 2742 | 2742 | | 5536 | | | | 13102 | 49 |
| 20.3 Communication Corridor - Contaminated | 8 | <1 | 1 | <1 | 36 | <1 | 10 | 57 | 57 | | 118 | | | | 288 | <1 |
| 20.4 Fuel Building | 349 | 264 | 41 | 13 | 664 | 174 | 372 | 1878 | 1878 | | 2156 | | | | 23412 | 52 |
| 20.5 Hot Machine Shop | 15 | | 1 | <1 | 44 | | 14 | 74 | 74 | | 142 | | | | 500 | 1 |
| 20.6 Radwaste | 204 | 11 | 28 | 8 | 900 | 38 | 250 | 1440 | 1440 | | 2921 | | | | 6973 | 52 |
| 20.7 Radwaste Drum Storage | 23 | <1 | 3 | <1 | 100 | 3 | 28 | 159 | 159 | | 324 | | | | 784 | 2 |
| 20. Totals | 1719 | 615 | 284 | 77 | 7064 | 604 | 2201 | 12544 | 12544 | | 22926 | | | | 78385 | 280 |

C-22

Document W11-25-002

TABLE C-2 (continued)
SAFSTOR COST ESTIMATE FOR WOLF CREEK GENERATING STATION

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Contgcy | Total | LicTerm | Clean | A CF | B CF | C CF | >C CF | M-Hrs | M-Rm |
|---------------------------------------|-------|--------|------|------|-------|-------|---------|--------|---------|-------|--------|------|------|-------|--------|------|
| 21. License termination survey | | | | | | 299 | 45 | 344 | 344 | | | | | | | |
| 22. Terminate license | | | | | | | | a | | | | | | | | |
| Subtotal Period 4 Activity Costs | 3477 | 19192 | 3393 | 4700 | 60692 | 20362 | 21076 | 132892 | 125689 | 7202 | 176021 | 2489 | 476 | 221 | 782717 | 1867 |
| Period 4 Undistributed Costs | | | | | | | | | | | | | | | | |
| 1. Decon equipment | | | | | | 189 | 28 | 217 | 217 | | | | | | | |
| 2. Decon supplies | | | | | | 327 | 82 | 408 | 408 | | | | | | | |
| 3. DOC staff relocation expenses | | | | | | 845 | 127 | 972 | 972 | | | | | | | |
| 4. Process liquid waste | 318 | | 300 | 346 | 2061 | | 550 | 3576 | 3576 | | | 4416 | | | 551 | 13 |
| 5. Insurance | | | | | | 696 | 70 | 766 | 766 | | | | | | | |
| 6. Property taxes | | | | | | 978 | 98 | 1075 | 968 | 108 | | | | | | |
| 7. Health physics supplies | | | | | | 2261 | 565 | 2826 | 2826 | | | | | | | |
| 8. Heavy equipment rental | | | | | | 3648 | 577 | 4425 | 3983 | 443 | | | | | | |
| 9. Small tool allowance | | | | | | 324 | 49 | 373 | 335 | 37 | | | | | | |
| 10. Pipe cutting equipment | | | | | | 587 | 88 | 675 | 675 | | | | | | | |
| 11. Disposal of DAW generated | | | 468 | 18 | 2253 | | 387 | 3126 | 3126 | | 7350 | | | | 16056 | 40 |
| 12. Plant energy budget | | | | | | 2350 | 353 | 2703 | 2433 | 270 | | | | | | |
| 13. NRC Fees | | | | | | 210 | 21 | 231 | 231 | | | | | | | |
| Subtotal Undistributed Costs Period 4 | 318 | | 768 | 364 | 4314 | 12616 | 2995 | 21375 | 20517 | 858 | 7350 | 4416 | | | 16608 | 53 |
| Staff Costs | | | | | | | | | | | | | | | | |
| DOC Staff Cost | | | | | | 11486 | 1723 | 13208 | 13208 | | | | | | | |
| Utility Staff Cost | | | | | | 30388 | 4558 | 34946 | 34946 | | | | | | | |
| TOTAL PERIOD 4 | 3795 | 19192 | 4162 | 5064 | 65006 | 74851 | 30351 | 202421 | 194360 | 8060 | 183371 | 6905 | 476 | 221 | 799325 | 1920 |
| PERIOD 5 | | | | | | | | | | | | | | | | |
| Removal of Major Equipment | | | | | | | | | | | | | | | | |
| 23. Main Turbine/generator | | 70 | | | | | 10 | 80 | | 80 | | | | | 3082 | |
| 24. Main Condensers | | 219 | | | | | 33 | 252 | | 252 | | | | | 9282 | |

C-23

Document W11-25-002

TABLE C-2 (continued)
SAFSTOR COST ESTIMATE FOR WOLF CREEK GENERATING STATION

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Contcy | Total | LIC Term | Clean | A CF | B CF | C CF | >C CF | M-Hrs | M-Rom |
|---|-------|--------|------|------|------|-------|--------|-------|----------|-------|-------|------|------|-------|-------|--------|
| Demolition of Remaining Site Buildings | | | | | | | | | | | | | | | | |
| 25.1 Reactor | | 4823 | | | | | 723 | 5546 | | 5546 | | | | | | 118164 |
| 25.2 Access Vaults | | 37 | | | | | 6 | 43 | | 43 | | | | | | 436 |
| 25.3 Administration | | 209 | | | | | 31 | 241 | | 241 | | | | | | 4753 |
| 25.4 Auxiliary | | 7834 | | | | | 1175 | 9009 | | 9009 | | | | | | 162497 |
| 25.5 Auxiliary Boiler | | 23 | | | | | 3 | 26 | | 26 | | | | | | 672 |
| 25.6 Chlorine Storage | | 17 | | | | | 3 | 19 | | 19 | | | | | | 376 |
| 25.7 Circ. Water Discharge Structure | | 351 | | | | | 53 | 403 | | 403 | | | | | | 4140 |
| 25.8 Circulating Water Intake & Screenhouse | | 828 | | | | | 124 | 952 | | 952 | | | | | | 5369 |
| 25.9 Communication Corridor - Contaminated | | 346 | | | | | 52 | 398 | | 398 | | | | | | 8911 |
| 25.10 Communication Corridor-Clean | | 2292 | | | | | 344 | 2635 | | 2635 | | | | | | 53284 |
| 25.11 Covered Walkways | | 8 | | | | | 1 | 10 | | 10 | | | | | | 322 |
| 25.12 Diesel Generator | | 398 | | | | | 60 | 458 | | 458 | | | | | | 7888 |
| 25.13 E.S.W.S. Pumphouse | | 781 | | | | | 117 | 898 | | 898 | | | | | | 5070 |
| 25.14 ESWS Valve House | | 12 | | | | | 2 | 14 | | 14 | | | | | | 243 |
| 25.15 Fuel Building | | 2574 | | | | | 386 | 2960 | | 2960 | | | | | | 63283 |
| 25.16 Hot Machine Shop | | 22 | | | | | 3 | 25 | | 25 | | | | | | 639 |
| 25.17 M.M.O. Building | | 172 | | | | | 26 | 198 | | 198 | | | | | | 3483 |
| 25.18 Misc. Site Foundations | | 374 | | | | | 56 | 431 | | 431 | | | | | | 7394 |
| 25.19 Misc. Site Structures | | 999 | | | | | 150 | 1149 | | 1149 | | | | | | 20240 |
| 25.20 Oil Separator and Waste Tank | | 2 | | | | | <1 | 3 | | 3 | | | | | | 48 |
| 25.21 Radwaste | | 2714 | | | | | 407 | 3121 | | 3121 | | | | | | 58493 |
| 25.22 Radwaste Drum Storage | | 422 | | | | | 63 | 485 | | 485 | | | | | | 12006 |
| 25.23 Security/Guardhouse | | 317 | | | | | 47 | 364 | | 364 | | | | | | 4682 |
| 25.24 Site Diesel Generator | | 3 | | | | | <1 | 3 | | 3 | | | | | | 60 |
| 25.25 Turbine Building | | 5712 | | | | | 857 | 6569 | | 6569 | | | | | | 166045 |
| 25.26 Waste Water Treatment | | 17 | | | | | 3 | 20 | | 20 | | | | | | 432 |
| 25. Totals | | 31285 | | | | | 4693 | 35978 | | 35978 | | | | | | 708928 |
| Site Closeout Activities | | | | | | | | | | | | | | | | |
| 26. Remove Rubble | | 3804 | | | | | 571 | 4374 | | 4374 | | | | | | 12323 |
| 27. Grade & Landscape Site | | 1393 | | | | | 209 | 1602 | | 1602 | | | | | | 8028 |
| 28. Final report to NRC | | | | | | 156 | 23 | 179 | | 179 | | | | | | |
| Subtotal Period 5 Activity Costs | | 36771 | | | | 156 | 5539 | 42466 | | 179 | 42287 | | | | | 741643 |

C-24

Document W11-25-002

TABLE C-2 (continued)
SAPSTOR COST ESTIMATE FOR WOLF CREEK GENERATING STATION

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Contgcy | Total | LicTerm | Clean A CF | B CF | C CF | >C CF | M-Hrs | M-Rm |
|--|-------------|--------------|--------------|-------------|--------------|---------------|--------------|----------------------|---------------|-------------------|---------------|-------------|------------|---------------|---------------------|
| Period 5 Undistributed Costs | | | | | | | | | | | | | | | |
| 1. Insurance | | | | | | 172 | 17 | 190 | 190 | | | | | | |
| 2. Property taxes | | | | | | 516 | 52 | 567 | | 567 | | | | | |
| 3. Heavy equipment rental | | | | | | 2192 | 329 | 2521 | | 2521 | | | | | |
| 4. Small tool allowance | | | | | | 286 | 43 | 329 | | 329 | | | | | |
| 5. Plant energy budget | | | | | | 120 | 18 | 138 | | 138 | | | | | |
| Subtotal Undistributed Costs Period 5 | | | | | | 3287 | 459 | 3745 | 190 | 3556 | | | | | |
| Staff Costs | | | | | | | | | | | | | | | |
| DOC Staff Cost | | | | | | 6170 | 925 | 7095 | | 7095 | | | | | |
| Utility Staff Cost | | | | | | 7512 | 1127 | 8639 | 7775 | 864 | | | | | |
| TOTAL PERIOD 5 | | | 36771 | | | 17125 | 8050 | 61946 | 8144 | 53802 | | | | 741643 | |
| TOTAL COST TO DECOMMISSION | 5568 | 56218 | 4743 | 5268 | 69465 | 381568 | 82904 | 605734 | 543872 | 61862 | 195371 | 8649 | 476 | 221 | 1610054 1973 |
| TOTAL COST TO DECOMMISSION WITH 15.86% CONTINGENCY: | | | | | | | | \$605,733.632 | | | | | | | |
| TOTAL NRC LICENSE TERMINATION COST IS 89.79% OR | | | | | | | | \$543,871.872 | | | | | | | |
| NON-NUCLEAR DEMOLITION COST IS 10.21% OR: | | | | | | | | \$ 61,861.820 | | | | | | | |
| TOTAL RADWASTE VOLUME BURIED: | | | | | | | | 204,717 | | CUBIC foot | | | | | |
| TOTAL SCRAP METAL REMOVED: | | | | | | | | 41,775.9 | | tons | | | | | |
| TOTAL CRAFT LABOR REQUIREMENTS: | | | | | | | | 1,610,054.4 | | man-hours | | | | | |
| TOTAL PERSONNEL RADIATION EXPOSURE: | | | | | | | | 1,973.5 | | man-rem | | | | | |
| TOTAL CRAFT LABOR COST WITH 22.93% CONTINGENCY: | | | | | | | | \$ 43,984.232 | | | | | | | |

C-25

Document W11-25-002

TABLE C-3
ENTOMB COST ESTIMATE FOR WOLF CREEK GENERATING STATION
(THOUSANDS OF 1993 DOLLARS)

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Contgy | Total | Lic/Perm | Clean A CF | B CF | C CF | >C CF | M-Hrs | M-Rom |
|---|-------|--------|------|------|------|-------|--------|-------|----------|------------|------|------|-------|-------|-------|
| PERIOD 1 | | | | | | | | | | | | | | | |
| 1. Prepare preliminary decommissioning plan | | | | | | 130 | 20 | 150 | 150 | | | | | | |
| 2. Revise decommissioning plan | | | | | | | | a | | | | | | | |
| 3. Review plant dwgs & specs. | | | | | | 460 | 69 | 529 | 529 | | | | | | |
| 4. Perform detailed rad survey | | | | | | | | a | | | | | | | |
| 5. End product description | | | | | | 100 | 15 | 115 | 115 | | | | | | |
| 6. Detailed by-product inventory | | | | | | 130 | 20 | 150 | 150 | | | | | | |
| 7. Define major work sequence | | | | | | 750 | 113 | 863 | 863 | | | | | | |
| 8. Perform safety analysis of operation | | | | | | 200 | 30 | 230 | 230 | | | | | | |
| 9. Perform safety analysis | | | | | | 310 | 47 | 357 | 357 | | | | | | |
| 10. Submit dismantling plan | | | | | | 52 | 8 | 60 | 60 | | | | | | |
| 11. Submit dismantling plan | | | | | | | | a | | | | | | | |
| Subtotal Period 1 Activity Costs | | | | | | 2132 | 320 | 2452 | 2452 | | | | | | |
| Period 1 Undistributed Costs | | | | | | | | | | | | | | | |
| 1. Decon equipment | | | | | | 189 | 28 | 217 | 217 | | | | | | |
| 2. Decon supplies | | | | | | 137 | 34 | 171 | 171 | | | | | | |
| 3. DOC staff relocation expenses | | | | | | 845 | 127 | 972 | 972 | | | | | | |
| 4. Process liquid waste | 102 | | 52 | 70 | 303 | | 112 | 639 | 639 | | 695 | | | 180 | 4 |
| 5. Insurance | | | | | | 980 | 98 | 1078 | 1078 | | | | | | |
| 6. Property taxes | | | | | | 1861 | 186 | 2047 | 2047 | | | | | | |
| 7. Health physics supplies | | | | | | 947 | 237 | 1184 | 1184 | | | | | | |
| 8. Disposal of DAW generated | | | 198 | 6 | 762 | | 135 | 1101 | 1101 | 2473 | | | | 6725 | 17 |
| 9. Plant energy budget | | | | | | 5606 | 841 | 6447 | 6447 | | | | | | |
| 10. NRC Fees | | | | | | 194 | 19 | 214 | 214 | | | | | | |
| 11. Emergency planning fees | | | | | | 442 | 44 | 486 | 486 | | | | | | |
| Subtotal Undistributed Costs Period 1 | 102 | | 250 | 76 | 1065 | 11200 | 1862 | 14555 | 14555 | 2473 | 695 | | | 6905 | 21 |

NOTES- "n/a" indicates that fuel handling, packaging, shipping, and disposal are charged to plant operations, not decommissioning
 - "a" indicates that costs are included in the utility staff costs.
 - Columns may not total due to rounding errors.

C-26

Document W11-25-002

TABLE C-3 (continued)
ENTOMB COST ESTIMATE FOR WOLF CREEK GENERATING STATION

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Chgcy | Total | LicT97M | Clean | A CF | B CF | C CF | >C CF | M-Hrs | M-Rm |
|---|------------|--------|------------|-----------|-------------|--------------|--------------|--------------|--------------|-------------|------------|------|------|-------|-------------|-----------|
| Staff Costs | | | | | | | | | | | | | | | | |
| DOC Staff Cost | | | | | | 4607 | 691 | 5298 | 5298 | | | | | | | |
| Utility Staff Cost | | | | | | 50050 | 7508 | 57558 | 57558 | | | | | | | |
| TOTAL PERIOD 1 COST | 102 | | 250 | 76 | 1065 | 67989 | 10380 | 79862 | 79862 | 2473 | 695 | | | | 6905 | 21 |
| PERIOD 2 | | | | | | | | | | | | | | | | |
| Activity Specifications | | | | | | | | | | | | | | | | |
| 12.1 Prepare plant and facilities for entombm | | | | | | 492 | 74 | 566 | 566 | | | | | | | |
| 12.2 Plant systems | | | | | | 417 | 63 | 479 | 479 | | | | | | | |
| 12.3 Reinforced concrete | | | | | | 160 | 24 | 184 | 184 | | | | | | | |
| 12.4 Plant structures and buildings | | | | | | 312 | 47 | 359 | 359 | | | | | | | |
| 12.5 Waste management | | | | | | 460 | 69 | 529 | 529 | | | | | | | |
| 12.6 Facility and site dormancy | | | | | | 90 | 14 | 104 | 104 | | | | | | | |
| 12. Total | | | | | | 1931 | 290 | 2220 | 2220 | | | | | | | |
| Detailed Work Procedures | | | | | | | | | | | | | | | | |
| 13.1 Plant systems | | | | | | 473 | 71 | 544 | 544 | | | | | | | |
| 13.2 Entombment structures | | | | | | 90 | 14 | 104 | 104 | | | | | | | |
| 13.3 Facility closeout & dormancy | | | | | | 120 | 18 | 138 | 138 | | | | | | | |
| 13.4 Auxiliary Building | | | | | | 273 | 41 | 314 | 314 | | | | | | | |
| 13. Total | | | | | | 956 | 143 | 1100 | 1100 | | | | | | | |
| 14. Prepare dismantling sequence | | | | | | 50 | 8 | 58 | 58 | | | | | | | |
| 15. Procure vacuum drying system | | | | | | 10 | 2 | 12 | 12 | | | | | | | |
| 16. Drain/de-energize non-cont. systems | | | | | | | | | | | | | | | | |
| 17. Drain & dry NSSS | | | | | | | | | | | | | | | | |
| 18. Drain/de-energize contaminated systems | | | | | | | | | | | | | | | | |
| RACK Removal | | | | | | | | | | | | | | | | |
| 19. Remove spent fuel racks | 212 | 35 | 80 | 22 | 945 | 731 | 378 | 2402 | 2402 | 3150 | | | | | 8531 | 46 |

C-27

Document W11-25-002

TABLE C-3 (continued)
ENTOMB COST ESTIMATE FOR WOLF CREEK GENERATING STATION

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Cntgcy | Total | LicTerm | Clean | A CF | B CF | C CF | >C CF | M-Hrs | M-Rom |
|--|-------|--------|------|------|-------|-------|--------|-------|---------|-------|-------|------|------|-------|--------|-------|
| Disposal of Plant Systems | | | | | | | | | | | | | | | | |
| External to Entombment Barrier | | | | | | | | | | | | | | | | |
| 20.1 Accumulator Safety Injection | | 88 | 27 | 6 | 190 | 121 | 72 | 504 | 504 | | 617 | | | | 3844 | 31 |
| 20.2 Auxiliary Bldg Non-System Specific Cont | | 247 | 103 | 34 | 767 | 577 | 279 | 2007 | 2007 | | 2488 | | | | 11246 | 14 |
| 20.3 Auxiliary Building HVAC | | 280 | 46 | 12 | 290 | 213 | 152 | 992 | 992 | | 940 | | | | 9618 | 13 |
| 20.4 Borated Refueling Water Storage | | 163 | 56 | 9 | 355 | 266 | 141 | 990 | 990 | | 1152 | | | | 7142 | 23 |
| 20.5 Boron Recycle | | 273 | 71 | 18 | 438 | 275 | 185 | 1260 | 1260 | | 1422 | | | | 11754 | 126 |
| 20.6 Chemical & Detergent Waste | 31 | 75 | 19 | 5 | 124 | 85 | 68 | 406 | 406 | | 401 | | | | 4502 | 25 |
| 20.7 Chemical & Volume Control | 354 | 507 | 173 | 47 | 2147 | 560 | 734 | 4523 | 4523 | | 6968 | | | | 32065 | 177 |
| 20.8 Containment Atmospheric Control | | 6 | 23 | 4 | 377 | 19 | 64 | 492 | 492 | | 1222 | | | | 343 | <1 |
| 20.9 Containment Cooling | | 330 | 104 | 22 | 1119 | 313 | 311 | 2198 | 2198 | | 3631 | | | | 12706 | 16 |
| 20.10 Containment Hydrogen Control | | 28 | 19 | 5 | 148 | 85 | 45 | 330 | 330 | | 481 | | | | 1285 | <1 |
| 20.11 Containment Purge HVAC | | 72 | 32 | 5 | 322 | 110 | 87 | 629 | 629 | | 1046 | | | | 2724 | 3 |
| 20.12 Control Bldg Non-System Specific Cont | | 226 | 106 | 34 | 759 | 571 | 272 | 1968 | 1968 | | 2462 | | | | 10332 | 12 |
| 20.13 Decontamination | | 43 | 47 | 6 | 134 | 88 | 49 | 366 | 366 | | 435 | | | | 1945 | 5 |
| 20.14 Floor & Equipment Drains | | 1093 | 209 | 55 | 1342 | 971 | 649 | 4320 | 4320 | | 4357 | | | | 46675 | 126 |
| 20.15 Fuel Bldg Non-System Specific Cont | | 36 | 15 | 5 | 118 | 89 | 42 | 306 | 306 | | 383 | | | | 1638 | 2 |
| 20.16 Fuel Building HVAC | | 154 | 45 | 10 | 518 | 123 | 141 | 991 | 991 | | 1682 | | | | 5374 | 7 |
| 20.17 Fuel Handling & Storage Reactor Vessel | | 6 | 8 | 5 | 266 | | 43 | 329 | 329 | | 864 | | | | 292 | <1 |
| 20.18 Fuel Pool Cooling & Cleanup | | 248 | 71 | 18 | 649 | 301 | 214 | 1501 | 1501 | | 2106 | | | | 10872 | 29 |
| 20.19 Gaseous Radwaste | | 162 | 71 | 15 | 512 | 159 | 150 | 1069 | 1069 | | 1662 | | | | 7023 | 17 |
| 20.20 High Pressure Coolant Injection | | 173 | 57 | 17 | 518 | 240 | 165 | 1170 | 1170 | | 1682 | | | | 7576 | 37 |
| 20.21 Liquid Radwaste | 384 | 442 | 130 | 27 | 823 | 394 | 502 | 2702 | 2702 | | 2670 | | | | 32913 | 384 |
| 20.22 Nuclear Sampling | | 33 | 46 | 6 | 423 | 29 | 81 | 618 | 618 | | 1373 | | | | 1564 | 3 |
| 20.23 Process Sampling & Analysis | | 60 | 42 | 13 | 644 | 124 | 136 | 1020 | 1020 | | 2090 | | | | 2650 | 4 |
| 20.24 Radwaste Bldg Non-System Specific Cont | | 106 | 46 | 14 | 310 | 234 | 115 | 825 | 825 | | 1007 | | | | 4848 | 6 |
| 20.25 Radwaste Building HVAC | | 108 | 28 | 7 | 293 | 88 | 88 | 611 | 611 | | 951 | | | | 3781 | 5 |
| 20.26 Reactor Bldg Non-System Specific Cont | | 86 | 30 | 9 | 187 | 141 | 75 | 527 | 527 | | 607 | | | | 3884 | 5 |
| 20.27 Reactor Makeup Water | | 152 | 31 | 9 | 222 | 138 | 96 | 647 | 647 | | 720 | | | | 6469 | 7 |
| 20.28 Residual Heat Removal | | 221 | 77 | 18 | 801 | 284 | 228 | 1628 | 1628 | | 2599 | | | | 9890 | 82 |
| 20.29 Secondary Liquid Waste | 328 | 493 | 191 | 36 | 940 | 513 | 530 | 3030 | 3030 | | 3050 | | | | 33315 | 195 |
| 20.30 Solid Radwaste | | 258 | 207 | 27 | 911 | 289 | 269 | 1961 | 1961 | | 2955 | | | | 11609 | 58 |
| 20.31 Steam Generator Blowdown | | 341 | 104 | 29 | 1006 | 429 | 315 | 2225 | 2225 | | 3264 | | | | 14867 | 117 |
| 20. Totals | 1096 | 6509 | 2233 | 526 | 17652 | 7829 | 6300 | 42145 | 42145 | | 57289 | | | | 314747 | 1530 |
| 21. Erect scaffolding for systems removal | | 856 | | | | | 128 | 985 | 985 | | | | | | 27060 | |

C28

Document W11-25-002

TABLE C-3 (continued)
ENTOMB COST ESTIMATE FOR WOLF CREEK GENERATING STATION

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Cntgcy | Total | LicTerm | Clean | A CF | B CF | C CF | >C CF | M-Hrs | M-Rom |
|--|-------------|-------------|-------------|------------|--------------|--------------|-------------|--------------|--------------|-------|--------------|-------------|------|---------------|-------------|-------|
| Decontamination of Site Buildings | | | | | | | | | | | | | | | | |
| External to Entombment Barrier | | | | | | | | | | | | | | | | |
| 22.1 Auxiliary | 409 | 27 | 56 | 16 | 1706 | 83 | 487 | 2784 | 2784 | | 5536 | | | 14327 | 54 | |
| 22.2 Communication Corridor - Contaminated | 9 | <1 | 1 | <1 | 36 | <1 | 10 | 58 | 58 | | 118 | | | 315 | <1 | |
| 22.3 Fuel Building | 378 | 289 | 41 | 13 | 664 | 174 | 393 | 1953 | 1953 | | 2156 | | | 25593 | 56 | |
| 22.4 Hot Machine Shop | 16 | | 1 | <1 | 44 | | 15 | 76 | 76 | | 142 | | | 546 | 1 | |
| 22.5 Radwaste | 218 | 12 | 29 | 8 | 900 | 38 | 257 | 1462 | 1462 | | 2921 | | | 7625 | 57 | |
| 22.6 Radwaste Drum Storage | 24 | 1 | 3 | <1 | 100 | 3 | 28 | 161 | 161 | | 324 | | | 857 | 2 | |
| 22. Totals | 1054 | 330 | 131 | 38 | 3450 | 299 | 1191 | 6494 | 6494 | | 11197 | | | 49263 | 171 | |
| 23. Prepare support equipment for storage | | 118 | | | | | 18 | 135 | 135 | | | | | 1500 | 2 | |
| 24. Isolate sys & comp. at entombment bndry | | 53 | | | | | 8 | 62 | 62 | | | | | 2000 | 5 | |
| 25. Construct entombment barriers | | 396 | | | | | 59 | 456 | 456 | | | | | 7549 | | |
| 26. Install containment pressure equal. line | | 19 | | | | | 3 | 22 | 22 | | | | | 700 | 2 | |
| 27. Interim survey prior to dormancy | | | | | | 299 | 45 | 344 | 344 | | | | | | | |
| 28. Secure building accesses | | | | | | | | a | | | | | | | | |
| 29. Prepare and submit interim report | | | | | | 120 | 18 | 138 | 138 | | | | | | | |
| Subtotal Period 2 Activity Costs | 2362 | 8316 | 2444 | 586 | 22048 | 12226 | 8589 | 56571 | 56571 | | 71637 | | | 411349 | 1756 | |
| Period 2 Undistributed Costs | | | | | | | | | | | | | | | | |
| 1. Decon equipment | | | | | | 189 | 28 | 217 | 217 | | | | | | | |
| 2. Decon supplies | | | | | | 274 | 68 | 342 | 342 | | | | | | | |
| 3. DOC staff relocation expenses | | | | | | 845 | 127 | 972 | 972 | | | | | | | |
| 4. Process liquid waste | 230 | | 257 | 286 | 1799 | | 454 | 3026 | 3026 | | 3818 | | | 477 | 11 | |
| 5. Insurance | | | | | | 444 | 44 | 488 | 488 | | | | | | | |
| 6. Property taxes | | | | | | 842 | 64 | 927 | 927 | | | | | | | |
| 7. Health physics supplies | | | | | | 1894 | 474 | 2368 | 2368 | | | | | | | |
| 8. Heavy equipment rental | | | | | | 1072 | 161 | 1233 | 1233 | | | | | | | |
| 9. Small tool allowance | | | | | | 158 | 24 | 182 | 182 | | | | | | | |
| 10. Pipe cutting equipment | | | | | | 587 | 88 | 675 | 675 | | | | | | | |
| 11. Disposal of DAW generated | | | 396 | 12 | 1524 | | 270 | 2202 | 2202 | | 4945 | | | 13450 | 34 | |
| 12. Plant energy budget | | | | | | 2416 | 362 | 2778 | 2778 | | | | | | | |
| 13. NRC Fees | | | | | | 44 | 4 | 48 | 48 | | | | | | | |
| 14. Emergency Planning Fees | | | | | | 58 | 6 | 64 | 64 | | | | | | | |
| Subtotal Undistributed Costs Period 2 | 230 | | 653 | 299 | 3323 | 8823 | 2195 | 15522 | 15522 | | 4945 | 3818 | | 13928 | 45 | |

C-29

Document W11-25-002

TABLE C-3 (continued)
ENTOMB COST ESTIMATE FOR WOLF CREEK GENERATING STATION

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Contgcy | Total | LicTerm | Clean A | CF | B CF | C CF | -C CF | M-Hrs | M-Rom |
|--|-------|--------|------|------|-------|-------|---------|---------------|---------|------------|-------|------|------|-------|--------|-------|
| <hr/> | | | | | | | | | | | | | | | | |
| Staff Costs | | | | | | | | | | | | | | | | |
| DOC Staff Cost | | | | | | 9000 | 1350 | 10350 | 10350 | | | | | | | |
| Utility Staff Cost | | | | | | 28092 | 4214 | 32306 | 32306 | | | | | | | |
| TOTAL PERIOD 2 COST | 2593 | 8316 | 3097 | 885 | 25371 | 58142 | 16348 | 114750 | 114750 | | 76582 | 3818 | | | 425277 | 1800 |
| TOTAL COST TO ENTOMB | 2593 | 8316 | 3097 | 885 | 25371 | 58142 | 16348 | 114750 | 114750 | | 76582 | 3818 | | | 425277 | 1800 |
| TOTAL COST TO ENTOMB WITH 15.92% CONTINGENCY | | | | | | | | \$194,612,496 | | | | | | | | |
| TOTAL ENTOMBMENT RADWASTE VOLUME BURIED | | | | | | | | 83.566 | | CUBIC FEET | | | | | | |
| TOTAL SCRAP REMOVED | | | | | | | | 0.0 | | TONS | | | | | | |
| TOTAL CRAFT LABOR REQUIREMENTS | | | | | | | | 432,182.3 | | MAN-HOURS | | | | | | |
| TOTAL PERSONNEL RADIATION EXPOSURE | | | | | | | | 1,821.3 | | MAN-REM | | | | | | |
| TOTAL CRAFT LABOR COST WITH 15.92% CONTINGENCY | | | | | | | | \$8,987,725 | | | | | | | | |

C-30

Document W11-25-002

TABLE C-3 (continued)
ENTOMB COST ESTIMATE FOR WOLF CREEK GENERATING STATION

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Chgcy | Total | LicTerm | Clean | A CF | B CF | C CF | -C CF | M-Hrs | M-Rob |
|--|-------|--------|------|------|-------------|------------|-------------|-------------------|---------|-------|------|------|------|-------|-------|-------|
| ENTOMBMENT DORMANCY | | | | | | | | | | | | | | | | |
| PERIOD 3: Entombed Annual Maintenance Cost | | | | | | | | | | | | | | | | |
| 1. Quarterly inspection | | | | | | | | \$ | | | | | | | | |
| 2. Semi-annual environmental survey | | | | | | | | \$ | | | | | | | | |
| 3. Prepare reports | | | | | | | | \$ | | | | | | | | |
| 4. Health physics supplies | | | | | 7 | 2 | 9 | 9 | | | | | | | | |
| 5. Insurance | | | | | 48 | 5 | 53 | 53 | | | | | | | | |
| 6. Property taxes | | | | | 421 | 42 | 463 | 463 | | | | | | | | |
| 7. Maintenance supplies | | | | | 52 | 13 | 65 | 65 | | | | | | | | |
| 8. Plant energy budget | | | | | 84 | 13 | 97 | 97 | | | | | | | | |
| 9. NRC Fees | | | | | 9 | 41 | 10 | 10 | | | | | | | | |
| 10. Site maintenance staff | | | | | 1666 | 250 | 1915 | 1915 | | | | | | | | |
| PERIOD 3 ANNUAL MAINTENANCE TOTALS | | | | | 2287 | 325 | 2612 | 2612 | | | | | | | | |
| MAINTENANCE COST FOR 49.59917 YEARS DORMANCY: | | | | | | | | 29,568,064 | | | | | | | | |
| ENTOMBMENT DISMANTLING | | | | | | | | | | | | | | | | |
| PERIOD 4 | | | | | | | | | | | | | | | | |
| 1. Review plant dwgs & specs. | | | | | 130 | 20 | 150 | 150 | | | | | | | | |
| 2. Perform detailed rad survey | | | | | | | N/A | | | | | | | | | |
| 3. Submit for possession-only license | | | | | 100 | 15 | 115 | 115 | | | | | | | | |
| 4. End product description | | | | | 32 | 5 | 37 | 37 | | | | | | | | |
| 5. Detailed by-product inventory | | | | | 150 | 23 | 173 | 173 | | | | | | | | |
| 6. Define major work sequence | | | | | 100 | 15 | 115 | 115 | | | | | | | | |
| 7. Perform safety analysis of operation | | | | | 200 | 30 | 230 | 230 | | | | | | | | |
| 8. Perform safety analysis of end product | | | | | 200 | 30 | 230 | 230 | | | | | | | | |
| 9. Submit dismantling plan | | | | | 100 | 15 | 115 | 115 | | | | | | | | |
| 10. Receive dismantling order | | | | | | | a | | | | | | | | | |
| Subtotal Period 4 Activity Costs | | | | | 1012 | 152 | 1164 | 1164 | | | | | | | | |

C-31

Document W11-25-002

TABLE C-3 (continued)
ENTOMB COST ESTIMATE FOR WOLF CREEK GENERATING STATION

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Cntgcy | Total | Lictrm | Clean | A CF | B CF | C CF | >C CF | M-Hrs | M-Rm |
|---|-------|--------|------|------|------|--------------|-------------|--------------|--------------|------------|------|------|------|-------|-------|------|
| Period 4 Undistributed Costs | | | | | | | | | | | | | | | | |
| 1. DOC staff relocation expenses | | | | | | 845 | 127 | 972 | 972 | | | | | | | |
| 2. Insurance | | | | | | 333 | 33 | 366 | 366 | | | | | | | |
| 3. Property taxes | | | | | | 632 | 63 | 695 | 695 | | | | | | | |
| 4. Health physics supplies | | | | | | 947 | 237 | 1184 | 1184 | | | | | | | |
| 5. Heavy equipment rental | | | | | | 233 | 35 | 267 | 267 | | | | | | | |
| 6. Plant energy budget | | | | | | 923 | 138 | 1061 | 1061 | | | | | | | |
| 7. NRC Fees | | | | | | 66 | 7 | 73 | 73 | | | | | | | |
| Subtotal Undistributed Costs Period 4 | | | | | | 3978 | 640 | 4618 | 4618 | | | | | | | |
| Staff Costs | | | | | | | | | | | | | | | | |
| DOC Staff Cost | | | | | | 4607 | 691 | 5298 | 5298 | | | | | | | |
| Utility Staff Cost | | | | | | 13449 | 2017 | 15466 | 15466 | | | | | | | |
| TOTAL PERIOD 4 COST | | | | | | 23046 | 3500 | 26546 | 26546 | | | | | | | |
| PERIOD 5 | | | | | | | | | | | | | | | | |
| Activity Specifications | | | | | | | | | | | | | | | | |
| 11.1 Re-activate plant & temporary facilities | | | | | | 737 | 111 | 848 | 763 | 85 | | | | | | |
| 11.2 Plant systems | | | | | | 417 | 63 | 479 | 431 | 48 | | | | | | |
| 11.3 Reactor internals | | | | | | 710 | 107 | 817 | 817 | | | | | | | |
| 11.4 Reactor vessel | | | | | | 650 | 98 | 748 | 748 | | | | | | | |
| 11.5 Biological shield | | | | | | 50 | 8 | 58 | 58 | | | | | | | |
| 11.6 Steam generators | | | | | | 312 | 47 | 359 | 359 | | | | | | | |
| 11.7 Reinforced concrete | | | | | | 160 | 24 | 184 | 92 | 92 | | | | | | |
| 11.8 Turbine & condenser | | | | | | 80 | 12 | 92 | | 92 | | | | | | |
| 11.9 Plant structures & buildings | | | | | | 312 | 47 | 359 | 179 | 179 | | | | | | |
| 11.10 Waste management | | | | | | 460 | 69 | 529 | 529 | | | | | | | |
| 11.11 Facility & site closeout | | | | | | 90 | 14 | 104 | 52 | 52 | | | | | | |
| 11. Total | | | | | | 3978 | 597 | 4574 | 4026 | 548 | | | | | | |

C-32

Document W11-25-002

TABLE C-3 (continued)
ENTOMB COST ESTIMATE FOR WOLF CREEK GENERATING STATION

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Cntgcy | Total | LicTerm | Clean A | CF | B CF | C CF | >C CF | M-Hrs | M-Rm |
|--|-------|--------|------|------|-------|-------|--------|-------|---------|---------|------|------|------|--------|-------|------|
| Planning & Site Preparations | | | | | | | | | | | | | | | | |
| 12. Prepare dismantling sequence | | | | | 240 | | 36 | 276 | 276 | | | | | | | |
| 13. Plant prep. & temp. svces | | | | | 1485 | | 223 | 1708 | 1708 | | | | | | | |
| 14. Design water clean-up system | | | | | 140 | | 21 | 161 | 161 | | | | | | | |
| 15. Rigging/CCES/tooling/etc. | | | | | 1257 | | 189 | 1446 | 1446 | | | | | | | |
| 16. Procure casks/liners & containers | | | | | 123 | | 18 | 141 | 141 | | | | | | | |
| Detailed Work Procedures | | | | | | | | | | | | | | | | |
| 17.1 Plant systems | | | | | 473 | | 71 | 544 | 490 | 54 | | | | | | |
| 17.2 Vessel head | | | | | 250 | | 38 | 288 | 288 | | | | | | | |
| 17.3 Reactor internals | | | | | 250 | | 38 | 288 | 288 | | | | | | | |
| 17.4 Remaining buildings | | | | | 135 | | 20 | 155 | 39 | 116 | | | | | | |
| 17.5 CRD cooling assembly | | | | | 100 | | 15 | 115 | 115 | | | | | | | |
| 17.6 CRD housings & ICI tubes | | | | | 100 | | 15 | 115 | 115 | | | | | | | |
| 17.7 Incore instrumentation | | | | | 100 | | 15 | 115 | 115 | | | | | | | |
| 17.8 Reactor vessel | | | | | 363 | | 54 | 417 | 417 | | | | | | | |
| 17.9 Facility closeout | | | | | 120 | | 18 | 138 | 69 | 69 | | | | | | |
| 17.10 Missile shields | | | | | 45 | | 7 | 52 | 52 | | | | | | | |
| 17.11 Biological shield | | | | | 120 | | 18 | 138 | 138 | | | | | | | |
| 17.12 Steam generators | | | | | 460 | | 69 | 529 | 529 | | | | | | | |
| 17.13 Reinforced concrete | | | | | 100 | | 15 | 115 | 58 | 58 | | | | | | |
| 17.14 Turbine & condensers | | | | | 312 | | 47 | 359 | | 359 | | | | | | |
| 17.15 Reactor building | | | | | 273 | | 41 | 314 | 283 | 31 | | | | | | |
| 17. Total | | | | | 3201 | | 480 | 3681 | 2994 | 688 | | | | | | |
| Nuclear Steam Supply System Removal | | | | | | | | | | | | | | | | |
| 18.1 Reactor Coolant Piping | 61 | 118 | 62 | 18 | 2066 | | 379 | 2703 | 2703 | 6485 | | | | | 7280 | 26 |
| 18.2 Pressurizer Relief Tank | 11 | 56 | 5 | 4 | 196 | | 50 | 321 | 321 | 621 | | | | | 2731 | 2 |
| 18.3 Reactor Coolant Pumps & Motors | 23 | 35 | 33 | 40 | 3491 | | 553 | 4175 | 4175 | 11312 | | | | | 2633 | 2 |
| 18.4 Pressurizer | 22 | 27 | 4 | 10 | 1280 | | 212 | 1554 | 1554 | 4147 | | | | | 1852 | 1 |
| 18.5 Steam Generators | 125 | 2487 | 133 | 3502 | 17895 | | 3907 | 28050 | 28050 | 58484 | | | | | 98627 | 50 |
| 18.6 CRDMs/ ICIs/Service Structure Removal | 54 | 36 | 20 | 14 | 596 | | 130 | 851 | 851 | 1843 | | | | | 3308 | 2 |
| 18.7 Reactor Vessel Internals | 38 | 984 | 251 | 220 | 6201 | | 1805 | 9499 | 9499 | 1834 | 393 | 476 | 221 | 11270 | | 3 |
| 18.8 Reactor Vessel | 94 | 2656 | 265 | 252 | 2569 | | 2553 | 8389 | 8389 | 5540 | 2096 | | | 15026 | | 4 |
| 18. Totals | 429 | 6398 | 773 | 4059 | 34294 | | 9589 | 55542 | 55542 | 90266 | 2489 | 476 | 221 | 142727 | | 90 |

C-33

Document W11-25-002

TABLE C-3 (continued)
ENTOMB COST ESTIMATE FOR WOLF CREEK GENERATING STATION

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Contgcy | Total | LicTerm | Clean A | CF | B CF | C CF | >C CF | M-Hrs | M-Rm |
|--|-------|--------|------|------|------|-------|---------|-------|---------|---------|----|------|------|-------|-------|------|
| Disposal of Plant Systems | | | | | | | | | | | | | | | | |
| 19.1 AX - Acid Feed | | 19 | | | | | 3 | 22 | | 22 | | | | | 833 | |
| 19.2 Auxiliary Bldg Non-System Specific Clean | | 404 | | | | | 61 | 465 | | 465 | | | | | 17709 | |
| 19.3 Auxiliary Bldg Non-System Specific Decon | 31 | 135 | | | | | 36 | 202 | 47 | 155 | | | | | 7182 | |
| 19.4 Auxiliary Feedwater | | 20 | | | | | 3 | 23 | | 23 | | | | | 912 | |
| 19.5 Auxiliary Steam | | 65 | | | | | 10 | 75 | | 75 | | | | | 2948 | |
| 19.6 Auxiliary Steam Chemical Addition | | 3 | | | | | <1 | 3 | | 3 | | | | | 121 | |
| 19.7 Auxiliary Steam Generator | | 7 | | | | | 1 | 8 | | 8 | | | | | 321 | |
| 19.8 Auxiliary Turbines | | 31 | | | | | 5 | 36 | | 36 | | | | | 1358 | |
| 19.9 CL - Chlorination | | 14 | | | | | 2 | 16 | | 16 | | | | | 607 | |
| 19.10 CW - Circulating Water | | 190 | | | | | 29 | 219 | | 219 | | | | | 8903 | |
| 19.11 CZ - Caustic Acid | | 3 | | | | | <1 | 3 | | 3 | | | | | 134 | |
| 19.12 Central Chilled Water | | 51 | | | | | 8 | 59 | | 59 | | | | | 2304 | |
| 19.13 Closed Cooling Water | | 32 | | | | | 5 | 37 | | 37 | | | | | 1443 | |
| 19.14 CO - Carbon Dioxide | | 4 | | | | | <1 | 5 | | 5 | | | | | 177 | |
| 19.15 Component Cooling Water | | 134 | | | | | 20 | 154 | | 154 | | | | | 6177 | |
| 19.16 Condensate | | 133 | | | | | 20 | 153 | | 153 | | | | | 5956 | |
| 19.17 Condensate & Feedwater Chemical Addition | | 12 | | | | | 2 | 14 | | 14 | | | | | 526 | |
| 19.18 Condensate Demineralizer | | 46 | | | | | 7 | 53 | | 53 | | | | | 2068 | |
| 19.19 Condensate Storage & Transfer | | 39 | | | | | 6 | 45 | | 45 | | | | | 1656 | |
| 19.20 Condenser Air Removal | | 16 | | | | | 2 | 18 | | 18 | | | | | 699 | |
| 19.21 Containment Integrated Leak Rate Test | | 6 | | | | | <1 | 7 | | 7 | | | | | 287 | |
| 19.22 Containment Spray | 44 | 40 | | | | | 28 | 112 | 67 | 46 | | | | | 3219 | |
| 19.23 Control Bldg Non-System Specific Clean | | 378 | | | | | 57 | 435 | | 435 | | | | | 16569 | |
| 19.24 Control Bldg Non-System Specific Decon | 32 | 124 | | | | | 34 | 189 | 47 | 142 | | | | | 6691 | |
| 19.25 Control Building HVAC | | 147 | | | | | 22 | 169 | | 169 | | | | | 6162 | |
| 19.26 DA - Circulating Water System | | 196 | | | | | 29 | 226 | | 226 | | | | | 9126 | |
| 19.27 DM - Equipment Drains | | 60 | | | | | 9 | 69 | | 69 | | | | | 2710 | |
| 19.28 DO - Diesel Oil | | 1 | | | | | <1 | 1 | | 1 | | | | | 47 | |
| 19.29 Demineralized Water Storage & Transfer | | 41 | | | | | 6 | 47 | | 47 | | | | | 1819 | |
| 19.30 Diesel Generator Building HVAC | | 27 | | | | | 4 | 31 | | 31 | | | | | 1115 | |
| 19.31 EA - Service Water | | 63 | | | | | 10 | 73 | | 73 | | | | | 2928 | |
| 19.32 EF - Essential Service Water | | 77 | | | | | 12 | 89 | | 89 | | | | | 3541 | |
| 19.33 Emergency Fuel Oil | | 31 | | | | | 5 | 36 | | 36 | | | | | 1329 | |
| 19.34 FO - Fuel Oil | | 14 | | | | | 2 | 16 | | 16 | | | | | 625 | |
| 19.35 FP - Fire Protection | | 152 | | | | | 23 | 175 | | 175 | | | | | 7096 | |

C-34

Document W11-25-002

TABLE C-3 (continued)
ENTOMB COST ESTIMATE FOR WOLF CREEK GENERATING STATION

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Cntgcy | Total | LicTerm | Clean A CF | B CF | C CF | >C CF | M-Hrs | M-Rom |
|--|-------|--------|------|------|------|-------|--------|-------|---------|------------|------|------|-------|-------|-------|
| Disposal of Plant Systems (continued) | | | | | | | | | | | | | | | |
| 19.36 Feedwater | | 90 | | | | | 14 | 104 | | 104 | | | | 4105 | |
| 19.37 Feedwater Heater Extraction | | 135 | | | | | 20 | 155 | | 155 | | | | 6164 | |
| 19.38 Fuel Bldg Non-System Specific Clean | | 52 | | | | | 8 | 60 | | 60 | | | | 2293 | |
| 19.39 Fuel Bldg Non-System Specific Decon | 3 | 16 | | | | | 4 | 24 | 5 | 18 | | | | 840 | |
| 19.40 GD - Esstl. Srvc. Wtr Pumphs. Bldg HVAC | | 9 | | | | | 1 | 10 | | 10 | | | | 365 | |
| 19.41 GE - Turbine Bldg HVAC | | 102 | | | | | 15 | 118 | | 118 | | | | 4319 | |
| 19.42 GF - Miscellaneous Building HVAC | | 33 | | | | | 5 | 38 | | 38 | | | | 1387 | |
| 19.43 Generator Hydrogen Seal & CO2 | | 5 | | | | | <1 | 6 | | 6 | | | | 210 | |
| 19.44 Generator Seal Oil | | 7 | | | | | 1 | 8 | | 8 | | | | 296 | |
| 19.45 HY - Hydrogen | | 6 | | | | | <1 | 7 | | 7 | | | | 277 | |
| 19.46 KA - Compressed Air and Instrument | | 160 | | | | | 24 | 185 | | 185 | | | | 7081 | |
| 19.47 KB - Breathing Air | | 26 | | | | | 4 | 30 | | 30 | | | | 1182 | |
| 19.48 KC - Fire Protection | | 277 | | | | | 42 | 319 | | 319 | | | | 12879 | |
| 19.49 KD - Domestic water | | 46 | | | | | 7 | 52 | | 52 | | | | 2023 | |
| 19.50 KH - Service Gas | | 18 | | | | | 3 | 21 | | 21 | | | | 780 | |
| 19.51 LA - Sanitary Drains | | 13 | | | | | 2 | 15 | | 15 | | | | 582 | |
| 19.52 LC - Yard Drains | | 2 | | | | | <1 | 3 | | 3 | | | | 95 | |
| 19.53 LE - Oily Waste | | 98 | | | | | 15 | 112 | | 112 | | | | 4433 | |
| 19.54 Lube Oil Storage, Transfer, & Purification | | 21 | | | | | 3 | 24 | | 24 | | | | 925 | |
| 19.55 Main Steam | | 139 | | | | | 21 | 160 | | 160 | | | | 6475 | |
| 19.56 Main Turbine | | 131 | | | | | 20 | 151 | | 151 | | | | 5932 | |
| 19.57 Main Turbine Control Oil | | 29 | | | | | 4 | 33 | | 33 | | | | 1211 | |
| 19.58 Main Turbine Lube Oil | | 27 | | | | | 4 | 31 | | 31 | | | | 1164 | |
| 19.59 NT - Nitrogen | | 4 | | | | | <1 | 5 | | 5 | | | | 186 | |
| 19.60 OX - Oxygen | | 4 | | | | | <1 | 5 | | 5 | | | | 177 | |
| 19.61 Plant Heating | | 70 | | | | | 11 | 81 | | 81 | | | | 3155 | |
| 19.62 Radwaste Bldg Non-System Specific Clean | | 153 | | | | | 23 | 176 | | 176 | | | | 6704 | |
| 19.63 Radwaste Bldg Non-System Specific Decon | 11 | 46 | | | | | 12 | 69 | 16 | 53 | | | | 2449 | |
| 19.64 Reactor Bldg Non-System Specific Clean | | 136 | | | | | 20 | 157 | | 157 | | | | 5982 | |
| 19.65 Reactor Bldg Non-System Specific Decon | 10 | 46 | | | | | 12 | 68 | 15 | 53 | | | | 2438 | |
| 19.66 Reactor Coolant System | | 105 | 64 | 16 | 736 | 202 | 176 | 1299 | 1299 | 2390 | | | | 4772 | 68 |
| 19.67 Roof Drains | | 55 | | | | | 8 | 63 | | 63 | | | | 2529 | |
| 19.68 ST - Sewage Treatment | | 23 | | | | | 3 | 26 | | 26 | | | | 1000 | |
| 19.69 SW - Screen Wash | | 15 | | | | | 2 | 17 | | 17 | | | | 640 | |
| 19.70 SZ - Service Air | | 47 | | | | | 7 | 54 | | 54 | | | | 2101 | |
| 19.71 Standby Diesel Engine | | 101 | | | | | 15 | 117 | | 117 | | | | 4394 | |

C-35

Document W11-25-002

TABLE C-3 (continued)
ENTOMB COST ESTIMATE FOR WOLF CREEK GENERATING STATION

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Cntgcy | Total | LicTerm | Clean | A CF | B CF | C CF | >C CF | M-Hrs | M-Rm |
|---|-------|--------|------|------|-------|-------|--------|-------|---------|-------|--------|------|------|-------|--------|------|
| Disposal of Plant Systems (continued) | | | | | | | | | | | | | | | | |
| 19.72 Stator cooling water | | 6 | | | | | <1 | 7 | | 7 | | | | | 249 | |
| 19.73 Steam Seal | | 12 | | | | | 2 | 14 | | 14 | | | | | 539 | |
| 19.74 VA - I&C Shop HVAC | | 3 | | | | | <1 | 4 | | 4 | | | | | 141 | |
| 19.75 VB - I&C Shop Computer Room HVAC | | 2 | | | | | <1 | 3 | | 3 | | | | | 95 | |
| 19.76 VC - Health Physics Computer Room HVAC | | 5 | | | | | <1 | 5 | | 5 | | | | | 200 | |
| 19.77 VH - Circ Water & Makeup Water Scrubrs Vt | | 6 | | | | | <1 | 6 | | 6 | | | | | 245 | |
| 19.78 VJ - Shop Bldg Machine Shop Area Vent | | 1 | | | | | <1 | 1 | | 1 | | | | | 51 | |
| 19.79 VL - Shop Building HVAC | | 2 | | | | | <1 | 2 | | 2 | | | | | 92 | |
| 19.80 VS - Admin. Bldg HVAC | | 5 | | | | | <1 | 6 | | 6 | | | | | 238 | |
| 19.81 VT - Tech Support Building HVAC | | 2 | | | | | <1 | 2 | | 2 | | | | | 79 | |
| 19.82 VV - Misc. Bldg. HVAC | | 3 | | | | | <1 | 3 | | 3 | | | | | 123 | |
| 19.83 VW - Waste Water Treatment Ventilation | | 1 | | | | | <1 | 1 | | 1 | | | | | 48 | |
| 19.84 WD - Domestic Water | | 25 | | | | | 4 | 28 | | 28 | | | | | 1089 | |
| 19.85 WG - Gland Water & Motor Cooling Water | | 17 | | | | | 3 | 20 | | 20 | | | | | 781 | |
| 19.86 WL - Cooling Lake Makeup & Blowdown | | 17 | | | | | 3 | 19 | | 19 | | | | | 754 | |
| 19.87 WM - Makeup Demineralizer | | 92 | | | | | 14 | 105 | | 105 | | | | | 4108 | |
| 19.88 WS - Plant Services Water | | 82 | | | | | 12 | 94 | | 94 | | | | | 3791 | |
| 19.89 WT - Waste Water Treatment | | 17 | | | | | 3 | 19 | | 19 | | | | | 767 | |
| 19.90 WZ - Radioactive Liquid Waste | | 5 | | | | | <1 | 6 | | 6 | | | | | 237 | |
| 19. Totals | 131 | 5266 | 64 | 16 | 736 | 202 | 1016 | 7432 | 1496 | 5936 | 2390 | | | | 240471 | 68 |
| 20. Erect scaffolding for systems removal | | 62 | | | | | 9 | 71 | 71 | | | | | | 1948 | |
| Decontamination of Site Buildings | | | | | | | | | | | | | | | | |
| 21.1 Reactor | 735 | 314 | 135 | 39 | 3614 | 304 | 1053 | 6194 | 6194 | 11728 | | | | | 33325 | 124 |
| 21. Totals | 735 | 314 | 135 | 39 | 3614 | 304 | 1053 | 6194 | 6194 | 11728 | | | | | 33325 | 124 |
| 22. License termination survey | | | | | | 299 | 45 | 344 | 344 | | | | | | | |
| 23. Terminate license | | | | | | | | a | | | | | | | | |
| Subtotal Period 5 Activity Costs | 1296 | 12040 | 972 | 4114 | 38644 | 11229 | 13276 | 81571 | 74400 | 7171 | 104384 | 2489 | 476 | 221 | 418470 | 282 |

C-36

Document W11-25-002

TABLE C-3 (continued)
ENTOMB COST ESTIMATE FOR WOLF CREEK GENERATING STATION

| Activity | Decon Remove | Pack | Ship | Bury | Other | Critcyl | Total | LicTerm | Clean A CF | B CF | C CF | D CF | M-HRS | M-ROR |
|--|--------------|--------------|-------------|-------------|--------------|--------------|--------------|---------------|---------------|-------------|---------------|-------------|--------------|-----------------------|
| Period 5 Undistributed Costs | | | | | | | | | | | | | | |
| 1. Decon equipment | | | | | 189 | 28 | 217 | 217 | | | | | | |
| 2. Decon supplies | | | | | 340 | 85 | 425 | 425 | | | | | | |
| 3. DOC staff relocation expenses | | | | | 845 | 127 | 972 | 972 | | | | | | |
| 4. Process liquid waste | 193 | 98 | 132 | 574 | | 212 | 1209 | 1209 | | 1314 | | | 297 | 7 |
| 5. Insurance | | | | | 724 | 72 | 797 | 797 | | | | | | |
| 6. Property taxes | | | | | 1017 | 102 | 1119 | 1007 | 112 | | | | | |
| 7. Health physics supplies | | | | | 2352 | 588 | 2940 | 2940 | | | | | | |
| 8. Heavy equipment rental | | | | | 4003 | 600 | 4603 | 4143 | 460 | | | | | |
| 9. Small tool allowance | | | | | 184 | 28 | 212 | 191 | 21 | | | | | |
| 10. Pipe cutting equipment | | | | | 587 | 88 | 675 | 675 | | | | | | |
| 11. Disposal of DAW generated | | 487 | 18 | 2326 | | 400 | 3231 | 3231 | 7587 | | | | 16701 | 42 |
| 12. Plant energy budget | | | | | 1270 | 190 | 1460 | 1314 | 146 | | | | | |
| 13. NRC Fees | | | | | 219 | 22 | 240 | 240 | | | | | | |
| Subtotal Undistributed Costs Period 5 | 193 | 585 | 150 | 2900 | 11729 | 2543 | 18100 | 17361 | 739 | 7587 | 1314 | | 16998 | 49 |
| Staff Costs | | | | | | | | | | | | | | |
| DOC Staff Cost | | | | | 11977 | 1797 | 13774 | 13774 | | | | | | |
| Utility Staff Cost | | | | | 26727 | 4009 | 30736 | 30736 | | | | | | |
| TOTAL PERIOD 5 | 1489 | 12040 | 1556 | 4264 | 41544 | 51663 | 21624 | 144181 | 136271 | 7910 | 111972 | 3803 | 476 | 221 435468 330 |
| PERIOD 6 | | | | | | | | | | | | | | |
| Removal of Major Equipment | | | | | | | | | | | | | | |
| 24. Main Turbine/Generator | | 70 | | | | 10 | 80 | | 80 | | | | 3082 | |
| 25. Main Condensers | | 219 | | | | 33 | 252 | | 252 | | | | 9282 | |

C-37

Document W11-25-002

TABLE C-3 (continued)
ENTOMB COST ESTIMATE FOR WOLF CREEK GENERATING STATION

| Activity | Decon | Remove | Pack | Ship | Bury | Other | Cntgcy | Total | LICTERM | Clean | A CF | B CF | C CF | >C CF | M-Hrs | M-Rm |
|---|-------|--------|------|------|------|-------|--------|-------|---------|-------|------|------|------|-------|--------|------|
| Demolition of Remaining Site Buildings | | | | | | | | | | | | | | | | |
| 26.1 Reactor | | 4823 | | | | | 723 | 5546 | | 5546 | | | | | 118164 | |
| 26.2 Access Vaults | | 37 | | | | | 6 | 43 | | 43 | | | | | 436 | |
| 26.3 Administration | | 209 | | | | | 31 | 241 | | 241 | | | | | 4753 | |
| 26.4 Auxiliary | | 7834 | | | | | 1175 | 9009 | | 9009 | | | | | 162497 | |
| 26.5 Auxiliary Boiler | | 23 | | | | | 3 | 26 | | 26 | | | | | 672 | |
| 26.6 Chlorine Storage | | 17 | | | | | 3 | 19 | | 19 | | | | | 376 | |
| 26.7 Circ. Water Discharge Structure | | 351 | | | | | 53 | 403 | | 403 | | | | | 4140 | |
| 26.8 Circulating Water Intake & Screenhouse | | 828 | | | | | 124 | 952 | | 952 | | | | | 5369 | |
| 26.9 Communication Corridor - Contaminated | | 346 | | | | | 52 | 398 | | 398 | | | | | 8911 | |
| 26.10 Communication Corridor-Clean | | 2292 | | | | | 344 | 2635 | | 2635 | | | | | 53284 | |
| 26.11 Covered walkways | | 8 | | | | | 1 | 10 | | 10 | | | | | 322 | |
| 26.12 Diesel Generator | | 398 | | | | | 60 | 458 | | 458 | | | | | 7888 | |
| 26.13 E.S.W.S. Pumphouse | | 781 | | | | | 117 | 898 | | 898 | | | | | 5070 | |
| 26.14 ESWS Valve House | | 12 | | | | | 2 | 14 | | 14 | | | | | 243 | |
| 26.15 Fuel Building | | 2574 | | | | | 386 | 2960 | | 2960 | | | | | 63283 | |
| 26.16 Hot Machine Shop | | 22 | | | | | 3 | 25 | | 25 | | | | | 639 | |
| 26.17 M.M.O. Building | | 172 | | | | | 26 | 198 | | 198 | | | | | 3483 | |
| 26.18 Misc. Site Foundations | | 374 | | | | | 56 | 431 | | 431 | | | | | 7394 | |
| 26.19 Misc. Site Structures | | 999 | | | | | 150 | 1149 | | 1149 | | | | | 20240 | |
| 26.20 Oil Separator and Waste Tank | | 2 | | | | | <1 | 3 | | 3 | | | | | 48 | |
| 26.21 Radwaste | | 2714 | | | | | 407 | 3121 | | 3121 | | | | | 58493 | |
| 26.22 Radwaste Drum Storage | | 422 | | | | | 63 | 485 | | 485 | | | | | 12006 | |
| 26.23 Security/Guardhouse | | 317 | | | | | 47 | 364 | | 364 | | | | | 4682 | |
| 26.24 Site Diesel Generator | | 3 | | | | | <1 | 3 | | 3 | | | | | 60 | |
| 26.25 Turbine Building | | 5712 | | | | | 857 | 6569 | | 6569 | | | | | 166045 | |
| 26.26 Waste Water Treatment | | 17 | | | | | 3 | 20 | | 20 | | | | | 432 | |
| 26. Totals | | 31285 | | | | | 4693 | 35978 | | 35978 | | | | | 708928 | |
| Site Closeout Activities | | | | | | | | | | | | | | | | |
| 27. Remove Rubble | | 3804 | | | | | 571 | 4374 | | 4374 | | | | | 12323 | |
| 28. Grade & landscape site | | 1393 | | | | | 209 | 1602 | | 1602 | | | | | 8028 | |
| 29. Final report to NRC | | | | | | 156 | 23 | 179 | 179 | | | | | | | |
| Subtotal Period 6 Activity Costs | | 36771 | | | | 156 | 5539 | 42466 | 179 | 42287 | | | | | 741643 | |

C38

Document W11-25-002

639

Document W11-25-002