

# Exhibit No. 18P

Exhibit No.: \_\_\_\_\_  
Issue: Asbury  
Witness: Drew W. Landoll  
Type of Exhibit: Direct Testimony  
Sponsoring Party: The Empire District  
Electric Company  
Case No.: ER-2021-0312  
Date Testimony Prepared: May 2021

**Before the Public Service Commission  
of the State of Missouri**

**Direct Testimony**

**of**

**Drew W. Landoll**

**on behalf of**

**The Empire District Electric Company**

**May 2021**



**\*\*DENOTES CONFIDENTIAL\*\***  
20 CSR 4240-2.135(2)(A)5,6,3

TABLE OF CONTENTS  
FOR THE DIRECT TESTIMONY OF DREW W. LANDOLL  
THE EMPIRE DISTRICT ELECTRIC COMPANY  
BEFORE THE MISSOURI PUBLIC SERVICE COMMISSION  
CASE NO. ER-2021-0312

<b>SUBJECT</b>	<b>PAGE</b>
I. INTRODUCTION.....	1
II. ASBURY DECOMMISSIONING AND REPURPOSING.....	3
A. CREATING A SAFE AND COMPLIANT FACILITY .....	4
B. DEVELOPING A DECOMMISSIONING PLAN.....	7
C. REPURPOSING EXISTING ASBURY ASSETS.....	12
III. CONCLUSION .....	17

DIRECT TESTIMONY OF DREW W. LANDOLL  
THE EMPIRE DISTRICT ELECTRIC COMPANY  
BEFORE THE MISSOURI PUBLIC SERVICE COMMISSION  
CASE NO. ER-2021-0312

1 **I. INTRODUCTION**

2 **Q. Please state your name and business address.**

3 A. Drew W. Landoll; 602 S Joplin Ave. Joplin, MO, 64801.

4 **Q. By whom are you employed and in what capacity?**

5 A. I am employed by Liberty Utilities Service Corp. (“LUSC”), a subsidiary of Liberty  
6 Utilities Co. (“LUCo”), as the Director of Strategic Projects for The Empire District  
7 Electric Company (“Empire” or the “Company”).

8 **Q. On whose behalf are you testifying in this proceeding?**

9 A. I am testifying on behalf of Empire.

10 **Q. Please describe your educational and professional background.**

11 A. I completed my Bachelor of Science in Civil Engineering at the University of Missouri  
12 – Rolla, now known as Missouri University of Science and Technology. My civil  
13 engineering emphasis was in construction and environmental with a minor in  
14 communications. I am a registered Professional Engineer within the State of Missouri.

15 Until 2012, I was employed by Aquaterra Environmental Solutions, a civil and  
16 environmental consulting firm within the Midwest as a Project Engineer. As a Project  
17 Engineer, I designed and permitted landfill expansions, wastewater pumping systems,  
18 air emissions permit applications, and operational support for multiple clients within  
19 the waste and environmental industries.

20 In May of 2012, I joined Empire at the Asbury Power Plant as a Local Projects  
21 Manager planning and managing projects and outages for the plant. In May of 2015, I

1 was promoted to Manager of Strategic Projects. In that role, I was the lead for: the  
2 demolition of Riverton Units 7, 8, and 9; the completion of the Riverton 12 Combined  
3 Cycle Conversion Project; the early development of the Missouri wind farms, Kings  
4 Point and North Fork Ridge; and multiple other smaller projects within the Company.  
5 Then, in July of 2019, I was promoted to my current position of Director of Strategic  
6 Projects. As Director of Strategic Projects, I oversee environmental compliance, certain  
7 large projects, capital expenditure budgeting, project accounting and forecasting, and I  
8 provide support for regulatory filings related to certain projects.

9 **Q. Have you previously testified before the Missouri Public Service Commission**  
10 **(“Commission”) or any other regulatory agency?**

11 A. No. This is the first opportunity I have had to testify before this Commission.

12 **Q. What is the purpose of your Direct Testimony in this proceeding?**

13 A. I provide an update on the status of the Company’s decommissioning plan for the  
14 Asbury Power Plant (“Asbury”). Asbury Unit 1, first operational in 1970, was  
15 originally an approximate 200MW mine-mouth, coal-fired electric power plant located  
16 in Jasper County, Missouri. My Direct Testimony also addresses the creation of the  
17 Asbury Renewable Operations Center and the repurposing of certain assets to support  
18 ongoing operations.

19 **Q. Do additional Empire witnesses address issues related to the retirement of**  
20 **Asbury?**

21 A. Yes. Empire witnesses Timothy N. Wilson, Aaron J. Doll, and Shaen T. Rooney  
22 address various components of the Company’s decision making regarding the  
23 retirement of Asbury, and Empire witness Frank C. Graves addresses the  
24 appropriateness of the Company recovering the undepreciated investments at Asbury.

1 Finally, Company witness Tisha Sanderson addresses the impact of the retirement of  
2 Asbury within the Company’s revenue requirement.

3 **Q. What is the current status of Asbury?**

4 A. Asbury Unit 1 was de-designated from the Southwest Power Pool (“SPP”) and retired  
5 in March of 2020. The Asbury campus includes facilities and buildings that were  
6 necessary to support the operations of the original plant. Some of these facilities are  
7 now repurposed to support the Asbury Renewable Operations Center.

8 **Q. What is the purpose of the Asbury Renewable Operations Center?**

9 A. The Company repurposed certain Asbury facilities to host the operations and  
10 maintenance activities of the Kings Point, North Fork Ridge, and Neosho Ridge wind  
11 farms (collectively, the “Wind Projects”), the Prosperity Solar Facility and other  
12 renewable generation facilities that may be contemplated in the future. To support the  
13 personnel that are operating and maintaining the Wind Projects, the Asbury Renewable  
14 Operations Center is using the former Asbury office and break room facilities, the  
15 maintenance buildings, parking areas, and supporting infrastructure. An aerial  
16 photograph showing the assets remaining in use is provided in Figure 2 on page 14 of  
17 this testimony.

18 **II. ASBURY DECOMMISSIONING AND REPURPOSING**

19 **Q. Is the decommissioning and repurposing at Asbury complete?**

20 A. No. The Company has received the decommissioning study from Black and Veatch  
21 and has developed a plan for the decommissioning of the plant in a safe and efficient  
22 manner. Under the current plan, it will take approximately 3 to 4 years to  
23 decommission and dismantle the plant. Concurrently with executing this plan, the  
24 Company continues to evaluate potential for repurposing certain plant components.

1 **Q. Please briefly describe the scope and status of Asbury decommissioning and**  
2 **repurposing activities.**

3 A. The Company has been working towards three goals recently: (A) creating a safe and  
4 compliant work location; (B) developing a decommissioning plan for the final  
5 disposition of the unused physical facilities on site; and (C) repurposing certain  
6 facilities onsite to support the operations and maintenance activities of the Wind  
7 Projects, the Prosperity Solar Facility and other renewable generation facilities as they  
8 are envisioned.

9 **A. CREATING A SAFE AND COMPLIANT FACILITY**

10 **Q. What activities have been done on site since Asbury Unit 1's de-designation in**  
11 **March of 2020?**

12 A. Once the unit was de-designated, the Company prioritized removal of environmentally  
13 sensitive items. This first step was needed to protect the environment, increase safety  
14 to employees and neighbors, reduce risks of potential contamination, and meet, and in  
15 some instances, reduce the Company's environmental permit obligations. The work  
16 completed to date includes:

- 17 a. removal of anhydrous ammonia;
- 18 b. removal of oil from equipment;
- 19 c. removal of Coal Combustion Residuals ("CCR") waste within plant ductwork;
- 20 d. removal of certain chemicals stored onsite and within equipment;
- 21 e. removal of residual coal from the coal piles;
- 22 f. modifications to water discharge Outfalls;
- 23 g. isolation and Lock-Out Tag-Out on certain plant systems; and
- 24 h. modifications of environmental and operating permits.

1 **Q. Please describe the ongoing modifications of environmental and operating**  
2 **permits.**

3 A. The facility's air emission Part 70 Permit to Operate (OP2018-001), enforced through  
4 the Missouri Department of Natural Resources ("MDNR") Air Program, became non-  
5 effective on March 1, 2020. This action also removed all other associated air permits  
6 including, but not limited to, the facility's Acid Rain Permit and construction permits.  
7 The facility is in the process of renewing its National Pollutant Discharge Elimination  
8 System Permit (NPDES) MO-0095362 with the MDNR that will expire March 31,  
9 2022. The Company and MDNR have been working together to remove certain  
10 operating parameters that no longer apply to the facility since it is no longer a coal-  
11 fired electric generating facility. This will eliminate certain monitoring and testing  
12 requirements of water discharges from the facility. In response to recent changes and  
13 extensions to the federal Coal Combustion Residuals Rule (CCR Rule), the Company  
14 has updated the operating record and is revising the closure plan for the applicable ash  
15 impoundment. Also, since the Company is not storing anhydrous ammonia on site,  
16 there is no longer a requirement to maintain a Risk Management Plan ("RMP"). For  
17 that reason, Asbury's RMP has been deregistered with the Environmental Protection  
18 Agency.

19 **Q. What tasks remain to accomplish the goal of maintaining a safe and compliant**  
20 **facility?**

21 A. The Company has obligations to comply with all safety requirements, remaining  
22 permits, and all regulations pertaining to the facility, and will meet these requirements  
23 as we have for the last fifty years at Asbury. The Company and onsite personnel will



1 continue permit compliance reporting and keep the facility maintained to provide a  
2 workplace that is safe for our employees, contractors and the general public.

3 As the above work proceeds, Empire will continue identifying and proactively  
4 mitigating (where feasible) any risks posed by the age and condition of the remaining  
5 equipment and facilities. Some examples that may require emergency intervention (and  
6 may affect the scope and timing of the overall project) include ruptured piping, broken  
7 hoses, leaking roofs, inoperable elevators, exposed asbestos or other items that require  
8 immediate attention.

9 The Company is currently in the process of removing the residual coal from the  
10 previous two coal piles and creating a rainwater detention pond that will comply with  
11 the NPDES permit. Additional improvements may be necessary to comply with the  
12 terms of the new permit and are not known at this time. In addition, ongoing stormwater  
13 sampling remains a requirement. The NPDES permit renewal application will be  
14 submitted to the MDNR in late 2021 and will follow the public comment process as  
15 required by federal and state regulations, with an anticipated effective date of May 1,  
16 2022.

17 **Q. Does the work described above include the work required for the ash**  
18 **impoundment closure?**

19 A. No, the ash impoundment closure is required regardless of whether Asbury Unit 1 was  
20 retired or not. The ongoing compliance for the ash impoundment under the CCR rule,  
21 in general, has not changed over the last several years. The Company still plans to close  
22 the impoundment in place. The final Impoundment Closure Plan is being revised to

1 comply with the most recently promulgated changes in deadlines and reporting  
2 obligations to the CCR Rule.<sup>1</sup>

3 **B. DEVELOPING A DECOMMISSIONING PLAN**

4 **Q. Has the Company developed a plan of final disposition for the facility?**

5 A. Yes, with a three-phased plan to be executed over the coming years. The Company  
6 completed Phase 1, the initial decommissioning analysis and studies of the facility. The  
7 studies completed were to determine the final disposition of Unit 1 within the  
8 Company's overall decommissioning plan. Based on these findings, the Company  
9 plans to demolish the unused portions of Unit 1 while maintaining operations of the  
10 Asbury Renewable Operations Center for the Company's renewable generation plants.  
11 The memo contained in **Confidential Direct Schedule DWL-1** includes the summary,  
12 findings, schedule, preliminary cost estimates, and supporting reports for the Phase 1  
13 Studies.

14 Phase 2 includes the development of work plans, schedules, engineering plans  
15 and specifications, expound on and execution of the Isolation Study, asbestos removal,  
16 completion of NPDES modifications, and risk register mitigations. Phase 2 will  
17 conclude with the preparation of the bid documents for the demolition of the selected  
18 facilities and is anticipated to be complete by the Q4-2021 to Q1-2022 timeframe. The  
19 Company is currently working on certain scopes of Phase 2.

---

<sup>1</sup> See <https://www.federalregister.gov/documents/2020/08/28/2020-16872/hazardous-and-solid-waste-management-system-disposal-of-coal-combustion-residuals-from-electric> Phase one part one: <https://www.federalregister.gov/documents/2018/07/30/2018-16262/hazardous-and-solid-waste-management-system-disposal-of-coal-combustion-residuals-from-electric>. "*A Holistic Approach to Closure Part A: Deadline to Initiate Closure and Enhancing Public Access to Information.*"<sup>1</sup>

1 Phase 3 is planned to include finalization of bid documents, revision of cost  
2 estimates, bid administration, construction management, demolition of the facilities,  
3 reporting, and project accounting. Phase 3 is tentatively scheduled to be completed in  
4 2024 subject to the scope and timing of required engineering work and the results of  
5 Phase 2.

6 **Q. Did the Company engage a qualified consulting firm to assist in developing the**  
7 **Phase 1 plan?**

8 A. Yes, the Company retained Black and Veatch (“B&V”), one of the top-ranked design  
9 firms in fossil fuel generation and the original engineering firm that designed Asbury  
10 Unit 1. B&V was retained in August 2019 to perform a multi-part study to support  
11 Phase 1 of the Asbury decommissioning. This work included the initial retirement  
12 planning process and provided technical guidance and support to the Company’s  
13 decision-making process for the final disposition of the facility.

14 **Q. Please describe the findings of Phase 1.**

15 A. Phase 1 included an internal meeting to discuss the possibility of repurposing Asbury  
16 into the Asbury Renewable Operations Center and document major items to be  
17 cognizant of should the process move forward. Phase 1 also included two market  
18 studies to determine “bookend” values of the facility; one if the operating facility was  
19 to be sold on the open market to another owner-operator and the other to determine an  
20 estimate of razing the facility.

21 The Fair Market Valuation Report found that the facility had a \*\* [REDACTED]  
22 [REDACTED],\*\* meaning the Company would have to pay someone \*\* [REDACTED]  
23 [REDACTED]\*\* to purchase and operate the facility in its state at the time and assume all  
24 associated liabilities. The Demolition Order of Magnitude Report estimated the cost to

1       raze the in-scope facilities to be approximately \*\* [REDACTED]  
2       [REDACTED] \*\* An aerial photograph from  
3       this report which depicts these facilities is provided below:



4  
5       Figure 1 – Facilities Identified for Demolition

6       A study of Unit 1’s equipment was performed to establish potential for  
7       secondary markets and begin the work for isolating Unit 1 from the remaining onsite  
8       facilities to support Asbury Renewable Operations Center. The Equipment Study was  
9       also shared with external vendors through B&V to explore whether any additional  
10      markets existed for the unit. This endeavor was not successful. Upon identifying no  
11      viable markets for the operating facility, the Company then explored the middle-ground  
12      of the “bookends”, Abandon-In-Place (“AIP”).

13      AIP uses a minimalistic approach for securing the plant and equipment that will  
14      no longer be used. A cost estimate and summary report were performed to analyze the  
15      scope of work needed to safely abandon the structures while still operating the Asbury

1 Renewable Operations Center over the coming ten years. Risk registers were then  
2 created to summarize and document the risks associated with demolition and  
3 abandoning Unit 1. Finally, a summary letter was prepared by B&V of the work  
4 completed. The B&V reports are found in attachments within **Confidential Direct**  
5 **Schedule DWL-1**.

6 **Q. Why was demolition chosen over abandoning-in-place?**

7 A. While the AIP scenario has a lower initial cost, the ongoing safety and environmental  
8 risks outweigh the temporary savings. To maintain an abandoned fifty-year-old power  
9 plant at an operating facility, the Asbury Renewable Operations Center, there would be  
10 an initial expense and ongoing expenses to keep the facility compliant and safe. These  
11 expenses borne by the Company, and ultimately our customers, over the next ten years  
12 has been estimated at approximately \*\* [REDACTED] \*\* – see  
13 **Confidential Direct Schedule DWL-1, Abandon-In-Place Cost Estimate (2020), p.**  
14 **115**. The AIP scenario should also not be considered an in lieu of demolition plan, but  
15 instead delaying the eventual demolition of Unit 1. Within the Abandon-In-Place Cost  
16 Estimate Report, B&V provided the following:

17 It should be noted that the cumulative cost in 2030 at the end of the 10-  
18 year period does not significantly approach the estimated demolition  
19 cost of \*\* [REDACTED] \*\*. However, these should be considered costs  
20 to Liberty Utilities (and the rate payers) for deferral of the demolition  
21 project, thus adding to the overall cost of the Asbury Plant.  
22

23 In addition to increasing the ultimate cost of retirement and removal of the plant, a ten-  
24 year delay in final removal would also further contribute to inter-generational customer  
25 inequity, by distancing the customers that benefitted from Asbury's Unit 1 energy  
26 production from those customers paying for its demolition.

1 To support options analysis and prioritize the scope and sequencing of  
2 activities, the Company and B&V developed risk registers for both AIP and demolition  
3 scenarios, see **Confidential Direct Schedule DWL-1, Abandon-In-Place Risk**  
4 **Register (2020), p. 116-120 and Demolition Risk Register (2020), p. 121-128.** When  
5 comparing the risks of each scenario, the demolition scenario appears to carry less long-  
6 term risk exposure to employees, contractors, customers, and the Company. The  
7 greatest risks identified for this option involve the potential of physical harm to humans  
8 from deteriorating structures and potential exposure to remaining environmentally  
9 sensitive items, which may get worse over time. The AIP scenario would have also  
10 required frequent re-assessments and risk register updates in the event of future events  
11 affecting the site, such as regulation changes, damage to remaining facilities, extreme  
12 weather or other events impacting the Company's decisions.

13 Having considered these risks and their economic implications, the Company decided  
14 to proceed with the demolition of Unit 1.

15 **Q. What activities are involved in Phase 2?**

16 A. Over the next year, we anticipate performing the following scopes of work:

- 17 a. asbestos identification and quantification study;
- 18 b. Unit 1 engineering for isolation of the utilities;
- 19 c. Construction work to isolate and repower the Asbury Renewable Operations  
20 Center from Unit 1;
- 21 d. continued compliance-driven modifications;
- 22 e. certain risk register mitigations; and
- 23 f. on-going development of demolition plans and associated work specifications;
- 24 g. Removal of asbestos.

1 **Q. When does the Company expect to complete Phase 3 and at what cost?**

2 A. Upon completion of Phase 2, the Company will prepare an execution strategy, which  
3 will include the demolition scope of work. This execution strategy will be dependent  
4 on what is found during the removal of asbestos, timing of the original stack removal,  
5 and other items that the contractor is to perform. The Company will follow an approach  
6 for contracting and execution of the demolition of Asbury similar to the approach used  
7 for the Riverton Units 7, 8, and 9 demolition performed in 2017. Currently, the  
8 Company anticipates completing the demolition of Unit 1 in 2024.

9 Current cost estimates have been provided within **Confidential Direct**  
10 **Schedule DWL-1, Demolition Order of Magnitude Cost Estimate, Table 3-1, p. 77.**

11 This estimate amounts to **\*\*[REDACTED]\*\*** in costs and is a Class 5 Budget Estimate  
12 per the Association of Cost Engineering guidelines, or -50% to +100% accuracy. Cost  
13 estimates will be updated as the scope of work is established, quantities are determined,  
14 and bids are received. The Company will continue exploring cost savings, contracting,  
15 and execution strategies while developing these plans. Work for Phase 1 and Phase 2  
16 is expected to be completed by Q1-2022 and is forecasted to cost approximately **\*\*[REDACTED]**  
17 **[REDACTED]\*\*** - which represents a part of the total \$36.9-million estimate. The Company  
18 is requesting to continue tracking these costs for the decommissioning and retirement  
19 of Asbury Unit 1 captured in the recently established Accounting Authority Order as  
20 further described by Company Witness Tisha Sanderson.

21 **C. REPURPOSING EXISTING ASBURY ASSETS**

22 **Q. How is the Asbury Renewable Operations Center being utilized?**

23 A. The Asbury Renewable Operations Center is the main operations and maintenance  
24 center for the Company's renewable generation fleet and the Company's Site Support

1 Services group. The facility houses approximately 27 employees responsible for  
2 inventory management, engineering, operations, purchasing, and maintenance of these  
3 facilities. It also is the location of the primary warehouse for inventory, tools and  
4 equipment. The Vestas long-term maintenance-contract employees and their associated  
5 equipment and inventory are located on the site as well. Company witness Shaen  
6 Rooney provides further details of the contract work that will be conducted by Vestas  
7 relating to the Wind Projects.

8 **Q. What renewable generation resources will be operated from the Asbury**  
9 **Renewable Operations Center?**

10 A. The Company's Wind Projects, the Prosperity Solar Facility, other future community  
11 solar facilities, and future solar and battery distributed energy resources will be  
12 operated from the former Asbury plant site.

13 A control room has been established in the administration building that will be  
14 operated 24/7 and currently has control of the Wind Projects and the Prosperity Solar  
15 Facility. The control room can be expanded to include future renewable generation  
16 assets, if necessary.

17 **Q. What facilities have been repurposed?**


18 A. The following items are being utilized by the Asbury Renewable Operations Center:  
19 administration building, maintenance building, break room building, old admin  
20 building, land, fire suppression and detection, rail spur, warehouses, and the related  
21 infrastructure supporting these facilities. These repurposed in-service facilities  
22 represented approximately \$12.8M of net plant (excluding general plant assets<sup>2</sup>) at

---

<sup>2</sup> General plant assets include items such as office furniture/equipment and computer, communication, and transportation equipment.



1 March 31, 2020. An aerial photograph, with items identified in purple remaining in use,  
2 is provided in Figure 2.



3  
4 Figure 2 – Remaining Facilities Indicated in Purple


5 **Q. Why was Asbury chosen for the Renewable Operations Center?**

6 A. Asbury's centralized location relative to the Wind Projects made the site an ideal  
7 candidate on location alone. Other attributes that led to the decision to host the  
8 renewable operations center at Asbury include warehouse and office facilities that met  
9 Vestas' minimum space requirements, ample parking, no schedule impacts due to  
10 building construction, existing fiber communication lines, co-located point of  
11 interconnection with North Fork Ridge, existing Company networking infrastructure,  
12 offices and break rooms meeting Company requirements, and no additional permitting  
13 or zoning requirements. The repurposing of these assets came with minimal additional

1 investment which would have otherwise been required nearly immediately, saving our  
2 customers money.

3 A large part of the workforce that previously supported Asbury Unit 1 had spent  
4 most of their careers there, and, as such, had housing and family plans built around  
5 working from the Asbury location. Maintaining the operations center at Asbury and  
6 primarily staffing with legacy employees allowed an easy and welcomed transition for  
7 those employees. Company witness Timothy N. Wilson provides more detail on the  
8 staffing transition. For all of these reasons, Empire was excited to choose the Asbury  
9 campus for repurposing.

10 **Q. What work must be completed to operate the Asbury Renewable Operations**  
11 **Center?**

12 A. Currently, the Asbury Renewable Operations Center is fully operational. Minimal  
13 improvements were made to create a new control room in the existing office building.  
14 However, as the decommissioning and demolition plan proceeds for Unit 1, the  
15 infrastructure providing power, water, sewer, fire protection, etc. to the plant must be  
16 de-energized and isolated to safely perform the demolition work. This will create the  
17 need to install a new 12kV power source and install new utilities at the Asbury  
18 Renewable Operations Center. These items are identified and described within the  
19 **Confidential Direct Schedule DWL-1, Isolation Study, p. 78-97.** The Asbury  
20 Renewable Operations Center staff are currently expanding upon the Isolation Study  
21 as part of Phase 2 work to create engineered plans and specifications to perform the  
22 isolations. While the full scoping of the work has not been completed, current cost  
23 estimates of these improvements are approximately \*\*\*\* and anticipated to  
24 be in service in 2021.

1 **Q. What other items will the Asbury Renewable Operations Center support for the**  
2 **company?**

3 A. The Asbury Renewable Operations Center will also host the Company's Site Services  
4 Group. This is a group of skilled union employees that will maintain the balance of  
5 plant for the Wind Projects and support the Company's other generation plants. These  
6 employees report to the Plant Director – Wind.

7 **Q. Has the Company explored other options for the facility?**

8 A. Yes, during the Phase 1 study a lot of effort was put into the potential to repurpose  
9 Asbury Unit 1 to host additional renewables and/or battery storage. The Company went  
10 as far as soliciting proposals to perform an energy storage assessment to repurpose the  
11 structure for flow batteries and other technologies. These efforts to reuse the plant  
12 systems and the steel and concrete structure of Unit 1 were abandoned before  
13 performing any detailed study or engineering. It did not take long to find that reusing  
14 specific purpose-built systems and structures that contain asbestos, fifty-year-old  
15 motors, valves, wires and pipes, with limited detailed digital drawings did not align  
16 with the Company's current preferred plan for renewable generation additions. The  
17 Company continues to search for economic and value-enhancing proposals for  
18 expanding the reuse of the remaining facilities and infrastructure and expects to do so  
19 well into the future. The Company's Integrated Resource Plan will continue to be the  
20 platform by which these opportunities are analyzed. It is one of Empire's key focuses  
21 to continue the drive of sustainability and reuse of our natural resources. Finding a  
22 secondary use for a mine-mouth coal-fired power plant's land, substructure,  
23 superstructure, and campus would be a great reuse of our resources. Should an  
24 opportunity present itself, the Company will keep stakeholders informed.

1 **III. CONCLUSION**

2 **Q. Please briefly summarize your Direct Testimony.**

3 A. The Company is currently working on a three-phased decommissioning plan of the  
4 retired Asbury Power Plant. The decision has been made, with support from Black and  
5 Veatch, to demolish the Unit 1 structure and ancillary facilities, at an estimated cost of  
6 **\*\*[REDACTED]\*\***. Phase 2 is currently underway to prepare for and develop the scope of  
7 work for the demolition. Phase 3 will entail the demolition of Unit 1 estimated to be  
8 completed in 2024. In order to reduce costs and utilizing existing infrastructure to  
9 support our customers, the Company established a renewable operations center at  
10 Asbury. In doing so, the Company successfully repurposed tens of millions of dollars  
11 in assets while avoiding additional investments. Finally, the Company has and will  
12 continue to analyze and search for new opportunities for additional repurposing of  
13 retired assets at this location.

14 **Q. Does this conclude your Direct Testimony at this time?**

15 A. Yes.

**VERIFICATION**

I, Drew W. Landoll, under penalty of perjury, on this 28th day of May, 2021, declare that the foregoing is true and correct to the best of my knowledge and belief.

/s/ Drew W. Landoll